

# **K50 Sub-Family Reference Manual**

Supports: MK50DN512ZCLQ10, MK50DN512ZCMD10



Document Number: K50P144M100SF2RM Rev. 6, Nov 2011









## **Contents**

Section Number Title		umber Title	Page
		Chapter 1 About This Document	
1.1	Overvie	ew	53
	1.1.1	Purpose	53
	1.1.2	Audience	53
1.2	Conven	ntions	53
	1.2.1	Numbering systems	53
	1.2.2	Typographic notation	54
	1.2.3	Special terms	54
		Chapter 2 Introduction	
2.1	Overvie	ew	55
2.2	K50 Fa	55	
2.3	Module	55	
	2.3.1	ARM Cortex-M4 Core Modules	56
	2.3.2	System Modules	57
	2.3.3	Memories and Memory Interfaces	58
	2.3.4	Clocks	59
	2.3.5	Security and Integrity modules.	59
	2.3.6	Analog modules	59
	2.3.7	Timer modules	60
	2.3.8	Communication interfaces	61
	2.3.9	Human-machine interfaces.	62
2.4	Orderal	ble part numbers	62
		Chapter 3 Chip Configuration	
3.1	Introdu	ction	65



Sec	tion Nu	umber Title	Page	
3.2	Core me	odules	65	
	3.2.1	ARM Cortex-M4 Core Configuration.	65	
	3.2.2	Nested Vectored Interrupt Controller (NVIC) Configuration	68	
	3.2.3	Asynchronous Wake-up Interrupt Controller (AWIC) Configuration	74	
	3.2.4	JTAG Controller Configuration.	75	
3.3	System	modules	76	
	3.3.1	SIM Configuration	76	
	3.3.2	Mode Controller Configuration.	77	
	3.3.3	PMC Configuration.	77	
	3.3.4	Low-Leakage Wake-up Unit (LLWU) Configuration	78	
	3.3.5	MCM Configuration.	80	
	3.3.6	Crossbar Switch Configuration.	80	
	3.3.7	Memory Protection Unit (MPU) Configuration	83	
	3.3.8	Peripheral Bridge Configuration.	85	
	3.3.9	DMA request multiplexer configuration.	87	
	3.3.10	DMA Controller Configuration	90	
	3.3.11	External Watchdog Monitor (EWM) Configuration	91	
	3.3.12	Watchdog Configuration	92	
3.4	Clock N	93		
	3.4.1	MCG Configuration	93	
	3.4.2	OSC Configuration.	94	
	3.4.3	RTC OSC configuration	95	
3.5	Memori	ies and Memory Interfaces	95	
	3.5.1	Flash Memory Configuration	95	
	3.5.2	Flash Memory Controller Configuration	98	
	3.5.3	SRAM Configuration	99	
	3.5.4	SRAM Controller Configuration.	102	



Sec	Section Number		Title	Page
	3.5.5	System Register File Configuration		103
	3.5.6	VBAT Register File Configuration		104
	3.5.7	EzPort Configuration		104
	3.5.8	FlexBus Configuration		105
3.6	Security	,		108
	3.6.1	CRC Configuration		108



Sec	tion Nu	mber Title	Page
3.7	Analog.		109
	3.7.1	16-bit SAR ADC with PGA Configuration	109
	3.7.2	CMP Configuration.	116
	3.7.3	12-bit DAC Configuration	118
	3.7.4	Op-amp Configuration	119
	3.7.5	TRIAMP Configuration	
	3.7.6	VREF Configuration.	
3.8	Timers		
	3.8.1	PDB Configuration	
	3.8.2	FlexTimer Configuration.	
	3.8.3	PIT Configuration.	
	3.8.4	Low-power timer configuration	131
	3.8.5	CMT Configuration.	
	3.8.6	RTC configuration.	
3.9	Commu	nication interfaces	
	3.9.1	Universal Serial Bus (USB) Subsystem	
	3.9.2	SPI configuration.	140
	3.9.3	I2C Configuration.	143
	3.9.4	UART Configuration.	144
	3.9.5	SDHC Configuration.	146
	3.9.6	I2S configuration.	147
3.10	Human-	149	
	3.10.1	GPIO configuration.	149
	3.10.2	TSI Configuration.	150
		Chapter 4 Memory Map	
4.1	Introduc	tion	153
4.2	System	memory map	153
	4.2.1	Aliased bit-band regions	



Section Number		umber Title	Page
4.3	Flash M	Memory Map	
	4.3.1	Alternate Non-Volatile IRC User Trim Description	156
4.4	SRAM	memory map	156
4.5	Peripher	eral bridge (AIPS-Lite0 and AIPS-Lite1) memory maps	156
	4.5.1	Peripheral Bridge 0 (AIPS-Lite 0) Memory Map	157
	4.5.2	Peripheral Bridge 1 (AIPS-Lite 1) Memory Map	161
4.6	Private :	Peripheral Bus (PPB) memory map	165
		Chapter 5 Clock Distribution	
5.1	Introduc	ction	167
5.2	Progran	nming model	167
5.3	High-Le	evel device clocking diagram	167
5.4	Clock d	lefinitions	168
	5.4.1	Device clock summary	169
5.5	Internal	l clocking requirements	171
	5.5.1	Clock divider values after reset	172
	5.5.2	VLPR mode clocking.	172
5.6	Clock C	Gating	172
5.7	Module clocks		173
	5.7.1	PMC 1-kHz LPO clock	174
	5.7.2	WDOG clocking	175
	5.7.3	Debug trace clock	175
	5.7.4	PORT digital filter clocking	175
	5.7.5	LPTMR clocking	176
	5.7.6	USB FS OTG Controller clocking.	176
	5.7.7	UART clocking.	177
	5.7.8	SDHC clocking.	177
	5.7.9	I2S clocking	178
	5.7.10	TSI clocking	178



**Title Section Number Page Chapter 6 Reset and Boot** 6.1 Introduction 181 6.2 6.2.1 6.2.2 6.2.3 6.3 6.3.1 6.3.2 6.3.3 6.3.4 Chapter 7 **Power Management** 7.1 7.2 Power modes. 191 7.3 7.4 Power mode transitions. 194 Power modes shutdown sequencing 195 7.5 7.6 7.7 **Chapter 8** Security 8.1 8.2 8.3 8.3.1 8.3.2 8.3.3 



#### **Title Section Number Page Chapter 9** Debug 9.1 Introduction 203 9.1.1 References 205 9.2 9.2.1 9.2.2 JTAG-to-cJTAG change sequence 206 9.3 9.4 9.4.1 9.5 9.5.1 9.5.2 Debug Resets 212 9.6 9.7 9.8 9.9 9.10 9.11 9.11.1 ETB Counter Control 216 9.11.2 9.12 9.13 9.14 9.14.1

## Chapter 10 Signal Multiplexing and Signal Descriptions

10.1 Introduction.



Sec	tion Nu	imber Title	Page
10.2	Signal N	Multiplexing Integration	219
	10.2.1	Port control and interrupt module features	220
	10.2.2	Clock gating	220
	10.2.3	Signal multiplexing constraints	220
10.3	Pinout		220
	10.3.1	K50 Signal Multiplexing and Pin Assignments	
	10.3.2	K50 Pinouts	227
10.4	Module	Signal Description Tables.	229
	10.4.1	Core Modules	229
	10.4.2	System Modules	230
	10.4.3	Clock Modules	231
	10.4.4	Memories and Memory Interfaces	231
	10.4.5	Analog	232
	10.4.6	Communication Interfaces.	234
	10.4.7	Human-Machine Interfaces (HMI)	238
		Chapter 11 Port control and interrupts (PORT)	
11.1	Introduc	ction	241
	11.1.1	Overview	241
	11.1.2	Features.	241
	11.1.3	Modes of operation	242
11.2	External	l signal description	243
11.3	Detailed	l signal descriptions	243
11.4	Memory	y map and register definition	243
	11.4.1	Pin Control Register n (PORTx_PCRn)	250
	11.4.2	Global Pin Control Low Register (PORTx_GPCLR)	252
	11.4.3	Global Pin Control High Register (PORTx_GPCHR)	253
	11.4.4	Interrupt Status Flag Register (PORTx_ISFR)	253
	11.4.5	Digital Filter Enable Register (PORTx_DFER)	254



Sec	tion Nu	mber Title	Page
	11.4.6	Digital Filter Clock Register (PORTx_DFCR)	255
	11.4.7	Digital Filter Width Register (PORTx_DFWR)	255
11.5	Function	nal description	256
	11.5.1	Pin control.	256
	11.5.2	Global pin control.	256
	11.5.3	External interrupts.	257
	11.5.4	Digital filter	258
		Chapter 12 System integration module (SIM)	
12.1	Introduc	tion	259
	12.1.1	Features.	259
	12.1.2	Modes of operation	259
	12.1.3	SIM Signal Descriptions	260
12.2	Memory	260	
	12.2.1	System Options Register 1 (SIM_SOPT1)	262
	12.2.2	System Options Register 2 (SIM_SOPT2)	264
	12.2.3	System Options Register 4 (SIM_SOPT4)	266
	12.2.4	System Options Register 5 (SIM_SOPT5)	269
	12.2.5	System Options Register 6 (SIM_SOPT6)	270
	12.2.6	System Options Register 7 (SIM_SOPT7)	271
	12.2.7	System Device Identification Register (SIM_SDID)	273
	12.2.8	System Clock Gating Control Register 1 (SIM_SCGC1)	274
	12.2.9	System Clock Gating Control Register 2 (SIM_SCGC2)	275
	12.2.10	System Clock Gating Control Register 3 (SIM_SCGC3)	276
	12.2.11	System Clock Gating Control Register 4 (SIM_SCGC4)	277
	12.2.12	System Clock Gating Control Register 5 (SIM_SCGC5)	280
	12.2.13	System Clock Gating Control Register 6 (SIM_SCGC6)	282
	12.2.14	System Clock Gating Control Register 7 (SIM_SCGC7)	284
	12.2.15	System Clock Divider Register 1 (SIM_CLKDIV1)	285



Sec	tion Nu	mber Title	Page	
	12.2.16	System Clock Divider Register 2 (SIM_CLKDIV2)	288	
	12.2.17	Flash Configuration Register 1 (SIM_FCFG1)	289	
	12.2.18	Flash Configuration Register 2 (SIM_FCFG2)	290	
	12.2.19	Unique Identification Register High (SIM_UIDH)	291	
	12.2.20	Unique Identification Register Mid-High (SIM_UIDMH)	292	
	12.2.21	Unique Identification Register Mid Low (SIM_UIDML)	292	
	12.2.22	Unique Identification Register Low (SIM_UIDL)	293	
12.3	Function	nal description	293	
		Chapter 13 Mode Controller		
13.1	Introduc	tion	295	
	13.1.1	Features	295	
	13.1.2	Modes of Operation.	295	
	13.1.3	MCU Reset	306	
13.2	Mode Co	309		
	13.2.1	System Reset Status Register High (MC_SRSH)	310	
	13.2.2	System Reset Status Register Low (MC_SRSL)	311	
	13.2.3	Power Mode Protection Register (MC_PMPROT)	312	
	13.2.4	Power Mode Control Register (MC_PMCTRL)	314	
		Chapter 14 Power Management Controller		
14.1	Introduc	tion	317	
14.2	Features		317	
14.3	Low-Vo	ltage Detect (LVD) System	317	
	14.3.1	LVD Reset Operation	318	
	14.3.2	LVD Interrupt Operation	318	
	14.3.3	Low-Voltage Warning (LVW) Interrupt Operation	318	
14.4	PMC Me	emory Map/Register Definition.	319	
	14.4.1	Low Voltage Detect Status and Control 1 Register (PMC_LVDSC1)	319	



Section Number Title		imber Title	Page	
	14.4.2	Low Voltage Detect Status and Control 2 Register (PMC_LVDSC2)	320	
	14.4.3	Regulator Status and Control Register (PMC_REGSC)	322	
		Chapter 15 Low-leakage wake-up unit (LLWU)		
15.1	Introduc	ction	323	
	15.1.1	Features	324	
	15.1.2	Modes of operation	324	
	15.1.3	Block diagram	325	
15.2	LLWU	Signal Descriptions	326	
15.3	Memory	y map/register definition	327	
	15.3.1	LLWU Pin Enable 1 Register (LLWU_PE1)	327	
	15.3.2	LLWU Pin Enable 2 Register (LLWU_PE2)	328	
	15.3.3	LLWU Pin Enable 3 Register (LLWU_PE3)	330	
	15.3.4	LLWU Pin Enable 4 Register (LLWU_PE4)	331	
	15.3.5	LLWU Module Enable Register (LLWU_ME)	332	
	15.3.6	LLWU Flag 1 Register (LLWU_F1)	333	
	15.3.7	LLWU Flag 2 Register (LLWU_F2)	335	
	15.3.8	LLWU Flag 3 Register (LLWU_F3)	337	
	15.3.9	LLWU Control and Status Register (LLWU_CS)	338	
15.4	Functional description.		339	
	15.4.1	LLS mode	340	
	15.4.2	VLLS modes	340	
	15.4.3	Initialization	341	
	15.4.4	Low power mode recovery	341	
		Chapter 16 Miscellaneous Control Module (MCM)		
16.1	Introduc	ction	343	
	16.1.1	Features	343	



Section Number Title		imber Title	Page	
16.2	2 Memory Map/Register Descriptions		343	
	16.2.1	Crossbar switch (AXBS) slave configuration (MCM_PLASC)	344	
	16.2.2	Crossbar switch (AXBS) master configuration (MCM_PLAMC)	344	
	16.2.3	SRAM arbitration and protection (MCM_SRAMAP)	345	
	16.2.4	Interrupt status register (MCM_ISR)	346	
	16.2.5	ETB counter control register (MCM_ETBCC)	347	
	16.2.6	ETB reload register (MCM_ETBRL)	348	
	16.2.7	ETB counter value register (MCM_ETBCNT)	349	
16.3	Function	nal Description	349	
	16.3.1	Interrupts	349	
		Chapter 17 Crossbar Switch (AXBS)		
17.1	Introduc	ction	351	
	17.1.1	Features	351	
17.2	Memory	352		
	17.2.1	Priority Registers Slave (AXBS_PRSn)	353	
	17.2.2	Control Register (AXBS_CRSn)	356	
	17.2.3	Master General Purpose Control Register (AXBS_MGPCRn)	358	
17.3	Function	nal Description	359	
	17.3.1	General operation.	359	
	17.3.2	Register coherency	360	
	17.3.3	Arbitration	360	
17.4	Initializa	ation/application information	363	
		Chapter 18 Memory Protection Unit (MPU)		
18.1	Introduc	ction	365	
18.2	Overvie	w	365	
	18.2.1	Block Diagram	365	
	18.2.2	Features	366	



Sec	Section Number Title		Page	
18.3	Memory	/ Map/Register Definition	367	
	18.3.1	Control/Error Status Register (MPU_CESR)	370	
	18.3.2	Error Address Register, Slave Port n (MPU_EARn)	372	
	18.3.3	Error Detail Register, Slave Port n (MPU_EDRn)	373	
	18.3.4	Region Descriptor n, Word 0 (MPU_RGDn_WORD0)	374	
	18.3.5	Region Descriptor n, Word 1 (MPU_RGDn_WORD1)	375	
	18.3.6	Region Descriptor n, Word 2 (MPU_RGDn_WORD2)	375	
	18.3.7	Region Descriptor n, Word 3 (MPU_RGDn_WORD3)	378	
	18.3.8	Region Descriptor Alternate Access Control n (MPU_RGDAACn)	379	
18.4	Function	381		
	18.4.1	Access Evaluation Macro.	381	
	18.4.2	Putting It All Together and Error Terminations.	382	
	18.4.3	Power Management	383	
18.5	Initializa	ation Information	383	
18.6	Applicat	tion Information	383	
		Chapter 19 Peripheral Bridge (AIPS-Lite)		
19.1	Introduc	ction	387	
	19.1.1	Features.	387	
	19.1.2	General operation	387	
19.2	Memory	map/register definition	388	
	19.2.1	Master Privilege Register A (AIPSx_MPRA)	389	
	19.2.2	Peripheral Access Control Register (AIPSx_PACRn)	393	
	19.2.3	Peripheral Access Control Register (AIPSx_PACRn)	398	
19.3	Function	nal Description	403	
	19.3.1	Access support	403	



## Section Number Title Page

# Chapter 20 Direct memory access multiplexer (DMAMUX)

20.1	Introduc	tion	405
	20.1.1	Overview	405
	20.1.2	Features	406
	20.1.3	Modes of operation	406
20.2	External	signal description.	407
20.3	Memory	map/register definition	407
	20.3.1	Channel Configuration Register (DMAMUX_CHCFGn)	408
20.4	Function	nal description	409
	20.4.1	DMA channels with periodic triggering capability	409
	20.4.2	DMA channels with no triggering capability	412
	20.4.3	"Always enabled" DMA sources	412
20.5	Initializa	ation/application information	413
	20.5.1	Reset	413
	20.5.2	Enabling and configuring sources	413
		Chapter 21	
		Direct Memory Access Controller (eDMA)	
21.1		tion	
	21.1.1	Block diagram	
	21.1.2	Block parts	418
	21.1.3	Features	420
21.2	Modes o	of operation.	421
21.3	Memory	map/register definition.	421
	21.3.1	Control Register (DMA_CR)	436
	21.3.2	Error Status Register (DMA_ES)	438
	21.3.3	Enable Request Register (DMA_ERQ)	440
	21.3.4	Enable Error Interrupt Register (DMA_EEI)	442
	21.3.5	Clear Enable Error Interrupt Register (DMA_CEEI)	444



Section Nur	mber Title	Page
21.3.6	Set Enable Error Interrupt Register (DMA_SEEI)	445
21.3.7	Clear Enable Request Register (DMA_CERQ)	446
21.3.8	Set Enable Request Register (DMA_SERQ)	447
21.3.9	Clear DONE Status Bit Register (DMA_CDNE)	448
21.3.10	Set START Bit Register (DMA_SSRT)	449
21.3.11	Clear Error Register (DMA_CERR)	450
21.3.12	Clear Interrupt Request Register (DMA_CINT)	451
21.3.13	Interrupt Request Register (DMA_INT)	451
21.3.14	Error Register (DMA_ERR)	454
21.3.15	Hardware Request Status Register (DMA_HRS)	456
21.3.16	Channel n Priority Register (DMA_DCHPRIn)	458
21.3.17	TCD Source Address (DMA_TCDn_SADDR)	459
21.3.18	TCD Signed Source Address Offset (DMA_TCDn_SOFF)	460
21.3.19	TCD Transfer Attributes (DMA_TCDn_ATTR)	460
21.3.20	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCDn_NBYTES_MLNO)	461
21.3.21	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCDn_NBYTES_MLOFFNO)	462
21.3.22	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCDn_NBYTES_MLOFFYES)	463
21.3.23	TCD Last Source Address Adjustment (DMA_TCDn_SLAST)	464
21.3.24	TCD Destination Address (DMA_TCDn_DADDR)	464
21.3.25	TCD Signed Destination Address Offset (DMA_TCDn_DOFF)	465
21.3.26	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCDn_CITER_ELINKYES)	465
21.3.27	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCDn_CITER_ELINKNO)	466
21.3.28	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCDn_DLASTSGA)	467
21.3.29	TCD Control and Status (DMA_TCDn_CSR)	468
21.3.30	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCDn_BITER_ELINKYES)	470



Sec	tion Nu	mber Title	Page
	21.3.31	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCDn_BITER_ELINKNO)	471
21.4	Function	al description	
21	21.4.1	eDMA basic data flow	
	21.4.2	Error reporting and handling.	
	21.4.3	Channel preemption.	
	21.4.4	Performance	
21.5		tion/application information	
	21.5.1	eDMA initialization	482
	21.5.2	Programming errors	484
	21.5.3	Arbitration mode considerations	484
	21.5.4	Performing DMA transfers	485
	21.5.5	Monitoring transfer descriptor status.	489
	21.5.6	Channel Linking.	490
	21.5.7	Dynamic programming.	492
		Chapter 22 External Watchdog Monitor (EWM)	
22.1	Introduc	tion	495
	22.1.1	Features	495
	22.1.2	Modes of Operation	496
	22.1.3	Block Diagram	497
22.2	EWM Si	gnal Descriptions	498
22.3	Memory	Map/Register Definition.	498
	22.3.1	Control Register (EWM_CTRL)	498
	22.3.2	Service Register (EWM_SERV)	499
	22.3.3	Compare Low Register (EWM_CMPL)	500
	22.3.4	Compare High Register (EWM_CMPH)	500
22.4	Function	al Description	501
	22.4.1	The EWM_out Signal	501



Section Number Title		Page	
	22.4.2	The EWM_in Signal	502
	22.4.3	EWM Counter	502
	22.4.4	EWM Compare Registers	502
	22.4.5	EWM Refresh Mechanism.	503
		Chapter 23 Watchdog Timer (WDOG)	
23.1	Introduc	tion	505
23.2	Features		505
23.3	Function	nal Overview	507
	23.3.1	Unlocking and Updating the Watchdog	508
	23.3.2	The Watchdog Configuration Time (WCT)	509
	23.3.3	Refreshing the Watchdog.	510
	23.3.4	Windowed Mode of Operation.	510
	23.3.5	Watchdog Disabled Mode of Operation.	510
	23.3.6	Low Power Modes of Operation	511
	23.3.7	Debug Modes of Operation.	511
23.4	Testing	the Watchdog	512
	23.4.1	Quick Test	512
	23.4.2	Byte Test	512
23.5	Backup	Reset Generator	514
23.6	Generate	ed Resets and Interrupts	514
23.7	Memory	Map and Register Definition	515
	23.7.1	Watchdog Status and Control Register High (WDOG_STCTRLH)	516
	23.7.2	Watchdog Status and Control Register Low (WDOG_STCTRLL)	518
	23.7.3	Watchdog Time-out Value Register High (WDOG_TOVALH)	518
	23.7.4	Watchdog Time-out Value Register Low (WDOG_TOVALL)	519
	23.7.5	Watchdog Window Register High (WDOG_WINH)	519
	23.7.6	Watchdog Window Register Low (WDOG_WINL)	520
	23.7.7	Watchdog Refresh Register (WDOG_REFRESH)	520



Sec	Section Number Title		Page	
	23.7.8	Watchdog Unlock Register (WDOG_UNLOCK)	520	
	23.7.9	Watchdog Timer Output Register High (WDOG_TMROUTH)	521	
	23.7.10	Watchdog Timer Output Register Low (WDOG_TMROUTL)	521	
	23.7.11	Watchdog Reset Count Register (WDOG_RSTCNT)	522	
	23.7.12	Watchdog Prescaler Register (WDOG_PRESC)	522	
23.8	Watchdo	og Operation with 8-bit access	522	
	23.8.1	General Guideline	522	
	23.8.2	Refresh and Unlock operations with 8-bit access	523	
23.9	Restriction	ons on Watchdog Operation.	524	
		Chapter 24 Multipurpose Clock Generator (MCG)		
24.1	Introduct	tion	527	
	24.1.1	Features	527	
	24.1.2	Modes of Operation	530	
24.2	External	Signal Description	531	
24.3	Memory	Map/Register Definition.	531	
	24.3.1	MCG Control 1 Register (MCG_C1)	532	
	24.3.2	MCG Control 2 Register (MCG_C2)	533	
	24.3.3	MCG Control 3 Register (MCG_C3)	534	
	24.3.4	MCG Control 4 Register (MCG_C4)	535	
	24.3.5	MCG Control 5 Register (MCG_C5)	536	
	24.3.6	MCG Control 6 Register (MCG_C6)	538	
	24.3.7	MCG Status Register (MCG_S)	539	
	24.3.8	MCG Auto Trim Control Register (MCG_ATC)	541	
	24.3.9	MCG Auto Trim Compare Value High Register (MCG_ATCVH)	541	
	24.3.10	MCG Auto Trim Compare Value Low Register (MCG_ATCVL)	542	
24.4	Function	nal Description	542	
	24.4.1	MCG Mode State Diagram	542	
	24.4.2	Low Power Bit Usage	547	



Section Number Title		mber Title	Page
	24.4.3	MCG Internal Reference Clocks.	547
	24.4.4	External Reference Clock	548
	24.4.5	MCG Fixed Frequency Clock	548
	24.4.6	MCG PLL Clock	549
	24.4.7	MCG Auto TRIM (ATM)	549
24.5	Initializat	tion / Application Information	550
	24.5.1	MCG Module Initialization Sequence	550
	24.5.2	Using a 32.768 kHz Reference	552
	24.5.3	MCG Mode Switching	553
		Chapter 25 Oscillator (OSC)	
25.1	Introduct	ion	563
25.2	Features	and Modes	563
25.3	Block Dia	agram	564
25.4	OSC Sign	nal Descriptions	564
25.5	External	Crystal / Resonator Connections	565
25.6	External	Clock Connections	566
25.7	Memory	Map/Register Definitions	567
	25.7.1	OSC Memory Map/Register Definition.	567
25.8	Functiona	al Description	568
	25.8.1	OSC Module States	568
	25.8.2	OSC Module Modes	570
	25.8.3	Counter	572
	25.8.4	Reference Clock Pin Requirements	572
25.9	Reset		572
25.10	Low Pow	ver Modes Operation	573
25 11	Intonner		572



**Title Section Number** Page Chapter 26 **RTC Oscillator** 26.1 26.1.1 Features and Modes. 575 26.1.2 26.2 26.2.1 26.2.2 26.3 26.4 26.5 26.6 Reset Overview. 578 26.7 Interrupts 578 Chapter 27 Flash Memory Controller (FMC) 27.1 27.1.1 27.1.2 Features 579 27.2 27.3 27.4 27.4.1 27.4.2 27.4.3 Cache Tag Storage (FMC\_TAGVDW0Sn)......594 27.4.4 27.4.5 27.4.6 27.4.7 27.4.8 



Sec	Section Number Title		Page
	27.4.9	Cache Data Storage (lower word) (FMC_DATAW0SnL)	599
	27.4.10	Cache Data Storage (upper word) (FMC_DATAW1SnU)	600
	27.4.11	Cache Data Storage (lower word) (FMC_DATAW1SnL)	601
	27.4.12	Cache Data Storage (upper word) (FMC_DATAW2SnU)	602
	27.4.13	Cache Data Storage (lower word) (FMC_DATAW2SnL)	603
	27.4.14	Cache Data Storage (upper word) (FMC_DATAW3SnU)	604
	27.4.15	Cache Data Storage (lower word) (FMC_DATAW3SnL)	605
27.5	Function	nal description	605
		Chapter 28 Flash Memory Module (FTFL)	
28.1	Introduc	tion	607
	28.1.1	Features	608
	28.1.2	Block Diagram	608
	28.1.3	Glossary	609
28.2	External	Signal Description.	610
28.3	Memory	Map and Registers	611
	28.3.1	Flash Configuration Field Description	611
	28.3.2	Program Flash IFR Map	611
	28.3.3	Register Descriptions	612
28.4	Function	nal Description	621
	28.4.1	Program Flash Memory Swap	621
	28.4.2	Interrupts	622
	28.4.3	Flash Operation in Low-Power Modes	622
	28.4.4	Functional Modes of Operation.	623
	28.4.5	Flash Reads and Ignored Writes	623
	28.4.6	Read While Write (RWW)	623
	28.4.7	Flash Program and Erase	623
	28.4.8	FTFL Command Operations	624
	28.4.9	Margin Read Commands	629



29.1. 29.1. 29.1.	11 Security	652
29.1 Introd 29.1. 29.1. 29.1.	12 Reset Sequence	
29.1 Introd 29.1. 29.1. 29.1.	•	654
29.1. 29.1. 29.1.	Chanter 29	
29.1. 29.1. 29.1.	External Bus Interface (FlexBus)	
29.1.: 29.1.:	duction	655
29.1.	1 Overview	655
	2 Features	655
29.2 Signa	3 Modes of Operation	656
	al Descriptions	656
29.2.	1 Address and Data Buses (FB_An, FB_Dn, FB_ADn)	657
29.2.	2 Chip Selects (FB_CS[5:0])	657
29.2.	3 Byte Enables (FB_BE_31_24, FB_BE_23_16, FB_BE_15_8, FB_BE_7_0)	658
29.2.	4 Output Enable (FB_OE)	658
29.2.	5 Read/Write (FB_R/W)	658
29.2.	6 Transfer Start/Address Latch Enable (FB_TS/FB_ALE)	658
29.2.	7 Transfer Size (FB_TSIZ[1:0])	659
29.2.	8 Transfer Burst (FB_TBST)	659
29.2.	9 Transfer Acknowledge (FB_TA)	660
29.3 Mem	ory Map/Register Definition	660
29.3.	1 Chip select address register (FB_CSAR <i>n</i> )	662
29.3.	2 Chip select mask register (FB_CSMRn)	663
29.3.	3 Chip select control register (FB_CSCRn)	664
29.3.	4 Chip select port multiplexing control register (FB_CSPMCR)	667
29.4 Func	tional Description	668
29.4.	1 Chip-Select Operation	668
29.4.	2 Data Transfer Operation	670
29.4.	3 Data Byte Alignment and Physical Connections	670
29.4.	4 Address/Data Bus Multiplexing	671



Section Number Title		Page	
	29.4.5	Bus Cycle Execution.	672
	29.4.6	FlexBus Timing Examples	674
	29.4.7	Burst Cycles	692
	29.4.8	Extended Transfer Start/Address Latch Enable	701
	29.4.9	Bus Errors	701
29.5	Initializa	ation/Application Information	702
	29.5.1	Initializing a Chip Select	702
	29.5.2	Reconfiguring a Chip Select	702
		Chapter 30 EzPort	
30.1	Overvie	W	703
	30.1.1	Introduction	703
	30.1.2	Features	704
	30.1.3	Modes of Operation	704
30.2	External Signal Description.		705
	30.2.1	EzPort Clock (EZP_CK)	705
	30.2.2	EzPort Chip Select (EZP_CS)	705
	30.2.3	EzPort Serial Data In (EZP_D)	706
	30.2.4	EzPort Serial Data Out (EZP_Q)	706
30.3	Commar	nd Definition	706
	30.3.1	Command Descriptions	707
30.4	Flash Mo	emory Map for EzPort Access	711
		Chapter 31 Cyclic redundancy check (CRC)	
31.1	Introduc	tion	713
	31.1.1	Features	713
	31.1.2	Block diagram	713



Sec	tion Nu	imber Title	Page
	31.1.3	Modes of operation	714
31.2	Memory	map and register descriptions	714
	31.2.1	CRC Data Register (CRC_CRC)	715
	31.2.2	CRC Polynomial Register (CRC_GPOLY)	716
	31.2.3	CRC Control Register (CRC_CTRL)	717
31.3	Function	nal description	718
	31.3.1	CRC initialization/re-initialization	718
	31.3.2	CRC calculations	718
	31.3.3	Transpose feature	719
	31.3.4	CRC result complement	721
		Chapter 32 Analog-to-Digital Converter (ADC)	
32.1	Introduc	etion	723
	32.1.1	Features	
	32.1.2	Block diagram	724
32.2	ADC Signal Descriptions.		725
	32.2.1	Analog power (VDDA)	726
	32.2.2	Analog ground (VSSA)	726
	32.2.3	Voltage reference select	726
	32.2.4	Analog channel inputs (ADx)	727
	32.2.5	Differential analog channel inputs (DADx)	727
32.3	Register	Definition	727
	32.3.1	ADC status and control registers 1 (ADCx_SC1n)	730
	32.3.2	ADC configuration register 1 (ADCx_CFG1)	733
	32.3.3	Configuration register 2 (ADCx_CFG2)	735
	32.3.4	ADC data result register (ADCx_Rn)	736
	32.3.5	Compare value registers (ADCx_CVn)	737
	32.3.6	Status and control register 2 (ADCx_SC2)	738
	32.3.7	Status and control register 3 (ADCx_SC3)	740



Sect	tion Nu	mber Title	Page
	32.3.8	ADC offset correction register (ADCx_OFS)	741
	32.3.9	ADC plus-side gain register (ADCx_PG)	742
	32.3.10	ADC minus-side gain register (ADCx_MG)	742
	32.3.11	ADC plus-side general calibration value register (ADCx_CLPD)	743
	32.3.12	ADC plus-side general calibration value register (ADCx_CLPS)	744
	32.3.13	ADC plus-side general calibration value register (ADCx_CLP4)	744
	32.3.14	ADC plus-side general calibration value register (ADCx_CLP3)	745
	32.3.15	ADC plus-side general calibration value register (ADCx_CLP2)	745
	32.3.16	ADC plus-side general calibration value register (ADCx_CLP1)	746
	32.3.17	ADC plus-side general calibration value register (ADCx_CLP0)	746
	32.3.18	ADC PGA register (ADCx_PGA)	747
	32.3.19	ADC minus-side general calibration value register (ADCx_CLMD)	748
	32.3.20	ADC minus-side general calibration value register (ADCx_CLMS)	749
	32.3.21	ADC minus-side general calibration value register (ADCx_CLM4)	749
	32.3.22	ADC minus-side general calibration value register (ADCx_CLM3)	750
	32.3.23	ADC minus-side general calibration value register (ADCx_CLM2)	750
	32.3.24	ADC minus-side general calibration value register (ADCx_CLM1)	751
	32.3.25	ADC minus-side general calibration value register (ADCx_CLM0)	751
32.4	Function	al description	752
	32.4.1	PGA functional description.	752
	32.4.2	Clock select and divide control.	753
	32.4.3	Voltage reference selection	753
	32.4.4	Hardware trigger and channel selects	754
	32.4.5	Conversion control.	755
	32.4.6	Automatic compare function.	762
	32.4.7	Calibration function	763
	32.4.8	User defined offset function	765
	32.4.9	Temperature sensor	766
	32.4.10	MCU wait mode operation	766



Section Number		mber Title	Page
	32.4.11	MCU Normal Stop mode operation.	767
	32.4.12	MCU Low Power Stop mode operation	768
32.5	Initializa	tion information	768
	32.5.1	ADC module initialization example	769
32.6	Applicat	ion information	771
	32.6.1	External pins and routing	771
	32.6.2	Sources of error	773
		Chapter 33 Comparator (CMP)	
33.1	Introduct	tion	779
33.2	CMP Fea	atures	779
33.3	6-bit DA	C Key Features	780
33.4	ANMUX	Key Features	781
33.5	CMP, D	AC, and ANMUX Diagram	781
33.6	CMP Blo	ock Diagram	782
33.7	Memory	Map/Register Definitions	784
	33.7.1	CMP Control Register 0 (CMPx_CR0)	785
	33.7.2	CMP Control Register 1 (CMPx_CR1)	786
	33.7.3	CMP Filter Period Register (CMPx_FPR)	787
	33.7.4	CMP Status and Control Register (CMPx_SCR)	788
	33.7.5	DAC Control Register (CMPx_DACCR)	789
	33.7.6	MUX Control Register (CMPx_MUXCR)	790
33.8	CMP Fu	nctional Description	791
	33.8.1	CMP Functional Modes.	792
	33.8.2	Power Modes	801
	33.8.3	Startup and Operation.	802
	33.8.4	Low Pass Filter	803
33.9	CMP Int	errupts	805
33.10	CMP DN	AA Support	805



Sect	Section Number Title		Page	
33.11	Digital t	to Analog Converter Block Diagram	805	
33.12	DAC Fu	unctional Description	806	
	33.12.1	Voltage Reference Source Select	806	
33.13	DAC Re	esets	806	
33.14	DAC CI	locks	806	
33.15	DAC In	terrupts	807	
		Chapter 34 12-bit Digital-to-Analog Converter (DAC)		
34.1	Introduc	ction	809	
34.2	Features	S	809	
34.3	Block D	Diagram	809	
34.4	Memory	y Map/Register Definition	810	
	34.4.1	DAC Data Low Register (DACx_DATnL)	814	
	34.4.2	DAC Data High Register (DACx_DATnH)	815	
	34.4.3	DAC Status Register (DACx_SR)	815	
	34.4.4	DAC Control Register (DACx_C0)	816	
	34.4.5	DAC Control Register 1 (DACx_C1)	817	
	34.4.6	DAC Control Register 2 (DACx_C2)	818	
34.5	Function	nal Description	818	
	34.5.1	DAC Data Buffer Operation.	819	
	34.5.2	DMA Operation	820	
	34.5.3	Resets	820	
	34.5.4	Low Power Mode Operation	820	
		Chapter 35 Operational Amplifier (OPAMP)		
35.1	Introduc	ction	823	
	35.1.1	Features	823	
	35.1.2	Block Diagram	824	
	35.1.3	Low power modes	824	



Section Number		mber Title	Page	
	35.1.4	Operating modes	825	
35.2	Signal D	Signal Description.		
	35.2.1	INPx+	827	
	35.2.2	INPx	827	
	35.2.3	VOUTx	827	
35.3	Memory Map and Registers		828	
	35.3.1	Control Register 0 (OPAMPx_C0)	828	
	35.3.2	Control Register 1 (OPAMPx_C1)	829	
	35.3.3	Control Register 2 (OPAMPx_C2)	830	
35.4	Function	nal Description.	831	
	35.4.1	Operational Amplifier Configuration.	831	
	35.4.2	Buffer Configuration.	831	
	35.4.3	Non-Inverting/Inverting PGA Configuration.	832	
36.1	Introduc	Chapter 36 Transimpedance Amplifier (TRIAMP)		
	36.1.1	Features	835	
	36.1.2	Module operation in low power modes	835	
	36.1.3	Block Diagram	836	
	36.1.4	Signal Description.	836	
	36.1.5	inp_3v	836	
	36.1.6	inn_3v	836	
	36.1.7	out_3v	836	
36.2	Memory	Map/Register Definition	837	
	36.2.1	Control Register 0 (TRIAMPx_C0)	837	
36.3	Functional Description.		838	
	36.3.1	Trans-Impedance Amplifier Configuration	838	
	36.3.2	Photodiode Zero-Biased Operation	838	
	36.3.3	Photodiode Reverse-Biased Operation.	838	



**Title Section Number Page** Chapter 37 **Voltage Reference (VREFV1)** 37.1 Introduction 841 37.1.1 Overview 842 37.1.2 Features 842 37.1.3 37.1.4 Memory Map and Register Definition......843 37.2 37.2.1 VREF Trim Register (VREF\_TRM).....844 37.2.2 VREF Status and Control Register (VREF\_SC)......845 37.3 37.3.1 Voltage Reference Disabled, SC[VREFEN] = 0......846 37.3.2 Voltage Reference Enabled, SC[VREFEN] = 1......846 37.4 **Chapter 38** Programmable Delay Block (PDB) 38.1 Introduction 849 38.1.1 Features 849 38.1.2 38.1.3 38.1.4 38.1.5 38.1.6 38.2 PDB Signal Descriptions 853 38.3 38.3.1 38.3.2 Modulus Register (PDBx MOD)......857 38.3.3 Counter Register (PDBx\_CNT)......858

38.3.4



Section Number Title		Page	
	38.3.5	Channel n Control Register 1 (PDBx_CHnC1)	859
	38.3.6	Channel n Status Register (PDBx_CHnS)	860
	38.3.7	Channel n Delay 0 Register (PDBx_CHnDLY0)	861
	38.3.8	Channel n Delay 1 Register (PDBx_CHnDLY1)	861
	38.3.9	DAC Interval Trigger n Control Register (PDBx_DACINTCn)	862
	38.3.10	DAC Interval n Register (PDBx_DACINTn)	862
	38.3.11	Pulse-Out n Enable Register (PDBx_POEN)	863
	38.3.12	Pulse-Out n Delay Register (PDBx_POnDLY)	863
38.4	Function	al Description	864
	38.4.1	PDB Pre-trigger and Trigger Outputs.	864
	38.4.2	PDB Trigger Input Source Selection	866
	38.4.3	DAC Interval Trigger Outputs	866
	38.4.4	Pulse-Out's	867
	38.4.5	Updating the Delay Registers	867
	38.4.6	Interrupts	869
	38.4.7	DMA	869
38.5	Applicat	ion Information	869
	38.5.1	Impact of Using the Prescaler and Multiplication Factor on Timing Resolution	869
		Chapter 39 FlexTimer (FTM)	
39.1	Introduc	tion	871
	39.1.1	FlexTimer Philosophy	871
	39.1.2	Features	872
	39.1.3	Modes of Operation	873
	39.1.4	Block Diagram.	873
39.2	FTM Signal Descriptions		876
	39.2.1	EXTCLK — FTM External Clock	876
	39.2.2	CHn — FTM Channel (n) I/O Pin	876
	39.2.3	FAULTj — FTM Fault Input	876



Section Numbe		mber Title	Page
	39.2.4	PHA — FTM Quadrature Decoder Phase A Input	877
	39.2.5	PHB — FTM Quadrature Decoder Phase B Input	877
39.3	Memory	Map and Register Definition.	877
	39.3.1	Module Memory Map	877
	39.3.2	Register Descriptions	877
	39.3.3	Status and Control (FTMx_SC)	884
	39.3.4	Counter (FTMx_CNT)	885
	39.3.5	Modulo (FTMx_MOD)	886
	39.3.6	Channel (n) Status and Control (FTMx_CnSC)	
	39.3.7	Channel (n) Value (FTMx_CnV)	890
	39.3.8	Counter Initial Value (FTMx_CNTIN)	891
	39.3.9	Capture and Compare Status (FTMx_STATUS)	891
	39.3.10	Features Mode Selection (FTMx_MODE)	894
	39.3.11	Synchronization (FTMx_SYNC)	895
	39.3.12	Initial State for Channels Output (FTMx_OUTINIT)	898
	39.3.13	Output Mask (FTMx_OUTMASK)	899
	39.3.14	Function for Linked Channels (FTMx_COMBINE)	901
	39.3.15	Deadtime Insertion Control (FTMx_DEADTIME)	906
	39.3.16	FTM External Trigger (FTMx_EXTTRIG)	907
	39.3.17	Channels Polarity (FTMx_POL)	909
	39.3.18	Fault Mode Status (FTMx_FMS)	911
	39.3.19	Input Capture Filter Control (FTMx_FILTER)	913
	39.3.20	Fault Control (FTMx_FLTCTRL)	915
	39.3.21	Quadrature Decoder Control and Status (FTMx_QDCTRL)	917
	39.3.22	Configuration (FTMx_CONF)	919
	39.3.23	FTM Fault Input Polarity (FTMx_FLTPOL)	920
	39.3.24	Synchronization Configuration (FTMx_SYNCONF)	922
	39.3.25	FTM Inverting Control (FTMx_INVCTRL)	924
	39.3.26	FTM Software Output Control (FTMx_SWOCTRL)	925



Section Number		mber Title	Page
	39.3.27	FTM PWM Load (FTMx_PWMLOAD)	927
39.4	Function	al Description	929
	39.4.1	Clock Source	929
	39.4.2	Prescaler	930
	39.4.3	Counter	930
	39.4.4	Input Capture Mode	935
	39.4.5	Output Compare Mode	938
	39.4.6	Edge-Aligned PWM (EPWM) Mode	939
	39.4.7	Center-Aligned PWM (CPWM) Mode	941
	39.4.8	Combine Mode	942
	39.4.9	Complementary Mode	950
	39.4.10	Registers Updated from Write Buffers	951
	39.4.11	PWM Synchronization	953
	39.4.12	Inverting.	969
	39.4.13	Software Output Control	970
	39.4.14	Deadtime Insertion.	972
	39.4.15	Output Mask	975
	39.4.16	Fault Control.	976
	39.4.17	Polarity Control.	979
	39.4.18	Initialization	980
	39.4.19	Features Priority	980
	39.4.20	Channel Trigger Output	981
	39.4.21	Initialization Trigger	982
	39.4.22	Capture Test Mode	984
	39.4.23	DMA	985
	39.4.24	Dual Edge Capture Mode	986
	39.4.25	Quadrature Decoder Mode	993
	39.4.26	BDM Mode	998
	39.4.27	Intermediate Load	999



Section Number		mber Title	Page
	39.4.28	Global Time Base (GTB)	1001
39.5	Reset Ov	verview	1002
39.6	FTM Interrupts		1004
	39.6.1	Timer Overflow Interrupt	1004
	39.6.2	Channel (n) Interrupt	1004
	39.6.3	Fault Interrupt.	1004
		Chapter 40 Periodic Interrupt Timer (PIT)	
40.1	Introduct	tion	1007
	40.1.1	Block Diagram	1007
	40.1.2	Features	1008
40.2	Signal D	escription	1008
40.3	Memory Map/Register Description.		1009
	40.3.1	PIT Module Control Register (PIT_MCR)	1010
	40.3.2	Timer Load Value Register (PIT_LDVALn)	1011
	40.3.3	Current Timer Value Register (PIT_CVALn)	1011
	40.3.4	Timer Control Register (PIT_TCTRLn)	1012
	40.3.5	Timer Flag Register (PIT_TFLGn)	1012
40.4	Function	al Description	1013
	40.4.1	General	1013
	40.4.2	Interrupts	1014
40.5	Initializa	tion and Application Information	1015
		Chapter 41 Low power timer (LPTMR)	
41.1	Introduct	tion	1017
	41.1.1	Features	1017
	41.1.2	Modes of operation	1017
41.2	LPTMR	signal descriptions	1018
	41.2.1	Detailed signal descriptions.	1018



Section Number		imber Title	Page	
41.3	Memory map and register definition		1019	
	41.3.1	Low Power Timer Control Status Register (LPTMRx_CSR)	1020	
	41.3.2	Low Power Timer Prescale Register (LPTMRx_PSR)	1021	
	41.3.3	Low Power Timer Compare Register (LPTMRx_CMR)		
	41.3.4	Low Power Timer Counter Register (LPTMRx_CNR)		
41.4	Function	Functional description.		
	41.4.1	LPTMR power and reset	1024	
	41.4.2	LPTMR clocking	1024	
	41.4.3	LPTMR prescaler/glitch filter		
	41.4.4	LPTMR compare	1026	
	41.4.5	LPTMR counter	1026	
	41.4.6	LPTMR hardware trigger	1027	
	41.4.7	LPTMR interrupt		
		Chapter 42 Carrier Modulator Transmitter (CMT)		
42.1	Introduc	ction	1029	
42.2	Features			
42.3	Block Diagram			
42.4	Modes o	Modes of Operation.		
	42.4.1	Wait Mode Operation	1032	
	42.4.2	Stop Mode Operation	1032	
42.5	CMT Ex	xternal Signal Descriptions	1033	
	42.5.1	CMT_IRO — Infrared Output	1033	
42.6	Memory	Map/Register Definition		
	42.6.1	CMT Carrier Generator High Data Register 1 (CMT_CGH1)	1034	
	42.6.2	CMT Carrier Generator Low Data Register 1 (CMT_CGL1)	1035	
	42.6.3	CMT Carrier Generator High Data Register 2 (CMT_CGH2)	1036	
	42.6.4	CMT Carrier Generator Low Data Register 2 (CMT_CGL2)	1036	
	42.6.5	CMT Output Control Register (CMT_OC)	1037	



Sec	tion Nu	mber Title	Page
	42.6.6	CMT Modulator Status and Control Register (CMT_MSC)	1038
	42.6.7	CMT Modulator Data Register Mark High (CMT_CMD1)	1039
	42.6.8	CMT Modulator Data Register Mark Low (CMT_CMD2)	1040
	42.6.9	CMT Modulator Data Register Space High (CMT_CMD3)	1040
	42.6.10	CMT Modulator Data Register Space Low (CMT_CMD4)	1041
	42.6.11	CMT Primary Prescaler Register (CMT_PPS)	1041
	42.6.12	CMT Direct Memory Access (CMT_DMA)	1042
42.7	Function	nal Description	1043
	42.7.1	Clock Divider	1043
	42.7.2	Carrier Generator	1043
	42.7.3	Modulator	1046
	42.7.4	Extended Space Operation.	1050
42.8	CMT Int	terrupts and DMA	1051
		Chapter 43 Real Time Clock (RTC)	
43.1	Introduc	tion	1053
	43.1.1	Features	1053
	43.1.2	Modes of operation	1053
	43.1.3	RTC signal descriptions.	1054
43.2	Register	1054	
	43.2.1	RTC Time Seconds Register (RTC_TSR)	1055
	43.2.2	RTC Time Prescaler Register (RTC_TPR)	1056
	43.2.3	RTC Time Alarm Register (RTC_TAR)	1056
	43.2.4	RTC Time Compensation Register (RTC_TCR)	1057
	43.2.5	RTC Control Register (RTC_CR)	1058
	43.2.6	RTC Status Register (RTC_SR)	1060
	43.2.7	RTC Lock Register (RTC_LR)	1061
	43.2.8	RTC Interrupt Enable Register (RTC_IER)	1062
	43.2.9	RTC Write Access Register (RTC_WAR)	1063



Sec	tion Nu	mber Title	Page
	43.2.10	RTC Read Access Register (RTC_RAR)	1064
43.3	Function	al description	1065
	43.3.1	Power, clocking and reset	1065
	43.3.2	Time counter	1066
	43.3.3	Compensation	1067
	43.3.4	Time alarm	1068
	43.3.5	Update mode	1068
	43.3.6	Register lock	1068
	43.3.7	Access control.	1069
	43.3.8	Interrupt	1069
		Chapter 44 Universal Serial Bus OTG Controller (USBOTG)	
44.1	Introduct	tion	1071
	44.1.1	USB	1071
	44.1.2	USB On-The-Go	1072
	44.1.3	USB-FS Features	1073
44.2	Function	al Description	1073
	44.2.1	Data Structures	1073
44.3	Program	mers Interface	1074
	44.3.1	Buffer Descriptor Table	1074
	44.3.2	Rx vs. Tx as a USB Target Device or USB Host	1075
	44.3.3	Addressing Buffer Descriptor Table Entries	1076
	44.3.4	Buffer Descriptor Formats	1076
	44.3.5	USB Transaction	1079
44.4	Memory	Map/Register Definitions	1081
	44.4.1	Peripheral ID Register (USBx_PERID)	1083
	44.4.2	Peripheral ID Complement Register (USBx_IDCOMP)	1084
	44.4.3	Peripheral Revision Register (USBx_REV)	1084
	44.4.4	Peripheral Additional Info Register (USBx_ADDINFO)	1085



Sec	tion Nu	mber Title	Page
	44.4.5	OTG Interrupt Status Register (USBx_OTGISTAT)	1085
	44.4.6	OTG Interrupt Control Register (USBx_OTGICR)	1086
	44.4.7	OTG Status Register (USBx_OTGSTAT)	1087
	44.4.8	OTG Control Register (USBx_OTGCTL)	1088
	44.4.9	Interrupt Status Register (USBx_ISTAT)	1089
	44.4.10	Interrupt Enable Register (USBx_INTEN)	1090
	44.4.11	Error Interrupt Status Register (USBx_ERRSTAT)	1091
	44.4.12	Error Interrupt Enable Register (USBx_ERREN)	1092
	44.4.13	Status Register (USBx_STAT)	1094
	44.4.14	Control Register (USBx_CTL)	1095
	44.4.15	Address Register (USBx_ADDR)	1096
	44.4.16	BDT Page Register 1 (USBx_BDTPAGE1)	1097
	44.4.17	Frame Number Register Low (USBx_FRMNUML)	1097
	44.4.18	Frame Number Register High (USBx_FRMNUMH)	1098
	44.4.19	Token Register (USBx_TOKEN)	1098
	44.4.20	SOF Threshold Register (USBx_SOFTHLD)	1099
	44.4.21	BDT Page Register 2 (USBx_BDTPAGE2)	1100
	44.4.22	BDT Page Register 3 (USBx_BDTPAGE3)	1100
	44.4.23	Endpoint Control Register (USBx_ENDPTn)	1100
	44.4.24	USB Control Register (USBx_USBCTRL)	1102
	44.4.25	USB OTG Observe Register (USBx_OBSERVE)	1102
	44.4.26	USB OTG Control Register (USBx_CONTROL)	1103
	44.4.27	USB Transceiver Control Register 0 (USBx_USBTRC0)	1104
14.5	OTG and	l Host Mode Operation	1105
14.6	Host Mo	de Operation Examples	1105
14.7	On-The-	Go Operation	1108
	44.7.1	OTG Dual Role A Device Operation	1109
	44.7.2	OTG Dual Role B Device Operation	1110



## Chapter 45 USB Device Charger Detection Module (USBDCD)

45.1	Preface		1113
	45.1.1	References	1113
	45.1.2	Acronyms and Abbreviations	1113
	45.1.3	Glossary	1114
45.2	Introduc	tion	1114
	45.2.1	Block Diagram	1114
	45.2.2	Features	1115
	45.2.3	Modes of Operation	1115
45.3	Module	Signal Description	1116
	45.3.1	USB Signal Descriptions	1116
45.4	Memory	Map/Register Definition.	1117
	45.4.1	Control Register (USBDCD_CONTROL)	1118
	45.4.2	Clock Register (USBDCD_CLOCK)	1119
	45.4.3	Status Register (USBDCD_STATUS)	1120
	45.4.4	TIMER0 Register (USBDCD_TIMER0)	1122
	45.4.5	USBDCD_TIMER1	1123
	45.4.6	USBDCD_TIMER2	1123
45.5	Function	nal Description	1124
	45.5.1	The Charger Detection Sequence.	1125
	45.5.2	Interrupts and Events	1135
	45.5.3	Resets	1136
45.6	Initializa	ation Information	1137
45.7	Applicat	ion Information	1137
	45.7.1	External Pullups	1137
	45.7.2	Dead or Weak Battery	1137
	45.7.3	Handling Unplug Events	1138



**Title Section Number Page Chapter 46 USB Voltage Regulator** 46.1 Introduction 1139 46.1.1 Overview 1139 46.1.2 Features 1140 46.1.3 46.2 Chapter 47 SPI (DSPI) Introduction 1143 47.1 47.1.1 47.1.2 Features 1144 47.1.3 47.1.4 47.2 47.2.1 47.2.2 47.2.3 47.2.4 47.2.5 47.2.6 47.2.7 47.3

DSPI Clock and Transfer Attributes Register (In Slave Mode) (SPIx CTARn SLAVE)......1161

47.3.1

47.3.2

47.3.3

47.3.4

47.3.5

47.3.6



Section Number		mber Title	Page
	47.3.7	DSPI PUSH TX FIFO Register In Master Mode (SPIx_PUSHR)	1167
	47.3.8	DSPI PUSH TX FIFO Register In Slave Mode (SPIx_PUSHR_SLAVE)	1169
	47.3.9	DSPI POP RX FIFO Register (SPIx_POPR)	1169
	47.3.10	DSPI Transmit FIFO Registers (SPIx_TXFRn)	1170
	47.3.11	DSPI Receive FIFO Registers (SPIx_RXFRn)	1170
47.4	Function	al Description	1171
	47.4.1	Start and Stop of DSPI Transfers	1172
	47.4.2	Serial Peripheral Interface (SPI) Configuration	1172
	47.4.3	DSPI Baud Rate and Clock Delay Generation	1176
	47.4.4	Transfer Formats	1180
	47.4.5	Continuous Serial Communications Clock	1185
	47.4.6	Slave Mode Operation Constraints	1186
	47.4.7	Interrupts/DMA Requests	1187
	47.4.8	Power Saving Features.	1189
47.5	Initializa	1190	
	47.5.1	How to Manage DSPI Queues	1190
	47.5.2	Switching Master and Slave Mode	1191
	47.5.3	Baud Rate Settings	1192
	47.5.4	Delay Settings	1192
	47.5.5	Calculation of FIFO Pointer Addresses.	1193
		Chapter 48 Inter-Integrated Circuit (I2C)	
48.1	Introduc	tion	1197
	48.1.1	Features	1197
	48.1.2	Modes of Operation	1198
	48.1.3	Block Diagram	1198
48.2	I2C Sign	nal Descriptions	1199
48.3	Memory	Map and Register Descriptions.	1199
	48.3.1	I2C Address Register 1 (I2Cx_A1)	1201



Sect	Section Number Title		Page	
	48.3.2	I2C Frequency Divider register (I2Cx_F)	1201	
	48.3.3	I2C Control Register 1 (I2Cx_C1)	1202	
	48.3.4	I2C Status Register (I2Cx_S)	1204	
	48.3.5	I2C Data I/O register (I2Cx_D)	1206	
	48.3.6	I2C Control Register 2 (I2Cx_C2)	1207	
	48.3.7	I2C Programmable Input Glitch Filter register (I2Cx_FLT)	1208	
	48.3.8	I2C Range Address register (I2Cx_RA)	1208	
	48.3.9	I2C SMBus Control and Status register (I2Cx_SMB)	1209	
	48.3.10	I2C Address Register 2 (I2Cx_A2)	1210	
	48.3.11	I2C SCL Low Timeout Register High (I2Cx_SLTH)	1211	
	48.3.12	I2C SCL Low Timeout Register Low (I2Cx_SLTL)	1211	
48.4	Function	al Description	1212	
	48.4.1	I2C Protocol	1212	
	48.4.2	10-bit Address	1217	
	48.4.3	Address Matching	1218	
	48.4.4	System Management Bus Specification	1219	
	48.4.5	Resets	1222	
	48.4.6	Interrupts	1222	
	48.4.7	Programmable Input Glitch Filter.	1224	
	48.4.8	Address Matching Wakeup	1224	
	48.4.9	DMA Support	1225	
48.5	Initializa	tion/Application Information	1225	
		Chapter 49 Universal Asynchronous Receiver/Transmitter (UART)		
49.1	Introduc	tion	1229	
	49.1.1	Features	1229	
	49.1.2	Modes of operation	1231	
49.2	UART s	ignal descriptions	1232	
	49.2.1	Detailed signal descriptions.	1232	



Section Number Title			Page	
49.3	Memory	map and registers	1233	
	49.3.1	UART Baud Rate Registers:High (UARTx_BDH)	1243	
	49.3.2	UART Baud Rate Registers: Low (UARTx_BDL)	1244	
	49.3.3	UART Control Register 1 (UARTx_C1)	1245	
	49.3.4	UART Control Register 2 (UARTx_C2)	1247	
	49.3.5	UART Status Register 1 (UARTx_S1)	1249	
	49.3.6	UART Status Register 2 (UARTx_S2)	1252	
	49.3.7	UART Control Register 3 (UARTx_C3)	1254	
	49.3.8	UART Data Register (UARTx_D)	1255	
	49.3.9	UART Match Address Registers 1 (UARTx_MA1)	1257	
	49.3.10	UART Match Address Registers 2 (UARTx_MA2)	1257	
	49.3.11	UART Control Register 4 (UARTx_C4)	1258	
	49.3.12	UART Control Register 5 (UARTx_C5)	1259	
	49.3.13	UART Extended Data Register (UARTx_ED)	1260	
	49.3.14	UART Modem Register (UARTx_MODEM)	1261	
	49.3.15	UART Infrared Register (UARTx_IR)	1262	
	49.3.16	UART FIFO Parameters (UARTx_PFIFO)	1263	
	49.3.17	UART FIFO Control Register (UARTx_CFIFO)	1265	
	49.3.18	UART FIFO Status Register (UARTx_SFIFO)	1266	
	49.3.19	UART FIFO Transmit Watermark (UARTx_TWFIFO)	1267	
	49.3.20	UART FIFO Transmit Count (UARTx_TCFIFO)	1268	
	49.3.21	UART FIFO Receive Watermark (UARTx_RWFIFO)	1268	
	49.3.22	UART FIFO Receive Count (UARTx_RCFIFO)	1269	
	49.3.23	UART 7816 Control Register (UARTx_C7816)	1270	
	49.3.24	UART 7816 Interrupt Enable Register (UARTx_IE7816)	1271	
	49.3.25	UART 7816 Interrupt Status Register (UARTx_IS7816)	1273	
	49.3.26	UART 7816 Wait Parameter Register (UARTx_WP7816T0)	1275	
	49.3.27	UART 7816 Wait Parameter Register (UARTx_WP7816T1)	1276	
	49.3.28	UART 7816 Wait N Register (UARTx_WN7816)	1277	



Sec	tion Nu	mber Title	Page
	49.3.29	UART 7816 Wait FD Register (UARTx_WF7816)	1277
	49.3.30	UART 7816 Error Threshold Register (UARTx_ET7816)	1278
	49.3.31	UART 7816 Transmit Length Register (UARTx_TL7816)	1279
49.4	Function	al description	1279
	49.4.1	Transmitter	1279
	49.4.2	Receiver	1285
	49.4.3	Baud rate generation.	1299
	49.4.4	Data format (non ISO-7816)	1301
	49.4.5	Single-wire operation.	1304
	49.4.6	Loop operation	1305
	49.4.7	ISO-7816 / smartcard support	1305
	49.4.8	Infrared interface	1310
49.5	Reset		1311
49.6	System 1	evel interrupt sources	1311
	49.6.1	RXEDGIF description	1312
49.7	DMA op	eration	1313
49.8	Applicat	Application information	
	49.8.1	Transmit/receive data buffer operation	1313
	49.8.2	ISO-7816 initialization sequence	1314
	49.8.3	Initialization sequence (non ISO-7816)	1316
	49.8.4	Overrun (OR) flag implications	1317
	49.8.5	Overrun NACK considerations	1318
	49.8.6	Match address registers	1319
	49.8.7	Modem feature	1319
	49.8.8	IrDA minimum pulse width	1320
	49.8.9	Clearing 7816 wait timer (WT, BWT, CWT) interrupts	1320
	49.8.10	Legacy and reverse compatibility considerations	1321



## Chapter 50 Secured digital host controller (SDHC)

50.1	Introduct	tion	1323
50.2	Overviev	W	1323
	50.2.1	Supported types of cards	1323
	50.2.2	SDHC block diagram	1324
	50.2.3	Features	1325
	50.2.4	Modes and operations	1326
50.3	SDHC si	ignal descriptions	1327
50.4	Memory	map and register definition.	1328
	50.4.1	DMA System Address Register (SDHC_DSADDR)	1329
	50.4.2	Block Attributes Register (SDHC_BLKATTR)	1330
	50.4.3	Command Argument Register (SDHC_CMDARG)	1331
	50.4.4	Transfer Type Register (SDHC_XFERTYP)	1332
	50.4.5	Command Response 0 (SDHC_CMDRSP0)	1336
	50.4.6	Command Response 1 (SDHC_CMDRSP1)	1337
	50.4.7	Command Response 2 (SDHC_CMDRSP2)	1337
	50.4.8	Command Response 3 (SDHC_CMDRSP3)	1337
	50.4.9	Buffer Data Port Register (SDHC_DATPORT)	1339
	50.4.10	Present State Register (SDHC_PRSSTAT)	1339
	50.4.11	Protocol Control Register (SDHC_PROCTL)	1344
	50.4.12	System Control Register (SDHC_SYSCTL)	1348
	50.4.13	Interrupt Status Register (SDHC_IRQSTAT)	1351
	50.4.14	Interrupt Status Enable Register (SDHC_IRQSTATEN)	1357
	50.4.15	Interrupt Signal Enable Register (SDHC_IRQSIGEN)	1360
	50.4.16	Auto CMD12 Error Status Register (SDHC_AC12ERR)	1362
	50.4.17	Host Controller Capabilities (SDHC_HTCAPBLT)	1365
	50.4.18	Watermark Level Register (SDHC_WML)	1367
	50.4.19	Force Event Register (SDHC_FEVT)	1367



Sec	tion Nu	mber Title	Page
	50.4.20	ADMA Error Status Register (SDHC_ADMAES)	1370
	50.4.21	ADMA System Address Register (SDHC_ADSADDR)	1372
	50.4.22	Vendor Specific Register (SDHC_VENDOR)	1372
	50.4.23	MMC Boot Register (SDHC_MMCBOOT)	1374
	50.4.24	Host Controller Version (SDHC_HOSTVER)	1375
50.5	Function	al description	1376
	50.5.1	Data buffer	1376
	50.5.2	DMA crossbar switch interface	1382
	50.5.3	SD protocol unit	1388
	50.5.4	Clock & reset manager	1390
	50.5.5	Clock generator.	1391
	50.5.6	SDIO card interrupt.	1391
	50.5.7	Card insertion and removal detection.	1393
	50.5.8	Power management and wakeup events.	1394
	50.5.9	MMC fast boot	1395
50.6	Initializa	tion/application of SDHC	1397
	50.6.1	Command send and response receive basic operation	1397
	50.6.2	Card identification mode	1398
	50.6.3	Card access.	1403
	50.6.4	Switch function.	1414
	50.6.5	ADMA operation	1416
	50.6.6	Fast boot operation.	1417
	50.6.7	Commands for MMC/SD/SDIO/CE-ATA	1421
50.7	Software	e restrictions	1427
	50.7.1	Initialization active	1427
	50.7.2	Software polling procedure	1428
	50.7.3	Suspend operation.	1428
	50.7.4	Data length setting	1428
	50.7.5	(A)DMA address setting	1428



Sec	tion Nu	mber Title	Page
	50.7.6	Data port access	1429
	50.7.7	Change clock frequency	1429
	50.7.8	Multi-block read	1429
		Chapter 51 Integrated interchip sound (I2S)	
51.1	Introduc	tion	1431
	51.1.1	Block diagram	1431
	51.1.2	Features	1432
	51.1.3	Modes of operation	1433
51.2	I2S signa	al descriptions	1435
51.3	Memory	map/register definition.	1439
	51.3.1	I <sup>2</sup> S Transmit Data Registers 0 (I2Sx_TX0)	1441
	51.3.2	I <sup>2</sup> S Transmit Data Registers 1 (I2Sx_TX1)	1441
	51.3.3	I <sup>2</sup> S Receive Data Registers 0 (I2Sx_RX0)	1442
	51.3.4	I <sup>2</sup> S Receive Data Registers 1 (I2Sx_RX1)	1442
	51.3.5	I <sup>2</sup> S Control Register (I2Sx_CR)	1443
	51.3.6	I <sup>2</sup> S Interrupt Status Register (I2Sx_ISR)	1446
	51.3.7	I <sup>2</sup> S Interrupt Enable Register (I2S <i>x</i> _IER)	1451
	51.3.8	I <sup>2</sup> S Transmit Configuration Register (I2S <i>x</i> _TCR)	1455
	51.3.9	I <sup>2</sup> S Receive Configuration Register (I2S <i>x</i> _RCR)	1457
	51.3.10	I <sup>2</sup> S Transmit Clock Control Registers (I2Sx_TCCR)	1459
	51.3.11	I <sup>2</sup> S Receive Clock Control Registers (I2Sx_RCCR)	1461
	51.3.12	I <sup>2</sup> S FIFO Control/Status Register (I2Sx_FCSR)	1462
	51.3.13	I <sup>2</sup> S AC97 Control Register (I2Sx_ACNT)	1468
	51.3.14	I <sup>2</sup> S AC97 Command Address Register (I2Sx_ACADD)	1469
	51.3.15	I <sup>2</sup> S AC97 Command Data Register (I2Sx_ACDAT)	1470
	51.3.16	I <sup>2</sup> S AC97 Tag Register (I2Sx_ATAG)	1470
	51.3.17	I <sup>2</sup> S Transmit Time Slot Mask Register (I2Sx_TMSK)	1471
	51.3.18	I <sup>2</sup> S Receive Time Slot Mask Register (I2S <i>x</i> _RMSK)	1471



Sec	tion Nu	mber Title	Page
	51.3.19	I <sup>2</sup> S AC97 Channel Status Register (I2Sx_ACCST)	1472
	51.3.20	I <sup>2</sup> S AC97 Channel Enable Register (I2Sx_ACCEN)	1472
	51.3.21	I <sup>2</sup> S AC97 Channel Disable Register (I2Sx_ACCDIS)	1473
51.4	Function	nal description	1473
	51.4.1	Detailed operating mode descriptions	1473
	51.4.2	I2S clocking	1489
	51.4.3	External frame and clock operation	1494
	51.4.4	Receive interrupt enable bit description	1496
	51.4.5	Transmit interrupt enable bit description	1497
	51.4.6	Internal frame and clock shutdown	1498
	51.4.7	Reset	1499
51.5	Initializa	ation/application information	1499
		Chapter 52 General purpose input/output (GPIO)	
52.1	Introduc	tion	1503
	52.1.1	Features	1503
	52.1.2	Modes of operation	1503
	52.1.3	GPIO signal descriptions	1504
52.2	Memory map and register definition.		1505
	52.2.1	Port Data Output Register (GPIOx_PDOR)	1508
	52.2.2	Port Set Output Register (GPIOx_PSOR)	1508
	52.2.3	Port Clear Output Register (GPIOx_PCOR)	1509
	52.2.4	Port Toggle Output Register (GPIOx_PTOR)	1509
	52.2.5	Port Data Input Register (GPIOx_PDIR)	1510
	52.2.6	Port Data Direction Register (GPIOx_PDDR)	1510
52.3	Function	nal description	1511
	52.3.1	General purpose input	1511
	52.3.2	General purpose output.	1511



# Chapter 53 Touch sense input (TSI)

53.1	Introduc	tion	1513
53.2	Features	S	1513
53.3	Overvie	w	1514
	53.3.1	Electrode capacitance measurement unit	1514
	53.3.2	Electrode scan unit	1515
	53.3.3	Touch detection unit	1516
53.4	Modes o	of operation	1516
	53.4.1	TSI disabled mode	1516
	53.4.2	TSI active mode	1516
	53.4.3	TSI low power mode	1517
	53.4.4	Block diagram	1517
53.5	TSI sign	nal descriptions	1518
	53.5.1	TSI_IN[15:0]	1518
53.6	Memory	map and register definition	1518
	53.6.1	General Control and Status Register (TSIx_GENCS)	1520
	53.6.2	SCAN control register (TSIx_SCANC)	1523
	53.6.3	Pin enable register (TSIx_PEN)	1526
	53.6.4	Status Register (TSIx_STATUS)	1529
	53.6.5	Counter Register (TSLx_CNTRn)	1532
	53.6.6	Channel n threshold register (TSLx_THRESHLDn)	1533
53.7	Function	nal descriptions	1533
	53.7.1	Capacitance measurement	1533
	53.7.2	TSI measurement result	1536
	53.7.3	Electrode scan unit	1537
	53.7.4	Touch detection unit	1540
53.8	Applicat	tion information	1541
	53.8.1	TSI module sensitivity	1541



## Chapter 54 JTAG Controller (JTAGC)

54.1	Introduc	tion	1543
	54.1.1	Block diagram	1543
	54.1.2	Features	1544
	54.1.3	Modes of operation	1544
54.2	External	signal description	1546
	54.2.1	TCK—Test clock input	1546
	54.2.2	TDI—Test data input.	1546
	54.2.3	TDO—Test data output	1546
	54.2.4	TMS—Test mode select.	1546
54.3	Register	description	1547
	54.3.1	Instruction register	1547
	54.3.2	Bypass register	1547
	54.3.3	Device identification register.	1547
	54.3.4	Boundary scan register.	1548
54.4	Function	al description	1549
	54.4.1	JTAGC reset configuration.	1549
	54.4.2	IEEE 1149.1-2001 (JTAG) Test Access Port	1549
	54.4.3	TAP controller state machine.	1549
	54.4.4	JTAGC block instructions.	1551
	54.4.5	Boundary scan	1554
54.5	Initializa	tion/Application information	1554





# **Chapter 1 About This Document**

#### 1.1 Overview

## 1.1.1 Purpose

This document describes the features, architecture, and programming model of the Freescale K50 microcontroller.

### 1.1.2 Audience

This document is primarily for system architects and software application developers who are using or considering using the K50 microcontroller in a system.

## 1.2 Conventions

## 1.2.1 Numbering systems

The following suffixes identify different numbering systems:

This suffix	Identifies a
b	Binary number. For example, the binary equivalent of the number 5 is written 101b. In some cases, binary numbers are shown with the prefix <i>0b</i> .
d	Decimal number. Decimal numbers are followed by this suffix only when the possibility of confusion exists. In general, decimal numbers are shown without a suffix.
h	Hexadecimal number. For example, the hexadecimal equivalent of the number 60 is written 3Ch. In some cases, hexadecimal numbers are shown with the prefix 0x.



## 1.2.2 Typographic notation

The following typographic notation is used throughout this document:

Example	Description
placeholder, x	Items in italics are placeholders for information that you provide. Italicized text is also used for the titles of publications and for emphasis. Plain lowercase letters are also used as placeholders for single letters and numbers.
code	Fixed-width type indicates text that must be typed exactly as shown. It is used for instruction mnemonics, directives, symbols, subcommands, parameters, and operators. Fixed-width type is also used for example code. Instruction mnemonics and directives in text and tables are shown in all caps; for example, BSR.
SR[SCM]	A mnemonic in brackets represents a named field in a register. This example refers to the Scaling Mode (SCM) field in the Status Register (SR).
REVNO[6:4], XAD[7:0]	Numbers in brackets and separated by a colon represent either:  • A subset of a register's named field
	For example, REVNO[6:4] refers to bits 6–4 that are part of the COREREV field that occupies bits 6–0 of the REVNO register.
	A continuous range of individual signals of a bus
	For example, XAD[7:0] refers to signals 7–0 of the XAD bus.

## 1.2.3 Special terms

The following terms have special meanings:

Term	Meaning
asserted	Refers to the state of a signal as follows:  • An active-high signal is asserted when high (1).  • An active-low signal is asserted when low (0).
deasserted	Refers to the state of a signal as follows:  • An active-high signal is deasserted when low (0).  • An active-low signal is deasserted when high (1).  In some cases, deasserted signals are described as negated.
reserved	Refers to a memory space, register, or field that is either reserved for future use or for which, when written to, the module or chip behavior is unpredictable.



# Chapter 2 Introduction

#### 2.1 Overview

This chapter provides an overview of the Kinetis portfolio and K50 family of products. It also presents high-level descriptions of the modules available on the devices covered by this document.

## 2.2 K50 Family Introduction

The K50 MCU family includes a flexible, low-power segment LCD controller with support for up to 320 segments, analog front end capability, and full-speed USB 2.0 On-The-Go with device charger detect capability. Devices start from 128 KB of flash in 64LQFP packages extending up to 512 KB in a 144MAPBGA package with a rich suite of analog, communication, timing and control peripherals. High-memory density K50 family devices include IEEE1588 Ethernet.

## 2.3 Module Functional Categories

The modules on this device are grouped into functional categories. The following sections describe the modules assigned to each category in more detail.

Table 2-1. Module functional categories

Module category	Description
ARM Cortex-M4 core	<ul> <li>32-bit MCU core from ARM's Cortex-M class adding DSP instructions, 1.25 DMIPS/MHz, based on ARMv7 architecture</li> </ul>



#### **woule Functional Categories**

## Table 2-1. Module functional categories (continued)

Module category	Description
System	System integration module Power management and mode controllers  Multiple power modes available based on run, wait, stop, and power-down modes  Low-leakage wakeup unit Miscellaneous control module Crossbar switch Memory protection unit Peripheral bridge Direct memory access (DMA) controller with multiplexer to increase available DMA requests External watchdog monitor Watchdog
Memories	Internal memories include: Program flash memory Programming acceleration RAM SRAM External memory or peripheral bus interface: FlexBus Serial programming interface: EzPort
Clocks	<ul> <li>Multiple clock generation options available from internally- and externally-generated clocks</li> <li>System oscillator to provide clock source for the MCU</li> <li>RTC oscillator to provide clock source for the RTC</li> </ul>
Security	Cyclic Redundancy Check module for error detection
Analog	High speed analog-to-digital converter with integrated programmable gain amplifier Comparator Digital-to-analog converter Op-amp Transimpedance amplifier Internal voltage reference
Timers	Programmable delay block FlexTimers Periodic interrupt timer Low power timer Carrier modulator transmitter Independent real time clock
Communications	USB OTG controller with built-in FS/LS transceiver USB device charger detect USB voltage regulator Serial peripheral interface Inter-integrated circuit (I <sup>2</sup> C) UART Secured Digital host controller Integrated interchip sound (I <sup>2</sup> S)
Human-Machine Interfaces (HMI)	General purpose input/output controller     Capacitive touch sense input interface enabled in hardware



#### 2.3.1 ARM Cortex-M4 Core Modules

The following core modules are available on this device.

Table 2-2. Core modules

Module	Description
ARM Cortex-M4	The ARM Cortex-M4 is the newest member of the Cortex M Series of processors targeting microcontroller cores focused on very cost sensitive, deterministic, interrupt driven environments. The Cortex M4 processor is based on the ARMv7 Architecture and Thumb®-2 ISA and is upward compatible with the Cortex M3, Cortex M1, and Cortex M0 architectures. Cortex M4 improvements include an ARMv7 Thumb-2 DSP (ported from the ARMv7-A/R profile architectures) providing 32-bit instructions with SIMD (single instruction multiple data) DSP style multiply-accumulates and saturating arithmetic.
NVIC	The ARMv7-M exception model and nested-vectored interrupt controller (NVIC) implement a relocatable vector table supporting many external interrupts, a single non-maskable interrupt (NMI), and priority levels.
	The NVIC replaces shadow registers with equivalent system and simplified programmability. The NVIC contains the address of the function to execute for a particular handler. The address is fetched via the instruction port allowing parallel register stacking and look-up. The first sixteen entries are allocated to ARM internal sources with the others mapping to MCU-defined interrupts.
AWIC	The primary function of the Asynchronous Wake-up Interrupt Controller (AWIC) is to detect asynchronous wake-up events in stop modes and signal to clock control logic to resume system clocking. After clock restart, the NVIC observes the pending interrupt and performs the normal interrupt or event processing.
Debug interfaces	Most of this device's debug is based on the ARM CoreSight <sup>™</sup> architecture. Four debug interfaces are supported:
	<ul> <li>IEEE 1149.1 JTAG</li> <li>IEEE 1149.7 JTAG (cJTAG)</li> <li>Serial Wire Debug (SWD)</li> <li>ARM Real-Time Trace Interface</li> </ul>

## 2.3.2 System Modules

The following system modules are available on this device.

Table 2-3. System modules

Module	Description
System integration module (SIM)	The SIM includes integration logic and several module configuration settings.
Mode controller	The MC provides control and protection on entry and exit to each power mode, control for the Power management controller (PMC), and reset entry and exit for the complete MCU.
Power management controller (PMC)	The PMC provides the user with multiple power options. Ten different modes are supported that allow the user to optimize power consumption for the level of functionality needed. Includes power-on-reset (POR) and integrated low voltage detect (LVD) with reset (brownout) capability and selectable LVD trip points.



#### woulde Functional Categories

Table 2-3. System modules (continued)

Module	Description
Low-leakage wakeup unit (LLWU)	The LLWU module allows the device to wake from low leakage power modes (LLS and VLLS) through various internal peripheral and external pin sources.
Miscellaneous control module (MCM)	The MCM includes integration logic and embedded trace buffer details.
Crossbar switch (XBS)	The XBS connects bus masters and bus slaves, allowing all bus masters to access different bus slaves simultaneously and providing arbitration among the bus masters when they access the same slave.
Memory protection unit (MPU)	The MPU provides memory protection and task isolation. It concurrently monitors all bus master transactions for the slave connections.
Peripheral bridges	The peripheral bridge converts the crossbar switch interface to an interface to access a majority of peripherals on the device.
DMA multiplexer (DMAMUX)	The DMA multiplexer selects from many DMA requests down to 16 for the DMA controller.
Direct memory access (DMA) controller	The DMA controller provides programmable channels with transfer control descriptors for data movement via dual-address transfers for 8-, 16-, 32- and 128-bit data values.
External watchdog monitor (EWM)	The EWM is a redundant mechanism to the software watchdog module that monitors both internal and external system operation for fail conditions.
Software watchdog (WDOG)	The WDOG monitors internal system operation and forces a reset in case of failure. It can run from an independent 1 KHz low power oscillator with a programmable refresh window to detect deviations in program flow or system frequency.

## 2.3.3 Memories and Memory Interfaces

The following memories and memory interfaces are available on this device.

Table 2-4. Memories and memory interfaces

Module	Description
Flash memory	Program flash memory — non-volatile flash memory that can execute program code FlexMemory — encompasses the following memory types: Programming acceleration RAM — RAM memory that accelerates flash programming
Flash memory controller	Manages the interface between the device and the on-chip flash memory.
SRAM	Internal system RAM. Partial SRAM kept powered in VLLS2 low leakage mode.
SRAM controller	Manages simultaneous accesses to system RAM by multiple master peripherals and core.
System register file	32-byte register file that is accessible during all power modes and is powered by VDD.
VBAT register file	32-byte register file that is accessible during all power modes and is powered by VBAT.



#### Table 2-4. Memories and memory interfaces (continued)

Module	Description
Serial programming interface (EzPort)	Same serial interface as, and subset of, the command set used by industry-standard SPI flash memories. Provides the ability to read, erase, and program flash memory and reset command to boot the system after flash programming.
FlexBus	External bus interface with multiple independent, user-programmable chip-select signals that can interface with external SRAM, PROM, EPROM, EEPROM, flash, and other peripherals via 8-, 16- and 32-bit port sizes. Configurations include multiplexed or non-multiplexed address and data buses using 8-bit, 16-bit, 32-bit, and 16-byte line-sized transfers.

#### **2.3.4 Clocks**

The following clock modules are available on this device.

Table 2-5. Clock modules

Module	Description		
Multi-clock generator (MCG)	The MCG provides several clock sources for the MCU that include:		
	<ul> <li>Phase-locked loop (PLL) — Voltage-controlled oscillator (VCO)</li> <li>Frequency-locked loop (FLL) — Digitally-controlled oscillator (DCO)</li> <li>Internal reference clocks — Can be used as a clock source for other on-chip peripherals</li> </ul>		
System oscillator	The system oscillator, in conjunction with an external crystal or resonator, generates a reference clock for the MCU.		
Real-time clock oscillator	The RTC oscillator has an independent power supply and supports a 32 kHz crystal oscillator to feed the RTC clock. Optionally, the RTC oscillator can replace the system oscillator as the main oscillator source.		

## 2.3.5 Security and Integrity modules

The following security and integrity modules are available on this device:

Table 2-6. Security and integrity modules

Module	Description
Cyclic Redundancy Check (CRC)	Hardware CRC generator circuit using 16/32-bit shift register. Error detection for all single, double, odd, and most multi-bit errors, programmable initial seed value, and optional feature to transpose input data and CRC result via transpose register.

## 2.3.6 Analog modules

The following analog modules are available on this device:

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### woule Functional Categories

Table 2-7. Analog modules

Module	Description
16-bit analog-to-digital converters (ADC) and programmable-gain amplifiers (PGA)	16-bit successive-approximation ADC designed with integrated programmable gain amplifiers (PGA)
Analog comparators	Compares two analog input voltages across the full range of the supply voltage.
6-bit digital-to-analog converters (DAC)	64-tap resistor ladder network which provides a selectable voltage reference for applications where voltage reference is needed.
12-bit digital-to-analog converters (DAC)	Low-power general-purpose DAC, whose output can be placed on an external pin or set as one of the inputs to the analog comparator, op-amps, or ADC.
Voltage reference (VREF)	Supplies an accurate voltage output that is trimmable in 0.5 mV steps. The VREF can be used in medical applications, such as glucose meters, to provide a reference voltage to biosensors or as a reference to analog peripherals, such as the ADC, DAC, or CMP.
Operational amplifier (Op-amp)	The op-amp is a low-input offset voltage, low-input offset, and bias current amplifier that is designed for low-voltage, low-power operation over an input voltage range of 0 to supply. The amplifier supports inverting, non-inverting, buffer, and general-purpose modes.
Trans-impedance amplifier (TRIAMP)	The trans-impedance amplifier conditions the current input into voltages that can be read by the ADC or analog comparator.

## 2.3.7 Timer modules

The following timer modules are available on this device:

Table 2-8. Timer modules

Module	Description			
Programmable delay block (PDB)	<ul> <li>16-bit resolution</li> <li>3-bit prescaler</li> <li>Positive transition of trigger event signal initiates the counter</li> <li>Supports two triggered delay output signals, each with an independently-controlled delay from the trigger event</li> <li>Outputs can be OR'd together to schedule two conversions from one input trigger event and can schedule precise edge placement for a pulsed output. This feature is used to generate the control signal for the CMP windowing feature and output to a package pin if needed for applications, such as critical conductive mode power factor correction.</li> <li>Continuous-pulse output or single-shot mode supported, each output is independently enabled, with possible trigger events</li> <li>Supports bypass mode</li> <li>Supports DMA</li> </ul>			



Table 2-8. Timer modules (continued)

Module	Description				
Flexible timer modules (FTM)	<ul> <li>Selectable FTM source clock, programmable prescaler</li> <li>16-bit counter supporting free-running or initial/final value, and counting is up or up-down</li> <li>Input capture, output compare, and edge-aligned and center-aligned PWM modes</li> <li>Operation of FTM channels as pairs with equal outputs, pairs with complimentary outputs, or independent channels with independent outputs</li> <li>Deadtime insertion is available for each complementary pair</li> <li>Generation of hardware triggers</li> <li>Software control of PWM outputs</li> <li>Up to 4 fault inputs for global fault control</li> <li>Configurable channel polarity</li> <li>Programmable interrupt on input capture, reference compare, overflowed counter, or detected fault condition</li> <li>Quadrature decoder with input filters, relative position counting, and interrupt on position count or capture of position count on external event</li> <li>DMA support for FTM events</li> </ul>				
Periodic interrupt timers (PIT)	<ul> <li>Four general purpose interrupt timers</li> <li>Interrupt timers for triggering ADC conversions</li> <li>32-bit counter resolution</li> <li>Clocked by system clock frequency</li> <li>DMA support</li> </ul>				
Low-power timer (LPTimer)	<ul> <li>Selectable clock for prescaler/glitch filter of 1 kHz (internal LPO), 32.768 kHz (external crystal), or internal reference clock</li> <li>Configurable Glitch Filter or Prescaler with 16-bit counter</li> <li>16-bit time or pulse counter with compare</li> <li>Interrupt generated on Timer Compare</li> <li>Hardware trigger generated on Timer Compare</li> </ul>				
Carrier modulator timer (CMT)	Four CMT modes of operation:  Time with independent control of high and low times Baseband Frequency shift key (FSK) Direct software control of CMT_IRO pin Extended space operation in time, baseband, and FSK modes Selectable input clock divider Interrupt on end of cycle with the ability to disable CMT_IRO pin and use as timer interrupt  DMA support				
Real-time clock (RTC)	<ul> <li>Independent power supply, POR, and 32 kHz Crystal Oscillator</li> <li>32-bit seconds counter with 32-bit Alarm</li> <li>16-bit Prescaler with compensation that can correct errors between 0.12 ppm and 3906 ppm</li> </ul>				

## 2.3.8 Communication interfaces

The following communication interfaces are available on this device:



#### **Orderable part numbers**

Table 2-9. Communication modules

Module	Description	
USB OTG (low-/full-speed)	USB 2.0 compliant module with support for host, device, and On-The-Go modes. Includes an on-chip transceiver for full and low speeds.	
USB Device Charger Detect (USBDCD)	The USBDCD monitors the USB data lines to detect a smart charger meeting the USB Battery Charging Specification Rev1.1. This information allows the MCU to better manage the battery charging IC in a portable device.	
USB voltage regulator	Up to 5 V regulator input typically provided by USB VBUS power with 3.3 V regulated output that powers on-chip USB subsystem, capable of sourcing 120 mA to external board components.	
Serial peripheral interface (SPI)	Synchronous serial bus for communication to an external device	
Inter-integrated circuit (I2C)	Allows communication between a number of devices. Also supports the System Management Bus (SMBus) Specification, version 2.	
Universal asynchronous receiver/ transmitters (UART)	Asynchronous serial bus communication interface with programmable 8- or 9-bit data format and support of ISO 7816 smart card interface	
Secure Digital host controller (SDHC)	Interface between the host system and the SD, SDIO, MMC, or CE-ATA cards. The SDHC acts as a bridge, passing host bus transactions to the cards by sending commands and performing data accesses to/from the cards. It handles the SD, SDIO, MMC, and CE-ATA protocols at the transmission level.	
128	The I <sup>2</sup> S is a full-duplex, serial port that allows the chip to communicate with a variety of serial devices, such as standard codecs, digital signal processors (DSPs), microprocessors, peripherals, and audio codecs that implement the inter-IC sound bus (I <sup>2</sup> S) and the Intel <sup>®</sup> AC97 standards	

### 2.3.9 Human-machine interfaces

The following human-machine interfaces (HMI) are available on this device:

Table 2-10. HMI modules

Module	Description	
General purpose input/output (GPIO)	All general purpose input or output (GPIO) pins are capable of interrupt and DMA request generation. All GPIO pins have 5 V tolerance.	
Capacitive touch sense input (TSI)	Contains up to 16 channel inputs for capacitive touch sensing applications.  Operation is available in low-power modes via interrupts.	

## 2.4 Orderable part numbers

The following table summarizes the part numbers of the devices covered by this document.



## Table 2-11. Orderable part numbers summary

Freescale part number	CPU frequenc y	Pin count	Package	Total flash memory	Program flash	EEPROM	SRAM	GPIO
MK50DN512ZCLQ10	100 MHz	144	LQFP	512 KB	512 KB	_	128 KB	96
MK50DN512ZCMD10	100 MHz	144	MAPBGA	512 KB	512 KB	_	128 KB	96



Oruerable part numbers



# **Chapter 3 Chip Configuration**

#### 3.1 Introduction

This chapter provides details on the individual modules of the microcontroller. It includes:

- module block diagrams showing immediate connections within the device,
- specific module-to-module interactions not necessarily discussed in the individual module chapters, and
- links for more information.

#### 3.2 Core modules

## 3.2.1 ARM Cortex-M4 Core Configuration

This section summarizes how the module has been configured in the chip. Full documentation for this module is provided by ARM and can be found at http://www.arm.com.



#### Core modules




Figure 3-1. Core configuration

Table 3-1. Reference links to related information

Topic	Related module	Reference
Full description	ARM Cortex-M4 core, r0p0	http://www.arm.com
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
System/instruction/data bus module	Crossbar switch	Crossbar switch
System/instruction/data bus module	SRAM	SRAM
Debug	IEEE 1149.1 JTAG	Debug
	IEEE 1149.7 JTAG (cJTAG)	
	Serial Wire Debug (SWD)	
	ARM Real-Time Trace Interface	
Interrupts	Nested Vectored Interrupt Controller (NVIC)	NVIC
Private Peripheral Bus (PPB) module	Miscellaneous Control Module (MCM)	MCM

## 3.2.1.1 Buses, interconnects, and interfaces

The ARM Cortex-M4 core has four buses as described in the following table.



Bus name	Description	
Instruction code (ICODE) bus	The ICODE and DCODE buses are muxed. This muxed bus is called the CODE bus and is	
Data code (DCODE) bus	connected to the crossbar switch via a single master port. In addition, the CODE bus is also tightly coupled to the lower half of the system RAM (SRAM_L).	
System bus	The system bus is connected to a separate master port on the crossbar. In addition, the system bus is tightly coupled to the upper half system RAM (SRAM_U).	
Private peripheral (PPB) bus	Peral (PPB) bus  The PPB provides access to these modules:  ARM modules such as the NVIC, ETM, ITM, DWT, FBP, and ROM table  Freescale Miscellaneous Control Module (MCM)	

### 3.2.1.2 System Tick Timer

The System Tick Timer's clock source is always the core clock, FCLK. This results in the following:

- The CLKSOURCE bit in SysTick Control and Status register is always set to select the core clock.
- Because the timing reference (FCLK) is a variable frequency, the TENMS bit in the SysTick Calibration Value Register is always zero.
- The NOREF bit in SysTick Calibration Value Register is always set, implying that FCLK is the only available source of reference timing.

## 3.2.1.3 Debug facilities

This device has extensive debug capabilities including run control and tracing capabilities. The standard ARM debug port that supports JTAG and SWD interfaces. Also the cJTAG interface is supported on this device.

### 3.2.1.4 Core privilege levels

The ARM documentation uses different terms than this document to distinguish between privilege levels.

If you see this term	it also means this term	
Privileged	Supervisor	
Unprivileged or user	User	



## 3.2.2 Nested Vectored Interrupt Controller (NVIC) Configuration

This section summarizes how the module has been configured in the chip. Full documentation for this module is provided by ARM and can be found at http://www.arm.com.




Figure 3-2. NVIC configuration

Table 3-2. Reference links to related information

Topic	Related module	Reference
Full description	Nested Vectored Interrupt Controller (NVIC)	http://www.arm.com
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Private Peripheral Bus (PPB)	ARM Cortex-M4 core	ARM Cortex-M4 core

## 3.2.2.1 Interrupt priority levels

This device supports 16 priority levels for interrupts. Therefore, in the NVIC each source in the IPR registers contains 4 bits. For example, IPR0 is shown below:



#### 3.2.2.2 Non-maskable interrupt

The non-maskable interrupt request to the NVIC is controlled by the external  $\overline{\text{NMI}}$  signal. The pin the  $\overline{\text{NMI}}$  signal is multiplexed on, must be configured for the  $\overline{\text{NMI}}$  function to generate the non-maskable interrupt request.



## 3.2.2.3 Interrupt channel assignments

The interrupt source assignments are defined in the following table.

- Vector number the value stored on the stack when an interrupt is serviced.
- IRQ number non-core interrupt source count, which is the vector number minus 16.

The IRQ number is used within ARM's NVIC documentation.

Table 3-4. Interrupt vector assignments

Address	Vector	IRQ <sup>1</sup>	NVIC non-IPR register number	NVIC IPR register number	Source module	Source description
ARM Core System	m Handler V	ectors				
0x0000_0000	0	_	_	_	ARM core	Initial Stack Pointer
0x0000_0004	1	_	_	_	ARM core	Initial Program Counter
0x0000_0008	2	_	_	_	ARM core	Non-maskable Interrupt (NMI)
0x0000_000C	3	_	_	_	ARM core	Hard Fault
0x0000_0010	4	_	_	_	ARM core	MemManage Fault
0x0000_0014	5	_	_	_	ARM core	Bus Fault
0x0000_0018	6	_	_	_	ARM core	Usage Fault
0x0000_001C	7	_	_	_	_	_
0x0000_0020	8	_	_	_	_	_
0x0000_0024	9	_	_	_	_	_
0x0000_0028	10	_	_	_	_	_
0x0000_002C	11	_	_	_	ARM core	Supervisor call (SVCall)
0x0000_0030	12	_	_	_	ARM core	Debug Monitor
0x0000_0034	13	_	_	_	_	_
0x0000_0038	14	_	_	_	ARM core	Pendable request for system service (PendableSrvReq)
0x0000_003C	15	_	_	_	ARM core	System tick timer (SysTick)
Non-Core Vector	s					
0x0000_0040	16	0	0	0	DMA	DMA channel 0 transfer complete
0x0000_0044	17	1	0	0	DMA	DMA channel 1 transfer complete
0x0000_0048	18	2	0	0	DMA	DMA channel 2 transfer complete
0x0000_004C	19	3	0	0	DMA	DMA channel 3 transfer complete
0x0000_0050	20	4	0	1	DMA	DMA channel 4 transfer complete



#### Core modules

Table 3-4. Interrupt vector assignments (continued)

0x0000_0054         21         5         0         1         DMA         DMA channel 5 transfer complete           0x0000_0058         22         6         0         1         DMA         DMA channel 6 transfer complete           0x0000_005C         23         7         0         1         DMA         DMA channel 7 transfer complete           0x0000_0060         24         8         0         2         DMA         DMA channel 8 transfer complete           0x0000_0064         25         9         0         2         DMA         DMA channel 9 transfer complete           0x0000_0066         27         11         0         2         DMA         DMA channel 10 transfer complete           0x0000_0066         27         11         0         2         DMA         DMA channel 11 transfer complete           0x0000_0070         28         12         0         3         DMA         DMA channel 12 transfer complete           0x0000_0070         28         12         0         3         DMA         DMA channel 13 transfer complete           0x0000_0070         30         13         0         3         DMA         DMA channel 14 transfer complete           0x0000_0070         31         15	
0x0000_005C         23         7         0         1         DMA         DMA channel 7 transfer complet           0x0000_0060         24         8         0         2         DMA         DMA channel 8 transfer complet           0x0000_0064         25         9         0         2         DMA         DMA channel 9 transfer complet           0x0000_0068         26         10         0         2         DMA         DMA channel 10 transfer complet           0x0000_006C         27         11         0         2         DMA         DMA channel 11 transfer complet           0x0000_0070         28         12         0         3         DMA         DMA channel 12 transfer complet           0x0000_0074         29         13         0         3         DMA         DMA channel 13 transfer complet           0x0000_0078         30         14         0         3         DMA         DMA channel 14 transfer complet           0x0000_0070         31         15         0         3         DMA         DMA channel 15 transfer complet           0x0000_0080         32         16         0         4         DMA         DMA channel 15 transfer complet           0x0000_0084         33         17	<del></del>
0x0000_0060         24         8         0         2         DMA         DMA channel 8 transfer complet           0x0000_0064         25         9         0         2         DMA         DMA channel 9 transfer complet           0x0000_0068         26         10         0         2         DMA         DMA channel 10 transfer complet           0x0000_006C         27         11         0         2         DMA         DMA channel 11 transfer complet           0x0000_0070         28         12         0         3         DMA         DMA channel 12 transfer complet           0x0000_0074         29         13         0         3         DMA         DMA channel 13 transfer complet           0x0000_0078         30         14         0         3         DMA         DMA channel 14 transfer complet           0x0000_0070         31         15         0         3         DMA         DMA channel 13 transfer complete           0x0000_0080         32         16         0         4         DMA         DMA channel 14 transfer complete           0x0000_0084         33         17         0         4         MCM         Normal interrupt           0x0000_0086         35         19         0	<del></del>
0x0000_0064         25         9         0         2         DMA         DMA channel 9 transfer complete.           0x0000_0068         26         10         0         2         DMA         DMA channel 10 transfer complete.           0x0000_006C         27         11         0         2         DMA         DMA channel 11 transfer complete.           0x0000_0070         28         12         0         3         DMA         DMA channel 12 transfer complete.           0x0000_0074         29         13         0         3         DMA         DMA channel 13 transfer complete.           0x0000_0078         30         14         0         3         DMA         DMA channel 14 transfer complete.           0x0000_007C         31         15         0         3         DMA         DMA channel 15 transfer complete.           0x0000_0080         32         16         0         4         DMA         DMA error interrupt channels 0-1.           0x0000_0084         33         17         0         4         MCM         Normal interrupt           0x0000_0096         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage of the controller controller to avoid a size where the system does exit stop mode on an	<del></del>
0x0000_0068         26         10         0         2         DMA         DMA channel 10 transfer completed by the c	<del></del>
0x0000_006C         27         11         0         2         DMA         DMA channel 11 transfer comple           0x0000_0070         28         12         0         3         DMA         DMA channel 12 transfer comple           0x0000_0074         29         13         0         3         DMA         DMA channel 13 transfer comple           0x0000_0078         30         14         0         3         DMA         DMA channel 14 transfer comple           0x0000_007C         31         15         0         3         DMA         DMA channel 15 transfer comple           0x0000_0080         32         16         0         4         DMA         DMA channel 15 transfer comple           0x0000_0084         33         17         0         4         DMA         DMA channel 15 transfer comple           0x0000_0084         33         17         0         4         DMA         DMA channel 15 transfer comple           0x0000_0086         34         18         0         4         MCM         Normal interrupt           0x0000_0086         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5	<del></del>
0x0000_0070         28         12         0         3         DMA         DMA channel 12 transfer completed by transfer completed by transfer completed by the interrupt of the system does exit stop mode on an LL recovery.           0x0000_0074         29         13         0         3         DMA         DMA channel 13 transfer completed by the interrupt of transfer complete by the interrupt of transfer complete by the interrupt of transfer completed by the interrupt of transfer complete by the interrupt by the interrupt of transfer complete by the interrupt by the interr	te
0x0000_0074         29         13         0         3         DMA         DMA channel 13 transfer complete           0x0000_0078         30         14         0         3         DMA         DMA channel 14 transfer complete           0x0000_007C         31         15         0         3         DMA         DMA channel 15 transfer complete           0x0000_0080         32         16         0         4         DMA         DMA error interrupt channels 0-1           0x0000_0084         33         17         0         4         MCM         Normal interrupt           0x0000_0088         34         18         0         4         Flash memory         Command complete           0x0000_008C         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage           0x0000_0094         37         21         0         5         LLWU         Low Leakage Wakeup           NOTE: The LLWU interrupt must be masked by the interrupt be masked by the interrupt of a voltage sexit stop mode on an LL recovery.         0         5         WDOG         Watchdog interrupt           0x0000_0096	te
0x0000_0078         30         14         0         3         DMA         DMA channel 14 transfer complete           0x0000_007C         31         15         0         3         DMA         DMA channel 15 transfer complete           0x0000_0080         32         16         0         4         DMA         DMA error interrupt channels 0-1           0x0000_0084         33         17         0         4         MCM         Normal interrupt           0x0000_0088         34         18         0         4         Flash memory         Command complete           0x0000_008C         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage of the controller	te
0x0000_007C         31         15         0         3         DMA         DMA channel 15 transfer complete           0x0000_0080         32         16         0         4         DMA         DMA error interrupt channels 0-1           0x0000_0084         33         17         0         4         MCM         Normal interrupt           0x0000_0088         34         18         0         4         Flash memory         Command complete           0x0000_008C         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage           0x0000_0094         37         21         0         5         LLWU         Low Leakage Wakeup           NOTE: The LLWU interrupt must be masked by the interrupt of the avoid a sce where the system does exit stop mode on an LL recovery.         0         5         WDOG         Watchdog interrupt           0x0000_0090         39         23         0         5         —         —           0x0000_000A0         40         24         0         6         I²C0         —           0x0000_000A4         41         25         0	te
0x0000_0080         32         16         0         4         DMA         DMA error interrupt channels 0-1           0x0000_0084         33         17         0         4         MCM         Normal interrupt           0x0000_0088         34         18         0         4         Flash memory         Command complete           0x0000_008C         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage of the controller of the controll	te
0x0000_0084         33         17         0         4         MCM         Normal interrupt           0x0000_0088         34         18         0         4         Flash memory         Command complete           0x0000_008C         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage of the controller of the control	te
0x0000_0088         34         18         0         4         Flash memory         Command complete           0x0000_008C         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage of	5
0x0000_008C         35         19         0         4         Flash memory         Read collision           0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage of the controller of the	
0x0000_0090         36         20         0         5         Mode Controller         Low-voltage detect, low-voltage of the controller of the controll	
0x0000_0094         37         21         0         5         LLWU         Low Leakage Wakeup NOTE: The LLWU interrupt must be masked by the interrupt controller to avoid a sce where the system does exit stop mode on an LL recovery.           0x0000_0098         38         22         0         5         WDOG         Watchdog interrupt           0x0000_009C         39         23         0         5         —         —           0x0000_00A0         40         24         0         6         I²C0         —           0x0000_00A4         41         25         0         6         I²C1         —	
NOTE:         The LLWU interrupt must be masked by the interrupt must be masked by the interrupt controller to avoid a sce where the system does exit stop mode on an LL recovery.           0x0000_0098         38         22         0         5         WDOG         Watchdog interrupt           0x0000_009C         39         23         0         5         —         —           0x0000_00A0         40         24         0         6         I²C0         —           0x0000_00A4         41         25         0         6         I²C1         —	warning
0x0000_009C         39         23         0         5         —         —           0x0000_00A0         40         24         0         6         I²C0         —           0x0000_00A4         41         25         0         6         I²C1         —	upt nario not fully
0x0000_00A0         40         24         0         6         I²C0         —           0x0000_00A4         41         25         0         6         I²C1         —	
0x0000_00A4	
_	
0x0000_00A8 42 26 0 6 SPI0 Single interrupt vector for all sou	
	rces
0x0000_00AC 43 27 0 6 SPI1 Single interrupt vector for all sou	rces
0x0000_00B0	rces
0x0000_00B4	
0x0000_00B8	
0x0000_00BC 47 31 0 7 — —	
0x0000_00C0 48 32 1 8 — —	



Table 3-4. Interrupt vector assignments (continued)

			The state of the s			
Address	Vector	IRQ <sup>1</sup>	NVIC non-IPR register number	NVIC IPR register number	Source module	Source description
0x0000_00C4	49	33	1	8	_	_
0x0000_00C8	50	34	1	8	_	_
0x0000_00CC	51	35	1	8	_	_
0x0000_00D0	52	36	1	9	_	_
0x0000_00D4	53	37	1	9	_	_
0x0000_00D8	54	38	1	9	_	_
0x0000_00DC	55	39	1	9	_	_
0x0000_00E0	56	40	1	10	_	_
0x0000_00E4	57	41	1	10	_	_
0x0000_00E8	58	42	1	10	_	_
0x0000_00EC	59	43	1	10	_	_
0x0000_00F0	60	44	1	11	_	_
0x0000_00F4	61	45	1	11	UART0	Single interrupt vector for UART status sources
0x0000_00F8	62	46	1	11	UART0	Single interrupt vector for UART error sources
0x0000_00FC	63	47	1	11	UART1	Single interrupt vector for UART status sources
0x0000_0100	64	48	1	12	UART1	Single interrupt vector for UART error sources
0x0000_0104	65	49	1	12	UART2	Single interrupt vector for UART status sources
0x0000_0108	66	50	1	12	UART2	Single interrupt vector for UART error sources
0x0000_010C	67	51	1	12	UART3	Single interrupt vector for UART status sources
0x0000_0110	68	52	1	13	UART3	Single interrupt vector for UART error sources
0x0000_0114	69	53	1	13	UART4	Single interrupt vector for UART status sources
0x0000_0118	70	54	1	13	UART4	Single interrupt vector for UART error sources
0x0000_011C	71	55	1	13	UART5	Single interrupt vector for UART status sources
0x0000_0120	72	56	1	14	UART5	Single interrupt vector for UART error sources
0x0000_0124	73	57	1	14	ADC0	_
					1	I .



#### **Core modules**

Table 3-4. Interrupt vector assignments (continued)

Address	Vector	IRQ <sup>1</sup>	NVIC non-IPR register number	NVIC IPR register number	Source module	Source description
0x0000_0128	74	58	1	14	ADC1	_
0x0000_012C	75	59	1	14	CMP0	_
0x0000_0130	76	60	1	15	CMP1	_
0x0000_0134	77	61	1	15	CMP2	_
0x0000_0138	78	62	1	15	FTM0	Single interrupt vector for all sources
0x0000_013C	79	63	1	15	FTM1	Single interrupt vector for all sources
0x0000_0140	80	64	2	16	FTM2	Single interrupt vector for all sources
0x0000_0144	81	65	2	16	CMT	_
0x0000_0148	82	66	2	16	RTC	Alarm interrupt
0x0000_014C	83	67	2	16	_	_
0x0000_0150	84	68	2	17	PIT	Channel 0
0x0000_0154	85	69	2	17	PIT	Channel 1
0x0000_0158	86	70	2	17	PIT	Channel 2
0x0000_015C	87	71	2	17	PIT	Channel 3
0x0000_0160	88	72	2	18	PDB	_
0x0000_0164	89	73	2	18	USB OTG	_
0x0000_0168	90	74	2	18	USB Charger Detect	_
0x0000_016C	91	75	2	18	_	_
0x0000_0170	92	76	2	19	_	_
0x0000_0174	93	77	2	19	_	_
0x0000_0178	94	78	2	19	_	_
0x0000_017C	95	79	2	19	I <sup>2</sup> S0	_
0x0000_0180	96	80	2	20	SDHC	_
0x0000_0184	97	81	2	20	DAC0	_
0x0000_0188	98	82	2	20	DAC1	_
0x0000_018C	99	83	2	20	TSI	Single interrupt vector for all sources
0x0000_0190	100	84	2	21	MCG	_
0x0000_0194	101	85	2	21	Low Power Timer	_
0x0000_0198	102	86	2	21	_	_
0x0000_019C	103	87	2	21	Port control module	Pin detect (Port A)



Table 3-4.	Interrupt ved	tor assignme	ents (continued)
------------	---------------	--------------	------------------

Address	Vector	IRQ <sup>1</sup>	NVIC non-IPR register number	NVIC IPR register number	Source module	Source description
0x0000_01A0	104	88	2	22	Port control module	Pin detect (Port B)
0x0000_01A4	105	89	2	22	Port control module	Pin detect (Port C)
0x0000_01A8	106	90	2	22	Port control module	Pin detect (Port D)
0x0000_01AC	107	91	2	22	Port control module	Pin detect (Port E)
0x0000_01B0	108	92	2	23	_	_
0x0000_01B4	109	93	2	23	_	_
0x0000_01B8	110	94	2	23	Software	Software interrupt <sup>4</sup>

<sup>1.</sup> Indicates the NVIC's interrupt source number.

# 3.2.2.3.1 Determining the bitfield and register location for configuring a particular interrupt

Suppose you need to configure the low-power timer (LPTMR) interrupt. The following table is an excerpt of the LPTMR row from Interrupt channel assignments.

Table 3-5. LPTMR interrupt vector assignment

Address	Vector	IRQ <sup>1</sup>	NVIC non-IPR register number 2	NVIC IPR register number	Source module	Source description
0x0000_0194	101	85	2	21	Low Power Timer	_

<sup>1.</sup> Indicates the NVIC's interrupt source number.

- The NVIC registers you would use to configure the interrupt are:
  - NVICISER2
  - NVICICER2
  - NVICISPR2
  - NVICICPR2

<sup>2.</sup> Indicates the NVIC's ISER, ICER, ISPR, ICPR, and IABR register number used for this IRQ. The equation to calculate this value is: IRQ div 32

<sup>3.</sup> Indicates the NVIC's IPR register number used for this IRQ. The equation to calculate this value is: IRQ div 4

<sup>4.</sup> This interrupt can only be pended or cleared via the NVIC registers.

<sup>2.</sup> Indicates the NVIC's ISER, ICER, ISPR, ICPR, and IABR register number used for this IRQ. The equation to calculate this value is: IRQ div 32

<sup>3.</sup> Indicates the NVIC's IPR register number used for this IRQ. The equation to calculate this value is: IRQ div 4



#### **Core modules**

- NVICIABR2
- NVICIPR21
- To determine the particular IRQ's bitfield location within these particular registers:
  - NVICISER2, NVICICER2, NVICISPR2, NVICICPR2, NVICIABR2 bit location = IRQ mod 32 = 21
  - NVICIPR21 bitfield starting location = 8 \* (IRQ mod 4) + 4 = 12

Since the NVICIPR bitfields are 4-bit wide (16 priority levels), the NVICIPR21 bitfield range is 12-15

Therefore, the following bitfield locations are used to configure the LPTMR interrupts:

- NVICISER2[21]
- NVICICER2[21]
- NVICISPR2[21]
- NVICICPR2[21]
- NVICIABR2[21]
- NVICIPR21[15:12]

# 3.2.3 Asynchronous Wake-up Interrupt Controller (AWIC) Configuration

This section summarizes how the module has been configured in the chip. Full documentation for this module is provided by ARM and can be found at http://www.arm.com.




Figure 3-3. Asynchronous Wake-up Interrupt Controller configuration

Table 3-6. Reference links to related information

Topic	Related module	Reference
System memory map		System memory map
Clocking		Clock distribution

Table continues on the next page...



Table 3-6. Reference links to related information (continued)

Topic	Related module	Reference
Power management		Power management
	Nested Vectored Interrupt Controller (NVIC)	NVIC
Wake-up requests		AWIC wake-up sources

# 3.2.3.1 Wake-up sources

The device uses the following internal and external inputs to the AWIC module.

Table 3-7. AWIC Stop and VLPS Wake-up Sources

Wake-up source	Description
Available system resets	RESET pin and WDOG when LPO is its clock source, and JTAG
Low-voltage detect	Mode Controller
Low-voltage warning	Mode Controller
Pin interrupts	Port Control Module - Any enabled pin interrupt is capable of waking the system
ADCx	The ADC is functional when using internal clock source
CMPx	Since no system clocks are available, functionality is limited
I <sup>2</sup> C	Address match wakeup
UART	Active edge on RXD
USB	Wakeup
LPTMR	Functional in Stop/VLPS modes
RTC	Functional in Stop/VLPS modes
SDHC	Wakeup
I2S	Wakeup
TSI	

# 3.2.4 JTAG Controller Configuration



system modules




Figure 3-4. JTAGC Controller configuration

Table 3-8. Reference links to related information

Topic	Related module	Reference
Full description	JTAGC	JTAGC
Signal multiplexing	Port control	Signal multiplexing

# 3.3 System modules

# 3.3.1 SIM Configuration




Figure 3-5. SIM configuration

Table 3-9. Reference links to related information

Topic	Related module	Reference
Full description	SIM	SIM
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management



# 3.3.2 Mode Controller Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-6. Mode controller configuration

Table 3-10. Reference links to related information

Topic	Related module	Reference
Full description	Mode Controller	Mode Controller
System memory map		System memory map
Power management		Power management
Power management controller (PMC)		PMC

# 3.3.3 PMC Configuration






Figure 3-7. PMC configuration

Table 3-11. Reference links to related information

Topic	Related module	Reference
Full description	PMC	PMC
System memory map		System memory map
Power management		Power management
Full description	Mode Controller	Mode Controller
	Low-Leakage Wakeup Unit (LLWU)	LLWU

# 3.3.4 Low-Leakage Wake-up Unit (LLWU) Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-8. Low-Leakage Wake-up Unit configuration

Table 3-12. Reference links to related information

Topic	Related module	Reference
Full description	LLWU	LLWU
System memory map		System memory map

Table continues on the next page...



Table 3-12	Reference lin	ks to related	l information	(continued)
I able 3-12.	neierence iii	ns to related	ı illibi illalıbi	(Continued)

Topic	Related module	Reference	
Clocking		Clock distribution	
Power management		Power management chapter	
	Power Management Controller (PMC)	Power Management Controller (PMC)	
	Mode Controller	Mode Controller	
Wake-up requests		LLWU wake-up sources	

### 3.3.4.1 Wake-up Sources

This chip uses the following internal peripheral and external pin inputs as wakeup sources to the LLWU module:

- LLWU\_P0-15 are external pin inputs. See the chip's signal multiplexing table for the individual input signal options.
- LLWU\_M0IF-M7IF are connections to the internal peripheral interrupt flags.

#### **NOTE**

RESET is also a wakeup source, depending on the bit setting in the LLWU\_CS register. On devices where RESET is not a dedicated pin, it must also be enabled in the explicit port mux control.

Table 3-13. Wakeup sources for LLWU inputs

Input	Wakeup source	Input	Wakeup source
LLWU_P0	PTE1/LLWU_P0 pin	LLWU_P12	PTD0/LLWU_P12 pin
LLWU_P1	PTE2/LLWU_P1 pin	LLWU_P13	PTD2/LLWU_P13 pin
LLWU_P2	PTE4/LLWU_P2 pin	LLWU_P14	PTD4/LLWU_P14 pin
LLWU_P3	PTA4/LLWU_P3 pin <sup>1</sup>	LLWU_P15	PTD6/LLWU_P15 pin
LLWU_P4	PTA13/LLWU_P4 pin	LLWU_M0IF	LPTMR <sup>2</sup>
LLWU_P5	PTB0/LLWU_P5 pin	LLWU_M1IF	CMP0 <sup>2</sup>
LLWU_P6	PTC1/LLWU_P6 pin	LLWU_M2IF	CMP1 <sup>2</sup>
LLWU_P7	PTC3/LLWU_P7 pin	LLWU_M3IF	CMP2 <sup>2</sup>
LLWU_P8	PTC4/LLWU_P8 pin	LLWU_M4IF	TSI <sup>2</sup>
LLWU_P9	PTC5/LLWU_P9 pin	LLWU_M5IF	RTC Alarm <sup>2</sup>
LLWU_P10	PTC6/LLWU_P10 pin	LLWU_M6IF	Reserved
LLWU_P11	PTC11/LLWU_P11 pin	LLWU_M7IF	Error Detect - wake-up source unknown

<sup>1.</sup> A falling edge input that remains low on this pin when waking up the MCU from VLLSx modes with the EzPort enabled causes entry into EzPort mode during the reset sequence. A falling edge input that remains low on this pin when waking



#### **System modules**

- up the MCU from any non-VLLSx mode with the NMI function selected in its port control register asserts an NMI exception on low power mode recovery. The same occurs when recovering from VLLSx modes if EzPort is disabled; otherwise, EzPort mode is entered. See the "EzPort Configuration" section in this chapter for more information.
- 2. Requires the peripheral and the peripheral interrupt to be enabled. The LLWU's WUME bit enables the internal module flag as a wakeup input. After wakeup, the flags are cleared based on the peripheral clearing mechanism.

### 3.3.5 MCM Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-9. MCM configuration

Table 3-14. Reference links to related information

Topic	Related module	Reference
Full description	Miscellaneous control module (MCM)	MCM
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Transfers	ARM Cortex-M4 core	ARM Cortex-M4 core
Private Peripheral Bus (PPB)		

### 3.3.6 Crossbar Switch Configuration






Figure 3-10. Crossbar switch integration

Table 3-15. Reference links to related information

Topic	Related module	Reference
Full description	Crossbar switch	Crossbar Switch
System memory map		System memory map
Clocking		Clock Distribution
Memory protection	MPU	MPU
Crossbar switch master	ARM Cortex-M4 core	ARM Cortex-M4 core
Crossbar switch master	DMA controller	DMA controller
Crossbar switch master	EzPort	EzPort
Crossbar switch master	USB FS/LS	USB FS/LS
Crossbar switch master	SDHC	SDHC
Crossbar switch slave	Flash	Flash
Crossbar switch slave	SRAM backdoor	SRAM backdoor
Crossbar switch slave	Peripheral bridges	Peripheral bridge

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



**System modules** 

Table 3-15. Reference links to related information (continued)

Topic	Related module	Reference
Crossbar switch slave	GPIO controller	GPIO controller
Crossbar switch slave	FlexBus	FlexBus

### 3.3.6.1 Crossbar Switch Master Assignments

The masters connected to the crossbar switch are assigned as follows:

Master module	Master port number
ARM core code bus	0
ARM core system bus	1
DMA/EzPort	2
USB OTG	4
SDHC	5

#### **NOTE**

The DMA and EzPort share a master port. Since these modules never operate at the same time, no configuration or arbitration explanations are necessary.

## 3.3.6.2 Crossbar Switch Slave Assignments

The slaves connected to the crossbar switch are assigned as follows:

Slave module	Slave port number	Protected by MPU?
Flash memory controller	0	Yes
SRAM backdoor	1	Yes
Peripheral bridge 0 <sup>1</sup>	2	No. Protection built into bridge.
Peripheral bridge 1/GPIO <sup>1</sup>	3	No. Protection built into bridge.
FlexBus	4	Yes

<sup>1.</sup> See System memory map for access restrictions.

# 3.3.6.3 PRS register reset values

The AXBS\_PRS*n* registers reset to 0054\_3210h.



# 3.3.7 Memory Protection Unit (MPU) Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-11. Memory Protection Unit configuration

Table 3-16. Reference links to related information

Topic	Related module	Reference
Full description	Memory Protection Unit (MPU)	MPU
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Logical masters		Logical master assignments
Slave modules		Slave module assignments

# 3.3.7.1 MPU Slave Port Assignments

The memory-mapped resources protected by the MPU are:

**Table 3-17. MPU Slave Port Assignments** 

Source	MPU Slave Port Assignment	Destination	
Crossbar slave port 0	MPU slave port 0	Flash Controller	
Crossbar slave port 1	MPU slave port 1	SRAM backdoor	
Code Bus	MPU slave port 2	SRAM_L frontdoor	
System Bus	MPU slave port 3	SRAM_U frontdoor	
Crossbar slave port 4	MPU slave port 4	FlexBus	



### 3.3.7.2 MPU Logical Bus Master Assignments

The logical bus master assignments for the MPU are:

Table 3-18. MPU Logical Bus Master Assignments

MPU Logical Bus Master Number	Bus Master
0	Core
1	Debugger
2	DMA
3	none
4	USB
5	SDHC
6	none
7	none

#### 3.3.7.3 MPU Access Violation Indications

Access violations detected by the MPU are signaled to the appropriate bus master as shown below:

**Table 3-19. Access Violation Indications** 

Bus Master	Core Indication	
Core	Bus fault (interrupt vector #5) Note: To enable bus faults set the core's System Handler Control and State Register's BUSFAULTENA bit. If this bit is not set, MPU violations result in a hard fault (interrupt vector #3).	
Debugger	The STICKYERROR flag is set in the Debug Port Control/Status Register.	
DMA	Interrupt vector #32	
USB_OTG	Interrupt vector #89	
SDHC	Interrupt vector #96	

### 3.3.7.4 Reset Values for RGD0 Registers

At reset, the MPU is enabled with a single region descriptor (RGD0) that maps the entire 4 GB address space with read, write and execute permissions given to the core, debugger and the DMA bus masters.

The following table shows the chip-specific reset values for RGD0 and RGDAAC0.



Table 3-20.	Reset	Values fo	r RGD0	Registers
-------------	-------	-----------	--------	-----------

Register	Reset value
RGD0_WORD0	0000_0000h
RGD0_WORD1	FFFF_FFFFh
RGD0_WORD2	0061_F7DFh
RGD0_WORD3	0000_0001h
RGDAAC0	0061_F7DFh

#### 3.3.7.5 Write Access Restrictions for RGD0 Registers

In addition to configuring the initial state of RGD0, the MPU implements further access control on writes to the RGD0 registers. Specifically, the MPU assigns a priority scheme where the debugger is treated as the highest priority master followed by the core and then all the remaining masters.

The MPU does not allow writes from the core to affect the RGD0 start or end addresses nor the permissions associated with the debugger; it can only write the permission fields associated with the other masters.

These protections (summarized below) guarantee that the debugger always has access to the entire address space and those rights cannot be changed by the core or any other bus master.

Table 3-21. Write Access to RGD0 Registers

Bus Master	Write Access?
Core	Partial. The Core cannot write to the following registers or register fields:  RGD0_WORD0, RGD0_WORD1, RGD0_WORD3 RGD0_WORD2[M1SM, M1UM] RGDAAC0[M1SM, M1UM]  NOTE: Changes to the RGD0_WORD2 alterable fields should be done via a write to RGDAAC0.
Debugger	Yes
All other masters	No

# 3.3.8 Peripheral Bridge Configuration



ovsiem modules




Figure 3-12. Peripheral bridge configuration

Table 3-22. Reference links to related information

Topic	Related module	Reference
Full description	Peripheral bridge (AIPS-Lite)	Peripheral bridge (AIPS-Lite)
System memory map		System memory map
Clocking		Clock Distribution
Crossbar switch	Crossbar switch	Crossbar switch

### 3.3.8.1 Number of peripheral bridges

This device contains two identical peripheral bridges.

### **3.3.8.2 Memory maps**

The peripheral bridges are used to access the registers of most of the modules on this device. See AIPS0 Memory Map and AIPS1 Memory Map for the memory slot assignment for each module.

### 3.3.8.3 MPRA register

Each of the two peripheral bridges supports up to 8 crossbar switch masters, each assigned to a MPROTx field in the MPRA register. However, fewer are supported on this device. See Crossbar switch for details of the master port assignments for this device.

# 3.3.8.4 AIPS\_Lite MPRA register reset value

• AIPSx\_MPRA reset value is 0x7770\_0000

Therefore, masters 0, 1, and 2 are trusted bus masters after reset.



#### 3.3.8.5 PACR registers

Each of the two peripheral bridges support up to 128 peripherals each assigned to an PACRx field within the PACRA-PACRP registers. However, fewer peripherals are supported on this device. See AIPSO Memory MapandAIPS1 Memory Map for details of the peripheral slot assignments for this device. Unused PACRx fields are reserved.

#### 3.3.8.6 AIPS\_Lite PACRE-P register reset values

The AIPS*x*\_PACRE-P reset values depend on if the module is available on your particular device. For each populated slot in slots 32-127 in Peripheral Bridge 0 (AIPS-Lite 0) Memory Map and Peripheral Bridge 1 (AIPS-Lite 1) Memory Map, the corresponding module's PACR[32:127] field resets to 0x4.

# 3.3.9 DMA request multiplexer configuration




Figure 3-13. DMA request multiplexer configuration

Table 3-23. Reference links to related information

Topic	Related module	Reference
Full description	DMA request multiplexer	DMA Mux
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Channel request	DMA controller	DMA Controller
Requests		DMA request sources



### 3.3.9.1 DMA MUX request sources

This device includes a DMA request mux that allows up to 63 DMA request signals to be mapped to any of the 16 DMA channels.

Because of the mux there is not a hard correlation between any of the DMA request sources and a specific DMA channel.

Table 3-24. DMA request sources - MUX 0

Source number	Source module	Source description	
0	<del>-</del>	Channel disabled <sup>1</sup>	
1	Reserved	Not used	
2	UART0	Receive	
3	UART0	Transmit	
4	UART1	Receive	
5	UART1	Transmit	
6	UART2	Receive	
7	UART2	Transmit	
8	UART3	Receive	
9	UART3	Transmit	
10	UART4	Receive	
11	UART4	Transmit	
12	UART5	Receive	
13	UART5	Transmit	
14	I <sup>2</sup> S0	Receive	
15	I <sup>2</sup> S0	Transmit	
16	SPI0	Receive	
17	SPI0	Transmit	
18	SPI1	Receive	
19	SPI1	Transmit	
20			
21			
22	I <sup>2</sup> C0	_	
23	I <sup>2</sup> C1	_	
24	FTM0	Channel 0	
25	FTM0	Channel 1	
26	FTM0	Channel 2	

Table continues on the next page...



# Table 3-24. DMA request sources - MUX 0 (continued)

Source number	Source module	ource module Source description	
27	FTM0	Channel 3	
28	FTM0	Channel 4	
29	FTM0	Channel 5	
30	FTM0	Channel 6	
31	FTM0	Channel 7	
32	FTM1	Channel 0	
33	FTM1	Channel 1	
34	FTM2	Channel 0	
35	FTM2	Channel 1	
36	FTM3	Channel 0	
37	FTM3	Channel 1	
38	FTM3	Channel 2	
39	FTM1	Channel 3	
40	ADC0	_	
41	ADC1	_	
42	CMP0	_	
43	CMP1	_	
44	CMP2	_	
45	DAC0	_	
46	DAC1 —		
47	CMT	_	
48	PDB	_	
49	Port control module	Port A	
50	Port control module	Port B	
51	Port control module	Port C	
52	Port control module	Port D	
53	Port control module	Port E	
54	FTM3 Channel 4		
55	FTM3 Channel 5		
56	FTM3 Channel 6		
57	FTM3 Channel 7		
58	DMA MUX Always enabled		
59	DMA MUX Always enabled		
60	DMA MUX	Always enabled	

Table continues on the next page...



#### **System modules**

Table 3-24. DMA request sources - MUX 0 (continued)

Source number	Source module	Source description
61	DMA MUX	Always enabled
62	DMA MUX	Always enabled
63	DMA MUX	Always enabled

<sup>1.</sup> Configuring a DMA channel to select source 0 or any of the reserved sources disables that DMA channel.

### 3.3.9.2 DMA transfers via PIT trigger

The PIT module can trigger a DMA transfer on the first four DMA channels. The assignments are detailed at PIT/DMA Periodic Trigger Assignments.

# 3.3.10 DMA Controller Configuration




Figure 3-14. DMA Controller configuration

Table 3-25. Reference links to related information

Topic	Related module	Reference
Full description	DMA Controller	DMA Controller
System memory map		System memory map
Register access	Peripheral bridge (AIPS-Lite 0)	AIPS-Lite 0
Clocking		Clock distribution
Power management		Power management
Transfers	Crossbar switch	Crossbar switch



# 3.3.11 External Watchdog Monitor (EWM) Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-15. External Watchdog Monitor configuration

Table 3-26. Reference links to related information

Topic	Related module	Reference
Full description	External Watchdog Monitor (EWM)	EWM
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Signal multiplexing	Port Control Module	Signal multiplexing

#### 3.3.11.1 EWM clocks

This table shows the EWM clocks and the corresponding chip clocks.

Table 3-27. EWM clock connections

Module clock	Chip clock
Low Power Clock	1 kHz LPO Clock

# 3.3.11.2 EWM low-power modes

This table shows the EWM low-power modes and the corresponding chip low-power modes.

Table 3-28. EWM low-power modes

Module mode	Chip mode
Wait	Wait, VLPW
Stop	Stop, VLPS, LLS
Power Down	VLLS3, VLLS2, VLLS1

#### 3.3.11.3 **EWM OUT** pin state in low power modes

During Wait, Stop and Power Down modes the EWM\_OUT pin enters a high-impedance state. A user has the option to control the logic state of the pin using an external pull device or by configuring the internal pull device. When the CPU enters a Run mode from Wait or Stop recovery, the pin resumes its previous state before entering Wait or Stop mode. When the CPU enters Run mode from Power Down, the pin returns to its reset state.

# 3.3.12 Watchdog Configuration




Figure 3-16. Watchdog configuration

Table 3-29. Reference links to related information

Topic	Related module	Reference
Full description	Watchdog	Watchdog
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
	Mode Controller (MC)	Mode Controller



#### 3.3.12.1 WDOG clocks

This table shows the WDOG module clocks and the corresponding chip clocks.

Table 3-30. WDOG clock connections

Module clock	Chip clock
LPO Oscillator	1 kHz LPO Clock
Alt Clock	Bus Clock
Fast Test Clock	Bus Clock
System Bus Clock	Bus Clock

### 3.3.12.2 WDOG low-power modes

This table shows the WDOG low-power modes and the corresponding chip low-power modes.

Table 3-31. WDOG low-power modes

Module mode	Chip mode
Wait	Wait, VLPW
Standby	Stop, VLPS
Stop	Stop, VLPS
Power Down	LLS, VLLSx

#### NOTE

To enable the WDOG module when the chip is in Stop mode, write ones to both the STNDBYEN bit and the STOPEN bit of the Watchdog Status and Control Register High.

# 3.4 Clock Modules

# 3.4.1 MCG Configuration






Figure 3-17. MCG configuration

Table 3-32. Reference links to related information

Topic	Related module	Reference
Full description	MCG	MCG
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Signal multiplexing	Port control	Signal multiplexing

# 3.4.2 OSC Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-18. OSC configuration

Table 3-33. Reference links to related information

Topic	Related module	Reference
Full description	OSC	OSC
System memory map		System memory map
Clocking		Clock distribution

Table continues on the next page...



Table 3-33	Reference link	e to related	l information	(continued)
i abie 5-55.	neierence iink	S to related	ı illilorillation	(Continued)

Topic	Related module	Reference
Power management		Power management
Signal multiplexing	Port control	Signal multiplexing
Full description	MCG	MCG

### 3.4.2.1 OSC modes of operation with MCG

The MCG's C2 register bits configure the oscillator frequency range. See the OSC and MCG chapters for more details.

# 3.4.3 RTC OSC configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-19. RTC OSC configuration

Table 3-34. Reference links to related information

Topic	Related module	Reference
Full description	RTC OSC	RTC OSC
Signal multiplexing	Port control	Signal multiplexing
Full description	MCG	MCG

# 3.5 Memories and Memory Interfaces

# 3.5.1 Flash Memory Configuration






Figure 3-20. Flash memory configuration

Table 3-35. Reference links to related information

Topic	Related module	Reference
Full description	Flash memory	Flash memory
System memory map		System memory map
Clocking		Clock Distribution
Transfers	Flash memory controller	Flash memory controller
Register access	Peripheral bridge	Peripheral bridge

### 3.5.1.1 Flash memory types

This device contains the following types of flash memory:

- Program flash memory non-volatile flash memory that can execute program code
- FlexMemory encompasses the following memory types:
  - Programming acceleration RAM RAM memory that accelerates flash programming

# 3.5.1.2 Flash Memory Sizes

The devices covered in this document contain:

• 2 blocks of program flash consisting of 2 KB sectors

The amounts of flash memory for the devices covered in this document are:

Device	Program flash (KBytes)	Block 0 (P-Flash) address range <sup>1</sup>	Block 1 (P-Flash) address range <sup>1</sup>
MK50DN512ZCLQ10	512	0x0000_0000 - 0x0003_FFFF	0x0004_0000 - 0x0007_FFFF

Table continues on the next page...



Device	Program flash (KBytes)	Block 0 (P-Flash) address range <sup>1</sup>	Block 1 (P-Flash) address range <sup>1</sup>
MK50DN512ZCMD10	512	0x0000_0000 - 0x0003_FFFF	0x0004_0000 - 0x0007_FFFF

<sup>1.</sup> The addresses shown assume program flash swap is disabled (default configuration).

### 3.5.1.3 Flash Memory Map

The various flash memories and the flash registers are located at different base addresses as shown in the following figure. The base address for each is specified in System memory map.




Figure 3-21. Flash memory map

# 3.5.1.4 Flash Security

How flash security is implemented on this device is described in Chip Security.

### 3.5.1.5 Flash Modes

The flash memory operates in NVM normal and NVM special modes. The flash memory enters NVM special mode when the EzPort is enabled (EZP\_CS asserted during reset), or the system is under debug mode. Otherwise, flash memory operates in NVM normal mode.

#### 3.5.1.6 Erase All Flash Contents

In addition to software, the entire flash memory may be erased external to the flash memory in two ways:



#### wemories and Memory Interfaces

- 1. Via the EzPort by issuing a bulk erase (BE) command. See the EzPort chapter for more details.
- 2. Via the SWJ-DP debug port by setting DAP\_CONTROL[0]. DAP\_STATUS[0] is set to indicate the mass erase command has been accepted. DAP\_STATUS[0] is cleared when the mass erase completes.

# 3.5.1.7 FTFL\_FOPT Register

The flash memory's FTFL\_FOPT register allows the user to customize the operation of the MCU at boot time. See FOPT boot options for details of its definition.

### 3.5.2 Flash Memory Controller Configuration




Figure 3-22. Flash memory controller configuration

Table 3-36. Reference links to related information

Topic	Related module	Reference
Full description	Flash memory controller	Flash memory controller
System memory map		System memory map
Clocking		Clock Distribution
Transfers	Flash memory	Flash memory
Transfers	MPU	MPU
Transfers	Crossbar switch	Crossbar Switch
Register access	Peripheral bridge	Peripheral bridge



#### 3.5.2.1 Number of masters

The Flash Memory Controller supports up to eight crossbar switch masters. However, this device has a different number of crossbar switch masters. See Crossbar Switch Configuration for details on the master port assignments.

#### 3.5.2.2 Program Flash Swap

On devices that contain program flash memory only, the program flash memory blocks may swap their base addresses.

While not using swap:

- FMC\_PFB0CR controls the lower code addresses (block 0)
- FMC\_PFB1CR controls the upper code addresses (block 1)

If swap is used, the opposite is true:

- FMC\_PFB0CR controls the upper code addresses (now in block 0)
- FMC\_PFB1CR controls the lower code addresses (now in block 1)

# 3.5.3 SRAM Configuration

This section summarizes how the module has been configured in the chip.




Figure 3-23. SRAM configuration

Table 3-37. Reference links to related information

Topic	Related module	Reference
Full description	SRAM	SRAM
System memory map		System memory map
Clocking		Clock Distribution
Transfers	SRAM controller	SRAM controller
	ARM Cortex-M4 core	ARM Cortex-M4 core
	Memory protection unit	Memory protection unit



#### 3.5.3.1 **SRAM** sizes

This device contains SRAM tightly coupled to the ARM Cortex-M4 core. The amount of SRAM for the devices covered in this document is shown in the following table.

Device	SRAM (KB)
MK50DN512ZCLQ10	128
MK50DN512ZCMD10	128

#### 3.5.3.2 SRAM Arrays

The on-chip SRAM is split into two equally-sized logical arrays, SRAM\_L and SRAM\_U.

The on-chip RAM is implemented such that the SRAM\_L and SRAM\_U ranges form a contiguous block in the memory map. As such:

- SRAM\_L is anchored to 0x1FFF\_FFFF and occupies the space before this ending address.
- SRAM\_U is anchored to 0x2000\_0000 and occupies the space after this beginning address.

Valid address ranges for SRAM\_L and SRAM\_U are then defined as:

- $SRAM_L = [0x2000\_0000-(SRAM\_size/2)]$  to  $0x1FFF\_FFFF$
- $SRAM_U = 0x2000\_0000$  to  $[0x2000\_0000+(SRAM\_size/2)-1]$

This is illustrated in the following figure.




Figure 3-24. SRAM blocks memory map

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



For example, for a device containing 64 KB of SRAM the ranges are:

- SRAM\_L: 0x1FFF\_8000 0x1FFF\_FFF
- SRAM\_U: 0x2000\_0000 0x2000\_7FFF

#### 3.5.3.3 SRAM retention in low power modes

The SRAM is retained down to VLLS3 mode.

In VLLS2 the 4 KB region of SRAM\_U from 0x2000\_0000 is powered.

In VLLS1 no SRAM is retained. However, the 32-byte register file is available in VLLS1.

#### 3.5.3.4 SRAM accesses

The SRAM is split into two logical arrays that are 32-bits wide.

- SRAM\_L Accessible by the code bus of the Cortex-M4 core and by the backdoor port.
- SRAM\_U Accessible by the system bus of the Cortex-M4 core and by the backdoor port.

The backdoor port makes the SRAM accessible to the non-core bus masters (such as DMA).

The following figure illustrates the SRAM accesses within the device.




Figure 3-25. SRAM access diagram

The following simultaneous accesses can be made to different logical halves of the SRAM:

Core code and core system



#### wemories and Memory Interfaces

- Core code and non-core master
- Core system and non-core master

#### NOTE

Two non-core masters cannot access SRAM simultaneously. The required arbitration and serialization is provided by the crossbar switch. The SRAM\_{L,U} arbitration is controlled by the SRAM controller based on the configuration bits in the MCM module.

#### NOTE

Burst-access cannot occur across the 0x2000\_0000 boundary that separates the two SRAM arrays. The two arrays should be treated as separate memory ranges for burst accesses.

### 3.5.3.5 SRAM arbitration and priority control

The MCM's SRAMAP register controls the arbitration and priority schemes for the two SRAM arrays.

# 3.5.4 SRAM Controller Configuration

This section summarizes how the module has been configured in the chip.




Figure 3-26. SRAM controller configuration

Table 3-38. Reference links to related information

Topic	Related module	Reference
System memory map		System memory map
Power management		Power management
Power management controller (PMC)		PMC

Table continues on the next page...



Table 3-38. Reference links to related information (continued)

Topic	Related module	Reference
Transfers	SRAM	SRAM
	ARM Cortex-M4 core	ARM Cortex-M4 core
	MPU	Memory protection unit
Configuration	MCM	MCM

# 3.5.5 System Register File Configuration

This section summarizes how the module has been configured in the chip.




Figure 3-27. System Register file configuration

Table 3-39. Reference links to related information

Topic	Related module	Reference
Full description	Register file	Register file
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management

# 3.5.5.1 System Register file

This device includes a 32-byte register file that is powered in all power modes.

Also, it retains contents during low-voltage detect (LVD) events and is only reset during a power-on reset.



# 3.5.6 VBAT Register File Configuration

This section summarizes how the module has been configured in the chip.




Figure 3-28. VBAT Register file configuration

Table 3-40. Reference links to related information

Topic	Related module	Reference
Full description	VBAT register file	VBAT register file
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management

### 3.5.6.1 VBAT register file

This device includes a 32-byte register file that is powered in all power modes and is powered by VBAT.

It is only reset during VBAT power-on reset.

# 3.5.7 EzPort Configuration



Figure 3-29. EzPort configuration

Table 3-41. Reference links to related information

Topic	Related module	Reference
Full description	EzPort	EzPort
System memory map		System memory map
Clocking		Clock Distribution
Transfers	Crossbar switch	Crossbar switch
Signal Multiplexing	Port control	Signal Multiplexing

#### 3.5.7.1 JTAG instruction

The system JTAG controller implements an EZPORT instruction. When executing this instruction, the JTAG controller resets the core logic and asserts the EzPort chip select signal to force the processor into EzPort mode.

### 3.5.7.2 Flash Option Register (FOPT)

The FOPT[EZPORT\_DIS] bit can be used to prevent entry into EzPort mode during reset. If the FOPT[EZPORT\_DIS] bit is cleared, then the state of the chip select signal (EZP\_CS) is ignored and the MCU always boots in normal mode.

This option is useful for systems that use the  $\overline{EZP\_CS}/NMI$  signal configured for its NMI function. Disabling EzPort mode prevents possible unwanted entry into EzPort mode if the external circuit that drives the NMI signal asserts it during reset.

The FOPT register is loaded from the flash option byte. If the flash option byte is modified the new value takes effect for any subsequent resets, until the value is changed again.

### 3.5.8 FlexBus Configuration






Figure 3-30. FlexBus configuration

Table 3-42. Reference links to related information

Topic	Related module	Reference
Full description	FlexBus	FlexBus
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Transfers	Memory protection unit (MPU)	Memory protection unit (MPU)
Signal multiplexing	Port control	Signal multiplexing

### 3.5.8.1 FlexBus clocking

The system provides a dedicated clock source to the FlexBus module's external FB\_CLKOUT. Its clock frequency is derived from a divider of the MCGOUTCLK. See Clock Distribution for more details.

### 3.5.8.2 FlexBus signal multiplexing

The multiplexing of the FlexBus address and data signals is controlled by the port control module. However, the multiplexing of some of the FlexBus control signals are controlled by the port control and FlexBus modules. The port control module registers control whether the FlexBus or another module signals are available on the external pin, while the FlexBus's CSPMCR register configures which FlexBus signals are available from the module. The control signals are grouped as illustrated:






Figure 3-31. FlexBus control signal multiplexing

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



**Security** 

Therefore, use the CSPMCR and port control registers to configure which control signal is available on the external pin. All control signals, except for FB\_TA, are assigned to the ALT5 function in the port control module. Since, unlike the other control signals, FB\_TA is an input signal, it is assigned to the ALT6 function.

#### 3.5.8.3 FlexBus CSCR0 reset value

On this device the CSCR0 resets to 0x003F\_FC00. Configure this register as needed before performing any FlexBus access.

#### 3.5.8.4 FlexBus Security

When security is enabled on the device, FlexBus accesses may be restricted by configuring the FBSEL field in the SIM's SOPT2 register. See System Integration Module (SIM) for details.

#### 3.5.8.5 FlexBus line transfers

Line transfers are not possible from the ARM Cortex-M4 core. Ignore any references to line transfers in the FlexBus chapter.

# 3.6 Security

### 3.6.1 CRC Configuration






Figure 3-32. CRC configuration

Table 3-43. Reference links to related information

Topic	Related module	Reference
Full description	CRC	CRC
System memory map		System memory map
Power management		Power management

# 3.7 Analog

# 3.7.1 16-bit SAR ADC with PGA Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-33. 16-bit SAR ADC with PGA configuration

Table 3-44. Reference links to related information

Topic	Related module	Reference
Full description	16-bit SAR ADC with PGA	16-bit SAR ADC with PGA

Table continues on the next page...



AllaiO

Table 3-44. Reference links to related information (continued)

Topic	Related module	Reference
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Signal multiplexing	Port control	Signal multiplexing

#### 3.7.1.1 ADC instantiation information

This device contains two ADCs. Each ADC contains a PGA channel for a total of two separate PGAs.

#### 3.7.1.1.1 Number of ADC channels

The number of ADC channels present on the device is determined by the pinout of the specific device package. For details regarding the number of ADC channel available on a particular package, refer to the signal multiplexing chapter of this MCU.

### 3.7.1.2 DMA Support on ADC

Applications may require continuous sampling of the ADC (4K samples/sec) that may have considerable load on the CPU. Though using PDB to trigger ADC may reduce some CPU load, The ADC supports DMA request functionality for higher performance when the ADC is sampled at a very high rate or cases were PDB is bypassed. The ADC can trigger the DMA (via DMA req) on conversion completion.

# 3.7.1.3 ADC0 Connections/Channel Assignment

#### NOTE

As indicated by the following sections, each ADCx\_DPx input and certain ADCx\_DMx inputs may operate as single-ended ADC channels in single-ended mode.



# 3.7.1.3.1 ADC0 Channel Assignment for 144-Pin Package

ADC Channel (SC1n[ADCH])	Channel	Input signal (SC1n[DIFF]= 1)	Input signal (SC1n[DIFF]= 0)
00000	DAD0	ADC0_DP0 and ADC0_DM01	ADC0_DP0 <sup>2</sup>
00001	DAD1	ADC0_DP1 and ADC0_DM1	ADC0_DP1
00010	DAD2	PGA0_DP and PGA0_DM	PGA0_DP
00011	DAD3	ADC0_DP3 and ADC0_DM3 <sup>3</sup>	ADC0_DP3 <sup>4</sup>
00100 <sup>5</sup>	AD4a	Reserved	Reserved
00101 <sup>5</sup>	AD5a	Reserved	Reserved
00110 <sup>5</sup>	AD6a	Reserved	Reserved
00111 <sup>5</sup>	AD7a	Reserved	Reserved
00100 <sup>5</sup>	AD4b	Reserved	ADC0_SE4b
00101 <sup>5</sup>	AD5b	Reserved	ADC0_SE5b
00110 <sup>5</sup>	AD6b	Reserved	ADC0_SE6b
00111 <sup>5</sup>	AD7b	Reserved	ADC0_SE7b
01000	AD8	Reserved	ADC0_SE8 <sup>6</sup>
01001	AD9	Reserved	ADC0_SE9 <sup>7</sup>
01010	AD10	Reserved	ADC0_SE10
01011	AD11	Reserved	ADC0_SE11
01100	AD12	Reserved	ADC0_SE12
01101	AD13	Reserved	ADC0_SE13
01110	AD14	Reserved	ADC0_SE14
01111	AD15	Reserved	ADC0_SE15
10000	AD16	Reserved	ADC0_SE16
10001	AD17	Reserved	Reserved
10010	AD18	Reserved	Reserved
10011	AD19	Reserved	ADC0_DM0 <sup>8</sup>
10100	AD20	Reserved	ADC0_DM1
10101	AD21	Reserved	OP0 Output
10110	AD22	Reserved	OP1 Output
10111	AD23	Reserved	12-bit DAC0 Output
11000	AD24	Reserved	Reserved
11001	AD25	Reserved	Reserved
11010	AD26	Temperature Sensor (Diff)	Temperature Sensor (S.E)
11011	AD27	Bandgap (Diff) <sup>9</sup>	Bandgap (S.E) <sup>9</sup>
11100	AD28	Reserved	Reserved
11101	AD29	-VREFH (Diff)	VREFH (S.E)
11110	AD30	Reserved	VREFL
11111	AD31	Module Disabled	Module Disabled

<sup>1.</sup> Interleaved with ADC1\_DP3 and ADC1\_DM3

<sup>2.</sup> Interleaved with ADC1\_DP3

<sup>3.</sup> Interleaved with ADC1\_DP0 and ADC1\_DM0

<sup>4.</sup> Interleaved with ADC1\_DP0



#### AliaiOQ

- ADCx\_CFG2[MUXSEL] bit selects between ADCx\_SEn channels a and b. Refer to MUXSEL description in ADC chapter for details.
- 6. Interleaved with ADC1\_SE8
- 7. Interleaved with ADC1\_SE9
- 8. Interleaved with ADC1\_DM3
- 9. This is the PMC bandgap 1V reference voltage not the VREF module 1.2 V reference voltage. Prior to reading from this ADC channel, ensure that you enable the bandgap buffer by setting the PMC\_REGSC[BGBE] bit. Refer to the device data sheet for the bandgap voltage (V<sub>BG</sub>) specification.

# 3.7.1.4 ADC1 Connections/Channel Assignment

#### NOTE

As indicated in the following tables, each ADCx\_DPx input and certain ADCx\_DMx inputs may operate as single-ended ADC channels in single-ended mode.

#### 3.7.1.4.1 ADC1 Channel Assignment for 144-Pin Package

ADC Channel (SC1n[ADCH])	Channel	Input signal (SC1n[DIFF]= 1)	Input signal (SC1n[DIFF]= 0)
00000	DAD0	ADC1_DP0 and ADC1_DM0 <sup>1</sup>	ADC1_DP0 <sup>2</sup>
00001	DAD1	ADC1_DP1 and ADC1_DM1	ADC1_DP1
00010	DAD2	PGA1_DP and PGA1_DM	PGA1_DP
00011	DAD3	ADC1_DP3 and ADC1_DM3 <sup>3</sup>	ADC1_DP3 <sup>4</sup>
00100 <sup>5</sup>	AD4a	Reserved	ADC1_SE4a
00101 <sup>5</sup>	AD5a	Reserved	ADC1_SE5a
00110 <sup>5</sup>	AD6a	Reserved	ADC1_SE6a
00111 <sup>5</sup>	AD7a	Reserved	ADC1_SE7a
00100 <sup>5</sup>	AD4b	Reserved	ADC1_SE4b
00101 <sup>5</sup>	AD5b	Reserved	ADC1_SE5b
00110 <sup>5</sup>	AD6b	Reserved	ADC1_SE6b
00111 <sup>5</sup>	AD7b	Reserved	ADC1_SE7b
01000	AD8	Reserved	ADC1_SE8 <sup>6</sup>
01001	AD9	Reserved	ADC1_SE9 <sup>7</sup>
01010	AD10	Reserved	ADC1_SE10
01011	AD11	Reserved	ADC1_SE11
01100	AD12	Reserved	ADC1_SE12
01101	AD13	Reserved	ADC1_SE13
01110	AD14	Reserved	ADC1_SE14
01111	AD15	Reserved	ADC1_SE15
10000	AD16	Reserved	ADC1_SE16
10001	AD17	Reserved	ADC1_SE17
10010	AD18	Reserved	VREF Output

Table continues on the next page...



ADC Channel (SC1n[ADCH])	Channel	Input signal (SC1n[DIFF]= 1)	Input signal (SC1n[DIFF]= 0)
10011	AD19	Reserved	ADC1_DM0 <sup>8</sup>
10100	AD20	Reserved	ADC1_DM1
10101	AD21	Reserved	Reserved
10110	AD22	Reserved	TRI1 Output
10111	AD23	Reserved	12-bit DAC1 Output
11000	AD24	Reserved	Reserved
11001	AD25	Reserved	Reserved
11010	AD26	Temperature Sensor (Diff)	Temperature Sensor (S.E)
11011	AD27	Bandgap (Diff) <sup>9</sup>	Bandgap (S.E) <sup>9</sup>
11100	AD28	Reserved	Reserved
11101	AD29	-VREFH (Diff)	VREFH (S.E)
11110	AD30	Reserved	VREFL
11111	AD31	Module Disabled	Module Disabled

- Interleaved with ADC0\_DP3 and ADC0\_DM3
- 2. Interleaved with ADC0\_DP3
- Interleaved with ADC0\_DP0 and ADC0\_DM0
- 4. Interleaved with ADC0\_DP0
- ADCx\_CFG2[MUXSEL] bit selects between ADCx\_SEn channels a and b. Refer to MUXSEL description in ADC chapter for details.
- 6. Interleaved with ADC0\_SE8
- 7. Interleaved with ADC0\_SE9
- 8. Interleaved with ADC0\_DM3
- 9. This is the PMC bandgap 1V reference voltage not the VREF module 1.2 V reference voltage. Prior to reading from this ADC channel, ensure that you enable the bandgap buffer by setting the PMC\_REGSC[BGBE] bit. Refer to the device data sheet for the bandgap voltage (V<sub>BG</sub>) specification.

#### 3.7.1.5 ADC Channels MUX Selection

The following figure shows the assignment of ADCx\_SEn channels a and b through a MUX selection to ADC. To select between alternate set of channels, refer to ADCx\_CFG2[MUXSEL] bit settings for more details.




Figure 3-34. ADCx\_SEn channels a and b selection



Allaiog

#### 3.7.1.6 ADC Hardware Interleaved Channels

The AD8 and AD9 channels on ADCx are interleaved in hardware using the following configuration.




Figure 3-35. ADC hardware interleaved channels integration

# 3.7.1.7 ADC and PGA Reference Options

The ADC supports the following references:

- VREFH/VREFL connected as the primary reference option
- 1.2 V VREF\_OUT connected as the V<sub>ALT</sub> reference option

ADCx\_SC2[REFSEL] bit selects the voltage reference sources for ADC. Refer to REFSEL description in ADC chapter for more details.

The only reference option for the PGA is the 1.2 V VREF\_OUT source. The VREF\_OUT signal can either be driven by an external voltage source via the VREF\_OUT pin or from the output of the VREF module. Ensure that the VREF module is disabled when an external voltage source is used instead. For PGA maximum differential input signal swing range, refer to the device data sheet for 16-bit ADC with PGA characteristics.



### 3.7.1.8 ADC triggers

The ADC supports both software and hardware triggers. The primary hardware mechanism for triggering the ADC is the PDB. The PDB itself can be triggered by other peripherals. For example: RTC (Alarm, Seconds) signal is connected to the PDB. The PDB trigger can receive the RTC (alarm/seconds) trigger input forcing ADC conversions in run mode (where PDB is enabled). On the other hand, the ADC can conduct conversions in low power modes, not triggered by PDB. This allows the ADC to do conversions in low power mode and store the output in the result register. The ADC generates interrupt when the data is ready in the result register that wakes the system from low power mode. The PDB can also be bypassed by using the ADCxTRGSEL bits in the SOPT7 register.

For operation of triggers in different modes, refer to Power Management chapter.

#### 3.7.1.9 Alternate clock

For this device, the alternate clock is connected to OSCERCLK.

#### **NOTE**

This clock option is only usable when OSCERCLK is in the MHz range. A system with OSCERCLK in the kHz range has the optional clock source below minimum ADC clock operating frequency.

### 3.7.1.10 ADC low-power modes

This table shows the ADC low-power modes and the corresponding chip low-power modes.

 Module mode
 Chip mode

 Wait
 Wait, VLPW

 Normal Stop
 Stop, VLPS

 Low Power Stop
 LLS, VLLS3, VLLS2, VLLS1

Table 3-45. ADC low-power modes



Aliaiog

### 3.7.1.11 PGA Integration

- No additional external pins are required for the PGA as it is part of the ADC and is selected as a separate channel
- Each PGA connects to the differential ADC channels
- The PGA outputs differential pairs that are connected to ADC differential input
- When the PGA is used, differential input from the pins is connected to differential input channel 2 on ADCx




Figure 3-36. PGA Integration

### 3.7.2 CMP Configuration






Figure 3-37. CMP configuration

Table 3-46. Reference links to related information

Topic	Related module	Reference
Full description	Comparator (CMP)	Comparator
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Signal multiplexing	Port control	Signal multiplexing

# 3.7.2.1 CMP input connections

The following table shows the fixed internal connections to the CMP.

CMP Inputs	CMP0	CMP1	CMP2
IN0	CMP0_IN0	CMP1_IN0	CMP2_IN0
IN1	CMP0_IN1	CMP1_IN1	CMP2_IN1
IN2	CMP0_IN2	Op-amp 0 output/CMP1_IN2	Op-amp 1 output/CMP2_IN2
IN3	CMP0_IN3	12b DAC0 reference/ CMP1_IN3	12b DAC1 reference/ CMP2_IN3
IN4	CMP0_IN4	_	_
IN5	VREF output/CMP0_IN5	VREF output/CMP1_IN5	TRIAMP1 output/CMP2_IN5
IN6	Bandgap	Bandgap	Bandgap
IN7	6b DAC0 reference	6b DAC1 reference	_

# 3.7.2.2 CMP external references

The 6-bit DAC sub-block supports selection of two references. For this device, the references are connected as follows:

- VREF\_OUT V<sub>in1</sub> input
- VDD  $V_{in2}$  input



## 3.7.2.3 External window/sample input

PDB pulse-out controls the CMP Sample/Window timing.

### 3.7.3 12-bit DAC Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-38. 12-bit DAC configuration

Table 3-47. Reference links to related information

Topic	Related module	Reference
Full description	12-bit DAC	12-bit DAC
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Signal multiplexing	Port control	Signal multiplexing

#### 3.7.3.1 12-bit DAC Overview

This device contains two 12-bit digital-to-analog converters (DAC) with programmable reference generator output. The DAC includes a FIFO for DMA support.

### 3.7.3.2 12-bit DAC Output

The output of the DAC can be placed on an external pin or set as one of the inputs to the analog comparator, op-amps, or ADC.



#### 3.7.3.3 12-bit DAC Reference

For this device VREF\_OUT and VDDA are selectable as the DAC reference. VREF\_OUT is connected to the DACREF\_1 input and VDDA is connected to the DACREF\_2 input. Use DACx\_C0[DACRFS] control bit to select between these two options.

Be aware that if the DAC and ADC use the VREF\_OUT reference simultaneously, some degradation of ADC accuracy is to be expected due to DAC switching.

# 3.7.4 Op-amp Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-39. Op-amp configuration

Table 3-48. Reference links to related information

Topic	Related module	Reference
Full description	Op-amp	Op-amp
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Signal multiplexing	Port control	Signal multiplexing

### 3.7.4.1 Op-amp Instantiation

The number of op-amp module instances on this chip is: two.



# 3.7.4.2 Op-amp 0 input mux connections

The op-amp 0 module contains multiplexers for selecting the positive and negative inputs. The inputs to these muxes are defined as follows:

Op-amp 0 minus input number	Signal connection
0	OP0_DM0 input signal (default)
1	Reserved
2	Op-amp 1 output
3	CMP0 6-bit DAC output
4	12-bit DAC0 output
5	12-bit DAC1 Output
6	$V_{DD}$
7	Ground

Op-amp 0 positive input number	Signal connection
0	OP0_DP0 input signal
1	Op-amp 0 output
2	Op-amp 1 output
3	CMP0 6-bit DAC output
4	12-bit DAC0 output
5	12-bit DAC1 Output
6	$V_{DD}$
7	Ground

# 3.7.4.3 Op-amp 1 input mux connections

The op-amp 1 module contains multiplexers for selecting the positive and negative inputs. The inputs to these muxes are defined as follows:

Op-amp 1 negative input number	Signal connection
0	OP1_DM0 input signal
1	Op-amp 0 output
2	OP1_DM1 input signal <sup>1</sup>
3	CMP0 6-bit DAC output
4	12-bit DAC0 output
5	TRI0_OUT/OP1_DM2 input signal <sup>2</sup>
6	$V_{DD}$
7	Ground



Op-amp 1 positive input number	Signal connection
0	OP1_DP0 input signal
1	Op-amp 0 output
2	Op-amp 1 output
3	CMP0 6-bit DAC output
4	12-bit DAC0 output
5	12-bit DAC1 Output
6	$V_{DD}$
7	Ground

### 3.7.4.4 Op-amp output connections

The op-amp module output is optionally available as follows:

Op-amp number	Op-amp output signal connection
0	CMP1 input
0	ADC0 channel
0	OP0_OUT output signal
1	CMP2 input
1	ADC0 channel
1	OP1_OUT output signal

# 3.7.5 TRIAMP Configuration



AliaiOg




Figure 3-40. TRIAMP configuration

Table 3-49. Reference links to related information

Topic	Related module	Reference	
Full description	TRIAMP	TRIAMP	
System memory map		System memory map	
Clocking		Clock distribution	
Power management		Power management	
Signal multiplexing	Port control	Signal multiplexing	

### 3.7.5.1 TRIAMP signals

Details regarding the TRIAMP signals used on this device are as follows:

- The TRIAMP inputs (TRIx\_DM and TRIx\_DP) are dedicated low-leakage input pads.
- The TRIAMP0 output is driven to external pin, TRI0\_OUT, and is shared with the OP1\_DM2 analog input.
- The TRIAMP1 output is driven to external pin, TRI1\_OUT, and is shared with the ADC1's AD22 and CMP2's IN5 inputs.

# 3.7.6 VREF Configuration






Figure 3-41. VREF configuration

Table 3-50. Reference links to related information

Topic	Related module	Reference	
Full description	VREF	VREF	
System memory map		System memory map	
Clocking		Clock distribution	
Power management		Power management	
Signal multiplexing	Port control	Signal multiplexing	

#### 3.7.6.1 VREF Overview

This device includes a voltage reference (VREF) to supply an accurate 1.2 V voltage output.

The voltage reference can provide a reference voltage to external peripherals or a reference to analog peripherals, such as the ADC, DAC, Op-amp, TRIAMP, or CMP.

#### NOTE

For either an internal or external reference if the VREF\_OUT functionality is being used, VREF\_OUT signal must be connected to an output load capacitor. Refer the device data sheet for more details.

## 3.8 Timers

# 3.8.1 PDB Configuration








Figure 3-42. PDB configuration

Table 3-51. Reference links to related information

Topic	Related module	Reference	
Full description	PDB	PDB	
System memory map		System memory map	
Clocking		Clock distribution	
Power management		Power management	
Signal multiplexing	Port control	Signal multiplexing	

#### 3.8.1.1 PDB Instantiation

# 3.8.1.1.1 PDB Output Triggers

Table 3-52. PDB output triggers

Number of PDB channels for ADC trigger	2
Number of pre-triggers per PDB channel	2
Number of DAC triggers	2
Number of PulseOut	1

### 3.8.1.1.2 PDB Input Trigger Connections

**Table 3-53. PDB Input Trigger Options** 

PDB Trigger	PDB Input
0000	External Trigger
0001	CMP 0
0010	CMP 1
0011	CMP 2
0100	PIT Ch 0 Output

Table continues on the next page...



Table 3-53. PDB Input Trigger Options (continued)

PDB Trigger	PDB Input	
0101	PIT Ch 1 Output	
0110	PIT Ch 2 Output	
0111	PIT Ch 3 Output	
1000	FTM0 Init and Ext Trigger Outputs	
1001	FTM1 Init and Ext Trigger Outputs	
1010	FTM2 Init and Ext Trigger Outputs	
1011	Reserved	
1100	RTC Alarm	
1101	RTC Seconds	
1110	LPTMR Output	
1111	Software Trigger	

#### 3.8.1.2 PDB Module Interconnections

PDB trigger outputs	Connection
Channel 0 triggers	ADC0 trigger
Channel 1 triggers	ADC1 trigger and synchronous input 1 of FTM0
DAC triggers	DAC0 and DAC1 trigger
Pulse-out	Pulse-out connected to each CMP module's sample/window input to control sample operation

### 3.8.1.3 Back-to-back acknowledgement connections

In this MCU, PDB back-to-back operation acknowledgment connections are implemented as follows:

- PDB channel 0 pre-trigger 0 acknowledgement input: ADC1SC1B\_COCO
- PDB channel 0 pre-trigger 1 acknowledgement input: ADC0SC1A\_COCO
- PDB channel 1 pre-trigger 0 acknowledgement input: ADC0SC1B\_COCO
- PDB channel 1 pre-trigger 1 acknowledgement input: ADC1SC1A\_COCO

So, the back-to-back chain is connected as a ring:






Figure 3-43. PDB back-to-back chain

The application code can set the PDBx\_CHnC1[BB] bits to configure the PDB pre-triggers as a single chain or several chains.

### 3.8.1.4 PDB Interval Trigger Connections to DAC

In this MCU, PDB interval trigger connections to DAC are implemented as follows.

- PDB interval trigger 0 connects to DAC0 hardware trigger input.
- PDB interval trigger 1 connects to DAC1 hardware trigger input.

### 3.8.1.5 DAC External Trigger Input Connections

In this MCU, two DAC external trigger inputs are implemented.

- DAC external trigger input 0: ADC0SC1A\_COCO
- DAC external trigger input 1: ADC1SC1A\_COCO

#### NOTE

Application code can set the PDBx\_DACINTCn[EXT] bit to allow DAC external trigger input when the corresponding ADC Conversion complete flag, ADCx\_SC1n[COCO], is set.

#### 3.8.1.6 Pulse-Out Connection

The Pulse-Out of PDB is connected to all the CMP blocks and used as the sample window.



### 3.8.1.7 Pulse-Out Enable Register Implementation

The following table shows the comparison of pulse-out enable register at the module and chip level.

Table 3-54. PDB pulse-out enable register

Register	Module implementation	Chip implementation
POnEN	7:0 - POEN	0 - POEN
	31:8 - Reserved	31:1 - Reserved

# 3.8.2 FlexTimer Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-44. FlexTimer configuration

Table 3-55. Reference links to related information

Topic	Related module	Reference	
Full description	FlexTimer	FlexTimer	
System memory map		System memory map	
Clocking		Clock distribution	
Power management		Power management	
Signal multiplexing	Port control	Signal multiplexing	

### 3.8.2.1 Instantiation Information

This device contains three FlexTimer modules.

The following table shows how these modules are configured.



Table 3-56. FTM Instantiations

FTM instance	Number of channels	Features/usage
FTM0	8	3-phase motor + 2 general purpose or stepper motor
FTM1	2	Quadrature decoder or general purpose
FTM2	2	Quadrature decoder or general purpose

Compared with the FTM0 configuration, the FTM1 and FTM2 configuration adds the Quadrature decoder feature and reduces the number of channels.

### 3.8.2.2 External Clock Options

By default each FTM is clocked by the internal bus clock (the FTM refers to it as system clock). Each module contains a register setting that allows the module to be clocked from an external clock instead. There are two external FTM\_CLKINx pins that can be selected by any FTM module via the SOPT4 register in the SIM module.

### 3.8.2.3 Fixed frequency clock

The fixed frequency clock for each FTM is MCGFFCLK.

### 3.8.2.4 FTM Interrupts

The FlexTimer has multiple sources of interrupt. However, these sources are OR'd together to generate a single interrupt request to the interrupt controller. When an FTM interrupt occurs, read the FTM status registers (FMS, SC, and STATUS) to determine the exact interrupt source.

# 3.8.2.5 FTM Fault Detection Inputs

The following fault detection input options for the FTM modules are selected via the SOPT4 register in the SIM module. The external pin option is selected by default.

- FTM0 FAULT0 = FTM0\_FLT0 pin or CMP0 output
- FTM0 FAULT1 = FTM0\_FLT1 pin or CMP1 output
- FTM0 FAULT2 = FTM0\_FLT2 pin or CMP2 output
- FTM0 FAULT3 = FTM0\_FLT3 pin
- FTM1 FAULT0 = FTM1\_FLT0 pin or CMP0 output



- FTM1 FAULT1 = CMP1 output
- FTM1 FAULT2 = CMP2 output
- FTM2 FAULT0 = FTM2\_FLT0 pin or CMP0 output
- FTM2 FAULT1 = CMP1 output
- FTM2 FAULT2 = CMP2 output

### 3.8.2.6 FTM Hardware Triggers

The FTM synchronization hardware triggers are connected in the chip as follows:

- FTM0 hardware trigger 0 = CMP0 Output
- FTM0 hardware trigger 1 = PDB channel 1 Trigger Output
- FTM0 hardware trigger 2 = FTM0\_FLT0 pin
- FTM1 hardware trigger 0 = CMP0 Output
- FTM1 hardware trigger 1 = CMP1 Output
- FTM1 hardware trigger 2 = FTM1\_FLT0 pin
- FTM2 hardware trigger 0 = CMP0 Output
- FTM2 hardware trigger 1 = CMP2 Output
- FTM2 hardware trigger 2 = FTM2\_FLT0 pin

### 3.8.2.7 Input capture options for FTM module instances

The following channel 0 input capture source options are selected via the SOPT4 register in the SIM module. The external pin option is selected by default.

- FTM1 channel 0 input capture = FTM1\_CH0 pin or CMP0 output or CMP1 output
- FTM2 channel 0 input capture = FTM2\_CH0 pin or CMP0 output or CMP1 output

### 3.8.2.8 FTM output triggers for other modules

FTM output triggers can be selected as input triggers for the PDB and ADC modules. See PDB Instantiation and ADC triggers.

#### 3.8.2.9 FTM Global Time Base

This chip provides the optional FTM global time base feature (see Global Time Base (GTB)).



#### rimers

FTM0 provides the only source for the FTM global time base. The other FTM modules can share the time base as shown in the following figure:




Figure 3-45. FTM Global Time Base Configuration

### 3.8.2.10 FTM BDM and debug halt mode

In the FTM chapter, references to the chip being in "BDM" are the same as the chip being in "debug halt mode".

# 3.8.3 PIT Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-46. PIT configuration

Table 3-57. Reference links to related information

Topic	Related module	Reference
Full description	PIT	PIT

Table continues on the next page...



#### Table 3-57. Reference links to related information (continued)

Topic	Related module	Reference
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management

### 3.8.3.1 PIT/DMA Periodic Trigger Assignments

The PIT generates periodic trigger events to the DMA Mux as shown in the table below.

Table 3-58. PIT channel assignments for periodic DMA triggering

DMA Channel Number	PIT Channel
DMA Channel 0	PIT Channel 0
DMA Channel 1	PIT Channel 1
DMA Channel 2	PIT Channel 2
DMA Channel 3	PIT Channel 3

## 3.8.3.2 PIT/ADC Triggers

PIT triggers are selected as ADCx trigger sources using the SOPT7[ADCxTRGSEL] bits in the SIM module. For more details, refer to SIM chapter.

# 3.8.4 Low-power timer configuration



Peripheral bridge

Register access

Module signals

Low-power timer

Module signals

Figure 3-47. LPT configuration

Table 3-59. Reference links to related information

Topic	Related module	Reference
Full description	Low-power timer	Low-power timer
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management
Signal Multiplexing	Port control	Signal Multiplexing

# 3.8.4.1 LPTMR prescaler/glitch filter clocking options

The prescaler and glitch filter of the LPTMR module can be clocked from one of four sources determined by the LPTMR0\_PSR[PCS] bitfield. The following table shows the chip-specific clock assignments for this bitfield.

#### NOTE

The chosen clock must remain enabled if the LPTMR is to continue operating in all required low-power modes.

LPTMR0_PSR[PCS]	Prescaler/glitch filter clock number	Chip clock
00	0	MCGIRCLK — internal reference clock (not available in VLPS/LLS/VLLS modes)
01	1	LPO — 1 kHz clock
10	2	ERCLK32K — secondary external reference clock
11	3	OSCERCLK — external reference clock

See Clock Distribution for more details on these clocks.



## 3.8.4.2 LPTMR pulse counter input options

The LPTMR\_CSR[TPS] bitfield configures the input source used in pulse counter mode. The following table shows the chip-specific input assignments for this bitfield.

LPTMR_CSR[TPS]	Pulse counter input number	Chip input
00	0	CMP0 output
01	1	LPTMR_ALT1 pin
10	2	LPTMR_ALT2 pin
11	3	Reserved

### 3.8.5 CMT Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-48. CMT configuration

Table 3-60. Reference links to related information

Topic	Related module	Reference
Full description	Carrier modulator transmitter (CMT)	СМТ
System memory map		System memory map
Clocking		Clock distribution
Power management		Power management
Signal multiplexing	Port control	Signal multiplexing

#### 3.8.5.1 Instantiation Information

This device contains one CMT module.



ımers

### 3.8.5.2 IRO Drive Strength

The IRO pad requires higher current drive than can be obtained from a single pad. For this device, the pin associated with the CMT\_IRO signal is doubled bonded to two pads.

The SOPT2[CMTUARTPAD] field in SIM module can be used to configure the pin associated with the CMT\_IRO signal as a higher current output port pin.

# 3.8.6 RTC configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-49. RTC configuration

Table 3-61. Reference links to related information

Topic	Related module	Reference
Full description	RTC	RTC
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management

### 3.8.6.1 RTC\_CLKOUT signal

When the RTC is enabled and the port control module selects the RTC\_CLKOUT function, the RTC\_CLKOUT signal is fixed to a 1 Hz output.

## 3.8.6.2 RTC\_WAKEUP signal

The RTC\_WAKEUP pin is not supported on this device.



### 3.8.6.3 RTC seconds interrupt

The RTC seconds interrupt is not supported on this device.

#### 3.9 Communication interfaces

# 3.9.1 Universal Serial Bus (USB) Subsystem

The USB subsystem includes these components:

- Dual-role USB OTG-capable (On-The-Go) controller that supports a full-speed (FS) device or FS/LS host. The module complies with the USB 2.0 specification.
- USB transceiver that includes internal 15 k $\Omega$  pulldowns on the D+ and D- lines for host mode functionality.
- A 3.3 V regulator.
- USB device charger detection module.
- VBUS detect signal: To detect a valid VBUS in device mode, use a GPIO signal that can wake the chip in all power modes.




Figure 3-50. USB Subsystem Overview

### 3.9.1.1 **USB Wakeup**

When the USB detects that there is no activity on the USB bus for more than 3 ms, the INT\_STAT[SLEEP] bit is set. This bit can cause an interrupt and software decides the appropriate action.

Waking from a low power mode (except in LLS/VLLS mode where USB is not powered) occurs through an asynchronous interrupt triggered by activity on the USB bus. Setting the USBTRC0[USBRESMEN] bit enables this function.



#### 3.9.1.2 USB Power Distribution

This chip includes an internal 5 V to 3.3 V USB regulator that powers the USB transceiver or the MCU (depending on the application).

### 3.9.1.2.1 AA/AAA cells power supply

The chip can be powered by two AA/AAA cells. In this case, the MCU is powered through VDD which is within the 1.8 to 3.0 V range. After USB cable insertion is detected, the USB regulator is enabled to power the USB transceiver.




Figure 3-51. USB regulator AA cell usecase

### 3.9.1.2.2 Li-lon battery power supply

The chip can also be powered by a single Li-ion battery. In this case, VOUT33 is connected to VDD. The USB regulator must be enabled by default to power the MCU. When connected to a USB host, the input source of this regulator is switched to the USB bus supply from the Li-ion battery. To charge the battery, the MCU can configure the battery charger according to the charger detection information.






Figure 3-52. USB regulator Li-ion usecase

#### 3.9.1.2.3 USB bus power supply

The chip can also be powered by the USB bus directly. In this case, VOUT33 is connected to VDD. The USB regulator must be enabled by default to power the MCU, then to power USB transceiver or external sensor.




Figure 3-53. USB regulator bus supply



**communication interfaces** 

### 3.9.1.3 USB power management

The regulator should be put into STANDBY mode whenever the chip is in Stop mode. This can be done by setting the SIM\_SOPT1[USBSTBY] bit.

### 3.9.1.4 USB controller configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-54. USB controller configuration

Table 3-62. Reference links to related information

Topic	Related module	Reference
Full description	USB controller	USB controller
System memory map		System memory map
Clocking		Clock Distribution
Transfers	Crossbar switch	Crossbar switch
Signal Multiplexing	Port control	Signal Multiplexing

#### NOTE

When USB is not used in the application, it is recommended that the USB regulator VREGIN and VOUT33 pins remain floating.

# 3.9.1.5 USB DCD Configuration






Figure 3-55. USB DCD configuration

Table 3-63. Reference links to related information

Topic	Related module	Reference
Full description	USB DCD	USB DCD
System memory map		System memory map
Clocking		Clock Distribution
	USB controller	USB controller

# 3.9.1.6 USB Voltage Regulator Configuration




Figure 3-56. USB Voltage Regulator configuration

Table 3-64. Reference links to related information

Topic	Related module	Reference
Full description	USB Voltage Regulator	USB Voltage Regulator
System memory map		System memory map
Clocking		Clock Distribution
	USB controller	USB controller
Signal Multiplexing	Port control	Signal Multiplexing



#### NOTE

When USB is not used in the application, it is recommended that the USB regulator VREGIN and VOUT33 pins remain floating.

# 3.9.2 SPI configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-57. SPI configuration

Table 3-65. Reference links to related information

Topic	Related module	Reference
Full description	SPI	SPI
System memory map		System memory map
Clocking		Clock Distribution
Signal Multiplexing	Port control	Signal Multiplexing

### 3.9.2.1 SPI Modules Configuration

This device contains three SPI modules.

# 3.9.2.2 SPI clocking

The SPI module is clocked by the internal bus clock (the DSPI refers to it as system clock). The module has an internal divider, with a minimum divide is two. So, the SPI can run at a maximum frequency of bus clock/2.



#### 3.9.2.3 Number of CTARs

SPI CTAR registers define different transfer attribute configurations. The SPI module supports up to eight CTAR registers. This device supports two CTARs on all instances of the SPI.

In master mode, the CTAR registers define combinations of transfer attributes, such as frame size, clock phase, clock polarity, data bit ordering, baud rate, and various delays. In slave mode only CTAR0 is used, and a subset of its bitfields sets the slave transfer attributes.

#### 3.9.2.4 TX FIFO size

Table 3-66. SPI transmit FIFO size

SPI Module	Transmit FIFO size
SPI0	4
SPI1	4
SPI2	4

#### 3.9.2.5 RX FIFO Size

SPI supports up to 16-bit frame size during reception.

Table 3-67. SPI receive FIFO size

SPI Module	Receive FIFO size
SPI0	4
SPI1	4
SPI2	4

# 3.9.2.6 Number of PCS signals

The following table shows the number of peripheral chip select signals available per SPI module.

Table 3-68. SPI PCS signals

SPI Module	PCS Signals
SPI0	SPI_PCS[5:0]
SPI1	SPI_PCS[3:0]

Table continues on the next page...



# Table 3-68. SPI PCS signals (continued)

SPI Module	PCS Signals
SPI2	SPI_PCS[1:0]

### 3.9.2.7 SPI Operation in Low Power Modes

In VLPR and VLPW modes the SPI is functional; however, the reduced system frequency also reduces the max frequency of operation for the SPI. In VLPR and VLPW modes the max SPI\_CLK frequency is 1MHz.

In stop and VLPS modes, the clocks to the SPI module are disabled. The module is not functional, but it is powered so that it retains state.

There is one way to wake from stop mode via the SPI, which is explained in the following section.

#### 3.9.2.7.1 Using GPIO Interrupt to Wake from stop mode

Here are the steps to use a GPIO to create a wakeup upon reception of SPI data in slave mode:

- 1. Point the GPIO interrupt vector to the desired interrupt handler.
- 2. Enable the GPIO input to generate an interrupt on either the rising or falling edge (depending on the polarity of the chip select signal).
- 3. Enter Stop or VLPS mode and Wait for the GPIO interrupt.

#### NOTE

It is likely that in using this approach the first word of data from the SPI host might not be received correctly. This is dependent on the transfer rate used for the SPI, the delay between chip select assertion and presentation of data, and the system interrupt latency.

#### 3.9.2.8 SPI Doze Mode

The Doze mode for the SPI module is the same as the Wait and VLPW modes for the chip.



# 3.9.2.9 SPI Interrupts

The SPI has multiple sources of interrupt requests. However, these sources are OR'd together to generate a single interrupt request per SPI module to the interrupt controller. When an SPI interrupt occurs, read the SPI\_SR to determine the exact interrupt source.

#### 3.9.2.10 SPI clocks

This table shows the SPI module clocks and the corresponding chip clocks.

Table 3-69. SPI clock connections

Module clock	Chip clock
System Clock	Bus Clock

# 3.9.3 I2C Configuration




Figure 3-58. I2C configuration

Table 3-70. Reference links to related information

Topic	Related module	Reference
Full description	I <sup>2</sup> C	I <sup>2</sup> C
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management
Signal Multiplexing	Port control	Signal Multiplexing



**communication interfaces** 

#### 3.9.3.1 Number of I2C modules

This device has two I<sup>2</sup>C modules.

### 3.9.4 UART Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-59. UART configuration

Table 3-71. Reference links to related information

Topic	Related module	Reference
Full description	UART	UART
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management
Signal Multiplexing	Port control	Signal Multiplexing

### 3.9.4.1 UART configuration information

This device contains six UART modules. This section describes how each module is configured on this device.

- 1. Standard features of all UARTs:
  - RS-485 support
  - Hardware flow control (RTS/CTS)
  - 9-bit UART to support address mark with parity
  - MSB/LSB configuration on data
- 2. UART0 and UART1 are clocked from the core clock, the remaining UARTs are clocked on the bus clock. The maximum baud rate is 1/16 of related source clock frequency.



- 3. IrDA is available on all UARTs
- 4. UART0 contains the standard features plus ISO7816
- 5. AMR support on all UARTs. The pin control and interrupts (PORT) module supports open-drain for all I/O.
- 6. UART0 and UART1 contains 8-entry transmit and 8-entry receive FIFOs
- 7. All other UARTs contain a 1-entry transmit and receive FIFOs

## **3.9.4.2 UART wakeup**

The UART can be configured to generate an interrupt/wakeup on the first active edge that it receives.

# 3.9.4.3 UART interrupts

The UART has multiple sources of interrupt requests. However, some of these sources are OR'd together to generate a single interrupt request. See below for the mapping of the individual interrupt sources to the interrupt request:

The status interrupt combines the following interrupt sources:

Source	UART 0	UART 1	UART 2	UART 3	UART 4	UART 5
Transmit data empty	x	х	х	х	х	х
Transmit complete	х	х	х	х	х	x
Idle line	х	х	х	х	х	х
Receive data full	х	х	х	х	х	х
LIN break detect	x	х	х	х	х	х
RxD pin active edge	х	х	х	х	х	x
Initial character detect	х	_	_	_	_	_

The error interrupt combines the following interrupt sources:

Source	UART 0	UART 1	UART 2	UART 3	UART 4	UART 5
Receiver overrun	х	х	х	х	х	х
Noise flag	х	х	х	х	х	х
Framing error	х	х	х	х	х	х



#### **communication interfaces**

Source	UART 0	UART 1	UART 2	UART 3	UART 4	UART 5
Parity error	х	х	х	х	х	х
Transmitter buffer overflow	х	х	х	х	х	х
Receiver buffer underflow	х	х	х	х	х	х
Transmit threshold (ISO7816)	х	_	_	_	_	_
Receiver threshold (ISO7816)	х	_	_	_	_	_
Wait timer (ISO7816)	х	_	_	_	_	_
Character wait timer (ISO7816)	х	_	_	_	_	_
Block wait timer (ISO7816)	х	_	_	_	_	_
Guard time violation (ISO7816)	х	_	_	_	_	_

# 3.9.5 SDHC Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 3-60. SDHC configuration

Table 3-72. Reference links to related information

Topic	Related module	Reference
Full description	SDHC	SDHC
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management



### Table 3-72. Reference links to related information (continued)

Topic	Related module	Reference
Transfers	Crossbar switch	Crossbar switch
Signal Multiplexing	Port control	Signal Multiplexing

# 3.9.5.1 SDHC clocking

In addition to the system clock, the SDHC needs a clock for the base for the external card clock. There are four possible clock sources for this clock, selected by the SIM's SOPT2 register:

- Core/system clock
- MCGPLLCLK or MCGFLLCLK
- EXTAL
- Bypass clock from off-chip (SDHC0\_CLKIN)

# 3.9.5.2 SD bus pullup/pulldown constraints

The SD standard requires the SD bus signals (except the SD clock) to be pulled up during data transfers. The SDHC also provides a feature of detecting card insertion/removal, by detecting voltage level changes on DAT[3] of the SD bus. To support this DAT[3] must be pulled down. To avoid a situation where the SDHC detects voltage changes due to normal data transfers on the SD bus as card insertion/removal, the interrupt relating to this event must be disabled after the card has been inserted and detected. It can be reenabled after the card is removed.

# 3.9.6 I<sup>2</sup>S configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.



# Peripheral bridge Register access Module signals Peripheral bridge Register access

Figure 3-61. I<sup>2</sup>S configuration

Table 3-73. Reference links to related information

Topic	Related module	Reference
Full description	I <sup>2</sup> S	I2S
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management
Signal multiplexing	Port control	Signal Multiplexing

### NOTE

The I2S master clock can be output on the I2S0\_MCLK pin or input on the I2S0\_CLKIN pin. Using the I2S0\_RX\_BCLK pin to output the I2S master clock in synchronous mode is not supported on this device.

# 3.9.6.1 Interrupts

The interrupt outputs from the I<sup>2</sup>S module are OR'd to create a single interrupt to the interrupt control logic.

## 3.9.6.2 DMA requests

The I<sup>2</sup>S module has two DMA requests:

- Transmit FIFO
- Receive FIFO



# 3.9.6.3 I<sup>2</sup>S clock generation

To generate the desired frequencies for the I<sup>2</sup>S module there are multiple clocking options as shown below:

- The core/system clock is routed to an 8-bit fractional divider to generate the I<sup>2</sup>S clock.
- The PLL output is routed to an 8-bit fractional divider to generate the I<sup>2</sup>S clock.
- The EXTAL pin directly drives the I<sup>2</sup>S clock.
- The I2S0\_CLKIN pin directly drives the I<sup>2</sup>S clock.

These options are controlled by the SIM\_SOPT2[I2SSRC] field, and the 8-bit fractional divider is controlled by the SIM\_CLKDIV2[I2SDIV, I2SFRAC] fields. See the SIM module for details.

# 3.9.6.4 I<sup>2</sup>S operation in low power modes

The I<sup>2</sup>S module requires interaction with the rest of the system to move data in or out of the FIFOs. Since the rest of the system is not active in stop, VLPS, and LLS modes, there is no use for the I<sup>2</sup>S in these modes. The I<sup>2</sup>S is powered so that it retains state in these modes, but it is not functional.

In VLPR and VLPW modes, the I<sup>2</sup>S is functional. However, the I<sup>2</sup>S is limited to 400 kHz maximum frequency.

# 3.10 Human-machine interfaces (HMI)

# 3.10.1 GPIO configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.






Figure 3-62. GPIO configuration

Table 3-74. Reference links to related information

Topic	Related module	Reference
Full description	GPIO	GPIO
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management
Transfers	Crossbar switch	Clock Distribution
Signal Multiplexing	Port control	Signal Multiplexing

# 3.10.1.1 GPIO access protection

The GPIO module does not have access protection because it is not connected to a peripheral bridge slot and is not protected by the MPU.

# 3.10.1.2 Number of GPIO signals

The number of GPIO signals available on the devices covered by this document are detailed in Orderable part numbers.

# 3.10.2 TSI Configuration

This section summarizes how the module has been configured in the chip. For a comprehensive description of the module itself, see the module's dedicated chapter.






Figure 3-63. TSI configuration

Table 3-75. Reference links to related information

Topic	Related module	Reference
Full description	TSI	TSI
System memory map		System memory map
Clocking		Clock Distribution
Power management		Power management
Signal Multiplexing	Port control	Signal Multiplexing

# 3.10.2.1 Number of inputs

This device includes one TSI module containing 16 inputs. In low-power modes, one selectable pin is active.

# 3.10.2.2 TSI module functionality in MCU operation modes Table 3-76. TSI module functionality in MCU operation modes

MCU operation mode	TSI clock sources	TSI operation mode when GENCS[TSIEN] is 1	Functional electrode pins	Required GENCS[STPE] state
Run	BUSCLK, MCGIRCLK, OSCERCLK	Active mode	All	Don't care
Wait	BUSCLK, MCGIRCLK, OSCERCLK	Active mode	All	Don't care
Stop	MCGIRCLK, OSCERCLK	Active mode	All	1
VLPR	BUSCLK, MCGIRCLK, OSCERCLK	Active mode	All	Don't care
VLPW	BUSCLK, MCGIRCLK, OSCERCLK	Active mode	All	Don't care



muman-machine interfaces (HMI)

Table 3-76. TSI module functionality in MCU operation modes (continued)

MCU operation mode	TSI clock sources	TSI operation mode when GENCS[TSIEN] is 1	Functional electrode pins	Required GENCS[STPE] state
VLPS	OSCERCLK	Active mode	All	1
LLS	LPOCLK, VLPOSCCLK	Low power mode	Determined by PEN[LPSP]	1
VLLS3	LPOCLK, VLPOSCCLK	Low power mode	Determined by PEN[LPSP]	1
VLLS2	LPOCLK, VLPOSCCLK	Low power mode	Determined by PEN[LPSP]	1
VLLS1	LPOCLK, VLPOSCCLK	Low power mode	Determined by PEN[LPSP]	1

### 3.10.2.3 TSI clocks

This table shows the TSI clocks and the corresponding chip clocks.

Table 3-77. TSI clock connections

Module clock	Chip clock
BUSCLK	Bus clock
MCGIRCLK	MCGIRCLK
OSCERCLK	OSCERCLK
LPOCLK	1 kHz LPO clock
VLPOSCCLK	ERCLK32K

# 3.10.2.4 TSI Interrupts

The TSI has multiple sources of interrupt requests. However, these sources are OR'd together to generate a single interrupt request. When a TSI interrupt occurs, read the TSI status register to determine the exact interrupt source.

# 3.10.2.5 Shield drive signal

The shield drive signal is not supported on this device. Ignore this feature in the TSI chapter.



# **Chapter 4 Memory Map**

# 4.1 Introduction

This device contains various memories and memory-mapped peripherals which are located in one 32-bit contiguous memory space. This chapter describes the memory and peripheral locations within that memory space.

# 4.2 System memory map

The following table shows the high-level device memory map.

Table 4-1. System memory map

System 32-bit Address Range	Destination Slave	Access
0x0000_0000-0x0FFF_FFF	Program flash and read-only data	All masters
	(Includes exception vectors in first 1024 bytes)	
0x1000_0000-0x13FF_FFFF	Reserved	All masters
0x1400_0000-0x17FF_FFFF	Programming acceleration RAM	All masters
0x1800_0000-0x1FFF_FFFF	SRAM_L: Lower SRAM (ICODE/DCODE)	All masters
0x2000_0000-0x200F_FFFF	SRAM_U: Upper SRAM bitband region	All masters
0x2010_0000-0x21FF_FFFF	Reserved	_
0x2200_0000-0x23FF_FFFF	Aliased to SRAM_U bitband	Cortex-M4 core only
0x2400_0000-0x3FFF_FFFF	Reserved	_
0x4000_0000-0x4007_FFFF	Bitband region for peripheral bridge 0 (AIPS-Lite0)	Cortex-M4 core & DMA/EzPort
0x4008_0000-0x400F_EFFF	Bitband region for peripheral bridge 1 (AIPS-Lite1)	Cortex-M4 core & DMA/EzPort
0x400F_F000-0x400F_FFFF	Bitband region for general purpose input/output (GPIO)	Cortex-M4 core & DMA/EzPort



#### **System memory map**

Table 4-1. System memory map (continued)

System 32-bit Address Range	Destination Slave	Access
0x4010_0000-0x41FF_FFFF	Reserved	_
0x4200_0000-0x43FF_FFFF	Aliased to peripheral bridge (AIPS-Lite) and general purpose input/output (GPIO) bitband	Cortex-M4 core only
0x4400_0000-0x5FFF_FFF	Reserved	_
0x6000_0000-0x7FFF_FFF	FlexBus (External Memory - Write-back)	All masters
0x8000_0000-0x9FFF_FFF	FlexBus (External Memory - Write-through)	All masters
0xA000_0000-0xDFFF_FFFF	FlexBus (External Peripheral - Not executable)	All masters
0xE000_0000-0xE00F_FFFF	Private peripherals	Cortex-M4 core only
0xE010_0000-0xFFFF_FFF	Reserved	_

### NOTE

- 1. EzPort master port is statically muxed with DMA master port. Access rights to AIPS-Lite peripheral bridges and general purpose input/output (GPIO) module address space is limited to the core, DMA, and EzPort.
- 2. ARM Cortex-M4 core access privileges also includes accesses via the debug interface.

# 4.2.1 Aliased bit-band regions

The SRAM\_U, AIPS-Lite, and general purpose input/output (GPIO) module resources reside in the Cortex-M4 processor bit-band regions.

The processor also includes two 32 MB aliased bit-band regions associated with the two 1 MB bit-band spaces. Each 32-bit location in the 32 MB space maps to an individual bit in the bit-band region. A 32-bit write in the alias region has the same effect as a read-modify-write operation on the targeted bit in the bit-band region.

Bit 0 of the value written to the alias region determines what value is written to the target bit:

- Writing a value with bit 0 set writes a 1 to the target bit.
- Writing a value with bit 0 clear writes a 0 to the target bit.

A 32-bit read in the alias region returns either:

- a value of 0x0000\_0000 to indicate the target bit is clear
- a value of 0x0000\_0001 to indicate the target bit is set






Figure 4-1. Alias bit-band mapping

### NOTE

Each bit in bit-band region has an equivalent bit that can be manipulated through bit 0 in a corresponding long word in the alias bit-band region.

# 4.3 Flash Memory Map

The various flash memories and the flash registers are located at different base addresses as shown in the following figure. The base address for each is specified in System memory map.




Figure 4-2. Flash memory map

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# 4.3.1 Alternate Non-Volatile IRC User Trim Description

The following non-volatile locations (4 bytes) are reserved for custom IRC user trim supported by some development tools. An alternate IRC trim to the factory loaded trim can be stored at this location. To override the factory trim, user software must load new values into the MCG trim registers.

Non-Volatile Byte Address	Alternate IRC Trim Value	
0x0000_03FC	Reserved	
0x0000_03FD	Reserved	
0x0000_03FE (bit 0)	SCFTRIM	
0x0000_03FE (bit 4:1)	FCTRIM	
0x0000_03FF	SCTRIM	

# 4.4 SRAM memory map

The on-chip RAM is split evenly among SRAM\_L and SRAM\_U. The RAM is also implemented such that the SRAM\_L and SRAM\_U ranges form a contiguous block in the memory map. See SRAM Arrays for details.

Accesses to the SRAM\_L and SRAM\_U memory ranges outside the amount of RAM on the device causes the bus cycle to be terminated with an error followed by the appropriate response in the requesting bus master.

# 4.5 Peripheral bridge (AIPS-Lite0 and AIPS-Lite1) memory maps

The peripheral memory map is accessible via two slave ports on the crossbar switch in the 0x4000\_0000-0x400F\_FFFF region. The device implements two peripheral bridges (AIPS-Lite 0 and 1):

- AIPS-Lite0 covers 512 KB
- AIPS-Lite1 covers 508 KB with 4 KB assigned to the general purpose input/output module (GPIO)

AIPS-Lite0 is connected to crossbar switch slave port 2, and is accessible at locations 0x4000\_0000-0x4007\_FFFF.



AIPS-Lite1 and the general purpose input/output module share the connection to crossbar switch slave port 3. The AIPS-Lite1 is accessible at locations 0x4008\_0000— 0x400F\_EFFF. The general purpose input/output module is accessible in a 4-kbyte region at 0x400F\_F000—0x400F\_FFFF. Its direct connection to the crossbar switch provides master access without incurring wait states associated with accesses via the AIPS-Lite controllers.

Modules that are disabled via their clock gate control bits in the SIM registers disable the associated AIPS slots. Access to any address within an unimplemented or disabled peripheral bridge slot results in a transfer error termination.

For programming model accesses via the peripheral bridges, there is generally only a small range within the 4 KB slots that is implemented. Accessing an address that is not implemented in the peripheral results in a transfer error termination.

# 4.5.1 Peripheral Bridge 0 (AIPS-Lite 0) Memory Map

Table 4-2. Peripheral bridge 0 slot assignments

System 32-bit base address	Slot number	Module
0x4000_0000	0	Peripheral bridge 0 (AIPS-Lite 0)
0x4000_1000	1	_
0x4000_2000	2	_
0x4000_3000	3	_
0x4000_4000	4	Crossbar switch
0x4000_5000	5	_
0x4000_6000	6	_
0x4000_7000	7	_
0x4000_8000	8	DMA controller
0x4000_9000	9	DMA controller transfer control descriptors
0x4000_A000	10	_
0x4000_B000	11	_
0x4000_C000	12	FlexBus
0x4000_D000	13	MPU
0x4000_E000	14	_
0x4000_F000	15	_
0x4001_0000	16	_
0x4001_1000	17	_
0x4001_2000	18	_



reripheral bridge (AIPS-Lite0 and AIPS-Lite1) memory maps

Table 4-2. Peripheral bridge 0 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x4001_3000	19	_
0x4001_4000	20	_
0x4001_5000	21	_
0x4001_6000	22	_
0x4001_7000	23	_
0x4001_8000	24	_
0x4001_9000	25	_
0x4001_A000	26	_
0x4001_B000	27	_
0x4001_C000	28	_
0x4001_D000	29	_
0x4001_E000	30	_
0x4001_F000	31	Flash memory controller
0x4002_0000	32	Flash memory
0x4002_1000	33	DMA channel mutiplexer 0
0x4002_2000	34	_
0x4002_3000	35	_
0x4002_4000	36	_
0x4002_5000	37	_
0x4002_6000	38	_
0x4002_7000	39	_
0x4002_8000	40	_
0x4002_9000	41	_
0x4002_A000	42	_
0x4002_B000	43	_
0x4002_C000	44	SPI 0
0x4002_D000	45	SPI 1
0x4002_E000	46	_
0x4002_F000	47	12S 0
0x4003_0000	48	_
0x4003_1000	49	_
0x4003_2000	50	CRC
0x4003_3000	51	_
0x4003_4000	52	_



Table 4-2. Peripheral bridge 0 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x4003_5000	53	USB DCD
0x4003_6000	54	Programmable delay block (PDB)
0x4003_7000	55	Periodic interrupt timers (PIT)
0x4003_8000	56	FlexTimer (FTM) 0
0x4003_9000	57	FlexTimer (FTM) 1
0x4003_A000	58	_
0x4003_B000	59	Analog-to-digital converter (ADC) 0
0x4003_C000	60	_
0x4003_D000	61	Real-time clock (RTC)
0x4003_E000	62	VBAT register file
0x4003_F000	63	_
0x4004_0000	64	Low-power timer (LPTMR)
0x4004_1000	65	System register file
0x4004_2000	66	_
0x4004_3000	67	_
0x4004_4000	68	_
0x4004_5000	69	Touch sense interface (TSI)
0x4004_6000	70	_
0x4004_7000	71	SIM low-power logic
0x4004_8000	72	System integration module (SIM)
0x4004_9000	73	Port A multiplexing control
0x4004_A000	74	Port B multiplexing control
0x4004_B000	75	Port C multiplexing control
0x4004_C000	76	Port D multiplexing control
0x4004_D000	77	Port E multiplexing control
0x4004_E000	78	_
0x4004_F000	79	
0x4005_0000	80	
0x4005_1000	81	
0x4005_2000	82	Software watchdog
0x4005_3000	83	_
0x4005_4000	84	_
0x4005_5000	85	_
0x4005_6000	86	_



reripheral bridge (AIPS-Lite0 and AIPS-Lite1) memory maps

Table 4-2. Peripheral bridge 0 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x4005_7000	87	_
0x4005_8000	88	_
0x4005_9000	89	_
0x4005_A000	90	_
0x4005_B000	91	_
0x4005_C000	92	_
0x4005_D000	93	_
0x4005_E000	94	_
0x4005_F000	95	_
0x4006_0000	96	_
0x4006_1000	97	External watchdog
0x4006_2000	98	Carrier modulator timer (CMT)
0x4006_3000	99	_
0x4006_4000	100	Multi-purpose Clock Generator (MCG)
0x4006_5000	101	System oscillator (OSC)
0x4006_6000	102	I <sup>2</sup> C 0
0x4006_7000	103	I <sup>2</sup> C 1
0x4006_8000	104	
0x4006_9000	105	_
0x4006_A000	106	UART 0
0x4006_B000	107	UART 1
0x4006_C000	108	UART 2
0x4006_D000	109	UART 3
0x4006_E000	110	_
0x4006_F000	111	_
0x4007_0000	112	_
0x4007_1000	113	_
0x4007_2000	114	USB OTG FS/LS
0x4007_3000	115	Analog comparator (CMP) / 6-bit digital-to-analog converter (DAC)
0x4007_4000	116	Voltage reference (VREF)
0x4007_5000	117	_
0x4007_6000	118	
0x4007_7000	119	
0x4007_8000	120	



Table 4-2. Peripheral bridge 0 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x4007_9000	121	_
0x4007_A000	122	_
0x4007_B000	123	_
0x4007_C000	124	Low-leakage wakeup unit (LLWU)
0x4007_D000	125	Power management controller (PMC)
0x4007_E000	126	System Mode controller (SMC)
0x4007_F000	127	_

# 4.5.2 Peripheral Bridge 1 (AIPS-Lite 1) Memory Map

Table 4-3. Peripheral bridge 1 slot assignments

System 32-bit base address	Slot number	Module
0x4008_0000	0	Peripheral bridge 1 (AIPS-Lite 1)
0x4008_1000	1	_
0x4008_2000	2	_
0x4008_3000	3	_
0x4008_4000	4	_
0x4008_5000	5	_
0x4008_6000	6	_
0x4008_7000	7	_
0x4008_8000	8	_
0x4008_9000	9	_
0x4008_A000	10	_
0x4008_B000	11	_
0x4008_C000	12	_
0x4008_D000	13	_
0x4008_E000	14	_
0x4008_F000	15	_
0x4009_0000	16	_
0x4009_1000	17	_
0x4009_2000	18	_
0x4009_3000	19	_
0x4009_4000	20	_



reripheral bridge (AIPS-Lite0 and AIPS-Lite1) memory maps

Table 4-3. Peripheral bridge 1 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x4009_5000	21	_
0x4009_6000	22	_
0x4009_7000	23	_
0x4009_8000	24	_
0x4009_9000	25	_
0x4009_A000	26	_
0x4009_B000	27	_
0x4009_C000	28	_
0x4009_D000	29	_
0x4009_E000	30	_
0x4009_F000	31	_
0x400A_0000	32	_
0x400A_1000	33	_
0x400A_2000	34	_
0x400A_3000	35	_
0x400A_4000	36	_
0x400A_5000	37	_
0x400A_6000	38	_
0x400A_7000	39	_
0x400A_8000	40	_
0x400A_9000	41	_
0x400A_A000	42	_
0x400A_B000	43	_
0x400A_C000	44	SPI 2
0x400A_D000	45	_
0x400A_E000	46	_
0x400A_F000	47	_
0x400B_0000	48	_
0x400B_1000	49	SDHC
0x400B_2000	50	_
0x400B_3000	51	_
0x400B_4000	52	_
0x400B_5000	53	_
0x400B_6000	54	_



Table 4-3. Peripheral bridge 1 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x400B_7000	55	_
0x400B_8000	56	FlexTimer (FTM) 2
0x400B_9000	57	_
0x400B_A000	58	_
0x400B_B000	59	Analog-to-digital converter (ADC) 1
0x400B_C000	60	_
0x400B_D000	61	
0x400B_E000	62	_
0x400B_F000	63	
0x400C_0000	64	
0x400C_1000	65	_
0x400C_2000	66	
0x400C_3000	67	_
0x400C_4000	68	_
0x400C_5000	69	
0x400C_6000	70	
0x400C_7000	71	_
0x400C_8000	72	_
0x400C_9000	73	_
0x400C_A000	74	_
0x400C_B000	75	_
0x400C_C000	76	12-bit digital-to-analog converter (DAC) 0
0x400C_D000	77	12-bit digital-to-analog converter (DAC) 1
0x400C_E000	78	_
0x400C_F000	79	_
0x400D_0000	80	_
0x400D_1000	81	_
0x400D_2000	82	_
0x400D_3000	83	_
0x400D_4000	84	_
0x400D_5000	85	_
0x400D_6000	86	_
0x400D_7000	87	_
0x400D_8000	88	_



reripheral bridge (AIPS-Lite0 and AIPS-Lite1) memory maps

Table 4-3. Peripheral bridge 1 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x400D_9000	89	_
0x400D_A000	90	_
0x400D_B000	91	_
0x400D_C000	92	_
0x400D_D000	93	_
0x400D_E000	94	_
0x400D_F000	95	_
0x400E_0000	96	_
0x400E_1000	97	_
0x400E_2000	98	_
0x400E_3000	99	_
0x400E_4000	100	_
0x400E_5000	101	_
0x400E_6000	102	_
0x400E_7000	103	_
0x400E_8000	104	_
0x400E_9000	105	_
0x400E_A000	106	UART 4
0x400E_B000	107	UART 5
0x400E_C000	108	_
0x400E_D000	109	_
0x400E_E000	110	_
0x400E_F000	111	_
0x400F_0000	112	_
0x400F_1000	113	_
0x400F_2000	114	_
0x400F_3000	115	_
0x400F_4000	116	
0x400F_5000	117	Subslot A: Op-amp 0
0x400F_5800		Subslot B: Op-amp 1
0x400F_6000	118	
0x400F_7000	119	
0x400F_8000	120	Subslot a: TRIAMP 0
0x400F_8800		Subslot b: TRIAMP 1



Table 4-3. Peripheral bridge 1 slot assignments (continued)

System 32-bit base address	Slot number	Module
0x400F_9000	121	_
0x400F_A000	122	_
0x400F_B000	123	_
0x400F_C000	124	_
0x400F_D000	125	_
0x400F_E000	126	_
0x400F_F000		6-Lite slot. The 32-bit general purpose input/output module that shares the vitch slave port with the AIPS-Lite is accessed at this address.

# 4.6 Private Peripheral Bus (PPB) memory map

The PPB is part of the defined ARM bus architecture and provides access to select processor-local modules. These resources are only accessible from the core; other system masters do not have access to them.

Table 4-4. PPB memory map

System 32-bit Address Range	Resource
0xE000_0000-0xE000_0FFF	Instrumentation Trace Macrocell (ITM)
0xE000_1000-0xE000_1FFF	Data Watchpoint and Trace (DWT)
0xE000_2000-0xE000_2FFF	Flash Patch and Breakpoint (FPB)
0xE000_3000-0xE000_DFFF	Reserved
0xE000_E000-0xE000_EFFF	System Control Space (SCS) (for NVIC)
0xE000_F000-0xE003_FFFF	Reserved
0xE004_0000-0xE004_0FFF	Trace Port Interface Unit (TPIU)
0xE004_1000-0xE004_1FFF	Embedded Trace Macrocell (ETM)
0xE004_2000-0xE004_2FFF	Embedded Trace Buffer (ETB)
0xE004_3000-0xE004_3FFF	Embedded Trace Funnel
0xE004_4000-0xE007_FFFF	Reserved
0xE008_0000-0xE008_0FFF	Miscellaneous Control Module (MCM)(including ETB Almost Full)
0xE008_1000-0xE008_1FFF	Reserved
0xE008_2000-0xE00F_EFFF	Reserved
0xE00F_F000-0xE00F_FFFF	ROM Table - allows auto-detection of debug components



rrivate Peripheral Bus (PPB) memory map



# Chapter 5 Clock Distribution

### 5.1 Introduction

The MCG module controls which clock source is used to derive the system clocks. The clock generation logic divides the selected clock source into a variety of clock domains, including the clocks for the system bus masters, system bus slaves, and flash memory. The clock generation logic also implements module-specific clock gating to allow granular shutoff of modules.

The primary clocks for the system are generated from the MCGOUTCLK clock. The clock generation circuitry provides several clock dividers that allow different portions of the device to be clocked at different frequencies. This allows for trade-offs between performance and power dissipation.

Various modules, such as the USB OTG Controller, have module-specific clocks that can be generated from the MCGPLLCLK or MCGFLLCLK clock. In addition, there are various other module-specific clocks that have other alternate sources. Clock selection for most modules is controlled by the SOPT registers in the SIM module.

# 5.2 Programming model

The selection and multiplexing of system clock sources is controlled and programmed via the MCG module. The setting of clock dividers and module clock gating for the system are programmed via the SIM module. Reference those sections for detailed register and bit descriptions.


# 5.3 High-Level device clocking diagram

The following system oscillator, MCG, and SIM module registers control the multiplexers, dividers, and clock gates shown in the below figure:



### Ciock definitions

	OSC	MCG	SIM
Multiplexers	MCG_Cx	MCG_Cx	SIM_SOPT1, SIM_SOPT2
Dividers	_	MCG_Cx	SIM_CLKDIVx
Clock gates	OSC_CR	MCG_C1	SIM_SCGCx



Note: See subsequent sections for details on where these clocks are used.

Figure 5-1. Clocking diagram

## 5.4 Clock definitions

The following table describes the clocks in the previous block diagram.

Clock name	Description
Core clock	MCGOUTCLK divided by OUTDIV1 clocks the ARM Cortex-M4 core
System clock	MCGOUTCLK divided by OUTDIV1 clocks the crossbar switch and bus masters directly connected to the crossbar. In addition, this clock is used for UART0 and UART1.



Clock name	Description	
Bus clock	MCGOUTCLK divided by OUTDIV2 clocks the bus slaves and peripheral (excluding memories)	
FlexBus clock	MCGOUTCLK divided by OUTDIV3 clocks the external FlexBus interface	
Flash clock	MCGOUTCLK divided by OUTDIV4 clocks the flash memory	
MCGIRCLK	MCG output of the slow or fast internal reference clock	
MCGFFCLK	MCG output of the slow internal reference clock or a divided MCG external reference clock. The MCGFFCLK is further divided by 2 before being made available to modules outside the MCG (as shown in the preceding figure).	
MCGOUTCLK	MCG output of either IRC, MCGFLLCLK, MCGPLLCLK, or MCG's external reference clock that sources the core, system, bus, FlexBus, and flash clock. It is also an option for the debug trace clock.	
MCGFLLCLK	MCG output of the FLL. MCGFLLCLK or MCGPLLCLK maclock some modules.	
MCGPLLCLK	MCG output of the PLL. MCGFLLCLK or MCGPLLCLK may clock some modules.	
MCG external reference clock	Input clock to the MCG sourced by the system oscillator (OSCCLK) or RTC oscillator	
OSCCLK	System oscillator output of the internal oscillator or sourced directly from EXTAL	
OSCERCLK	System oscillator output sourced from OSCCLKthat may clock some on-chip modules	
OSC32KCLK	System oscillator 32kHz output	
ERCLK32K	Clock source for some modules that is chosen as OSC32KCLK or the RTC clock	
RTC clock	RTC oscillator output for the RTC module	
LPO	PMC 1kHz output	

# 5.4.1 Device clock summary

The following table provides more information regarding the on-chip clocks.

Table 5-1. Clock Summary

Clock name	Run mode	VLPR mode	Clock source	Clock is disabled
	clock frequency	clock frequency		when
MCGOUTCLK	Up to 100 MHz	Up to 2 MHz	MCG	In all stop modes
Core clock	Up to 100 MHz	Up to 2 MHz	MCGOUTCLK clock divider	In all wait and stop modes
System clock	Up to 100 MHz	Up to 2 MHz	MCGOUTCLK clock divider	In all stop modes
Bus clock	Up to 50 MHz	Up to 2 MHz	MCGOUTCLK clock divider	In all stop modes



### CIOCK definitions

Table 5-1. Clock Summary (continued)

Clock name	Run mode	VLPR mode	Clock source	Clock is disabled
	clock frequency	clock frequency		when
FlexBus clock	Up to 50 MHz	Up to 2 MHz	MCGOUTCLK clock	In all stop modes or
(FB_CLK)			divider	FlexBus disabled
Flash clock	Up to 25 MHz	Up to 1 MHz	MCGOUTCLK clock divider	In all stop modes
Internal reference (MCGIRCLK)	30-40 kHz or 2 MHz	2 MHz only	MCG	MCG_C1[IRCLKEN] cleared,
(				Stop mode and MCG_C1[IREFSTEN] cleared, or
				VLPS/LLS/VLLS mode
External reference	Up to 50 MHz	Up to 4 MHz (bypass),	System OSC	System OSC's
(OSCERCLK)	(bypass), 30-40 kHz, or	30-40 kHz (low-range crystal) or		OSC_CR[ERCLKEN] cleared, or
	4-32 MHz (crystal)	Up to 4 MHz (high-range crystal)		Stop mode and OSC_CR[EREFSTEN] cleared
External reference 32kHz (ERCLK32K)	30-40 kHz	30-40 kHz	System OSC or RTC OSC depending on SIM_SOPT1[OSC32K	System OSC's OSC_CR[ERCLKEN] cleared or
(ENOLKSZK)			SEL]	RTC's RTC_CR[OSCE] cleared
RTC_CLKOUT	1 Hz	1 Hz	RTC clock	Clock is disabled in LLS and VLLSx modes
LPO	1 kHz	1 kHz	PMC	Available in all power modes
USB FS clock	48 MHz	N/A	MCGPLLCLK or MCGFLLCLK with fractional clock divider, or USB_CLKIN	USB FS OTG is disabled
I2S master clock	Up to 50 MHz	N/A	System clock, MCGPLLCLK, or MCGFLLCLK with fractional clock divider, OSCERCLK, or	I <sup>2</sup> S is disabled
			I2S_CLKIN	
SDHC clock	Up to 50 MHz	N/A	System clock, MCGPLLCLK/	SDHC is disabled
			MCGFLLCLK, or	
			OSCERCLK	
TRACE clock	Up to 100 MHz	Up to 2 MHz	System clock or	Trace is disabled
			MCGOUTCLK	



# 5.5 Internal clocking requirements

The clock dividers are programmed via the SIM module's CLKDIV registers. Each divider is programmable from a divide-by-1 through divide-by-16 setting. The following requirements must be met when configuring the clocks for this device:

- 1. The core and system clock frequencies must be 100 MHz or slower.
- 2. The bus clock frequency must be programmed to 50 MHz or less and an integer divide of the core clock.
- 3. The flash clock frequency must be programmed to 25 MHz or less and an integer divide of the bus clock.
- 4. The FlexBus clock frequency must be programmed to be less than or equal to the bus clock frequency.

The following are a few of the more common clock configurations for this device:

# Option 1:

Clock	Frequency
Core clock	50 MHz
System clock	50 MHz
Bus clock	50 MHz
FlexBus clock	50 MHz
Flash clock	25 MHz

### Option 2:

Clock	Frequency
Core clock	100 MHz
System clock	100 MHz
Bus clock	50 MHz
FlexBus clock	25 MHz
Flash clock	25 MHz

# Option 3:

Clock	Frequency
Core clock	96 MHz
System clock	96 MHz
Bus clock	48 MHz
FlexBus clock	48 MHz
Flash clock	24 MHz



### 5.5.1 Clock divider values after reset

Each clock divider is programmed via the SIM module's CLKDIV*n* registers. The flash memory's FTFL\_FOPT[LPBOOT] bit controls the reset value of the core clock, system clock, bus clock, and flash clock dividers as shown below:

FTFL_FOPT [LPBOOT]	Core/system clock	Bus clock	FlexBus clock	Flash clock	Description
0	0x7 (divide by 8)	0x7 (divide by 8)	0xF (divide by 16)	0xF (divide by 16)	Low power boot
1	0x0 (divide by 1)	0x0 (divide by 1)	0x1 (divide by 2)	0x1 (divide by 2)	Fast clock boot

This gives the user flexibility for a lower frequency, low-power boot option. The flash erased state defaults to fast clocking mode, since where the low power boot (FTFL\_FOPT[LPBOOT]) bit resides in flash is logic 1 in the flash erased state.

To enable the low power boot option program FTFL\_FOPT[LPBOOT] to zero. During the reset sequence, if LPBOOT is cleared, the system is in a slow clock configuration. Upon any system reset, the clock dividers return to this configurable reset state.

# 5.5.2 VLPR mode clocking

The clock dividers cannot be changed while in VLPR mode. They must be programmed prior to entering VLPR mode to guarantee:

- the core/system, FlexBus, and bus clocks are less than or equal to 2 MHz, and
- the flash memory clock is less than or equal to 1 MHz

# 5.6 Clock Gating

The clock to each module can be individually gated on and off using the SIM module's SCGCx registers. These bits are cleared after any reset, which disables the clock to the corresponding module to conserve power. Prior to initializing a module, set the corresponding bit in SCGCx register to enable the clock. Before turning off the clock, make sure to disable the module.

Any bus access to a peripheral that has its clock disabled generates an error termination.



# 5.7 Module clocks

The following table summarizes the clocks associated with each module.

Table 5-2. Module clocks

Module	Bus interface clock	Internal clocks	I/O interface clocks			
	Core modules					
ARM Cortex-M4 core	System clock	Core clock	_			
NVIC	System clock	_	_			
DAP	System clock	_	_			
ITM	System clock	_	-			
ETM	System clock	TRACE clock	TRACE_CLKOUT			
ETB	System clock	_	_			
cJTAG, JTAGC	_	_	JTAG_CLK			
	System	modules				
DMA	System clock	_	_			
DMA Mux	Bus clock	_	_			
Port control	Bus clock	LPO	_			
Crossbar Switch	System clock	_	_			
Peripheral bridges	System clock	Bus clock	_			
MPU	System clock	_	_			
LLWU, PMC, SIM	Bus clock	LPO	_			
Mode controller	Bus clock	_	_			
MCM	System clock	_	_			
EWM	Bus clock	LPO	_			
Watchdog timer	Bus clock	LPO	_			
	CI	ocks				
MCG	Bus clock	MCGOUTCLK, MCGPLLCLK, MCGFLLCLK, MCGIRCLK, OSCERCLK	_			
OSC	Bus clock	OSCERCLK	_			
Memory and memory interfaces						
Flash Controller	System clock	Flash clock	_			
Flash memory	Flash clock	_	-			
FlexBus	System clock	_	FB_CLKOUT			
EzPort	System clock	_	EZP_CLK			
	Security					



### woule clocks

Table 5-2. Module clocks (continued)

Module	Bus interface clock	Internal clocks	I/O interface clocks		
CRC	Bus clock	_	_		
	An	alog			
ADC	Bus clock	OSCERCLK	_		
CMP	Bus clock	-	_		
DAC	Bus clock	-	_		
VREF	Bus clock	-	_		
Op-Amp	Bus clock	-	_		
TRIAMP	Bus clock	-	_		
	Tin	ners			
PDB	Bus clock	_	_		
FlexTimers	Bus clock	MCGFFCLK	FTM_CLKINx		
PIT	Bus clock	_	_		
LPTMR	Bus clock	LPO, OSCERCLK, MCGIRCLK, ERCLK32K	-		
CMT	Bus clock	_	_		
RTC	Bus clock	EXTAL32	_		
	Communicat	ion interfaces			
USB FS OTG	System clock	USB FS clock	_		
USB DCD	Bus clock	_	_		
DSPI	Bus clock	_	DSPI_SCK		
I <sup>2</sup> C	Bus clock	_	I2C_SCL		
UARTO, UART1	System clock	_	_		
UART2-5	Bus clock	_	_		
SDHC	System clock	SDHC clock	SDHC_DCLK		
I <sup>2</sup> S	Bus clock	I <sup>2</sup> S master clock	I2S_TX_BCLK, I2S_RX_BCLK		
	Human-machine interfaces				
GPIO	System clock	_			
TSI	Bus clock	LPO, ERCLK32K, MCGIRCLK	_		

# 5.7.1 PMC 1-kHz LPO clock

The Power Management Controller (PMC) generates a 1-kHz clock that is enabled in all modes of operation, including all low power modes. This 1-kHz source is commonly referred to as LPO clock or 1-kHz LPO clock.



# 5.7.2 WDOG clocking

The WDOG may be clocked from two clock sources as shown in the following figure.




Figure 5-2. WDOG clock generation

# 5.7.3 Debug trace clock

The debug trace clock source can be clocked as shown in the following figure.




Figure 5-3. Trace clock generation

### NOTE

The trace clock frequency observed at the TRACE\_CLKOUT pin will be half that of the selected clock source.

# 5.7.4 PORT digital filter clocking

The digital filters in each of the PORT*x* modules can be clocked as shown in the following figure.



### **NOTE**

In stop mode, the digital input filters are bypassed unless they are configured to run from the 1 kHz LPO clock source.




Figure 5-4. PORTx digital input filter clock generation

# 5.7.5 LPTMR clocking

The prescaler and glitch filters in each of the LPTMRx modules can be clocked as shown in the following figure.

### NOTE

The chosen clock must remain enabled if the LPTMRx is to continue operating in all required low-power modes.




Figure 5-5. LPTMRx prescaler/glitch filter clock generation

# 5.7.6 USB FS OTG Controller clocking

The USB FS OTG controller is a bus master attached to the crossbar switch. As such, its clock is connected to the system clock.



### NOTE

For the USB FS OTG controller to operate, the minimum system clock frequency is 20 MHz.

The USB OTG controller also requires a 48 MHz clock. The clock source options are shown below.




Figure 5-6. USB 48 MHz clock source

### NOTE

The MCGFLLCLK does not meet the USB jitter specifications for certification.

# 5.7.7 UART clocking

UART0 and UART1 modules operate from the core/system clock, which provides higher performance level for these modules. All other UART modules operate from the bus clock.

# 5.7.8 SDHC clocking

The SDHC module has four possible clock sources for the external clock source, as shown in the following figure.



woule clocks




Figure 5-7. SDHC clock generation

# 5.7.9 I<sup>2</sup>S clocking

In addition to the bus clock, the I<sup>2</sup>S has a clock source for master clock generation. The maximum frequency of this clock is 50 MHz. The master clock source can be derived from several sources, as shown in the following figure.




Figure 5-8. I<sup>2</sup>S baud clock generation

# 5.7.10 TSI clocking

In active mode, the TSI can be clocked as shown in the following figure.






Figure 5-9. TSI clock generation

In low-power mode, the TSI can be clocked as shown in the following figure.

### **NOTE**

In the TSI chapter, these two clocks are referred to as LPOCLK and VLPOSCCLK.




Figure 5-10. TSI low-power clock generation



woule clocks



# Chapter 6 Reset and Boot

#### 6.1 Introduction

The following reset sources are supported in this MCU:

Table 6-1. Reset sources

Reset sources	Description
POR reset	Power-on reset (POR)
System resets	External pin reset (PIN)     Low-voltage detect (LVD)     Computer operating properly (COP) watchdog reset     Low leakage wakeup (LLWU) reset     Multipurpose clock generator loss of clock (LOC) reset     Software reset (SW)     Lockup reset (LOCKUP)     EzPort reset     MDM DAP system reset
Debug reset	<ul><li>JTAG reset</li><li>nTRST reset</li></ul>

Each of the system reset sources, with the exception of the EzPort and MDM-AP reset, has an associated bit in the system reset status registers (SRSH and SRSL). See the Mode controller for more details.

The MCU exits reset in functional mode that is controlled by EZP\_CS pin to select between the single chip (default) or serial flash programming (EzPort) modes. See Boot options for more details.

## 6.2 Reset

This section discusses basic reset mechanisms and sources. Some modules that cause resets can be configured to cause interrupts instead. Consult the individual peripheral chapters for more information.



# 6.2.1 Power-on reset (POR)

When power is initially applied to the MCU or when the supply voltage drops below the power-on reset re-arm voltage level ( $V_{POR}$ ), the POR circuit causes a POR reset condition.

As the supply voltage rises, the LVD circuit holds the MCU in reset until the supply has risen above the LVD low threshold ( $V_{LVDL}$ ). The POR and LVD bits in SRSL register are set following a POR.

# 6.2.2 System resets

Resetting the MCU provides a way to start processing from a known set of initial conditions. System reset begins with the on-chip regulator in full regulation and system clocking generation from an internal reference. When the processor exits reset, it performs the following:

- Reads the start SP (SP\_main) from vector-table offset 0
- Reads the start PC from vector-table offset 4
- LR is set to 0xFFFF\_FFFF

The on-chip peripheral modules are disabled and the non-analog I/O pins are initially configured as disabled. The pins with analog functions assigned to them default to their analog function after reset.

During and following a reset, the JTAG pins have their associated input pins configured as:

- TDI in pull-up (PU)
- TCK in pull-down (PD)
- TMS in PU

and associated output pin configured as:

• TDO with no pull-down or pull-up

Note that the nTRST signal is initially configured as disabled, however once configured to its JTAG functionality its associated input pin is configured as:

• nTRST in PU



## 6.2.2.1 External pin reset (PIN)

On this device,  $\overline{RESET}$  is a dedicated pin. This pin is open drain and has an internal pullup device. Asserting  $\overline{RESET}$  wakes the device from any mode. During a pin reset, the SRSL[PIN] bit is set.

#### 6.2.2.1.1 Reset pin filter

The RESET pin supports digital filtering in all modes of operation. For LLS and VLLSx modes, the LLWU provides an optional fixed digital filter running off the 1 kHz LPO clock. See the LLWU chapter for operation of this filter. During non-low leakage operation, there are two clock options for the RESET pin filter – the 1kHz LPO clock and the bus clock.

This RESET pin filter implemented in SIM logic includes a separate filter for each clock source. In Stop and VLPS operation this logic either switches to bypass operation or has continued filtering operation depending on the filtering mode selected.

There are several modes defined – See the SOPT6 register description in module for more details. SOPT6[RSTFLTEN[2:0]] and SOPT6[RSTFLTSEL[4:0]] fields control the desired functionality. Both filters are reset on POR, LVD, and wakeup from VLLS. The reset value for each filter defaults to off (non-detect).

The LPO filter is simple with a fixed filter value count of 3. There is also a synchronizer on the input signal that results in an associated latency (2 cycles). As such, it takes 5 cycles to complete a transition from low-to-high or high-to-low. The LPO Filter initializes to off (logic 1) when the LPO filter is not enabled.

The Bus Filter initializes to off (logic 1) when the Bus Filter not enabled. When the Bus Filter is enabled, the number of counts is controlled by SOPT6[RSTFLTSEL[4:0]].

## 6.2.2.2 Low-voltage detect (LVD) reset

This device includes a system to protect against low voltage conditions to protect memory contents and control MCU system states during supply voltage variations. The system is comprised of a power-on reset (POR) circuit and a low-voltage detect (LVD) circuit with a user-selectable trip voltage, either high ( $V_{LVDH}$ ) or low ( $V_{LVDL}$ ). The trip voltage is selected by the LVDSC1[LVDV] bits. The LVD system is always enabled in normal run, wait, and stop modes. The LVD system is disabled in VLPx, LLSx, and VLLSx modes. Refer to Power Management Controller (PMC) chapter for more details.



neset

The LVD can be configured to generate a reset upon detection of a low voltage condition by setting LVDSC1[LVDRE]. After an LVD reset has occurred, the LVD system holds the MCU in reset until the supply voltage rises above the low voltage detection threshold.

The SRSL[LVD] bit is set following an LVD reset or POR.

## 6.2.2.3 Computer operating properly (COP) watchdog reset

The watchdog timer monitors the operation of the system by expecting periodic communication from the software, generally known as servicing (or refreshing) the watchdog. If this periodic refreshing does not occur, the watchdog issues a system reset. The COP reset causes the SRSL[COP] bit to set.

# 6.2.2.4 Low leakage wakeup (LLWU) reset

The LLWU allows up to 16 external pins, the RESET pin, and up to seven internal peripherals to wake the MCU from LLS and VLLSx power modes. The LLWU module is only functional in LLS and VLLSx power modes. In both these modes, LLS mode exits via RESET pin and any VLLS mode exits via a wakeup or reset event, the SRSL[WAKEUP] bit in mode controller module is set indicating the low leakage mode was active prior to the last system reset flow. Using the RESET pin to trigger an exit from LLS or VLLS results in the SRSL[PIN] bit being set as well. Refer to the mode controller chapter for more details.

After a system reset, the LLWU retains the flags to indicate the source of the last wakeup until the user clears them.

#### NOTE

Pin wakeup and error condition flags are cleared in the LLWU and module wakeup flags are required to be cleared in the peripheral module. Refer to the individual peripheral specifications for more information.

## 6.2.2.5 Multipurpose clock generator loss-of-clock (LOC) reset

The MCG includes a clock monitor. The clock monitor resets the device when the following conditions are met:

- The clock monitor is enabled (MCG\_C6[CME] = 1)
- The MCG's external reference clock falls outside of the expected frequency range, depending on the MCG\_C2[RANGE] bit



The MC\_SRSL[LOC] bit is set to indicate the error.

## 6.2.2.6 Software reset (SW)

The SYSRESETREQ bit in the NVIC application interrupt and reset control register can be set to force a software reset on the device. (See ARM's NVIC documentation for the full description of the register fields, especially the VECTKEY field requirements.) Setting SYSRESETREQ generates a software reset request. This reset forces a system reset of all major components except for the debug module. A software reset causes SRSH[SW] bit to set.

## 6.2.2.7 Lockup reset (LOCKUP)

The LOCKUP gives immediate indication of seriously errant kernel software. This is the result of the core being locked because of an unrecoverable exception following the activation of the processor's built in system state protection hardware.

The LOCKUP condition causes a system reset and also causes SRSH[LOCKUP] bit to set.

#### 6.2.2.8 EzPort reset

The EzPort supports a system reset request via EzPort signalling. The EzPort generates a system reset request following execution of a Reset Chip (RESET) command via the EzPort interface. This method of reset allows the chip to boot from flash memory after it has been programmed by an external source. The EzPort is enabled or disabled by the EZP\_CS pin.

## 6.2.2.9 MDM-AP system reset request

Set the system reset request bit in the MDM-AP control register to initiate a system reset. This is the primary method for resets via the JTAG interface. The system reset is held until this bit is cleared.

Set the core hold reset bit in the MDM-AP control register to hold the core in reset as the rest of the chip comes out of system reset.



neset

# 6.2.3 Debug resets

The following sections detail the debug resets available on the device.

#### **6.2.3.1 JTAG reset**

The JTAG module generate a system reset when certain IR codes are selected. This functional reset is asserted when EzPort, EXTEST, HIGHZ and CLAMP instructions are active. The reset source from the JTAG module is released when any other IR code is selected. A JTAG reset causes the SRSH[JTAG] bit to set.

#### 6.2.3.2 nTRST reset

The nTRST pin causes a reset of the JTAG logic when asserted. Asserting the nTRST pin allows the debugger to gain control of the TAP controller state machine (after exiting LLS or VLLSx) without resetting the state of the debug modules.

The nTRST pin does not cause a system reset.

## 6.2.3.3 Resetting the Debug subsystem

Use the CDBGRSTREQ bit within the SWJ-DP CTRL/STAT register to reset the debug modules. However, as explained below, using the CDBGRSTREQ bit does not reset all debug-related registers.

CDBGRSTREQ resets the debug-related registers within the following modules:

- SWJ-DP
- AHB-AP
- ETM
- ATB replicators
- ATB upsizers
- ATB funnels
- ETB
- TPIU
- MDM-AP (MDM control and status registers)
- MCM (ETB "Almost Full" logic)

CDBGRSTREQ does not reset the debug-related registers within the following modules:

- CM4 core (core debug registers: DHCSR, DCRSR, DCRDR, DEMCR)
- FPB



- DWT
- ITM
- NVIC
- Crossbar bus switch<sup>1</sup>
- AHB-AP<sup>1</sup>
- Private peripheral bus<sup>1</sup>

#### 6.3 Boot

This section describes the boot sequence, including sources and options.

#### 6.3.1 Boot sources

This device only supports booting from internal flash. Any secondary boot must go through an initialization sequence in flash.

# 6.3.2 Boot options

The device's functional mode is controlled by the state of the EzPort chip select  $(\overline{EZP}CS)$  pin during reset.

The device can be in single chip (default) or serial flash programming mode (EzPort). While in single chip mode the device can be in run or various low power modes mentioned in Power mode transitions.

Table 6-2. Mode select decoding

EzPort chip select (EZP_CS)	Description
0	Serial flash programming mode (EzPort)
1	Single chip (default)

## 6.3.3 FOPT boot options

The flash option register (FOPT) in flash memory module (FTFL) allows the user to customize the operation of the MCU at boot time. The register contains read-only bits that are loaded from the NVM's option byte in the flash configuration field. The user can

CDBGRSTREQ does not affect AHB resources so that debug resources on the private peripheral bus are available during System Reset.



DUU

reprogram the option byte in flash to change the FOPT values that are used for subsequent resets. For more details on programming the option byte, refer to the flash memory chapter.

The MCU uses the FTFL\_FOPT register bits to configure the device at reset as shown in the following table.

Table 6-3. Flash Option Register (FTFL\_FOPT) Bit Definitions

Bit Num	Field	Value	Definition	
7-2	Reserved		Reserved for future expansion.	
1	EZPORT_DIS	0	EzPort operation is disabled. The device always boots to normal CPU execution and the state of EZP_CS signal during reset is ignored. This option avoids inadvertent resets into EzPort mode if the EZP_CS/NMI pin is used for its NMI function.	
		1	EzPort operation is enabled. The state of $\overline{\text{EZP\_CS}}$ pin during reset determines if device enters EzPort mode.	
0	LPBOOT	0	Low-power boot: OUTDIVx values in SIM_CLKDIV1 register are auto-configur at reset exit for higher divide values that produce lower power consumption at reset exit.  • Core and system clock divider (OUTDIV1) and bus clock divider (OUTD are 0x7 (divide by 8)  • Flash clock divider (OUTDIV4) and FlexBus clock divider (OUTDIV3) are 0xF (divide by 16)	
		1	Normal boot: OUTDIVx values in SIM_CLKDIV1 register are auto-configured at reset exit for higher frequency values that produce faster operating frequencies at reset exit.	
			<ul> <li>Core and system clock divider (OUTDIV1) and bus clock divider (OUTDIV2) are 0x0 (divide by 1)</li> <li>Flash clock divider (OUTDIV4) and FlexBus clock divider (OUTDIV3) are 0x1 (divide by 2)</li> </ul>	

## 6.3.4 Boot sequence

At power up, the on-chip regulator holds the system in a POR state until the input supply is above the POR threshold. The system continues to be held in this static state until the internally regulated supplies have reached a safe operating voltage as determined by the LVD. The Mode Controller reset logic then controls a sequence to exit reset.

- 1. A system reset is held on internal logic, the RESET pin is driven out low, and the MCG is enabled in its default clocking mode.
- 2. Required clocks are enabled (Core Clock, System Clock, Flash Clock, and any Bus Clocks that do not have clock gate control).
- 3. The system reset on internal logic continues to be held, but the Flash Controller is released from reset and begins initialization operation while the Mode Control logic continues to drive the RESET pin out low for a count of ~128 Bus Clock cycles.



- 4. The RESET pin is released, but the system reset of internal logic continues to be held until the Flash Controller finishes initialization. EzPort mode is selected instead of the normal CPU execution if EZP\_CS is low when the internal reset is deasserted. EzPort mode can be disabled by programming FTFL\_FOPT[EZPORT\_DIS]. Note: If recovering from VLLS1, 2, or 3 with the LLWU\_P3 wakeup pin (PTA4/FTM0\_CH1/NMI/EZP\_CS), use rising-edge wakeup in the LLWU or disable EzPort mode to ensure normal recovery.
- 5. When Flash Initialization completes, the RESET pin is observed. If RESET continues to be asserted (an indication of a slow rise time on the RESET pin or external drive in low), the system continues to be held in reset. Once the RESET pin is detected high, the system is released from reset.
- 6. At release of system reset, clocking is switched to a slow clock if FTFL FOPT[LPBOOT] is configured for Low Power Boot
- 7. When the system exits reset, the processor sets up the stack, program counter (PC), and link register (LR). The processor reads the start SP (SP\_main) from vector-table offset 0. The core reads the start PC from vector-table offset 4. LR is set to 0xFFFF\_FFFF. The CPU begins execution at the PC location. EzPort mode is entered instead of the normal CPU execution if Ezport mode was latched during the sequence.

Subsequent system resets follow this reset flow beginning with the step where system clocks are enabled.





# **Chapter 7 Power Management**

#### 7.1 Introduction

This chapter describes the various chip power modes and functionality of the individual modules in these modes.

## 7.2 Power modes

The power management controller (PMC) provides multiple power options to allow the user to optimize power consumption for the level of functionality needed.

Depending on the stop requirements of the user application, a variety of stop modes are available that provide state retention, partial power down or full power down of certain logic and/or memory. I/O states are held in all modes of operation. The following table compares the various power modes available.

For each run mode there is a corresponding wait and stop mode. Wait modes are similar to ARM sleep modes. Stop modes (VLPS, STOP) are similar to ARM sleep deep mode. The very low power run (VLPR) operating mode can drastically reduce runtime power when the maximum bus frequency is not required to handle the application needs.

The three primary modes of operation are run, wait and stop. The WFI instruction invokes both wait and stop modes for the chip. The primary modes are augmented in a number of ways to provide lower power based on application needs.

Table 7-1. Chip power modes

Chip m	e Description	Core mode	Normal recovery method
Normal	Allows maximum performance of chip. Default mode out of reset; on- chip voltage regulator is on.	Run	-

Table continues on the next page...



#### Fower modes

Table 7-1. Chip power modes (continued)

Chip mode	Description	Core mode	Normal recovery method
Normal Wait - via WFI	Allows peripherals to function while the core is in sleep mode, reducing power. NVIC remains sensitive to interrupts; peripherals continue to be clocked.	Sleep	Interrupt
Normal Stop - via WFI	Places chip in static state. Lowest power mode that retains all registers while maintaining LVD protection. NVIC is disabled; AWIC is used to wake up from interrupt; peripheral clocks are stopped.	Sleep Deep	Interrupt
VLPR (Very Low Power Run)	On-chip voltage regulator is in a low power mode that supplies only enough power to run the chip at a reduced frequency. Reduced frequency Flash access mode (1 MHz); LVD off; internal oscillator provides a low power 2 MHz source for the core, the bus and the peripheral clocks.	Run	Interrupt
VLPW (Very Low Power Wait) -via WFI	Same as VLPR but with the core in sleep mode to further reduce power; NVIC remains sensitive to interrupts (FCLK = ON). On-chip voltage regulator is in a low power mode that supplies only enough power to run the chip at a reduced frequency.	Sleep	Interrupt
VLPS (Very Low Power Stop)-via WFI	Places chip in static state with LVD operation off. Lowest power mode with ADC and pin interrupts functional. Peripheral clocks are stopped, but LPTimer, RTC, CMP, TSI, DAC can be used. NVIC is disabled (FCLK = OFF); AWIC is used to wake up from interrupt. On-chip voltage regulator is in a low power mode that supplies only enough power to run the chip at a reduced frequency. All SRAM is operating (content retained and I/O states held).	Sleep Deep	Interrupt
LLS (Low Leakage Stop)	State retention power mode. Most peripherals are in state retention mode (with clocks stopped), but LLWU, LPTimer, RTC, CMP, TSI, DAC can be used. NVIC is disabled; LLWU is used to wake up.  NOTE: The LLWU interrupt must not be masked by the interrupt controller to avoid a scenario where the system does not fully exit stop mode on an LLS recovery.  All SRAM is operating (content retained and I/O states held).	Sleep Deep	Wakeup Interrupt <sup>1</sup>
VLLS3 (Very Low Leakage Stop3)	Most peripherals are disabled (with clocks stopped), but LLWU, LPTimer, RTC, CMP, TSI, DAC can be used. NVIC is disabled; LLWU is used to wake up.  SRAM_U and SRAM_L remain powered on (content retained and I/O)	Sleep Deep	Wakeup Reset <sup>2</sup>
VLLS2 (Very Low Leakage Stop2)	states held).  Most peripherals are disabled (with clocks stopped), but LLWU, LPTimer, RTC, CMP, TSI, DAC can be used. NVIC is disabled; LLWU is used to wake up.  SRAM_L is powered off. A portion of SRAM_U remains powered on (content retained and I/O states held).	Sleep Deep	Wakeup Reset <sup>2</sup>
VLLS1 (Very Low Leakage Stop1)	Most peripherals are disabled (with clocks stopped), but LLWU, LPTimer, RTC, CMP, TSI, DAC can be used. NVIC is disabled; LLWU is used to wake up.  All of SRAM_U and SRAM_L are powered off. The 32-byte system register file and the 32-byte VBAT register file remain powered for	Sleep Deep	Wakeup Reset <sup>2</sup>

Table continues on the next page...



Table 7-1.	Chin	power modes	(continued)
I abic I - I .	OHID	DOWGI IIIOGGS	(COIILIIIACA)

Chip mode	Description	Core mode	Normal recovery method
BAT (backup battery only)	The chip is powered down except for the VBAT supply. The RTC and the 32-byte VBAT register file for customer-critical data remain powered.	Off	Power-up Sequence

- 1. Resumes normal run mode operation by executing the LLWU interrupt service routine.
- 2. Follows the reset flow with the LLWU interrupt flag set for the NVIC.

# 7.3 Entering and exiting power modes

The WFI instruction invokes wait and stop modes for the chip. The processor exits the low-power mode via an interrupt. The Nested Vectored Interrupt Controller (NVIC) describes interrupt operation and what peripherals can cause interrupts.

#### NOTE

The WFE instruction can have the side effect of entering a low-power mode, but that is not its intended usage. See ARM documentation for more on the WFE instruction.

Recovery from VLLSx is through the wake-up Reset event. The chip wake-ups from VLLSx by means of reset, an enabled pin or enabled module. See the table "LLWU inputs" in the LLWU configuration section for a list of the sources.

The wake-up flow from VLLSx is through reset. The wakeup bit in the SRS registers in the Mode Controller is set indicating that the chip is recovering from a low power mode. Code execution begins; however, the I/O pins are held in their pre low power mode entry states, and the system oscillator and MCG registers are reset (even if EREFSTEN had been set before entering VLLSx). Software must clear this hold by writing a 1 to the ACKISO bit in the Control and Status register in the LLWU module.

#### NOTE

To avoid unwanted transitions on the pins, software must reinitialize the I/O pins to their pre-low-power mode entry states *before* releasing the hold.

If the oscillator was configured to continue running during VLLSx modes, it must be reconfigured before the ACKISO bit is cleared. The oscillator configuration within the MCG is cleared after VLLSx recovery and the oscillator will stop when ACKISO is cleared unless the register is re-configured.



#### 7.4 Power mode transitions

The following figure shows the power mode transitions. Any reset always brings the chip back to the normal run state. In run, wait, and stop modes active power regulation is enabled. The VLPx modes are limited in frequency, but offer a lower power operating mode than normal modes. The LLS and VLLSx modes are the lowest power stop modes based on amount of logic or memory that is required to be retained by the application.




Figure 7-1. Power mode state transition diagram



# 7.5 Power modes shutdown sequencing

When entering stop or other low-power modes, the clocks are shut off in an orderly sequence to safely place the chip in the targeted low-power state. All low-power entry sequences are initiated by the core executing an WFI instruction. The ARM core's outputs, SLEEPDEEP and SLEEPING, trigger entry to the various low-power modes:

- System level wait and VLPW modes equate to: SLEEPING & SLEEPDEEP
- All other low power modes equate to: SLEEPING & SLEEPDEEP

When entering the non-wait modes, the chip performs the following sequence:

- Shuts off Core Clock and System Clock to the ARM Cortex-M4 core immediately.
- Polls stop acknowledge indications from the non-core crossbar masters (DMA), supporting peripherals (SPI, PIT) and the Flash Controller for indications that System Clocks, Bus Clock and/or Flash Clock need to be left enabled to complete a previously initiated operation, effectively stalling entry to the targeted low power mode. When all acknowledges are detected, System Clock, Bus Clock and Flash Clock are turned off at the same time.
- MCG and Mode Controller shut off clock sources and/or the internal supplies driven from the on-chip regulator as defined for the targeted low power mode.

In wait modes, most of the system clocks are not affected by the low power mode entry. The Core Clock to the ARM Cortex-M4 core is shut off. Some modules support stop-in-wait functionality and have their clocks disabled under these configurations.

The debugger modules support a transition from stop, wait, VLPS, and VLPW back to a halted state when the debugger is enabled. This transition is initiated by setting the Debug Request bit in MDM-AP control register. As part of this transition, system clocking is reestablished and is equivalent to normal run/VLPR mode clocking configuration.

# 7.6 Module Operation in Low Power Modes

The following table illustrates the functionality of each module while the chip is in each of the low power modes. (Debug modules are discussed separately; see Debug in Low Power Modes.) Number ratings (such as 2 MHz and 1 Mbps) represent the maximum frequencies or maximum data rates per mode. Also, these terms are used:

- FF = Full functionality. In VLPR and VLPW the system frequency is limited, but if a module does not have a limitation in its functionality, it is still listed as FF.
- static = Module register states and associated memories are retained.



#### **woulde Operation in Low Power Modes**

- powered = Memory is powered to retain contents.
- low power = Flash has a low power state that retains configuration registers to support faster wakeup.
- OFF = Modules are powered off; module is in reset state upon wakeup.
- wakeup = Modules can serve as a wakeup source for the chip.

Table 7-2. Module operation in low power modes

Modules	Stop	VLPR	VLPW	VLPS	LLS	VLLSx
	Core modules					
NVIC	static	FF	FF	static	static	OFF
			System modules			
Mode Controller	FF	FF	FF	FF	FF	FF
LLWU <sup>1</sup>	static	static	static	static	FF	FF
Regulator	ON	low power	low power	low power	low power	low power
LVD	ON	disabled	disabled	disabled	disabled	disabled
Brown-out Detection	ON	ON	ON	ON	ON	ON
DMA	static	FF	FF	static	static	OFF
Watchdog	FF	FF	FF	FF	static	OFF
EWM	static	FF	static	static	static	OFF
			Clocks			
1kHz LPO	ON	ON	ON	ON	ON	ON
System oscillator (OSC)	OSCERCLK optional	OSCERCLK max of 4MHz crystal	OSCERCLK max of 4MHz crystal	OSCERCLK max of 4MHz crystal	limited to low range/low power	limited to low range/low power
MCG	static - MCGIRCLK optional; PLL optionally on but gated	2 MHz IRC	2 MHz IRC	static - no clock output	static - no clock output	OFF
Core clock	OFF	2 MHz max	OFF	OFF	OFF	OFF
System clock	OFF	2 MHz max	2 MHz max	OFF	OFF	OFF
Bus clock	OFF	2 MHz max	2 MHz max	OFF	OFF	OFF
		Memor	y and memory in	terfaces		
Flash	powered	1 MHz max access - no pgm	low power	low power	OFF	OFF
Portion of SRAM_U <sup>2</sup>	low power	low power	low power	low power	low power	low power in VLLS3,2
Remaining SRAM_U and all of SRAM_L	low power	low power	low power	low power	low power	low power in VLLS3

Table continues on the next page...



Table 7-2. Module operation in low power modes (continued)

Madulaa			VI DW			VI I 0
Modules	Stop	VLPR	VLPW .	VLPS .	LLS	VLLSx
Register files <sup>3</sup>	powered	powered	powered	powered	powered	powered
FlexBus	static	FF	FF	static	static	OFF
EzPort	disabled	disabled	disabled	disabled	disabled	disabled
		Com	munication inter	faces		
USB FS/LS	static	static	static	static	static	OFF
USB DCD	static	FF	FF	static	static	OFF
USB Voltage Regulator	optional	optional	optional	optional	optional	optional
UART	static, wakeup on edge	125 kbps	125 kbps	static, wakeup on edge	static	OFF
SPI	static	1 Mbps	1 Mbps	static	static	OFF
I <sup>2</sup> C	static, address match wakeup	100 kbps	100 kbps	static, address match wakeup	static	OFF
I <sup>2</sup> S	FF with external clock <sup>4</sup>	FF	FF	FF with external clock <sup>4</sup>	static	OFF
SDHC	wakeup	FF	FF	wakeup	static	OFF
			Security			
CRC	static	FF	FF	static	static	OFF
			Timers			
FTM	static	FF	FF	static	static	OFF
PIT	static	FF	FF	static	static	OFF
PDB	static	FF	FF	static	static	OFF
LPTMR	FF	FF	FF	FF	FF	FF
RTC - 32kHz OSC <sup>3</sup>	FF	FF	FF	FF	FF <sup>5</sup>	FF <sup>5</sup>
CMT	static	FF	FF	static	static	OFF
			Analog			
16-bit ADC	ADC internal clock only	FF	FF	ADC internal clock only	static	OFF
CMP <sup>6</sup>	HS or LS compare	FF	FF	HS or LS compare	LS compare	LS compare
6-bit DAC	static	FF	FF	static	static	static
VREF	FF	FF	FF	FF	static	OFF
OPAMP	FF	FF	FF	FF	static	OFF
TRIAMP	FF	FF	FF	FF	static	OFF
12-bit DAC	static	FF	FF	static	static	static
		Hum	an-machine inter	faces		

Table continues on the next page...



#### **CIOCK Gating**

Table 7-2. Module operation in low power modes (continued)

Modules	Stop	VLPR	VLPW	VLPS	LLS	VLLSx
GPIO	wakeup	FF	FF	wakeup	static, pins latched	OFF, pins latched
TSI	wakeup	FF	FF	wakeup	wakeup <sup>7</sup>	wakeup <sup>7</sup>

- Using the LLWU module, the external pins available for this chip do not require the associated peripheral function to be enabled. It only requires the function controlling the pin (GPIO or peripheral) to be configured as an input to allow a transition to occur to the LLWU.
- 2. A 4KB portion of SRAM\_U block is left powered on in low power mode VLLS2.
- 3. These components remain powered in BAT power mode.
- 4. Use an externally generated bit clock or an externally generated audio master clock (including EXTAL).
- 5. RTC\_CLKOUT is not available.
- 6. CMP in stop or VLPS supports high speed or low speed external pin to pin or external pin to DAC compares. CMP in LLS or VLLSx only supports low speed external pin to pin or external pin to DAC compares. Windowed, sampled & filtered modes of operation are not available while in stop, VLPS, LLS, or VLLSx modes.
- 7. TSI wakeup from LLS and VLLSx modes is limited to a single selectable pin.

# 7.7 Clock Gating

To conserve power, the clocks to most modules can be turned off using the SCGCx registers in the SIM module. These bits are cleared after any reset, which disables the clock to the corresponding module. Prior to initializing a module, set the corresponding bit in the SCGCx register to enable the clock. Before turning off the clock, make sure to disable the module. For more details, refer to the clock distribution and SIM chapters.



# Chapter 8 Security

#### 8.1 Introduction

This device implements security based on the mode selected from the flash module. The following sections provide an overview of flash security and details the effects of security on non-flash modules.

# 8.2 Flash Security

The flash module provides security information to the MCU based on the state held by the FSEC[SEC] bits. The MCU, in turn, confirms the security request and limits access to flash resources. During reset, the flash module initializes the FSEC register using data read from the security byte of the flash configuration field.

#### **NOTE**

The security features apply only to external accesses: debug and EzPort. CPU accesses to the flash are not affected by the status of FSEC.

In the unsecured state all flash commands are available to the programming interfaces (JTAG and EzPort), as well as user code execution of Flash Controller commands. When the flash is secured (FSEC[SEC] = 00, 01, or 11), programmer interfaces are only allowed to launch mass erase operations and have no access to memory locations.

Further information regarding the flash security options and enabling/disabling flash security is available in the Flash Memory Module.



# 8.3 Security Interactions with other Modules

The flash security settings are used by the SoC to determine what resources are available. The following sections describe the interactions between modules and the flash security settings or the impact that the flash security has on non-flash modules.

# 8.3.1 Security interactions with FlexBus

When flash security is enabled, SIM\_SOPT2[FBSL] enables/disables off-chip accesses through the FlexBus interface. The FBSL bitfield also has an option to allow opcode and operand accesses or only operand accesses.

# 8.3.2 Security Interactions with EzPort

When flash security is active the MCU can still boot in EzPort mode. The EzPort holds the flash logic in NVM special mode and thus limits flash operation when flash security is active. While in EzPort mode and security is active, flash bulk erase (BE) can still be executed. The write FCCOB registers (WRFCCOB) command is limited to the mass erase (Erase All Blocks) and verify all 1s (Read 1s All Blocks) commands. Read accesses to internal memories via the EzPort are blocked when security is enabled.

The mass erase can be used to disable flash security, but all of the flash contents are lost in the process. A mass erase via the EzPort is allowed even when some memory locations are protected.

When mass erase has been disabled, mass erase via the EzPort is blocked and cannot be defeated.

# 8.3.3 Security Interactions with Debug

When flash security is active the JTAG port cannot access the memory resources of the MCU. Boundary scan chain operations work, but debugging capabilities are disabled so that the debug port cannot read flash contents.

Although most debug functions are disabled, the debugger can write to the Flash Mass Erase in Progress bit in the MDM-AP Control register to trigger a mass erase (Erase All Blocks) command. A mass erase via the debugger is allowed even when some memory locations are protected.



When mass erase is disabled, mass erase via the debugger is blocked.



**Security Interactions with other Modules** 



# Chapter 9 Debug

#### 9.1 Introduction

This device's debug is based on the ARM coresight architecture and is configured in each device to provide the maximum flexibility as allowed by the restrictions of the pinout and other available resources.

Four debug interfaces are supported:

- IEEE 1149.1 JTAG
- IEEE 1149.7 JTAG (cJTAG)
- Serial Wire Debug (SWD)
- ARM Real-Time Trace Interface

The basic Cortex-M4 debug architecture is very flexible. The following diagram shows the topology of the core debug architecture and its components.



#### muroduction




Figure 9-1. Cortex-M4 Debug Topology

The following table presents a brief description of each one of the debug components.

**Table 9-1. Debug Components Description** 

Module	Description
SWJ-DP+ cJTAG	Modified Debug Port with support for SWD, JTAG, cJTAG
AHB-AP	AHB Master Interface from JTAG to debug module and SOC system memory maps
JTAG-AP	Bridge to DFT/BIST resources.
ROM Table	Identifies which debug IP is available.
Core Debug	Singlestep, Register Access, Run, Core Status
CoreSight Trace Funnel (not shown in figure)	The CSTF combines multiple trace streams onto a single ATB bus.
CoreSight Trace Replicator (not shown in figure)	The ATB replicator enables two trace sinks to be wired together and operate from the same incoming trace stream.
ETM (Embedded Trace Macrocell)	ETMv3.5 Architecture
CoreSight ETB (Embedded Trace Buffer)	Memory mapped buffer used to store trace data.
ITM	S/W Instrumentation Messaging + Simple Data Trace Messaging + Watchpoint Messaging

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



**Table 9-1. Debug Components Description (continued)** 

Module	Description
DWT (Data and Address Watchpoints)	4 data and address watchpoints (configurable for less, but 4 seems to be accepted)
FPB (Flash Patch and Breakpoints)	The FPB implements hardware breakpoints and patches code and data from code space to system space.
	The FPB unit contains two literal comparators for matching against literal loads from Code space, and remapping to a corresponding area in System space.
	The FBP also contains six instruction comparators for matching against instruction fetches from Code space, and remapping to a corresponding area in System space.  Alternatively, the six instruction comparators can individually configure the comparators to return a Breakpoint Instruction (BKPT) to the processor core on a match, so providing hardware breakpoint capability.
TPIU (Trace Port Inteface Unit)	Synchronous Mode (5-pin) = TRACE_D[3:0] + TRACE_CLKOUT
	Synchronous Mode (3-pin) = TRACE_D[1:0] + TRACE_CLKOUT
	Asynchronous Mode (1-pin) = TRACE_SWO (available on JTAG_TDO)
MCM (Miscellaneous Control Module)	The MCM provides miscellaneous control functions including control of the ETB and trace path switching.

### 9.1.1 References

For more information on ARM debug components, see these documents:

- ARMv7-M Architecture Reference Manual
- ARM Debug Interface v5.1
- ARM CoreSight Architecture Specification
- ARM ETM Architecture Specification v3.5

# 9.2 The Debug Port

The configuration of the cJTAG module, JTAG controller, and debug port is illustrated in the following figure:



тпе Debug Port




Figure 9-2. Modified Debug Port

The debug port comes out of reset in standard JTAG mode and is switched into either cJTAG or SWD mode by the following sequences. Once the mode has been changed, unused debug pins can be reassigned to any of their alternative muxed functions.

# 9.2.1 JTAG-to-SWD change sequence

- 1. Send more than 50 TCK cycles with TMS (SWDIO) =1
- 2. Send the 16-bit sequence on TMS (SWDIO) = 0111\_1001\_1110\_0111 (MSB transmitted first)
- 3. Send more than 50 TCK cycles with TMS (SWDIO) =1

#### NOTE

See the ARM documentation for the CoreSight DAP Lite for restrictions.

## 9.2.2 JTAG-to-cJTAG change sequence

1. Reset the debug port



- 2. Set the control level to 2 via zero-bit scans
- 3. Execute the Store Format (STFMT) command (00011) to set the scan format register to 1149.7 scan format

# 9.3 Debug Port Pin Descriptions

The debug port pins default after POR to their JTAG functionality with the exception of JTAG\_TRST\_b and can be later reassigned to their alternate functionalities. In cJTAG and SWD modes JTAG\_TDI and JTAG\_TRST\_b can be configured to alternate GPIO functions.

Pin Name	JTAG Debug Port		cJTAG Debug Port		SWD Debug Port		Internal Pull- up\Down
	Туре	Description	Туре	Description	Туре	Description	
JTAG_TMS/ SWD_DIO	I/O	JTAG Test Mode Selection	I/O	cJTAG Data	I/O	Serial Wire Data	Pull-up
JTAG_TCLK/ SWD_CLK	I	JTAG Test Clock	I	cJTAG Clock	I	Serial Wire Clock	Pull-down
JTAG_TDI	I	JTAG Test Data Input	-	-	-	-	Pull-up
JTAG_TDO/ TRACE_SW O	0	JTAG Test Data Output	0	Trace output over a single pin	0	Trace output over a single pin	N/C
JTAG_TRST _b	I	JTAG Reset	I	cJTAG Reset	-	-	Pull-up

Table 9-2. Debug port pins

# 9.4 System TAP connection

The system JTAG controller is connected in parallel to the ARM TAP controller. The system JTAG controller IR codes overlay the ARM JTAG controller IR codes without conflict. Refer to the IR codes table for a list of the available IR codes. The output of the TAPs (TDO) are muxed based on the IR code which is selected. This design is fully JTAG compliant and appears to the JTAG chain as a single TAP. At power on reset, ARM's IDCODE (IR=4'b1110) is selected.



#### 9.4.1 IR Codes

Table 9-3. JTAG Instructions

Instruction	Code[3:0]	Instruction Summary
IDCODE	0000	Selects device identification register for shift
SAMPLE/PRELOAD	0010	Selects boundary scan register for shifting, sampling, and preloading without disturbing functional operation
SAMPLE	0011	Selects boundary scan register for shifting and sampling without disturbing functional operation
EXTEST	0100	Selects boundary scan register while applying preloaded values to output pins and asserting functional reset
HIGHZ	1001	Selects bypass register while three-stating all output pins and asserting functional reset
CLAMP	1100	Selects bypass register while applying preloaded values to output pins and asserting functional reset
EZPORT	1101	Enables the EZPORT function for the SoC and asserts functional reset.
ARM_IDCODE	1110	ARM JTAG-DP Instruction
BYPASS	1111	Selects bypass register for data operations
Factory debug reserved	0101, 0110, 0111	Intended for factory debug only
ARM JTAG-DP Reserved	1000, 1010, 1011, 1110	These instructions will go the ARM JTAG-DP controller. Please look at ARM JTAG-DP documentation for more information on these instructions.
Reserved <sup>1</sup>	All other opcodes	Decoded to select bypass register

<sup>1.</sup> The manufacturer reserves the right to change the decoding of reserved instruction codes in the future

# 9.5 JTAG status and control registers

Through the ARM Debug Access Port (DAP), the debugger has access to the status and control elements, implemented as registers on the DAP bus as shown in the following figure. These registers provide additional control and status for low power mode recovery and typical run-control scenarios. The status register bits also provide a means for the debugger to get updated status of the core without having to initiate a bus transaction across the crossbar switch, thus remaining less intrusive during a debug session.



It is important to note that these DAP control and status registers are not memory mapped within the system memory map and are only accessible via the Debug Access Port (DAP) using JTAG, cJTAG, or SWD. The MDM-AP is accessible as Debug Access Port 1 with the available registers shown in the table below.

Table 9-4. MDM-AP Register Summary

Address	Register	Description
0x0100_0000	Status	See MDM-AP Status Register
0x0100_0004	Control	See MDM-AP Control Register
0x0100_00FC	ID	Read-only identification register that always reads as 0x001C_0000




Figure 9-3. MDM AP Addressing



பால் status and control registers

# 9.5.1 MDM-AP Control Register

Table 9-5. MDM-AP Control register assignments

Bit	Name	Secure <sup>1</sup>	Description
0	Flash Mass Erase in Progress	Y	Set to cause mass erase. Cleared by hardware after mass erase operation completes.
			When mass erase is disabled (via MEEN and SEC settings), the erase request does not occur and the Flash Mass Erase in Progress bit continues to assert until the next system reset.
1	Debug Disable	N	Set to disable debug. Clear to allow debug operation. When set it overrides the C_DEBUGEN bit within the DHCSR and force disables Debug logic.
2	Debug Request	N	Set to force the Core to halt.
			If the Core is in a stop or wait mode, this bit can be used to wakeup the core and transition to a halted state.
3	System Reset Request	N	Set to force a system reset. The system remains held in reset until this bit is cleared.
4	Core Hold Reset	N	Configuration bit to control Core operation at the end of system reset sequencing.
			0 Normal operation - release the Core from reset along with the rest of the system at the end of system reset sequencing.
			1 Suspend operation - hold the Core in reset at the end of reset sequencing. Once the system enters this suspended state, clearing this control bit immediately releases the Core from reset and CPU operation begins.
5	VLLSx Debug Request (VLLDBGREQ)	N	Set to configure the system to be held in reset after the next recovery from a VLLSx mode. This bit drives directly to the Mode Controller to control this feature.
			This bit holds the Core in reset when VLLSx modes are exited to allow the debugger time to re-initialize debug IP before the debug session continues.
			The Mode Controller captures this bit logic on entry to VLLSx modes. Upon exit from VLLSx modes, the Mode Controller holds the Core in reset at the end of system reset sequencing. The Mode Controller will hold the Core in reset until VLLDBGACK is asserted.
			The VLLDBGREQ bit clears automatically due to the POR reset generated as part of the VLLSx recovery.
6	VLLSx Debug Acknowledge	N	Set to release a Core being held in reset following a VLLSx recovery
	VLLDBGACK)		This bit is used by the debugger to release the system reset when it is being held on VLLSx mode exit. The debugger re-initializes all debug IP and then assert this control bit to allow the Mode Controller to release the Core from reset and allow CPU operation to begin.
			The VLLDBGACK bit is cleared by the debugger or can be left set because it clears automatically due to the POR reset generated as part of the next VLLSx recovery.

Table continues on the next page...



# Table 9-5. MDM-AP Control register assignments (continued)

Bit	Name	Secure <sup>1</sup>	Description
7	LLS, VLLSx Status Acknowledge	N	Set this bit to acknowledge the DAP LLS and VLLS Status bits have been read. This acknowledge automatically clears the status bits.  This bit is used by the debugger to clear the sticky LLS and VLLSx mode entry status bits. This bit is asserted and cleared by the debugger.
8 – 31	Reserved for future use	N	

<sup>1.</sup> Command available in secure mode

# 9.5.2 MDM-AP Status Register

Table 9-6. MDM-AP Status register assignments

Bit	Name	Description
0	Flash Mass Erase Acknowledge	The Flash Mass Erase Acknowledge bit is cleared after any system reset. The bit is also cleared at launch of a mass erase command due to write of Flash Mass Erase in Progress bit in MDM AP Control Register. The Flash Mass Erase Acknowledge is set after Flash control logic has started the mass erase operation.
		When mass erase is disabled (via MEEN and SEC settings), an erase request due to seting of Flash Mass Erase in Progress bit is not acknowledged.
1	Flash Ready	Indicate Flash has been initialized and debugger can be configured even if system is continuing to be held in reset via the debugger.
2	System Security	Indicates the security state. When secure, the debugger does not have access to the system bus or any memory mapped peripherals. This bit indicates when the part is locked and no system bus access is possible.
3	System Reset	Indicates the system reset state.
		0 System is in reset
		1 System is not in reset
4	Reserved	
5	Mass Erase Enable	Indicates if the MCU can be mass erased or not
		0 Mass erase is disabled
		1 Mass erase is enabled
6	Backdoor Access Key Enable	Indicates if the MCU has the backdoor access key enabled.
		0 Disabled
		1 Enabled

Table continues on the next page...



#### **Debug Resets**

Table 9-6. MDM-AP Status register assignments (continued)

Bit	Name	Description
7	LP Enabled	Decode of LPLLSM control bits to indicate that VLPS, LLS, or VLLSx are the selected power mode the next time the ARM Core enters Deep Sleep.
		0 Low Power Stop Mode is not enabled
		1 Low Power Stop Mode is enabled
		Usage intended for debug operation in which Run to VLPS is attempted. Per debug definition, the system actually enters the Stop state. A debugger should interpret deep sleep indication (with SLEEPDEEP and SLEEPING asserted), in conjuntion with this bit asserted as the debugger-VLPS status indication.
8	Very Low Power Mode	Indicates current power mode is VLPx. This bit is not 'sticky' and should always represent whether VLPx is enabled or not.
		This bit is used to throttle JTAG TCK frequency up/down.
9	LLS Mode Exit	This bit indicates an exit from LLS mode has occurred. The debugger will lose communication while the system is in LLS (including access to this register). Once communication is reestablished, this bit indicates that the system had been in LLS. Since the debug modules held their state during LLS, they do not need to be reconfigured.
		This bit is set during the LLS recovery sequence. The LLS Mode Exit bit is held until the debugger has had a chance to recognize that LLS was exited and is cleared by a write of 1 to the LLS, VLLSx Status Acknowledge bit in MDM AP Control register.
10	VLLSx Modes Exit	This bit indicates an exit from VLLSx mode has occurred. The debugger will lose communication while the system is in VLLSx (including access to this register). Once communication is reestablished, this bit indicates that the system had been in VLLSx. Since the debug modules lose their state during VLLSx modes, they need to be reconfigured.
		This bit is set during the VLLSx recovery sequence. The VLLSx Mode Exit bit is held until the debugger has had a chance to recognize that a VLLS mode was exited and is cleared by a write of 1 to the LLS, VLLSx Status Acknowledge bit in MDM AP Control register.
11 – 15	Reserved for future use	Always read 0.
16	Core Halted	Indicates the Core has entered debug halt mode
17	Core SLEEPDEEP	Indicates the Core has entered a low power mode
18	Core SLEEPING	SLEEPING==1 and SLEEPDEEP==0 indicates wait or VLPW mode.
		SLEEPING==1 and SLEEPDEEP==1 indicates stop or VLPS mode.
19 – 31	Reserved for future use	Always read 0.

# 9.6 Debug Resets

The debug system receives the following sources of reset:

• JTAG\_TRST\_b from an external signal. This signal is optional and may not be available in all packages.



- Debug reset (CDBGRSTREQ bit within the SWJ-DP CTRL/STAT register) in the TCLK domain that allows the debugger to reset the debug logic.
- TRST asserted via the cJTAG escape command.
- System POR reset

Conversely the debug system is capable of generating system reset using the following mechanism:

- A system reset in the DAP control register which allows the debugger to hold the system in reset.
- SYSRESETREQ bit in the NVIC application interrupt and reset control register
- A system reset in the DAP control register which allows the debugger to hold the Core in reset.

#### 9.7 AHB-AP

AHB-AP provides the debugger access to all memory and registers in the system, including processor registers through the NVIC. System access is independent of the processor status. AHB-AP does not do back-to-back transactions on the bus, so all transactions are non-sequential. AHB-AP can perform unaligned and bit-band transactions. AHB-AP transactions bypass the FPB, so the FPB cannot remap AHB-AP transactions. SWJ/SW-DP-initiated transaction aborts drive an AHB-AP-supported sideband signal called HABORT. This signal is driven into the Bus Matrix, which resets the Bus Matrix state, so that AHB-AP can access the Private Peripheral Bus for last ditch debugging such as read/stop/reset the core. AHB-AP transactions are little endian.

The MPU includes default settings and protections for the Region Descriptor 0 (RGD0) such that the Debugger always has access to the entire address space and those rights cannot be changed by the core or any other bus master.

For a short period at the start of a system reset event the system security status is being determined and debugger access to all AHB-AP transactions is blocked. The MDM-AP Status register is accessible and can be monitored to determine when this initial period is completed. After this initial period, if system reset is held via assertion of the RESET pin, the debugger has access via the bus matrix to the private peripheral bus to configure the debug IP even while system reset is asserted. While in system reset, access to other memory and register resources, accessed over the Crossbar Switch, is blocked.



#### 9.8 ITM

The ITM is an application-driven trace source that supports printf style debugging to trace Operating System (OS) and application events, and emits diagnostic system information. The ITM emits trace information as packets. There are four sources that can generate packets. If multiple sources generate packets at the same time, the ITM arbitrates the order in which packets are output. The four sources in decreasing order of priority are:

- 1. Software trace -- Software can write directly to ITM stimulus registers. This emits packets.
- 2. Hardware trace -- The DWT generates these packets, and the ITM emits them.
- 3. Time stamping -- Timestamps are emitted relative to packets. The ITM contains a 21-bit counter to generate the timestamp. The Cortex-M4 clock or the bitclock rate of the Serial Wire Viewer (SWV) output clocks the counter.
- 4. Global system timestamping. Timestamps can optionally be generated using a system-wide 48-bit count value. The same count value can be used to insert timestamps in the ETM trace stream, allowing coarse-grain correlation.

# 9.9 Core Trace Connectivity

# 9.10 Embedded Trace Macrocell v3.5 (ETM)

The Cortex-M4 Embedded Trace Macrocell (ETM-M4) is a debug component that enables a debugger to reconstruct program execution. The CoreSight ETM-M4 supports only instruction trace. You can use it either with the Cortex-M4 Trace Port Interface Unit (M4-TPIU), or with the CoreSight ETB.

The main features of an ETM are:

- tracing of 16-bit and 32-bit Thumb instructions
- four EmbeddedICE watchpoint inputs
- a Trace Start/Stop block with EmbeddedICE inputs
- one reduced function counter
- two external inputs
- a 24-byte FIFO queue
- global timestamping



# 9.11 Coresight Embedded Trace Buffer (ETB)

The ETB provides on-chip storage of trace data using 32-bit RAM. The ETB accepts trace data from any CoreSight-compliant component trace source with an ATB master port, such as a trace source or a trace funnel. It is included in this device to remove dependencies from the trace pin pad speed, and enable low cost trace solutions. The TraceRAM size is 2 KB.




Figure 9-4. ETB Block Diagram

The ETB contains the following blocks:

- Formatter -- Inserts source ID signals into the data packet stream so that trace data can be re-associated with its trace source after the data is read back out of the ETB.
- Control -- Control registers for trace capture and flushing.
- APB interface -- Read, write, and data pointers provide access to ETB registers. In addition, the APB interface supports wait states through the use of a PREADYDBG signal output by the ETB. The APB interface is synchronous to the ATB domain.
- Register bank -- Contains the management, control, and status registers for triggers, flushing behavior, and external control.
- Trace RAM interface -- Controls reads and writes to the Trace RAM.

## 9.11.1 Performance Profiling with the ETB

To create a performance profile (e.g. gprof) for the target application, a means to collect trace over a long period of time is needed. The ETB buffer is too small to capture a meaningful profile in just one take. What is needed is to collect and concatenate data from the ETB buffer for multiple sequential runs. Using the ETB packet counter (described in Miscellaneous Control Module (MCM)), the trace analysis tool can capture



IPIU

multiple sequential runs by executing code until the ETB is almost full, and halting or executing an interrupt handler to allow the buffer to be emptied, and then continuing executing code. The target halts or executes an interrupt handler when the buffer is almost full to empty the data and then the debugger runs the target again.

#### 9.11.2 ETB Counter Control

The ETB packet counter is controlled by the ETB counter control register, ETB reload register, and ETB counter value register implemented in the Miscellaneous Control Module (MCM) accessible via the Private Peripheral Bus. Via the ETB counter control register the ETB control logic can be configured to cause an MCM Alert Interrupt, an NMI Interrupt, or cause a Debug halt when the down counter reaches 0. Other features of the ETB control logic include:

- Down counter to count as many as 512 x 32-bit packets.
- Reload request transfers reload value to counter.
- ATB valid and ready signals used to form counter decrement.
- The counter disarms itself when the count reaches 0.

#### 9.12 TPIU

The TPIU acts as a bridge between the on-chip trace data from the Embedded Trace Macrocell (ETM) and the Instrumentation Trace Macrocell (ITM), with separate IDs, to a data stream, encapsulating IDs where required, that is then captured by a Trace Port Analyzer (TPA). The TPIU is specially designed for low-cost debug.

## 9.13 **DWT**

The DWT is a unit that performs the following debug functionality:

- It contains four comparators that you can configure as a hardware watchpoint, an ETM trigger, a PC sampler event trigger, or a data address sampler event trigger. The first comparator, DWT\_COMP0, can also compare against the clock cycle counter, CYCCNT. The second comparator, DWT\_COMP1, can also be used as a data comparator.
- The DWT contains counters for:
  - Clock cycles (CYCCNT)
  - Folded instructions
  - Load store unit (LSU) operations



- Sleep cycles
- CPI (all instruction cycles except for the first cycle)
- Interrupt overhead

#### NOTE

An event is emitted each time a counter overflows.

• The DWT can be configured to emit PC samples at defined intervals, and to emit interrupt event information.

# 9.14 Debug in Low Power Modes

In low power modes in which the debug modules are kept static or powered off, the debugger cannot gather any debug data for the duration of the low power mode. In the case that the debugger is held static, the debug port returns to full functionality as soon as the low power mode exits and the system returns to a state with active debug. In the case that the debugger logic is powered off, the debugger is reset on recovery and must be reconfigured once the low power mode is exited.

Power mode entry logic monitors Debug Power Up and System Power Up signals from the debug port as indications that a debugger is active. These signals can be changed in RUN, VLPR, WAIT and VLPW. If the debug signal is active and the system attempts to enter stop or VLPS, FCLK continues to run to support core register access and trace. In these modes in which FCLK is left active the debug modules have access to core registers but not to system memory resources accessed via the crossbar.

With debug enabled, transitions from Run directly to VLPS are not allowed and result in the system entering Stop mode instead. Status bits within the MDM-AP Status register can be evaluated to determine this pseudo-VLPS state. Note with the debug enabled, transitions from Run--> VLPR --> VLPS are still possible but also result in the system entering Stop mode instead.

In VLLS mode all debug modules are powered off and reset at wakeup. In LLS mode, the debug modules retain their state but no debug activity is possible.

#### NOTE

When using cJTAG and entering LLS mode, the cJTAG controller must be reset on exit from LLS mode.

Going into a VLLSx mode causes all the debug controls and settings to be reset. To give time to the debugger to sync up with the HW, the MDM-AP Control register can be configured hold the system in reset on recovery so that the debugger can regain control and reconfigure debug logic prior to the system exiting reset and resuming operation.



# 9.14.1 Debug Module State in Low Power Modes

The following table shows the state of the debug modules in low power modes. These terms are used:

- FF = Full functionality. In VLPR and VLPW the system frequency is limited, but if a module does not have a limitation in its functionality, it is still listed as FF.
- static = Module register states and associated memories are retained.
- OFF = Modules are powered off; module is in reset state upon wakeup.

**STOP VLPR VLPW VLPS VLLSx LLS** Module **Debug Port** FF FF FF OFF static OFF AHB-AP FF FF OFF OFF FF static ITM FF FF FF OFF static OFF **ETM** FF FF FF OFF static OFF FF FF OFF OFF **ETB** FF static **TPIU** FF FF FF OFF static **OFF DWT** FF FF FF OFF static OFF

Table 9-7. Debug Module State in Low Power Modes

# 9.15 Debug & Security

When security is enabled (FSEC[SEC] != 10), the debug port capabilities are limited in order to prevent exploitation of secure data. In the secure state the debugger still has access to the MDM-AP Status Register and can determine the current security state of the device. In the case of a secure device, the debugger also has the capability of performing a mass erase operation via writes to the MDM-AP Control Register. In the case of a secure device that has mass erase disabled (FSEC[MEEN] = 10), attempts to mass erase via the debug interface are blocked.



# **Chapter 10 Signal Multiplexing and Signal Descriptions**

### 10.1 Introduction

To optimize functionality in small packages, pins have several functions available via signal multiplexing. This chapter illustrates which of this device's signals are multiplexed on which external pin.

The Port Control block controls which signal is present on the external pin. Reference that chapter to find which register controls the operation of a specific pin.

# 10.2 Signal Multiplexing Integration

This section summarizes how the module is integrated into the device. For a comprehensive description of the module itself, see the module's dedicated chapter.




Figure 10-1. Signal multiplexing integration

Table 10-1. Reference links to related information

Topic	Related module	Reference
Full description	Port control	Port control
System memory map		System memory map



rmout

Table 10-1. Reference links to related information (continued)

Topic	Related module	Reference
Clocking		Clock Distribution
Register access	Peripheral bus controller	Peripheral bridge

# 10.2.1 Port control and interrupt module features

• Five 32-pin ports

#### NOTE

Not all pins are available on the device. See the following section for details.

- Each 32-pin port is assigned one interrupt.
- The digital filter option has two clock source options: bus clock and 1-kHz LPO. The 1-kHz LPO option gives users this feature in low power modes.
- The digital filter is configurable from 1 to 32 clock cycles when enabled.

# 10.2.2 Clock gating

The clock to the port control module can be gated on and off using the SCGC5[PORTx] bits in the SIM module. These bits are cleared after any reset, which disables the clock to the corresponding module to conserve power. Prior to initializing the corresponding module, set SCGC5[PORTx] in the SIM module to enable the clock. Before turning off the clock, make sure to disable the module. For more details, refer to the clock distribution chapter.

# 10.2.3 Signal multiplexing constraints

- 1. A given peripheral function must be assigned to a maximum of one package pin. Do not program the same function to more than one pin.
- 2. To ensure the best signal timing for a given peripheral's interface, choose the pins in closest proximity to each other.

# 10.3 Pinout



# 10.3.1 K50 Signal Multiplexing and Pin Assignments

The following table shows the signals available on each pin and the locations of these pins on the devices supported by this document. The Port Control Module is responsible for selecting which ALT functionality is available on each pin.

144 LQF P	144 MAP BGA	Pin Name	Default	ALT0	ALT1	ALT2	ALT3	ALT4	ALT5	ALT6	ALT7	EzPort
-	C10	NC	NC	NC								
_	B10	NC	NC	NC								
-	A10	NC	NC	NC								
1	D3	PTE0	ADC1_SE4	ADC1_SE4	PTE0	SPI1_PCS1	UART1_TX	SDHC0_D1		I2C1_SDA		
2	D2	PTE1/ LLWU_P0	ADC1_SE5	ADC1_SE5	PTE1/ LLWU_P0	SPI1_SOUT	UART1_RX	SDHC0_D0		I2C1_SCL		
3	D1	PTE2/ LLWU_P1	ADC1_SE6	ADC1_SE6	PTE2/ LLWU_P1	SPI1_SCK	UART1_CT S_b	SDHC0_DC LK				
4	E4	PTE3	ADC1_SE7	ADC1_SE7	PTE3	SPI1_SIN	UART1_RT S_b	SDHC0_CM D				
5	E5	VDD	VDD	VDD								
6	F6	VSS	VSS	VSS								
7	E3	PTE4/ LLWU_P2	DISABLED		PTE4/ LLWU_P2	SPI1_PCS0	UART3_TX	SDHC0_D3				
8	E2	PTE5	DISABLED		PTE5	SPI1_PCS2	UART3_RX	SDHC0_D2				
9	E1	PTE6	DISABLED		PTE6	SPI1_PCS3	UART3_CT S_b	I2S0_MCLK		I2S0_CLKIN		
10	F4	PTE7	DISABLED		PTE7		UART3_RT S_b	I2S0_RXD				
11	F3	PTE8	DISABLED		PTE8		UART5_TX	I2S0_RX_F S				
12	F2	PTE9	DISABLED		PTE9		UART5_RX	I2S0_RX_B CLK				
13	F1	PTE10	DISABLED		PTE10		UART5_CT S_b	I2S0_TXD				
14	G4	PTE11	DISABLED		PTE11		UART5_RT S_b	12S0_TX_F   S				
15	G3	PTE12	DISABLED		PTE12			I2S0_TX_B CLK				
16	E6	VDD	VDD	VDD								
17	F7	VSS	VSS	VSS								
18	НЗ	VSS	VSS	VSS								
19	H1	USB0_DP	USB0_DP	USB0_DP								
20	H2	USB0_DM	USB0_DM	USB0_DM								
21	G1	VOUT33	VOUT33	VOUT33								
22	G2	VREGIN	VREGIN	VREGIN								

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### rmout

144 LQF P	144 MAP BGA	Pin Name	Default	ALT0	ALT1	ALT2	ALT3	ALT4	ALT5	ALT6	ALT7	EzPort
23	J1	ADC0_DP1/ OP0_DP0	ADC0_DP1/ OP0_DP0	ADC0_DP1/ OP0_DP0								
24	J2	ADC0_DM1/ OP0_DM0	ADC0_DM1/ OP0_DM0	ADC0_DM1/ OP0_DM0								
25	K1	ADC1_DP1/ OP1_DP0/ OP1_DM1	ADC1_DP1/ OP1_DP0/ OP1_DM1	ADC1_DP1/ OP1_DP0/ OP1_DM1								
26	K2	ADC1_DM1/ OP1_DM0	ADC1_DM1/ OP1_DM0	ADC1_DM1/ OP1_DM0								
27	L1	PGA0_DP/ ADC0_DP0/ ADC1_DP3	PGA0_DP/ ADC0_DP0/ ADC1_DP3	PGA0_DP/ ADC0_DP0/ ADC1_DP3								
28	L2	PGA0_DM/ ADC0_DM0/ ADC1_DM3	PGA0_DM/ ADC0_DM0/ ADC1_DM3	PGA0_DM/ ADC0_DM0/ ADC1_DM3								
29	M1	PGA1_DP/ ADC1_DP0/ ADC0_DP3	PGA1_DP/ ADC1_DP0/ ADC0_DP3	PGA1_DP/ ADC1_DP0/ ADC0_DP3								
30	M2	PGA1_DM/ ADC1_DM0/ ADC0_DM3	PGA1_DM/ ADC1_DM0/ ADC0_DM3	PGA1_DM/ ADC1_DM0/ ADC0_DM3								
31	H5	VDDA	VDDA	VDDA								
32	G5	VREFH	VREFH	VREFH								
33	G6	VREFL	VREFL	VREFL								
34	H6	VSSA	VSSA	VSSA								
35	K3	ADC1_SE1 6/ OP1_OUT/ CMP2_IN2/ ADC0_SE2 2/OP0_DP2/ OP1_DP2	ADC1_SE1 6/ OP1_OUT/ CMP2_IN2/ ADC0_SE2 2/OP0_DP2/ OP1_DP2	ADC1_SE1 6/ OP1_OUT/ CMP2_IN2/ ADC0_SE2 2/OP0_DP2/ OP1_DP2								
36	J3	ADC0_SE1 6/ OP0_OUT/ CMP1_IN2/ ADC0_SE2 1/OP0_DP1/ OP1_DP1	ADC0_SE1 6/ OP0_OUT/ CMP1_IN2/ ADC0_SE2 1/OP0_DP1/ OP1_DP1	ADC0_SE1 6/ OP0_OUT/ CMP1_IN2/ ADC0_SE2 1/OP0_DP1/ OP1_DP1				_				
37	M3	VREF_OUT/ CMP1_IN5/ CMP0_IN5/ ADC1_SE1 8	VREF_OUT/ CMP1_IN5/ CMP0_IN5/ ADC1_SE1 8	VREF_OUT/ CMP1_IN5/ CMP0_IN5/ ADC1_SE1 8								
38	L3	TRI0_OUT/ OP1_DM2	TRI0_OUT/ OP1_DM2	TRI0_OUT/ OP1_DM2								
39	L4	TRI0_DM	TRI0_DM	TRI0_DM								
40	M4	TRI0_DP	TRI0_DP	TRI0_DP								
41	L5	TRI1_DM	TRI1_DM	TRI1_DM								



### **Chapter 10 Signal Multiplexing and Signal Descriptions**

144 LQF P	144 MAP BGA	Pin Name	Default	ALT0	ALT1	ALT2	ALT3	ALT4	ALT5	ALT6	ALT7	EzPort
42	M5	TRI1_DP	TRI1_DP	TRI1_DP								
43	K5	TRI1_OUT/ CMP2_IN5/ ADC1_SE2 2	TRI1_OUT/ CMP2_IN5/ ADC1_SE2 2	TRI1_OUT/ CMP2_IN5/ ADC1_SE2 2								
44	K4	DACO_OUT/ CMP1_IN3/ ADCO_SE2 3/OPO_DP4/ OP1_DP4	DACO_OUT/ CMP1_IN3/ ADCO_SE2 3/OPO_DP4/ OP1_DP4	DACO_OUT/ CMP1_IN3/ ADCO_SE2 3/OPO_DP4/ OP1_DP4								
45	J4	DAC1_OUT/ CMP2_IN3/ ADC1_SE2 3/OP0_DP5/ OP1_DP5	DAC1_OUT/ CMP2_IN3/ ADC1_SE2 3/OP0_DP5/ OP1_DP5	DAC1_OUT/ CMP2_IN3/ ADC1_SE2 3/OP0_DP5/ OP1_DP5								
46	M7	XTAL32	XTAL32	XTAL32								
47	M6	EXTAL32	EXTAL32	EXTAL32								
48	L6	VBAT	VBAT	VBAT								
49	H4	PTE28	DISABLED		PTE28							
50	<del>J</del> 5	PTA0	JTAG_TCL K/ SWD_CLK/ EZP_CLK	TSI0_CH1	PTA0	UARTO_CT S_b	FTM0_CH5				JTAG_TCL K/ SWD_CLK	EZP_CLK
51	J6	PTA1	JTAG_TDI/ EZP_DI	TSI0_CH2	PTA1	UARTO_RX	FTM0_CH6				JTAG_TDI	EZP_DI
52	K6	PTA2	JTAG_TDO/ TRACE_SW O/EZP_DO	TSI0_CH3	PTA2	UART0_TX	FTM0_CH7				JTAG_TDO/ TRACE_SW O	EZP_DO
53	K7	PTA3	JTAG_TMS/ SWD_DIO	TSI0_CH4	PTA3	UARTO_RT S_b	FTM0_CH0				JTAG_TMS/ SWD_DIO	
54	L7	PTA4/ LLWU_P3	NMI_b/ EZP_CS_b	TSI0_CH5	PTA4/ LLWU_P3		FTM0_CH1				NMI_b	EZP_CS_b
55	M8	PTA5	DISABLED		PTA5		FTM0_CH2		CMP2_OUT	I2S0_RX_B CLK	JTAG_TRS T	
56	E7	VDD	VDD	VDD								
57	G7	VSS	VSS	VSS								
58	J7	PTA6	DISABLED		PTA6		FTM0_CH3				TRACE_CL KOUT	
59	J8	PTA7	ADC0_SE1	ADC0_SE1	PTA7		FTM0_CH4				TRACE_D3	
60	K8	PTA8	ADC0_SE1	ADC0_SE1	PTA8		FTM1_CH0			FTM1_QD_ PHA	TRACE_D2	
61	L8	PTA9	DISABLED		PTA9		FTM1_CH1			FTM1_QD_ PHB	TRACE_D1	
62	M9	PTA10	DISABLED		PTA10		FTM2_CH0			FTM2_QD_ PHA	TRACE_D0	
63	L9	PTA11	DISABLED		PTA11		FTM2_CH1		·	FTM2_QD_ PHB		

### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### rmout

144 LQF P	144 MAP BGA	Pin Name	Default	ALT0	ALT1	ALT2	ALT3	ALT4	ALT5	ALT6	ALT7	EzPort
64	K9	PTA12	CMP2_IN0	CMP2_IN0	PTA12		FTM1_CH0			I2S0_TXD	FTM1_QD_ PHA	
65	J9	PTA13/ LLWU_P4	CMP2_IN1	CMP2_IN1	PTA13/ LLWU_P4		FTM1_CH1			I2S0_TX_F S	FTM1_QD_ PHB	
66	L10	PTA14	DISABLED		PTA14	SPI0_PCS0	UART0_TX			I2S0_TX_B CLK		
67	L11	PTA15	DISABLED		PTA15	SPI0_SCK	UART0_RX			I2S0_RXD		
68	K10	PTA16	DISABLED		PTA16	SPI0_SOUT	UARTO_CT S_b			I2S0_RX_F S		
69	K11	PTA17	ADC1_SE1 7	ADC1_SE1 7	PTA17	SPI0_SIN	UARTO_RT S_b			I2S0_MCLK	I2S0_CLKIN	
70	E8	VDD	VDD	VDD								
71	G8	VSS	VSS	VSS								
72	M12	PTA18	EXTAL	EXTAL	PTA18		FTM0_FLT2	FTM_CLKIN 0				
73	M11	PTA19	XTAL	XTAL	PTA19		FTM1_FLT0	FTM_CLKIN 1		LPT0_ALT1		
74	L12	RESET_b	RESET_b	RESET_b								
75	K12	PTA24	DISABLED		PTA24					FB_A29		
76	J12	PTA25	DISABLED		PTA25					FB_A28		
77	J11	PTA26	DISABLED		PTA26					FB_A27		
78	J10	PTA27	DISABLED		PTA27					FB_A26		
79	H12	PTA28	DISABLED		PTA28					FB_A25		
80	H11	PTA29	DISABLED		PTA29					FB_A24		
81	H10	PTB0/ LLWU_P5	/ ADC0_SE8/ ADC1_SE8/ TSI0_CH0	/ ADC0_SE8/ ADC1_SE8/ TSI0_CH0	PTB0/ LLWU_P5	I2C0_SCL	FTM1_CH0			FTM1_QD_ PHA		
82	H9	PTB1	/ ADC0_SE9/ ADC1_SE9/ TSI0_CH6	/ ADC0_SE9/ ADC1_SE9/ TSI0_CH6	PTB1	I2C0_SDA	FTM1_CH1			FTM1_QD_ PHB		
83	G12	PTB2	/ ADC0_SE1 2/TSI0_CH7	/ ADC0_SE1 2/TSI0_CH7	PTB2	I2C0_SCL	UARTO_RT S_b			FTM0_FLT3		
84	G11	PTB3	/ ADC0_SE1 3/TSI0_CH8	/ ADC0_SE1 3/TSI0_CH8	PTB3	I2C0_SDA	UARTO_CT S_b			FTM0_FLT0		
85	G10	PTB4	/ ADC1_SE1 0	/ ADC1_SE1 0	PTB4					FTM1_FLT0		
86	G9	PTB5	/ ADC1_SE1 1	/ ADC1_SE1 1	PTB5					FTM2_FLT0		
87	F12	PTB6	/ ADC1_SE1 2	/ ADC1_SE1 2	PTB6				FB_AD23			



### **Chapter 10 Signal Multiplexing and Signal Descriptions**

144 LQF P	144 MAP BGA	Pin Name	Default	ALT0	ALT1	ALT2	ALT3	ALT4	ALT5	ALT6	ALT7	EzPort
88	F11	PTB7	/ ADC1_SE1 3	/ ADC1_SE1 3	PTB7				FB_AD22			
89	F10	PTB8			PTB8		UART3_RT S_b		FB_AD21			
90	F9	PTB9			PTB9	SPI1_PCS1	UART3_CT S_b		FB_AD20			
91	E12	PTB10	/ ADC1_SE1 4	/ ADC1_SE1 4	PTB10	SPI1_PCS0	UART3_RX		FB_AD19	FTM0_FLT1		
92	E11	PTB11	/ ADC1_SE1 5	/ ADC1_SE1 5	PTB11	SPI1_SCK	UART3_TX		FB_AD18	FTM0_FLT2		
93	H7	VSS	VSS	VSS								
94	F5	VDD	VDD	VDD								
95	E10	PTB16	/TSI0_CH9	/TSI0_CH9	PTB16	SPI1_SOUT	UART0_RX		FB_AD17	EWM_IN		
96	E9	PTB17	/TSI0_CH10	/TSI0_CH10	PTB17	SPI1_SIN	UART0_TX		FB_AD16	EWM_OUT		
97	D12	PTB18	/TSI0_CH11	/TSI0_CH11	PTB18		FTM2_CH0	I2S0_TX_B CLK	FB_AD15	FTM2_QD_ PHA		
98	D11	PTB19	/TSI0_CH12	/TSI0_CH12	PTB19		FTM2_CH1	12S0_TX_F S	FB_OE_b	FTM2_QD_ PHB		
99	D10	PTB20			PTB20	SPI2_PCS0			FB_AD31	CMP0_OUT		
100	D9	PTB21			PTB21	SPI2_SCK			FB_AD30	CMP1_OUT		
101	C12	PTB22			PTB22	SPI2_SOUT			FB_AD29	CMP2_OUT		
102	C11	PTB23			PTB23	SPI2_SIN	SPI0_PCS5		FB_AD28			
103	B12	PTC0	/ ADC0_SE1 4/ TSI0_CH13	/ ADC0_SE1 4/ TSI0_CH13	PTC0	SPI0_PCS4	PDB0_EXT RG	I2SO_TXD	FB_AD14			
104	B11	PTC1/ LLWU_P6	/ ADC0_SE1 5/ TSI0_CH14	/ ADC0_SE1 5/ TSI0_CH14	PTC1/ LLWU_P6	SPI0_PCS3	UART1_RT S_b	FTM0_CH0	FB_AD13			
105	A12	PTC2	/ ADC0_SE4 b/ CMP1_IN0/ TSI0_CH15	/ ADC0_SE4 b/ CMP1_IN0/ TSI0_CH15	PTC2	SPI0_PCS2	UART1_CT S_b	FTM0_CH1	FB_AD12			
106	A11	PTC3/ LLWU_P7	/CMP1_IN1	/CMP1_IN1	PTC3/ LLWU_P7	SPI0_PCS1	UART1_RX	FTM0_CH2	FB_CLKOU T			
107	H8	VSS	VSS	VSS								
108	-	VDD	VDD	VDD								
109	A9	PTC4/ LLWU_P8			PTC4/ LLWU_P8	SPI0_PCS0	UART1_TX	FTM0_CH3	FB_AD11	CMP1_OUT		
110	D8	PTC5/ LLWU_P9			PTC5/ LLWU_P9	SPI0_SCK		LPT0_ALT2	FB_AD10	CMP0_OUT		

### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### rmout

144 LQF P	144 MAP BGA	Pin Name	Default	ALT0	ALT1	ALT2	ALT3	ALT4	ALT5	ALT6	ALT7	EzPort
111	C8	PTC6/ LLWU_P10	/CMP0_IN0	/CMP0_IN0	PTC6/ LLWU_P10	SPI0_SOUT	PDB0_EXT RG		FB_AD9			
112	B8	PTC7	/CMP0_IN1	/CMP0_IN1	PTC7	SPI0_SIN			FB_AD8			
113	A8	PTC8	/ ADC1_SE4 b/ CMP0_IN2	/ ADC1_SE4 b/ CMP0_IN2	PTC8		I2S0_MCLK	I2SO_CLKIN	FB_AD7			
114	D7	PTC9	/ ADC1_SE5 b/ CMP0_IN3	/ ADC1_SE5 b/ CMP0_IN3	PTC9			I2S0_RX_B CLK	FB_AD6	FTM2_FLT0		
115	C7	PTC10	/ ADC1_SE6 b/ CMP0_IN4	/ ADC1_SE6 b/ CMP0_IN4	PTC10	I2C1_SCL		12S0_RX_F S	FB_AD5			
116	B7	PTC11/ LLWU_P11	/ ADC1_SE7 b	/ ADC1_SE7 b	PTC11/ LLWU_P11	I2C1_SDA		I2S0_RXD	FB_RW_b			
117	A7	PTC12			PTC12		UART4_RT S_b		FB_AD27			
118	D6	PTC13			PTC13		UART4_CT S_b		FB_AD26			
119	C6	PTC14			PTC14		UART4_RX		FB_AD25			
120	B6	PTC15			PTC15		UART4_TX		FB_AD24			
121	_	VSS	VSS	VSS			_					
122	_	VDD	VDD	VDD								
123	A6	PTC16			PTC16		UART3_RX		FB_CS5_b/ FB_TSIZ1/ FB_BE23_1 6_BLS15_8 _b			
124	D5	PTC17			PTC17		UART3_TX		FB_CS4_b/ FB_TSIZ0/ FB_BE31_2 4_BLS7_0_ b			
125	C5	PTC18			PTC18		UART3_RT S_b		FB_TBST_b /FB_CS2_b/ FB_BE15_8 _BLS23_16 _b			
126	B5	PTC19			PTC19		UART3_CT S_b		FB_CS3_b/ FB_BE7_0_ BLS31_24_ b	FB_TA_b		
127	A5	PTD0/ LLWU_P12			PTD0/ LLWU_P12	SPI0_PCS0	UART2_RT S_b		FB_ALE/ FB_CS1_b/ FB_TS_b			



144 LQF P	144 MAP BGA	Pin Name	Default	ALT0	ALT1	ALT2	ALT3	ALT4	ALT5	ALT6	ALT7	EzPort
128	D4	PTD1	/ ADC0_SE5 b	/ ADC0_SE5 b	PTD1	SPI0_SCK	UART2_CT S_b		FB_CS0_b			
129	C4	PTD2/ LLWU_P13			PTD2/ LLWU_P13	SPI0_SOUT	UART2_RX		FB_AD4			
130	B4	PTD3			PTD3	SPI0_SIN	UART2_TX		FB_AD3			
131	A4	PTD4/ LLWU_P14			PTD4/ LLWU_P14	SPI0_PCS1	UARTO_RT S_b	FTM0_CH4	FB_AD2	EWM_IN		
132	A3	PTD5	/ ADC0_SE6 b	/ ADC0_SE6 b	PTD5	SPI0_PCS2	UARTO_CT S_b	FTM0_CH5	FB_AD1	EWM_OUT _b		
133	A2	PTD6/ LLWU_P15	/ ADC0_SE7 b	/ ADC0_SE7 b	PTD6/ LLWU_P15	SPI0_PCS3	UARTO_RX	FTM0_CH6	FB_AD0	FTM0_FLT0		
134	M10	VSS	VSS	VSS								
135	F8	VDD	VDD	VDD								
136	A1	PTD7			PTD7	CMT_IRO	UART0_TX	FTM0_CH7		FTM0_FLT1		
137	C9	PTD8	DISABLED		PTD8	I2C0_SCL	UART5_RX			FB_A16		
138	В9	PTD9	DISABLED		PTD9	I2C0_SDA	UART5_TX			FB_A17		
139	B3	PTD10	DISABLED		PTD10		UART5_RT S_b			FB_A18		
140	B2	PTD11	DISABLED		PTD11	SPI2_PCS0	UART5_CT S_b	SDHC0_CL KIN		FB_A19		
141	B1	PTD12	DISABLED		PTD12	SPI2_SCK		SDHC0_D4		FB_A20		
142	C3	PTD13	DISABLED		PTD13	SPI2_SOUT		SDHC0_D5		FB_A21		
143	C2	PTD14	DISABLED		PTD14	SPI2_SIN		SDHC0_D6		FB_A22		
144	C1	PTD15	DISABLED		PTD15	SPI2_PCS1		SDHC0_D7		FB_A23		

# 10.3.2 K50 Pinouts

The below figure shows the pinout diagram for the devices supported by this document. Many signals may be multiplexed onto a single pin. To determine what signals can be used on which pin, see the previous section.

rmout




Figure 10-2. K50 144 LQFP Pinout Diagram




Figure 10-3. K50 144 MAPBGA Pinout Diagram

# 10.4 Module Signal Description Tables

The following sections correlate the chip-level signal name with the signal name used in the module's chapter. They also briefly describe the signal function and direction.



### 10.4.1 Core Modules

### Table 10-2. JTAG Signal Descriptions

Chip signal name	Module signal name	Description	I/O
JTAG_TMS	JTAG_TMS/ SWD_DIO	JTAG Test Mode Selection	I/O
JTAG_TCLK	JTAG_TCLK/ SWD_CLK	JTAG Test Clock	I
JTAG_TDI	JTAG_TDI	JTAG Test Data Input	I
JTAG_TDO	JTAG_TDO/ TRACE_SWO	JTAG Test Data Output	0
JTAG_TRST	JTAG_TRST_b	JTAG Reset	I

### Table 10-3. SWD Signal Descriptions

Chip signal name	Module signal name	Description	I/O
SWD_DIO	JTAG_TMS/ SWD_DIO	Serial Wire Data	I/O
SWD_CLK	JTAG_TCLK/ SWD_CLK	Serial Wire Clock	1

### **Table 10-4. TPIU Signal Descriptions**

Chip signal name	Module signal name	Description	I/O
TRACE_CLKOUT	TRACECLK	Trace clock output from the ARM CoreSight debug block	0
TRACE_D[3:2]	TRACEDATA	Trace output data from the ARM CoreSight debug block used for 5-pin interface	0
TRACE_D[1:0]	TRACEDATA	Trace output data from the ARM CoreSight debug block used for both 5-pin and 3-pin interfaces	0
TRACE_SWO	JTAG_TDO/ TRACE_SWO	Trace output data from the ARM CoreSight debug block over a single pin	0

# 10.4.2 System Modules

# **Table 10-5. System Signal Descriptions**

Chip signal name	Module signal name	Description	I/O
NMI		Non-maskable interrupt	I
		NOTE: Driving the NMI signal low forces a non-maskable interrupt, if the NMI function is selected on the corresponding pin.	



### **Table 10-5. System Signal Descriptions (continued)**

Chip signal name	Module signal name	Description	I/O
RESET	_	Reset bi-directional signal	I/O
VDD	_	MCU power	I
VSS	_	MCU ground	I

### Table 10-6. EWM Signal Descriptions

Chip signal name	Module signal name	Description	I/O
EWM_IN	EWM_in	EWM input for safety status of external safety circuits. The polarity of EWM_in is programmable using the CTRL[ASSIN] bit. The default polarity is active-low.	I
EWM_OUT	EWM_out	EWM reset out signal	0

# 10.4.3 Clock Modules

### Table 10-7. OSC Signal Descriptions

Chip signal name	Module signal name	Description	I/O
EXTAL0	EXTAL	External clock/Oscillator input	I
XTAL0	XTAL	Oscillator output	0

### Table 10-8. RTC OSC Signal Descriptions

Chip signal name	Module signal name	Description	I/O
EXTAL32	EXTAL32	32.768 kHz oscillator input	I
XTAL32	XTAL32	32.768 kHz oscillator output	0

# 10.4.4 Memories and Memory Interfaces

### Table 10-9. EzPort Signal Descriptions

Chip signal name	Module signal name	Description	I/O
EZP_CLK	EZP_CK	EzPort Clock	Input
EZP_CS	EZP_CS	EzPort Chip Select	Input
EZP_DI	EZP_D	EzPort Serial Data In	Input
EZP_DO	EZP_Q	EzPort Serial Data Out	Output

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### woule Signal Description Tables

# Table 10-10. FlexBus Signal Descriptions

Chip signal name	Module signal name	Description	I/O
FB_CLKOUT	FB_CLK	FlexBus clock output	0
FB_A[29:16]	FB_A[29:16]	In a non-multiplexed configuration, this is the address bus.	0
FB_AD[31:0]	FB_D[31:0]/ FB_AD[31:0]	In a non-multiplexed configuration, this is the data bus. In a multiplexed configuration this bus is the address/data bus, FB_AD[31:0]. In non-multiplexed and multiplexed configurations, during the first cycle, this bus drives the upper address byte, addr[31:24].	I/O
FB_CS[5:0]	FB_CS[5:0]	General purpose chip-selects. The actual number of chip selects available depends upon the device and its pin configuration.	0
FB_BE31_24_BLS7 0, FB_BE23_16_BLS1 5_8, FB_BE15_8_BLS23 16, FB_BE7_0_BLS31_ 24	FB_BE_31_24 FB_BE_23_16 FB_BE_15_8 FB_BE_7_0	Byte enables	0
FB_OE	FB_OE	Output enable	0
FB_R ₩	FB_R/W	Read/write. 1 = Read, 0 = Write	0
FB_TS/ FB_ALE	FB_TS	Transfer start	0
FB_TSIZ[1:0]	FB_TSIZ[1:0]	Transfer size	0
FB_TA	FB_TA	Transfer acknowledge	I
FB_TBST	FB_TBST	Burst transfer indicator	0

# 10.4.5 Analog

Table 10-11. ADC 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
ADC0_DP3, PGA0_DP, ADC0_DP[1:0]	DADP[3:0]	Differential analog channel inputs	I
ADC0_DM3, PGA0_DM, ADC0_DM[1:0]	DADM[3:0]	Differential analog channel inputs	I
ADC0_SE[18:4]	AD[23:4]	Single-ended analog channel inputs	I
VREFH	V <sub>REFSH</sub>	Voltage reference select high	I
VREFL	V <sub>REFSL</sub>	Voltage reference select low	I
VDDA	$V_{DDA}$	Analog power supply	I

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# Table 10-11. ADC 0 Signal Descriptions (continued)

Chip signal name	Module signal name	Description	I/O
VSSA	V <sub>SSA</sub>	Analog ground	I

### Table 10-12. ADC 1 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
ADC1_DP3, PGA1_DP, ADC1_DP[1:0]	DADP[3:0]	Differential analog channel inputs	I
ADC1_DM3, PGA1_DM, ADC1_DM[1:0]	DADM[3:0]	Differential analog channel inputs	I
ADC1_SE[18:4]	AD[23:4]	Single-ended analog channel inputs	I
VREFH	V <sub>REFSH</sub>	Voltage reference select high	I
VREFL	V <sub>REFSL</sub>	Voltage reference select low	I
VDDA	$V_{DDA}$	Analog power supply	I
VSSA	V <sub>SSA</sub>	Analog ground	I

# Table 10-13. CMP 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
CMP0_IN[5:0]	IN[5:0]	Analog voltage inputs	Ι
CMP0_OUT	СМРО	Comparator output	0

### Table 10-14. CMP 1 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
CMP1_IN[5:0]	IN[5:0]	Analog voltage inputs	Ι
CMP1_OUT	СМРО	Comparator output	0

# Table 10-15. CMP 2 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
CMP2_IN[5:0]	IN[5:0]	Analog voltage inputs	I
CMP2_OUT	СМРО	Comparator output	0



#### **woulle Signal Description Tables**

# Table 10-16. DAC 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
DAC0_OUT	_	DAC output	0

### Table 10-17. DAC 1 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
DAC1_OUT	_	DAC output	0

### Table 10-18. Op-Amp 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
OP0_DP0	INP <sub>x</sub> -	Amplifier positive input terminal	I
OP0_DM0	INP <sub>x</sub> +	Amplifier negative input terminal	I
OP0_OUT	VOUT <sub>x</sub>	Amplifier output terminal	0

### Table 10-19. Op-Amp 1 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
OP1_DP0	INP <sub>x</sub> -	Amplifier positive input terminal	I
OP1_DM[2:0]	INP <sub>x</sub> +	Amplifier negative input terminal	I
OP1_OUT	VOUT <sub>x</sub>	Amplifier output terminal	0

### Table 10-20. TRIAMP 1 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
TRI1_DP	inp_3v	Amplifier positive input terminal	I
TRI1_DM	inn_3v	Amplifier negative input terminal	I
TRI1_OUT	out_3v	Amplifier output terminal	0

# Table 10-21. VREF Signal Descriptions

Chip signal name	Module signal name	Description	I/O
VREF_OUT	VREF_OUT	Internally-generated Voltage Reference output	0



# 10.4.6 Communication Interfaces

### Table 10-22. USB FS OTG Signal Descriptions

Chip signal name	Module signal name	Description	I/O
USB0_DM	usb_dm	USB D- analog data signal on the USB bus.	I/O
USB0_DP	usb_dp	USB D+ analog data signal on the USB bus.	I/O
USB_CLKIN	_	Alternate USB clock input	I

### Table 10-23. USB VREG Signal Descriptions

Chip signal name	Module signal name	Description	I/O
VOUT33	reg33_out	Regulator output voltage	0
VREGIN	reg33_in	Unregulated power supply	I

### Table 10-24. SPI 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
SPI0_PCS0	PCS0/SS	Master mode: Peripheral Chip Select 0 output	I/O
		Slave mode: Slave Select input	
SPI0_PCS[3:1]	PCS[3:1]	Master mode: Peripheral Chip Select 1 - 3	0
		Slave mode: Unused	
SPI0_PCS4	PCS4	Master mode: Peripheral Chip Select 4	0
		Slave mode: Unused	
SPI0_PCS5	PCS5/ PCSS	Master mode: Peripheral Chip Select 5 /	0
		Peripheral Chip Select Strobe	
		Slave mode: Unused	
SPI0_SIN	SIN	Serial Data In	I
SPI0_SOUT	SOUT	Serial Data Out	0
SPI0_SCK	SCK	Master mode: Serial Clock (output)	I/O
		Slave mode: Serial Clock (input)	

# Table 10-25. I<sup>2</sup>C 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
I2C0_SCL	SCL	Bidirectional serial clock line of the I <sup>2</sup> C system.	I/O
I2C0_SDA	SDA	Bidirectional serial data line of the I <sup>2</sup> C system.	I/O

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### **woulde Signal Description Tables**

# Table 10-26. I<sup>2</sup>C 1 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
I2C1_SCL	SCL	Bidirectional serial clock line of the I <sup>2</sup> C system.	I/O
I2C1_SDA	SDA	Bidirectional serial data line of the I <sup>2</sup> C system.	I/O

### Table 10-27. UART 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
UARTO_CTS	CTS	Clear to send	Ι
UARTO_RTS	RTS	Request to send	0
UART0_TX	TXD	Transmit data	0
UART0_RX	RXD	Receive data	I

### Table 10-28. UART 1 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
UART1_CTS	CTS	Clear to send	I
UART1_RTS	RTS	Request to send	0
UART1_TX	TXD	Transmit data	0
UART1_RX	RXD	Receive data	I

### Table 10-29. UART 2 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
UART2_CTS	CTS	Clear to send	I
UART2_RTS	RTS	Request to send	0
UART2_TX	TXD	Transmit data	0
UART2_RX	RXD	Receive data	I

# Table 10-30. UART 3 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
UART3_CTS	CTS	Clear to send	I
UART3_RTS	RTS	Request to send	0
UART3_TX	TXD	Transmit data	0
UART3_RX	RXD	Receive data	I



# Table 10-31. UART 4 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
UART4_CTS	CTS	Clear to send	I
UART4_RTS	RTS	Request to send	0
UART4_TX	TXD	Transmit data	0
UART4_RX	RXD	Receive data	I

### Table 10-32. UART 5 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
UART5_CTS	CTS	Clear to send	I
UART5_RTS	RTS	Request to send	0
UART5_TX	TXD	Transmit data	0
UART5_RX	RXD	Receive data	I

# Table 10-33. SDHC Signal Descriptions

Chip signal name	Module signal name	Description	I/O
SDHC0_CLKIN	_	SDHC clock input	I
SDHC0_DCLK	SDHC_DCLK	Generated clock used to drive the MMC, SD, SDIO or CE-ATA cards.	0
SDHC0_CMD	SDHC_CMD	Send commands to and receive responses from the card.	I/O
SDHC0_D0	SDHC_D0	DAT0 line or busy-state detect	I/O
SDHC0_D1	SDHC_D1	8-bit mode: DAT1 line	I/O
		4-bit mode: DAT1 line or interrupt detect	
		1-bit mode: Interrupt detect	
SDHC0_D2	SDHC_D2	4-/8-bit mode: DAT2 line or read wait	I/O
		1-bit mode: Read wait	
SDHC0_D3	SDHC_D3	4-/8-bit mode: DAT3 line or configured as card detection pin	
		1-bit mode: May be configured as card detection pin	
SDHC0_D4	SDHC_D4	DAT4 line in 8-bit mode	
		Not used in other modes	
SDHC0_D5	SDHC_D5	5 DAT5 line in 8-bit mode	
		Not used in other modes	
SDHC0_D6	SDHC_D6	DAT6 line in 8-bit mode	
		Not used in other modes	
SDHC0_D7	SDHC_D7	DAT7 line in 8-bit mode	
		Not used in other modes	

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### พเงนนle Signal Description Tables

# Table 10-34. I<sup>2</sup>S 0 Signal Descriptions

Chip signal name	Module signal name	al Description	
I2S0_MCLK	_	Serial master clock output	I/O
I2S0_RX_BCLK	SRCK	Serial receive clock. SRCK can be used as an input or output.	I/O
		<ul> <li>In asynchronous mode the receiver uses this clock signal and it is always continuous.</li> </ul>	
		In synchronous mode, the STCK port is used instead for clocking in data.	
I2S0_RX_FS	SRFS	Serial receive frame Sync. The SRFS port can be used as an input or output. The frame sync is used by the receiver to synchronize the transfer of data. The frame sync signal can be one bit or one word in length and can occur one bit before the transfer of data or right at the transfer of data. If SRFS is configured as an input, the external device should drive SRFS during the rising edge of STCK or SRCK.	I/O
I2S0_RXD	SRXD	Serial receive data. The SRXD port is an input and is used to bring serial data into the receive data shift register.	
I2S0_TX_BCLK	STCK	Serial transmit clock. The STCK port can be used as an input or output. This clock signal is used by the transmitter and can be continuous or gated. During gated clock mode, data on STCK is valid only during the transmission of data. Otherwise, it is pulled to the inactive state. In synchronous mode, this port is used by the transmit and receive sections.	
I2S0_TX_FS	STFS	Serial transmit frame sync. The STFS port can be used as an input or output. The frame sync is used by the transmitter to synchronize the transfer of data. The frame sync signal can be one bit or one word in length and can occur one bit before the transfer of data or right at the transfer of data. In synchronous mode, this port is used by both the transmit and receive sections. In gated clock mode, frame sync signals are not used. If STFS is configured as an input, the external device should drive STFS during the rising edge of STCK if TSCKP is positive-edge triggered. The external device should drive STFS during the falling edge of STCK if TSCKP is negative-edge triggered.	
I2S0_TXD	STXD	Serial transmit data. The STXD port is an output and transmits data from the serial transmit shift register. The STXD port is an output port when data is being transmitted and is disabled between data word transmissions and on the trailing edge of the bit clock after the last bit of a word is transmitted.	0

# 10.4.7 Human-Machine Interfaces (HMI)

### Table 10-35. GPIO Signal Descriptions

Chip signal name	Module signal name	Description	I/O
PTA[31:0] <sup>1</sup>	PORTA[31:0]	General purpose input/output	I/O



# **Table 10-35. GPIO Signal Descriptions (continued)**

Chip signal name	Module signal name	Description	I/O
PTB[31:0] <sup>1</sup>	PORTB[31:0]	General purpose input/output	I/O
PTC[31:0] <sup>1</sup>	PORTC[31:0]	General purpose input/output	I/O
PTD[31:0] <sup>1</sup>	PORTD[31:0]	General purpose input/output	I/O
PTE[31:0] <sup>1</sup>	PORTE[31:0]	General purpose input/output	I/O

<sup>1.</sup> The available GPIO pins depends on the specific package. See the signal multiplexing section for which exact GPIO signals are available.

### Table 10-36. TSI 0 Signal Descriptions

Chip signal name	Module signal name	Description	I/O
TSI0_CH[15:0]	TSI_IN[15:0]	TSI pins. Switchable driver that connects directly to the electrode pins TSI[15:0] can operate as GPIO pins	I/O



**woulle Signal Description Tables** 



# Chapter 11 Port control and interrupts (PORT)

### 11.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

#### 11.1.1 Overview

The port control and interrupt (PORT) module provides support for external interrupt, digital filtering and port control functions. Most functions can be configured independently for each pin in the 32-bit port and affect the pin regardless of its pin muxing state.

There is one instance of the PORT module for each port. Not all pins within each port are implemented on a specific device.

# 11.1.2 Features

- Pin interrupt
  - Interrupt flag and enable registers for each pin
  - Supports edge sensitive (rising, falling, both) or level sensitive (low, high) configured per pin
  - Support for interrupt or DMA request configured per pin
  - Asynchronous wakeup in low-power modes
  - Pin interrupt is functional in all digital pin muxing modes
- Digital input filter
  - Digital input filter for each pin, usable by any digital peripheral muxed onto pin
  - Individual enable or bypass control bit per pin



#### muroduction

- Selectable clock source for digital input filter with 5-bit resolution on filter size
- Digital filter is functional in all digital pin muxing modes
- Port control
  - Individual pull control registers with pullup, pulldown and pull-disable support
  - Individual drive strength register supporting high and low drive strength
  - Individual slew rate register supporting fast and slow slew rates
  - Individual input passive filter register supporting enabled and disabled
  - Individual open-drain register supporting enabled and disabled
  - Individual mux control register supporting analog (or pin disabled), GPIO plus up to six chip specific digital functions
  - Pad configuration registers are functional in all digital pin muxing modes

# 11.1.3 Modes of operation

#### 11.1.3.1 Run mode

In run mode, the PORT operates normally.

### 11.1.3.2 Wait mode

In wait mode, the PORT continues to operate normally and may be configured to exit the low power mode if an enabled interrupt is detected. DMA requests are still generated during wait mode, but do not cause an exit from the low power mode.

# 11.1.3.3 Stop mode

In stop mode, the digital input filters are bypassed unless they are configured to run from the 1 kHz LPO clock source. The PORT can be configured to exit the low power mode via an asynchronous wakeup signal if an enabled interrupt (but not DMA request) is detected.

### 11.1.3.4 Debug mode

In debug mode, the PORTx operates normally.



# 11.2 External signal description

Table 11-1. Signal properties

Name	Function	I/O	Reset	Pull
PORTx[31:0]	External interrupt	I/O	0	-

#### NOTE

Not all pins within each port are implemented on each device.

# 11.3 Detailed signal descriptions

Table 11-2. PORTx interface-detailed signal descriptions

Signal	I/O	Description		
PORTx[31:0]	I/O	External interrupt.		
		State meaning	Asserted-pin is logic one.  Negated-pin is logic zero.	
		Timing	Assertion-may occur at any time and can assert asynchronously to the system clock.	
			Negation-may occur at any time and can assert asynchronously to the system clock.	

# 11.4 Memory map and register definition

Any read or write access to the PORT memory space that is outside the valid memory map results in a bus error. All register accesses complete with zero wait states.

# PORT memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_9000	Pin Control Register n (PORTA_PCR0)	32	R/W	0000_0000h	11.4.1/250
4004_9004	Pin Control Register n (PORTA_PCR1)	32	R/W	0000_0000h	11.4.1/250
4004_9008	Pin Control Register n (PORTA_PCR2)	32	R/W	0000_0000h	11.4.1/250



#### wemory map and register definition

# PORT memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_900C	Pin Control Register n (PORTA_PCR3)	32	R/W	0000_0000h	11.4.1/250
4004_9010	Pin Control Register n (PORTA_PCR4)	32	R/W	0000_0000h	11.4.1/250
4004_9014	Pin Control Register n (PORTA_PCR5)	32	R/W	0000_0000h	11.4.1/250
4004_9018	Pin Control Register n (PORTA_PCR6)	32	R/W	0000_0000h	11.4.1/250
4004_901C	Pin Control Register n (PORTA_PCR7)	32	R/W	0000_0000h	11.4.1/250
4004_9020	Pin Control Register n (PORTA_PCR8)	32	R/W	0000_0000h	11.4.1/250
4004_9024	Pin Control Register n (PORTA_PCR9)	32	R/W	0000_0000h	11.4.1/250
4004_9028	Pin Control Register n (PORTA_PCR10)	32	R/W	0000_0000h	11.4.1/250
4004_902C	Pin Control Register n (PORTA_PCR11)	32	R/W	0000_0000h	11.4.1/250
4004_9030	Pin Control Register n (PORTA_PCR12)	32	R/W	0000_0000h	11.4.1/250
4004_9034	Pin Control Register n (PORTA_PCR13)	32	R/W	0000_0000h	11.4.1/250
4004_9038	Pin Control Register n (PORTA_PCR14)	32	R/W	0000_0000h	11.4.1/250
4004_903C	Pin Control Register n (PORTA_PCR15)	32	R/W	0000_0000h	11.4.1/250
4004_9040	Pin Control Register n (PORTA_PCR16)	32	R/W	0000_0000h	11.4.1/250
4004_9044	Pin Control Register n (PORTA_PCR17)	32	R/W	0000_0000h	11.4.1/250
4004_9048	Pin Control Register n (PORTA_PCR18)	32	R/W	0000_0000h	11.4.1/250
4004_904C	Pin Control Register n (PORTA_PCR19)	32	R/W	0000_0000h	11.4.1/250
4004_9050	Pin Control Register n (PORTA_PCR20)	32	R/W	0000_0000h	11.4.1/250
4004_9054	Pin Control Register n (PORTA_PCR21)	32	R/W	0000_0000h	11.4.1/250
4004_9058	Pin Control Register n (PORTA_PCR22)	32	R/W	0000_0000h	11.4.1/250
4004_905C	Pin Control Register n (PORTA_PCR23)	32	R/W	0000_0000h	11.4.1/250
4004_9060	Pin Control Register n (PORTA_PCR24)	32	R/W	0000_0000h	11.4.1/250
4004_9064	Pin Control Register n (PORTA_PCR25)	32	R/W	0000_0000h	11.4.1/250
4004_9068	Pin Control Register n (PORTA_PCR26)	32	R/W	0000_0000h	11.4.1/250
4004_906C	Pin Control Register n (PORTA_PCR27)	32	R/W	0000_0000h	11.4.1/250
4004_9070	Pin Control Register n (PORTA_PCR28)	32	R/W	0000_0000h	11.4.1/250
4004_9074	Pin Control Register n (PORTA_PCR29)	32	R/W	0000_0000h	11.4.1/250
4004_9078	Pin Control Register n (PORTA_PCR30)	32	R/W	0000_0000h	11.4.1/250
4004_907C	Pin Control Register n (PORTA_PCR31)	32	R/W	0000_0000h	11.4.1/250
4004_9080	Global Pin Control Low Register (PORTA_GPCLR)	32	W (always reads zero)	0000_0000h	11.4.2/252
4004_9084	Global Pin Control High Register (PORTA_GPCHR)	32	W (always	0000_0000h	11.4.3/253



# PORT memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
			reads zero)		
4004_90A0	Interrupt Status Flag Register (PORTA_ISFR)	32	w1c	0000_0000h	11.4.4/253
4004_90C0	Digital Filter Enable Register (PORTA_DFER)	32	R/W	0000_0000h	11.4.5/254
4004_90C4	Digital Filter Clock Register (PORTA_DFCR)	32	R/W	0000_0000h	11.4.6/255
4004_90C8	Digital Filter Width Register (PORTA_DFWR)	32	R/W	0000_0000h	11.4.7/255
4004_A000	Pin Control Register n (PORTB_PCR0)	32	R/W	0000_0000h	11.4.1/250
4004_A004	Pin Control Register n (PORTB_PCR1)	32	R/W	0000_0000h	11.4.1/250
4004_A008	Pin Control Register n (PORTB_PCR2)	32	R/W	0000_0000h	11.4.1/250
4004_A00C	Pin Control Register n (PORTB_PCR3)	32	R/W	0000_0000h	11.4.1/250
4004_A010	Pin Control Register n (PORTB_PCR4)	32	R/W	0000_0000h	11.4.1/250
4004_A014	Pin Control Register n (PORTB_PCR5)	32	R/W	0000_0000h	11.4.1/250
4004_A018	Pin Control Register n (PORTB_PCR6)	32	R/W	0000_0000h	11.4.1/250
4004_A01C	Pin Control Register n (PORTB_PCR7)	32	R/W	0000_0000h	11.4.1/250
4004_A020	Pin Control Register n (PORTB_PCR8)	32	R/W	0000_0000h	11.4.1/250
4004_A024	Pin Control Register n (PORTB_PCR9)	32	R/W	0000_0000h	11.4.1/250
4004_A028	Pin Control Register n (PORTB_PCR10)	32	R/W	0000_0000h	11.4.1/250
4004_A02C	Pin Control Register n (PORTB_PCR11)	32	R/W	0000_0000h	11.4.1/250
4004_A030	Pin Control Register n (PORTB_PCR12)	32	R/W	0000_0000h	11.4.1/250
4004_A034	Pin Control Register n (PORTB_PCR13)	32	R/W	0000_0000h	11.4.1/250
4004_A038	Pin Control Register n (PORTB_PCR14)	32	R/W	0000_0000h	11.4.1/250
4004_A03C	Pin Control Register n (PORTB_PCR15)	32	R/W	0000_0000h	11.4.1/250
4004_A040	Pin Control Register n (PORTB_PCR16)	32	R/W	0000_0000h	11.4.1/250
4004_A044	Pin Control Register n (PORTB_PCR17)	32	R/W	0000_0000h	11.4.1/250
4004_A048	Pin Control Register n (PORTB_PCR18)	32	R/W	0000_0000h	11.4.1/250
4004_A04C	Pin Control Register n (PORTB_PCR19)	32	R/W	0000_0000h	11.4.1/250
4004_A050	Pin Control Register n (PORTB_PCR20)	32	R/W	0000_0000h	11.4.1/250
4004_A054	Pin Control Register n (PORTB_PCR21)	32	R/W	0000_0000h	11.4.1/250
4004_A058	Pin Control Register n (PORTB_PCR22)	32	R/W	0000_0000h	11.4.1/250
4004_A05C	Pin Control Register n (PORTB_PCR23)	32	R/W	0000_0000h	11.4.1/250
4004_A060	Pin Control Register n (PORTB_PCR24)	32	R/W	0000_0000h	11.4.1/250
4004_A064	Pin Control Register n (PORTB_PCR25)	32	R/W	0000_0000h	11.4.1/250
4004_A068	Pin Control Register n (PORTB_PCR26)	32	R/W	0000_0000h	11.4.1/250
4004_A06C	Pin Control Register n (PORTB_PCR27)	32	R/W	0000_0000h	11.4.1/250



#### wemory map and register definition

# PORT memory map (continued)

4004_A070   Pin Control Register n (PORTB_PCR28)   32   R/W   0000_0000h   11.4.1/250   4004_A074   Pin Control Register n (PORTB_PCR29)   32   R/W   0000_0000h   11.4.1/250   4004_A076   Pin Control Register n (PORTB_PCR30)   32   R/W   0000_0000h   11.4.1/250   4004_A076   Pin Control Register n (PORTB_PCR31)   32   R/W   0000_0000h   11.4.1/250   4004_A080   Global Pin Control Low Register (PORTB_GPCLR)   32   W   W   W (always reads zero)   4004_A084   Global Pin Control High Register (PORTB_GPCHR)   32   W (always reads zero)   4004_A084   Global Pin Control High Register (PORTB_GPCHR)   32   W (always reads zero)   4004_A084   Global Pin Control High Register (PORTB_ISFR)   32   W (always reads zero)   4004_A000   Interrupt Status Flag Register (PORTB_ISFR)   32   W (always reads zero)   4004_A000   Digital Filter Enable Register (PORTB_DFCR)   32   W (always reads zero)   4004_A000   Digital Filter Clock Register (PORTB_DFCR)   32   R/W   0000_0000h   11.4.4/253   4004_A004   Digital Filter Clock Register (PORTB_DFCR)   32   R/W   0000_0000h   11.4.1/250   4004_A002   Digital Filter Width Register (PORTB_DFCR)   32   R/W   0000_0000h   11.4.1/250   4004_B000   Pin Control Register n (PORTC_PCR0)   32   R/W   0000_0000h   11.4.1/250   4004_B000   Pin Control Register n (PORTC_PCR1)   32   R/W   0000_0000h   11.4.1/250   4004_B000   Pin Control Register n (PORTC_PCR2)   32   R/W   0000_0000h   11.4.1/250   4004_B001   Pin Control Register n (PORTC_PCR3)   32   R/W   0000_0000h   11.4.1/250   4004_B010   Pin Control Register n (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250   4004_B014   Pin Control Register n (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250   4004_B014   Pin Control Register n (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250   4004_B014   Pin Control Register n (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250   4004_B014   Pin Control Register n (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250   4004_B020   Pin Control Register n (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250	Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_A076	4004_A070	Pin Control Register n (PORTB_PCR28)	32	R/W	0000_0000h	11.4.1/250
4004_A07C   Pin Control Register n (PORTB_PCR31)   32   R/W   0000_0000h   11.4.1/250   11.4.2/252   11.4.2/252   12.4   12.5	4004_A074	Pin Control Register n (PORTB_PCR29)	32	R/W	0000_0000h	11.4.1/250
4004_A080   Global Pin Control Low Register (PORTB_GPCLR)   32   1.4.2/252   32   32   32   32   32   32   32	4004_A078	Pin Control Register n (PORTB_PCR30)	32	R/W	0000_0000h	11.4.1/250
4004_A080   Global Pin Control Low Register (PORTB_GPCLR)   32   (always reads zero)   11.4.2/252   24004_A084   Global Pin Control High Register (PORTB_GPCHR)   32   Wtc   0000_0000h   11.4.3/253   24004_A000   Interrupt Status Flag Register (PORTB_ISFR)   32   Wtc   0000_0000h   11.4.3/253   24004_A000   Digital Filter Enable Register (PORTB_DFER)   32   R/W   0000_0000h   11.4.5/254   24004_A004   Digital Filter Clock Register (PORTB_DFER)   32   R/W   0000_0000h   11.4.5/254   24004_A004   Digital Filter Width Register (PORTB_DFWR)   32   R/W   0000_0000h   11.4.1/250   24004_A008   Digital Filter Width Register (PORTB_DFWR)   32   R/W   0000_0000h   11.4.1/250   24004_B004   Pin Control Register in (PORTC_PCR0)   32   R/W   0000_0000h   11.4.1/250   24004_B004   Pin Control Register in (PORTC_PCR1)   32   R/W   0000_0000h   11.4.1/250   24004_B006   Pin Control Register in (PORTC_PCR2)   32   R/W   0000_0000h   11.4.1/250   24004_B006   Pin Control Register in (PORTC_PCR3)   32   R/W   0000_0000h   11.4.1/250   24004_B010   Pin Control Register in (PORTC_PCR3)   32   R/W   0000_0000h   11.4.1/250   24004_B010   Pin Control Register in (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250   24004_B016   Pin Control Register in (PORTC_PCR6)   32   R/W   0000_0000h   11.4.1/250   24004_B016   Pin Control Register in (PORTC_PCR8)   32   R/W   0000_0000h   11.4.1/250   24004_B024   Pin Control Register in (PORTC_PCR8)   32   R/W   0000_0000h   11.4.1/250   24004_B024   Pin Control Register in (PORTC_PCR9)   32   R/W   0000_0000h   11.4.1/250   24004_B024   Pin Control Register in (PORTC_PCR1)   32   R/W   0000_0000h   11.4.1/250   24004_B024   Pin Control Register in (PORTC_PCR1)   32   R/W   0000_0000h   11.4.1/250   24004_B024   Pin Control Register in (PORTC_PCR12)   32   R/W   0000_0000h   11.4.1/250   24004_B034   Pin Control Register in (PORTC_PCR13)   32   R/W   0000_0000h   11.4.1/250   24004_B034   Pin Control Register in (PORTC_PCR15)   32   R/W   0000_0000h   11.4.1/250   24004_B034   Pin Control Regis	4004_A07C	Pin Control Register n (PORTB_PCR31)	32	R/W	0000_0000h	11.4.1/250
4004_A084         Global Pin Control High Register (PORTB_GPCHR)         32         (always reads zero)         0000_0000h         11.4.3/253           4004_A0A0         Interrupt Status Flag Register (PORTB_ISFR)         32         w1c         0000_0000h         11.4.4/253           4004_A0C0         Digital Filter Enable Register (PORTB_DFER)         32         R/W         0000_0000h         11.4.5/254           4004_A0C4         Digital Filter Clock Register (PORTB_DFCR)         32         R/W         0000_0000h         11.4.7/255           4004_A0C8         Digital Filter Width Register (PORTB_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_B000         Pin Control Register (PORTC_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_B004         Pin Control Register (PORTC_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_B008         Pin Control Register (PORTC_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_B000         Pin Control Register (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B012	4004_A080	Global Pin Control Low Register (PORTB_GPCLR)	32	(always reads	0000_0000h	11.4.2/252
4004_A0C0         Digital Filter Enable Register (PORTB_DFER)         32         R/W         0000_0000h         11.4.5/254           4004_A0C4         Digital Filter Clock Register (PORTB_DFCR)         32         R/W         0000_0000h         11.4.6/255           4004_A0C8         Digital Filter Width Register (PORTB_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_B000         Pin Control Register n (PORTC_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_B004         Pin Control Register n (PORTC_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_B008         Pin Control Register n (PORTC_PCR2)         32         R/W         0000_0000h         11.4.1/250           4004_B000         Pin Control Register n (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR5)         32         R/W         0000_0000h         11.4.1/250           4004_B014         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Re	4004_A084	Global Pin Control High Register (PORTB_GPCHR)	32	(always reads	0000_0000h	11.4.3/253
4004_A0C4         Digital Filter Clock Register (PORTB_DFCR)         32         RW         0000_0000h         11.4.6/255           4004_A0C8         Digital Filter Width Register (PORTB_DFWR)         32         RW         0000_0000h         11.4.7/255           4004_B000         Pin Control Register n (PORTC_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_B004         Pin Control Register n (PORTC_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_B008         Pin Control Register n (PORTC_PCR2)         32         R/W         0000_0000h         11.4.1/250           4004_B000         Pin Control Register n (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B014         Pin Control Register n (PORTC_PCR5)         32         R/W         0000_0000h         11.4.1/250           4004_B018         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR7)         32         R/W         0000_0000h         11.4.1/250           4004_B016         Pin Control Register n (	4004_A0A0	Interrupt Status Flag Register (PORTB_ISFR)	32	w1c	0000_0000h	11.4.4/253
4004_A0C8         Digital Filter Width Register (PORTB_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_B000         Pin Control Register n (PORTC_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_B004         Pin Control Register n (PORTC_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_B008         Pin Control Register n (PORTC_PCR2)         32         R/W         0000_0000h         11.4.1/250           4004_B000         Pin Control Register n (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR4)         32         R/W         0000_0000h         11.4.1/250           4004_B014         Pin Control Register n (PORTC_PCR5)         32         R/W         0000_0000h         11.4.1/250           4004_B018         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR7)         32         R/W         0000_0000h         11.4.1/250           4004_B020         Pin Control Register n (PORTC_PCR8)         32         R/W         0000_0000h         11.4.1/250           4004_B028         Pin Control Register n (PORTC	4004_A0C0	Digital Filter Enable Register (PORTB_DFER)	32	R/W	0000_0000h	11.4.5/254
4004_B000         Pin Control Register n (PORTC_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_B004         Pin Control Register n (PORTC_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_B008         Pin Control Register n (PORTC_PCR2)         32         R/W         0000_0000h         11.4.1/250           4004_B000         Pin Control Register n (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR4)         32         R/W         0000_0000h         11.4.1/250           4004_B014         Pin Control Register n (PORTC_PCR5)         32         R/W         0000_0000h         11.4.1/250           4004_B018         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR7)         32         R/W         0000_0000h         11.4.1/250           4004_B020         Pin Control Register n (PORTC_PCR8)         32         R/W         0000_0000h         11.4.1/250           4004_B024         Pin Control Register n (PORTC_PCR10)         32         R/W         0000_0000h         11.4.1/250           4004_B030         Pin Control Register n (PORTC_PCR12	4004_A0C4	Digital Filter Clock Register (PORTB_DFCR)	32	R/W	0000_0000h	11.4.6/255
4004_B004         Pin Control Register n (PORTC_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_B008         Pin Control Register n (PORTC_PCR2)         32         R/W         0000_0000h         11.4.1/250           4004_B00C         Pin Control Register n (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR4)         32         R/W         0000_0000h         11.4.1/250           4004_B014         Pin Control Register n (PORTC_PCR5)         32         R/W         0000_0000h         11.4.1/250           4004_B018         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR7)         32         R/W         0000_0000h         11.4.1/250           4004_B020         Pin Control Register n (PORTC_PCR8)         32         R/W         0000_0000h         11.4.1/250           4004_B024         Pin Control Register n (PORTC_PCR9)         32         R/W         0000_0000h         11.4.1/250           4004_B028         Pin Control Register n (PORTC_PCR10)         32         R/W         0000_0000h         11.4.1/250           4004_B030         Pin Control Register n (PORTC_PCR12	4004_A0C8	Digital Filter Width Register (PORTB_DFWR)	32	R/W	0000_0000h	11.4.7/255
4004_B008       Pin Control Register n (PORTC_PCR2)       32       R/W       0000_0000h       11.4.1/250         4004_B00C       Pin Control Register n (PORTC_PCR3)       32       R/W       0000_0000h       11.4.1/250         4004_B010       Pin Control Register n (PORTC_PCR4)       32       R/W       0000_0000h       11.4.1/250         4004_B014       Pin Control Register n (PORTC_PCR5)       32       R/W       0000_0000h       11.4.1/250         4004_B018       Pin Control Register n (PORTC_PCR6)       32       R/W       0000_0000h       11.4.1/250         4004_B01C       Pin Control Register n (PORTC_PCR7)       32       R/W       0000_0000h       11.4.1/250         4004_B020       Pin Control Register n (PORTC_PCR8)       32       R/W       0000_0000h       11.4.1/250         4004_B024       Pin Control Register n (PORTC_PCR9)       32       R/W       0000_0000h       11.4.1/250         4004_B028       Pin Control Register n (PORTC_PCR10)       32       R/W       0000_0000h       11.4.1/250         4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250 <tr< td=""><td>4004_B000</td><td>Pin Control Register n (PORTC_PCR0)</td><td>32</td><td>R/W</td><td>0000_0000h</td><td>11.4.1/250</td></tr<>	4004_B000	Pin Control Register n (PORTC_PCR0)	32	R/W	0000_0000h	11.4.1/250
4004_B00C         Pin Control Register n (PORTC_PCR3)         32         R/W         0000_0000h         11.4.1/250           4004_B010         Pin Control Register n (PORTC_PCR4)         32         R/W         0000_0000h         11.4.1/250           4004_B014         Pin Control Register n (PORTC_PCR5)         32         R/W         0000_0000h         11.4.1/250           4004_B018         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B01C         Pin Control Register n (PORTC_PCR7)         32         R/W         0000_0000h         11.4.1/250           4004_B020         Pin Control Register n (PORTC_PCR8)         32         R/W         0000_0000h         11.4.1/250           4004_B024         Pin Control Register n (PORTC_PCR9)         32         R/W         0000_0000h         11.4.1/250           4004_B028         Pin Control Register n (PORTC_PCR10)         32         R/W         0000_0000h         11.4.1/250           4004_B030         Pin Control Register n (PORTC_PCR11)         32         R/W         0000_0000h         11.4.1/250           4004_B034         Pin Control Register n (PORTC_PCR13)         32         R/W         0000_0000h         11.4.1/250           4004_B038         Pin Control Register n (PORTC_PCR	4004_B004	Pin Control Register n (PORTC_PCR1)	32	R/W	0000_0000h	11.4.1/250
4004_B010       Pin Control Register n (PORTC_PCR4)       32       R/W       0000_0000h       11.4.1/250         4004_B014       Pin Control Register n (PORTC_PCR5)       32       R/W       0000_0000h       11.4.1/250         4004_B018       Pin Control Register n (PORTC_PCR6)       32       R/W       0000_0000h       11.4.1/250         4004_B01C       Pin Control Register n (PORTC_PCR7)       32       R/W       0000_0000h       11.4.1/250         4004_B020       Pin Control Register n (PORTC_PCR8)       32       R/W       0000_0000h       11.4.1/250         4004_B024       Pin Control Register n (PORTC_PCR9)       32       R/W       0000_0000h       11.4.1/250         4004_B028       Pin Control Register n (PORTC_PCR10)       32       R/W       0000_0000h       11.4.1/250         4004_B020       Pin Control Register n (PORTC_PCR11)       32       R/W       0000_0000h       11.4.1/250         4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B036       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250      <	4004_B008	Pin Control Register n (PORTC_PCR2)	32	R/W	0000_0000h	11.4.1/250
4004_B014         Pin Control Register n (PORTC_PCR5)         32         R/W         0000_0000h         11.4.1/250           4004_B018         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B01C         Pin Control Register n (PORTC_PCR7)         32         R/W         0000_0000h         11.4.1/250           4004_B020         Pin Control Register n (PORTC_PCR8)         32         R/W         0000_0000h         11.4.1/250           4004_B024         Pin Control Register n (PORTC_PCR9)         32         R/W         0000_0000h         11.4.1/250           4004_B028         Pin Control Register n (PORTC_PCR10)         32         R/W         0000_0000h         11.4.1/250           4004_B02C         Pin Control Register n (PORTC_PCR11)         32         R/W         0000_0000h         11.4.1/250           4004_B030         Pin Control Register n (PORTC_PCR12)         32         R/W         0000_0000h         11.4.1/250           4004_B034         Pin Control Register n (PORTC_PCR13)         32         R/W         0000_0000h         11.4.1/250           4004_B038         Pin Control Register n (PORTC_PCR15)         32         R/W         0000_0000h         11.4.1/250           4004_B030         Pin Control Register n (PORTC_P	4004_B00C	Pin Control Register n (PORTC_PCR3)	32	R/W	0000_0000h	11.4.1/250
4004_B018         Pin Control Register n (PORTC_PCR6)         32         R/W         0000_0000h         11.4.1/250           4004_B01C         Pin Control Register n (PORTC_PCR7)         32         R/W         0000_0000h         11.4.1/250           4004_B020         Pin Control Register n (PORTC_PCR8)         32         R/W         0000_0000h         11.4.1/250           4004_B024         Pin Control Register n (PORTC_PCR9)         32         R/W         0000_0000h         11.4.1/250           4004_B028         Pin Control Register n (PORTC_PCR10)         32         R/W         0000_0000h         11.4.1/250           4004_B02C         Pin Control Register n (PORTC_PCR11)         32         R/W         0000_0000h         11.4.1/250           4004_B030         Pin Control Register n (PORTC_PCR12)         32         R/W         0000_0000h         11.4.1/250           4004_B034         Pin Control Register n (PORTC_PCR13)         32         R/W         0000_0000h         11.4.1/250           4004_B038         Pin Control Register n (PORTC_PCR14)         32         R/W         0000_0000h         11.4.1/250           4004_B030         Pin Control Register n (PORTC_PCR15)         32         R/W         0000_0000h         11.4.1/250           4004_B040         Pin Control Register n (PORTC_	4004_B010	Pin Control Register n (PORTC_PCR4)	32	R/W	0000_0000h	11.4.1/250
4004_B01C       Pin Control Register n (PORTC_PCR7)       32       R/W       0000_0000h       11.4.1/250         4004_B020       Pin Control Register n (PORTC_PCR8)       32       R/W       0000_0000h       11.4.1/250         4004_B024       Pin Control Register n (PORTC_PCR9)       32       R/W       0000_0000h       11.4.1/250         4004_B028       Pin Control Register n (PORTC_PCR10)       32       R/W       0000_0000h       11.4.1/250         4004_B02C       Pin Control Register n (PORTC_PCR11)       32       R/W       0000_0000h       11.4.1/250         4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250	4004_B014	Pin Control Register n (PORTC_PCR5)	32	R/W	0000_0000h	11.4.1/250
4004_B020       Pin Control Register n (PORTC_PCR8)       32       R/W       0000_0000h       11.4.1/250         4004_B024       Pin Control Register n (PORTC_PCR9)       32       R/W       0000_0000h       11.4.1/250         4004_B028       Pin Control Register n (PORTC_PCR10)       32       R/W       0000_0000h       11.4.1/250         4004_B02C       Pin Control Register n (PORTC_PCR11)       32       R/W       0000_0000h       11.4.1/250         4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B018	Pin Control Register n (PORTC_PCR6)	32	R/W	0000_0000h	11.4.1/250
4004_B024       Pin Control Register n (PORTC_PCR9)       32       R/W       0000_0000h       11.4.1/250         4004_B028       Pin Control Register n (PORTC_PCR10)       32       R/W       0000_0000h       11.4.1/250         4004_B02C       Pin Control Register n (PORTC_PCR11)       32       R/W       0000_0000h       11.4.1/250         4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B01C	Pin Control Register n (PORTC_PCR7)	32	R/W	0000_0000h	11.4.1/250
4004_B028       Pin Control Register n (PORTC_PCR10)       32       R/W       0000_0000h       11.4.1/250         4004_B02C       Pin Control Register n (PORTC_PCR11)       32       R/W       0000_0000h       11.4.1/250         4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B020	Pin Control Register n (PORTC_PCR8)	32	R/W	0000_0000h	11.4.1/250
4004_B02C       Pin Control Register n (PORTC_PCR11)       32       R/W       0000_0000h       11.4.1/250         4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B024	Pin Control Register n (PORTC_PCR9)	32	R/W	0000_0000h	11.4.1/250
4004_B030       Pin Control Register n (PORTC_PCR12)       32       R/W       0000_0000h       11.4.1/250         4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B028	Pin Control Register n (PORTC_PCR10)	32	R/W	0000_0000h	11.4.1/250
4004_B034       Pin Control Register n (PORTC_PCR13)       32       R/W       0000_0000h       11.4.1/250         4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B02C	Pin Control Register n (PORTC_PCR11)	32	R/W	0000_0000h	11.4.1/250
4004_B038       Pin Control Register n (PORTC_PCR14)       32       R/W       0000_0000h       11.4.1/250         4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B030	Pin Control Register n (PORTC_PCR12)	32	R/W	0000_0000h	11.4.1/250
4004_B03C       Pin Control Register n (PORTC_PCR15)       32       R/W       0000_0000h       11.4.1/250         4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B034	Pin Control Register n (PORTC_PCR13)	32	R/W	0000_0000h	11.4.1/250
4004_B040       Pin Control Register n (PORTC_PCR16)       32       R/W       0000_0000h       11.4.1/250         4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B038	Pin Control Register n (PORTC_PCR14)	32	R/W	0000_0000h	11.4.1/250
4004_B044       Pin Control Register n (PORTC_PCR17)       32       R/W       0000_0000h       11.4.1/250         4004_B048       Pin Control Register n (PORTC_PCR18)       32       R/W       0000_0000h       11.4.1/250	4004_B03C	Pin Control Register n (PORTC_PCR15)	32	R/W	0000_0000h	11.4.1/250
4004_B048 Pin Control Register n (PORTC_PCR18) 32 R/W 0000_0000h 11.4.1/250	4004_B040	Pin Control Register n (PORTC_PCR16)	32	R/W	0000_0000h	11.4.1/250
	4004_B044	Pin Control Register n (PORTC_PCR17)	32	R/W	0000_0000h	11.4.1/250
4004_B04C Pin Control Register n (PORTC_PCR19) 32 R/W 0000_0000h 11.4.1/250	4004_B048	Pin Control Register n (PORTC_PCR18)	32	R/W	0000_0000h	11.4.1/250
	4004_B04C	Pin Control Register n (PORTC_PCR19)	32	R/W	0000_0000h	11.4.1/250



# PORT memory map (continued)

4004_B054	Pin Control Register n (PORTC_PCR20) Pin Control Register n (PORTC_PCR21)	22			page
	Pin Control Register n (PORTC PCR21)	32	R/W	0000_0000h	11.4.1/250
_	· • • · · · · · · · · · · · · · · ·	32	R/W	0000_0000h	11.4.1/250
4004_B058	Pin Control Register n (PORTC_PCR22)	32	R/W	0000_0000h	11.4.1/250
4004_B05C	Pin Control Register n (PORTC_PCR23)	32	R/W	0000_0000h	11.4.1/250
4004_B060	Pin Control Register n (PORTC_PCR24)	32	R/W	0000_0000h	11.4.1/250
4004_B064	Pin Control Register n (PORTC_PCR25)	32	R/W	0000_0000h	11.4.1/250
4004_B068	Pin Control Register n (PORTC_PCR26)	32	R/W	0000_0000h	11.4.1/250
4004_B06C	Pin Control Register n (PORTC_PCR27)	32	R/W	0000_0000h	11.4.1/250
4004_B070	Pin Control Register n (PORTC_PCR28)	32	R/W	0000_0000h	11.4.1/250
4004_B074	Pin Control Register n (PORTC_PCR29)	32	R/W	0000_0000h	11.4.1/250
4004_B078	Pin Control Register n (PORTC_PCR30)	32	R/W	0000_0000h	11.4.1/250
4004_B07C	Pin Control Register n (PORTC_PCR31)	32	R/W	0000_0000h	11.4.1/250
4004_B080	Global Pin Control Low Register (PORTC_GPCLR)	32	W (always reads zero)	0000_0000h	11.4.2/252
4004_B084	Global Pin Control High Register (PORTC_GPCHR)	32	W (always reads zero)	0000_0000h	11.4.3/253
4004_B0A0	Interrupt Status Flag Register (PORTC_ISFR)	32	w1c	0000_0000h	11.4.4/253
4004_B0C0	Digital Filter Enable Register (PORTC_DFER)	32	R/W	0000_0000h	11.4.5/254
4004_B0C4	Digital Filter Clock Register (PORTC_DFCR)	32	R/W	0000_0000h	11.4.6/255
4004_B0C8	Digital Filter Width Register (PORTC_DFWR)	32	R/W	0000_0000h	11.4.7/255
4004_C000	Pin Control Register n (PORTD_PCR0)	32	R/W	0000_0000h	11.4.1/250
4004_C004	Pin Control Register n (PORTD_PCR1)	32	R/W	0000_0000h	11.4.1/250
4004_C008	Pin Control Register n (PORTD_PCR2)	32	R/W	0000_0000h	11.4.1/250
4004_C00C	Pin Control Register n (PORTD_PCR3)	32	R/W	0000_0000h	11.4.1/250
4004_C010	Pin Control Register n (PORTD_PCR4)	32	R/W	0000_0000h	11.4.1/250
4004_C014	Pin Control Register n (PORTD_PCR5)	32	R/W	0000_0000h	11.4.1/250
4004_C018	Pin Control Register n (PORTD_PCR6)	32	R/W	0000_0000h	11.4.1/250
4004_C01C	Pin Control Register n (PORTD_PCR7)	32	R/W	0000_0000h	11.4.1/250
4004_C020	Pin Control Register n (PORTD_PCR8)	32	R/W	0000_0000h	11.4.1/250
4004_C024	Pin Control Register n (PORTD_PCR9)	32	R/W	0000_0000h	11.4.1/250
4004_C028	Pin Control Register n (PORTD_PCR10)	32	R/W	0000_0000h	11.4.1/250
4004_C02C	Pin Control Register n (PORTD_PCR11)	32	R/W	0000_0000h	11.4.1/250



#### wemory map and register definition

# PORT memory map (continued)

4004_C030   Pin Control Register n (PORTD_PCR12)   32   R/W   0000_0000h   11.4.1/250   4004_C034   Pin Control Register n (PORTD_PCR13)   32   R/W   0000_0000h   11.4.1/250   4004_C036   Pin Control Register n (PORTD_PCR14)   32   R/W   0000_0000h   11.4.1/250   4004_C036   Pin Control Register n (PORTD_PCR15)   32   R/W   0000_0000h   11.4.1/250   4004_C036   Pin Control Register n (PORTD_PCR16)   32   R/W   0000_0000h   11.4.1/250   4004_C040   Pin Control Register n (PORTD_PCR17)   32   R/W   0000_0000h   11.4.1/250   4004_C044   Pin Control Register n (PORTD_PCR17)   32   R/W   0000_0000h   11.4.1/250   4004_C046   Pin Control Register n (PORTD_PCR19)   32   R/W   0000_0000h   11.4.1/250   4004_C046   Pin Control Register n (PORTD_PCR20)   32   R/W   0000_0000h   11.4.1/250   4004_C054   Pin Control Register n (PORTD_PCR20)   32   R/W   0000_0000h   11.4.1/250   4004_C054   Pin Control Register n (PORTD_PCR21)   32   R/W   0000_0000h   11.4.1/250   4004_C058   Pin Control Register n (PORTD_PCR21)   32   R/W   0000_0000h   11.4.1/250   4004_C056   Pin Control Register n (PORTD_PCR22)   32   R/W   0000_0000h   11.4.1/250   4004_C056   Pin Control Register n (PORTD_PCR23)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR26)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR26)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR26)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR26)   32   R/W   0000_0000h   11.4.1/250   4004_C070   Pin Control Register n (PORTD_PCR20)   32   R/W   0000_0000h   11.4.1/250   4004_C070   Pin Control Register n (PORTD_PCR20)   32   R/W   0000_0000h   11.4.1/250   4004_C070   Pin Control Register n (PORTD_PCR20)   32   R/W   0000_0000h   11.4.1/250   4004_C070   Pin Control Register n (PORTD_PCR31)   32   R/W   0000_0000h   11.4.1/250   4004_C070   Pin Control Register n (PORTD_PCR31)   32   R/W   0000_0000h   11.4.1/250   4004_C070   Pin Cont	Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_C036	4004_C030	Pin Control Register n (PORTD_PCR12)	32	R/W	0000_0000h	11.4.1/250
4004_C03C   Pin Control Register n (PORTD_PCR15)   32   R/W   0000_0000h   11.4.1/250   4004_C040   Pin Control Register n (PORTD_PCR16)   32   R/W   0000_0000h   11.4.1/250   4004_C044   Pin Control Register n (PORTD_PCR17)   32   R/W   0000_0000h   11.4.1/250   4004_C046   Pin Control Register n (PORTD_PCR18)   32   R/W   0000_0000h   11.4.1/250   4004_C046   Pin Control Register n (PORTD_PCR18)   32   R/W   0000_0000h   11.4.1/250   4004_C050   Pin Control Register n (PORTD_PCR20)   32   R/W   0000_0000h   11.4.1/250   4004_C054   Pin Control Register n (PORTD_PCR20)   32   R/W   0000_0000h   11.4.1/250   4004_C056   Pin Control Register n (PORTD_PCR21)   32   R/W   0000_0000h   11.4.1/250   4004_C056   Pin Control Register n (PORTD_PCR22)   32   R/W   0000_0000h   11.4.1/250   4004_C056   Pin Control Register n (PORTD_PCR23)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR24)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR25)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR25)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR26)   32   R/W   0000_0000h   11.4.1/250   4004_C066   Pin Control Register n (PORTD_PCR26)   32   R/W   0000_0000h   11.4.1/250   4004_C076   Pin Control Register n (PORTD_PCR28)   32   R/W   0000_0000h   11.4.1/250   4004_C076   Pin Control Register n (PORTD_PCR28)   32   R/W   0000_0000h   11.4.1/250   4004_C076   Pin Control Register n (PORTD_PCR29)   32   R/W   0000_0000h   11.4.1/250   4004_C076   Pin Control Register n (PORTD_PCR31)   32   R/W   0000_0000h   11.4.1/250   4004_C076   Pin Control Register (PORTD_PCR31)   32   R/W   0000_0000h   11.4.1/250   4004_C080   R/W   0000	4004_C034	Pin Control Register n (PORTD_PCR13)	32	R/W	0000_0000h	11.4.1/250
4004_C040         Pin Control Register n (PORTD_PCR16)         32         R/W         0000_0000h         11.4.1/250           4004_C044         Pin Control Register n (PORTD_PCR17)         32         R/W         0000_0000h         11.4.1/250           4004_C048         Pin Control Register n (PORTD_PCR18)         32         R/W         0000_0000h         11.4.1/250           4004_C04C         Pin Control Register n (PORTD_PCR19)         32         R/W         0000_0000h         11.4.1/250           4004_C050         Pin Control Register n (PORTD_PCR20)         32         R/W         0000_0000h         11.4.1/250           4004_C054         Pin Control Register n (PORTD_PCR21)         32         R/W         0000_0000h         11.4.1/250           4004_C058         Pin Control Register n (PORTD_PCR22)         32         R/W         0000_0000h         11.4.1/250           4004_C050         Pin Control Register n (PORTD_PCR23)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR24)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR25)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PO	4004_C038	Pin Control Register n (PORTD_PCR14)	32	R/W	0000_0000h	11.4.1/250
4004_C044         Pin Control Register n (PORTD_PCR17)         32         R/W         0000_0000h         11.4.1/250           4004_C048         Pin Control Register n (PORTD_PCR18)         32         R/W         0000_0000h         11.4.1/250           4004_C04C         Pin Control Register n (PORTD_PCR19)         32         R/W         0000_0000h         11.4.1/250           4004_C050         Pin Control Register n (PORTD_PCR20)         32         R/W         0000_0000h         11.4.1/250           4004_C054         Pin Control Register n (PORTD_PCR21)         32         R/W         0000_0000h         11.4.1/250           4004_C056         Pin Control Register n (PORTD_PCR22)         32         R/W         0000_0000h         11.4.1/250           4004_C056         Pin Control Register n (PORTD_PCR23)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR24)         32         R/W         0000_0000h         11.4.1/250           4004_C064         Pin Control Register n (PORTD_PCR25)         32         R/W         0000_0000h         11.4.1/250           4004_C066         Pin Control Register n (PORTD_PCR26)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Pin Control Register n (PO	4004_C03C	Pin Control Register n (PORTD_PCR15)	32	R/W	0000_0000h	11.4.1/250
4004_C048         Pin Control Register n (PORTD_PCR18)         32         R/W         0000_0000h         11.4.1/250           4004_C04C         Pin Control Register n (PORTD_PCR19)         32         R/W         0000_0000h         11.4.1/250           4004_C050         Pin Control Register n (PORTD_PCR20)         32         R/W         0000_0000h         11.4.1/250           4004_C054         Pin Control Register n (PORTD_PCR21)         32         R/W         0000_0000h         11.4.1/250           4004_C058         Pin Control Register n (PORTD_PCR22)         32         R/W         0000_0000h         11.4.1/250           4004_C05C         Pin Control Register n (PORTD_PCR23)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR23)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR25)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR26)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PO	4004_C040	Pin Control Register n (PORTD_PCR16)	32	R/W	0000_0000h	11.4.1/250
4004_C04C         Pin Control Register n (PORTD_PCR19)         32         R/W         0000_0000h         11.4.1/250           4004_C050         Pin Control Register n (PORTD_PCR20)         32         R/W         0000_0000h         11.4.1/250           4004_C054         Pin Control Register n (PORTD_PCR21)         32         R/W         0000_0000h         11.4.1/250           4004_C058         Pin Control Register n (PORTD_PCR22)         32         R/W         0000_0000h         11.4.1/250           4004_C050         Pin Control Register n (PORTD_PCR23)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR24)         32         R/W         0000_0000h         11.4.1/250           4004_C064         Pin Control Register n (PORTD_PCR25)         32         R/W         0000_0000h         11.4.1/250           4004_C066         Pin Control Register n (PORTD_PCR26)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Pin Control Register n (PORTD_PCR27)         32         R/W         0000_0000h         11.4.1/250           4004_C077         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PO	4004_C044	Pin Control Register n (PORTD_PCR17)	32	R/W	0000_0000h	11.4.1/250
4004_C050         Pin Control Register n (PORTD_PCR20)         32         RW         0000_0000h         11.4.1/250           4004_C054         Pin Control Register n (PORTD_PCR21)         32         RW         0000_0000h         11.4.1/250           4004_C058         Pin Control Register n (PORTD_PCR22)         32         RW         0000_0000h         11.4.1/250           4004_C05C         Pin Control Register n (PORTD_PCR23)         32         RW         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR24)         32         RW         0000_0000h         11.4.1/250           4004_C064         Pin Control Register n (PORTD_PCR25)         32         RW         0000_0000h         11.4.1/250           4004_C068         Pin Control Register n (PORTD_PCR26)         32         RW         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR27)         32         RW         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         RW         0000_0000h         11.4.1/250           4004_C076         Pin Control Register n (PORTD_PCR30)         32         RW         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Register (PORTD_B	4004_C048	Pin Control Register n (PORTD_PCR18)	32	R/W	0000_0000h	11.4.1/250
4004_C054         Pin Control Register n (PORTD_PCR21)         32         RW         0000_0000h         11.4.1/250           4004_C058         Pin Control Register n (PORTD_PCR22)         32         RW         0000_0000h         11.4.1/250           4004_C05C         Pin Control Register n (PORTD_PCR23)         32         RW         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR24)         32         RW         0000_0000h         11.4.1/250           4004_C064         Pin Control Register n (PORTD_PCR25)         32         RW         0000_0000h         11.4.1/250           4004_C068         Pin Control Register n (PORTD_PCR26)         32         RW         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR27)         32         RW         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         RW         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PORTD_PCR30)         32         RW         0000_0000h         11.4.1/250           4004_C070         Global Pin Control Low Register (PORTD_GPCLR)         32         RW         0000_0000h         11.4.1/250           4004_C080         Global Pin Control High Reg	4004_C04C	Pin Control Register n (PORTD_PCR19)	32	R/W	0000_0000h	11.4.1/250
4004_C058         Pin Control Register n (PORTD_PCR22)         32         R/W         0000_0000h         11.4.1/250           4004_C05C         Pin Control Register n (PORTD_PCR23)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR24)         32         R/W         0000_0000h         11.4.1/250           4004_C068         Pin Control Register n (PORTD_PCR25)         32         R/W         0000_0000h         11.4.1/250           4004_C066         Pin Control Register n (PORTD_PCR26)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR27)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR28)         32         R/W         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Pin Control Register (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control High Regi	4004_C050	Pin Control Register n (PORTD_PCR20)	32	R/W	0000_0000h	11.4.1/250
4004_C05C         Pin Control Register n (PORTD_PCR23)         32         R/W         0000_0000h         11.4.1/250           4004_C060         Pin Control Register n (PORTD_PCR24)         32         R/W         0000_0000h         11.4.1/250           4004_C064         Pin Control Register n (PORTD_PCR25)         32         R/W         0000_0000h         11.4.1/250           4004_C068         Pin Control Register n (PORTD_PCR26)         32         R/W         0000_0000h         11.4.1/250           4004_C06C         Pin Control Register n (PORTD_PCR27)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR28)         32         R/W         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C076         Global Pin Control Low Register (PORTD_GPCLR)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Interrupt Status	4004_C054	Pin Control Register n (PORTD_PCR21)	32	R/W	0000_0000h	11.4.1/250
4004_C060         Pin Control Register n (PORTD_PCR24)         32         RW         0000_0000h         11.4.1/250           4004_C064         Pin Control Register n (PORTD_PCR25)         32         RW         0000_0000h         11.4.1/250           4004_C068         Pin Control Register n (PORTD_PCR26)         32         RW         0000_0000h         11.4.1/250           4004_C06C         Pin Control Register n (PORTD_PCR27)         32         RW         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR28)         32         RW         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         RW         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PORTD_PCR30)         32         RW         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR31)         32         RW         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W         0000_0000h         11.4.2/252           4004_C084         Interrupt Status Flag Register (PORTD_ISFR)         32         w1c         0000_0000h         11.4.4/253           4004_C0A0         Interrupt Status Fla	4004_C058	Pin Control Register n (PORTD_PCR22)	32	R/W	0000_0000h	11.4.1/250
4004_C064         Pin Control Register n (PORTD_PCR25)         32         R/W         0000_0000h         11.4.1/250           4004_C068         Pin Control Register n (PORTD_PCR26)         32         R/W         0000_0000h         11.4.1/250           4004_C06C         Pin Control Register n (PORTD_PCR27)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR28)         32         R/W         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W         0000_0000h         11.4.2/252           4004_C084         Global Pin Control High Register (PORTD_GPCHR)         32         W         0000_0000h         11.4.3/253           4004_C084         Interrupt Status Flag Register (PORTD_DFCR)         32         W         0000_0000h         11.4.4/253           4004_C0C0         Digita	4004_C05C	Pin Control Register n (PORTD_PCR23)	32	R/W	0000_0000h	11.4.1/250
4004_C068         Pin Control Register n (PORTD_PCR26)         32         R/W         0000_0000h         11.4.1/250           4004_C06C         Pin Control Register n (PORTD_PCR27)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR28)         32         R/W         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W         (always reads zero)         0000_0000h         11.4.3/253           4004_C084         Global Pin Control High Register (PORTD_GPCHR)         32         w1c         0000_0000h         11.4.3/253           4004_C0A         Interrupt Status Flag Register (PORTD_DFER)         32         w1c         0000_0000h         11.4.5/253           4004_C0C0         Digital Filter Enable Register (PORTD_DFER)         32         R/W         0000_0000h         11.4.6/255 <tr< td=""><td>4004_C060</td><td>Pin Control Register n (PORTD_PCR24)</td><td>32</td><td>R/W</td><td>0000_0000h</td><td>11.4.1/250</td></tr<>	4004_C060	Pin Control Register n (PORTD_PCR24)	32	R/W	0000_0000h	11.4.1/250
4004_C06C         Pin Control Register n (PORTD_PCR27)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR28)         32         R/W         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C070         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W (always reads zero)         0000_0000h         11.4.2/252           4004_C084         Global Pin Control High Register (PORTD_GPCHR)         32         w1c         0000_0000h         11.4.3/253           4004_C0A0         Interrupt Status Flag Register (PORTD_DFER)         32         w1c         0000_0000h         11.4.3/253           4004_C0C0         Digital Filter Enable Register (PORTD_DFER)         32         R/W         0000_0000h         11.4.5/254           4004_C0C4         Digital Filter Width Register (PORTD_DFCR)         32         R/W         0000_0000h         11.4.7/255	4004_C064	Pin Control Register n (PORTD_PCR25)	32	R/W	0000_0000h	11.4.1/250
4004_C070         Pin Control Register n (PORTD_PCR28)         32         R/W         0000_0000h         11.4.1/250           4004_C074         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C07C         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W (always reads zero)         0000_0000h         11.4.2/252           4004_C084         Interrupt Status Flag Register (PORTD_ISFR)         32         w1c         0000_0000h         11.4.3/253           4004_C0A0         Interrupt Status Flag Register (PORTD_DFER)         32         W1c         0000_0000h         11.4.4/253           4004_C0C0         Digital Filter Enable Register (PORTD_DFER)         32         R/W         0000_0000h         11.4.6/255           4004_C0C4         Digital Filter Width Register (PORTD_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_D000         Pin Control Register n (PORTE_PCR0)         32         R/W         0000_0000h         11.4.1/250	4004_C068	Pin Control Register n (PORTD_PCR26)	32	R/W	0000_0000h	11.4.1/250
4004_C074         Pin Control Register n (PORTD_PCR29)         32         R/W         0000_0000h         11.4.1/250           4004_C078         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C07C         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W (always reads zero)         0000_0000h         11.4.2/252           4004_C084         Global Pin Control High Register (PORTD_GPCHR)         32         W1c         0000_0000h         11.4.3/253           4004_C0A0         Interrupt Status Flag Register (PORTD_ISFR)         32         w1c         0000_0000h         11.4.4/253           4004_C0C0         Digital Filter Enable Register (PORTD_DFER)         32         R/W         0000_0000h         11.4.5/254           4004_C0C4         Digital Filter Clock Register (PORTD_DFCR)         32         R/W         0000_0000h         11.4.6/255           4004_C0C8         Digital Filter Width Register (PORTD_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_D000         Pin Control Register n (PORTE_PCR0)         32         R/W         0000_0000h         11.4.1/250	4004_C06C	Pin Control Register n (PORTD_PCR27)	32	R/W	0000_0000h	11.4.1/250
4004_C078         Pin Control Register n (PORTD_PCR30)         32         R/W         0000_0000h         11.4.1/250           4004_C07C         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W (always reads zero)         0000_0000h         11.4.2/252           4004_C084         Global Pin Control High Register (PORTD_GPCHR)         32         W1c         0000_0000h         11.4.3/253           4004_C0A0         Interrupt Status Flag Register (PORTD_ISFR)         32         W1c         0000_0000h         11.4.4/253           4004_C0C0         Digital Filter Enable Register (PORTD_DFER)         32         R/W         0000_0000h         11.4.5/254           4004_C0C4         Digital Filter Clock Register (PORTD_DFCR)         32         R/W         0000_0000h         11.4.6/255           4004_C0C8         Digital Filter Width Register (PORTD_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_D000         Pin Control Register n (PORTE_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_D008         Pin Control Register n (PORTE_PCR2)         32         R/W         0000_0000h         11.4.1/250	4004_C070	Pin Control Register n (PORTD_PCR28)	32	R/W	0000_0000h	11.4.1/250
4004_C07C         Pin Control Register n (PORTD_PCR31)         32         R/W         0000_0000h         11.4.1/250           4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         W (always reads zero)         0000_0000h         11.4.2/252           4004_C084         Global Pin Control High Register (PORTD_GPCHR)         32         W (always reads zero)         0000_0000h         11.4.3/253           4004_C0A0         Interrupt Status Flag Register (PORTD_ISFR)         32         w1c         0000_0000h         11.4.4/253           4004_C0C0         Digital Filter Enable Register (PORTD_DFER)         32         R/W         0000_0000h         11.4.5/254           4004_C0C4         Digital Filter Clock Register (PORTD_DFCR)         32         R/W         0000_0000h         11.4.6/255           4004_C0C8         Digital Filter Width Register (PORTD_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_D000         Pin Control Register n (PORTE_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_D008         Pin Control Register n (PORTE_PCR1)         32         R/W         0000_0000h         11.4.1/250	4004_C074	Pin Control Register n (PORTD_PCR29)	32	R/W	0000_0000h	11.4.1/250
4004_C080 Global Pin Control Low Register (PORTD_GPCLR)  32	4004_C078	Pin Control Register n (PORTD_PCR30)	32	R/W	0000_0000h	11.4.1/250
4004_C080         Global Pin Control Low Register (PORTD_GPCLR)         32         (always reads zero)         0000_0000h         11.4.2/252           4004_C084         Global Pin Control High Register (PORTD_GPCHR)         32         W (always reads zero)         0000_0000h         11.4.3/253           4004_C0A0         Interrupt Status Flag Register (PORTD_ISFR)         32         W1c         0000_0000h         11.4.4/253           4004_C0C0         Digital Filter Enable Register (PORTD_DFER)         32         R/W         0000_0000h         11.4.5/254           4004_C0C4         Digital Filter Clock Register (PORTD_DFCR)         32         R/W         0000_0000h         11.4.6/255           4004_C0C8         Digital Filter Width Register (PORTD_DFWR)         32         R/W         0000_0000h         11.4.7/255           4004_D000         Pin Control Register n (PORTE_PCR0)         32         R/W         0000_0000h         11.4.1/250           4004_D004         Pin Control Register n (PORTE_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_D008         Pin Control Register n (PORTE_PCR2)         32         R/W         0000_0000h         11.4.1/250	4004_C07C	Pin Control Register n (PORTD_PCR31)	32	R/W	0000_0000h	11.4.1/250
4004_C084       Global Pin Control High Register (PORTD_GPCHR)       32       (always reads zero)       0000_0000h       11.4.3/253         4004_C0A0       Interrupt Status Flag Register (PORTD_ISFR)       32       w1c       0000_0000h       11.4.4/253         4004_C0C0       Digital Filter Enable Register (PORTD_DFER)       32       R/W       0000_0000h       11.4.5/254         4004_C0C4       Digital Filter Clock Register (PORTD_DFCR)       32       R/W       0000_0000h       11.4.6/255         4004_C0C8       Digital Filter Width Register (PORTD_DFWR)       32       R/W       0000_0000h       11.4.7/255         4004_D000       Pin Control Register n (PORTE_PCR1)       32       R/W       0000_0000h       11.4.1/250         4004_D008       Pin Control Register n (PORTE_PCR2)       32       R/W       0000_0000h       11.4.1/250	4004_C080	Global Pin Control Low Register (PORTD_GPCLR)	32	(always reads	0000_0000h	11.4.2/252
4004_C0C0       Digital Filter Enable Register (PORTD_DFER)       32       R/W       0000_0000h       11.4.5/254         4004_C0C4       Digital Filter Clock Register (PORTD_DFCR)       32       R/W       0000_0000h       11.4.6/255         4004_C0C8       Digital Filter Width Register (PORTD_DFWR)       32       R/W       0000_0000h       11.4.7/255         4004_D000       Pin Control Register n (PORTE_PCR0)       32       R/W       0000_0000h       11.4.1/250         4004_D004       Pin Control Register n (PORTE_PCR1)       32       R/W       0000_0000h       11.4.1/250         4004_D008       Pin Control Register n (PORTE_PCR2)       32       R/W       0000_0000h       11.4.1/250	4004_C084	Global Pin Control High Register (PORTD_GPCHR)	32	(always reads	0000_0000h	11.4.3/253
4004_C0C4       Digital Filter Clock Register (PORTD_DFCR)       32       R/W       0000_0000h       11.4.6/255         4004_C0C8       Digital Filter Width Register (PORTD_DFWR)       32       R/W       0000_0000h       11.4.7/255         4004_D000       Pin Control Register n (PORTE_PCR0)       32       R/W       0000_0000h       11.4.1/250         4004_D004       Pin Control Register n (PORTE_PCR1)       32       R/W       0000_0000h       11.4.1/250         4004_D008       Pin Control Register n (PORTE_PCR2)       32       R/W       0000_0000h       11.4.1/250	4004_C0A0	Interrupt Status Flag Register (PORTD_ISFR)	32	w1c	0000_0000h	11.4.4/253
4004_C0C8       Digital Filter Width Register (PORTD_DFWR)       32       R/W       0000_0000h       11.4.7/255         4004_D000       Pin Control Register n (PORTE_PCR0)       32       R/W       0000_0000h       11.4.1/250         4004_D004       Pin Control Register n (PORTE_PCR1)       32       R/W       0000_0000h       11.4.1/250         4004_D008       Pin Control Register n (PORTE_PCR2)       32       R/W       0000_0000h       11.4.1/250	4004_C0C0	Digital Filter Enable Register (PORTD_DFER)	32	R/W	0000_0000h	11.4.5/254
4004_D000       Pin Control Register n (PORTE_PCR0)       32       R/W       0000_0000h       11.4.1/250         4004_D004       Pin Control Register n (PORTE_PCR1)       32       R/W       0000_0000h       11.4.1/250         4004_D008       Pin Control Register n (PORTE_PCR2)       32       R/W       0000_0000h       11.4.1/250	4004_C0C4	Digital Filter Clock Register (PORTD_DFCR)	32	R/W	0000_0000h	11.4.6/255
4004_D004         Pin Control Register n (PORTE_PCR1)         32         R/W         0000_0000h         11.4.1/250           4004_D008         Pin Control Register n (PORTE_PCR2)         32         R/W         0000_0000h         11.4.1/250	4004_C0C8	Digital Filter Width Register (PORTD_DFWR)	32	R/W	0000_0000h	11.4.7/255
4004_D008 Pin Control Register n (PORTE_PCR2) 32 R/W 0000_0000h 11.4.1/250	4004_D000	Pin Control Register n (PORTE_PCR0)	32	R/W	0000_0000h	11.4.1/250
, , ,	4004_D004	Pin Control Register n (PORTE_PCR1)	32	R/W	0000_0000h	11.4.1/250
4004_D00C Pin Control Register n (PORTE_PCR3) 32 R/W 0000_0000h 11.4.1/250	4004_D008	Pin Control Register n (PORTE_PCR2)	32	R/W	0000_0000h	11.4.1/250
	4004_D00C	Pin Control Register n (PORTE_PCR3)	32	R/W	0000_0000h	11.4.1/250



# PORT memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_D010	Pin Control Register n (PORTE_PCR4)	32	R/W	0000_0000h	11.4.1/250
4004_D014	Pin Control Register n (PORTE_PCR5)	32	R/W	0000_0000h	11.4.1/250
4004_D018	Pin Control Register n (PORTE_PCR6)	32	R/W	0000_0000h	11.4.1/250
4004_D01C	Pin Control Register n (PORTE_PCR7)	32	R/W	0000_0000h	11.4.1/250
4004_D020	Pin Control Register n (PORTE_PCR8)	32	R/W	0000_0000h	11.4.1/250
4004_D024	Pin Control Register n (PORTE_PCR9)	32	R/W	0000_0000h	11.4.1/250
4004_D028	Pin Control Register n (PORTE_PCR10)	32	R/W	0000_0000h	11.4.1/250
4004_D02C	Pin Control Register n (PORTE_PCR11)	32	R/W	0000_0000h	11.4.1/250
4004_D030	Pin Control Register n (PORTE_PCR12)	32	R/W	0000_0000h	11.4.1/250
4004_D034	Pin Control Register n (PORTE_PCR13)	32	R/W	0000_0000h	11.4.1/250
4004_D038	Pin Control Register n (PORTE_PCR14)	32	R/W	0000_0000h	11.4.1/250
4004_D03C	Pin Control Register n (PORTE_PCR15)	32	R/W	0000_0000h	11.4.1/250
4004_D040	Pin Control Register n (PORTE_PCR16)	32	R/W	0000_0000h	11.4.1/250
4004_D044	Pin Control Register n (PORTE_PCR17)	32	R/W	0000_0000h	11.4.1/250
4004_D048	Pin Control Register n (PORTE_PCR18)	32	R/W	0000_0000h	11.4.1/250
4004_D04C	Pin Control Register n (PORTE_PCR19)	32	R/W	0000_0000h	11.4.1/250
4004_D050	Pin Control Register n (PORTE_PCR20)	32	R/W	0000_0000h	11.4.1/250
4004_D054	Pin Control Register n (PORTE_PCR21)	32	R/W	0000_0000h	11.4.1/250
4004_D058	Pin Control Register n (PORTE_PCR22)	32	R/W	0000_0000h	11.4.1/250
4004_D05C	Pin Control Register n (PORTE_PCR23)	32	R/W	0000_0000h	11.4.1/250
4004_D060	Pin Control Register n (PORTE_PCR24)	32	R/W	0000_0000h	11.4.1/250
4004_D064	Pin Control Register n (PORTE_PCR25)	32	R/W	0000_0000h	11.4.1/250
4004_D068	Pin Control Register n (PORTE_PCR26)	32	R/W	0000_0000h	11.4.1/250
4004_D06C	Pin Control Register n (PORTE_PCR27)	32	R/W	0000_0000h	11.4.1/250
4004_D070	Pin Control Register n (PORTE_PCR28)	32	R/W	0000_0000h	11.4.1/250
4004_D074	Pin Control Register n (PORTE_PCR29)	32	R/W	0000_0000h	11.4.1/250
4004_D078	Pin Control Register n (PORTE_PCR30)	32	R/W	0000_0000h	11.4.1/250
4004_D07C	Pin Control Register n (PORTE_PCR31)	32	R/W	0000_0000h	11.4.1/250
4004_D080	Global Pin Control Low Register (PORTE_GPCLR)	32	W (always reads zero)	0000_0000h	11.4.2/252
4004_D084	Global Pin Control High Register (PORTE_GPCHR)	32	W (always reads zero)	0000_0000h	11.4.3/253





### **PORT memory map (continued)**

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_D0A0	Interrupt Status Flag Register (PORTE_ISFR)	32	w1c	0000_0000h	11.4.4/253
4004_D0C0	Digital Filter Enable Register (PORTE_DFER)	32	R/W	0000_0000h	11.4.5/254
4004_D0C4	Digital Filter Clock Register (PORTE_DFCR)	32	R/W	0000_0000h	11.4.6/255
4004_D0C8	Digital Filter Width Register (PORTE_DFWR)	32	R/W	0000_0000h	11.4.7/255

# 11.4.1 Pin Control Register n (PORTx\_PCRn)

For PCR1 to PCR5 of the port A, bit 0, 1, 6, 8, 9,10 reset to 1; for the PCR0 of the port A, bit 1, 6, 8, 9, 10 reset to 1; in other conditions, all bits reset to 0.





### PORTx\_PCRn field descriptions

Field	Description
31–25 Reserved	This read-only field is reserved and always has the value zero.
24 ISF	Interrupt Status Flag  The pin interrupt configuration is valid in all digital pin muxing modes.  Configured interrupt has not been detected.  Configured interrupt has been detected. If pin is configured to generate a DMA request then the corresponding flag will be cleared automatically at the completion of the requested DMA transfer, otherwise the flag remains set until a logic one is written to that flag. If configured for a level sensitive
23–20 Reserved	interrupt that remains asserted then flag will set again immediately.  This read-only field is reserved and always has the value zero.
19–16 IRQC	Interrupt Configuration  The pin interrupt configuration is valid in all digital pin muxing modes. The corresponding pin is configured to generate interrupt / DMA Request as follows:  0000



# PORTx\_PCRn field descriptions (continued)

Field	Description
	1001 Interrupt on rising edge. 1010 Interrupt on falling edge. 1011 Interrupt on either edge. 1100 Interrupt when logic one. Others Reserved.
15 LK	Lock Register  O Pin Control Register bits [15:0] are not locked.  Pin Control Register bits [15:0] are locked and cannot be updated until the next System Reset.
14–11 Reserved	This read-only field is reserved and always has the value zero.
10–8 MUX	Pin Mux Control  The corresponding pin is configured as follows:  000 Pin Disabled (Analog).  001 Alternative 1 (GPIO).  010 Alternative 2 (chip specific).  011 Alternative 3 (chip specific).  100 Alternative 4 (chip specific).  101 Alternative 5 (chip specific).  110 Alternative 6 (chip specific).  111 Alternative 7 (chip specific / JTAG / NMI).
7 Reserved	This read-only field is reserved and always has the value zero.
6 DSE	Drive Strength Enable  Drive Strength configuration is valid in all digital pin muxing modes.  Under the configuration is valid in all digital pin muxing modes.  How drive strength is configured on the corresponding pin, if pin is configured as a digital output.  High drive strength is configured on the corresponding pin, if pin is configured as a digital output.
5 ODE	Open Drain Enable  Open Drain configuration is valid in all digital pin muxing modes.  Open Drain output is disabled on the corresponding pin.  Open Drain output is enabled on the corresponding pin, provided pin is configured as a digital output.
4 PFE	Passive Filter Enable  Passive Filter configuration is valid in all digital pin muxing modes.  O Passive Input Filter is disabled on the corresponding pin.  Passive Input Filter is enabled on the corresponding pin, provided pin is configured as a digital input. A low pass filter (10 MHz to 30 MHz bandwidth) is enabled on the digital input path. Disable the Passive Input Filter when supporting high speed interfaces (> 2 MHz) on the pin.
3 Reserved	This read-only field is reserved and always has the value zero.



#### wemory map and register definition

### PORTx\_PCRn field descriptions (continued)

Field	Description
2 SRE	Slew Rate Enable
OFFE	Slew Rate configuration is valid in all digital pin muxing modes.
	0 Fast slew rate is configured on the corresponding pin, if pin is configured as a digital output.
	1 Slow slew rate is configured on the corresponding pin, if pin is configured as a digital output.
1 PE	Pull Enable
	Pull configuration is valid in all digital pin muxing modes.
	0 Internal pull-up or pull-down resistor is not enabled on the corresponding pin.
	1 Internal pull-up or pull-down resistor is enabled on the corresponding pin, provided pin is configured as a digital input.
0 PS	Pull Select
	Pull configuration is valid in all digital pin muxing modes.
	0 Internal pull-down resistor is enabled on the corresponding pin, if the corresponding Port Pull Enable Register bit is set.
	1 Internal pull-up resistor is enabled on the corresponding pin, if the corresponding Port Pull Enable Register bit is set.


# 11.4.2 Global Pin Control Low Register (PORTx\_GPCLR)

Addresses: PORTA\_GPCLR is 4004\_9000h base + 80h offset = 4004\_9080h PORTB\_GPCLR is 4004\_A000h base + 80h offset = 4004\_A080h

PORTC\_GPCLR is 4004\_B000h base + 80h offset = 4004\_B080h

PORTD\_GPCLR is 4004\_C000h base + 80h offset = 4004\_C080h

PORTE\_GPCLR is 4004\_D000h base + 80h offset = 4004\_D080h




#### PORTx\_GPCLR field descriptions

Field	Description
31–16 GPWE	Global Pin Write Enable  When set, causes bits [15:0] of the corresponding Pin Control Register (15 through 0) to update with the value in the Global Pin Write Data field.
15–0 GPWD	Global Pin Write Data  Value to be written to bits [15:0] of all Pin Control Registers that are enabled by the Global Pin Write Enable field, provided the corresponding register has not been locked.



## 11.4.3 Global Pin Control High Register (PORTx\_GPCHR)

Addresses: PORTA\_GPCHR is 4004\_9000h base + 84h offset = 4004\_9084h
PORTB\_GPCHR is 4004\_A000h base + 84h offset = 4004\_A084h
PORTC\_GPCHR is 4004\_B000h base + 84h offset = 4004\_B084h
PORTD\_GPCHR is 4004\_C000h base + 84h offset = 4004\_C084h
PORTE\_GPCHR is 4004\_D000h base + 84h offset = 4004\_D084h




#### PORTx\_GPCHR field descriptions

Field	Description
31–16 GPWE	Global Pin Write Enable
	When set, causes bits [15:0] of the corresponding Pin Control Register (31 through 16) to update with the value in the Global Pin Write Data field.
15–0 GPWD	Global Pin Write Data
	Value to be written to bits [15:0] of all Pin Control Registers that are enabled by the Global Pin Write Enable field, provided the corresponding register has not been locked.

## 11.4.4 Interrupt Status Flag Register (PORTx\_ISFR)

The pin interrupt configuration is valid in all digital pin muxing modes. The Interrupt Status Flag for each pin is also visible in the corresponding Pin Control Register, and each flag can be cleared in either location.

Addresses: PORTA\_ISFR is 4004\_9000h base + A0h offset = 4004\_90A0h PORTB\_ISFR is 4004\_A000h base + A0h offset = 4004\_A0A0h PORTC\_ISFR is 4004\_B000h base + A0h offset = 4004\_B0A0h PORTD\_ISFR is 4004\_C000h base + A0h offset = 4004\_C0A0h PORTE\_ISFR is 4004\_D000h base + A0h offset = 4004\_D0A0h





#### wemory map and register definition


## PORTx\_ISFR field descriptions

Field	Description
31–0 ISF	Interrupt Status Flag  Each bit in the field indicates the detection of the configured interrupt of the same number as the bit.
	O Configured interrupt has not been detected.  Configured interrupt has been detected. If pin is configured to generate a DMA request then the corresponding flag will be cleared automatically at the completion of the requested DMA transfer, otherwise the flag remains set until a logic one is written to the flag. If configured for a level sensitive interrupt and the pin remains asserted then the flag will set again immediately after it is cleared.

## 11.4.5 Digital Filter Enable Register (PORTx\_DFER)

0 0 0 0 0

0



#### PORTx\_DFER field descriptions

0 0 0 0 0

0

0 0

0 0

0

Field	Description
31–0 DFE	Digital Filter Enable
_, _	The digital filter configuration is valid in all digital pin muxing modes. The output of each digital filter is reset to zero at system reset and whenever the digital filter is disabled.
	O Digital Filter is disabled on the corresponding pin and output of the digital filter is reset to zero. Each bit in the field enables the digital filter of the same number as the bit.
	1 Digital Filter is enabled on the corresponding pin, provided pin is configured as a digital input.

Reset 0

0


0 0

0 0 0



## 11.4.6 Digital Filter Clock Register (PORTx\_DFCR)

Addresses: PORTA\_DFCR is 4004\_9000h base + C4h offset = 4004\_90C4h
PORTB\_DFCR is 4004\_A000h base + C4h offset = 4004\_A0C4h
PORTC\_DFCR is 4004\_B000h base + C4h offset = 4004\_B0C4h
PORTD\_DFCR is 4004\_C000h base + C4h offset = 4004\_C0C4h
PORTE\_DFCR is 4004\_D000h base + C4h offset = 4004\_D0C4h



#### **PORTx\_DFCR** field descriptions


Field	Description							
31–1 Reserved	s read-only field is reserved and always has the value zero.							
0 CS	Clock Source  The digital filter configuration is valid in all digital pin muxing modes. Configures the clock source for the digital input filters. Changing the filter clock source should only be done after disabling all enabled digital filters.							
	<ul><li>Digital Filters are clocked by the bus clock.</li><li>Digital Filters are clocked by the 1 kHz LPO clock.</li></ul>							

## 11.4.7 Digital Filter Width Register (PORTx\_DFWR)

The digital filter configuration is valid in all digital pin muxing modes.

Addresses: PORTA\_DFWR is 4004\_9000h base + C8h offset = 4004\_90C8h
PORTB\_DFWR is 4004\_A000h base + C8h offset = 4004\_A0C8h
PORTC\_DFWR is 4004\_B000h base + C8h offset = 4004\_B0C8h
PORTD\_DFWR is 4004\_C000h base + C8h offset = 4004\_C0C8h

PORTE\_DFWR is 4004\_D000h base + C8h offset = 4004\_D0C8h





#### runctional description

#### PORTx\_DFWR field descriptions

Field	Description
31–5 Reserved	This read-only field is reserved and always has the value zero.
4–0 FILT	Filter Length  The digital filter configuration is valid in all digital pin muxing modes. Configures the maximum size of the glitches (in clock cycles) the digital filter absorbs for enabled digital filters. Glitches that are longer than this register setting (in clock cycles) will pass through the digital filter, while glitches that are equal to or less than this register setting (in clock cycles) will be filtered. Changing the filter length should only be done after disabling all enabled filters.

# 11.5 Functional description

#### 11.5.1 Pin control

The lower half of the pin control register configures the following functions for each pin within the 32-bit port. These functions apply across all digital pin muxing modes and individual peripherals do not override the configuration in this register (for example, if an I<sup>2</sup>C function is enabled on a pin then that does not override the pullup or open drain configuration for that pin).

When the pin muxing mode is configured for analog/disabled then the all digital functions on that pin are disabled. This includes the pullup and pulldown enables, digital output buffer enable, digital input buffer enable and passive filter enable.

- Pullup or pulldown enable
- Drive strength and slew rate configuration
- Open drain enable
- Passive input filter enable
- Pin muxing mode

A lock bit also exists that allows the configuration for each pin to be locked until the next system reset. Once locked, writes to the lower half of that pin control register are ignored, although a bus error is not generated on an attempted write to a locked register.

The configuration of each pin control register is retained when the PORT module is disabled.



## 11.5.2 Global pin control

The two global pin control registers allow a single register write to update the lower half of the pin control register on up to sixteen pins, all with the same value. Registers that are locked cannot be written using the global pin control registers.

The global pin control registers are designed to enable software to quickly configure multiple pins within the one port for the same peripheral function. Note however that interrupt functions are unable to be configured using the global pin control registers.

The global pin control registers are write only registers, that always read as zero.

## 11.5.3 External interrupts

The external interrupt capability of the PORT module are available in all digital pin muxing modes provided the PORT module is enabled.

Each pin can be individually configured for any of the following external interrupt modes:

- Interrupt disabled (default out of reset)
- Active high level sensitive interrupt
- Active low level sensitive interrupt
- Rising edge sensitive interrupt
- Falling edge sensitive interrupt
- Rising and falling edge sensitive interrupt
- Rising edge sensitive DMA request
- Falling edge sensitive DMA request
- Rising and falling edge sensitive DMA request

The interrupt status flag is set when the configured edge or level is detected on the output of the digital filter (if enabled) or pin (if digital filter is bypassed). When not in stop mode, the input is first synchronized to the bus clock to detect the configured level or edge transition.

The PORT module generates a single interrupt that asserts when the interrupt status flag is set for any enabled interrupt for that port. The interrupt negates once the interrupt status flags for all enabled interrupts have been cleared.

The PORT module generates a single DMA request that asserts when the interrupt status flag is set for any enabled DMA request in that port. The DMA request negates once the DMA transfer has been completed, since that clears the interrupt status flags for all enabled DMA requests.



#### runctional description

During stop mode, the interrupt status flag for any enabled interrupt (but not DMA request) will asynchronously set if the required level or edge is detected. This also generates an asynchronous wakeup signal to exit the low power mode.

## 11.5.4 Digital filter

The digital filter capabilities of the PORT module are available in all digital pin muxing modes provided the PORT module is enabled.

The clock used for all digital filters within the one port can be configured between the bus clock or the 1 kHz LPO clock. This selection should be changed only when all digital filters for that port are disabled. If the digital filters for a port are configured to use the bus clock, then the digital filters are bypassed (and do not update) during stop mode.

The filter width in clock size is the same for all enabled digital filters within the one port and should be changed only when all digital filters for that port are disabled.

The output of each digital filter is logic zero after system reset and whenever a digital filter is disabled. Once a digital filter is enabled, the input is synchronized to the filter clock (either the bus clock or the 1 kHz LPO clock). If the synchronized input and the output of the digital filter remain different for a number of filter clock cycles equal to the filter width register configuration, then the output of the digital filter updates to equal the synchronized filter input.

The minimum latency through a digital filter equals two or three filter clock cycles plus the filter width configuration register.



# **Chapter 12 System integration module (SIM)**

## 12.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The system integration module (SIM) provides system control and chip configuration registers.

## 12.1.1 Features

- Configuration for system clocking
  - Clock source selection for SDHC, I<sup>2</sup>S, USB, and PLL/FLL source
  - System clock divide values
  - I<sup>2</sup>S and USB clock divide values
- Architectural clock gating control
- Flash configuration
- USB regulator configuration
- RAM size configuration
- Flextimer external clock and fault source selection
- UART0 and UART1 receive/transmit source selection/configuration
- Reset pin filtering

## 12.1.2 Modes of operation

- Run mode
- Sleep mode
- Deep sleep mode
- VLLS mode



## 12.1.3 SIM Signal Descriptions

**Table 12-1. SIM Signal Descriptions** 

Signa I	Description	I/O
EZP_ CS	EzPort mode select	I

## 12.1.3.1 Detailed signal description

Table 12-2. SIM interface-detailed signal descriptions

Signal	I/O	Description							
EZP_CS	I	EZ	PORT mode select						
		State meaning	Assertion-0 - Configure part for EZPORT mode						
			Negation- 1 - Configure part for normal flash operation						
		Timing	As a mode select, this signal is only recognized during reset although it can be asserted and negated at any time.						
			Assertion-May occur at any time; input may be asserted asynchronously to the system clock.						
			Negation-May occur at any time; input may be negated asynchronously to the system clock.						

# 12.2 Memory map and register definition

The SIM module contains many bitfields for selecting the clock source and dividers for various module clocks. See the Clock Distribution chapter for more information including block diagrams and clock definitions.

#### NOTE

The SIM\_SOPT1 register is located at a different base address than the other SIM registers.



## SIM memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page		
4004_7000	System Options Register 1 (SIM_SOPT1) 32 R/W Undefined						
4004_8004	System Options Register 2 (SIM_SOPT2)	32	R/W	0000_1000h	12.2.2/264		
4004_800C	System Options Register 4 (SIM_SOPT4)	32	R/W	0000_0000h	12.2.3/266		
4004_8010	System Options Register 5 (SIM_SOPT5)	32	R/W	0000_0000h	12.2.4/269		
4004_8014	System Options Register 6 (SIM_SOPT6)	32	R/W	0000_0000h	12.2.5/270		
4004_8018	System Options Register 7 (SIM_SOPT7)	32	R/W	0000_0000h	12.2.6/271		
4004_8024	System Device Identification Register (SIM_SDID)	32	R	Undefined	12.2.7/273		
4004_8028	System Clock Gating Control Register 1 (SIM_SCGC1)	32	R/W	0000_0000h	12.2.8/274		
4004_802C	System Clock Gating Control Register 2 (SIM_SCGC2)	32	R/W	0000_0000h	12.2.9/275		
4004_8030	System Clock Gating Control Register 3 (SIM_SCGC3)	32	R/W	0000_0000h	12.2.10/ 276		
4004_8034	System Clock Gating Control Register 4 (SIM_SCGC4)	32	R/W	6010_0030h	12.2.11/ 277		
4004_8038	System Clock Gating Control Register 5 (SIM_SCGC5)	32	R/W	0004_0180h	12.2.12/ 280		
4004_803C	System Clock Gating Control Register 6 (SIM_SCGC6)	32	R/W	4000_0001h	12.2.13/ 282		
4004_8040	System Clock Gating Control Register 7 (SIM_SCGC7)	32	R/W	0000_0007h	12.2.14/ 284		
4004_8044	System Clock Divider Register 1 (SIM_CLKDIV1)	32	R/W	Undefined	12.2.15/ 285		
4004_8048	System Clock Divider Register 2 (SIM_CLKDIV2)	32	R/W	0000_0000h	12.2.16/ 288		
4004_804C	Flash Configuration Register 1 (SIM_FCFG1)	32	R	Undefined	12.2.17/ 289		
4004_8050	Flash Configuration Register 2 (SIM_FCFG2)	32	R	Undefined	12.2.18/ 290		
4004_8054	Unique Identification Register High (SIM_UIDH)	32	R	Undefined	12.2.19/ 291		
4004_8058	Unique Identification Register Mid-High (SIM_UIDMH)	32	R	Undefined	12.2.20/ 292		
4004_805C	Unique Identification Register Mid Low (SIM_UIDML)	32	R	Undefined	12.2.21/ 292		
4004_8060	Unique Identification Register Low (SIM_UIDL)	32	R	Undefined	12.2.22/ 293		



## 12.2.1 System Options Register 1 (SIM\_SOPT1)

The reset value of the SOPT1 register is as follows: Exit from POR and LVD: USBREGEN is set, USBSTBY is cleared, and OSC32KSEL is cleared. Exit from VLLS or other system reset: USBREGEN, USBSTBY and OSC32KSEL are unaffected

Address: SIM\_SOPT1 is 4004\_7000h base + 0h offset = 4004\_7000h

Bit	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
R	EGEN STBY	TBY		4		0		MS		0		KSEL		0		
w	USBREGEN	USBSTBY	r	Reserve	u								OSC32KSEL			
Reset	<b>x</b> *	x*	<b>x</b> *	X*	x*	<b>X</b> *	X*	X*	<b>x</b> *	х*	<b>x</b> *	<b>X</b> *	X*	X*	<b>X</b> *	X*
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
R		RAM	SIZE							(	)					
w																
Reset	X*	X*	X*	X*	X*	X*	Х*	<b>X</b> *	Х*	Х*	<b>X</b> *	Х*	Х*	X*	Х*	X*

<sup>\*</sup> Notes:

#### SIM\_SOPT1 field descriptions

Field	Description
31 USBREGEN	USB voltage regulator enable
00211201211	Controls whether the USB voltage regulator is enabled.
	0 USB voltage regulator is disabled.
	1 USB voltage regulator is enabled.
30 USBSTBY	USB voltage regulator in standby mode
	Controls whether the USB voltage regulator is placed in standby mode.
	0 USB voltage regulator not in standby.
	1 USB voltage regulator in standby.
29–27 Reserved	This field is reserved.
26–24 Reserved	This read-only field is reserved and always has the value zero.
23 MS	EzPort chip select pin state
	Reflects the state of the EzPort chip select (EZP_CS) pin during the last reset. This bit is read-only.

<sup>•</sup> x = Undefined at reset.




# SIM\_SOPT1 field descriptions (continued)


Field	Description							
22–20 Reserved	This read-only field is reserved and always has the value zero.							
19 OSC32KSEL	32K oscillator clock select  Selects the 32 kHz clock source (ERCLK32K) for TSI and LPTMR. This bit is reset only for POR/LVD.  0 System oscillator (OSC32KCLK)  1 RTC oscillator							
18–16 Reserved	This read-only field is reserved and always has the value zero.							
15-12 RAMSIZE	RAM size This field specifies the amount of system RAM available on the device.  0000 Undefined 0001 Undefined 0010 Undefined 0011 Undefined 0100 Undefined 0110 Undefined 0101 32 KBytes 0110 Undefined 0111 64 KBytes 1000 96 KBytes 1001 128 KBytes 1010 Undefined 1011 Undefined 1011 Undefined 1110 Undefined 1110 Undefined 1110 Undefined 1111 Undefined							
11–0 Reserved	This read-only field is reserved and always has the value zero.							



## 12.2.2 System Options Register 2 (SIM\_SOPT2)

SOPT2 contains the controls for selecting many of the module clock source options on this device. See the Clock Distribution chapter for more information including clocking diagrams and definitions of device clocks.





#### SIM\_SOPT2 field descriptions

Field	Description						
31–30 Reserved	This read-only field is reserved and always has the value zero.						
29–28 SDHCSRC	SDHC clock source select Selects the clock source for the SDHC clock.						
	00 Core/system clock.						
	01 MCGPLLCLK/MCGFLLCLK clock						
	10 OSCERCLK clock						
	11 External bypass clock (SDHC0_CLKIN)						
27–26 Reserved	This read-only field is reserved and always has the value zero.						
25–24 I2SSRC	I2S master clock source select						
	Selects the clock source for I <sup>2</sup> S master clock.						
	00 Core/system clock divided by the I <sup>2</sup> S fractional clock divider. See the SIM_CLKDIV2[I2SFRAC, I2SDIV] descriptions.						
	01 MCGPLLCLK/MCGFLLCLK clock divided by the I <sup>2</sup> S fractional clock divider. See the SIM_CLKDIV2[I2SFRAC, I2SDIV] descriptions.						



# SIM\_SOPT2 field descriptions (continued)

Field	Description
	10 OSCERCLK clock
	11 External bypass clock (I2S0_CLKIN)
23–22 Reserved	This read-only field is reserved and always has the value zero.
21–20 Reserved	This read-only field is reserved and always has the value zero.
19 Reserved	This read-only field is reserved and always has the value zero.
18	USB clock source select
USBSRC	Selects the clock source for the USB 48 MHz clock.
	0 External bypass clock (USB_CLKIN).
	MCGPLLCLK/MCGFLLCLK clock divided by the USB fractional divider. See the SIM_CLKDIV2[USBFRAC, USBDIV] descriptions.
17 Reserved	This read-only field is reserved and always has the value zero.
16	PLL/FLL clock select
PLLFLLSEL	Selects the MCGPLLCLK or MCGFLLCLK clock for various peripheral clocking options.
	0 MCGFLLCLK clock
	1 MCGPLLCLK clock
15–13 Reserved	This read-only field is reserved and always has the value zero.
12	Debug trace clock select
TRACECLKSEL	Selects the core/system clock or MCG output clock (MCGOUTCLK) as the trace clock source.
	0 MCGOUTCLK
	1 Core/system clock
11	CMT/UART pad drive strength
CMTUARTPAD	Controls the output drive strength of the CMT IRO signal or UART0_TXD signal on PTD7 pin by selecting either one or two pads to drive it.
	<ul><li>0 Single-pad drive strength for CMT IRO or UART0_TXD.</li><li>1 Dual-pad drive strength for CMT IRO or UART0_TXD.</li></ul>
10 Reserved	This read-only field is reserved and always has the value zero.
9–8 FBSL	FlexBus security level
	If flash security is enabled, then this field affects what CPU operations can access off-chip via the FlexBus interface. This field has no effect if flash security is not enabled.
	00 All off-chip accesses (instruction and data) via the FlexBus are disallowed.
	01 All off-chip accesses (instruction and data) via the FlexBus are disallowed.




#### wemory map and register definition

## SIM\_SOPT2 field descriptions (continued)

Field	Description
	10 Off-chip instruction accesses are disallowed. Data accesses are allowed. 11 Off-chip instruction accesses and data accesses are allowed.
7–1 Reserved	This read-only field is reserved and always has the value zero.
0 MCGCLKSEL	MCG clock select  Selects the MCG's external reference clock.  0 System oscillator (OSCCLK)  1 32 kHz RTC oscillator

# 12.2.3 System Options Register 4 (SIM\_SOPT4)

Address: SIM\_SOPT4 is 4004\_7000h base + 100Ch offset = 4004\_800Ch



## SIM\_SOPT4 field descriptions

Field	Description
31–27 Reserved	This read-only field is reserved and always has the value zero.
26 ETMOCL KOEL	FlexTimer 2 External Clock Pin Select
FTM2CLKSEL	Selects the external pin used to drive the clock to the FTM2 module.
	NOTE: The selected pin must also be configured for the FTM2 module external clock function through the appropriate pin control register in the port control module.
	FTM2 external clock driven by FTM_CLK0 pin.      FTM2 external clock driven by FTM_CLK1 pin.



# SIM\_SOPT4 field descriptions (continued)

Field	Description
25	FTM1 External Clock Pin Select
FTM1CLKSEL	Selects the external pin used to drive the clock to the FTM1 module.
	NOTE: The selected pin must also be configured for the FTM external clock function through the appropriate pin control register in the port control module.
	0 FTM_CLK0 pin 1 FTM_CLK1 pin
24	FlexTimer 0 External Clock Pin Select
FTM0CLKSEL	Selects the external pin used to drive the clock to the FTM0 module.
	NOTE: The selected pin must also be configured for the FTM external clock function through the appropriate pin control register in the port control module.
	0 FTM_CLK0 pin 1 FTM_CLK1 pin
23–22 Reserved	This read-only field is reserved and always has the value zero.
21–20 ETM2CH0SBC	FTM2 channel 0 input capture source select
FTM2CH0SRC	Selects the source for FTM2 channel 0 input capture.
	NOTE: When the FTM is not in input capture mode, clear this field.
	00 FTM2_CH0 signal
	01 CMP0 output
	10 CMP1 output 11 Reserved
19–18	FTM1 channel 0 input capture source select
FTM1CH0SRC	Selects the source for FTM1 channel 0 input capture.
	NOTE: When the FTM is not in input capture mode, clear this field.
	00 FTM1_CH0 signal
	01 CMP0 output
	10 CMP1 output 11 Reserved
17–9	This read-only field is reserved and always has the value zero.
Reserved	This read-only lield is reserved and always has the value zero.
8 ETMOELTO	FTM2 Fault 0 Select
FTM2FLT0	Selects the source of FTM2 fault 0.
	NOTE: The pin source for fault 0 must be configured for the FTM module fault function through the appropriate PORTx pin control register.
	0 FTM2_FLT0 pin
	1 CMP0 out



#### wemory map and register definition


# SIM\_SOPT4 field descriptions (continued)

Field	Description
7–5 Reserved	This read-only field is reserved and always has the value zero.
4 FTM1FLT0	FTM1 Fault 0 Select
	Selects the source of FTM1 fault 0.
	<b>NOTE:</b> The pin source for fault 0 must be configured for the FTM module fault function through the appropriate pin control register in the port control module.
	0 FTM1_FLT0 pin
	1 CMP0 out
3 Reserved	This read-only field is reserved and always has the value zero.
2 FTM0FLT2	FTM0 Fault 2 Select
	Selects the source of FTM0 fault 2.
	<b>NOTE:</b> The pin source for fault 2 must be configured for the FTM module fault function through the appropriate pin control register in the port control module.
	0 FTM0_FLT2 pin
	1 CMP2 out
1 FTM0FLT1	FTM0 Fault 1 Select
FINOFEII	Selects the source of FTM0 fault 1.
	NOTE: The pin source for fault 1 must be configured for the FTM module fault function through the appropriate pin control register in the port control module.
	0 FTM0_FLT1 pin
	1 CMP1 out
0 FTM0FLT0	FTM0 Fault 0 Select
	Selects the source of FTM0 fault 0.
	<b>NOTE:</b> The pin source for fault 0 must be configured for the FTM module fault function through the appropriate pin control register in the port control module.
	0 FTM0_FLT0 pin
	1 CMP0 out



# 12.2.4 System Options Register 5 (SIM\_SOPT5)

Address: SIM\_SOPT5 is 4004\_7000h base + 1010h offset = 4004\_8010h



## SIM\_SOPT5 field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7–6 UART1RXSRC	UART 1 receive data source select  Selects the source for the UART 1 receive data.
	00 UART1_RX pin 01 CMP0 10 CMP1 11 Reserved
5–4 UARTTXSRC	UART 1 transmit data source select Selects the source for the UART 1 transmit data.
	00 UART1_TX pin 01 UART1_TX pin modulated with FTM1 channel 0 output 10 UART1_TX pin modulated with FTM2 channel 0 output 11 Reserved
3–2 UARTORXSRC	UART 0 receive data source select Selects the source for the UART 0 receive data.
	00 UART0_RX pin 01 CMP0 10 CMP1 11 Reserved
1-0 UART0TXSRC	UART 0 transmit data source select Selects the source for the UART 0 transmit data.
	00 UART0_TX pin 01 UART0_TX pin modulated with FTM1 channel 0 output



#### wemory map and register definition


## SIM\_SOPT5 field descriptions (continued)

Field	Description
	10 UART0_TX pin modulated with FTM2 channel 0 output
	11 Reserved

## 12.2.5 System Options Register 6 (SIM\_SOPT6)

The reset values of the RSTFLTEN and RSTFLTSEL bits are for power-on reset only. They are unaffected by other reset types.

Address: SIM\_SOPT6 is 4004\_7000h base + 1014h offset = 4004\_8014h





## SIM\_SOPT6 field descriptions

Field	Description
31–29 RSTFLTEN	Reset pin filter enable
	Selects how the reset pin filter is enabled. See Reset pin filter for more details.
	000 All filtering disabled
	001 Bus clock filter enabled in normal operation. LPO clock filter enabled in stop mode.
	010 LPO clock filter enabled
	011 Bus clock filter enabled in normal operation. All filtering disabled in stop mode.
	100 LPO clock filter enabled in normal operation. All filtering disabled in stop mode.
	101 Reserved (all filtering disabled)
	110 Reserved (all filtering disabled)
	111 Reserved (all filtering disabled)
28–24 RSTFLTSEL	Reset pin filter select
	Selects the reset pin bus clock filter count value. The filter count value is the RSTFL value + 1.
23–0 Reserved	This read-only field is reserved and always has the value zero.



# 12.2.6 System Options Register 7 (SIM\_SOPT7)





## SIM\_SOPT7 field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15 ADC1ALTTRGEN	ADC1 alternate trigger enable  Enable alternative conversion triggers for ADC1.
	O PDB trigger selected for ADC1 Alternate trigger selected for ADC1 as defined by ADC1TRGSEL.
14–13 Reserved	This read-only field is reserved and always has the value zero.
12 ADC1PRETRGSEL	ADC1 pre-trigger select  Selects the ADC1 pre-trigger source when alternative triggers are enabled through ADC1ALTTRGEN.  O Pre-trigger A selected for ADC1.
	1 Pre-trigger B selected for ADC1.
11–8	ADC1 trigger select
ADC1TRGSEL	Selects the ADC1 trigger source when alternative triggers are functional.
	NOTE: Not all trigger sources are available in Stop and VLPS modes.
	0000 PDB external trigger pin input (PDB0_EXTRG)



#### wemory map and register definition

# SIM\_SOPT7 field descriptions (continued)

Field	Description
	0001 High speed comparator 0 output
	0010 High speed comparator 1 output
	0011 High speed comparator 2 output
	0100 PIT trigger 0
	0101 PIT trigger 1
	0110 PIT trigger 2
	0111 PIT trigger 3
	1000 FTM0 trigger
	1001 FTM1 trigger
	1010 FTM2 trigger 1011 Unused
	1100 RTC alarm
	1101 RTC seconds
	1110 Low-power timer trigger
	1011 Unused
7	ADC0 alternate trigger enable
ADC0ALTTRGEN	Enable alternative conversion triggers for ADC0.
	0 PDB trigger selected for ADC0.
	1 Alternate trigger selected for ADC0.
6–5 Reserved	This read-only field is reserved and always has the value zero.
4 ADC0PRETRGSEL	ADC0 pretrigger select
	Selects the ADC0 pre-trigger source when alternative triggers are enabled through ADC0ALTTRGEN.
	0 Pre-trigger A
	1 Pre-trigger B
3–0	ADC0 trigger select
ADC0TRGSEL	Selects the ADC0 trigger source when alternative triggers are functional.
	NOTE: Not all trigger sources are available in Stop and VLPS modes.
	0000 PDB external trigger pin input (PDB0_EXTRG)
	0001 High speed comparator 0 output
	0010 High speed comparator 1 output
	0011 High speed comparator 2 output
	0100 PIT trigger 0
	0101 PIT trigger 1
	0110 PIT trigger 2
	0111 PIT trigger 3
	1000 FTM0 trigger
	1001 FTM1 trigger 1010 FTM2 trigger
	1010 F1M2 trigger 1011 Unused
	1100 RTC alarm
I	1 Galain



## SIM\_SOPT7 field descriptions (continued)

Field	Description
	1101 RTC seconds
	1110 Low-power timer trigger
	1011 Unused

# 12.2.7 System Device Identification Register (SIM\_SDID)

Address: SIM\_SDID is 4004\_7000h base + 1024h offset = 4004\_8024h



<sup>\*</sup> Notes:

#### SIM\_SDID field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–12 REVID	Device revision number  Specifies the silicon implementation number for the device.
11–10 Reserved	This read-only field is reserved and always has the value zero.
9 Reserved	This read-only field is reserved and always has the value zero.
8 Reserved	This read-only field is reserved and always has the value one.
7 Reserved	This read-only field is reserved and always has the value zero.
6–4 FAMID	Kinetis family identification  Specifies the Kinetis family of the device.  000 K10 001 K20 010 K30 011 K40 100 K60 101 K70 110 K50 and K52 111 K51 and K53

<sup>•</sup> x = Undefined at reset.




#### wemory map and register definition

## SIM\_SDID field descriptions (continued)

Field	Description
3–0 PINID	Pincount identification
	Specifies the pincount of the device.
	0000 Reserved
	0001 Reserved
	0010 32-pin
	0011 Reserved
	0100 48-pin
	0101 64-pin
	0110 80-pin
	0111 81-pin
	1000 100-pin
	1001 121-pin
	1010 144-pin
	1011 Reserved
	1100 196-pin
	1101 Reserved
	1110 256-pin
	1111 Reserved

## 12.2.8 System Clock Gating Control Register 1 (SIM\_SCGC1)

Address: SIM\_SCGC1 is 4004\_7000h base + 1028h offset = 4004\_8028h



## SIM\_SCGC1 field descriptions

Field	Description
31–25 Reserved	This read-only field is reserved and always has the value zero.
24 TRIAMP	TRIAMP Clock Gate Control  This bit controls the clock gate to the TRIAMP module.  0 Clock disabled 1 Clock enabled
23–22 Reserved	This read-only field is reserved and always has the value zero.




## SIM\_SCGC1 field descriptions (continued)

Field	Description
21 OPAMP	OPAMP Clock Gate Control
	This bit controls the clock gate to the OPAMP module.
	0 Clock disabled
	1 Clock enabled
20–12 Reserved	This read-only field is reserved and always has the value zero.
11	UART5 Clock Gate Control
UART5	This bit controls the clock gate to the UART5 module.
	0 Clock disabled
	1 Clock enabled
10 UART4	UART4 Clock Gate Control
<b>3</b> 7	This bit controls the clock gate to the UART4 module.
	0 Clock disabled
	1 Clock enabled
9–0 Reserved	This read-only field is reserved and always has the value zero.

## 12.2.9 System Clock Gating Control Register 2 (SIM\_SCGC2)

Address: SIM\_SCGC2 is 4004\_7000h base + 102Ch offset = 4004\_802Ch



#### SIM\_SCGC2 field descriptions

Field	Description
31–14 Reserved	This read-only field is reserved and always has the value zero.
13 DAC1	DAC1 Clock Gate Control  This bit controls the clock gate to the DAC1 module.  Clock disabled Clock enabled
12 DAC0	DAC0 Clock Gate Control

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### memory map and register definition

## SIM\_SCGC2 field descriptions (continued)

Field	Description
	This bit controls the clock gate to the DAC0 module.
	Clock disabled     Clock enabled
11–1 Reserved	This read-only field is reserved and always has the value zero.
0 Reserved	This read-only field is reserved and always has the value zero.

# 12.2.10 System Clock Gating Control Register 3 (SIM\_SCGC3)

Address: SIM\_SCGC3 is 4004\_7000h base + 1030h offset = 4004\_8030h



## SIM\_SCGC3 field descriptions


Field	Description
31 Reserved	This read-only field is reserved and always has the value zero.
30 Reserved	This read-only field is reserved and always has the value zero.
29–28 Reserved	This read-only field is reserved and always has the value zero.
27 ADC1	ADC1 Clock Gate Control  This bit controls the clock gate to the ADC1 module.  0 Clock disabled 1 Clock enabled
26–25 Reserved	This read-only field is reserved and always has the value zero.
24 FTM2	FTM2 Clock Gate Control  This bit controls the clock gate to the FTM2 module.  0 Clock disabled 1 Clock enabled
23–18 Reserved	This read-only field is reserved and always has the value zero.




## SIM\_SCGC3 field descriptions (continued)

Field	Description
17 SDHC	SDHC Clock Gate Control  This bit controls the clock gate to the SDHC module.  0 Clock disabled
	1 Clock enabled
16–13 Reserved	This read-only field is reserved and always has the value zero.
12 SPI2	SPI2 Clock Gate Control  This bit controls the clock gate to the SPI2 module.  Clock disabled Clock enabled
11–5 Reserved	This read-only field is reserved and always has the value zero.
4 Reserved	This read-only field is reserved and always has the value zero.
3–1 Reserved	This read-only field is reserved and always has the value zero.
0 Reserved	This read-only field is reserved and always has the value zero.

# 12.2.11 System Clock Gating Control Register 4 (SIM\_SCGC4)







#### memory map and register definition

# SIM\_SCGC4 field descriptions

Field	Description
31 Reserved	This read-only field is reserved and always has the value zero.
30–29 Reserved	This read-only field is reserved and always has the value one.
28 LLWU	LLWU Clock Gate Control  This bit controls the clock gate to the LLWU module.  0 Clock disabled 1 Clock enabled
27–21 Reserved	This read-only field is reserved and always has the value zero.
20 VREF	VREF Clock Gate Control  This bit controls the clock gate to the VREF module.  0 Clock disabled 1 Clock enabled
19 CMP	Comparator Clock Gate Control  This bit controls the clock gate to the comparator module.  Clock disabled Clock enabled
18 USBOTG	USB Clock Gate Control  This bit controls the clock gate to the USB module.  0 Clock disabled 1 Clock enabled
17–14 Reserved	This read-only field is reserved and always has the value zero.
13 UART3	UART3 Clock Gate Control  This bit controls the clock gate to the UART3 module.  0 Clock disabled 1 Clock enabled
12 UART2	UART2 Clock Gate Control  This bit controls the clock gate to the UART2 module.  0 Clock disabled 1 Clock enabled
11 UART1	UART1 Clock Gate Control  This bit controls the clock gate to the UART1 module.




# SIM\_SCGC4 field descriptions (continued)

Field	Description
	0 Clock disabled 1 Clock enabled
10 UART0	UART0 Clock Gate Control  This bit controls the clock gate to the UART0 module.  0 Clock disabled  1 Clock enabled
9–8 Reserved	This read-only field is reserved and always has the value zero.
7 I2C1	I2C1 Clock Gate Control  This bit controls the clock gate to the I <sup>2</sup> C1 module.  0 Clock disabled 1 Clock enabled
6 I2C0	I2C0 Clock Gate Control  This bit controls the clock gate to the I <sup>2</sup> C0 module.  0 Clock disabled 1 Clock enabled
5–4 Reserved	This read-only field is reserved and always has the value one.
3 Reserved	This read-only field is reserved and always has the value zero.
2 CMT	CMT Clock Gate Control  This bit controls the clock gate to the CMT module.  0 Clock disabled 1 Clock enabled
1 EWM	EWM Clock Gate Control  This bit controls the clock gate to the EWM module.  0 Clock disabled 1 Clock enabled
0 Reserved	This read-only field is reserved and always has the value zero.



# 12.2.12 System Clock Gating Control Register 5 (SIM\_SCGC5)

Address: SIM\_SCGC5 is 4004\_7000h base + 1038h offset = 4004\_8038h



## SIM\_SCGC5 field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18 Reserved	This read-only field is reserved and always has the value one.
17–14 Reserved	This read-only field is reserved and always has the value zero.
13 PORTE	Port E Clock Gate Control  This bit controls the clock gate to the Port E module.  0 Clock disabled 1 Clock enabled
12 PORTD	Port D Clock Gate Control  This bit controls the clock gate to the Port D module.  0 Clock disabled 1 Clock enabled
11 PORTC	Port C Clock Gate Control  This bit controls the clock gate to the Port C module.  0 Clock disabled 1 Clock enabled
10 PORTB	Port B Clock Gate Control  This bit controls the clock gate to the Port B module.




# SIM\_SCGC5 field descriptions (continued)

Field	Description
	0 Clock disabled 1 Clock enabled
9 PORTA	Port A Clock Gate Control  This bit controls the clock gate to the Port A module.  0 Clock disabled
	1 Clock enabled
8–7 Reserved	This read-only field is reserved and always has the value one.
6 Reserved	This read-only field is reserved and always has the value zero.
5 TSI	TSI Clock Gate Control  This bit controls the clock gate to the TSI module.  0 Clock disabled  1 Clock enabled
4–2 Reserved	This read-only field is reserved and always has the value zero.
1 REGFILE	Register File Clock Gate Control  This bit controls the clock gate to the Register File module.  O Clock disabled  1 Clock enabled
0 LPTIMER	Low Power Timer Clock Gate Control  This bit controls the clock gate to the Low Power Timer module.  0 Clock disabled 1 Clock enabled



# 12.2.13 System Clock Gating Control Register 6 (SIM\_SCGC6)

Address: SIM\_SCGC6 is 4004\_7000h base + 103Ch offset = 4004\_803Ch



## SIM\_SCGC6 field descriptions

Field	Description
31 Reserved	This read-only field is reserved and always has the value zero.
30 Reserved	This read-only field is reserved and always has the value one.
29 RTC	RTC Clock Gate Control  This bit controls the clock gate to the RTC module.  0 Clock disabled 1 Clock enabled
28 Reserved	This read-only field is reserved and always has the value zero.
27 ADC0	ADC0 Clock Gate Control  This bit controls the clock gate to the ADC0 module.  0 Clock disabled 1 Clock enabled
26 Reserved	This read-only field is reserved and always has the value zero.
25 FTM1	FTM1 Clock Gate Control  This bit controls the clock gate to the FTM1 module.  0 Clock disabled 1 Clock enabled



# SIM\_SCGC6 field descriptions (continued)

Field	Description
24	FTM0 Clock Gate Control
FTM0	This bit controls the clock gate to the FTM0 module.
	0 Clock disabled 1 Clock enabled
23	PIT Clock Gate Control
PIT	
	This bit controls the clock gate to the PIT module.
	Clock disabled     Clock enabled
22	PDB Clock Gate Control
PDB	This bit controls the clock gate to the PDB module.
	0 Clock disabled
	1 Clock enabled
21 USBDCD	USB DCD Clock Gate Control
000000	This bit controls the clock gate to the USB DCD module.
	0 Clock disabled
	1 Clock enabled
20–19 Reserved	This read-only field is reserved and always has the value zero.
18 CRC	CRC Clock Gate Control
Ono	This bit controls the clock gate to the CRC module.
	0 Clock disabled
	1 Clock enabled
17–16 Reserved	This read-only field is reserved and always has the value zero.
15 I2S	I2S Clock Gate Control
125	This bit controls the clock gate to the I <sup>2</sup> S module.
	0 Clock disabled
	1 Clock enabled
14 Reserved	This read-only field is reserved and always has the value zero.
13 SPI1	SPI1 Clock Gate Control
0.11	This bit controls the clock gate to the SPI1 module.
	0 Clock disabled
	1 Clock enabled





#### wemory map and register definition

## SIM\_SCGC6 field descriptions (continued)

Field	Description
12 SPI0	SPI0 Clock Gate Control  This bit controls the clock gate to the SPI0 module.  0 Clock disabled  1 Clock enabled
11–5 Reserved	This read-only field is reserved and always has the value zero.
4 Reserved	This read-only field is reserved and always has the value zero.
3–2 Reserved	This read-only field is reserved and always has the value zero.
1 DMAMUX	DMA Mux Clock Gate Control  This bit controls the clock gate to the DMA Mux module.  0 Clock disabled 1 Clock enabled
0 FTFL	Flash Memory Clock Gate Control  This bit controls the clock gate to the flash memory.  Clock disabled  Clock enabled

## 12.2.14 System Clock Gating Control Register 7 (SIM\_SCGC7)








## SIM\_SCGC7 field descriptions

Field	Description
31–3 Reserved	This read-only field is reserved and always has the value zero.
2 MPU	MPU Clock Gate Control  This bit controls the clock gate to the MPU module.  0 Clock disabled
	1 Clock enabled
1 DMA	DMA Clock Gate Control  This bit controls the clock gate to the DMA module.
	0 Clock disabled
	1 Clock enabled
0 FLEXBUS	FlexBus Clock Gate Control
	This bit controls the clock gate to the FlexBus module.
	0 Clock disabled 1 Clock enabled

## 12.2.15 System Clock Divider Register 1 (SIM\_CLKDIV1)

The CLKDIV1 register cannot be written to when the device is in VLPR mode.

Address: SIM\_CLKDIV1 is 4004\_7000h base + 1044h offset = 4004\_8044h



<sup>\*</sup> Notes:

## SIM\_CLKDIV1 field descriptions

Field	Description
31–28 OUTDIV1	Clock 1 output divider value
	This field sets the divide value for the core/system clock. At the end of reset, it is loaded with either 0000 or 0111 depending on FTFL_FOPT[LPBOOT].
	0000 Divide-by-1.
	0001 Divide-by-2.
	0010 Divide-by-3.
	0011 Divide-by-4.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

<sup>•</sup> x = Undefined at reset.



#### memory map and register definition

# SIM\_CLKDIV1 field descriptions (continued)

Field	Description
	0100 Divide-by-5.
	0101 Divide-by-6.
	0110 Divide-by-7.
	0111 Divide-by-8.
	1000 Divide-by-9.
	1001 Divide-by-10.
	1010 Divide-by-11.
	1011 Divide-by-12.
	1100 Divide-by-13.
	1101 Divide-by-14.
	1110 Divide-by-15.
	1111 Divide-by-16.
27–24 OUTDIV2	Clock 2 output divider value
	This field sets the divide value for the peripheral clock. At the end of reset, it is loaded with either 0000 or 0111 depending on FTFL_FOPT[LPBOOT].
	0000 Divide-by-1.
	0001 Divide-by-2.
	0010 Divide-by-3.
	0011 Divide-by-4.
	0100 Divide-by-5.
	0101 Divide-by-6.
	0110 Divide-by-7.
	0111 Divide-by-8.
	1000 Divide-by-9.
	1001 Divide-by-10.
	1010 Divide-by-11.
	1011 Divide-by-12.
	1100 Divide-by-13.
	1101 Divide-by-14.
	1110 Divide-by-15. 1111 Divide-by-16.
22.20	·
23–20 OUTDIV3	Clock 3 output divider value  This field sets the divide value for the FlexBus clock driven to the external pin (FB_CLK). At the end of
	reset, it is loaded with either 0001 or 1111 depending on FTFL_FOPT[LPBOOT].
	0000 Divide-by-1.
	0001 Divide-by-2.
	0010 Divide-by-3.
	0011 Divide-by-4.
	0100 Divide-by-5.
	0101 Divide-by-6.
	0110 Divide-by-7.
	0111 Divide-by-8.
	1000 Divide-by-9.
	1001 Divide-by-10.




# SIM\_CLKDIV1 field descriptions (continued)

Field	Description
	1010 Divide-by-11.
	1011 Divide-by-12.
	1100 Divide-by-13.
	1101 Divide-by-14.
	1110 Divide-by-15.
	1111 Divide-by-16.
19–16 OUTDIV4	Clock 4 output divider value
	This field sets the divide value for the flash clock. At the end of reset, it is loaded with either 0001 or 1111 depending on FTFL_FOPT[LPBOOT].
	0000 Divide-by-1.
	0001 Divide-by-2.
	0010 Divide-by-3.
	0011 Divide-by-4.
	0100 Divide-by-5.
	0101 Divide-by-6.
	0110 Divide-by-7.
	0111 Divide-by-8.
	1000 Divide-by-9.
	1001 Divide-by-10.
	1010 Divide-by-11.
	1011 Divide-by-12.
	1100 Divide-by-13.
	1101 Divide-by-14.
	1110 Divide-by-15.
	1111 Divide-by-16.
15–0 Reserved	This read-only field is reserved and always has the value zero.



# 12.2.16 System Clock Divider Register 2 (SIM\_CLKDIV2)

Address: SIM\_CLKDIV2 is 4004\_7000h base + 1048h offset = 4004\_8048h



## SIM\_CLKDIV2 field descriptions


Field	Description
31–20 I2SDIV	I2S clock divider value
	This field sets the divide value for when the fractional clock divider is used as the source for the I <sup>2</sup> S master clock. The clock input to the fractional clock divider is set by the SOPT2[I2SSRC] bit.
	Divider output clock = Divider input clock × [(I2SFRAC+1) / (I2SDIV+1) ]
	NOTE: The I2S clock must be disabled (SCGC6[I2S] = 0) before altering this bitfield.
19–16 Reserved	This read-only field is reserved and always has the value zero.
15–8	I2S clock divider fraction
I2SFRAC	This field sets the multiply value for when the fractional clock divider is used as a the source for I <sup>2</sup> S master clock. The clock input to the fractional clock divider is set by the SOPT2[I2SSRC] bit.
	Divider output clock = Divider input clock × [(I2SFRAC+1) / (I2SDIV+1) ]
	NOTE: The I2S clock must be disabled (SCGC6[I2S] = 0) before altering this bitfield.
7–4 Reserved	This read-only field is reserved and always has the value zero.
3–1	USB clock divider divisor
USBDIV	This field sets the divide value for the fractional clock divider when the MCGFLLCLK/MCGPLLCLK clock is the USB clock source (SOPT2[USBSRC] = 1).
	Divider output clock = Divider input clock × [ (USBFRAC+1) / (USBDIV+1) ]
0	USB clock divider fraction
USBFRAC	This field sets the fraction multiply value for the fractional clock divider when the MCGFLLCLK/MCGPLLCLK clock is the USB clock source (SOPT2[USBSRC] = 1).
	Divider output clock = Divider input clock × [ (USBFRAC+1) / (USBDIV+1) ]



## 12.2.17 Flash Configuration Register 1 (SIM\_FCFG1)

The EESIZE and DEPART filelds are not applicable.

Address: SIM\_FCFG1 is 4004\_7000h base + 104Ch offset = 4004\_804Ch



<sup>\*</sup> Notes:

#### SIM\_FCFG1 field descriptions

Field	Description		
31–28 NVMSIZE	FlexNVM size  This field specifies the amount of FlexNV	M memory available on the device. Undefined values are	
	reserved.		
	0000 0 KB of FlexNVM		
	0111 128 KB of FlexNVM, 16 KB prote 1001 256 KB of FlexNVM. 32 KB prote	-	
	1001 256 KB of FlexNVM, 32 KB prote 1111 256 KB of FlexNVM, 32 KB prote	_	
27–24 PFSIZE	Program flash size		
110122	This field specifies the amount of program flash memory available on the device. Undefined values are reserved.		
	<ul><li>111 128 KB of program flash memory, 4 KB protection region</li><li>1001 256 KB of program flash memory, 8 KB protection region</li></ul>		
	1011 512 KB of program flash memory, 16 KB protection region		
	1111 For devices without FlexNVM (SIM_FCFG2[PFLSH]=1): 512 KB of program flash memory, protection region		
23–20 Reserved	This read-only field is reserved and always has the value zero.		
19–16	EEPROM size EEPROM data size.		
EESIZE			
	0000 Reserved		
	0001 Reserved		
	0010 4 KB		
	0011 2 KB 0100 1 KB		
	0100 1 KB		
	0110 256 Bytes		
	0111 128 Bytes		

Table continues on the next page...

<sup>•</sup> x = Undefined at reset.




#### wemory map and register definition

## SIM\_FCFG1 field descriptions (continued)

Field	Description		
	1000	64 Bytes	
	1001	32 Bytes	
	1010-1110	Reserved	
	1111	0 Bytes	
	For devices without FlexNVM: Reserved		
15–12 Reserved	This read-only field is reserved and always has the value zero.		
11–8	FlexNVM partition		
DEPART	Reserved		
7–0 Reserved	This read-only field	reserved and always has the value zero.	

## 12.2.18 Flash Configuration Register 2 (SIM\_FCFG2)

Address: SIM\_FCFG2 is 4004\_7000h base + 1050h offset = 4004\_8050h



<sup>\*</sup> Notes:

• x = Undefined at reset.




#### SIM\_FCFG2 field descriptions

Field	Description
31 SWAPPFLSH	Swap program flash Indicates that swap is active.
	<ul><li>0 Swap is not active.</li><li>1 Swap is active.</li></ul>
30 Reserved	This read-only field is reserved and always has the value zero.
29–24 MAXADDR0	Max address block 0  This field concatenated with 13 zeros indicates the first invalid address of flash block 0 (program flash 0).
	For example, if MAXADDR0 = 0x20 the first invalid address of flash block 0 is 0x0004_0000. This would be the MAXADDR0 value for a device with 256 KB program flash in flash block 0.
23 PFLSH	Program flash  O Reserved  1 Physical flash block 1 is used as program flash
22 Reserved	This read-only field is reserved and always has the value zero.
21–16 MAXADDR1	Max address block 1  This field concatenated with 13 zeros plus the value of the MAXADDR1 field indicates the first invalid address of the second program flash block (flash block 1).  For example, if MAXADDR0 = MAXADDR1 = 0x20 the first invalid address of flash block 1 is 0x4_0000 + 0x4_0000. This would be the MAXADDR1 value for a device with 512 KB program flash memory and no FlexNVM.
15–0 Reserved	This read-only field is reserved and always has the value zero.

## 12.2.19 Unique Identification Register High (SIM\_UIDH)

Address: SIM\_UIDH is 4004\_7000h base + 1054h offset = 4004\_8054h



<sup>\*</sup> Notes:

• x = Undefined at reset.




#### wemory map and register definition

#### SIM\_UIDH field descriptions

Field	Description	
31–0 UID	Unique Identification	
	Unique identification for the device.	

## 12.2.20 Unique Identification Register Mid-High (SIM\_UIDMH)

Address: SIM\_UIDMH is 4004\_7000h base + 1058h offset = 4004\_8058h



<sup>\*</sup> Notes:

• x = Undefined at reset.

#### SIM\_UIDMH field descriptions

Field	Description
31–0 UID	Unique Identification
	Unique identification for the device.

## 12.2.21 Unique Identification Register Mid Low (SIM\_UIDML)

Address: SIM\_UIDML is 4004\_7000h base + 105Ch offset = 4004\_805Ch



<sup>\*</sup> Notes:

x = Undefined at reset.


#### SIM\_UIDML field descriptions

Field	Description
31–0 UID	Unique Identification
	Unique identification for the device.



## 12.2.22 Unique Identification Register Low (SIM\_UIDL)

Address: SIM\_UIDL is 4004\_7000h base + 1060h offset = 4004\_8060h



- \* Notes:
- x = Undefined at reset.

#### SIM\_UIDL field descriptions

Field	Description
31–0 UID	Unique Identification
	Unique identification for the device.

## 12.3 Functional description

See Introduction section.



runctional description



# **Chapter 13 Mode Controller**

#### 13.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

This section discusses the mode controller (MC) which controls power management and reset mechanisms including the various sources of resets on the device.

## The MC provides:

- control and protection on entry and exit to each power mode
- control for the Power Management Controller (PMC)
- reset entry and exit for the complete MCU

The device's operating power modes are described in this chapter. Entry into each mode, exit from each mode, and functionality while in each of the modes are described.

This chapter also discusses basic information about all reset sources in one place for easy reference. Modules that cause resets (such as the watchdog and the low leakage wake up (LLWU) modules) discuss the reset operation in their own chapters.

## 13.1.1 Features

- Power mode entry/exit and protection
- Reset control features include:
  - Multiple sources of reset for flexible system configuration and reliable operation
  - System reset status (SRSH and SRSL) registers to indicate source of most recent reset



muroduction

## 13.1.2 Modes of Operation

The ARM CPU has three primary modes of operation: run, sleep, and deep sleep. The WFI instruction is used to invoke sleep and deep sleep modes. For Freescale microcontrollers, run, wait and stop are the common terminology used for the primary operating modes. The following table shows the translation between the ARM CPU and the MCU power modes.

ARM CPU mode	MCU mode
Sleep	Wait
Deep sleep	Stop

Accordingly, the ARM CPU documentation refers to sleep and deep sleep, while the Freescale MCU documentation normally uses wait and stop.

This device augments stop, wait, and run in a number of ways. The power management controller (PMC) contains a run and a stop mode regulator. Run regulation is used in normal run, wait and stop modes. Stop mode regulation is used during all very low power and low leakage modes. During stop mode regulation the bus frequencies are limited for the very low power modes.

The PMC provides the user with multiple power options. The low power operating modes can drastically reduce run time power when maximum bus frequency is not required to handle the application needs. From normal run mode, the run mode (RUNM) bit field can be modified to change the the MCU into the very lower power run (VLPR) mode when limited frequency is required during the application. For the low power run mode, a corresponding wait and stop mode can be entered.

Depending on the needs of the user application, a variety of stop modes are available that allow the state retention, partial power down or full power down of certain logic and/or memory. I/O states are held in all modes of operation. Several registers are used to configure the various modes of operation for the device.

The following table describes the power modes available for the device.

Table 13-1. Power modes

Mode	Description		
Run	MCU can be run at full speed and the internal supply is fully regulated (run regulation mode). This mode is also referred to as normal run mode.		
Wait	In ARM architectures, the Core Clock to the ARM Cortex-M4 core is shut off. The System Clock continues to operate; Bus Clocks if enabled continue to operate; run regulation is maintained.		
Stop	In ARM architectures, Core Clock and System Clock to the ARM Cortex-M4 core shut off immediately. System Clock to other masters and Bus Clocks are stopped after all stop acknowledge signals from supporting peripherals are valid.		

Table continues on the next page...



## Table 13-1. Power modes (continued)

Mode	Description		
VLPR	The Core Clock, System Clock and Bus Clocks maximum frequency is restricted to 2MHz max, Flash Clock is restricted to 1MHz. The slow IRC within the MCG must not be enabled when VLPR is entered.		
VLPW	In ARM architectures, the Core Clock to the ARM Cortex-M4 core is shut off. The System Clock continues to operate; Bus Clocks if enabled continue to operate; System and Bus clock restricted to 2MHz max, Flash Clock is restricted to 1MHz		
VLPS	In ARM architectures, Core Clock and System Clock to the ARM Cortex-M4 core shut off immediately. System clock to other masters and Bus Clocks are stopped after all stop acknowledge signals from supporting peripherals are valid.		
LLS	In ARM architectures, Core Clock and System Clock to the ARM Cortex-M4 core shut off immediately. System clock and Bus Clocks are stopped after all stop acknowledge signals from supporting peripherals are valid. MCU is placed in a low leakage mode by reducing the voltage to internal logic. Internal logic states are retained.		
VLLS3	In ARM architectures, Core Clock and System Clock to the ARM Cortex-M4 core shut off immediately. System clock to other masters and Bus Clocks are stopped after all stop acknowledge signals from supporting peripherals are valid. MCU is placed in a low leakage mode by powering down the internal logic. System RAM contents retained and I/O states held. Internal logic states are not retained.		
VLLS2	In ARM architectures, Core Clock and System Clock to the ARM Cortex-M4 core shut off immediately. System clock to other masters and Bus Clocks are stopped after all stop acknowledge signals from supporting peripherals are valid. MCU is placed in a low leakage mode by powering down the internal logic and part of system RAM. The rest of the system RAM contents are retained and I/O states held. Internal logic states are not retained.		
	NOTE: See the device's Chip Configuration details for the amount of SRAM retained in VLLS2 mode.		
VLLS1	In ARM architectures, Core Clock and System Clock to the ARM Cortex-M4 core shut off immediately. System clock to other masters and Bus Clocks are stopped after all stop acknowledge signals from supporting peripherals are valid. MCU is placed in a low leakage mode by powering down the internal logic and all system RAM. A 32-byte register file (available in all modes) contents retained and I/O states held. Internal logic states are not retained.		

## 13.1.2.1 Power Mode Transitions

The following shows the power mode state transitions available on the device.








Figure 13-1. Power Mode State Diagram

The following table defines triggers for the various state transitions shown in the previous figure.

Table 13-2. Power mode transition triggers

Transition #	From	То	Trigger Conditions
1	Run	Wait	Sleep-now or sleep-on-exit modes entered with SLEEPDEEP clear, controlled in System Control Register in ARM core.
	Wait	Run	Interrupt or Reset
2	Run	STOP	Sleep-now or sleep-on-exit modes entered with SLEEPDEEP set, controlled in System Control Register in ARM core
	STOP	Run	Interrupt or Reset

Table continues on the next page...



Table 13-2. Power mode transition triggers (continued)

Transition #	From	То	Trigger Conditions
3	Run	VLPR	Reduce system, bus and core frequency to 2 MHz or less,
			Flash access limited to 1MHz.
			AVLP=1,
			Set RUNM = 10.
			NOTE: Poll VLPRS bit before transitioning out of VLPR mode.
	VLPR	Run	Set RUNM = 00 or
			Interrupt with LPWUI =1 or
			Reset.
			NOTE: Poll REGONS bit before increasing frequency.
4	VLPR	VLPW	Sleep-now or sleep-on-exit modes entered with SLEEPDEEP clear, controlled in System Control Register in ARM core
	VLPW	VLPR	Interrupt with LPWUI = 0
5	VLPW	Run	Interrupt with LPWUI = 1 or
			Reset
6	VLPR	VLPS	LPLLSM=000 or 010, Sleep-now or sleep-on-exit modes entered with SLEEPDEEP set, controlled in System Control Register in ARM core
	VLPS	VLPR	Interrupt with LPWUI = 0
7	Run	VLPS	AVLP=1, LPLLSM=010, Sleep-now or sleep-on-exit modes entered with SLEEPDEEP set, controlled in System Control Register in ARM core
			<b>NOTE:</b> Hardware will set LPWUI and will remain set until software clears.
	VLPS	Run	Interrupt with LPWUI =1 or
			Reset
8	Run	LLS	LPLLSM=011, Sleep-now or sleep-on-exit modes entered with SLEEPDEEP set, controlled in System Control Register in ARM core
	LLS	Run	Wakeup from enabled LLWU input source or RESET pin
9	VLPR	LLS	LPLLSM=011, Sleep-now or sleep-on-exit modes entered with SLEEPDEEP set, controlled in System Control Register in ARM core
10	Run	VLLS(3,2,1)	LPLLSM = (see PMCTRL register description for VLLS configuration),
			T. Control of the con
			Sleep-now or sleep-on-exit modes entered with SLEEPDEEP set, controlled in System Control Register in ARM core

Table continues on the next page...



#### ınıroduction

#### Table 13-2. Power mode transition triggers (continued)

Transition #	From	То	Trigger Conditions
11	VLPR	VLLS(3,2,1)	LPLLSM = (see PMCTRL register description for VLLS configuration),
			Sleep-now or sleep-on-exit modes entered with SLEEPDEEP set, controlled in System Control Register in ARM core

#### 13.1.2.2 Run Modes

The device contains two different run modes:

- Run
- Very low power run (VLPR)

#### 13.1.2.2.1 Run Mode

This is the normal operating mode for the device.

This mode is selected after any reset. When the ARM processor exits reset, it sets up the stack, program counter (PC), and link register (LR):

- The processor reads the start SP (SP\_main) from vector-table offset 0x000
- The processor reads the start PC from vector-table offset 0x004
- LR is set to 0xFFFF\_FFFF.

To reduce power in this mode, disable unused modules by clearing the peripherals corresponding clock gating control bit in the SIM's registers.

## 13.1.2.2.2 Very Low Power Run (VLPR) Mode

In VLPR, the on-chip voltage regulator is put into a stop mode regulation state. In this state, the regulator is designed to supply enough current to the MCU over a reduced frequency. To further reduce power in this mode, disable the clocks to unused modules in the peripherals' corresponding clock gating control bits in the SIM's registers.

Before entering this mode, the following conditions must be met:

- One of two clock sources selected:
  - Either BLPE is the selected clock mode for the MCG or
  - BLPI with the 2MHz IRC.
- The system, bus, and core frequency is 2 MHz or less.
- Flash frequency is 1 MHz or less.
- Mode protection must be set to allow VLP modes (AVLP = 1).



- RUNM set to 10b to enter VLPR.
- Flash programming/erasing is not allowed.
- The slow IRC must not be enabled.
- All clock monitors must be disabled before entering VLPR.

While in VLPR, the regulator is slow responding and cannot handle fast load transitions. Therefore, do not change the clock frequency. This includes a requirement to not modify the module clock enables in the SIM or any clock divider registers.

To re-enter normal run mode, simply clear RUNM. The REGONS and VLPRS bits in the REGSC register are read-only status bits that indicate if the regulator is in run regulation mode or not:

- When REGONS is set, the regulator is in run regulation mode and the MCU can run at full speed in any clock mode. If a higher execution frequency is desired, poll REGONS until it is set when returning from VLPR.
- When VLPRS is set, the system is fully in VLPR mode.

#### NOTE

- Do not enter VLPS, LLS, or VLLSx until the transition to VLPR completes as indicated by the VLPRS bit.
- Do not attempt to transition out of run mode until the REGONS bit sets.

VLPR also provides the option to return to run regulation if any interrupt occurs. This is done by setting the low power wake up on interrupt (LPWUI) bit in the PMCTRL register. In the interrupt service routine (ISR) it is not be necessary to poll the REGONS before increasing the frequency. The VLPR frequency limits are such that the regulator is in run regulation and REGONS is set before the ISR is entered.

Any reset exits VLPR, clears RUNM, REGONS is set, and the device is in normal run mode after the CPU exits its reset flow.

#### 13.1.2.3 Wait Modes

This device contains two different wait modes:

- Wait
- Very low power wait



muroduction

#### 13.1.2.3.1 Wait Mode

Wait mode is entered when the ARM core enters the sleep-now or sleep-on-exit modes. The ARM CPU enters a low-power state in which it is not clocked, but peripherals continue to be clocked provided they are enabled and clock gating to the peripheral is enabled via the SIM.

When an interrupt request occurs, the CPU exits wait mode and resumes processing, beginning with the stacking operations leading to the interrupt service routine.

An asserted RESET pin or LVD (if the LVD system is enabled) exits wait mode, returning the device to normal run mode.

## 13.1.2.3.2 Very Low Power Wait (VLPW) Mode

VLPW is entered by the entering the "sleep-now" or "sleep-on-exit" mode while the MCU is in the very low power run (VLPR) mode and configured appropriately.

In VLPW, the on-chip voltage regulator remains in its stop regulation state. In this state, the regulator is designed to supply enough current to the MCU over a reduced frequency. To further reduce power in this mode, disable the clocks to unused modules by clearing the peripherals' corresponding clock gating control bits in the SIM.

VLPR mode restrictions also apply to VLPW.

VLPW mode provides the option to return to full-regulated normal run mode if any enabled interrupt occurs. This is done by setting the low power wake up on interrupt (LPWUI) bit in the PMCTRL register. Wait for REGONS status to set before increasing the frequency.

If the LPWUI bit is clear when the interrupt from VLPW occurs, the device returns to VLPR mode to execute the interrupt service routine. Wait for VLPRS status to set before transitioning to other power modes.

An asserted RESET pin or a watchdog timeout exits VLPW and clears the RUNM and WAITE bits. This returns the regulator to run regulation and the device to normal run mode.

## 13.1.2.4 Stop Modes

This device contains a variety of stop modes to meet your application needs. The stop modes range from: stopped CPU where all states are saved and certain asynchronous mode peripherals are operating to only I/Os are held, a small register file is retained, and



certain asynchronous mode peripherals are operating with the remainer of the MCU powered off. The tradeoffs depend upon the user's application, where power usage and state retention versus functional needs are weighed.

The various stop modes are selected by setting the appropriate bits in the power mode protection (PMPROT) and power mode control (PMCTRL) registers. The selected stop mode mode is entered during the sleep-now or sleep-on-exit entry with with the SLEEPDEEP bit set in the System Control Register in the ARM core.

The available stop modes are:

- Stop
- Very low power stop (VLPS)
- Low leakage stop (LLS)
- Very low leakage stop 1 (VLLS1)
- Very low leakage stop 2 (VLLS2)
- Very low leakage stop 3 (VLLS3)

## 13.1.2.4.1 Stop Mode

Stop mode is entered via the sleep-now or sleep-on-exit with the SLEEPDEEP bit set in the System Control Register in the ARM core.

The MCG module can be configured to leave the reference clocks running.

A module capable of providing an asynchronous interrupt to the device (for example, an enabled pin interrupt, NMI, RTC, LVW, UART wakeup on edge, CMP, or ADC) takes the device out of stop mode and returns the device to normal run mode. Reference Table 13-1 for peripheral, I/O, and memory operation in stop. When an interrupt request occurs, the CPU exits stop mode and resumes processing, beginning with the stacking operations leading to the interrupt service routine.

An asserted RESET pin, a watchdog timeout, or LVD with LVDRE set exits stop mode. The device returns to normal run mode via a MCU reset.

## 13.1.2.4.2 Very Low Power Stop (VLPS) Mode

VLPS mode can be entered in one of two ways:

- Entry into stop via the sleep-now or sleep-on-exit with the SLEEPDEEP bit set in the System Control Register in the ARM core while the MCU is in very low power run (VLPR) mode and configured as per Table 13-2.
- When the MCU is in normal run mode with LPLLSM set to 010b, entry into stop via the sleep-now or sleep-on-exit with the SLEEPDEEP bit set in the System Control



#### muroduction

Register in the ARM core forces the MCU into VLPS and hardware sets the LPWUI bit set

In VLPS, the on-chip voltage regulator remains in its stop regulation state as in VLPR. On transitions from VLPR to VLPS with LPLLSM set to 000b, hardware forces LPLLSM to value of 010b.

A module capable of providing an asynchronous interrupt to the device (for example, an enabled pin interrupt, NMI, RTC, UART wakeup on edge, CMP or ADC) takes the device out of VLPS and returns the device to VLPR provided the LPWUI bit is clear.

If LPWUI is set, the device returns to normal run mode upon an interrupt request. The REGONS bit must be set before allowing the system to return to a frequency higher than allowed in VLPR.

An asserted RESET pin or a watchdog timeout causes VLPS exit. This returns the device to normal run mode.

## 13.1.2.4.3 Low-Leakage Stop (LLS) Mode

Low leakage stop (LLS) mode can be entered from normal run or VLPR modes.

The MCU enters LLS mode if:

- In sleep-now or sleep-on-exit mode, the SLEEPDEEP bit is set in the System Control Register in the ARM core, and
- The device is configured as per Table 13-2.

In LLS, the on-chip voltage regulator is in stop regulation. Most of the peripherals are put in a state-retention mode that does not allow them to operate while in LLS.

In LLS, configure the low leakage wake up (LLWU) module to enable the desired wakeup sources. The available wakeup sources in LLS are detailed in the Chip Configuration details for this device.

After wakeup from LLS, the device returns to normal run mode with a pending LLWU module interrupt. In the LLWU interrupt service routine (ISR) poll the LLWU module wakeup flags to determine the source of the wakeup.

#### NOTE

The LLWU interrupt must not be masked by the interrupt controller to avoid a scenario where the system does not fully exit stop mode on an LLS recovery.

An asserted RESET pin exits LLS. This returns the device to normal run mode. When LLS is exiting via the RESET pin, the PIN and WAKEUP bits are set in the SRSL register.



#### 13.1.2.4.4 Very Low-Leakage Stop (VLLS3,2,1) Modes

This device contains three very low leakage modes: VLLS3, VLLS2, and VLLS1. When a reference applies to all three low leakage modes, VLLS is used.

All three of the VLLS modes can be entered from normal run or VLPR.

The MCU enters the configured VLLS mode if:

- In sleep-now or sleep-on-exit mode, the SLEEPDEEP bit is set in the System Control Register in the ARM core, and
- The device is configured as per Table 13-2.

In VLLS, the on-chip voltage regulator is in its stop-regulation state.

In VLLS, configure the LLWU module to enable the desired wakeup sources. The available wakeup sources in VLLS are detailed LLWU's Chip Configuration details for this device.

When entering VLLS, each I/O pin is latched as configured before executing VLLS. Since all digital logic in the MCU is powered off, all port and peripheral data is lost during VLLS. This information must be restored before ACKISO in the LLWU is set.

An asserted RESET pin exits any VLLS mode. This returns the device to normal run mode. When exiting VLLS via the RESET pin, the PIN and WAKEUP bits are set in the SRSL register.

## 13.1.2.5 ARM Debug in Low Power Modes

When the MCU is secure the device disables/limits debugger operation. When the MCU is unsecure, the ARM debugger can assert two power-up request signals:

- System power up (SYSPWR bit in the Debug Port Control/Stat register)
- Debug power up (CDBGPWRUPREQ bit in the Debug Port Control/Stat register)

When asserted while in run, wait, VLPR, or VLPW, the Mode Controller drives a corresponding acknowledge for each signal (CDBGPWRUPACK, CSYSPWRUPACK). When both requests are asserted, the Mode Controller handles attempts to enter stop and VLPS by entering an emulated stop state. In this emulated stop state:

- The regulator is in stop regulation,
- The MCG-generated clock source is enabled,
- All system clocks, except core clock, are disabled,
- The debug module has access to core registers, and
- Access to the on-chip peripherals is blocked.



#### muroduction

No debug is available while the MCU is in LLS or VLLS modes. LLS is a state-retention mode and all debug operation can continue after waking from LLS, even in cases where system wakeup is due to a system reset event.

Entering into a VLLS mode causes all the debug controls and settings to be powered off. To give time to the debugger to sync with the MCU, the MDM AP Control Register includes a Very Low Leakage Debug Request (VLLDBGREQ) bit that is set to configure the Mode Controller logic to hold the system in reset after the next recovery from a VLLS mode. This bit allows the debugger time to re-initialize the debug module before the debug session continues.

The VLLDBGREQ bit clears automatically due to the reset generated as part of the VLLS recovery.

The MDM AP Control Register also includes a Very Low Leakage Debug Acknowledge (VLLDBGACK) bit that is set to release the ARM core being held in reset following a VLLS recovery. The debugger re-initializes all debug IP and then asserts the VLLDBGACK control bit to allow the Mode Controller to release the ARM core from reset and allow CPU operation to begin.

The VLLDBGACK bit is cleared by the debugger (or can be left set as is) or clears automatically due to the reset generated as part of the next VLLS recovery.

## **13.1.3 MCU Reset**

Resetting the MCU provides a way to start processing from a known set of initial conditions.

When the ARM processor exits reset, it sets up the stack, program counter (PC), and link register (LR).

- The processor reads the start SP (SP\_main) from vector-table offset 0x000
- The processor reads the start PC from vector-table offset 0x004
- LR is set to 0xFFFF\_FFFF

The device resets can be generalized into three distinct groups: POR, system resets, and debug resets.

#### POR reset:

• Power-on reset (POR)

### System resets:

• External pin reset (PIN)



- Computer operating properly (COP) timer
- Clock generator (MCG) loss of clock reset (LOC)
- Low-voltage detect (LVD)
- Wakeup from very low leakage stop modes, VLLSx
- Software reset (SW) by setting SYSRESETREQ bit of the NVIC's Application Interrupt and Reset Control Register
- LOCKUP core in lockup state
- EzPort
- MDM AP Reset by setting System Reset Request bit of the MDM AP Control Register

#### Debug reset:

Asserting JTAG\_TRST pin

Each of the system reset sources, with the exception of the EzPort and MDM AP reset, has an associated bit in the system reset status low (SRSL) register.

## 13.1.3.1 Power-On Reset (POR)

When power is initially applied to the device, or when the supply voltage drops below the power-on-reset re-arm voltage level  $(V_{POR})$ , the POR circuit causes a reset condition. As the supply voltage rises, the LVD circuit holds the MCU in reset until the supply rises above the LVD low threshold  $(V_{LVDL})$ . The POR and LVD bits in SRSL are set following a POR.

## 13.1.3.2 External RESET Pin

 $\overline{RESET}$  is a dedicated pin. This pin is open drain and has an internal pullup device. Asserting  $\overline{RESET}$  resets the device from any run, wait, stop, VLP, LLS, or VLLS mode. When the  $\overline{RESET}$  pin is the cause of reset, the SRSL[PIN] bit is set.

## 13.1.3.3 Computer Operating Properly (COP) Timer Reset

The watchdog timer monitors the operation of the system by expecting periodic communication from the software. Generally, this is known as servicing, or refreshing, the watchdog. If this periodic refreshing does not occur, the watchdog issues a system reset. When the watchdog timer expiration causes a reset, the SRSL[COP] bit is set.



muroduction

## 13.1.3.4 Multi-Clock Generator (MCG) Loss-of-Clock (LOC) Reset

The MCG module supports an external reference clock. If the clock monitor is enabled (MCG\_C6[CME] is set) and the external reference falls below a certain frequency (specified in the MCG\_C2[RANGE] field), the MCU resets. If a loss of clock causes a reset, the SRSL[LOC] bit is set.

For more details on the clock generator, see Multi-Clock Generator (MCG).

## 13.1.3.5 Low-Voltage Detect (LVD) Reset

If LVDRE is set, the LVD generates a reset upon detection of a low voltage condition. After an LVD reset has occurred, the LVD system holds the MCU in reset until the supply voltage rises above the LVD threshold (specified by the LVDV bits). The SRSL[LVD] bit is set following an LVD reset or POR.

## 13.1.3.6 Low Leakage Mode Recovery

The LLWU provides the means for up to 16 external pins, the  $\overline{RESET}$  pin, and seven internal peripherals to wake the device from LLS and VLLS power modes. When in VLLS mode, all enabled inputs to the LLWU will generate a system reset flow when detected. When in LLS mode, only a detected  $\overline{RESET}$  pin results in a recovery via a reset flow.

For LLS mode exits via RESET pin and any VLLS mode via a wakeup or reset event, the MC\_SRS[WAKEUP] is set indicating a low-leakage mode was active prior to the last system reset flow. Using the RESET pin to trigger an exit from LLS or VLLS results in the MC\_SRS[PIN] being set as well.

After the system reset, the LLWU continues to retain the flags indicating the source of wakeup until the user clears them or the next LLS or VLLS entry occurs.

#### NOTE

External pin flags are cleared by software via the LLWU registers and internal peripheral module flags are required to be cleared in associated peripheral's registers. Refer to the individual peripheral chapters for more information.



## 13.1.3.7 Software (SW) Reset

Setting the SYSRESETREQ bit in the NVIC's Application Interrupt and Reset Control Register forces a software reset on the device. A software reset resets of all major components except for debug.

When the device is reset by a software reset, the SRSH[SW] bit is set.

## 13.1.3.8 Lock-Up Reset

When the processor's built-in system state protection hardware detects the core is locked up because of an unrecoverable exception, a lock-up reset occurs.

When a lock-up condition causes a reset, the SRSH[LOCKUP] bit is set.

#### 13.1.3.9 EzPort Reset

The EzPort generates a system reset request following execution of a RESET command via the EzPort interface. This method of reset allows the chip to boot from flash memory after it has been programmed by an external source.

## 13.1.3.10 MDM-AP System Reset Request

A system reset is initiated by setting the System Reset Request bit in the MDM-AP Control register. This is the primary method for resets via the debug interface. System reset is held until this bit is cleared.

## 13.1.3.11 JTAG Reset

The JTAG module generates a system reset when certain IR codes are selected. This functional reset is asserted when the EZPORT, EXTEST, HIGHZ and CLAMP instructions are active. The reset source from the JTAG module is released when any other IR code is selected. A JTAG reset causes the SRSH[JTAG] bit to set.

## 13.2 Mode Control Memory Map/Register Definition

The following table shows the registers related to the Mode Controller.



#### MC memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4007_E000	System Reset Status Register High (MC_SRSH)	8	R/W	00h	13.2.1/310
4007_E001	System Reset Status Register Low (MC_SRSL)	8	R/W	82h	13.2.2/311
4007_E002	Power Mode Protection Register (MC_PMPROT)	8	R/W	00h	13.2.3/312
4007_E003	Power Mode Control Register (MC_PMCTRL)	8	R/W	00h	13.2.4/314

## 13.2.1 System Reset Status Register High (MC\_SRSH)

The SRSH:SRSL registers include read-only status flags to indicate the source of the most recent reset. The reset state of these bits depends on what caused the MCU to reset.


Throughout this document, SRS refers to SRSH:SRSL.

#### NOTE

The reset value of this register depends on the reset type:

- POR 0x00
- LVD 0x00
- Low-leakage wake-up (LLS exit via RESET pin or any exit from VLLS) — 0x00
- Other reset bits 2-0 are set if their corresponding reset source caused the reset

Address: MC\_SRSH is 4007\_E000h base + 0h offset = 4007\_E000h



#### MC\_SRSH field descriptions

Field	Description		
7–3 Reserved	This read-only field is reserved and always has the value zero.		
2 SW	Software  Indicates reset was caused by software setting of SYSRESETREQ bit in Application Interrupt and Reset Control Register in the ARM Core  0 Reset not caused by software setting of SYSRESETREQ bit 1 Reset caused by software setting of SYSRESETREQ bit		
1 LOCKUP	Core Lock-up		

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### MC\_SRSH field descriptions (continued)

Field	Description		
	Indicates reset was caused by the ARM core indication of a LOCKUP event.		
	0 Reset not caused by core LOCKUP event		
	1 Reset caused by core LOCKUP event		
0 JTAG	JTAG generated reset		
	Indicates reset was caused by JTAG selection of certain IR codes (EZPORT, EXTEST, HIGHZ, and CLAMP).		
	Reset not caused by JTAG     Reset caused by JTAG		

## 13.2.2 System Reset Status Register Low (MC\_SRSL)

The SRSH:SRSL registers includes read-only status flags to indicate the source of the most recent reset. The reset state of these bits depends on what caused the MCU to reset.


Throughout this document, SRS refers to SRSH:SRSL.

#### **NOTE**

The reset value of this register depends on the reset type:

- POR 0x82
- LVD 0x02
- Low-leakage wake-up due to RESET pin assertion 0x41
- Low-leakage wake-up due to other wake-up sources 0x01
- Other reset bits 6-5 and 2 are set if their corresponding reset source caused the reset

Address: MC\_SRSL is 4007\_E000h base + 1h offset = 4007\_E001h



#### MC\_SRSL field descriptions

Field	Description
7	Power-on reset
POR	
	Indicates a reset was caused by the power-on detection logic. Because the internal supply voltage was ramping up at the time, the low-voltage reset (LVD) status bit is also set to indicate that the reset occurred while the internal supply was below the LVD threshold.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### พเบนe Control Memory Map/Register Definition

#### MC\_SRSL field descriptions (continued)

Field	Description			
	0 Reset not caused by POR			
	1 Reset caused by POR			
6 PIN	External reset pin			
	Indicates reset was caused by an active-low level on the external RESETpin.			
	0 Reset not caused by external reset pin			
	1 Reset caused by external reset pin			
5 COP	Computer Operating Properly (COP) Watchdog			
	Reset was caused by the COP watchdog timer timing out. This reset source can be blocked by disabling the watchdog. For more information, see the watchdog chapter.			
	0 Reset not caused by COP timeout			
	1 Reset caused by COP timeout			
4–3 Reserved	This read-only field is reserved and always has the value zero.			
2 LOC	Loss-of-clock reset			
	Indicates reset was caused by a loss of external clock. The MCG clock monitor must be enabled for a loss of clock to be detected. See the MCG chapter for information on enabling the clock monitor.			
	0 Reset not caused by a loss of external clock.			
	1 Reset caused by a loss of external clock.			
1 LVD	Low-voltage detect reset			
LVD	If the LVDRE bit is set and the supply drops below the LVD trip voltage, an LVD reset occurs. This bit is also set by POR.			
	0 Reset not caused by LVD trip or POR			
	1 Reset caused by LVD trip or POR			
0 WAKEUP	Low-leakage wakeup reset			
WAILOI	Reset was caused by an enabled LLWU module wakeup source while the device was in LLS or VLLS modes. Wakeup sources in LLS is limited to the RESET pin. In VLLS, any enabled wakeup source causes a reset. This bit is cleared by any reset except WAKEUP.			
	0 Reset not caused by LLWU module wakeup source			
	1 Reset caused by LLWU module wakeup source			

## 13.2.3 Power Mode Protection Register (MC\_PMPROT)

This write-once register allows low power or low leakage modes to be entered. The actual enabling of the low power or low leakage modes is done by configuring the power mode control register (PMCTRL).



If the MCU is configured for a disallowed power mode, the MCU remains in its current power mode. For example, if in normal run (RUNM = 00, AVLP = 0) an attempt to enter VLPR using PMCTRL[RUNM] is blocked and the RUNM bits remain 00b indicating MCU is still in normal run mode.


PMPROT is write once after any reset. This write to PMPROT clears LPLLSM, which provides protection after wakeup from low power or low leakage modes. The state of LPLLSM prior to clearing due to update of PMPROT indicates which power mode was exited and should be used by initialization software for proper power mode recovery.

#### NOTE

The reset value of this register depends on the reset type:

- Low-leakage wake-up (LLS exit via RESET pin or any exit from VLLS) bits 4, 2-0 unaffected
- Other reset 0x00

Address: MC\_PMPROT is 4007\_E000h base + 2h offset = 4007\_E002h



#### MC\_PMPROT field descriptions

Field	Description
7–6 Reserved	This read-only field is reserved and always has the value zero.
5 AVLP	Allow very low power modes  Provided the appropriate control bits are set up in PMCTRL, this write-once bit allows the MCU to enter the very low power modes: VLPR, VLPW, and VLPS.  ULPR, VLPW, and VLPS are not allowed  VLPR, VLPW, and VLPS are allowed
4 ALLS	Allow low leakage stop mode  This write once bit allows the MCU to enter low leakage stop mode (LLS) provided the appropriate control bits are set up in PMCTRL.  0 LLS is not allowed 1 LLS is allowed
3 Reserved	This read-only field is reserved and always has the value zero.
2 AVLLS3	Allow Very Low Leakage Stop 3 Mode  This write once bit allows the MCU to enter very low leakage stop 3 mode (VLLS3) provided the appropriate control bits are set up in PMCTRL.

Table continues on the next page...



#### พเบนe Control Memory Map/Register Definition

#### MC\_PMPROT field descriptions (continued)

Field	Description	
	0 VLLS3 is not allowed	
	1 VLLS3 is allowed	
1	Allow very low leakage stop 2 mode	
AVLLS2		
	This write once bit allows the MCU to enter very low leakage stop 2 mode (VLLS2) provided the appropriate control bits are set up in PMCTRL.	
	0 VLLS2 is not allowed	
	1 VLLS2 is allowed	
0	Allow very low leakage stop 1 mode	
AVLLS1		
	This write once bit allows the MCU to enter very low leakage stop 1 mode (VLLS1) provided the	
	appropriate control bits are set up in PMCTRL.	
	0 VLLS1 is not allowed	
	1 VLLS1 is allowed	

## 13.2.4 Power Mode Control Register (MC\_PMCTRL)

The PMCTRL register is used to enter the wait, low power, or low leakage modes provided the selected power mode is allowed via appropriate setting of the protection register (PMPROT).

If the MCU is configured for a disallowed power mode or to a reserved RUNM setting, the device remains in its current power mode. For example, if in normal run (RUNM = 00, AVLP = 0) an attempt to enter VLPR using the PMCTRL[RUNM] bits is blocked and RUNM bits remain 00 indicating the device is still in normal run mode.

Before configuring the LPLLSM bits, the corresponding allow bit in PMPROT must be set. Writes to LPLLSM that do not meet this criteria are ignored.

A successful write to PMPROT clears the LPLLSM bits. The state of PMCTRL[LPLLSM] prior to clearing due to update of PMPROT indicates which power mode was exited and should be used by initialization software for proper power mode recovery.

#### NOTE

The reset value of this register depends on the reset type:

- Low-leakage wake-up (LLS exit via RESET pin or any exit from VLLS) — bits 2-0 unaffected
- Other reset 0x00



Address: MC\_PMCTRL is 4007\_E000h base + 3h offset = 4007\_E003h



## MC\_PMCTRL field descriptions

Field	Description
7 LPWUI	Low Power Wake Up on Interrupt
	Controls if the voltage regulator exits stop regulation when any active MCU interrupt occurs, returning the MCU to normal run mode.
	0 The voltage regulator remains in stop regulation on an interrupt
	1 The voltage regulator exits stop regulation on an interrupt
6–5 RUNM	Run Mode Enable
	This field is used to enter very low power run. Writes to this field are blocked if the protection level has not been enabled using PMPROT register. This field is cleared by hardware on exit from LLS or VLLS modes.
	00 Normal run mode
	01 Reserved
	10 Very low power run mode
	11 Reserved
4–3	This read-only field is reserved and always has the value zero.
Reserved	
2–0	Low Power, Low Leakage Stop Mode
LPLLSM	Select low power or low leakage stop modes provided the PMPROT was set properly and stop mode
	entry via the sleep-now or sleep-on-exit. After any system reset, writes to reconfigure PMPROT clears LPLLSM.
	000 Normal stop
	001 Reserved
	010 Very low power stop (VLPS)
	011 Low leakage stop (LLS)
	100 Reserved
	101 Very low leakage stop 3 (VLLS3)
	110 Very low leakage stop 2 (VLLS2)
	111 Very low leakage stop 1 (VLLS1)



woue Control Memory Map/Register Definition



# **Chapter 14 Power Management Controller**

### 14.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The PMC contains the internal voltage regulator, power on reset (POR), and low voltage detect system.

The Mode Controller controls the PMC and its chapter contains description of all device resets, including POR.

## 14.2 Features

Power management control features include:

- Internal voltage regulator
- Active POR providing brown-out detect
- Low-voltage detect protection including:
  - Multiple programmable trip voltages
  - Warning and detect interrupt control
  - Drive a reset on low voltage detect

## 14.3 Low-Voltage Detect (LVD) System

This device includes a system to protect against low-voltage conditions to protect memory contents and control MCU system states during supply voltage variations. The system is comprised of a power-on reset (POR) circuit and a LVD circuit with a user-



#### Low-Voltage Detect (LVD) System

selectable trip voltage: high  $(V_{LVDH})$  or low  $(V_{LVDL})$ . The trip voltage is selected by the LVDSC1[LVDV] bits. The LVD is disabled upon entering VLPx, LLS, and VLLSx modes.

Two flags are available to indicate the status of the low-voltage detect system:

- The low voltage detect flag (LVDF) operates in a level sensitive manner. The LVDF bit is set when the internal supply voltage falls below the selected internal monitor trip point (VLVD). The LVDF bit is cleared by writing one to the LVDACK bit, but only if the internal supply has returned above the internal trip point; otherwise, the LVDF bit remains set.
- The low voltage warning flag (LVWF) operates in a level sensitive manner. The LVWF bit is set when the internal supply voltage falls below the selected internal monitor trip point (VLVW). The LVWF bit is cleared by writing one to the LVWACK bit, but only if the internal supply has returned above the internal trip point; otherwise, the LVWF bit remains set.

## 14.3.1 LVD Reset Operation

By setting the LVDRE bit, the LVD generates a reset upon detection of a low voltage condition. The low voltage detection threshold is determined by the LVDV bits. After an LVD reset occurs, the LVD system holds the MCU in reset until the supply voltage rises above this threshold. The LVD bit in the SRS register is set following an LVD or power-on reset.

## 14.3.2 LVD Interrupt Operation

By configuring the LVD circuit for interrupt operation (LVDIE set and LVDRE clear), LVDSC1[LVDF] is set and an LVD interrupt request occurs upon detection of a low voltage condition. The LVDF bit is cleared by writing one to the LVDSC1[LVDACK] bit.

## 14.3.3 Low-Voltage Warning (LVW) Interrupt Operation

The LVD system contains a low voltage warning flag (LVWF) to indicate that the supply voltage is approaching, but is above, the LVD voltage. The LVW also has an interrupt, which is enabled by setting the LVDSC2[LVWIE] bit. If enabled, an LVW interrupt request occurs when the LVWF is set. LVWF is cleared by writing one to the LVDSC2[LVWACK] bit.



The LVDSC2[LVWV] bits select one of four trip voltages:

- Highest (V<sub>LVW4</sub>)
- Two mid-levels (V<sub>LVW3</sub> and V<sub>LVW2</sub>)
- Lowest (V<sub>LVW1</sub>)

## 14.4 PMC Memory Map/Register Definition

The following table shows the registers related to the PMC.

See Mode Control Memory Map/Register Definition for the mode controller registers.

#### **PMC** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4007_D000	Low Voltage Detect Status and Control 1 Register (PMC_LVDSC1)	8	R/W	10h	14.4.1/319
4007_D001	Low Voltage Detect Status and Control 2 Register (PMC_LVDSC2)	8	R/W	00h	14.4.2/320
4007_D002	Regulator Status and Control Register (PMC_REGSC)	8	R/W	04h	14.4.3/322

## 14.4.1 Low Voltage Detect Status and Control 1 Register (PMC\_LVDSC1)

This register contains status and control bits to support the low voltage detect function. This register should be written during the reset initialization program to set the desired controls even if the desired settings are the same as the reset settings.

While the device is in the very low power or low leakage modes, the LVD system is disabled regardless of LVDSC1 settings. To protect systems that must have LVD always on, configure the power mode protection register (PMPROT) to disallow any very low power or low leakage modes from being enabled.

See the device's data sheet for the exact LVD trip voltages.

#### NOTE


The reset value of this register depends on the reset type:

- POR -- 0x10
- Other reset -- bit 4 is set, bits 1-0 are unaffected



#### rии Метогу Map/Register Definition

Address: PMC\_LVDSC1 is 4007\_D000h base + 0h offset = 4007\_D000h



## PMC\_LVDSC1 field descriptions

Field	Description
7 LVDF	Low-Voltage Detect Flag
	This read-only status bit indicates a low-voltage detect event.
	0 Low-voltage event not detected
	1 Low-voltage event detected
6 LVDACK	Low-Voltage Detect Acknowledge
	This write-only bit is used to acknowledge low voltage detection errors (write 1 to clear LVDF). Reads always return 0.
5 LVDIE	Low-Voltage Detect Interrupt Enable
	Enables hardware interrupt requests for LVDF.
	0 Hardware interrupt disabled (use polling)
	1 Request a hardware interrupt when LVDF = 1.
4 LVDRE	Low-Voltage Detect Reset Enable
	This write-once bit enables LVDF events to generate a hardware reset. Additional writes are ignored.
	0 LVDF does not generate hardware resets
	1 Force an MCU reset when LVDF = 1
3–2 Reserved	This read-only field is reserved and always has the value zero.
1-0	Low-Voltage Detect Voltage Select
LVDV	Selects the LVD trip point voltage (V <sub>LVD</sub> ).
	00 Low trip point selected ( $V_{LVD} = V_{LVDL}$ )
	01 High trip point selected (V <sub>LVD</sub> = V <sub>LVDH</sub> )
	10 Reserved
	11 Reserved

## 14.4.2 Low Voltage Detect Status and Control 2 Register (PMC\_LVDSC2)

This register contains status and control bits to support the low voltage warning function.

While the device is in the very low power or low leakage modes, the LVD system is disabled regardless of LVDSC2 settings.



See the device's data sheet for the exact LVD trip voltages.

#### **NOTE**


The LVW trip voltages depend on LVWV and LVDV bits.

#### **NOTE**

The reset value of this register depends on the reset type:

- POR -- 0x00
- Other reset -- bits 1-0 are unaffected

Address: PMC\_LVDSC2 is 4007\_D000h base + 1h offset = 4007\_D001h




#### PMC\_LVDSC2 field descriptions


Field	Description
7 LVWF	Low-Voltage Warning Flag
	This read-only status bit indicates a low-voltage warning event. LVWF is set when $V_{Supply}$ transitions below the trip point or after reset and $V_{Supply}$ is already below $V_{LVW}$ .
	0 Low-voltage warning event not detected
	1 Low-voltage warning event detected
6 LVWACK	Low-Voltage Warning Acknowledge
	This write-only bit is used to acknowledge low voltage warning errors (write 1 to clear LVWF). Reads always return 0.
5 LVWIE	Low-Voltage Warning Interrupt Enable
LVVVIE	Enables hardware interrupt requests for LVWF.
	0 Hardware interrupt disabled (use polling)
	1 Request a hardware interrupt when LVWF = 1.
4–2 Reserved	This read-only field is reserved and always has the value zero.
1–0 LVWV	Low-Voltage Warning Voltage Select
	Selects the LVW trip point voltage (V <sub>LVW</sub> ). The actual voltage for the warning depends on LVDSC1[LVDV].
	00 Low trip point selected (V <sub>LVW</sub> = V <sub>LVW1H/L</sub> )
	01 Mid 1 trip point selected (V <sub>LVW</sub> = V <sub>LVW2H/L</sub> )
	10 Mid 2 trip point selected (V <sub>LVW</sub> = V <sub>LVW3H/L</sub> )
	11 High trip point selected (V <sub>LVW</sub> = V <sub>LVW4H/L</sub> )



## 14.4.3 Regulator Status and Control Register (PMC\_REGSC)

The power management controller contains an internal voltage regulator. The voltage regulator design uses a bandgap reference, that is also available through a buffer as input to certain internal peripherals. The internal regulator provides a status bit (REGONS) indicating the regulator is in run regulation. This bit is used when the application moves from a low power or very low power mode where the frequency is limited to normal run mode. The frequency of the application can not be increased until the regulator is back in run regulation (REGONS=1).





#### PMC\_REGSC field descriptions

Field	Description
7–5 Reserved	This read-only field is reserved and always has the value zero.
4 TRAMPO	Reserved  0 No effect  1 No effect
3 VLPRS	Very Low Power Run Status  This read only bit indicates the current run mode is VLPR.  0 MCU is not in VLPR mode 1 MCU is in VLPR mode
2 REGONS	Regulator in Run Regulation Status  This read-only bit provides the current status of the internal voltage regulator.  0 Regulator is in stop regulation or in transition to/from it 1 Regulator is in run regulation
1 Reserved	This field is reserved.
0 BGBE	Bandgap Buffer Enable  Enables the bandgap buffer.  0 Bandgap buffer not enabled 1 Bandgap buffer enabled



## Chapter 15 Low-leakage wake-up unit (LLWU)

#### 15.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The LLWU module allows the user to select up to 16 external pin sources and up to 7 internal modules as a wakeup source from low-leakage power modes (LLS and VLLS). The input sources vary by device and are described in the specific device's Chip Configuration details. Each of the available wakeup sources can be individually enabled.

The  $\overline{RESET}$  pin is an additional source for triggering an exit from low-leakage power modes and causes the MCU to exit both LLS and VLLS through a reset flow. On MCUs where the  $\overline{RESET}$  pin is shared with other functions, the explicit port mux control register must be set for  $\overline{RESET}$  pin before the  $\overline{RESET}$  pin can be used as a low-leakage reset source.

When in LLS mode, the I/O are released immediately on a wakeup or reset event. In the case of LLS exit via a RESET pin, the I/O default to their reset state.

When in VLLS modes, the I/O states are held on a wakeup event until the wakeup has been acknowledged via a write to the ACKISO bit. In the case of VLLS exit via a RESET pin, the I/O are released and default to their reset state. In this case, no write to the ACKISO is needed.

In both LLS mode exits via RESET pin and any VLLS mode via a wakeup or reset event, the MC\_SRS[WAKEUP] is set indicating the low-leakage mode was active prior to the last system reset flow. Using the RESET pin to trigger an exit from LLS or VLLS results in the MC\_SRS[PIN] being set as well.

The LLWU module also includes two optional digital pin filters. One for the external wakeup pins combined and one for the RESET pin.



#### **15.1.1 Features**

The LLWU module features include:

- Supports up to 16 external input pins and up to 7 internal modules with individual enable bits
- Input sources may be external pins or from internal peripherals capable of running in LLS or VLLS. See the Chip Configuration details for wakeup input sources for this device.
- Each external pin wakeup input is programmable as falling edge, rising edge, or any change
- Each internal module wakeup input source qualified with programmable enable
- Wakeup inputs are activated if enabled once MCU enters low leakage stop (LLS) or very low leakage stop (VLLS) modes
- Reset exit due to assertion of  $\overline{RESET}$  pin via reset flow. I/O states are reset on exit
- Wakeup from LLS mode is handled as an interrupt. I/O states are released on exit
- Wakeup exit via reset flow when MCU is in VLLS. I/O states remain in held state until wakeup has been acknowledged.
- An optional digital filter provided to qualify an external pin detect and RESET pin detect.

## 15.1.2 Modes of operation

The LLWU module is only functional in LLS and VLLS modes.

## 15.1.2.1 LLS mode

The LLWU module provides up to 16 external wakeup inputs and up to seven internal module wakeup inputs. In addition, an LLS reset event can be initiated via assertion of the  $\overline{RESET}$  pin.

Wakeup events due to external wakeup inputs and internal module wakeup inputs result in an interrupt flow when exiting LLS. A reset event due to  $\overline{RESET}$  pin assertion results in a reset flow when exiting LLS.

#### **NOTE**

The LLWU interrupt must not be masked by the interrupt controller to avoid a scenario where the system does not fully exit stop mode on an LLS recovery.



### 15.1.2.2 VLLS modes

The LLWU module provides up to 16 external wakeup inputs and up to seven internal module wakeup inputs. In addition, a VLLS reset event can be initiated via assertion of the  $\overline{\text{RESET}}$  pin. All wakeup and reset events result in VLLS exit via a reset flow.

### 15.1.2.3 Non-low leakage modes

The LLWU is not active in all non- LLS and VLLS modes where detection and control logic are in a static state. The LLWU registers are accessible in non-LLS and VLLS modes and are available for configuring and reading status when bus transactions are possible.

When the reset pin filter is enabled, filter operation begins immediately so that if LLS or VLLS modes are entered while the the filter logic has seen an active edge on the RESET pin and is currently sensing for minimum assertion duration, there is no restart of pin filtering as RESET filtering transitions from a non-low leakage filter operation (implemented external to LLWU) to the RESET pin filter circuit implemented in the LLWU.

# 15.1.2.4 Debug mode

In debug mode, when LLS/VLLS modes are entered, the chip enters fully functional VLLS and LLS modes and no debug logic is working; on exit from LLS/VLLS, the LLWU becomes inactive and the debug logic becomes active again.

# 15.1.3 Block diagram

The following figure is the block diagram for the LLWU module.

#### **∟∟vv** U Signal Descriptions




Figure 15-1. LLWU block diagram

# 15.2 LLWU Signal Descriptions

The signal properties of LLWU are shown in the following table. The external wakeup input pins can be enabled to detect either rising edge, falling edge, or on any change.

Table 15-1. LLWU Signal Descriptions

Signal	Description	I/O
LLWU_Pn	Wakeup inputs (n = 0-15)	I



# 15.3 Memory map/register definition

The LLWU includes the following registers:

- Five 8-bit wakeup source enable registers
  - Enable external pin input sources
  - Enable internal peripheral sources
- Three 8-bit wakeup flag registers
  - Indication of wakeup up source that caused exit from LLS or VLLS includes external pin or internal module interrupt
- One 8-bit status and control register
  - Digital filter enable for external pin detected and reset
  - Low leakage reset pin enable
  - Acknowledge bit to allow certain peripherals and pads to release their held low leakage state

#### **LLWU** memory map

Absolute address (hex)	Register name		Access	Reset value	Section/ page
4007_C000	LLWU Pin Enable 1 Register (LLWU_PE1)	8	R/W	00h	15.3.1/327
4007_C001	LLWU Pin Enable 2 Register (LLWU_PE2)	8	R/W	00h	15.3.2/328
4007_C002	LLWU Pin Enable 3 Register (LLWU_PE3)	8	R/W	00h	15.3.3/330
4007_C003	LLWU Pin Enable 4 Register (LLWU_PE4)	8	R/W	00h	15.3.4/331
4007_C004	LLWU Module Enable Register (LLWU_ME)	8	R/W	00h	15.3.5/332
4007_C005	LLWU Flag 1 Register (LLWU_F1)	8	R/W	00h	15.3.6/333
4007_C006	LLWU Flag 2 Register (LLWU_F2)	8	R/W	00h	15.3.7/335
4007_C007	LLWU Flag 3 Register (LLWU_F3)	8	R/W	00h	15.3.8/337
4007_C008	LLWU Control and Status Register (LLWU_CS)	8	R/W	04h	15.3.9/338

# 15.3.1 LLWU Pin Enable 1 Register (LLWU\_PE1)

LLWU\_PE1 contains the bit field to enable and select the edge detect type for the external wakeup input pins LLWU\_P3-LLWU\_P0.

#### NOTE

This register is unaffected by wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).



#### wemory map/register definition

Address: LLWU\_PE1 is 4007\_C000h base + 0h offset = 4007\_C000h

Bit	7	6	5	4	3	2	1	0
Read	10/1	IDE2	\\/\	PE2	\\/	IPE1	14/1	IDEO
Write	VV	JPE3	VVO	PE2	VVC	IPEI	VVC	JPE0
Reset	0	0	0	0	0	0	0	0

### LLWU\_PE1 field descriptions

Field	Description
7–6 WUPE3	Wakeup Pin Enable for LLWU_P3
	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
5–4 WUPE2	Wakeup Pin Enable for LLWU_P2
VVOI LZ	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
3–2 WUPE1	Wakeup Pin Enable for LLWU_P1
	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
1–0 WUPE0	Wakeup Pin Enable for LLWU_P0
	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection

# 15.3.2 LLWU Pin Enable 2 Register (LLWU\_PE2)

LLWU\_PE2 contains the bit field to enable and select the edge detect type for the external wakeup input pins LLWU\_P7-LLWU\_P4.



### **NOTE**

This register is unaffected by wakeup from low leakage modes (exit from LLS via  $\overline{RESET}$  or any exit from VLLS).

Address: LLWU\_PE2 is 4007\_C000h base + 1h offset = 4007\_C001h

Bit	7	6	5	4	3	2	1	0
Read			,,,,,	<b>DE</b> 0		.D.E.E		.D.E. 4
Write	VV	UPE7	WU	PE6	WC	JPE5	WC	JPE4
Reset	0	0	0	0	0	0	0	0

### LLWU\_PE2 field descriptions

Field	Description	
7–6 WUPE7	Wakeup Pin Enable for LLWU_P7	
	Enables and configures the edge detection for the wakeup pin.	
	00 External input pin disabled as wakeup input	
	01 External input pin enabled with rising edge detection	
	10 External input pin enabled with falling edge detection	
	11 External input pin enabled with any change detection	
5–4 WUPE6	Wakeup Pin Enable for LLWU_P6	
WOI LO	Enables and configures the edge detection for the wakeup pin.	
	00 External input pin disabled as wakeup input	
	01 External input pin enabled with rising edge detection	
	10 External input pin enabled with falling edge detection	
	11 External input pin enabled with any change detection	
3–2 WUPE5	Wakeup Pin Enable for LLWU_P5	
	Enables and configures the edge detection for the wakeup pin.	
	00 External input pin disabled as wakeup input	
	01 External input pin enabled with rising edge detection	
	10 External input pin enabled with falling edge detection	
	11 External input pin enabled with any change detection	
1–0 WUPE4	Wakeup Pin Enable for LLWU_P4	
	Enables and configures the edge detection for the wakeup pin.	
	00 External input pin disabled as wakeup input	
	01 External input pin enabled with rising edge detection	
	10 External input pin enabled with falling edge detection	
	11 External input pin enabled with any change detection	




# 15.3.3 LLWU Pin Enable 3 Register (LLWU\_PE3)

LLWU\_PE3 contains the bit field to enable and select the edge detect type for the external wakeup input pins LLWU\_P11-LLWU\_P8.

#### **NOTE**

This register is unaffected by wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).

Address: LLWU\_PE3 is 4007\_C000h base + 2h offset = 4007\_C002h



### LLWU\_PE3 field descriptions

Field	Description
7–6 WUPE11	Wakeup Pin Enable for LLWU_P11
	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
5–4 WUPE10	Wakeup Pin Enable for LLWU_P10
WO! E10	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
3–2 WUPE9	Wakeup Pin Enable for LLWU_P9
World	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
1–0 WUPE8	Wakeup Pin Enable for LLWU_P8
	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection



### LLWU\_PE3 field descriptions (continued)

Field	Description
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection


# 15.3.4 LLWU Pin Enable 4 Register (LLWU\_PE4)

LLWU\_PE4 contains the bit field to enable and select the edge detect type for the external wakeup input pins LLWU\_P15-LLWU\_P12.

#### **NOTE**

This register is unaffected by wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).

Address: LLWU\_PE4 is 4007\_C000h base + 3h offset = 4007\_C003h



### LLWU\_PE4 field descriptions

Field	Description
7–6 WUPE15	Wakeup Pin Enable for LLWU_P15
	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
5–4 WUPE14	Wakeup Pin Enable for LLWU_P14
WUPE14	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection
	10 External input pin enabled with falling edge detection
	11 External input pin enabled with any change detection
3–2	Wakeup Pin Enable for LLWU_P13
WUPE13	Enables and configures the edge detection for the wakeup pin.
	00 External input pin disabled as wakeup input
	01 External input pin enabled with rising edge detection



#### wemory map/register definition

### LLWU\_PE4 field descriptions (continued)

Field	Description			
	10 External input pin enabled with falling edge detection			
	11 External input pin enabled with any change detection			
1–0 WUPE12	Wakeup Pin Enable for LLWU_P12			
	Enables and configures the edge detection for the wakeup pin.			
	00 External input pin disabled as wakeup input			
	01 External input pin enabled with rising edge detection			
	10 External input pin enabled with falling edge detection			
	11 External input pin enabled with any change detection			


# 15.3.5 LLWU Module Enable Register (LLWU\_ME)

LLWU\_ME contains the bits to enable the internal module flag as a wakeup input source for inputs MWUF7-MWUF0.

#### **NOTE**

This register is unaffected by wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).

Address: LLWU\_ME is 4007\_C000h base + 4h offset = 4007\_C004h



#### **LLWU\_ME** field descriptions

Field	Description
7	Wakeup Module Enable for Module 7
WUME7	Enables an internal module as a wakeup source input.
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source
6	Wakeup Module Enable for Module 6
WUME6	Enables an internal module as a wakeup source input.
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source
5 WUME5	Wakeup Module Enable for Module 5
VVOIVIES	Enables an internal module as a wakeup source input.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### LLWU\_ME field descriptions (continued)

Field	Description
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source
4 WUME4	Wakeup Module Enable for Module 4
	Enables an internal module as a wakeup source input.
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source
3 WUME3	Wakeup Module Enable for Module 3
	Enables an internal module as a wakeup source input.
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source
2 WUME2	Wakeup Module Enable for Module 2
	Enables an internal module as a wakeup source input.
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source
1 WUME1	Wakeup Module Enable for Module 1
	Enables an internal module as a wakeup source input.
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source
0 WUME0	Wakeup Module Enable for Module 0
	Enables an internal module as a wakeup source input.
	0 Internal module flag not used as wakeup source
	1 Internal module flag used as wakeup source

# 15.3.6 LLWU Flag 1 Register (LLWU\_F1)

LLWU\_F1 contains the wakeup flags indicating which wakeup source caused the MCU to exit LLS or VLLS mode. For LLS, this will be the source causing the CPU interrupt flow. For VLLS, this will be the source causing the MCU reset flow.

The external wakeup flags are read only and clearing a flag is accomplished by a write of a one to the corresponding WUFx bit. The wakeup flag (WUFx) if set will remain set if the associated WUPEx bit is cleared.

#### NOTE

This register is unaffected by wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory map/register definition

Address: LLWU\_F1 is 4007\_C000h base + 5h offset = 4007\_C005h

Bit	7	6	5	4	3	2	1	0
Read	WUF7	WUF6	WUF5	WUF4	WUF3	WUF2	WUF1	WUF0
Write	w1c							
Reset	0	0	0	0	0	0	0	0

### LLWU\_F1 field descriptions

Field	Description
7	Wakeup Flag for LLWU_P7
WUF7	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF7.
	0 LLWU_P7 input was not a source of wakeup from LLS or VLLS mode
	1 LLWU_P7 input was a source of wakeup from LLS or VLLS mode
6 WUF6	Wakeup Flag for LLWU_P6
	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF6.
	0 LLWU_P6 input was not a source of wakeup from LLS or VLLS mode
	1 LLWU_P6 input was a source of wakeup from LLS or VLLS mode
5	Wakeup Flag for LLWU_P5
WUF5	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF5.
	0 LLWU_P5 input was not a source of wakeup from LLS or VLLS mode
	1 LLWU_P5 input was a source of wakeup from LLS or VLLS mode
4 WUF4	Wakeup Flag for LLWU_P4
	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF4.
	0 LLWU_P4 input was not a source of wakeup from LLS or VLLS mode
	1 LLWU_P4 input was a source of wakeup from LLS or VLLS mode
3	Wakeup Flag for LLWU_P3
WUF3	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF3.
	0 LLWU_P3 input was not a source of wakeup from LLS or VLLS mode
	1 LLWU_P3 input was a source of wakeup from LLS or VLLS mode
2 WUF2	Wakeup Flag for LLWU_P2
	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF2.
	0 LLWU_P2 input was not a source of wakeup from LLS or VLLS mode
	1 LLWU_P2 input was a source of wakeup from LLS or VLLS mode



### LLWU\_F1 field descriptions (continued)

Field	Description			
1	Wakeup Flag for LLWU_P1			
WUF1	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF1.			
	0 LLWU_P1 input was not a source of wakeup from LLS or VLLS mode			
	1 LLWU_P1 input was a source of wakeup from LLS or VLLS mode			
0 WUF0	Wakeup Flag for LLWU_P0			
	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF0.			
	0 LLWU_P0 input was not a source of wakeup from LLS or VLLS mode			
	1 LLWU_P0 input was a source of wakeup from LLS or VLLS mode			

# 15.3.7 LLWU Flag 2 Register (LLWU\_F2)


LLWU\_F2 contains the wakeup flags indicating which wakeup source caused the MCU to exit LLS or VLLS mode. For LLS, this will be the source causing the CPU interrupt flow. For VLLS, this will be the source causing the MCU reset flow.

The external wakeup flags are read only and clearing a flag is accomplished by a write of a one to the corresponding WUFx bit. The wakeup flag (WUFx) if set will remain set if the associated WUPEx bit is cleared.

#### NOTE

This register is unaffected by wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).

Address: LLWU\_F2 is 4007\_C000h base + 6h offset = 4007\_C006h



#### LLWU F2 field descriptions

Field	Description	
7 WUF15	Wakeup Flag for LLWU_P15	
	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF15.	



#### wemory map/register definition

# LLWU\_F2 field descriptions (continued)

Field	Description		
	0 LLWU_P15 input was not a source of wakeup from LLS or VLLS mode		
	1 LLWU_P15 input was a source of wakeup from LLS or VLLS mode		
6 WUF14	Wakeup Flag for LLWU_P14		
	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF14.		
	LLWU_P14 input was not a source of wakeup from LLS or VLLS mode     LLWU_P14 input was a source of wakeup from LLS or VLLS mode		
5 WUF13	Wakeup Flag for LLWU_P13		
	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF13.		
	0 LLWU_P13 input was not a source of wakeup from LLS or VLLS mode		
	1 LLWU_P13 input was a source of wakeup from LLS or VLLS mode		
4 WUF12	Wakeup Flag for LLWU_P12		
WUF12	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF12.		
	0 LLWU_P12 input was not a source of wakeup from LLS or VLLS mode		
	1 LLWU_P12 input was a source of wakeup from LLS or VLLS mode		
3 WUF11	Wakeup Flag for LLWU_P11		
WOFTI	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF11.		
	0 LLWU_P11 input was not a source of wakeup from LLS or VLLS mode		
	1 LLWU_P11 input was a source of wakeup from LLS or VLLS mode		
2	Wakeup Flag for LLWU_P10		
WUF10	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF10.		
	0 LLWU_P10 input was not a source of wakeup from LLS or VLLS mode		
	1 LLWU_P10 input was a source of wakeup from LLS or VLLS mode		
1 WUF9	Wakeup Flag for LLWU_P9		
Wors	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF9.		
	LLWU_P9 input was not a source of wakeup from LLS or VLLS mode     LLWU_P9 input was a source of wakeup from LLS or VLLS mode		
0 WUF8	Wakeup Flag for LLWU_P8		
VVOI 0	Indicates that an enabled external wakeup pin was a source of exiting LLS or VLLS. To clear the flag write a one to WUF8.		
	0 LLWU_P8 input was not a source of wakeup from LLS or VLLS mode 1 LLWU_P8 input was a source of wakeup from LLS or VLLS mode		



# 15.3.8 LLWU Flag 3 Register (LLWU\_F3)


LLWU\_F3 contains the wakeup flags indicating which internal wakeup source caused the MCU to exit LLS or VLLS mode. For LLS, this will be the source causing the CPU interrupt flow. For VLLS, this will be the source causing the MCU reset flow.

For internal peripherals that are capable of running in LLS or VLLS mode, such as RTC or CMP modules, the flag from the associated peripheral is accessible as the MWUFx bit. Clearing of the flag will need to be done in the peripheral instead of writing a one to the MWUFx bit.

#### NOTE

This register is unaffected by wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).

Address: LLWU\_F3 is 4007\_C000h base + 7h offset = 4007\_C007h



### LLWU\_F3 field descriptions

Field	Description
7 MWUF7	Wakeup flag for module 7 (Error Detect)
	Indicates that an unexpected source of wakeup was active when LLS or VLLS was entered. An immediate wakeup event was triggered and the source of the wakeup event is not known. Error handling routines should treat this source as an unknown wakeup. To clear the flag write a one to MWUF7.
	0 Module 7 (Error Detect) input was not a source of wakeup from LLS or VLLS mode
	1 Module 7 (Error Detect) input was a source of wakeup from LLS or VLLS mode
6	Wakeup flag for module 6
MWUF6	Indicates that an enabled internal peripheral was a source of exiting LLS or VLLS. To clear the flag follow the internal peripheral flag clearing mechanism.
	0 Module 6 input was not a source of wakeup from LLS or VLLS mode
	1 Module 6 input was a source of wakeup from LLS or VLLS mode
5 MWUF5	Wakeup flag for module 5
WWOIS	Indicates that an enabled internal peripheral was a source of exiting LLS or VLLS. To clear the flag follow the internal peripheral flag clearing mechanism.
	0 Module 5 input was not a source of wakeup from LLS or VLLS mode
	1 Module 5 input was a source of wakeup from LLS or VLLS mode



#### wemory map/register definition

### LLWU\_F3 field descriptions (continued)

Field	Description
4 MWUF4	Wakeup flag for module 4
	Indicates that an enabled internal peripheral was a source of exiting LLS or VLLS. To clear the flag follow the internal peripheral flag clearing mechanism.
	0 Module 4 input was not a source of wakeup from LLS or VLLS mode
	1 Module 4 input was a source of wakeup from LLS or VLLS mode
3 MWUF3	Wakeup flag for module 3
	Indicates that an enabled internal peripheral was a source of exiting LLS or VLLS. To clear the flag follow the internal peripheral flag clearing mechanism.
	0 Module 3 input was not a source of wakeup from LLS or VLLS mode
	1 Module 3 input was a source of wakeup from LLS or VLLS mode
2 MWUF2	Wakeup flag for module 2
	Indicates that an enabled internal peripheral was a source of exiting LLS or VLLS. To clear the flag follow the internal peripheral flag clearing mechanism.
	0 Module 2 input was not a source of wakeup from LLS or VLLS mode
	1 Module 2 input was a source of wakeup from LLS or VLLS mode
1 MWUF1	Wakeup flag for module 1
	Indicates that an enabled internal peripheral was a source of exiting LLS or VLLS. To clear the flag follow the internal peripheral flag clearing mechanism.
	0 Module 1 input was not a source of wakeup from LLS or VLLS mode
	1 Module 1 input was a source of wakeup from LLS or VLLS mode
0 MWUF0	Wakeup flag for module 0
	Indicates that an enabled internal peripheral was a source of exiting LLS or VLLS. To clear the flag follow the internal peripheral flag clearing mechanism.
	0 Module 0 input was not a source of wakeup from LLS or VLLS mode
	1 Module 0 input was a source of wakeup from LLS or VLLS mode

# 15.3.9 LLWU Control and Status Register (LLWU\_CS)

LLWU\_CS is a status and control register that is used to enable/disable the digital filter for the external pin detect and RESET pin.

#### NOTE

ACKISO is set following wakeup from VLLS modes. FLTEP and FLTR are unaffected following wakeup from low leakage modes (exit from LLS via RESET or any exit from VLLS).



Address: LLWU\_CS is 4007\_C000h base + 8h offset = 4007\_C008h



### LLWU\_CS field descriptions

Field	Description
7 ACKISO	Acknowledge Isolation  Reading this bit indicates whether certain peripherals and the I/O pads are in a latched state as a result of having been in a VLLS mode. Writing one to this bit when it is set releases the I/O pads and certain peripherals to their normal run mode state.  O Peripherals and I/O pads are in normal run state  Certain peripherals and I/O pads are in an isolated and latched state
6–3 Reserved	This read-only field is reserved and always has the value zero.
2 Reserved	This field is reserved.
1 FLTEP	Digital Filter on External Pin  Enables the digital filter for the external pin detect.  0 Filter not enabled 1 Filter enabled
0 FLTR	Digital Filter on RESET Pin  Enables the digital filter for the RESET pin during LLS and VLLS modes.  0 Filter not enabled 1 Filter enabled

# 15.4 Functional description

This on-chip peripheral module is called a low leakage wake up (LLWU) module because it allows internal peripherals and external input pins to be sources of wakeup from low leakage modes. It is only operational in LLS and VLLS modes.

The LLWU module contains pin enables for each external pin and internal module. For each external pin, the user can disable or select the edge type for the wakeup. Choices are falling, rising or either edge (any change). When an external pin is enabled as a wakeup source the pin must be configured as an input pin.



#### runctional description

The LLWU implements an optional 3-cycle glitch filter, based on the LPO clock, such that a detected external pin is required to stay asserted until the enabled glitch filter times out. There is also 2 additional cycles of latency due to synchronization that results in a total of 5 cycles of delay before the detect circuit alerts the system to the wakeup or reset event when the filter function is enabled. The wakeup detect glitch filter is implemented on the "OR" of external pin inputs of all enabled external pins. There is separate reset glitch filter implemented on the RESET pin. There is no glitch filtering on the internal modules.

#### NOTE

The wakeup glitch filter should not be enabled if any of the external pin detect edge types is set for either edge. Enabling the wakeup glitch filter and selecting either edge detect on any pin results in unpredictable operation.

For internal module wakeup operation, the WUMEx bit enables the respective module as a wakeup source.

### 15.4.1 LLS mode

While in LLS, the MCU is in a state retention mode where all registers and memory retains its contents. The I/O pins are held in their input or output state. Upon wakeup, the power management control (PMC) is re-enabled, goes through a power up sequence to full regulation and releases the logic from state retention mode. The I/O states are released. Wakeup events triggered from either an external pin input or an internal module input result in a CPU interrupt flow to begin user code execution.

An LLS reset event due to RESET pin assertion causes an exit via a system reset. State retention data is lost, the I/O states return to their reset state, and the ACKISO bit is not set. The MC\_SRS[WAKEUP] and MC\_SRS[PIN] bits are set and the system executes a reset flow before CPU operation begins with a reset vector fetch.

### 15.4.2 VLLS modes

While in VLLS, much of the internal digital logic is powered down. The I/O pins are held in their input or output state. Refer to the device's Power Management chapter for powered and un-powered modules in VLLSx modes. After wakeup or reset, the PMC is re-enabled and performs a power-up sequence to full regulation.



In the case of a wakeup due to external pin or internal module wakeup, the I/O states are held until software clears the ACKISO bit (by writing a 1 to it). Recovery is always via a system reset flow and the MC\_SRS[WAKEUP] is set indicating the low leakage mode was active prior to the last system reset flow.

An VLLS reset event due to RESET pin assertion causes an exit via a system reset. State retention data is lost, the I/O states return to their reset state, and the ACKISO bit is not set. The MC\_SRS[WAKEUP] and MC\_SRS[PIN] bits are set and the system executes a reset flow before CPU operation begins with a reset vector fetch.

### 15.4.3 Initialization

Flags associated with external input pins (WUFx) are cleared upon entry into LLS or VLLS modes.

For an enabled peripheral wakeup input, the peripheral flag should be cleared by the user before entering LLS or VLLS to avoid an immediate exit from LLS or VLLS.

# 15.4.4 Low power mode recovery

Recovery from VLLSx is through the wake-up Reset event. The chip wake-ups from VLLSx by means of reset, an enabled pin or enabled module. See the table "LLWU inputs" in the LLWU configuration section for a list of the sources.

The wake-up flow from VLLS1,2 and 3 is through reset. The wakeup bit in the SRS registers in the Mode Controller is set indicating that the chip is recovering from a low power mode. Code execution begins; however, the I/O pins are held in their pre-low-power mode entry states, and the oscillator is disabled (even if EREFSTEN had been set before entering VLLSx). Software must clear this hold by writing a 1 to the ACKISO bit in the Control and Status register in the LLWU module.

#### NOTE

To avoid unwanted transitions on the pins, software must reinitialize the I/O pins to their pre-low-power mode entry states *before* releasing the hold.

The oscillator cannot be re-enabled before the ACKISO bit is cleared and must be reconfigured after the hold is released.



runctional description



# **Chapter 16 Miscellaneous Control Module (MCM)**

### 16.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The Miscellaneous Control Module (MCM) provides a myriad of miscellaneous control functions.

### 16.1.1 Features

The MCM includes these distinctive features:

- Program-visible information on the platform configuration and revision
- Control and counting logic for ETB almost full

# 16.2 Memory Map/Register Descriptions

The memory map and register descriptions below describe the registers using byte addresses.

# MCM memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
E008_0008	Crossbar switch (AXBS) slave configuration (MCM_PLASC)	16	R	001Fh	16.2.1/344




### MCM memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
E008_000A	Crossbar switch (AXBS) master configuration (MCM_PLAMC)	16	R	003Fh	16.2.2/344
E008_000C	SRAM arbitration and protection (MCM_SRAMAP)	32	R/W	0000_0000h	16.2.3/345
E008_0010	Interrupt status register (MCM_ISR)	32	R	0000_0000h	16.2.4/346
E008_0014	ETB counter control register (MCM_ETBCC)	32	R/W	0000_0000h	16.2.5/347
E008_0018	ETB reload register (MCM_ETBRL)	32	R/W	0000_0000h	16.2.6/348
E008_001C	ETB counter value register (MCM_ETBCNT)	32	R	0000_0000h	16.2.7/349

# Crossbar switch (AXBS) slave configuration (MCM\_PLASC)

The PLASC is a 16-bit read-only register identifying the presence/absence of bus slave connections to the device's crossbar switch.

Address: MCM\_PLASC is E008\_0000h base + 8h offset = E008\_0008h




### MCM PLASC field descriptions

Field	Description
15–8 Reserved	This read-only field is reserved and always has the value zero.
7–0 ASC	Each bit in the ASC field indicates if there is a corresponding connection to the crossbar switch's slave input port.
	<ul> <li>0 A bus slave connection to AXBS input port n is absent</li> <li>1 A bus slave connection to AXBS input port n is present</li> </ul>

# Crossbar switch (AXBS) master configuration (MCM\_PLAMC)

The PLAMC is a 16-bit read-only register identifying the presence/absence of bus master connections to the device's crossbar switch.

Address: MCM\_PLAMC is E008\_0000h base + Ah offset = E008\_000Ah



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

0



### MCM\_PLAMC field descriptions


Field	Description
15–8 Reserved	This read-only field is reserved and always has the value zero.
7–0 AMC	Each bit in the AMC field indicates if there is a corresponding connection to the AXBS master input port.
	0 A bus master connection to AXBS input port <i>n</i> is absent
	1 A bus master connection to AXBS input port <i>n</i> is present

# 16.2.3 SRAM arbitration and protection (MCM\_SRAMAP)

The SRAMAP register defines the arbitration and protection schemes for the two SRAM arrays.

NOTE

Bits 23-0 are undefined after reset.



### MCM\_SRAMAP field descriptions

0

Field	Description		
31 Reserved	This read-only field is reserved and always has the value zero.		
30 SRAMLWP	SRAM_L write protect  When this bit is set, writes to SRAM_L array generates a bus error.		
29–28 SRAMLAP	SRAM_L arbitration priority  Defines the arbitration scheme and priority for the processor and SRAM backdoor accesses to the SRAM_L array.  00 Round robin		

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

0

Reset

0

0

0

0




#### wemory Map/Register Descriptions

### **MCM\_SRAMAP** field descriptions (continued)

Field	Description	
	01 Special round robin (favors SRAM backoor accesses over the processor)	
	10 Fixed priority. Processor has highest, backdoor has lowest	
	11 Fixed priority. Backdoor has highest, processor has lowest	
27 Reserved	This read-only field is reserved and always has the value zero.	
26 SRAMUWP	SRAM_U write protect	
	When this bit is set, writes to SRAM_U array generates a bus error.	
25–24 SRAMUAP	SRAM_U arbitration priority	
	Defines the arbitration scheme and priority for the processor and SRAM backdoor accesses to the SRAM_U array.	
	00 Round robin	
	01 Special round robin (favors SRAM backoor accesses over the processor)	
	10 Fixed priority. Processor has highest, backdoor has lowest	
	11 Fixed priority. Backdoor has highest, processor has lowest	
23–9 Reserved	This field is reserved.	
8–0 Reserved	This field is reserved.	

# 16.2.4 Interrupt status register (MCM\_ISR)

Address: MCM\_ISR is E008\_0000h base + 10h offset = E008\_0010h



### MCM\_ISR field descriptions

Field	Description
31–4 Reserved	This read-only field is reserved and always has the value zero.
3 Reserved	This read-only field is reserved and always has the value zero.

Table continues on the next page...


#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




### MCM\_ISR field descriptions (continued)

Field	Description	
2	Non-maskable interrupt pending	
NMI	If ETBCC[RSPT] is set to 10b, this bit is set when the ETB counter expires.	
	0 No pending NMI	
	1 Due to the ETB counter expiring, an NMI is pending	
1	Normal interrupt pending	
IRQ	If ETBCC[RSPT] is set to 01b, this bit is set when the ETB counter expires.	
	0 No pending interrupt	
	1 Due to the ETB counter expiring, a normal interrupt is pending	
0 Reserved	This read-only field is reserved and always has the value zero.	

# 16.2.5 ETB counter control register (MCM\_ETBCC)





### MCM\_ETBCC field descriptions

Field	Description
31–6 Reserved	This read-only field is reserved and always has the value zero.
5	ITM-to-TPIU disable
ITDIS	Disables the trace path from ITM to TPIU
	0 ITM-to-TPIU trace path enabled
	1 ITM-to-TPIU trace path disabled
4 ETDIS	ETM-to-TPIU disable
	Disables the trace path from ETM to TPIU
	0 ETM-to-TPIU trace path enabled
	1 ETM-to-TPIU trace path disabled
3 RLRQ	Reload request
RLRQ	Reloads the ETB packet counter with the MCM_ETBRL RELOAD value.
	If IRQ or NMI interrupts were enabled and an NMI or IRQ interrupt was generated on counter expiration, setting this bit clears the pending NMI or IRQ interrupt request.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory Map/Register Descriptions

# MCM\_ETBCC field descriptions (continued)

Field	Description			
	If debug halt was enabled and a debug halt request was asserted on counter expiration, setting this bit clears the debug halt request.			
	0 No effect			
	1 Clears pending debug halt, NMI, or IRQ interrupt requests			
2–1 RSPT	Response type			
	00 No response when the ETB count expires			
	01 Generate a normal interrupt when the ETB count expires			
	10 Generate an NMI when the ETB count expires			
	11 Generate a debug halt when the ETB count expires			
0 CNTEN	Counter enable			
0.11.2.1	Enables the ETB counter.			
	0 ETB counter disabled			
	1 ETB counter enabled			

# 16.2.6 ETB reload register (MCM\_ETBRL)

Address: MCM\_ETBRL is E008\_0000h base + 18h offset = E008\_0018h




### MCM\_ETBRL field descriptions

L	Field	Description	
	31–11 Reserved	This read-only field is reserved and always has the value zero.	
	10–0 RELOAD	Byte count reload value  Indicates the 0-mod-4 value the counter reloads to. Writing a non-0-mod-4 value to this field results in an bus error	



### 16.2.7 ETB counter value register (MCM\_ETBCNT)

Address: MCM\_ETBCNT is E008\_0000h base + 1Ch offset = E008\_001Ch



### MCM\_ETBCNT field descriptions

Description
This read-only field is reserved and always has the value zero.
Byte count counter value  Indicates the current 0-mod-4 value of the counter.
В

# 16.3 Functional Description

This section describes the functional description of MCM module.

# 16.3.1 Interrupts

The MCM generates two interrupt requests:

- Non-maskable interrupt
- Normal interrupt

# 16.3.1.1 Non-maskable interrupt

The MCM's non-maskable interrupt (NMI) is generated, if:

- MCM\_ISCR[ETBN] is set, which is caused by
  - The ETB counter is enabled (MCM\_ETBCC[CNTEN] = 1),
  - The ETB count expires, and
  - The response to counter expiration is an NMI (MCM\_ETBCC[RSPT] = 10)



runctional Description

### 16.3.1.2 Normal interrupt

The MCM's normal interrupt is generated if any of the following are true:

- MCM\_ISCR[ETBI] is set, which is caused by
  - The ETB counter is enabled (MCM\_ETBCC[CNTEN] = 1),
  - The ETB count expires, and
  - The response to counter expiration is a normal interrupt (MCM\_ETBCC[RSPT] = 01)



# **Chapter 17 Crossbar Switch (AXBS)**

### 17.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

This chapter provides information on the layout, configuration, and programming of the crossbar switch. The crossbar switch connects bus masters and bus slaves using a crossbar switch structure. This structure allows all bus masters to access different bus slaves simultaneously, while providing arbitration among the bus masters when they access the same slave. A variety of bus arbitration methods and attributes may be programmed on a slave by slave basis.

### 17.1.1 Features

The crossbar switch includes these distinctive features:

- Symmetric crossbar bus switch implementation
  - Allows concurrent accesses from different masters to different slaves
  - Slave arbitration attributes configured on a slave by slave basis
- 32-bit width and support for byte, 2-byte, 4-byte, and 16-byte burst transfers
- Operation at a 1-to-1 clock frequency with the bus masters
- Low-Power Park mode support



# 17.2 Memory Map / Register Definition

Each slave port of the crossbar switch contains configuration registers. Read- and write-transfers require two bus clock cycles. The registers can be read from and written to only in supervisor mode. Additionally, these registers can be read from or written to only by 32-bit accesses.

A bus error response is returned if an unimplemented location is accessed within the crossbar switch.

The slave registers also feature a bit that, when set, prevents the registers from being written. The registers remain readable, but future write attempts have no effect on the registers and are terminated with a bus error response to the master initiating the write. The core, for example, takes a bus error interrupt.

#### NOTE

This section shows the registers for all eight master and slave ports. If a master or slave is not used on this particular device, then unexpected results occur when writing to its registers. See the chip configuration details for the exact master/slave assignments for your device.

#### **AXBS** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_4000	Priority Registers Slave (AXBS_PRS0)	32	R/W	7654_3210h	17.2.1/353
4000_4010	Control Register (AXBS_CRS0)	32	R/W	0000_0000h	17.2.2/356
4000_4100	Priority Registers Slave (AXBS_PRS1)	32	R/W	7654_3210h	17.2.1/353
4000_4110	Control Register (AXBS_CRS1)	32	R/W	0000_0000h	17.2.2/356
4000_4200	Priority Registers Slave (AXBS_PRS2)	32	R/W	7654_3210h	17.2.1/353
4000_4210	Control Register (AXBS_CRS2)	32	R/W	0000_0000h	17.2.2/356
4000_4300	Priority Registers Slave (AXBS_PRS3)	32	R/W	7654_3210h	17.2.1/353
4000_4310	Control Register (AXBS_CRS3)	32	R/W	0000_0000h	17.2.2/356
4000_4400	Priority Registers Slave (AXBS_PRS4)	32	R/W	7654_3210h	17.2.1/353
4000_4410	Control Register (AXBS_CRS4)	32	R/W	0000_0000h	17.2.2/356
4000_4500	Priority Registers Slave (AXBS_PRS5)	32	R/W	7654_3210h	17.2.1/353
4000_4510	Control Register (AXBS_CRS5)	32	R/W	0000_0000h	17.2.2/356



### **AXBS** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_4600	Priority Registers Slave (AXBS_PRS6)	32	R/W	7654_3210h	17.2.1/353
4000_4610	Control Register (AXBS_CRS6)	32	R/W	0000_0000h	17.2.2/356
4000_4700	Priority Registers Slave (AXBS_PRS7)	32	R/W	7654_3210h	17.2.1/353
4000_4710	Control Register (AXBS_CRS7)	32	R/W	0000_0000h	17.2.2/356
4000_4800	Master General Purpose Control Register (AXBS_MGPCR0)	32	R/W	0000_0000h	17.2.3/358
4000_4900	Master General Purpose Control Register (AXBS_MGPCR1)	32	R/W	0000_0000h	17.2.3/358
4000_4A00	Master General Purpose Control Register (AXBS_MGPCR2)	32	R/W	0000_0000h	17.2.3/358
4000_4B00	Master General Purpose Control Register (AXBS_MGPCR3)	32	R/W	0000_0000h	17.2.3/358
4000_4C00	Master General Purpose Control Register (AXBS_MGPCR4)	32	R/W	0000_0000h	17.2.3/358
4000_4D00	Master General Purpose Control Register (AXBS_MGPCR5)	32	R/W	0000_0000h	17.2.3/358
4000_4E00	Master General Purpose Control Register (AXBS_MGPCR6)	32	R/W	0000_0000h	17.2.3/358
4000_4F00	Master General Purpose Control Register (AXBS_MGPCR7)	32	R/W	0000_0000h	17.2.3/358

# 17.2.1 Priority Registers Slave (AXBS\_PRSn)

The priority registers (PRSn) set the priority of each master port on a per slave port basis and reside in each slave port. The priority register can be accessed only with 32-bit accesses. After the CRSn[RO] bit is set, the PRSn register can only be read; attempts to write to it have no effect on PRSn and result in a bus-error response to the master initiating the write.

No two available master ports may be programmed with the same priority level. Attempts to program two or more masters with the same priority level result in a bus-error response and the PRSn is not updated.

#### NOTE

The possible values for the PRSn fields depend on the number of masters available on the device. See the device's Chip Configuration details for the number of masters supported.



#### wemory Map / Register Definition

- If the device contains less than five masters, values 000–011 are valid and writing other values results in an error.
- If the device contains n masters where  $n \ge 5$ , values 0 to n-1 are valid and writing other values results in an error.

Addresses: AXBS\_PRS0 is 4000\_4000h base + 0h offset = 4000\_4000h

AXBS\_PRS1 is 4000\_4000h base + 100h offset = 4000\_4100h

AXBS\_PRS2 is 4000\_4000h base + 200h offset = 4000\_4200h


AXBS\_PRS3 is 4000\_4000h base + 300h offset = 4000\_4300h

AXBS\_PRS4 is 4000\_4000h base + 400h offset = 4000\_4400h

AXBS\_PRS5 is 4000\_4000h base + 500h offset = 4000\_4500h

AXBS\_PRS6 is 4000\_4000h base + 600h offset = 4000\_4600h

AXBS\_PRS7 is 4000\_4000h base + 700h offset = 4000\_4700h



### AXBS\_PRSn field descriptions

Field	Description			
31 Reserved	This read-only field is reserved and always has the value zero.			
30–28 M7	Master 7 priority. Sets the arbitration priority for this port on the associated slave port.			
	000 This master has level 1, or highest, priority when accessing the slave port.			
	001 This master has level 2 priority when accessing the slave port.			
	010 This master has level 3 priority when accessing the slave port.			
	011 This master has level 4 priority when accessing the slave port.			
	100 This master has level 5 priority when accessing the slave port.			
	101 This master has level 6 priority when accessing the slave port.			
	110 This master has level 7 priority when accessing the slave port.			
	111 This master has level 8, or lowest, priority when accessing the slave port.			
27 Reserved	This read-only field is reserved and always has the value zero.			
26–24 M6	Master 6 priority. Sets the arbitration priority for this port on the associated slave port.			
	000 This master has level 1, or highest, priority when accessing the slave port.			
	001 This master has level 2 priority when accessing the slave port.			
	010 This master has level 3 priority when accessing the slave port.			
	011 This master has level 4 priority when accessing the slave port.			
	100 This master has level 5 priority when accessing the slave port.			
	101 This master has level 6 priority when accessing the slave port.			
	110 This master has level 7 priority when accessing the slave port.			
	111 This master has level 8, or lowest, priority when accessing the slave port.			
23 Reserved	This read-only field is reserved and always has the value zero.			



# AXBS\_PRSn field descriptions (continued)

Field	Description
22–20	Master 5 priority. Sets the arbitration priority for this port on the associated slave port.
M5	000 This master has level 1, or highest, priority when accessing the slave port.
	001 This master has level 2 priority when accessing the slave port.
	010 This master has level 3 priority when accessing the slave port.
	011 This master has level 4 priority when accessing the slave port.
	100 This master has level 5 priority when accessing the slave port.
	101 This master has level 6 priority when accessing the slave port.
	110 This master has level 7 priority when accessing the slave port.
	111 This master has level 8, or lowest, priority when accessing the slave port.
19 Reserved	This read-only field is reserved and always has the value zero.
18–16 M4	Master 4 priority. Sets the arbitration priority for this port on the associated slave port.
	O00 This master has level 1, or highest, priority when accessing the slave port.
	001 This master has level 2 priority when accessing the slave port.
	010 This master has level 3 priority when accessing the slave port.
	O11 This master has level 4 priority when accessing the slave port.
	100 This master has level 5 priority when accessing the slave port.
	101 This master has level 6 priority when accessing the slave port.
	110 This master has level 7 priority when accessing the slave port.  111 This master has level 8, or lowest, priority when accessing the slave port.
	, , , , ,
15 Reserved	This read-only field is reserved and always has the value zero.
14–12 M3	Master 3 priority. Sets the arbitration priority for this port on the associated slave port.
	O00 This master has level 1, or highest, priority when accessing the slave port.
	001 This master has level 2 priority when accessing the slave port.
	010 This master has level 3 priority when accessing the slave port.
	O11 This master has level 4 priority when accessing the slave port.
	100 This master has level 5 priority when accessing the slave port.
	101 This master has level 6 priority when accessing the slave port.
	<ul> <li>This master has level 7 priority when accessing the slave port.</li> <li>This master has level 8, or lowest, priority when accessing the slave port.</li> </ul>
11 Reserved	This read-only field is reserved and always has the value zero.
10–8 M2	Master 2 priority. Sets the arbitration priority for this port on the associated slave port.
	000 This master has level 1, or highest, priority when accessing the slave port.
	001 This master has level 2 priority when accessing the slave port.
	010 This master has level 3 priority when accessing the slave port.
	O11 This master has level 4 priority when accessing the slave port.
	100 This master has level 5 priority when accessing the slave port.
	101 This master has level 6 priority when accessing the slave port.
	110 This master has level 7 priority when accessing the slave port.
	111 This master has level 8, or lowest, priority when accessing the slave port.


#### wemory Map / Register Definition

### AXBS\_PRSn field descriptions (continued)

Field	Description
7	This read-only field is reserved and always has the value zero.
Reserved	
6–4 M1	Master 1 priority. Sets the arbitration priority for this port on the associated slave port.
	000 This master has level 1, or highest, priority when accessing the slave port.
	001 This master has level 2 priority when accessing the slave port.
	010 This master has level 3 priority when accessing the slave port.
	011 This master has level 4 priority when accessing the slave port.
	100 This master has level 5 priority when accessing the slave port.
	101 This master has level 6 priority when accessing the slave port.
	110 This master has level 7 priority when accessing the slave port.
	111 This master has level 8, or lowest, priority when accessing the slave port.
3 Reserved	This read-only field is reserved and always has the value zero.
2-0 M0	Master 0 priority. Sets the arbitration priority for this port on the associated slave port.
	000 This master has level 1, or highest, priority when accessing the slave port.
	001 This master has level 2 priority when accessing the slave port.
	010 This master has level 3 priority when accessing the slave port.
	011 This master has level 4 priority when accessing the slave port.
	100 This master has level 5 priority when accessing the slave port.
	101 This master has level 6 priority when accessing the slave port.
	110 This master has level 7 priority when accessing the slave port.
	111 This master has level 8, or lowest, priority when accessing the slave port.

# 17.2.2 Control Register (AXBS\_CRSn)

These registers control several features of each slave port and must be accessed using 32-bit accesses. After CRSn[RO] is set, the CRSn can only be read; attempts to write to it have no effect and result in an error response.



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

0

0 0

0 0

0

Reset 0



# AXBS\_CRSn field descriptions

Field	Description
31	Read only
RO	Forces the slave port's CSRn and PRSn registers to be read-only. After set, only a hardware reset clears it.
	<ul> <li>The slave port's registers are writeable</li> <li>The slave port's registers are read-only and cannot be written. Attempted writes have no effect on the registers and result in a bus error response.</li> </ul>
30	Halt low priority
HLP	Sets the initial arbitration priority for low power mode requests. Setting this bit will not effect the request for low power mode from attaining highest priority once it has control of the slave ports.
	<ul> <li>The low power mode request has the highest priority for arbitration on this slave port</li> <li>The low power mode request has the lowest initial priority for arbitration on this slave port</li> </ul>
29–10 Reserved	This read-only field is reserved and always has the value zero.
9–8 ADD	Arbitration mode
ARB	Selects the arbitration policy for the slave port.
	00 Fixed priority
	01 Round-robin, or rotating, priority
	10 Reserved
	11 Reserved
7–6 Reserved	This read-only field is reserved and always has the value zero.
5–4 DCTI	Parking control
PCTL	Determines the slave port's parking control. The low-power park feature results in an overall power savings if the slave port is not saturated. However, this forces an extra latency clock when any master tries to access the slave port while not in use because it is not parked on any master.
	00 When no master makes a request, the arbiter parks the slave port on the master port defined by the PARK bit field
	01 When no master makes a request, the arbiter parks the slave port on the last master to be in control of the slave port
	When no master makes a request, the slave port is not parked on a master and the arbiter drives all outputs to a constant safe state
	11 Reserved
3 Reserved	This read-only field is reserved and always has the value zero.
2–0 PARK	Park
	Determines which master port the current slave port parks on when no masters are actively making requests and the PCTL bits are cleared.
	NOTE: Only select master ports that are actually present on the device. If not, undefined behavior may occur.
	000 Park on master port M0




#### wemory Map / Register Definition

### AXBS\_CRSn field descriptions (continued)

Field	Description
	001 Park on master port M1
	010 Park on master port M2
	011 Park on master port M3
	100 Park on master port M4
	101 Park on master port M5
	110 Reserved
	111 Reserved

# 17.2.3 Master General Purpose Control Register (AXBS\_MGPCRn)

The MGPCR controls only whether the master's undefined length burst accesses are allowed to complete uninterrupted or whether they can be broken by requests from higher priority masters. The MGPCR can only be accessed in Supervisor mode with 32-bit accesses.



### AXBS\_MGPCRn field descriptions

Field	Description
31–3 Reserved	This read-only field is reserved and always has the value zero.
2–0 AULB	Arbitrates on undefined length bursts
	Determines whether, and when, the crossbar switch arbitrates away the slave port the master owns when the master is performing undefined length burst accesses.
	000 No arbitration is allowed during an undefined length burst
	001 Arbitration is allowed at any time during an undefined length burst
	010 Arbitration is allowed after four beats of an undefined length burst
	011 Arbitration is allowed after eight beats of an undefined length burst
	100 Arbitration is allowed after 16 beats of an undefined length burst

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



### AXBS\_MGPCRn field descriptions (continued)

Field	Description
	101 Reserved
	110 Reserved
	111 Reserved

# 17.3 Functional Description

# 17.3.1 General operation

When a master accesses the crossbar switch the access is immediately taken. If the targeted slave port of the access is available, then the access is immediately presented on the slave port. It is possible to make single-clock, or zero wait state, accesses through the crossbar. If the targeted slave port of the access is busy or parked on a different master port, the requesting master simply sees wait states inserted until the targeted slave port can service the master's request. The latency in servicing the request depends on each master's priority level and the responding peripheral's access time.

Because the crossbar switch appears to be just another slave to the master device, the master device has no knowledge of whether it actually owns the slave port it is targeting. While the master does not have control of the slave port it is targeting, it simply waits.

A master is given control of the targeted slave port only after a previous access to a different slave port completes, regardless of its priority on the newly targeted slave port. This prevents deadlock from occurring when:

- A higher priority master has:
  - An outstanding request to one slave port that has a long response time and
  - A pending access to a different slave port, and
- A lower priority master is also making a request to the same slave port as the pending access of the higher priority master.

After the master has control of the slave port it is targeting, the master remains in control of that slave port until it gives up the slave port by running an IDLE cycle or by leaving that slave port for its next access.

The master could also lose control of the slave port if another higher priority master makes a request to the slave port; however, if the master is running a fixed-length burst transfer it retains control of the slave port until that transfer completes. Based on MGPCR[AULB], the master either retains control of the slave port when doing undefined length incrementing burst transfers or loses the bus to a higher priority master.



#### runctional Description

The crossbar terminates all master IDLE transfers, as opposed to allowing the termination to come from one of the slave busses. Additionally, when no master is requesting access to a slave port, the crossbar drives IDLE transfers onto the slave bus, even though a default master may be granted access to the slave port.

When a slave bus is being idled by the crossbar, it can park the slave port on the master port indicated by CRSn[PARK]. This is done to save the initial clock of arbitration delay that otherwise would be seen if the master had to arbitrate to gain control of the slave port. The slave port can also be put into Low Power Park mode to save power, by using CRSn[PCTL].

# 17.3.2 Register coherency

Because the content of the registers has a real-time effect on the operation of the crossbar, it is important to understand that any register modifications take effect as soon as the register is written. The values of the registers do not track with slave-port-related master accesses, but instead track only with slave accesses.

The MGPCRx[AULB] bits are the exception to this rule. The update of these bits is only recognized when the master on that master port runs an IDLE cycle, even though the slave bus cycle to write them will have already terminated successfully. If the MGPCRx[AULB] bits are written between two burst accesses, the new AULB encodings do not take effect until an IDLE cycle is initiated by the master on that master port.

# 17.3.3 Arbitration

The crossbar switch supports two arbitration schemes:

- A fixed-priority comparison algorithm
- A round-robin fairness algorithm

The arbitration scheme is independently programmable for each slave port.

# 17.3.3.1 Arbitration during undefined length bursts

Arbitration points during an undefined length burst are defined by the current master's MGPCR[AULB] field setting. When a defined length is imposed on the burst via the AULB bits, the undefined length burst is treated as a single or series of single back-to-back fixed-length burst accesses.

The following figure illustrates an example:



Figure 17-28. Undefined length burst example

In this example, a master runs an undefined length burst and the MGPCR[AULB] bits indicate arbitration occurs after the fourth beat of the burst. The master runs two sequential beats and then starts what will be a 12-beat undefined length burst access to a new address within the same slave port region as the previous access. The crossbar does not allow an arbitration point until the fourth overall access, or the second beat of the second burst. At that point, all remaining accesses are open for arbitration until the master loses control of the slave port.

Assume the master loses control of the slave port after the fifth beat of the second burst. After the master regains control of the slave port no arbitration point is available until after the master has run four more beats of its burst. After the fourth beat of the now continued burst, or the ninth beat of the second burst from the master's perspective, is taken, all beats of the burst are once again open for arbitration until the master loses control of the slave port.

Assume the master again loses control of the slave port on the fifth beat of the third now continued burst, or the 10th beat of the second burst from the master's perspective. After the master regains control of the slave port, it is allowed to complete its final two beats of its burst without facing arbitration.

#### **Note**

Fixed-length burst accesses are not affected by the AULB bits. All fixed-length burst accesses lock out arbitration until the last beat of the fixed-length burst.

## 17.3.3.2 Fixed-priority operation

When operating in Fixed-Priority mode, each master is assigned a unique priority level in the priority registers (PRSn). If two masters request access to a slave port, the master with the highest priority in the selected priority register gains control over the slave port.



#### runctional Description

When a master makes a request to a slave port, the slave port checks if the new requesting master's priority level is higher than that of the master that currently has control over the slave port, unless the slave port is in a parked state. The slave port performs an arbitration check at every clock edge to ensure that the proper master, if any, has control of the slave port.

The following table describes possible scenarios based on the requesting master port:

Table 17-29. How AXBS grants control of a slave port to a master

When	Then AXBS grants control to the requesting master
Both of the following are true:  The current master is not running a transfer.  The new requesting master's priority level is higher than that of the current master.	At the next clock edge
Both of the following are true:         • The current master is running a fixed length burst transfer or a locked transfer.         • The requesting master's priority level is higher than that of the current master.	At the end of the burst transfer or locked transfer
The master is running an undefined length burst transfer.	At the next arbitration point
	NOTE: Arbitration points for an undefined length burst are defined in the MGPCR for each master.
The requesting master's priority level is lower than the current master.	At the conclusion of one of the following cycles:  • An IDLE cycle  • A non-IDLE cycle to a location other than the current slave port

## 17.3.3.3 Round-robin priority operation

When operating in Round-Robin mode, each master is assigned a relative priority based on the master port number. This relative priority is compared to the master port number (ID) of the last master to perform a transfer on the slave bus. The highest priority requesting master becomes owner of the slave bus at the next transfer boundary, accounting for locked and fixed-length burst transfers. Priority is based on how far ahead the ID of the requesting master is to the ID of the last master.

After granted access to a slave port, a master may perform as many transfers as desired to that port until another master makes a request to the same slave port. The next master in line is granted access to the slave port at the next transfer boundary, or possibly on the next clock cycle if the current master has no pending access request.

As an example of arbitration in Round-Robin mode, assume the crossbar is implemented with master ports 0, 1, 4, and 5. If the last master of the slave port was master 1, and master 0, 4 and 5 make simultaneous requests, they are serviced in the order 4, 5, and then 0.



Parking may continue to be used in a round-robin mode, but does not affect the round-robin pointer unless the parked master actually performs a transfer. Handoff occurs to the next master in line after one cycle of arbitration. If the slave port is put into low-power park mode, the round-robin pointer is reset to point at master port 0, giving it the highest priority.

## 17.3.3.4 Priority assignment

Each master port needs to be assigned a unique 3-bit priority level. If an attempt is made to program multiple master ports with the same priority level within the priority registers (PRSn), the crossbar switch responds with a bus error and the registers are not updated.

# 17.4 Initialization/application information

No initialization is required by or for the crossbar switch. Hardware reset ensures all the register bits used by the crossbar switch are properly initialized to a valid state. Settings and priorities should be programmed to achieve maximum system performance.



**ınınalization/application information** 



# **Chapter 18 Memory Protection Unit (MPU)**

## 18.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The Memory Protection Unit (MPU) provides hardware access control for all memory references generated in the device.

## 18.2 Overview

The MPU concurrently monitors all system bus transactions and evaluates their appropriateness using pre-programmed region descriptors that define memory spaces and their access rights. Memory references that have sufficient access control rights are allowed to complete, while references that are not mapped to any region descriptor or have insufficient rights are terminated with a protection error response.

## 18.2.1 Block Diagram

A simplified block diagram of the MPU module is shown in the following figure. The hardware's two-dimensional connection matrix is clearly visible with the basic access evaluation macro shown as the replicated submodule block. The crossbar switch slave ports are shown on the left, the region descriptor registers in the middle, and the peripheral bus interface on the right side. The evaluation macro contains two magnitude comparators connected to the start and end address registers from each region descriptor as well as the combinational logic blocks to determine the region hit and the access protection error. For details of the access evaluation macro, see Access Evaluation Macro.






Figure 18-1. MPU Block Diagram

## 18.2.2 Features

The MPU implements a two-dimensional hardware array of memory region descriptors and the crossbar slave ports to continuously monitor the legality of every memory reference generated by each bus master in the system. The feature set includes:

- 12 program-visible 128-bit region descriptors, accessible by four 32-bit words each
  - Each region descriptor defines a modulo-32 byte space, aligned anywhere in memory
    - Region sizes can vary from 32 bytes to 4 Gbytes
  - Two access control permissions defined in a single descriptor word
    - Masters 0–3: read, write, and execute attributes for supervisor and user accesses
    - Masters 4–7: read and write attributes
  - Hardware-assisted maintenance of the descriptor valid bit minimizes coherency issues



- Alternate programming model view of the access control permissions word
- Priority given to granting permission over denying access for overlapping region descriptors
- Detects access protection errors if a memory reference does not hit in any memory region, or if the reference is illegal in all hit memory regions. If an access error occurs, the reference is terminated with an error response, and the MPU inhibits the bus cycle being sent to the targeted slave device.
- Error registers (per slave port) capture the last faulting address, attributes, and other information
- Global MPU enable/disable control bit

# 18.3 Memory Map/Register Definition

The programming model is partitioned into three groups: control/status registers, the data structure containing the region descriptors, and the alternate view of the region descriptor access control values.

The programming model can only be referenced using 32-bit accesses. Attempted references using different access sizes, to undefined (reserved) addresses, or with a non-supported access type (a write to a read-only register, or a read of a write-only register) generate an error termination.

The programming model can be accessed only in supervisor mode.

#### NOTE

See the chip configuration details for any chip-specific register information for this module.

### MPU memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_D000	Control/Error Status Register (MPU_CESR)	32	R/W	0081_5101h	18.3.1/370
4000_D010	Error Address Register, Slave Port n (MPU_EAR0)	32	R	Undefined	18.3.2/372
4000_D014	Error Detail Register, Slave Port n (MPU_EDR0)	32	R	Undefined	18.3.3/373
4000_D018	Error Address Register, Slave Port n (MPU_EAR1)	32	R	Undefined	18.3.2/372
4000_D01C	Error Detail Register, Slave Port n (MPU_EDR1)	32	R	Undefined	18.3.3/373



# wemory Map/Register Definition

# MPU memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_D020	Error Address Register, Slave Port n (MPU_EAR2)	32	R	Undefined	18.3.2/372
4000_D024	Error Detail Register, Slave Port n (MPU_EDR2)	32	R	Undefined	18.3.3/373
4000_D028	Error Address Register, Slave Port n (MPU_EAR3)	32	R	Undefined	18.3.2/372
4000_D02C	Error Detail Register, Slave Port n (MPU_EDR3)	32	R	Undefined	18.3.3/373
4000_D030	Error Address Register, Slave Port n (MPU_EAR4)	32	R	Undefined	18.3.2/372
4000_D034	Error Detail Register, Slave Port n (MPU_EDR4)	32	R	Undefined	18.3.3/373
4000_D400	Region Descriptor n, Word 0 (MPU_RGD0_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D404	Region Descriptor n, Word 1 (MPU_RGD0_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D408	Region Descriptor n, Word 2 (MPU_RGD0_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D40C	Region Descriptor n, Word 3 (MPU_RGD0_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D410	Region Descriptor n, Word 0 (MPU_RGD1_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D414	Region Descriptor n, Word 1 (MPU_RGD1_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D418	Region Descriptor n, Word 2 (MPU_RGD1_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D41C	Region Descriptor n, Word 3 (MPU_RGD1_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D420	Region Descriptor n, Word 0 (MPU_RGD2_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D424	Region Descriptor n, Word 1 (MPU_RGD2_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D428	Region Descriptor n, Word 2 (MPU_RGD2_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D42C	Region Descriptor n, Word 3 (MPU_RGD2_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D430	Region Descriptor n, Word 0 (MPU_RGD3_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D434	Region Descriptor n, Word 1 (MPU_RGD3_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D438	Region Descriptor n, Word 2 (MPU_RGD3_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D43C	Region Descriptor n, Word 3 (MPU_RGD3_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D440	Region Descriptor n, Word 0 (MPU_RGD4_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D444	Region Descriptor n, Word 1 (MPU_RGD4_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D448	Region Descriptor n, Word 2 (MPU_RGD4_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D44C	Region Descriptor n, Word 3 (MPU_RGD4_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D450	Region Descriptor n, Word 0 (MPU_RGD5_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D454	Region Descriptor n, Word 1 (MPU_RGD5_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D458	Region Descriptor n, Word 2 (MPU_RGD5_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D45C	Region Descriptor n, Word 3 (MPU_RGD5_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D460	Region Descriptor n, Word 0 (MPU_RGD6_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D464	Region Descriptor n, Word 1 (MPU_RGD6_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D468	Region Descriptor n, Word 2 (MPU_RGD6_WORD2)	32	R/W	0000_0000h	18.3.6/375



# MPU memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_D46C	Region Descriptor n, Word 3 (MPU_RGD6_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D470	Region Descriptor n, Word 0 (MPU_RGD7_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D474	Region Descriptor n, Word 1 (MPU_RGD7_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D478	Region Descriptor n, Word 2 (MPU_RGD7_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D47C	Region Descriptor n, Word 3 (MPU_RGD7_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D480	Region Descriptor n, Word 0 (MPU_RGD8_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D484	Region Descriptor n, Word 1 (MPU_RGD8_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D488	Region Descriptor n, Word 2 (MPU_RGD8_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D48C	Region Descriptor n, Word 3 (MPU_RGD8_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D490	Region Descriptor n, Word 0 (MPU_RGD9_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D494	Region Descriptor n, Word 1 (MPU_RGD9_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D498	Region Descriptor n, Word 2 (MPU_RGD9_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D49C	Region Descriptor n, Word 3 (MPU_RGD9_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D4A0	Region Descriptor n, Word 0 (MPU_RGD10_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D4A4	Region Descriptor n, Word 1 (MPU_RGD10_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D4A8	Region Descriptor n, Word 2 (MPU_RGD10_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D4AC	Region Descriptor n, Word 3 (MPU_RGD10_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D4B0	Region Descriptor n, Word 0 (MPU_RGD11_WORD0)	32	R/W	0000_0000h	18.3.4/374
4000_D4B4	Region Descriptor n, Word 1 (MPU_RGD11_WORD1)	32	R/W	0000_001Fh	18.3.5/375
4000_D4B8	Region Descriptor n, Word 2 (MPU_RGD11_WORD2)	32	R/W	0000_0000h	18.3.6/375
4000_D4BC	Region Descriptor n, Word 3 (MPU_RGD11_WORD3)	32	R/W	0000_0000h	18.3.7/378
4000_D800	Region Descriptor Alternate Access Control n (MPU_RGDAAC0)	32	R/W	0000_0000h	18.3.8/379
4000_D804	Region Descriptor Alternate Access Control n (MPU_RGDAAC1)	32	R/W	0000_0000h	18.3.8/379
4000_D808	Region Descriptor Alternate Access Control n (MPU_RGDAAC2)	32	R/W	0000_0000h	18.3.8/379
4000_D80C	Region Descriptor Alternate Access Control n (MPU_RGDAAC3)	32	R/W	0000_0000h	18.3.8/379
4000_D810	Region Descriptor Alternate Access Control n (MPU_RGDAAC4)	32	R/W	0000_0000h	18.3.8/379
4000_D814	Region Descriptor Alternate Access Control n (MPU_RGDAAC5)	32	R/W	0000_0000h	18.3.8/379
4000_D818	Region Descriptor Alternate Access Control n (MPU_RGDAAC6)	32	R/W	0000_0000h	18.3.8/379


# wemory Map/Register Definition

## MPU memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_D81C	Region Descriptor Alternate Access Control n (MPU_RGDAAC7)	32	R/W	0000_0000h	18.3.8/379
4000_D820	Region Descriptor Alternate Access Control n (MPU_RGDAAC8)	32	R/W	0000_0000h	18.3.8/379
4000_D824	Region Descriptor Alternate Access Control n (MPU_RGDAAC9)	32	R/W	0000_0000h	18.3.8/379
4000_D828	Region Descriptor Alternate Access Control n (MPU_RGDAAC10)	32	R/W	0000_0000h	18.3.8/379
4000_D82C	Region Descriptor Alternate Access Control n (MPU_RGDAAC11)	32	R/W	0000_0000h	18.3.8/379

# **Control/Error Status Register (MPU\_CESR)**

Address: MPU\_CESR is 4000\_D000h base + 0h offset = 4000\_D000h



### MPU\_CESR field descriptions

Field	Description
31–27 SPERR	Slave port n error
G. 21.11.	Indicates a captured error in EARn and EDRn. This bit is set when the hardware detects an error and records the faulting address and attributes. It is cleared by writing one to it. If another error is captured at the exact same cycle as the write, the flag remains set. A find-first-one instruction (or equivalent) can detect the presence of a captured error.
	The following shows the correspondence between the bit number and slave port number:
	<ul> <li>Bit 31 corresponds to slave port 0.</li> <li>Bit 30 corresponds to slave port 1.</li> <li>Bit 29 corresponds to slave port 2.</li> <li>Bit 28 corresponds to slave port 3.</li> <li>Bit 27 corresponds to slave port 4.</li> </ul>
	<ul><li>No error has occurred for slave port n.</li><li>An error has occurred for slave port n.</li></ul>
26–24 Reserved	This read-only field is reserved and always has the value zero.
23 Reserved	This read-only field is reserved and always has the value one.



# MPU\_CESR field descriptions (continued)

Field	Description
22–20 Reserved	This read-only field is reserved and always has the value zero.
19–16 HRL	Hardware revision level  Specifies the MPU's hardware and definition revision level. It can be read by software to determine the functional definition of the module.
15–12 NSP	Number of slave ports Specifies the number of slave ports connected to the MPU.
11–8 NRGD	Number of region descriptors  Indicates the number of region descriptors implemented in the MPU.  0000 8 region descriptors  0001 12 region descriptors  0010 16 region descriptors
7–1 Reserved	This read-only field is reserved and always has the value zero.
0 VLD	Valid (global enable/disable for the MPU)  0 MPU is disabled. All accesses from all bus masters are allowed.  1 MPU is enabled



## 18.3.2 Error Address Register, Slave Port n (MPU\_EARn)

When the MPU detects an access error on slave port n, the 32-bit reference address is captured in this read-only register and the corresponding bit in CESR[SPERR] set. Additional information about the faulting access is captured in the corresponding EDRn at the same time. This register and the corresponding EDRn contain the most recent access error; there are no hardware interlocks with CESR[SPERR], as the error registers are always loaded upon the occurrence of each protection violation.

### MPU\_EARn field descriptions

Field	Description
31–0 EADDR	Error address
	Indicates the reference address from slave port n that generated the access error


<sup>\*</sup> Notes:

x = Undefined at reset.



## 18.3.3 Error Detail Register, Slave Port n (MPU\_EDRn)

When the MPU detects an access error on slave port n, 32 bits of error detail are captured in this read-only register and the corresponding bit in CESR[SPERR] is set. Information on the faulting address is captured in the corresponding EARn register at the same time. This register and the corresponding EARn register contain the most recent access error; there are no hardware interlocks with CESR[SPERR] as the error registers are always loaded upon the occurrence of each protection violation.



<sup>\*</sup> Notes:

#### MPU\_EDRn field descriptions

Field	Description
31–16 EACD	Error access control detail
	Indicates the region descriptor with the access error.
	If EDRn contains a captured error and EACD is cleared, an access did not hit in any region descriptor. If only a single EACD bit is set, the protection error was caused by a single non-overlapping region descriptor. If two or more EACD bits are set, the protection error was caused by an overlapping set of region descriptors.
15–8 Reserved	This read-only field is reserved and always has the value zero.
7–4 EMN	Error master number
	Indicates the bus master that generated the access error.
3–1 EATTR	Error attributes
	Indicates attribute information about the faulting reference.

x = Undefined at reset.



#### wemory Map/Register Definition


## MPU\_EDRn field descriptions (continued)

Field	Description
	NOTE: All other encodings are reserved.
	000 User mode, instruction access
	001 User mode, data access
	010 Supervisor mode, instruction access
	011 Supervisor mode, data access
0	Error read/write
ERW	Indicates the access type of the faulting reference.
	0 Read
	1 Write

## 18.3.4 Region Descriptor n, Word 0 (MPU\_RGD\_WORD0)

The first word of the region descriptor defines the 0-modulo-32 byte start address of the memory region. Writes to this register clear the region descriptor's valid bit (RGDn\_WORD3[VLD]).

Addresses: 4000\_D000h base + 400h offset +  $(16d \times n)$ , where n = 0d to 11d




### MPU\_RGDn\_WORD0 field descriptions

Field	Description
31–5 SRTADDR	Start address
	Defines the most significant bits of the 0-modulo-32 byte start address of the memory region.
4–0 Reserved	This read-only field is reserved and always has the value zero.



## 18.3.5 Region Descriptor n, Word 1 (MPU\_RGD\_WORD1)

The second word of the region descriptor defines the 31-modulo-32 byte end address of the memory region. Writes to this register clear the region descriptor's valid bit (RGDn\_WORD3[VLD]).



#### MPU\_RGDn\_WORD1 field descriptions

Field	Description
31–5	End address
ENDADDR	Defines the most significant bits of the 31-modulo-32 byte end address of the memory region.
	NOTE: The MPU does not verify that ENDADDR ≥ SRTADDR.
4–0 Reserved	This field is reserved.

## 18.3.6 Region Descriptor n, Word 2 (MPU\_RGD\_WORD2)

The third word of the region descriptor defines the access control rights of the memory region. The access control privileges depend on two broad classifications of bus masters:

- Bus masters 0–3 have a 5-bit field defining separate privilege rights for user and supervisor mode accesses.
- Bus masters 4–7 are limited to separate read and write permissions.

For the privilege rights of bus masters 0–3, there are three flags associated with this function:

- Read (r) refers to accessing the referenced memory address using an operand (data) fetch
- Write (w) refers to updating the referenced memory address using a store (data) instruction
- Execute (x) refers to reading the referenced memory address using an instruction fetch



#### wemory Map/Register Definition

M2SM

[bit 0]

W

Reset

M2UM

0

0

0

Writes to RGDn\_WORD2 clear the region descriptor's valid bit (RGDn\_WORD3[VLD]). If only updating the access controls, write to RGDAACn instead because stores to these locations do not affect the descriptor's valid bit.

Addresses:  $4000\_D000h$  base + 408h offset +  $(16d \times n)$ , where n = 0d to 11dBit 31 21 17 20 19 18 16 R M6WE M5WE M4WE Reserved Reserved M5RE M6RE M4RE M2SM M3SM M3UM [-14:1] W Reset 0 0 0 0 0 0 0 0 0 11 Bit 15 13 12 10 5 R Reserved

### MPU\_RGDn\_WORD2 field descriptions

M1UM

M0SM

0

0

0

0

M0UM

0

M1SM

0

0

0

Field	Description
31 M7RE	Bus master 7 read enable.
	0 Bus master 7 reads terminate with an access error and the read is not performed
	1 Bus master 7 reads allowed
30 M7WE	Bus master 7 write enable
	0 Bus master 7 writes terminate with an access error and the write is not performed
	1 Bus master 7 writes allowed
29 M6RE	Bus master 6 read enable.
	0 Bus master 6 reads terminate with an access error and the read is not performed
	1 Bus master 6 reads allowed
28 M6WE	Bus master 6 write enable
	0 Bus master 6 writes terminate with an access error and the write is not performed
	1 Bus master 6 writes allowed
27 M5RE	Bus master 5 read enable.
	0 Bus master 5 reads terminate with an access error and the read is not performed
	1 Bus master 5 reads allowed
26 M5WE	Bus master 5 write enable
	0 Bus master 5 writes terminate with an access error and the write is not performed
	1 Bus master 5 writes allowed
25 M4RE	Bus master 4 read enable.



# MPU\_RGDn\_WORD2 field descriptions (continued)

Field	Description						
- 13.0	Bus master 4 reads terminate with an access error and the read is not performed						
	1 Bus master 4 reads allowed						
24	Bus master 4 write enable						
M4WE	0. Rue mactor 4 writes terminate with an access error and the write is not performed						
	Bus master 4 writes terminate with an access error and the write is not performed     Bus master 4 writes allowed						
23	This field is reserved.						
Reserved	This bit must be written with a zero.						
22–21	Bus master 3 supervisor mode access control						
M3SM							
	Defines the access controls for bus master 3 in supervisor mode						
	00 r/w/x; read, write and execute allowed						
	01 r/x; read and execute allowed, but no write						
	10 r/w; read and write allowed, but no execute						
	11 Same as user mode defined in M3UM						
20–18 M3UM	Bus master 3 user mode access control						
IVIOUVI	Defines the access controls for bus master 3 in user mode. M3UM consists of three independent bits,						
	enabling read (r), write (w), and execute (x) permissions.						
	O An attempted access of that mode may be terminated with an access error (if not allowed by another						
	descriptor) and the access not performed.						
	1 Allows the given access type to occur						
17 Reserved	This field is reserved. This bit must be written with a zero.						
16–15 M2SM	Bus master 2 supervisor mode access control						
	See M3SM description						
14–12	Bus master 2 user mode access control						
M2UM	See M3UM description						
11	This field is reserved.						
Reserved	This bit must be written with a zero.						
10–9	Bus master 1 supervisor mode access control						
M1SM	· ·						
	See M3SM description						
8–6 M1UM	Bus master 1 user mode access control						
IVITOIVI	See M3UM description						
5	This field is reserved.						
Reserved	This bit must be written with a zero.						
4–3	Bus master 0 supervisor mode access control						
MOSM	See M3SM description						
2–0	Bus master 0 user mode access control						
MOUM	Dus master o aser mode access control						




#### wemory Map/Register Definition


## MPU\_RGDn\_WORD2 field descriptions (continued)

Field	Description
	See M3UM description

## 18.3.7 Region Descriptor n, Word 3 (MPU\_RGD\_WORD3)

The fourth word of the region descriptor contains the region descriptor's valid bit.






## MPU\_RGDn\_WORD3 field descriptions

Field	Description
31–1 Reserved	This read-only field is reserved and always has the value zero.
0 VLD	Valid Signals the region descriptor is valid. Any write to RGDn_WORD0–2 clears this bit.  Region descriptor is invalid Region descriptor is valid



# 18.3.8 Region Descriptor Alternate Access Control n (MPU\_RGDAACn)

Since software may adjust only the access controls within a region descriptor (RGDn\_WORD2) as different tasks execute, an alternate programming view of this 32-bit entity is available. Writing to this register does not affect the descriptor's valid bit.



## MPU\_RGDAACn field descriptions

Field	Description								
31 M7RE	Bus master 7 read enable.  0 Bus master 7 reads terminate with an access error and the read is not performed  1 Bus master 7 reads allowed								
30 M7WE	Bus master 7 write enable  Bus master 7 writes terminate with an access error and the write is not performed  Bus master 7 writes allowed								
29 M6RE	Bus master 6 read enable.  0 Bus master 6 reads terminate with an access error and the read is not performed  1 Bus master 6 reads allowed								
28 M6WE	Bus master 6 write enable  0 Bus master 6 writes terminate with an access error and the write is not performed  1 Bus master 6 writes allowed								
27 M5RE	Bus master 5 read enable.  0 Bus master 5 reads terminate with an access error and the read is not performed  1 Bus master 5 reads allowed								
26 M5WE	Bus master 5 write enable								



#### wemory Map/Register Definition

# MPU\_RGDAACn field descriptions (continued)

Field	Description							
	Bus master 5 writes terminate with an access error and the write is not performed							
	1 Bus master 5 writes allowed							
25 M4RE	Bus master 4 read enable.  O Bus master 4 reads terminate with an access error and the read is not performed							
	1 Bus master 4 reads allowed							
24 M4WE	Bus master 4 write enable  0 Bus master 4 writes terminate with an access error and the write is not performed							
	1 Bus master 4 writes allowed							
23 Reserved	This field is reserved. This bit must be written with a zero.							
22–21 M3SM	Bus master 3 supervisor mode access control							
IVISSIVI	Defines the access controls for bus master 3 in supervisor mode							
	00 r/w/x; read, write and execute allowed							
	01 r/x; read and execute allowed, but no write							
	10 r/w; read and write allowed, but no execute 11 Same as user mode defined in M3UM							
20–18	Bus master 3 user mode access control							
M3UM	Defines the access controls for bus master 3 in user mode. M3UM consists of three independent bits, enabling read (r), write (w), and execute (x) permissions.							
	<ul> <li>An attempted access of that mode may be terminated with an access error (if not allowed by another descriptor) and the access not performed.</li> <li>Allows the given access type to occur</li> </ul>							
17 Reserved	This field is reserved. This bit must be written with a zero.							
16–15 M2SM	Bus master 2 supervisor mode access control							
	See M3SM description.							
14–12 M2UM	Bus master 2 user mode access control							
	See M3UM description.							
11 Reserved	This field is reserved. This bit must be written with a zero.							
10-9 M1SM	Bus master 1 supervisor mode access control							
	See M3SM description.							
8–6 M1UM	Bus master 1 user mode access control							
	See M3UM description.							
5 Reserved	This field is reserved. This bit must be written with a zero.							



#### MPU\_RGDAACn field descriptions (continued)

Field	Description
4–3 M0SM	Bus master 0 supervisor mode access control
	See M3SM description.
2-0	Bus master 0 user mode access control
MOUM	See M3UM description.

# 18.4 Functional Description

In this section, the functional operation of the MPU is detailed, including the operation of the access evaluation macro and the handling of error-terminated bus cycles.

### 18.4.1 Access Evaluation Macro

The basic operation of the MPU is performed in the access evaluation macro, a hardware structure replicated in the two-dimensional connection matrix. As shown in the following figure, the access evaluation macro inputs the crossbar bus address phase signals and the contents of a region descriptor (RGDn) and performs two major functions: region hit determination and detection of an access protection violation. The following figure shows a functional block diagram.




Figure 18-80. MPU Access Evaluation Macro



**runctional Description** 

#### 18.4.1.1 Hit Determination

To determine if the current reference hits in the given region, two magnitude comparators are used with the region's start and end addresses. The boolean equation for this portion of the hit determination is:

```
region_hit = ((addr[31:5] >= RGDn_Word0[SRTADDR]) & (addr[31:5] <= RGDn_Word1[ENDADDR])) &
RGDn Word3[VLD]</pre>
```

where addr is the current reference address, RGD*n*\_Word0[SRTADDR] and RGD*n*\_Word1[ENDADDR] are the start and end addresses, and RGD*n*\_Word3[VLD] is the valid bit.

#### **NOTE**

The MPU does not verify that ENDADDR ≥ SRTADDR.

## 18.4.1.2 Privilege Violation Determination

While the access evaluation macro is determining region hit, the logic is also evaluating if the current access is allowed by the permissions defined in the region descriptor. Using the master and supervisor/user mode signals, a set of effective permissions is generated from the appropriate fields in the region descriptor. The protection violation logic then evaluates the access against the effective permissions using the specification shown below.

	MxUM			Protection	
Description	r	w	х	Violation?	
Instruction fetch read	_	_	0	Yes, no execute permission	
Instruction retorread	_	_	1	No, access is allowed	
Data read	0	_	_	Yes, no read permission	
Data Teau	1	_	_	No, access is allowed	
Data write	— — — — — —		_	Yes, no write permission	
Data Wille	_	1	_	No, access is allowed	

**Table 18-80. Protection Violation Definition** 

## 18.4.2 Putting It All Together and Error Terminations

For each slave port monitored, the MPU performs a reduction-AND of all the individual terms from each access evaluation macro. This expression then terminates the bus cycle with an error and reports a protection error for three conditions:



- 1. If the access does not hit in any region descriptor, a protection error is reported.
- 2. If the access hits in a single region descriptor and that region signals a protection violation, a protection error is reported.
- 3. If the access hits in multiple (overlapping) regions and all regions signal protection violations, a protection error is reported.

As shown in the third condition, granting permission is a higher priority than denying access for overlapping regions. This approach is more flexible to system software in region descriptor assignments. For an example of the use of overlapping region descriptors, see Application Information.

## 18.4.3 Power Management

Disabling the MPU by clearing CESR[VLD] minimizes power dissipation. To minimize the power dissipation of an enabled MPU, invalidate unused region descriptors by clearing the associated RGDn\_Word3[VLD] bits.

## 18.5 Initialization Information

At system startup, load the appropriate number of region descriptors, including setting RGD*n*\_Word3[VLD]. Setting CESR[VLD] enables the module.

If the system requires that all the loaded region descriptors be enabled simultaneously, first ensure that the entire MPU is disabled (CESR[VLD]=0).

#### **Note**

A region descriptor must be set to allow access to the MPU registers if further changes are needed.

## 18.6 Application Information

In an operational system, interfacing with the MPU is generally classified into the following activities:



#### **Application Information**

- Creating a new memory region—Load the appropriate region descriptor into an available RGDn, using four sequential 32-bit writes. The hardware assists in the maintenance of the valid bit, so if this approach is followed, there are no coherency issues with the multi-cycle descriptor writes. (Clearing RGDn\_Word3[VLD] deletes/removes an existing memory region.)
- Altering only access privileges—To not affect the valid bit, write to the alternate version of the access control word (RGDAACn), so there are no coherency issues involved with the update. When the write completes, the memory region's access rights switch instantaneously to the new value.
- Changing a region's start and end addresses—Write a minimum of three words to the region descriptor (RGDn\_Word{0,1,3}). Word 0 and 1 redefine the start and end addresses, respectively. Word 3 re-enables the region descriptor valid bit. In most situations, all four words of the region descriptor are rewritten.
- Accessing the MPU—Allocate a region descriptor to restrict MPU access to supervisor mode from a specific master.
- Detecting an access error—The current bus cycle is terminated with an error response and EARn and EDRn capture information on the faulting reference. The error-terminated bus cycle typically initiates an error response in the originating bus master. For example, a processor core may respond with a bus error exception, while a data movement bus master may respond with an error interrupt. The processor can retrieve the captured error address and detail information simply by reading E{A,D}Rn. CESR[SPERR] signals which error registers contain captured fault data.
- Overlapping region descriptors—Applying overlapping regions often reduces the number of descriptors required for a given set of access controls. In the overlapping memory space, the protection rights of the corresponding region descriptors are logically summed together (the boolean OR operator).

The following dual-core system example contains four bus masters: the two processors (CP0, CP1) and two DMA engines (DMA1, a traditional data movement engine transferring data between RAM and peripherals and DMA2, a second engine transferring data to/from the RAM only). Consider the following region descriptor assignments:

Table 18-81. Overlapping Region Descriptor Example

Region Description	RGDn	CP0	CP1	DMA1	DMA2	
CP0 code	0	rwx	r	_	_	Flash
CP1 code	1	r	rwx	_	_	i iasii



Table 18-81.	Overlapping Region Desc	criptor Example (continued)

Region Description		Dn	CP0	CP1	DMA1	DMA2	
CP0 data & stack	2	2	rw-	_	_	_	
CP0 → CP1 shared data	2	3	r	_			
CP1 → CP0 shared data	4			r	_	_	RAM
CP1 data & stack	4	4	_	rw-	_	_	
Shared DMA data	į	5	rw-	rw-	rw	rw	
MPU	6		rw-	rw-	_	_	Peripheral
Peripherals	7		rw-	rw-	rw	_	space

In this example, there are eight descriptors used to span nine regions in the three main spaces of the system memory map (flash, RAM, and peripheral space). Each region indicates the specific permissions for each of the four bus masters and this definition provides an appropriate set of shared, private and executable memory spaces.

Of particular interest are the two overlapping spaces: region descriptors 2 & 3 and 3 & 4.

The space defined by RGD2 with no overlap is a private data and stack area that provides read/write access to CP0 only. The overlapping space between RGD2 and RGD3 defines a shared data space for passing data from CP0 to CP1 and the access controls are defined by the logical OR of the two region descriptors. Thus, CP0 has (rw-|r--) = (rw-) permissions, while CP1 has (---|r--) = (r--) permission in this space. Both DMA engines are excluded from this shared processor data region. The overlapping spaces between RGD3 and RGD4 defines another shared data space, this one for passing data from CP1 to CP0. For this overlapping space, CP0 has (r--|---) = (r--) permission, while CP1 has (rw-|r--) = (rw-) permission. The non-overlapped space of RGD4 defines a private data and stack area for CP1 only.

The space defined by RGD5 is a shared data region, accessible by all four bus masters. Finally, the slave peripheral space mapped onto the IPS bus is partitioned into two regions: one containing the MPU's programming model accessible only to the two processor cores and the remaining peripheral region accessible to both processors and the traditional DMA1 master.

This simple example is intended to show one possible application of the capabilities of the MPU in a typical system.



Application Information



# **Chapter 19 Peripheral Bridge (AIPS-Lite)**

### 19.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The peripheral bridge (AIPS-Lite) converts the crossbar switch interface to an interface to access a majority of peripherals on the device.

The peripheral bridge supports up to 128 peripherals. The peripheral bridge occupies a 64 MB portion of the address space. The bridge includes separate clock enable inputs for each of the slots to accommodate slower peripherals.

## 19.1.1 Features

Key features of the peripheral bridge are:

- Supports up to 128 peripherals
- Supports 8-, 16-, and 32-bit width peripheral slots
- Each independently configurable peripheral includes a clock enable, which allows peripherals to operate at any speed less than the system clock rate.
- Programming model provides memory protection functionality

## 19.1.2 General operation

The peripherals connected to the peripheral bridge are modules that contain readable/ writable control and status registers. The system masters read and write these registers through the peripheral bridge. The peripheral bridge generates module enables, the



#### wemory map/register definition

module address, transfer attributes, byte enables, and write data as inputs to the peripherals. The peripheral bridge captures read data from the peripheral interface and drives it to the crossbar switch.

The register maps of the peripherals are located on 4 KB boundaries. Each peripheral is allocated one 4 KB block of the memory map.

The peripheral bridge (AIPS-Lite) memory map is illustrated as follows.

Addresses	Description
Base + 0x000_0000 - 0x000_0FFF	Module #0
Base + 0x000_1000 - 0x000_1FFF	Module #1
Base + 0x007_F000 - 0x007_FFFF	Module #127

# 19.2 Memory map/register definition

The peripheral bridge registers are 32-bit registers and can only be accessed in supervisor mode by trusted bus masters. Additionally, these registers must only be read from or written to by a 32-bit aligned access. The peripheral bridge registers are mapped into the PACR0 address space.

Two system clocks are required for read accesses, and three system clocks are required for write accesses to the peripheral bridge registers.

#### NOTE

The number of fields and registers available depends on the device-specific implementation of the peripheral bridge module. See the Chip Configuration chapter for more information.

#### **AIPS memory map**

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_0000	Master Privilege Register A (AIPS0_MPRA)	32	R/W	Undefined	19.2.1/389
4000_0020	Peripheral Access Control Register (AIPS0_PACRA)	32	R/W	4444_444h	19.2.2/393
4000_0024	Peripheral Access Control Register (AIPS0_PACRB)	32	R/W	4444_444h	19.2.2/393
4000_0028	Peripheral Access Control Register (AIPS0_PACRC)	32	R/W	4444_444h	19.2.2/393
4000_002C	Peripheral Access Control Register (AIPS0_PACRD)	32	R/W	4444_4444h	19.2.2/393



## **AIPS memory map (continued)**

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_0040	Peripheral Access Control Register (AIPS0_PACRE)	32	R/W	Undefined	19.2.3/398
4000_0044	Peripheral Access Control Register (AIPS0_PACRF)	32	R/W	Undefined	19.2.3/398
4000_0048	Peripheral Access Control Register (AIPS0_PACRG)	32	R/W	Undefined	19.2.3/398
4000_004C	Peripheral Access Control Register (AIPS0_PACRH)	32	R/W	Undefined	19.2.3/398
4000_0050	Peripheral Access Control Register (AIPS0_PACRI)	32	R/W	Undefined	19.2.3/398
4000_0054	Peripheral Access Control Register (AIPS0_PACRJ)	32	R/W	Undefined	19.2.3/398
4000_0058	Peripheral Access Control Register (AIPS0_PACRK)	32	R/W	Undefined	19.2.3/398
4000_005C	Peripheral Access Control Register (AIPS0_PACRL)	32	R/W	Undefined	19.2.3/398
4000_0060	Peripheral Access Control Register (AIPS0_PACRM)	32	R/W	Undefined	19.2.3/398
4000_0064	Peripheral Access Control Register (AIPS0_PACRN)	32	R/W	Undefined	19.2.3/398
4000_0068	Peripheral Access Control Register (AIPS0_PACRO)	32	R/W	Undefined	19.2.3/398
4000_006C	Peripheral Access Control Register (AIPS0_PACRP)	32	R/W	Undefined	19.2.3/398
4008_0000	Master Privilege Register A (AIPS1_MPRA)	32	R/W	Undefined	19.2.1/389
4008_0020	Peripheral Access Control Register (AIPS1_PACRA)	32	R/W	4444_444h	19.2.2/393
4008_0024	Peripheral Access Control Register (AIPS1_PACRB)	32	R/W	4444_444h	19.2.2/393
4008_0028	Peripheral Access Control Register (AIPS1_PACRC)	32	R/W	4444_444h	19.2.2/393
4008_002C	Peripheral Access Control Register (AIPS1_PACRD)	32	R/W	4444_444h	19.2.2/393
4008_0040	Peripheral Access Control Register (AIPS1_PACRE)	32	R/W	Undefined	19.2.3/398
4008_0044	Peripheral Access Control Register (AIPS1_PACRF)	32	R/W	Undefined	19.2.3/398
4008_0048	Peripheral Access Control Register (AIPS1_PACRG)	32	R/W	Undefined	19.2.3/398
4008_004C	Peripheral Access Control Register (AIPS1_PACRH)	32	R/W	Undefined	19.2.3/398
4008_0050	Peripheral Access Control Register (AIPS1_PACRI)	32	R/W	Undefined	19.2.3/398
4008_0054	Peripheral Access Control Register (AIPS1_PACRJ)	32	R/W	Undefined	19.2.3/398
4008_0058	Peripheral Access Control Register (AIPS1_PACRK)	32	R/W	Undefined	19.2.3/398
4008_005C	Peripheral Access Control Register (AIPS1_PACRL)	32	R/W	Undefined	19.2.3/398
4008_0060	Peripheral Access Control Register (AIPS1_PACRM)	32	R/W	Undefined	19.2.3/398
4008_0064	Peripheral Access Control Register (AIPS1_PACRN)	32	R/W	Undefined	19.2.3/398
4008_0068	Peripheral Access Control Register (AIPS1_PACRO)	32	R/W	Undefined	19.2.3/398
4008_006C	Peripheral Access Control Register (AIPS1_PACRP)	32	R/W	Undefined	19.2.3/398

# 19.2.1 Master Privilege Register A (AIPSx\_MPRA)

The MPRA register specifies identical 4-bit fields defining the access-privilege level associated with a bus master in the device to the various peripherals. The register provides one field per bus master.




#### NOTE

At reset, the default value loaded into the MPROT[7-0] fields is device-specific. See the Chip Configuration details for the value on your particular device.

Accesses to registers or register fields which correspond to master or peripheral locations which are not implemented return zeros on reads, and are ignored on writes.

Each master is assigned depending on its connection to the crossbar switch master ports. See your device-specific Chip Configuration details for information about the master assignments to these registers.

Addresses: AIPS0\_MPRA is 4000\_0000h base + 0h offset = 4000\_0000h AIPS1\_MPRA is 4008\_0000h base + 0h offset = 4008\_0000h



- \* Notes:
- x = Undefined at reset.

#### AIPSx\_MPRA field descriptions

Field	Description
31 Reserved	This read-only field is reserved and always has the value zero.
30 MTR0	Master trusted for read  Determines whether the master is trusted for read accesses.  0 This master is not trusted for read accesses.
	1 This master is trusted for read accesses.
29 MTW0	Master trusted for writes  Determines whether the master is trusted for write accesses.
	This master is not trusted for write accesses.  This master is trusted for write accesses.
28 MPL0	Master privilege level  Specifies how the privilege level of the master is determined.  O Accesses from this master are forced to user-mode.  1 Accesses from this master are not forced to user-mode.
27 Reserved	This read-only field is reserved and always has the value zero.



# AIPSx\_MPRA field descriptions (continued)

Field	Description
26	Master trusted for read
MTR1	Determines whether the master is trusted for read accesses.
	0 This master is not trusted for read accesses.
	1 This master is trusted for read accesses.
25 MTW1	Master trusted for writes
	Determines whether the master is trusted for write accesses.
	0 This master is not trusted for write accesses.
	1 This master is trusted for write accesses.
24 MPL1	Master privilege level
	Specifies how the privilege level of the master is determined.
	0 Accesses from this master are forced to user-mode.
	1 Accesses from this master are not forced to user-mode.
23 Reserved	This read-only field is reserved and always has the value zero.
22 MTP2	Master trusted for read
MTR2	Determines whether the master is trusted for read accesses.
	0 This master is not trusted for read accesses.
	1 This master is trusted for read accesses.
21 MTW2	Master trusted for writes
	Determines whether the master is trusted for write accesses.
	0 This master is not trusted for write accesses.
	1 This master is trusted for write accesses.
20 MPL2	Master privilege level
IVII LE	Specifies how the privilege level of the master is determined.
	0 Accesses from this master are forced to user-mode.
	1 Accesses from this master are not forced to user-mode.
19 Reserved	This read-only field is reserved and always has the value zero.
18 MTD2	Master trusted for read
MTR3	Determines whether the master is trusted for read accesses.
	0 This master is not trusted for read accesses.
	1 This master is trusted for read accesses.
17 MTW3	Master trusted for writes
1011 003	Determines whether the master is trusted for write accesses.



#### wemory map/register definition

# AIPSx\_MPRA field descriptions (continued)

Field	Description
	This master is not trusted for write accesses.
	1 This master is trusted for write accesses.
16	Master privilege level
MPL3	Specifies how the privilege level of the master is determined.
	0 Accesses from this master are forced to user-mode.
	1 Accesses from this master are not forced to user-mode.
15 Reserved	This read-only field is reserved and always has the value zero.
14 MTR4	Master trusted for read
	Determines whether the master is trusted for read accesses.
	0 This master is not trusted for read accesses.
	1 This master is trusted for read accesses.
13 MTW4	Master trusted for writes
	Determines whether the master is trusted for write accesses.
	O This master is not trusted for write accesses.
	1 This master is trusted for write accesses.
12 MPL4	Master privilege level
IVII L4	Specifies how the privilege level of the master is determined.
	0 Accesses from this master are forced to user-mode.
	1 Accesses from this master are not forced to user-mode.
11 Reserved	This read-only field is reserved and always has the value zero.
10 MTR5	Master trusted for read
	Determines whether the master is trusted for read accesses.
	0 This master is not trusted for read accesses.
	1 This master is trusted for read accesses.
9 MTW5	Master trusted for writes
	Determines whether the master is trusted for write accesses.
	0 This master is not trusted for write accesses.
	1 This master is trusted for write accesses.
8 MDI 5	Master privilege level
MPL5	Specifies how the privilege level of the master is determined.
	0 Accesses from this master are forced to user-mode.
	1 Accesses from this master are not forced to user-mode.
7–4 Reserved	This read-only field is reserved and always has the value zero.



#### AIPSx\_MPRA field descriptions (continued)

Field	Description
3–0 Reserved	This read-only field is reserved and always has the value zero.

## 19.2.2 Peripheral Access Control Register (AIPSx\_PACRn)

Each of the peripherals has a four-bit PACR[0:127] field which defines the access levels supported by the given module. Eight PACR fields are grouped together to form a 32-bit PACR[A:P] register:

• PACRA-P define the access levels for the 128 peripherals

The peripheral assignments to each PACR register is defined by the memory map slot that the peripherals are assigned. See the device's Memory Map details for the assignments for your particular device.

#### NOTE

The reset value of the PACRA-D registers is 0x4444\_4444.

The following table shows the top-level structure of the PACR registers.

Offset	Register	[31:28]	[27:24]	[23:20]	[19:16]	[15:12]	[11:8]	[7:4]	[3:0]
0x20	PACRA	PACR0	PACR1	PACR2	PACR3	PACR4	PACR5	PACR6	PACR7
0x24	PACRB	PACR8	PACR9	PACR10	PACR11	PACR12	PACR13	PACR14	PACR15
0x28	PACRC	PACR16	PACR17	PACR18	PACR19	PACR20	PACR21	PACR22	PACR23
0x2C	PACRD	PACR24	PACR25	PACR26	PACR27	PACR28	PACR29	PACR30	PACR31
0x30	Reserved								
0x34	Reserved								
0x38	Reserved								
0x3C	Reserved								
0x40	PACRE	PACR32	PACR33	PACR34	PACR35	PACR36	PACR37	PACR38	PACR39
0x44	PACRF	PACR40	PACR41	PACR42	PACR43	PACR44	PACR45	PACR46	PACR47
0x48	PACRG	PACR48	PACR49	PACR50	PACR51	PACR52	PACR53	PACR54	PACR55
0x4C	PACRH	PACR56	PACR57	PACR58	PACR59	PACR60	PACR61	PACR62	PACR63
0x50	PACRI	PACR64	PACR65	PACR66	PACR67	PACR68	PACR69	PACR70	PACR71
0x54	PACRJ	PACR72	PACR73	PACR74	PACR75	PACR76	PACR77	PACR78	PACR79
0x58	PACRK	PACR80	PACR81	PACR82	PACR83	PACR84	PACR85	PACR86	PACR87
0x5C	PACRL	PACR88	PACR89	PACR90	PACR91	PACR92	PACR93	PACR94	PACR95



#### wemory map/register definition

Offset	Register	[31:28]	[27:24]	[23:20]	[19:16]	[15:12]	[11:8]	[7:4]	[3:0]
0x60	PACRM	PACR96	PACR97	PACR98	PACR99	PACR100	PACR101	PACR102	PACR103
0x64	PACRN	PACR104	PACR105	PACR106	PACR107	PACR108	PACR109	PACR110	PACR111
0x68	PACRO	PACR112	PACR113	PACR114	PACR115	PACR116	PACR117	PACR118	PACR119
0x6C	PACRP	PACR120	PACR121	PACR122	PACR123	PACR124	PACR125	PACR126	PACR127

Addresses: AIPS0\_PACRA is 4000\_0000h base + 20h offset = 4000\_0020h

AIPS0\_PACRB is 4000\_0000h base + 24h offset = 4000\_0024h

AIPS0\_PACRC is 4000\_0000h base + 28h offset = 4000\_0028h


AIPS0\_PACRD is 4000\_0000h base + 2Ch offset = 4000\_002Ch

AIPS1\_PACRA is 4008\_0000h base + 20h offset = 4008\_0020h

AIPS1\_PACRB is 4008\_0000h base + 24h offset = 4008\_0024h

AIPS1\_PACRC is 4008\_0000h base + 28h offset = 4008\_0028h

AIPS1\_PACRD is 4008\_0000h base + 2Ch offset = 4008\_002Ch



## AIPSx\_PACRn field descriptions

Field	Description
31 Reserved	This read-only field is reserved and always has the value zero.
30 SP0	Supervisor protect  Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.  O This peripheral does not require supervisor privilege level for accesses.  This peripheral requires supervisor privilege level for accesses.
29 WP0	Write protect  Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.  O This peripheral allows write accesses.  This peripheral is write protected.
28 TP0	Trusted protect  Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.  O Accesses from an untrusted master are allowed.  1 Accesses from an untrusted master are not allowed.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# AIPSx\_PACRn field descriptions (continued)

Field	Description
27 Reserved	This read-only field is reserved and always has the value zero.
26 SP1	Supervisor protect
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
25 WP1	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
24 TP1	Trusted protect
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	<ul> <li>Accesses from an untrusted master are allowed.</li> <li>Accesses from an untrusted master are not allowed.</li> </ul>
23 Reserved	This read-only field is reserved and always has the value zero.
22 SP2	Supervisor protect
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
21 WP2	Write protect
2	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	<ul><li>This peripheral allows write accesses.</li><li>This peripheral is write protected.</li></ul>
20	Trusted protect
TP2	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.



#### wemory map/register definition

# AIPSx\_PACRn field descriptions (continued)

Field	Description
	Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.
19 Reserved	This read-only field is reserved and always has the value zero.
18 SP3	Supervisor protect
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	0 This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
47	
17 WP3	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
16 TP3	Trusted protect
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.
15	
15 Reserved	This read-only field is reserved and always has the value zero.
14 SP4	Supervisor protect
354	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	0 This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
13 WP4	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
10	
12 TP4	Trusted protect



# AIPSx\_PACRn field descriptions (continued)

Field	Description
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	<ul> <li>O Accesses from an untrusted master are allowed.</li> <li>1 Accesses from an untrusted master are not allowed.</li> </ul>
11 Reserved	This read-only field is reserved and always has the value zero.
10 SP5	Supervisor protect
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	0 This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
9 WP5	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	<ul><li>This peripheral allows write accesses.</li><li>This peripheral is write protected.</li></ul>
8	Trusted protect
TP5	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.
7 Reserved	This read-only field is reserved and always has the value zero.
6	Supervisor protect
SP6	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	<ul> <li>This peripheral does not require supervisor privilege level for accesses.</li> <li>This peripheral requires supervisor privilege level for accesses.</li> </ul>
5 WP6	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	<ul><li>This peripheral allows write accesses.</li><li>This peripheral is write protected.</li></ul>



#### wemory map/register definition

## AIPSx\_PACRn field descriptions (continued)

Field	Description
4 TP6	Trusted protect
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates .
	Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.
3 Reserved	This read-only field is reserved and always has the value zero.
2	Supervisor protect
SP7	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	0 This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
1	Write protect
WP7	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
0 TP7	Trusted protect
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.

## 19.2.3 Peripheral Access Control Register (AIPSx\_PACRn)

Each of the peripherals has a four-bit PACR[0:127] field which defines the access levels supported by the given module. Eight PACR fields are grouped together to form a 32-bit PACR[A:P] register:

• PACRA-P define the access levels for the 128 peripherals


The peripheral assignments to each PACR register is defined by the memory map slot that the peripherals are assigned. See the device's Memory Map details for the assignments for your particular device.



## **NOTE**

The reset value of the PACRE-P depends on your device's configuration.

Addresses:  $4000\_0000h$  base + 40h offset +  $(4d \times n)$ , where n = 0d to 11d



<sup>\*</sup> Notes:

## AIPSx\_PACRn field descriptions

Field	Description
31 Reserved	This read-only field is reserved and always has the value zero.
30 SP0	Supervisor protect  Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the
	master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	0 This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
29 WP0	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
28 TP0	Trusted protect
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	0 Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.
27 Reserved	This read-only field is reserved and always has the value zero.
26 SP1	Supervisor protect
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.

<sup>•</sup> x = Undefined at reset.



## wemory map/register definition

# AIPSx\_PACRn field descriptions (continued)

Field	Description		
	This peripheral does not require supervisor privilege level for accesses.		
	1 This peripheral requires supervisor privilege level for accesses.		
25 WP1	Write protect		
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.		
	<ul><li>This peripheral allows write accesses.</li><li>This peripheral is write protected.</li></ul>		
24 TP1	Trusted protect		
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.		
	0 Accesses from an untrusted master are allowed.		
	1 Accesses from an untrusted master are not allowed.		
23 Reserved	This read-only field is reserved and always has the value zero.		
22 SP2	Supervisor protect  Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.		
	<ul> <li>This peripheral does not require supervisor privilege level for accesses.</li> <li>This peripheral requires supervisor privilege level for accesses.</li> </ul>		
21 WP2	Write protect		
*****	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.		
	0 This peripheral allows write accesses.		
	1 This peripheral is write protected.		
20 TP2	Trusted protect		
112	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.		
	O Accesses from an untrusted master are allowed.		
	Accesses from an untrusted master are not allowed.		
19 Reserved	This read-only field is reserved and always has the value zero.		
18	Supervisor protect		
SP3	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for		



# AIPSx\_PACRn field descriptions (continued)

Field	Description	
	the master must be set. If not, access terminates with an error response and no peripheral access initiates.	
	O This peripheral does not require supervisor privilege level for accesses.	
	1 This peripheral requires supervisor privilege level for accesses.	
17 WP3	Write protect	
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.	
	0 This peripheral allows write accesses.	
	1 This peripheral is write protected.	
16 TP3	Trusted protect	
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.	
	0 Accesses from an untrusted master are allowed.	
	1 Accesses from an untrusted master are not allowed.	
15 Reserved	This read-only field is reserved and always has the value zero.	
14 SP4	Supervisor protect  Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.	
	0 This peripheral does not require supervisor privilege level for accesses.	
	1 This peripheral requires supervisor privilege level for accesses.	
13 WP4	Write protect	
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.	
	0 This peripheral allows write accesses.	
	1 This peripheral is write protected.	
12 TP4	Trusted protect	
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.	
	Accesses from an untrusted master are allowed.	
	1 Accesses from an untrusted master are not allowed.	
11 Reserved	This read-only field is reserved and always has the value zero.	
10	Supervisor protect	
SP5		



## wemory map/register definition

# AIPSx\_PACRn field descriptions (continued)

Field	Description
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	O This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
9 WP5	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
8 TP5	Trusted protect
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	0 Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.
7	This read-only field is reserved and always has the value zero.
Reserved	
6 SP6	Supervisor protect
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
5	Write protect
WP6	
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
4 TP6	Trusted protect
-	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	0 Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.
3 Reserved	This read-only field is reserved and always has the value zero.



## AIPSx\_PACRn field descriptions (continued)

Field	Description
2 SP7	Supervisor protect
	Determines whether the peripheral requires supervisor privilege level for access. When this bit is set, the master privilege level must indicate the supervisor access attribute, and the MPROTn[MPL] control bit for the master must be set. If not, access terminates with an error response and no peripheral access initiates.
	0 This peripheral does not require supervisor privilege level for accesses.
	1 This peripheral requires supervisor privilege level for accesses.
1 WP7	Write protect
	Determines whether the peripheral allows write accesss. When this bit is set and a write access is attempted, access terminates with an error response and no peripheral access initiates.
	0 This peripheral allows write accesses.
	1 This peripheral is write protected.
0 TP7	Trusted protect
	Determines whether the peripheral allows accesses from an untrusted master. When this bit is set and an access is attempted by an untrusted master, the access terminates with an error response and no peripheral access initiates.
	Accesses from an untrusted master are allowed.
	1 Accesses from an untrusted master are not allowed.

# 19.3 Functional Description

The peripheral bridge serves as an interface between the crossbar switch and the slave peripheral bus. It functions as a protocol translator.

Accesses which fall within the address space of the peripheral bridge are decoded to provide individual module selects for peripheral devices on the slave bus interface.

## 19.3.1 Access support

Aligned and misaligned 32-bit and 16-bit accesses, as well as byte accesses are supported for 32-bit peripherals. Misaligned accesses are supported to allow memory to be placed on the slave peripheral bus. Peripheral registers must not be misaligned, although no explicit checking is performed by the peripheral bridge. All accesses are performed with a single transfer.

All accesses to the peripheral slots must be sized less than or equal to the designated peripheral slot size. If an access is attempted which is larger (in size) than the targeted port, an error response is generated.



**runctional Description** 



# **Chapter 20 Direct memory access multiplexer (DMAMUX)**

## 20.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

## 20.1.1 Overview

The DMA Mux routes up to 63 DMA sources (called slots) to be mapped to any of the 16 DMA channels. This is illustrated in the following figure.



#### muroduction




Figure 20-1. DMA MUX block diagram

## 20.1.2 Features

The DMA channel MUX provides these features:

- 52 peripheral slots + 10 always-on slots can be routed to 16 channels.
- 16 independently selectable DMA channel routers.
  - The first 4 channels additionally provide a trigger functionality.
- Each channel router can be assigned to one of the 52 possible peripheral DMA slots or to one of the 10 always-on slots.

# 20.1.3 Modes of operation

The following operating modes are available:

Disabled mode



In this mode, the DMA channel is disabled. Since disabling and enabling of DMA channels is done primarily via the DMA configuration registers, this mode is used mainly as the reset state for a DMA channel in the DMA channel MUX. It may also be used to temporarily suspend a DMA channel while reconfiguration of the system takes place (e.g. changing the period of a DMA trigger).

#### Normal mode

In this mode, a DMA source (such as DSPI transmit or DSPI receive) is routed directly to the specified DMA channel. The operation of the DMA MUX in this mode is completely transparent to the system.

Periodic trigger mode

In this mode, a DMA source may only request a DMA transfer (such as when a transmit buffer becomes empty or a receive buffer becomes full) periodically. Configuration of the period is done in the registers of the periodic interrupt timer (PIT). This mode is only available for channels 0-3.

# 20.2 External signal description

The DMA MUX has no external pins.

# 20.3 Memory map/register definition

This section provides a detailed description of all memory-mapped registers in the DMA MUX.

The following table shows the memory map for the DMA MUX.

All registers are accessible via 8-bit, 16-bit or 32-bit accesses. However, 16-bit accesses must be aligned to 16-bit boundaries, and 32-bit accesses must be aligned to 32-bit boundaries. As an example, CHCFG0 through CHCFG3 are accessible by a 32-bit read/write to address 'base + 0x00', but performing a 32-bit access to address 'base + 0x01' is illegal.



## **DMAMUX** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4002_1000	Channel Configuration Register (DMAMUX_CHCFG0)	8	R/W	00h	20.3.1/408
4002_1001	Channel Configuration Register (DMAMUX_CHCFG1)	8	R/W	00h	20.3.1/408
4002_1002	Channel Configuration Register (DMAMUX_CHCFG2)	8	R/W	00h	20.3.1/408
4002_1003	Channel Configuration Register (DMAMUX_CHCFG3)	8	R/W	00h	20.3.1/408
4002_1004	Channel Configuration Register (DMAMUX_CHCFG4)	8	R/W	00h	20.3.1/408
4002_1005	Channel Configuration Register (DMAMUX_CHCFG5)	8	R/W	00h	20.3.1/408
4002_1006	Channel Configuration Register (DMAMUX_CHCFG6)	8	R/W	00h	20.3.1/408
4002_1007	Channel Configuration Register (DMAMUX_CHCFG7)	8	R/W	00h	20.3.1/408
4002_1008	Channel Configuration Register (DMAMUX_CHCFG8)	8	R/W	00h	20.3.1/408
4002_1009	Channel Configuration Register (DMAMUX_CHCFG9)	8	R/W	00h	20.3.1/408
4002_100A	Channel Configuration Register (DMAMUX_CHCFG10)	8	R/W	00h	20.3.1/408
4002_100B	Channel Configuration Register (DMAMUX_CHCFG11)	8	R/W	00h	20.3.1/408
4002_100C	Channel Configuration Register (DMAMUX_CHCFG12)	8	R/W	00h	20.3.1/408
4002_100D	Channel Configuration Register (DMAMUX_CHCFG13)	8	R/W	00h	20.3.1/408
4002_100E	Channel Configuration Register (DMAMUX_CHCFG14)	8	R/W	00h	20.3.1/408
4002_100F	Channel Configuration Register (DMAMUX_CHCFG15)	8	R/W	00h	20.3.1/408

# 20.3.1 Channel Configuration Register (DMAMUX\_CHCFGn)


Each of the DMA channels can be independently enabled/disabled and associated with one of the DMA slots (peripheral slots or always-on slots) in the system.

#### NOTE

Setting multiple CHCFG registers with the same Source value will result in unpredictable behavior.

#### **NOTE**

Before changing the trigger or source settings a DMA channel must be disabled via the CHCFGn[ENBL] bit.





## DMAMUX\_CHCFGn field descriptions

Field	Description
7 ENBL	DMA Channel Enable
2.452	Enables the DMA channel
	0 DMA channel is disabled. This mode is primarily used during configuration of the DMA Mux. The DMA has separate channel enables/disables, which should be used to disable or re-configure a DMA channel.
	1 DMA channel is enabled
6 TRIG	DMA Channel Trigger Enable
Truo	Enables the periodic trigger capability for the triggered DMA channel
	O Triggering is disabled. If triggering is disabled, and the ENBL bit is set, the DMA Channel will simply route the specified source to the DMA channel. (normal mode)
	1 Triggering is enabled. If triggering is enabled, and the ENBL bit is set, the DMAMUX is in periodic trigger mode.
5–0 SOURCE	DMA Channel Source (slot)
	Specifies which DMA source, if any, is routed to a particular DMA channel. Please check your device's Chip Configuration details for further details about the peripherals and their slot numbers.

# 20.4 Functional description

This section provides the functional description of the DMA MUX.

The primary purpose of the DMA MUX is to provide flexibility in the system's use of the available DMA channels. As such, configuration of the DMA MUX is intended to be a static procedure done during execution of the system boot code. However, if the procedure outlined in Enabling and configuring sources is followed, the configuration of the DMA MUX may be changed during the normal operation of the system.

Functionally, the DMA MUX channels may be divided into two classes: Channels, which implement the normal routing functionality plus periodic triggering capability, and channels, which implement only the normal routing functionality.

# 20.4.1 DMA channels with periodic triggering capability

Besides the normal routing functionality, the first four channels of the DMA MUX provide a special periodic triggering capability that can be used to provide an automatic mechanism to transmit bytes, frames or packets at fixed intervals without the need for processor intervention. The trigger is generated by the periodic interrupt timer (PIT); as



#### runctional description

such, the configuration of the periodic triggering interval is done via configuration registers in the PIT. Please refer to Periodic Interrupt Timer chapter for more information on this topic.

#### **Note**

Because of the dynamic nature of the system (i.e. DMA channel priorities, bus arbitration, interrupt service routine lengths, etc.), the number of clock cycles between a trigger and the actual DMA transfer cannot be guaranteed.




Figure 20-19. DMA MUX triggered channels

The DMA channel triggering capability allows the system to "schedule" regular DMA transfers, usually on the transmit side of certain peripherals, without the intervention of the processor. This trigger works by gating the request from the peripheral to the DMA until a trigger event has been seen. This is illustrated in the following figure.






Figure 20-20. DMA MUX channel triggering: normal operation

Once the DMA request has been serviced, the peripheral will negate its request, effectively resetting the gating mechanism until the peripheral re-asserts its request AND the next trigger event is seen. This means that if a trigger is seen, but the peripheral is not requesting a transfer, that triggered will be ignored. This situation is illustrated in the following figure.




Figure 20-21. DMA MUX channel triggering: ignored trigger

This triggering capability may be used with any peripheral that supports DMA transfers, and is most useful for two types of situations:

- Periodically polling external devices on a particular bus. As an example, the transmit side of an SPI is assigned to a DMA channel with a trigger, as described above. Once setup, the SPI will request DMA transfers (presumably from memory) as long as its transmit buffer is empty. By using a trigger on this channel, the SPI transfers can be automatically performed every 5µs (as an example). On the receive side of the SPI, the SPI and DMA can be configured to transfer receive data into memory, effectively implementing a method to periodically read data from external devices and transfer the results into memory without processor intervention.
- Using the GPIO ports to drive or sample waveforms. By configuring the DMA to transfer data to one or more GPIO ports, it is possible to create complex waveforms using tabular data stored in on-chip memory. Conversely, using the DMA to periodically transfer data from one or more GPIO ports, it is possible to sample complex waveforms and store the results in tabular form in on-chip memory.

A more detailed description of the capability of each trigger (which includes resolution, range of values, etc.) may be found in the Periodic Interrupt Timer chapter.



## 20.4.2 DMA channels with no triggering capability

The other channels of the DMA MUX provide the normal routing functionality as described in Modes of operation.

## 20.4.3 "Always enabled" DMA sources

In addition to the peripherals that can be used as DMA sources, there are 10 additional DMA sources that are "always enabled". Unlike the peripheral DMA sources, where the peripheral controls the flow of data during DMA transfers, the "always enabled" sources provide no such "throttling" of the data transfers. These sources are most useful in the following cases:

- Doing DMA transfers to/from GPIO—Moving data from/to one or more GPIO pins, either un-throttled (that is as fast as possible), or periodically (using the DMA triggering capability).
- Doing DMA transfers from memory to memory—Moving data from memory to memory, typically as fast as possible, sometimes with software activation.
- Doing DMA transfers from memory to the external bus (or vice-versa)—Similar to memory to memory transfers, this is typically done as quickly as possible.
- Any DMA transfer that requires software activation—Any DMA transfer that should be explicitly started by software.

In cases where software should initiate the start of a DMA transfer, an "always enabled" DMA source can be used to provide maximum flexibility. When activating a DMA channel via software, subsequent executions of the minor loop require a new "start" event be sent. This can either be a new software activation, or a transfer request from the DMA channel MUX. The options for doing this are:

• Transfer all data in a single minor loop. By configuring the DMA to transfer all of the data in a single minor loop (that is major loop counter = 1), no re-activation of the channel is necessary. The disadvantage to this option is the reduced granularity in determining the load that the DMA transfer will incur on the system. For this option, the DMA channel should be disabled in the DMA channel MUX.



- Use explicit software re-activation. In this option, the DMA is configured to transfer the data using both minor and major loops, but the processor is required to re-activate the channel (by writing to the DMA registers) *after every minor loop*. For this option, the DMA channel should be disabled in the DMA channel MUX.
- Use a "always enabled" DMA source. In this option, the DMA is configured to transfer the data using both minor and major loops, and the DMA channel MUX does the channel re-activation. For this option, the DMA channel should be enabled and pointing to an "always enabled" source. Note that the re-activation of the channel can be continuous (DMA triggering is disabled) or can use the DMA triggering capability. In this manner, it is possible to execute periodic transfers of packets of data from one source to another, without processor intervention.

# 20.5 Initialization/application information

This section provides instructions for initializing the DMA channel MUX.

## 20.5.1 Reset

The reset state of each individual bit is shown in Memory map/register definition. In summary, after reset, all channels are disabled and must be explicitly enabled before use.

## 20.5.2 Enabling and configuring sources

Enabling a source with periodic triggering

- 1. Determine with which DMA channel the source will be associated. Note that only the first 4 DMA channels have periodic triggering capability
- 2. Clear the CHCFG[ENBL] and CHCFG[TRIG] bits of the DMA channel
- 3. Ensure that the DMA channel is properly configured in the DMA. The DMA channel may be enabled at this point
- 4. Configure the corresponding timer
- 5. Select the source to be routed to the DMA channel. Write to the corresponding CHCFG register, ensuring that the CHCFG[ENBL] and CHCFG[TRIG] bits are set

Configure source #5 transmit for use with DMA channel 2, with periodic triggering capability

- 1. Write 0x00 to CHCFG2 (base address + 0x02)
- 2. Configure channel 2 in the DMA, including enabling the channel



#### unualization/application information

- 3. Configure a timer for the desired trigger interval
- 4. Write 0xC5 to CHCFG2 (base address + 0x02)

The following code example illustrates steps #1 and #4 above:

```
In File registers.h:
#define DMAMUX BASE ADDR
                               0xFC084000/* Example only ! */
/* Following example assumes char is 8-bits */
volatile unsigned char *CHCONFIG0 = (volatile unsigned char *)
                                                                   (DMAMUX_BASE_ADDR+0x0000);
volatile unsigned char *CHCONFIG1 = (volatile unsigned char *)
                                                                    (DMAMUX BASE ADDR+0x0001);
volatile unsigned char *CHCONFIG2 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x0002);
volatile unsigned char *CHCONFIG3 = (volatile unsigned char *) (DMAMUX BASE ADDR+0x0003);
volatile unsigned char *CHCONFIG4 = (volatile unsigned char *) (DMAMUX BASE ADDR+0x0004);
volatile unsigned char *CHCONFIG5 = (volatile unsigned char *) (DMAMUX BASE ADDR+0x0005);
volatile unsigned char *CHCONFIG6 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x0006);
volatile unsigned char *CHCONFIG7 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x0007); volatile unsigned char *CHCONFIG8 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x0008);
volatile unsigned char *CHCONFIG9 = (volatile unsigned char *) (DMAMUX BASE ADDR+0x0009);
volatile unsigned char *CHCONFIG10= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000A);
volatile unsigned char *CHCONFIG11= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000B);
volatile unsigned char *CHCONFIG12= (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000C);
                                                                   (DMAMUX_BASE_ADDR+0x000D);
volatile unsigned char *CHCONFIG13= (volatile unsigned char *)
volatile unsigned char *CHCONFIG14= (volatile unsigned char *)
                                                                   (DMAMUX BASE ADDR+0x000E);
volatile unsigned char *CHCONFIG15= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000F);
In File main.c:
#include "registers.h"
*CHCONFIG2 = 0x00;
*CHCONFIG2 = 0xC5;
```

Enabling a source without periodic triggering

- 1. Determine with which DMA channel the source will be associated. Note that only the first 4 DMA channels have periodic triggering capability
- 2. Clear the CHCFG[ENBL] and CHCFG[TRIG] bits of the DMA channel
- 3. Ensure that the DMA channel is properly configured in the DMA. The DMA channel may be enabled at this point
- 4. Select the source to be routed to the DMA channel. Write to the corresponding CHCFG register, ensuring that the CHCFG[ENBL] is set while the CHCFG[TRIG] bit is cleared

Configure source #5 Transmit for use with DMA channel 2, with no periodic triggering capability.

- 1. Write 0x00 to CHCFG2 (base address + 0x02)
- 2. Configure channel 2 in the DMA, including enabling the channel
- 3. Write 0x85 to CHCFG2 (base address + 0x02)

The following code example illustrates steps #1 and #3 above:



```
volatile unsigned char *CHCONFIG3 = (volatile unsigned char *)
                                                               (DMAMUX BASE ADDR+0x0003);
volatile unsigned char *CHCONFIG4 = (volatile unsigned char *)
                                                                (DMAMUX BASE ADDR+0x0004);
volatile unsigned char *CHCONFIG5 = (volatile unsigned char *)
                                                                (DMAMUX BASE ADDR+0x0005);
volatile unsigned char *CHCONFIG6 = (volatile unsigned char *) (DMAMUX BASE ADDR+0x0006);
volatile unsigned char *CHCONFIG7 = (volatile unsigned char *) (DMAMUX BASE ADDR+0x0007);
volatile unsigned char *CHCONFIG8 = (volatile unsigned char *) (DMAMUX BASE ADDR+0x0008);
volatile unsigned char *CHCONFIG9 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x0009);
volatile unsigned char *CHCONFIG10= (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000A);
volatile unsigned char *CHCONFIG11= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000B);
volatile unsigned char *CHCONFIG12= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000C);
volatile unsigned char *CHCONFIG13= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000D);
volatile unsigned char *CHCONFIG14= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000E);
volatile unsigned char *CHCONFIG15= (volatile unsigned char *) (DMAMUX BASE ADDR+0x000F);
In File main.c:
#include "registers.h"
*CHCONFIG2 = 0x00;
*CHCONFIG2 = 0x85;
```

## Disabling a source

A particular DMA source may be disabled by not writing the corresponding source value into any of the CHCFG registers. Additionally, some module specific configuration may be necessary. Please refer to the appropriate section for more details.

Switching the source of a DMA channel

- 1. Disable the DMA channel in the DMA and re-configure the channel for the new source
- 2. Clear the CHCFG[ENBL] and CHCFG[TRIG] bits of the DMA channel
- 3. Select the source to be routed to the DMA channel. Write to the corresponding CHCFG register, ensuring that the CHCFG[ENBL] and CHCFG[TRIG] bits are set

Switch DMA channel 8 from source #5 transmit to source #7 transmit

- 1. In the DMA configuration registers, disable DMA channel 8 and re-configure it to handle the transfers to peripheral slot 7. This example assumes channel 8 doesn't have triggering capability
- 2. Write 0x00 to CHCFG8 (base address + 0x08)
- 3. Write 0x87 to CHCFG8 (base address + 0x08). (In this example, setting the CHCFG[TRIG] bit would have no effect, due to the assumption that channels 8 does not support the periodic triggering functionality).

The following code example illustrates steps #2 and #3 above:



#### unualization/application information

```
volatile unsigned char *CHCONFIG8 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x0008);
volatile unsigned char *CHCONFIG9 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x0009);
volatile unsigned char *CHCONFIG10 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000A);
volatile unsigned char *CHCONFIG11 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000B);
volatile unsigned char *CHCONFIG12 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000C);
volatile unsigned char *CHCONFIG13 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000D);
volatile unsigned char *CHCONFIG14 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000E);
volatile unsigned char *CHCONFIG15 = (volatile unsigned char *) (DMAMUX_BASE_ADDR+0x000E);
The file main.c:
#include "registers.h"
:
    *CHCONFIG8 = 0x00;
*CHCONFIG8 = 0x87;
```



# **Chapter 21 Direct Memory Access Controller (eDMA)**

## 21.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The enhanced direct memory access (eDMA) controller is a second-generation module capable of performing complex data transfers with minimal intervention from a host processor. The hardware microarchitecture includes:

- A DMA engine that performs:
  - Source- and destination-address calculations
  - Data-movement operations
- Local memory containing transfer control descriptors for each of the 16 channels

## 21.1.1 Block diagram

This diagram illustrates the eDMA module.



#### muroduction




Figure 21-1. eDMA block diagram

# 21.1.2 Block parts

The eDMA module is partitioned into two major modules: the eDMA engine and the transfer-control descriptor local memory.

The eDMA engine is further partitioned into four submodules:



## Table 21-1. eDMA engine submodules

Submodule	Function
Address path	This block implements registered versions of two channel transfer control descriptors, channel x and channel y, and manages all master bus-address calculations. All the channels provide the same functionality. This structure allows data transfers associated with one channel to be preempted after the completion of a read/write sequence if a higher priority channel activation is asserted while the first channel is active. After a channel is activated, it runs until the minor loop is completed, unless preempted by a higher priority channel. This provides a mechanism (enabled by DCHPRIn[ECP]) where a large data move operation can be preempted to minimize the time another channel is blocked from execution.
	When any channel is selected to execute, the contents of its TCD are read from local memory and loaded into the address path channel x registers for a normal start and into channel y registers for a preemption start. After the minor loop completes execution, the address path hardware writes the new values for the TCDn_{SADDR, DADDR, CITER} back to local memory. If the major iteration count is exhausted, additional processing is performed, including the final address pointer updates, reloading the TCDn_CITER field, and a possible fetch of the next TCDn from memory as part of a scatter/gather operation.
Data path	This block implements the bus master read/write datapath. It includes 16 bytes of register storage and the necessary multiplex logic to support any required data alignment. The internal read data bus is the primary input, and the internal write data bus is the primary output.
	The address and data path modules directly support the 2-stage pipelined internal bus. The address path module represents the 1st stage of the bus pipeline (address phase), while the data path module implements the 2nd stage of the pipeline (data phase).
Program model/channel arbitration	This block implements the first section of the eDMA programming model as well as the channel arbitration logic. The programming model registers are connected to the internal peripheral bus. The eDMA peripheral request inputs and interrupt request outputs are also connected to this block (via control logic).
Control	This block provides all the control functions for the eDMA engine. For data transfers where the source and destination sizes are equal, the eDMA engine performs a series of source read/destination write operations until the number of bytes specified in the minor loop byte count has moved. For descriptors where the sizes are not equal, multiple accesses of the smaller size data are required for each reference of the larger size. As an example, if the source size references 16-bit data and the destination is 32-bit data, two reads are performed, then one 32-bit write.

The transfer-control descriptor local memory is further partitioned into:



#### muroduction

#### Table 21-2. Transfer control descriptor memory

Submodule	Description
Memory controller	This logic implements the required dual-ported controller, managing accesses from the eDMA engine as well as references from the internal peripheral bus. As noted earlier, in the event of simultaneous accesses, the eDMA engine is given priority and the peripheral transaction is stalled.
Memory array	TCD storage is implemented using a single-port, synchronous RAM array.

## 21.1.3 Features

The eDMA is a highly-programmable data-transfer engine optimized to minimize the required intervention from the host processor. It is intended for use in applications where the data size to be transferred is statically known and not defined within the data packet itself. The eDMA module features:

- All data movement via dual-address transfers: read from source, write to destination
  - Programmable source and destination addresses and transfer size
  - Support for enhanced addressing modes
- 16-channel implementation that performs complex data transfers with minimal intervention from a host processor
  - Internal data buffer, used as temporary storage to support 16-byte burst transfers
  - Connections to the crossbar switch for bus mastering the data movement
- Transfer control descriptor (TCD) organized to support two-deep, nested transfer operations
  - 32-byte TCD stored in local memory for each channel
  - An inner data transfer loop defined by a minor byte transfer count
  - An outer data transfer loop defined by a major iteration count
- Channel activation via one of three methods:
  - Explicit software initiation
  - Initiation via a channel-to-channel linking mechanism for continuous transfers
  - Peripheral-paced hardware requests, one per channel
- Fixed-priority and round-robin channel arbitration



- Channel completion reported via optional interrupt requests
  - One interrupt per channel, optionally asserted at completion of major iteration count
  - Optional error terminations per channel and logically summed together to form one error interrupt to the interrupt controller
- Optional support for scatter/gather DMA processing
- Support for complex data structures
- Support to cancel transfers via software

In the discussion of this module, *n* is used to reference the channel number.

# 21.2 Modes of operation

The eDMA operates in the following modes:

Table 21-3. Modes of operation

	i
Mode	Description
Normal	In Normal mode, the eDMA transfers data between a source and a destination. The source and destination can be a memory block or an I/O block capable of operation with the eDMA.
	A service request initiates a transfer of a specific number of bytes (NBYTES) as specified in the transfer control descriptor (TCD). The minor loop is the sequence of read-write operations that transfers these NBYTES per service request. Each service request executes one iteration of the major loop, which transfers NBYTES of data.
Debug	DMA operation is configurable in Debug mode via the control register:
	<ul> <li>If CR[EDBG] is cleared, the DMA continues to operate.</li> <li>If CR[EDBG] is set, the eDMA stops transferring data.</li> <li>If Debug mode is entered while a channel is active, the eDMA continues operation until the channel retires.</li> </ul>
Wait	Before entering Wait mode, the DMA attempts to complete its current transfer. After the transfer completes, the device enters Wait mode.

## 21.3 Memory map/register definition

The eDMA's programming model is partitioned into two regions:

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory map/register definition

- The first region defines a number of registers providing control functions
- The second region corresponds to the local transfer control descriptor memory

Each channel requires a 32-byte transfer control descriptor for defining the desired data movement operation. The channel descriptors are stored in the local memory in sequential order: channel 0, channel 1,... channel 15. Each TCDn definition is presented as 11 registers of 16 or 32 bits.

Reading reserved bits in a register returns the value of zero. Writes to reserved bits in a register are ignored. Reading or writing a reserved memory location generates a bus error.

## **DMA** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_8000	Control Register (DMA_CR)	32	R/W	0000_0000h	21.3.1/436
4000_8004	Error Status Register (DMA_ES)	32	R	0000_0000h	21.3.2/438
4000_800C	Enable Request Register (DMA_ERQ)	32	R/W	0000_0000h	21.3.3/440
4000_8014	Enable Error Interrupt Register (DMA_EEI)	32	R/W	0000_0000h	21.3.4/442
4000_8018	Clear Enable Error Interrupt Register (DMA_CEEI)	8	W (always reads zero)	00h	21.3.5/444
4000_8019	Set Enable Error Interrupt Register (DMA_SEEI)	8	W (always reads zero)	00h	21.3.6/445
4000_801A	Clear Enable Request Register (DMA_CERQ)	8	W (always reads zero)	00h	21.3.7/446
4000_801B	Set Enable Request Register (DMA_SERQ)	8	W (always reads zero)	00h	21.3.8/447
4000_801C	Clear DONE Status Bit Register (DMA_CDNE)	8	W (always reads zero)	00h	21.3.9/448
4000_801D	Set START Bit Register (DMA_SSRT)	8	W (always reads zero)	00h	21.3.10/ 449



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_801E	Clear Error Register (DMA_CERR)	8	W (always reads zero)	00h	21.3.11/ 450
4000_801F	Clear Interrupt Request Register (DMA_CINT)	8	W (always reads zero)	00h	21.3.12/ 451
4000_8024	Interrupt Request Register (DMA_INT)	32	R/W	0000_0000h	21.3.13/ 451
4000_802C	Error Register (DMA_ERR)	32	R/W	0000_0000h	21.3.14/ 454
4000_8034	Hardware Request Status Register (DMA_HRS)	32	R/W	0000_0000h	21.3.15/ 456
4000_8100	Channel n Priority Register (DMA_DCHPRI3)	8	R/W	Undefined	21.3.16/ 458
4000_8101	Channel n Priority Register (DMA_DCHPRI2)	8	R/W	Undefined	21.3.16/ 458
4000_8102	Channel n Priority Register (DMA_DCHPRI1)	8	R/W	Undefined	21.3.16/ 458
4000_8103	Channel n Priority Register (DMA_DCHPRI0)	8	R/W	Undefined	21.3.16/ 458
4000_8104	Channel n Priority Register (DMA_DCHPRI7)	8	R/W	Undefined	21.3.16/ 458
4000_8105	Channel n Priority Register (DMA_DCHPRI6)	8	R/W	Undefined	21.3.16/ 458
4000_8106	Channel n Priority Register (DMA_DCHPRI5)	8	R/W	Undefined	21.3.16/ 458
4000_8107	Channel n Priority Register (DMA_DCHPRI4)	8	R/W	Undefined	21.3.16/ 458
4000_8108	Channel n Priority Register (DMA_DCHPRI11)	8	R/W	Undefined	21.3.16/ 458
4000_8109	Channel n Priority Register (DMA_DCHPRI10)	8	R/W	Undefined	21.3.16/ 458
4000_810A	Channel n Priority Register (DMA_DCHPRI9)	8	R/W	Undefined	21.3.16/ 458
4000_810B	Channel n Priority Register (DMA_DCHPRI8)	8	R/W	Undefined	21.3.16/ 458
4000_810C	Channel n Priority Register (DMA_DCHPRI15)	8	R/W	Undefined	21.3.16/ 458
4000_810D	Channel n Priority Register (DMA_DCHPRI14)	8	R/W	Undefined	21.3.16/ 458



## wemory map/register definition

# **DMA** memory map (continued)

Absolute					
address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_810E	Channel n Priority Register (DMA_DCHPRI13)	8	R/W	Undefined	21.3.16/ 458
4000_810F	Channel n Priority Register (DMA_DCHPRI12)	8	R/W	Undefined	21.3.16/ 458
4000_9000	TCD Source Address (DMA_TCD0_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9004	TCD Signed Source Address Offset (DMA_TCD0_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9006	TCD Transfer Attributes (DMA_TCD0_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9008	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD0_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9008	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD0_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9008	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD0_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_900C	TCD Last Source Address Adjustment (DMA_TCD0_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9010	TCD Destination Address (DMA_TCD0_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9014	TCD Signed Destination Address Offset (DMA_TCD0_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9016	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD0_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9016	DMA_TCD0_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9018	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD0_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_901C	TCD Control and Status (DMA_TCD0_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_901E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD0_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_901E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD0_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9020	TCD Source Address (DMA_TCD1_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9024	TCD Signed Source Address Offset (DMA_TCD1_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9026	TCD Transfer Attributes (DMA_TCD1_ATTR)	16	R/W	Undefined	21.3.19/ 460
	•				



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_9028	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD1_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9028	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD1_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9028	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD1_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_902C	TCD Last Source Address Adjustment (DMA_TCD1_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9030	TCD Destination Address (DMA_TCD1_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9034	TCD Signed Destination Address Offset (DMA_TCD1_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9036	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD1_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9036	DMA_TCD1_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9038	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD1_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_903C	TCD Control and Status (DMA_TCD1_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_903E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD1_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_903E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD1_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9040	TCD Source Address (DMA_TCD2_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9044	TCD Signed Source Address Offset (DMA_TCD2_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9046	TCD Transfer Attributes (DMA_TCD2_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9048	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD2_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9048	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD2_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9048	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD2_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_904C	TCD Last Source Address Adjustment (DMA_TCD2_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9050	TCD Destination Address (DMA_TCD2_DADDR)	32	R/W	Undefined	21.3.24/ 464



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_9054	TCD Signed Destination Address Offset (DMA_TCD2_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9056	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD2_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9056	DMA_TCD2_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9058	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD2_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_905C	TCD Control and Status (DMA_TCD2_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_905E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD2_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_905E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD2_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9060	TCD Source Address (DMA_TCD3_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9064	TCD Signed Source Address Offset (DMA_TCD3_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9066	TCD Transfer Attributes (DMA_TCD3_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9068	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD3_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9068	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD3_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9068	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD3_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_906C	TCD Last Source Address Adjustment (DMA_TCD3_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9070	TCD Destination Address (DMA_TCD3_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9074	TCD Signed Destination Address Offset (DMA_TCD3_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9076	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD3_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9076	DMA_TCD3_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9078	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD3_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_907C	TCD Control and Status (DMA_TCD3_CSR)	16	R/W	Undefined	21.3.29/ 468



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_907E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD3_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_907E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD3_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9080	TCD Source Address (DMA_TCD4_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9084	TCD Signed Source Address Offset (DMA_TCD4_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9086	TCD Transfer Attributes (DMA_TCD4_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9088	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD4_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9088	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD4_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9088	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD4_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_908C	TCD Last Source Address Adjustment (DMA_TCD4_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9090	TCD Destination Address (DMA_TCD4_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9094	TCD Signed Destination Address Offset (DMA_TCD4_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9096	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD4_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9096	DMA_TCD4_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9098	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD4_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_909C	TCD Control and Status (DMA_TCD4_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_909E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD4_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_909E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD4_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_90A0	TCD Source Address (DMA_TCD5_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_90A4	TCD Signed Source Address Offset (DMA_TCD5_SOFF)	16	R/W	Undefined	21.3.18/ 460



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_90A6	TCD Transfer Attributes (DMA_TCD5_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_90A8	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD5_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_90A8	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD5_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_90A8	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD5_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_90AC	TCD Last Source Address Adjustment (DMA_TCD5_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_90B0	TCD Destination Address (DMA_TCD5_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_90B4	TCD Signed Destination Address Offset (DMA_TCD5_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_90B6	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD5_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_90B6	DMA_TCD5_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_90B8	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD5_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_90BC	TCD Control and Status (DMA_TCD5_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_90BE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD5_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_90BE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD5_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_90C0	TCD Source Address (DMA_TCD6_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_90C4	TCD Signed Source Address Offset (DMA_TCD6_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_90C6	TCD Transfer Attributes (DMA_TCD6_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_90C8	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD6_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_90C8	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD6_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_90C8	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD6_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_90CC	TCD Last Source Address Adjustment (DMA_TCD6_SLAST)	32	R/W	Undefined	21.3.23/ 464



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_90D0	TCD Destination Address (DMA_TCD6_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_90D4	TCD Signed Destination Address Offset (DMA_TCD6_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_90D6	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD6_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_90D6	DMA_TCD6_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_90D8	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD6_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_90DC	TCD Control and Status (DMA_TCD6_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_90DE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD6_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_90DE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD6_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_90E0	TCD Source Address (DMA_TCD7_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_90E4	TCD Signed Source Address Offset (DMA_TCD7_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_90E6	TCD Transfer Attributes (DMA_TCD7_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_90E8	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD7_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_90E8	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD7_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_90E8	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD7_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_90EC	TCD Last Source Address Adjustment (DMA_TCD7_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_90F0	TCD Destination Address (DMA_TCD7_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_90F4	TCD Signed Destination Address Offset (DMA_TCD7_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_90F6	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD7_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_90F6	DMA_TCD7_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_90F8	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD7_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_90FC	TCD Control and Status (DMA_TCD7_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_90FE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD7_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_90FE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD7_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9100	TCD Source Address (DMA_TCD8_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9104	TCD Signed Source Address Offset (DMA_TCD8_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9106	TCD Transfer Attributes (DMA_TCD8_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9108	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD8_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9108	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD8_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9108	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD8_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_910C	TCD Last Source Address Adjustment (DMA_TCD8_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9110	TCD Destination Address (DMA_TCD8_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9114	TCD Signed Destination Address Offset (DMA_TCD8_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9116	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD8_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9116	DMA_TCD8_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9118	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD8_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_911C	TCD Control and Status (DMA_TCD8_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_911E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD8_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_911E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD8_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9120	TCD Source Address (DMA_TCD9_SADDR)	32	R/W	Undefined	21.3.17/ 459



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_9124	TCD Signed Source Address Offset (DMA_TCD9_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9126	TCD Transfer Attributes (DMA_TCD9_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9128	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD9_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9128	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD9_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9128	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD9_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_912C	TCD Last Source Address Adjustment (DMA_TCD9_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9130	TCD Destination Address (DMA_TCD9_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9134	TCD Signed Destination Address Offset (DMA_TCD9_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9136	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD9_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9136	DMA_TCD9_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9138	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD9_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_913C	TCD Control and Status (DMA_TCD9_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_913E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD9_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_913E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD9_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9140	TCD Source Address (DMA_TCD10_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9144	TCD Signed Source Address Offset (DMA_TCD10_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9146	TCD Transfer Attributes (DMA_TCD10_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9148	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD10_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9148	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD10_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9148	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD10_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463



## wemory map/register definition

# **DMA** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_914C	TCD Last Source Address Adjustment (DMA_TCD10_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9150	TCD Destination Address (DMA_TCD10_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9154	TCD Signed Destination Address Offset (DMA_TCD10_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9156	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD10_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9156	DMA_TCD10_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9158	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD10_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_915C	TCD Control and Status (DMA_TCD10_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_915E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD10_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_915E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD10_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9160	TCD Source Address (DMA_TCD11_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9164	TCD Signed Source Address Offset (DMA_TCD11_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9166	TCD Transfer Attributes (DMA_TCD11_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9168	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD11_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9168	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD11_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9168	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD11_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_916C	TCD Last Source Address Adjustment (DMA_TCD11_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9170	TCD Destination Address (DMA_TCD11_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9174	TCD Signed Destination Address Offset (DMA_TCD11_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9176	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD11_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9176	DMA_TCD11_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_9178	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD11_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_917C	TCD Control and Status (DMA_TCD11_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_917E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD11_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_917E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD11_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_9180	TCD Source Address (DMA_TCD12_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_9184	TCD Signed Source Address Offset (DMA_TCD12_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_9186	TCD Transfer Attributes (DMA_TCD12_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_9188	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD12_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_9188	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD12_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_9188	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD12_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_918C	TCD Last Source Address Adjustment (DMA_TCD12_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_9190	TCD Destination Address (DMA_TCD12_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_9194	TCD Signed Destination Address Offset (DMA_TCD12_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_9196	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD12_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_9196	DMA_TCD12_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_9198	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD12_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_919C	TCD Control and Status (DMA_TCD12_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_919E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD12_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_919E	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD12_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_91A0	TCD Source Address (DMA_TCD13_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_91A4	TCD Signed Source Address Offset (DMA_TCD13_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_91A6	TCD Transfer Attributes (DMA_TCD13_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_91A8	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD13_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_91A8	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD13_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_91A8	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD13_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_91AC	TCD Last Source Address Adjustment (DMA_TCD13_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_91B0	TCD Destination Address (DMA_TCD13_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_91B4	TCD Signed Destination Address Offset (DMA_TCD13_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_91B6	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD13_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_91B6	DMA_TCD13_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_91B8	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD13_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_91BC	TCD Control and Status (DMA_TCD13_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_91BE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD13_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_91BE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD13_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_91C0	TCD Source Address (DMA_TCD14_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_91C4	TCD Signed Source Address Offset (DMA_TCD14_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_91C6	TCD Transfer Attributes (DMA_TCD14_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_91C8	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD14_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_91C8	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD14_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_91C8	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD14_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_91CC	TCD Last Source Address Adjustment (DMA_TCD14_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_91D0	TCD Destination Address (DMA_TCD14_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_91D4	TCD Signed Destination Address Offset (DMA_TCD14_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_91D6	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD14_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465
4000_91D6	DMA_TCD14_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_91D8	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD14_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_91DC	TCD Control and Status (DMA_TCD14_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_91DE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD14_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_91DE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD14_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471
4000_91E0	TCD Source Address (DMA_TCD15_SADDR)	32	R/W	Undefined	21.3.17/ 459
4000_91E4	TCD Signed Source Address Offset (DMA_TCD15_SOFF)	16	R/W	Undefined	21.3.18/ 460
4000_91E6	TCD Transfer Attributes (DMA_TCD15_ATTR)	16	R/W	Undefined	21.3.19/ 460
4000_91E8	TCD Minor Byte Count (Minor Loop Disabled) (DMA_TCD15_NBYTES_MLNO)	32	R/W	Undefined	21.3.20/ 461
4000_91E8	TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA_TCD15_NBYTES_MLOFFNO)	32	R/W	Undefined	21.3.21/ 462
4000_91E8	TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA_TCD15_NBYTES_MLOFFYES)	32	R/W	Undefined	21.3.22/ 463
4000_91EC	TCD Last Source Address Adjustment (DMA_TCD15_SLAST)	32	R/W	Undefined	21.3.23/ 464
4000_91F0	TCD Destination Address (DMA_TCD15_DADDR)	32	R/W	Undefined	21.3.24/ 464
4000_91F4	TCD Signed Destination Address Offset (DMA_TCD15_DOFF)	16	R/W	Undefined	21.3.25/ 465
4000_91F6	TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD15_CITER_ELINKYES)	16	R/W	Undefined	21.3.26/ 465



Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_91F6	DMA_TCD15_CITER_ELINKNO	16	R/W	Undefined	21.3.27/ 466
4000_91F8	TCD Last Destination Address Adjustment/Scatter Gather Address (DMA_TCD15_DLASTSGA)	32	R/W	Undefined	21.3.28/ 467
4000_91FC	TCD Control and Status (DMA_TCD15_CSR)	16	R/W	Undefined	21.3.29/ 468
4000_91FE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA_TCD15_BITER_ELINKYES)	16	R/W	Undefined	21.3.30/ 470
4000_91FE	TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA_TCD15_BITER_ELINKNO)	16	R/W	Undefined	21.3.31/ 471

# 21.3.1 Control Register (DMA\_CR)

The CR defines the basic operating configuration of the DMA.

Arbitration can be configured to use either a fixed-priority or a round-robin scheme. For fixed-priority arbitration, the highest priority channel requesting service is selected to execute. The channel priority registers assign the priorities; see the DCHPRIn registers. For round-robin arbitration, the channel priorities are ignored and channels are cycled through without regard to priority.

## **NOTE**

For proper operation, writes to the CR register must be performed only when the DMA channels are inactive; that is, when TCDn\_CSR[ACTIVE] bits are cleared.

Address: DMA\_CR is 4000\_8000h base + 0h offset = 4000\_8000h



## **DMA\_CR** field descriptions

Field	Description
31–18 Reserved	This read-only field is reserved and always has the value zero.
17 CX	Cancel Transfer



# **DMA\_CR** field descriptions (continued)

Field	Description
	<ul> <li>Normal operation</li> <li>Cancel the remaining data transfer. Stop the executing channel and force the minor loop to finish. The cancel takes effect after the last write of the current read/write sequence. The CX bit clears itself after</li> </ul>
	the cancel has been honored. This cancel retires the channel normally as if the minor loop was completed.
16 ECX	Error Cancel Transfer  0 Normal operation
	Cancel the remaining data transfer in the same fashion as the CX bit. Stop the executing channel and force the minor loop to finish. The cancel takes effect after the last write of the current read/write sequence. The ECX bit clears itself after the cancel is honored. In addition to cancelling the transfer, ECX treats the cancel as an error condition, thus updating the ES register and generating an optional error interrupt.
15–8 Reserved	This read-only field is reserved and always has the value zero.
7 EMLM	Enable Minor Loop Mapping
	0 Disabled. TCDn.word2 is defined as a 32-bit NBYTES field.
	1 Enabled. TCDn.word2 is redefined to include individual enable fields, an offset field, and the NBYTES field. The individual enable fields allow the minor loop offset to be applied to the source address, the destination address, or both. The NBYTES field is reduced when either offset is enabled.
6 CLM	Continuous Link Mode
	A minor loop channel link made to itself goes through channel arbitration before being activated again.
	1 A minor loop channel link made to itself does not go through channel arbitration before being activated again. Upon minor loop completion, the channel activates again if that channel has a minor loop channel link enabled and the link channel is itself. This effectively applies the minor loop offsets and restarts the next minor loop.
5 HALT	Halt DMA Operations
	<ul> <li>Normal operation</li> <li>Stall the start of any new channels. Executing channels are allowed to complete. Channel execution</li> </ul>
4	resumes when this bit is cleared.  Halt On Error
HOE	
	<ul> <li>Normal operation</li> <li>Any error causes the HALT bit to set. Subsequently, all service requests are ignored until the HALT bit is cleared.</li> </ul>
3 Reserved	This read-only field is reserved and always has the value zero.
2 ERCA	Enable Round Robin Channel Arbitration
	0 Fixed priority arbitration is used for channel selection.
	1 Round robin arbitration is used for channel selection.
1 EDBG	Enable Debug

## **DMA\_CR** field descriptions (continued)

Field	Description
	0 When in debug mode, the DMA continues to operate.
	1 When in debug mode, the DMA stalls the start of a new channel. Executing channels are allowed to complete. Channel execution resumes when the system exits debug mode or the EDBG bit is cleared.
0 Reserved	This read-only field is reserved and always has the value zero.


# 21.3.2 Error Status Register (DMA\_ES)

The ES provides information concerning the last recorded channel error. Channel errors can be caused by:

- A configuration error, that is:
  - An illegal setting in the transfer-control descriptor, or
  - An illegal priority register setting in fixed-arbitration
- An error termination to a bus master read or write cycle

See the Error Reporting and Handling section for more details.

Address: DMA\_ES is 4000\_8000h base + 4h offset = 4000\_8004h



# **DMA\_ES field descriptions**

Field	Description
31 VLD	Logical OR of all ERR status bits  0 No ERR bits are set
	1 At least one ERR bit is set indicating a valid error exists that has not been cleared
30–17 Reserved	This read-only field is reserved and always has the value zero.
16 ECX	Transfer Cancelled  O No cancelled transfers  The last recorded entry was a cancelled transfer by the error cancel transfer input



# DMA\_ES field descriptions (continued)

Field	Description
15 Reserved	This read-only field is reserved and always has the value zero.
14 CPE	Channel Priority Error  O No channel priority error  The last recorded error was a configuration error in the channel priorities. Channel priorities are not unique.
13–12 Reserved	This read-only field is reserved and always has the value zero.
11–8 ERRCHN	Error Channel Number or Cancelled Channel Number  The channel number of the last recorded error (excluding CPE errors) or last recorded error cancelled transfer.
7 SAE	Source Address Error  0 No source address configuration error.  1 The last recorded error was a configuration error detected in the TCDn_SADDR field. TCDn_SADDR is inconsistent with TCDn_ATTR[SSIZE].
6 SOE	Source Offset Error  O No source offset configuration error  The last recorded error was a configuration error detected in the TCDn_SOFF field. TCDn_SOFF is inconsistent with TCDn_ATTR[SSIZE].
5 DAE	<ul> <li>Destination Address Error</li> <li>No destination address configuration error</li> <li>The last recorded error was a configuration error detected in the TCDn_DADDR field. TCDn_DADDR is inconsistent with TCDn_ATTR[DSIZE].</li> </ul>
4 DOE	Destination Offset Error  0 No destination offset configuration error  1 The last recorded error was a configuration error detected in the TCDn_DOFF field. TCDn_DOFF is inconsistent with TCDn_ATTR[DSIZE].
3 NCE	NBYTES/CITER Configuration Error  No NBYTES/CITER configuration error  The last recorded error was a configuration error detected in the TCDn_NBYTES or TCDn_CITER fields.  TCDn_NBYTES is not a multiple of TCDn_ATTR[SSIZE] and TCDn_ATTR[DSIZE], or TCDn_CITER[CITER] is equal to zero, or TCDn_CITER[ELINK] is not equal to TCDn_BITER[ELINK]
2 SGE	Scatter/Gather Configuration Error  No scatter/gather configuration error  The last recorded error was a configuration error detected in the TCDn_DLASTSGA field. This field is checked at the beginning of a scatter/gather operation after major loop completion if TCDn_CSR[ESG] is enabled. TCDn_DLASTSGA is not on a 32 byte boundary.

## DMA\_ES field descriptions (continued)

Field	Description
1 SBE	Source Bus Error  O No source bus error  The last recorded error was a bus error on a source read
0 DBE	Destination Bus Error  O No destination bus error  The last recorded error was a bus error on a destination write

# 21.3.3 Enable Request Register (DMA\_ERQ)

The ERQ register provides a bit map for the 16 implemented channels to enable the request signal for each channel. The state of any given channel enable is directly affected by writes to this register; it is also affected by writes to the SERQ and CERQ. The {S,C}ERQ registers are provided so the request enable for a single channel can easily be modified without needing to perform a read-modify-write sequence to the ERQ.

DMA request input signals and this enable request flag must be asserted before a channel's hardware service request is accepted. The state of the DMA enable request flag does not affect a channel service request made explicitly through software or a linked channel request.

Address: DMA\_ERQ is 4000\_8000h base + Ch offset = 4000\_800Ch



#### DMA\_ERQ field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15 ERQ15	Enable DMA Request 15  O The DMA request signal for the corresponding channel is disabled  The DMA request signal for the corresponding channel is enabled
14 ERQ14	Enable DMA Request 14  0 The DMA request signal for the corresponding channel is disabled  1 The DMA request signal for the corresponding channel is enabled



# **DMA\_ERQ** field descriptions (continued)

Field	Description
13	Enable DMA Request 13
ERQ13	
	The DMA request signal for the corresponding channel is disabled     The DMA request signal for the corresponding channel is enabled
12	Enable DMA Request 12
ERQ12	
	O The DMA request signal for the corresponding channel is disabled
	1 The DMA request signal for the corresponding channel is enabled
11 ERQ11	Enable DMA Request 11
	0 The DMA request signal for the corresponding channel is disabled
	1 The DMA request signal for the corresponding channel is enabled
10	Enable DMA Request 10
ERQ10	The DMA request signal for the corresponding channel is disabled
	1 The DMA request signal for the corresponding channel is enabled
9	Enable DMA Request 9
ERQ9	The DMA request signal for the corresponding channel is disabled
	The DMA request signal for the corresponding channel is enabled
8	Enable DMA Request 8
ERQ8	
	<ul> <li>The DMA request signal for the corresponding channel is disabled</li> <li>The DMA request signal for the corresponding channel is enabled</li> </ul>
7	Enable DMA Request 7
ERQ7	
	The DMA request signal for the corresponding channel is disabled  The DMA request signal for the corresponding channel is enabled.
	1 The DMA request signal for the corresponding channel is enabled
6 ERQ6	Enable DMA Request 6
	0 The DMA request signal for the corresponding channel is disabled
	1 The DMA request signal for the corresponding channel is enabled
5	Enable DMA Request 5
ERQ5	0 The DMA request signal for the corresponding channel is disabled
	1 The DMA request signal for the corresponding channel is enabled
4	Enable DMA Request 4
ERQ4	The DMA request signal for the corresponding channel is disabled
	The DMA request signal for the corresponding channel is enabled
3	Enable DMA Request 3
ERQ3	
	<ul> <li>The DMA request signal for the corresponding channel is disabled</li> <li>The DMA request signal for the corresponding channel is enabled</li> </ul>
2	Enable DMA Request 2
ERQ2	Enable Divire Hoquest 2

## DMA\_ERQ field descriptions (continued)


Field	Description	
	The DMA request signal for the corresponding channel is disabled	
	1 The DMA request signal for the corresponding channel is enabled	
1	Enable DMA Request 1	
ERQ1	O The DMA year, act simple for the convergence dings about a dischlad	
	The DMA request signal for the corresponding channel is disabled	
	1 The DMA request signal for the corresponding channel is enabled	
0	Enable DMA Request 0	
ERQ0		
	0 The DMA request signal for the corresponding channel is disabled	
	The DMA request signal for the corresponding channel is enabled	

# 21.3.4 Enable Error Interrupt Register (DMA\_EEI)

The EEI register provides a bit map for the 16 channels to enable the error interrupt signal for each channel. The state of any given channel's error interrupt enable is directly affected by writes to this register; it is also affected by writes to the SEEI and CEEI. The {S,C}EEI are provided so the error interrupt enable for a single channel can easily be modified without the need to perform a read-modify-write sequence to the EEI register.

The DMA error indicator and the error interrupt enable flag must be asserted before an error interrupt request for a given channel is asserted to the interrupt controller.

Address: DMA\_EEI is 4000\_8000h base + 14h offset = 4000\_8014h



## **DMA\_EEI** field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15 EEI15	Enable Error Interrupt 15  0 The error signal for corresponding channel does not generate an error interrupt 1 The assertion of the error signal for corresponding channel generates an error interrupt request
14 EEI14	Enable Error Interrupt 14  0 The error signal for corresponding channel does not generate an error interrupt  1 The assertion of the error signal for corresponding channel generates an error interrupt request



# **DMA\_EEI** field descriptions (continued)

Field	Description
13	Enable Error Interrupt 13
EEI13	The error signal for corresponding channel does not generate an error interrupt
	The assertion of the error signal for corresponding channel generates an error interrupt request
12	Enable Error Interrupt 12
EEI12	
	<ul> <li>The error signal for corresponding channel does not generate an error interrupt</li> <li>The assertion of the error signal for corresponding channel generates an error interrupt request</li> </ul>
11	Enable Error Interrupt 11
EEI11	
	<ul> <li>The error signal for corresponding channel does not generate an error interrupt</li> <li>The assertion of the error signal for corresponding channel generates an error interrupt request</li> </ul>
10	
10 EEI10	Enable Error Interrupt 10
	O The error signal for corresponding channel does not generate an error interrupt
	The assertion of the error signal for corresponding channel generates an error interrupt request
9 EEI9	Enable Error Interrupt 9
LEIS	0 The error signal for corresponding channel does not generate an error interrupt
	The assertion of the error signal for corresponding channel generates an error interrupt request
8	Enable Error Interrupt 8
EEI8	The error signal for corresponding channel does not generate an error interrupt
	1 The assertion of the error signal for corresponding channel generates an error interrupt request
7	Enable Error Interrupt 7
EEI7	The error signal for corresponding channel does not generate an error interrupt
	1 The assertion of the error signal for corresponding channel generates an error interrupt request
6	Enable Error Interrupt 6
EEI6	The error signal for corresponding channel does not generate an error interrupt
	The assertion of the error signal for corresponding channel generates an error interrupt request
5	Enable Error Interrupt 5
EEI5	
	<ul> <li>The error signal for corresponding channel does not generate an error interrupt</li> <li>The assertion of the error signal for corresponding channel generates an error interrupt request</li> </ul>
4	Enable Error Interrupt 4
EEI4	
	<ul> <li>The error signal for corresponding channel does not generate an error interrupt</li> <li>The assertion of the error signal for corresponding channel generates an error interrupt request</li> </ul>
3	
EEI3	Enable Error Interrupt 3
	O The error signal for corresponding channel does not generate an error interrupt
	The assertion of the error signal for corresponding channel generates an error interrupt request
2 EEI2	Enable Error Interrupt 2




## **DMA\_EEI** field descriptions (continued)

Field	Description
	The error signal for corresponding channel does not generate an error interrupt
	1 The assertion of the error signal for corresponding channel generates an error interrupt request
1 EEI1	Enable Error Interrupt 1
	0 The error signal for corresponding channel does not generate an error interrupt
	1 The assertion of the error signal for corresponding channel generates an error interrupt request
0	Enable Error Interrupt 0
EEI0	
	The error signal for corresponding channel does not generate an error interrupt
	1 The assertion of the error signal for corresponding channel generates an error interrupt request

# 21.3.5 Clear Enable Error Interrupt Register (DMA\_CEEI)

The CEEI provides a simple memory-mapped mechanism to clear a given bit in the EEI to disable the error interrupt for a given channel. The data value on a register write causes the corresponding bit in the EEI to be cleared. Setting the CAEE bit provides a global clear function, forcing the EEI contents to be cleared, disabling all DMA request inputs. If the NOP bit is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.

Address: DMA\_CEEI is 4000\_8000h base + 18h offset = 4000\_8018h



## **DMA\_CEEI** field descriptions


Field	Description
7 NOP	<ul> <li>Normal operation</li> <li>No operation, ignore the other bits in this register</li> </ul>
6 CAEE	Clear All Enable Error Interrupts  O Clear only the EEI bit specified in the CEEI field  1 Clear all bits in EEI
5–4 Reserved	This field is reserved.
3–0 CEEI	Clear Enable Error Interrupt Clears the corresponding bit in EEI



# 21.3.6 Set Enable Error Interrupt Register (DMA\_SEEI)

The SEEI provides a simple memory-mapped mechanism to set a given bit in the EEI to enable the error interrupt for a given channel. The data value on a register write causes the corresponding bit in the EEI to be set. Setting the SAEE bit provides a global set function, forcing the entire EEI contents to be set. If the NOP bit is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.

Address: DMA\_SEEI is 4000\_8000h base + 19h offset = 4000\_8019h



## **DMA\_SEEI** field descriptions


Field	Description
7 NOP	<ul> <li>Normal operation</li> <li>No operation, ignore the other bits in this register</li> </ul>
6 SAEE	Sets All Enable Error Interrupts  O Set only the EEI bit specified in the SEEI field.  1 Sets all bits in EEI
5–4 Reserved	This field is reserved.
3–0 SEEI	Set Enable Error Interrupt Sets the corresponding bit in EEI



# 21.3.7 Clear Enable Request Register (DMA\_CERQ)

The CERQ provides a simple memory-mapped mechanism to clear a given bit in the ERQ to disable the DMA request for a given channel. The data value on a register write causes the corresponding bit in the ERQ to be cleared. Setting the CAER bit provides a global clear function, forcing the entire contents of the ERQ to be cleared, disabling all DMA request inputs. If NOP is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.

Address: DMA\_CERQ is 4000\_8000h base + 1Ah offset = 4000\_801Ah



## DMA\_CERQ field descriptions


Field	Description
7 NOP	<ul> <li>Normal operation</li> <li>No operation, ignore the other bits in this register</li> </ul>
6 CAER	Clear All Enable Requests  O Clear only the ERQ bit specified in the CERQ field  Clear all bits in ERQ
5–4 Reserved	This field is reserved.
3–0 CERQ	Clear Enable Request Clears the corresponding bit in ERQ



# 21.3.8 Set Enable Request Register (DMA\_SERQ)

The SERQ provides a simple memory-mapped mechanism to set a given bit in the ERQ to enable the DMA request for a given channel. The data value on a register write causes the corresponding bit in the ERQ to be set. Setting the SAER bit provides a global set function, forcing the entire contents of ERQ to be set. If the NOP bit is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.

Address: DMA\_SERQ is 4000\_8000h base + 1Bh offset = 4000\_801Bh



### DMA\_SERQ field descriptions


Field	Description
7 NOP	<ul><li>0 Normal operation</li><li>1 No operation, ignore the other bits in this register</li></ul>
6 SAER	Set All Enable Requests  O Set only the ERQ bit specified in the SERQ field  Set all bits in ERQ
5–4 Reserved	This field is reserved.
3–0 SERQ	Set enable request Sets the corresponding bit in ERQ



# 21.3.9 Clear DONE Status Bit Register (DMA\_CDNE)

The CDNE provides a simple memory-mapped mechanism to clear the DONE bit in the TCD of the given channel. The data value on a register write causes the DONE bit in the corresponding transfer control descriptor to be cleared. Setting the CADN bit provides a global clear function, forcing all DONE bits to be cleared. If the NOP bit is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.

Address: DMA\_CDNE is 4000\_8000h base + 1Ch offset = 4000\_801Ch



### DMA\_CDNE field descriptions


Field	Description
7 NOP	<ul> <li>Normal operation</li> <li>No operation, ignore the other bits in this register</li> </ul>
6 CADN	Clears All DONE Bits  O Clears only the TCDn_CSR[DONE] bit specified in the CDNE field  Clears all bits in TCDn_CSR[DONE]
5–4 Reserved	This field is reserved.
3–0 CDNE	Clear DONE Bit Clears the corresponding bit in TCDn_CSR[DONE]



# 21.3.10 Set START Bit Register (DMA\_SSRT)

The SSRT provides a simple memory-mapped mechanism to set the START bit in the TCD of the given channel. The data value on a register write causes the START bit in the corresponding transfer control descriptor to be set. Setting the SAST bit provides a global set function, forcing all START bits to be set. If the NOP bit is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.

Address: DMA\_SSRT is 4000\_8000h base + 1Dh offset = 4000\_801Dh



## **DMA\_SSRT** field descriptions

Field	Description
7 NOP	<ul><li>0 Normal operation</li><li>1 No operation, ignore the other bits in this register</li></ul>
6 SAST	Set All START Bits (activates all channels)  0 Set only the TCDn_CSR[START] bit specified in the SSRT field  1 Set all bits in TCDn_CSR[START]
5–4 Reserved	This field is reserved.
3–0 SSRT	Set START Bit Sets the corresponding bit in TCDn_CSR[START]



# 21.3.11 Clear Error Register (DMA\_CERR)

The CERR provides a simple memory-mapped mechanism to clear a given bit in the ERR to disable the error condition flag for a given channel. The given value on a register write causes the corresponding bit in the ERR to be cleared. Setting the CAEI bit provides a global clear function, forcing the ERR contents to be cleared, clearing all channel error indicators. If the NOP bit is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.

Address: DMA\_CERR is 4000\_8000h base + 1Eh offset = 4000\_801Eh




### DMA\_CERR field descriptions


Field	Description
7 NOP	<ul> <li>Normal operation</li> <li>No operation, ignore the other bits in this register</li> </ul>
6 CAEI	Clear All Error Indicators  O Clear only the ERR bit specified in the CERR field  Clear all bits in ERR
5–4 Reserved	This field is reserved.
3–0 CERR	Clear Error Indicator Clears the corresponding bit in ERR



# 21.3.12 Clear Interrupt Request Register (DMA\_CINT)

The CINT provides a simple, memory-mapped mechanism to clear a given bit in the INT to disable the interrupt request for a given channel. The given value on a register write causes the corresponding bit in the INT to be cleared. Setting the CAIR bit provides a global clear function, forcing the entire contents of the INT to be cleared, disabling all DMA interrupt requests. If the NOP bit is set, the command is ignored. This allows you to write multiple-byte registers as a 32-bit word. Reads of this register return all zeroes.





### DMA\_CINT field descriptions


Field	Description
7 NOP	<ul><li>0 Normal operation</li><li>1 No operation, ignore the other bits in this register</li></ul>
6 CAIR	Clear All Interrupt Requests  O Clear only the INT bit specified in the CINT field  Clear all bits in INT
5–4 Reserved	This field is reserved.
3–0 CINT	Clear Interrupt Request Clears the corresponding bit in INT

## 21.3.13 Interrupt Request Register (DMA\_INT)

The INT register provides a bit map for the 16 channels signaling the presence of an interrupt request for each channel. Depending on the appropriate bit setting in the transfer-control descriptors, the eDMA engine generates an interrupt on data transfer completion. The outputs of this register are directly routed to the interrupt controller (INTC). During the interrupt-service routine associated with any given channel, it is the software's responsibility to clear the appropriate bit, negating the interrupt request. Typically, a write to the CINT register in the interrupt service routine is used for this purpose.



The state of any given channel's interrupt request is directly affected by writes to this register; it is also affected by writes to the CINT register. On writes to INT, a 1 in any bit position clears the corresponding channel's interrupt request. A zero in any bit position has no affect on the corresponding channel's current interrupt status. The CINT register is provided so the interrupt request for a single channel can easily be cleared without the need to perform a read-modify-write sequence to the INT register.



## DMA\_INT field descriptions

Field	Description									
31–16 Reserved	This read-only field is reserved and always has the value zero.									
15 INT15	Interrupt Request 15  O The interrupt request for corresponding channel is cleared									
	1 The interrupt request for corresponding channel is active									
14 INT14	Interrupt Request 14									
	0 The interrupt request for corresponding channel is cleared									
	1 The interrupt request for corresponding channel is active									
13 INT13	Interrupt Request 13									
	0 The interrupt request for corresponding channel is cleared									
	1 The interrupt request for corresponding channel is active									
12 INT12	Interrupt Request 12									
	0 The interrupt request for corresponding channel is cleared									
	1 The interrupt request for corresponding channel is active									
11 INT11	Interrupt Request 11									



# **DMA\_INT field descriptions (continued)**


Field	Description
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
10 INT10	Interrupt Request 10
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
9 INT9	Interrupt Request 9
INTS	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
8	Interrupt Request 8
INT8	The interrupt request for corresponding channel is cleared
	The interrupt request for corresponding channel is active
7	Interrupt Request 7
INT7	
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
6 INT6	Interrupt Request 6
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
5 INT5	Interrupt Request 5
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
4 INT4	Interrupt Request 4
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
3 INT3	Interrupt Request 3
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
2 INT2	Interrupt Request 2
INIZ	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
1 INT1	Interrupt Request 1
	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active
0	Interrupt Request 0
INT0	0 The interrupt request for corresponding channel is cleared
	1 The interrupt request for corresponding channel is active




# 21.3.14 Error Register (DMA\_ERR)

The ERR provides a bit map for the 16 channels, signaling the presence of an error for each channel. The eDMA engine signals the occurrence of an error condition by setting the appropriate bit in this register. The outputs of this register are enabled by the contents of the EEI, and then routed to the interrupt controller. During the execution of the interrupt-service routine associated with any DMA errors, it is software's responsibility to clear the appropriate bit, negating the error-interrupt request. Typically, a write to the CERR in the interrupt-service routine is used for this purpose. The normal DMA channel completion indicators (setting the transfer control descriptor DONE flag and the possible assertion of an interrupt request) are not affected when an error is detected.

The contents of this register can also be polled because a non-zero value indicates the presence of a channel error regardless of the state of the EEI. The state of any given channel's error indicators is affected by writes to this register; it is also affected by writes to the CERR. On writes to the ERR, a one in any bit position clears the corresponding channel's error status. A zero in any bit position has no affect on the corresponding channel's current error status. The CERR is provided so the error indicator for a single channel can easily be cleared.





## DMA\_ERR field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.



# **DMA\_ERR** field descriptions (continued)

Field	Description
15	Error In Channel 15
ERR15	An error in the corresponding channel has not occurred
	An error in the corresponding channel has not occurred     An error in the corresponding channel has occurred
14	Error In Channel 14
ERR14	O An away in the corresponding abound has not accurred
	<ul> <li>An error in the corresponding channel has not occurred</li> <li>An error in the corresponding channel has occurred</li> </ul>
13	Error In Channel 13
ERR13	
	<ul> <li>An error in the corresponding channel has not occurred</li> <li>An error in the corresponding channel has occurred</li> </ul>
12	Error In Channel 12
ERR12	
	O An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
11 ERR11	Error In Channel 11
	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
10 ERR10	Error In Channel 10
Limito	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
9 ERR9	Error In Channel 9
Littis	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
8 ERR8	Error In Channel 8
ERRO	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
7	Error In Channel 7
ERR7	An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
6	Error In Channel 6
ERR6	An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
5	Error In Channel 5
ERR5	An error in the corresponding channel has not occurred
	An error in the corresponding channel has occurred
4	Error In Channel 4
ERR4	



## DMA\_ERR field descriptions (continued)


Field	Description
	An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
3 ERR3	Error In Channel 3
	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
2 ERR2	Error In Channel 2
	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
1 ERR1	Error In Channel 1
	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred
0 ERR0	Error In Channel 0
	0 An error in the corresponding channel has not occurred
	1 An error in the corresponding channel has occurred


# 21.3.15 Hardware Request Status Register (DMA\_HRS)

The HRS provides a bit map for the DMA channels, signaling the presence of a hardware request for each channel. The hardware request status bits reflect the current state of the register and qualified (via the ERQ fields) DMA request signals as seen by the DMA's arbitration logic. This view into the hardware request signals may be used for debug purposes.

#### NOTE

These bits reflect the state of the request as seen by the arbitration logic. Therefore, this status is affected by the ERQ bits.







# **DMA\_HRS** field descriptions

Field	Description										
31–16 Reserved	This read-only field is reserved and always has the value zero.										
15 HRS15	Hardware Request Status Channel 15										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
14 HRS14	Hardware Request Status Channel 14										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
13 HRS13	Hardware Request Status Channel 13										
	O A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
12 HRS12	Hardware Request Status Channel 12										
	O A hardware service request for the corresponding channel is not present										
	A hardware service request for the corresponding channel is present										
11 HRS11	Hardware Request Status Channel 11										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
10 HRS10	Hardware Request Status Channel 10										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
9 HRS9	Hardware Request Status Channel 9										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
8 HRS8	Hardware Request Status Channel 8										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
7 HRS7	Hardware Request Status Channel 7										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
6 HRS6	Hardware Request Status Channel 6										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
5 HRS5	Hardware Request Status Channel 5										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										



## DMA\_HRS field descriptions (continued)

Field	Description										
4 HRS4	Hardware Request Status Channel 4										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
3 HRS3	Hardware Request Status Channel 3										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
2 HRS2	Hardware Request Status Channel 2										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
1 HRS1	Hardware Request Status Channel 1										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										
0 HRS0	Hardware Request Status Channel 0										
	0 A hardware service request for the corresponding channel is not present										
	1 A hardware service request for the corresponding channel is present										

# 21.3.16 Channel n Priority Register (DMA\_DCHPRIn)

When fixed-priority channel arbitration is enabled (CR[ERCA] = 0), the contents of these registers define the unique priorities associated with each channel. The channel priorities are evaluated by numeric value; for example, 0 is the lowest priority, 1 is the next priority, then 2, 3, etc. Software must program the channel priorities with unique values. Otherwise, a configuration error is reported. The range of the priority value is limited to the values of 0 through 15.

Addresses:  $4000\_8000h$  base + 100h offset +  $(1d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

x = Undefined at reset.

#### DMA\_DCHPRIn field descriptions

Field	Description								
7 ECP	Enable Channel Preemption								

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




## DMA\_DCHPRIn field descriptions (continued)

Field	Description										
	Channel n cannot be suspended by a higher priority channel's service request										
	1 Channel n can be temporarily suspended by the service request of a higher priority channel										
6 DPA	Disable Preempt Ability										
	0 Channel n can suspend a lower priority channel										
	1 Channel n cannot suspend any channel, regardless of channel priority										
5–4 Reserved	This read-only field is reserved and always has the value zero.										
3–0	Channel n Arbitration Priority										
CHPRI	Channel priority when fixed-priority arbitration is enabled										
	NOTE: Reset value for the channel priority fields, CHPRI, is equal to the corresponding channel number for each priority register, i.e., DCHPRI15[CHPRI] equals 0b1111.										

# 21.3.17 TCD Source Address (DMA\_TCD\_SADDR)

Addresses:  $4000\_8000h$  base + 1000h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

## DMA\_TCDn\_SADDR field descriptions


Field	Description
31–0 SADDR	Source Address
_	Memory address pointing to the source data.

x = Undefined at reset.



# 21.3.18 TCD Signed Source Address Offset (DMA\_TCD\_SOFF)

Addresses:  $4000\_8000h$  base + 1004h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

## DMA\_TCDn\_SOFF field descriptions

Field	Description
15–0 SOFF	Source address signed offset  Sign-extended offset applied to the current source address to form the next-state value as each source read is completed.

# 21.3.19 TCD Transfer Attributes (DMA\_TCD\_ATTR)

Addresses:  $4000\_8000h$  base + 1006h offset +  $(32d \times n)$ , where n = 0d to 15d

Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Read	SMOD				SSIZE			DMOD					DSIZE			
Write					OOIZE		BINIOD					DOIZE				
Reset	х*	Х*	Х*	х*	х*	х*	Х*	х*	х*	х*	х*	х*	х*	х*	Х*	X*

<sup>\*</sup> Notes:

## DMA\_TCDn\_ATTR field descriptions

Field	Description
15–11 SMOD	Source Address Modulo.
	0 Source address modulo feature is disabled
	≠0 This value defines a specific address range specified to be the value after SADDR + SOFF calculation is performed or the original register value. The setting of this field provides the ability to implement a circular data queue easily. For data queues requiring power-of-2 size bytes, the queue should start at a 0-modulo-size address and the SMOD field should be set to the appropriate value for the queue, freezing the desired number of upper address bits. The value programmed into this field specifies the number of lower address bits allowed to change. For a circular queue application, the SOFF is typically set to the transfer size to implement post-increment addressing with the SMOD function constraining the addresses to a 0-modulo-size range.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

<sup>•</sup> x = Undefined at reset.

<sup>•</sup> x = Undefined at reset.




## DMA\_TCDn\_ATTR field descriptions (continued)

Field	Description
10–8 SSIZE	Source data transfer size
00.22	The attempted use of a Reserved encoding causes a configuration error.
	000 8-bit
	001 16-bit
	010 32-bit
	011 Reserved
	100 16-byte
	101 Reserved
	110 Reserved
	111 Reserved
7–3 DMOD	Destination Address Modulo
	See the SMOD definition
2–0 DSIZE	Destination Data Transfer Size
	See the SSIZE definition

# 21.3.20 TCD Minor Byte Count (Minor Loop Disabled) (DMA\_TCD\_NBYTES\_MLNO)

TCD word 2's register definition depends on the status of minor loop mapping. If minor loop mapping is disabled (CR[EMLM] = 0), TCD word 2 is defined as follows. If minor loop mapping is enabled, see the TCD\_NBYTES\_MLOFFNO and TCD\_NBYTES\_MLOFFYES register descriptions for TCD word 2's register definition.

Addresses:  $4000\_8000h$  base + 1008h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

## DMA\_TCDn\_NBYTES\_MLNO field descriptions

Field	Description
31–0 NBYTES	Minor Byte Transfer Count
	Number of bytes to be transferred in each service request of the channel. As a channel activates, the appropriate TCD contents load into the eDMA engine, and the appropriate reads and writes perform until the minor byte transfer count has transferred. This is an indivisible operation and cannot be halted. (Although, it may be stalled by using the bandwidth control field, or via preemption.) After the minor count

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

<sup>•</sup> x = Undefined at reset.



## DMA\_TCDn\_NBYTES\_MLNO field descriptions (continued)

Field	Description
	is exhausted, the SADDR and DADDR values are written back into the TCD memory, the major iteration count is decremented and restored to the TCD memory. If the major iteration count is completed, additional processing is performed.
	NOTE: An NBYTES value of 0x0000_0000 is interpreted as a 4 GB transfer.


# 21.3.21 TCD Signed Minor Loop Offset (Minor Loop Enabled and Offset Disabled) (DMA\_TCD\_NBYTES\_MLOFFNO)

TCD word 2 is defined as follows if:

- Minor loop mapping is enabled (CR[EMLM] = 1) and
- SMLOE = 0 and DMLOE = 0

If minor loop mapping is enabled and SMLOE or DMLOE is set then refer to the TCD\_NBYTES\_MLOFFYES register description.

Addresses:  $4000\_8000h$  base + 1008h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

## DMA\_TCDn\_NBYTES\_MLOFFNO field descriptions

Field	Description
31 SMLOE	Source Minor Loop Offset Enable
J22	Selects whether the minor loop offset is applied to the source address upon minor loop completion.
	0 The minor loop offset is not applied to the SADDR
	1 The minor loop offset is applied to the SADDR
30 DMLOE	Destination Minor Loop Offset enable
	Selects whether the minor loop offset is applied to the destination address upon minor loop completion.
	0 The minor loop offset is not applied to the DADDR
	1 The minor loop offset is applied to the DADDR
29–0 NBYTES	Minor Byte Transfer Count
INDITIES	Number of bytes to be transferred in each service request of the channel.

x = Undefined at reset.



## DMA\_TCDn\_NBYTES\_MLOFFNO field descriptions (continued)

Field	Description
	As a channel activates, the appropriate TCD contents load into the eDMA engine, and the appropriate reads and writes perform until the minor byte transfer count has transferred. This is an indivisible operation and cannot be halted; although, it may be stalled by using the bandwidth control field, or via preemption. After the minor count is exhausted, the SADDR and DADDR values are written back into the TCD memory, the major iteration count is decremented and restored to the TCD memory. If the major iteration count is completed, additional processing is performed.


# 21.3.22 TCD Signed Minor Loop Offset (Minor Loop and Offset Enabled) (DMA\_TCD\_NBYTES\_MLOFFYES)

TCD word 2 is defined as follows if:

- Minor loop mapping is enabled (CR[EMLM] = 1) and
- Minor loop offset enabled (SMLOE or DMLOE = 1)

If minor loop mapping is enabled and SMLOE and DMLOE are cleared then refer to the TCD\_NBYTES\_MLOFFNO register description.

Addresses:  $4000\_8000h$  base + 1008h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

## DMA\_TCDn\_NBYTES\_MLOFFYES field descriptions

Field	Description
31 SMLOE	Source Minor Loop Offset Enable
525.2	Selects whether the minor loop offset is applied to the source address upon minor loop completion.
	0 The minor loop offset is not applied to the SADDR
	1 The minor loop offset is applied to the SADDR
30 DMLOE	Destination Minor Loop Offset enable
	Selects whether the minor loop offset is applied to the destination address upon minor loop completion.
	0 The minor loop offset is not applied to the DADDR
	1 The minor loop offset is applied to the DADDR
29-10 MLOFF	If SMLOE or DMLOE is set, this field represents a sign-extended offset applied to the source or destination address to form the next-state value after the minor loop completes.

<sup>•</sup> x = Undefined at reset.



## DMA\_TCDn\_NBYTES\_MLOFFYES field descriptions (continued)

Field	Description
9-0 NBYTES	Minor Byte Transfer Count  Number of bytes to be transferred in each service request of the channel.
	As a channel activates, the appropriate TCD contents load into the eDMA engine, and the appropriate reads and writes perform until the minor byte transfer count has transferred. This is an indivisible operation and cannot be halted. (Although, it may be stalled by using the bandwidth control field, or via preemption.) After the minor count is exhausted, the SADDR and DADDR values are written back into the TCD memory, the major iteration count is decremented and restored to the TCD memory. If the major iteration count is completed, additional processing is performed.

# 21.3.23 TCD Last Source Address Adjustment (DMA\_TCD\_SLAST)

Addresses:  $4000\_8000h$  base + 100Ch offset +  $(32d \times n)$ , where n = 0d to 15d




<sup>\*</sup> Notes:

## DMA\_TCDn\_SLAST field descriptions

Field	Description
31–0 SLAST	Last source Address Adjustment
	Adjustment value added to the source address at the completion of the major iteration count. This value can be applied to restore the source address to the initial value, or adjust the address to reference the next data structure.

# 21.3.24 TCD Destination Address (DMA\_TCD\_DADDR)

Addresses:  $4000\_8000h$  base + 1010h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

<sup>•</sup> x = Undefined at reset.


x = Undefined at reset.



## DMA\_TCDn\_DADDR field descriptions

Field	Description
31–0 DADDR	Destination Address
	Memory address pointing to the destination data.

# 21.3.25 TCD Signed Destination Address Offset (DMA\_TCD\_DOFF)




<sup>\*</sup> Notes:


## DMA\_TCDn\_DOFF field descriptions

Field	Description
15–0 DOFF	Destination Address Signed offset  Sign-extended offset applied to the current destination address to form the next-state value as each destination write is completed.

# 21.3.26 TCD Current Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA\_TCD\_CITER\_ELINKYES)

If TCDn\_CITER[ELINK] is set, the TCDn\_CITER register is defined as follows.





<sup>\*</sup> Notes:

<sup>•</sup> x = Undefined at reset.

<sup>•</sup> x = Undefined at reset.




## DMA\_TCDn\_CITER\_ELINKYES field descriptions

Field	Description
15	Enable channel-to-channel linking on minor-loop complete
ELINK	As the channel completes the minor loop, this flag enables linking to another channel, defined by the LINKCH field. The link target channel initiates a channel service request via an internal mechanism that sets the TCDn_CSR[START] bit of the specified channel.
	If channel linking is disabled, the CITER value is extended to 15 bits in place of a link channel number. If the major loop is exhausted, this link mechanism is suppressed in favor of the MAJORELINK channel linking.
	NOTE: This bit must be equal to the BITER[ELINK] bit. Otherwise, a configuration error is reported.
	0 The channel-to-channel linking is disabled
	1 The channel-to-channel linking is enabled
14–13 Reserved	This read-only field is reserved and always has the value zero.
12–9	Link Channel Number
LINKCH	If channel-to-channel linking is enabled (ELINK = 1), then after the minor loop is exhausted, the eDMA engine initiates a channel service request to the channel defined by these four bits by setting that channel's TCDn_CSR[START] bit.
8–0	Current Major Iteration Count
CITER	This 9-bit (ELINK = 1) or 15-bit (ELINK = 0) count represents the current major loop count for the channel. It is decremented each time the minor loop is completed and updated in the transfer control descriptor memory. After the major iteration count is exhausted, the channel performs a number of operations (e.g., final source and destination address calculations), optionally generating an interrupt to signal channel completion before reloading the CITER field from the beginning iteration count (BITER) field.
	NOTE: When the CITER field is initially loaded by software, it must be set to the same value as that contained in the BITER field.
	NOTE: If the channel is configured to execute a single service request, the initial values of BITER and CITER should be 0x0001.

# 21.3.27 TCD Current Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA\_TCD\_CITER\_ELINKNO)

If TCDn\_CITER[ELINK] is cleared, the TCDn\_CITER register is defined as follows.

Addresses:  $4000\_8000h$  base + 1016h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

x = Undefined at reset.



## DMA\_TCDn\_CITER\_ELINKNO field descriptions

Field	Description
15 ELINK	Enable channel-to-channel linking on minor-loop complete
	As the channel completes the minor loop, this flag enables linking to another channel, defined by the LINKCH field. The link target channel initiates a channel service request via an internal mechanism that sets the TCDn_CSR[START] bit of the specified channel.
	If channel linking is disabled, the CITER value is extended to 15 bits in place of a link channel number. If the major loop is exhausted, this link mechanism is suppressed in favor of the MAJORELINK channel linking.
	NOTE: This bit must be equal to the BITER[ELINK] bit. Otherwise, a configuration error is reported.
	0 The channel-to-channel linking is disabled
	1 The channel-to-channel linking is enabled
14–0	Current Major Iteration Count
CITER	This 9-bit (ELINK = 1) or 15-bit (ELINK = 0) count represents the current major loop count for the channel. It is decremented each time the minor loop is completed and updated in the transfer control descriptor memory. After the major iteration count is exhausted, the channel performs a number of operations (e.g., final source and destination address calculations), optionally generating an interrupt to signal channel completion before reloading the CITER field from the beginning iteration count (BITER) field.
	NOTE: When the CITER field is initially loaded by software, it must be set to the same value as that contained in the BITER field.
	<b>NOTE:</b> If the channel is configured to execute a single service request, the initial values of BITER and CITER should be 0x0001.

# 21.3.28 TCD Last Destination Address Adjustment/Scatter Gather Address (DMA\_TCD\_DLASTSGA)

Addresses:  $4000\_8000h$  base + 1018h offset +  $(32d \times n)$ , where n = 0d to 15d



<sup>\*</sup> Notes:

• x = Undefined at reset.

## DMA\_TCDn\_DLASTSGA field descriptions

Field	Description
31–0 DLASTSGA	Destination last address adjustment or the memory address for the next transfer control descriptor to be loaded into this channel (scatter/gather).
	If (TCDn_CSR[ESG] = 0) then
	<ul> <li>Adjustment value added to the destination address at the completion of the major iteration count.         This value can apply to restore the destination address to the initial value or adjust the address to reference the next data structure.     </li> </ul>


#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




## DMA\_TCDn\_DLASTSGA field descriptions (continued)

Field	Description
	else
	<ul> <li>This address points to the beginning of a 0-modulo-32-byte region containing the next transfer control descriptor to be loaded into this channel. This channel reload is performed as the major iteration count completes. The scatter/gather address must be 0-modulo-32-byte, else a configuration error is reported.</li> </ul>

# 21.3.29 TCD Control and Status (DMA\_TCD\_CSR)





<sup>\*</sup> Notes:

## DMA\_TCDn\_CSR field descriptions

Field	Description
15–14 BWC	Bandwidth Control
	Throttles the amount of bus bandwidth consumed by the eDMA. In general, as the eDMA processes the minor loop, it continuously generates read/write sequences until the minor count is exhausted. This field forces the eDMA to stall after the completion of each read/write access to control the bus request bandwidth seen by the crossbar switch.
	NOTE: If the source and destination sizes are equal, this field is ignored between the first and second transfers and after the last write of each minor loop. This behavior is a side effect of reducing start-up latency.
	00 No eDMA engine stalls
	01 Reserved
	10 eDMA engine stalls for 4 cycles after each r/w
	11 eDMA engine stalls for 8 cycles after each r/w
13–12 Reserved	This read-only field is reserved and always has the value zero.
11–8 MAJORLINKCH	Link Channel Number
	If (MAJORELINK = 0) then
	No channel-to-channel linking (or chaining) is performed after the major loop counter is exhausted.
	else

Table continues on the next page...

## K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

<sup>•</sup> x = Undefined at reset.



# DMA\_TCDn\_CSR field descriptions (continued)

Field	Description
	<ul> <li>After the major loop counter is exhausted, the eDMA engine initiates a channel service request at the channel defined by these six bits by setting that channel's TCDn_CSR[START] bit.</li> </ul>
7	Channel Done
DONE	This flag indicates the eDMA has completed the major loop. The eDMA engine sets it as the CITER count reaches zero; The software clears it, or the hardware when the channel is activated.
	NOTE: This bit must be cleared to write the MAJORELINK or ESG bits.
6 ACTIVE	Channel Active
	This flag signals the channel is currently in execution. It is set when channel service begins, and the eDMA clears it as the minor loop completes or if any error condition is detected. This bit resets to zero.
5	Enable channel-to-channel linking on major loop complete
MAJORELINK	As the channel completes the major loop, this flag enables the linking to another channel, defined by MAJORLINKCH. The link target channel initiates a channel service request via an internal mechanism that sets the TCDn_CSR[START] bit of the specified channel.
	<b>NOTE:</b> To support the dynamic linking coherency model, this field is forced to zero when written to while the TCDn_CSR[DONE] bit is set.
	0 The channel-to-channel linking is disabled
	1 The channel-to-channel linking is enabled
4	Enable Scatter/Gather Processing
ESG	As the channel completes the major loop, this flag enables scatter/gather processing in the current channel. If enabled, the eDMA engine uses DLASTSGA as a memory pointer to a 0-modulo-32 address containing a 32-byte data structure loaded as the transfer control descriptor into the local memory.
	NOTE: To support the dynamic scatter/gather coherency model, this field is forced to zero when written to while the TCDn_CSR[DONE] bit is set.
	0 The current channel's TCD is normal format.
	1 The current channel's TCD specifies a scatter gather format. The DLASTSGA field provides a memory pointer to the next TCD to be loaded into this channel after the major loop completes its execution.
3	Disable Request
DREQ	If this flag is set, the eDMA hardware automatically clears the corresponding ERQ bit when the current major iteration count reaches zero.
	0 The channel's ERQ bit is not affected
	1 The channel's ERQ bit is cleared when the major loop is complete
2	Enable an interrupt when major counter is half complete.
INTHALF	If this flag is set, the channel generates an interrupt request by setting the appropriate bit in the INT register when the current major iteration count reaches the halfway point. Specifically, the comparison performed by the eDMA engine is (CITER == (BITER >> 1)). This halfway point interrupt request is provided to support double-buffered (aka ping-pong) schemes or other types of data movement where the processor needs an early indication of the transfer's progress. If BITER is set, do not use INTHALF. Use INTMAJOR instead.




#### wemory map/register definition


## DMA\_TCDn\_CSR field descriptions (continued)

Field	Description
	0 The half-point interrupt is disabled
	1 The half-point interrupt is enabled
1 INTMAJOR	Enable an interrupt when major iteration count completes
	If this flag is set, the channel generates an interrupt request by setting the appropriate bit in the INT when the current major iteration count reaches zero.
	0 The end-of-major loop interrupt is disabled
	1 The end-of-major loop interrupt is enabled
0 START	Channel Start
317.111	If this flag is set, the channel is requesting service. The eDMA hardware automatically clears this flag after the channel begins execution.
	0 The channel is not explicitly started
	1 The channel is explicitly started via a software initiated service request

# 21.3.30 TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Enabled) (DMA\_TCD\_BITER\_ELINKYES)

If the TCDn\_BITER[ELINK] bit is set, the TCDn\_BITER register is defined as follows.





<sup>\*</sup> Notes:

### DMA\_TCDn\_BITER\_ELINKYES field descriptions

Field	Description	
15 ELINK	Enables channel-to-channel linking on minor loop complete  As the channel completes the minor loop, this flag enables the linking to another channel, defined by BITER[LINKCH]. The link target channel initiates a channel service request via an internal mechanism that sets the TCDn_CSR[START] bit of the specified channel. If channel linking disables, the BITER value extends to 15 bits in place of a link channel number. If the major loop is exhausted, this link mechanism is suppressed in favor of the MAJORELINK channel linking.	
	<b>NOTE:</b> When the software loads the TCD, this field must be set equal to the corresponding CITER field. Otherwise, a configuration error is reported. As the major iteration count is exhausted, the contents of this field is reloaded into the CITER field.	

<sup>•</sup> x = Undefined at reset.




## DMA\_TCDn\_BITER\_ELINKYES field descriptions (continued)

Field	Description
	0 The channel-to-channel linking is disabled
	1 The channel-to-channel linking is enabled
14–13 Reserved	This read-only field is reserved and always has the value zero.
12–9	Link Channel Number
LINKCH	If channel-to-channel linking is enabled (ELINK = 1), then after the minor loop is exhausted, the eDMA engine initiates a channel service request at the channel defined by these four bits by setting that channel's TCDn_CSR[START] bit.
	NOTE: When the software loads the TCD, this field must be set equal to the corresponding CITER field.  Otherwise, a configuration error is reported. As the major iteration count is exhausted, the contents of this field is reloaded into the CITER field.
8–0	Starting Major Iteration Count
BITER	As the transfer control descriptor is first loaded by software, this 9-bit (ELINK = 1) or 15-bit (ELINK = 0) field must be equal to the value in the CITER field. As the major iteration count is exhausted, the contents of this field are reloaded into the CITER field.
	NOTE: When the software loads the TCD, this field must be set equal to the corresponding CITER field.  Otherwise, a configuration error is reported. As the major iteration count is exhausted, the contents of this field is reloaded into the CITER field. If the channel is configured to execute a single service request, the initial values of BITER and CITER should be 0x0001.

# 21.3.31 TCD Beginning Minor Loop Link, Major Loop Count (Channel Linking Disabled) (DMA\_TCD\_BITER\_ELINKNO)

If the TCDn\_BITER[ELINK] bit is cleared, the TCDn\_BITER register is defined as follows.



<sup>\*</sup> Notes:

## DMA\_TCDn\_BITER\_ELINKNO field descriptions

Field	Description
15 ELINK	Enables channel-to-channel linking on minor loop complete
	As the channel completes the minor loop, this flag enables the linking to another channel, defined by BITER[LINKCH]. The link target channel initiates a channel service request via an internal mechanism that sets the TCDn_CSR[START] bit of the specified channel. If channel linking is disabled, the BITER

x = Undefined at reset.



#### runctional description

# DMA\_TCDn\_BITER\_ELINKNO field descriptions (continued)

Field	Description
	value extends to 15 bits in place of a link channel number. If the major loop is exhausted, this link mechanism is suppressed in favor of the MAJORELINK channel linking.
	<b>NOTE:</b> When the software loads the TCD, this field must be set equal to the corresponding CITER field. Otherwise, a configuration error is reported. As the major iteration count is exhausted, the contents of this field is reloaded into the CITER field.
	0 The channel-to-channel linking is disabled
	1 The channel-to-channel linking is enabled
14–0	Starting Major Iteration Count
BITER	As the transfer control descriptor is first loaded by software, this 9-bit (ELINK = 1) or 15-bit (ELINK = 0) field must be equal to the value in the CITER field. As the major iteration count is exhausted, the contents of this field are reloaded into the CITER field.
	<b>NOTE:</b> When the software loads the TCD, this field must be set equal to the corresponding CITER field. Otherwise, a configuration error is reported. As the major iteration count is exhausted, the contents of this field is reloaded into the CITER field. If the channel is configured to execute a single service request, the initial values of BITER and CITER should be 0x0001.

# 21.4 Functional description

## 21.4.1 eDMA basic data flow

The basic flow of a data transfer can be partitioned into three segments.

As shown in the following diagram, the first segment involves the channel activation:






Figure 21-289. eDMA operation, part 1

This example uses the assertion of the eDMA peripheral request signal to request service for channel n. Channel activation via software and the TCDn\_CSR[START] bit follows the same basic flow as peripheral requests. The eDMA request input signal is registered internally and then routed through the eDMA engine: first through the control module, then into the program model and channel arbitration. In the next cycle, the channel arbitration performs, using the fixed-priority or round-robin algorithm. After arbitration is complete, the activated channel number is sent through the address path and converted into the required address to access the local memory for TCDn. Next, the TCD memory is accessed and the required descriptor read from the local memory and loaded into the eDMA engine address path channel x or y registers. The TCD memory is 64 bits wide to minimize the time needed to fetch the activated channel descriptor and load it into the address path channel x or y registers.

The following diagram illustrates the second part of the basic data flow:



#### runctional description




Figure 21-290. eDMA operation, part 2

The modules associated with the data transfer (address path, data path, and control) sequence through the required source reads and destination writes to perform the actual data movement. The source reads are initiated and the fetched data is temporarily stored in the data path block until it is gated onto the internal bus during the destination write. This source read/destination write processing continues until the minor byte count has transferred.

After the minor byte count has moved, the final phase of the basic data flow is performed. In this segment, the address path logic performs the required updates to certain fields in the appropriate TCD, e.g., SADDR, DADDR, CITER. If the major iteration count is exhausted, additional operations are performed. These include the final address adjustments and reloading of the BITER field into the CITER. Assertion of an optional interrupt request also occurs at this time, as does a possible fetch of a new TCD from memory using the scatter/gather address pointer included in the descriptor (if scatter/gather is enabled). The updates to the TCD memory and the assertion of an interrupt request are shown in the following diagram.






Figure 21-291. eDMA operation, part 3

## 21.4.2 Error reporting and handling

Channel errors are reported in the ES register and can be caused by:

- A configuration error, which is an illegal setting in the transfer-control descriptor or an illegal priority register setting in Fixed-Arbitration mode, or
- An error termination to a bus master read or write cycle

A configuration error is reported when the starting source or destination address, source or destination offsets, minor loop byte count, or the transfer size represent an inconsistent state. Each of these possible causes are detailed below:

- The addresses and offsets must be aligned on 0-modulo-transfer-size boundaries.
- The minor loop byte count must be a multiple of the source and destination transfer sizes.



#### runctional description

- All source reads and destination writes must be configured to the natural boundary of the programmed transfer size respectively.
- In fixed arbitration mode, a configuration error is caused by any two channel priorities being equal. All channel priority levels must be unique when fixed arbitration mode is enabled.
- If a scatter/gather operation is enabled upon channel completion, a configuration error is reported if the scatter/gather address (DLAST\_SGA) is not aligned on a 32-byte boundary.
- If minor loop channel linking is enabled upon channel completion, a configuration error is reported when the link is attempted if the TCDn\_CITER[E\_LINK] bit does not equal the TCDn\_BITER[E\_LINK] bit.

If enabled, all configuration error conditions, except the scatter/gather and minor-loop link errors, report as the channel activates and asserts an error interrupt request. A scatter/gather configuration error is reported when the scatter/gather operation begins at major loop completion when properly enabled. A minor loop channel link configuration error is reported when the link operation is serviced at minor loop completion.

If a system bus read or write is terminated with an error, the data transfer is stopped and the appropriate bus error flag set. In this case, the state of the channel's transfer control descriptor is updated by the eDMA engine with the current source address, destination address, and current iteration count at the point of the fault. When a system-bus error occurs, the channel terminates after the read or write transaction, which is already pipelined after errant access, has completed. If a bus error occurs on the last read prior to beginning the write sequence, the write executes using the data captured during the bus error. If a bus error occurs on the last write prior to switching to the next read sequence, the read sequence executes before the channel terminates due to the destination bus error.

A transfer may be cancelled by software with the CR[CX] bit. When a cancel transfer request is recognized, the DMA engine stops processing the channel. The current readwrite sequence is allowed to finish. If the cancel occurs on the last read-write sequence of a major or minor loop, the cancel request is discarded and the channel retires normally.

The error cancel transfer is the same as a cancel transfer except the ES register is updated with the cancelled channel number and ECX is set. The TCD of a cancelled channel contains the source and destination addresses of the last transfer saved in the TCD. If the channel needs to be restarted, you must re-initialize the TCD because the aforementioned fields no longer represent the original parameters. When a transfer is cancelled by the error cancel transfer mechanism, the channel number is loaded into DMA\_ES[ERRCHN] and ECX and VLD are set. In addition, an error interrupt may be generated if enabled.

The occurrence of any error causes the eDMA engine to stop the active channel immediately, and the appropriate channel bit in the eDMA error register is asserted. At the same time, the details of the error condition are loaded into the ES register. The major



loop complete indicators, setting the transfer control descriptor DONE flag and the possible assertion of an interrupt request, are not affected when an error is detected. After the error status has been updated, the eDMA engine continues operating by servicing the next appropriate channel. A channel that experiences an error condition is not automatically disabled. If a channel is terminated by an error and then issues another service request before the error is fixed, that channel executes and terminates with the same error condition.

# 21.4.3 Channel preemption

Channel preemption is enabled on a per-channel basis by setting the DCHPRIn[ECP] bit. Channel preemption allows the executing channel's data transfers to temporarily suspend in favor of starting a higher priority channel. After the preempting channel has completed all its minor loop data transfers, the preempted channel is restored and resumes execution. After the restored channel completes one read/write sequence, it is again eligible for preemption. If any higher priority channel is requesting service, the restored channel is suspended and the higher priority channel is serviced. Nested preemption, that is, attempting to preempt a preempting channel, is not supported. After a preempting channel begins execution, it cannot be preempted. Preemption is available only when fixed arbitration is selected.

A channel's ability to preempt another channel can be disabled by setting DCHPRIn[DPA]. When a channel's preempt ability is disabled, that channel cannot suspend a lower priority channel's data transfer, regardless of the lower priority channel's ECP setting. This allows for a pool of low priority, large data-moving channels to be defined. These low priority channels can be configured to not preempt each other, thus preventing a low priority channel from consuming the preempt slot normally available to a true, high priority channel.

## 21.4.4 Performance

This section addresses the performance of the eDMA module, focusing on two separate metrics:

- In the traditional data movement context, performance is best expressed as the peak data transfer rates achieved using the eDMA. In most implementations, this transfer rate is limited by the speed of the source and destination address spaces.
- In a second context where device-paced movement of single data values to/from peripherals is dominant, a measure of the requests that can be serviced in a fixed time is a more relevant metric. In this environment, the speed of the source and destination



#### runctional description

address spaces remains important. However, the microarchitecture of the eDMA also factors significantly into the resulting metric.

#### 21.4.4.1 Peak transfer rates

The peak transfer rates for several different source and destination transfers are shown in the following tables. These tables assume:

- Internal SRAM can be accessed with zero wait-states when viewed from the system bus data phase
- All internal peripheral bus reads require two wait-states, and internal peripheral bus writes three wait-states, when viewed from the system bus data phase
- All internal peripheral bus accesses are 32-bits in size

This table presents a peak transfer rate comparison.

32b internal peripheral bus-System Speed, Internal SRAM-to-Internal SRAM-toto-Width **Internal SRAM** 32b internal peripheral bus **Internal SRAM** 53.3 66.7 MHz, 32b 133.3 66.7 83.3 MHz, 32b 166.7 83.3 66.7 100.0 MHz, 32b 200.0 100.0 80.0 266.7 133.3 106.7 133.3 MHz, 32b 150.0 150.0 MHz, 32b 300.0 120.0

Table 21-292. eDMA peak transfer rates (Mbytes/sec)

Internal-SRAM-to-internal-SRAM transfers occur at the core's datapath width. For all transfers involving the internal peripheral bus, 32-bit transfer sizes are used. In all cases, the transfer rate includes the time to read the source plus the time to write the destination.

## 21.4.4.2 Peak request rates

The second performance metric is a measure of the number of DMA requests that can be serviced in a given amount of time. For this metric, assume that the peripheral request causes the channel to move a single internal peripheral bus-mapped operand to/from internal SRAM. The same timing assumptions used in the previous example apply to this calculation. In particular, this metric also reflects the time required to activate the channel.



The eDMA design supports the following hardware service request sequence:

Table 21-293. Hardware service request process, cycles 1–7

Cycle	Description
1	eDMA peripheral request is asserted.
2	The eDMA peripheral request is registered locally in the eDMA module and qualified. TCDn_CSR[START] bit initiated requests start at this point with the registering of the user write to TCDn word 7.
3	Channel arbitration begins.
4	Channel arbitration completes. The transfer control descriptor local memory read is initiated.
5–6	The first two parts of the activated channel's TCD is read from the local memory. The memory width to the eDMA engine is 64 bits, so the entire descriptor can be accessed in four cycles.
7	The first system bus read cycle is initiated, as the third part of the channel's TCD is read from the local memory. Depending on the state of the crossbar switch, arbitration at the system bus may insert an additional cycle of delay here.

The exact timing from this point is a function of the response times for the channel's read and write accesses. In the case of an internal peripheral bus read and internal SRAM write, the combined data phase time is 4 cycles. For an SRAM read and internal peripheral bus write, it is 5 cycles.

Table 21-294. Hardware service request process, cycles 8-17

Cycle		Description
With internal peripheral bus read and internal SRAM write	With SRAM read and internal peripheral bus write	
8–11	8–12	The last part of the TCD is read in. This cycle represents the first data phase for the read, and the address phase for the destination write.
12	13	This cycle represents the data phase of the last destination write.
13	14	The eDMA engine completes the execution of the inner minor loop and prepares to write back the required TCDn fields into the local memory. The TCDn word 7 is read and checked for channel linking or scatter/gather requests.
14	15	The appropriate fields in the first part of the TCD <i>n</i> are written back into the local memory.
15	16	The fields in the second part of the TCDn are written back into the local memory. This cycle coincides with the next channel arbitration cycle start.



#### runctional description

Table 21-294. Hardware service request process, cycles 8–17 (continued)

Cycle		Description
With internal peripheral bus read and internal SRAM write	With SRAM read and internal peripheral bus write	
16	17	The next channel to be activated performs the read of the first part of its TCD from the local memory. This is equivalent to Cycle 4 for the first channel's service request.

Assuming zero wait states on the system bus, DMA requests can be processed every 9 cycles. Assuming an average of the access times associated with internal peripheral bus-to-SRAM (4 cycles) and SRAM-to-internal peripheral bus (5 cycles), DMA requests can be processed every 11.5 cycles (4 + (4+5)/2 + 3). This is the time from Cycle 4 to Cycle? +5. The resulting peak request rate, as a function of the system frequency, is shown in the following table.

Table 21-295. eDMA peak request rate (MReg/sec)

Custom fraguency (MILIT)	Request rate	Request rate
System frequency (MHz)	with zero wait states	with wait states
66.6	7.4	5.8
83.3	9.2	7.2
100.0	11.1	8.7
133.3	14.8	11.6
150.0	16.6	13.0

A general formula to compute the peak request rate with overlapping requests is:

where:

Table 21-296. Peak request formula legend

Where	Represents
PEAKreq	Peak request rate
freq	System frequency
entry	Channel startup (4 cycles)
read_ws	Wait states seen during the system bus read data phase
write_ws	Wait states seen during the system bus write data phase
exit	Channel shutdown (3 cycles)



## 21.4.4.3 eDMA performance example

Consider a system with the following characteristics:

- Internal SRAM can be accessed with one wait-state when viewed from the system bus data phase
- All internal peripheral bus reads require two wait-states, and internal peripheral bus writes three wait-states viewed from the system bus data phase
- System operates at 150 MHz

For an SRAM to internal peripheral bus transfer,

$$PEAKreq = 150 MHz / [4 + (1 + 1) + (1 + 3) + 3] cycles = 11.5 Mreg/sec$$

For an internal peripheral bus to SRAM transfer,

$$PEAKreq = 150 MHz / [4 + (1 + 2) + (1 + 1) + 3] cycles = 12.5 Mreq/sec$$

Assuming an even distribution of the two transfer types, the average peak request rate would be:

$$PEAKreq = (11.5 Mreq/sec + 12.5 Mreq/sec) / 2 = 12.0 Mreq/sec$$

The minimum number of cycles to perform a single read/write, zero wait states on the system bus, from a cold start where no channel is executing and eDMA is idle are:

- 11 cycles for a software, that is, a TCDn\_CSR[START] bit, request
- 12 cycles for a hardware, that is, an eDMA peripheral request signal, request

Two cycles account for the arbitration pipeline and one extra cycle on the hardware request resulting from the internal registering of the eDMA peripheral request signals. For the peak request rate calculations above, the arbitration and request registering is absorbed in or overlaps the previous executing channel.

#### Note

When channel linking or scatter/gather is enabled, a two cycle delay is imposed on the next channel selection and startup. This allows the link channel or the scatter/gather channel to be eligible and considered in the arbitration pool for next channel selection.



# 21.5 Initialization/application information

The following sections discuss initialization of the eDMA and programming considerations.

### 21.5.1 eDMA initialization

A typical initialization of the eDMA has the following sequence:

- 1. Write the CR register if a configuration other than the default is desired.
- 2. Write the channel priority levels into the DCHPRI*n* registers if a configuration other than the default is desired.
- 3. Enable error interrupts in the EEI register if so desired.
- 4. Write the 32-byte TCD for each channel that may request service.
- 5. Enable any hardware service requests via the ERQ register.
- 6. Request channel service via either:
  - Software: setting the TCD*n*\_CSR[START] bit
  - Hardware: slave device asserting its eDMA peripheral request signal

After any channel requests service, a channel is selected for execution based on the arbitration and priority levels written into the programmer's model. The eDMA engine reads the entire TCD, including the TCD control and status fields, as shown in the following table, for the selected channel into its internal address path module.

As the TCD is read, the first transfer is initiated on the internal bus unless a configuration error is detected. Transfers from the source, as defined by the source address, TCD*n*\_SADDR, to the destination, as defined by the destination address, TCD*n*\_DADDR, continue until the specified number of bytes (TCD*n*\_NBYTES) are transferred.

When the transfer is complete, the eDMA engine's local TCD*n*\_SADDR, TCD*n*\_DADDR, and TCD*n*\_CITER are written back to the main TCD memory and any minor loop channel linking is performed, if enabled. If the major loop is exhausted, further post processing executes, such as interrupts, major loop channel linking, and scatter/gather operations, if enabled.



#### Table 21-297. TCD Control and Status fields

TCDn_CSR field name	Description
START	Control bit to start channel explicitly when using a software initiated DMA service (Automatically cleared by hardware)
ACTIVE	Status bit indicating the channel is currently in execution
DONE	Status bit indicating major loop completion (cleared by software when using a software initiated DMA service)
D_REQ	Control bit to disable DMA request at end of major loop completion when using a hardware initiated DMA service
BWC	Control bits for throttling bandwidth control of a channel
E_SG	Control bit to enable scatter-gather feature
INT_HALF	Control bit to enable interrupt when major loop is half complete
INT_MAJ	Control bit to enable interrupt when major loop completes

The following figure shows how each DMA request initiates one minor-loop transfer, or iteration, without CPU intervention. DMA arbitration can occur after each minor loop, and one level of minor loop DMA preemption is allowed. The number of minor loops in a major loop is specified by the beginning iteration count (BITER).




Figure 21-292. Example of multiple loop iterations

The following figure lists the memory array terms and how the TCD settings interrelate.



#### mualization/application information




Figure 21-293. Memory array terms

## 21.5.2 Programming errors

The eDMA performs various tests on the transfer control descriptor to verify consistency in the descriptor data. Most programming errors are reported on a per channel basis with the exception of channel priority error (ES[CPE]).

For all error types other than channel priority error, the channel number causing the error is recorded in the ES register. If the error source is not removed before the next activation of the problem channel, the error is detected and recorded again.

If priority levels are not unique, when any channel requests service, a channel priority error is reported. The highest channel priority with an active request is selected, but the lowest numbered channel with that priority is selected by arbitration and executed by the eDMA engine. The hardware service request handshake signals, error interrupts, and error reporting is associated with the selected channel.

## 21.5.3 Arbitration mode considerations

## 21.5.3.1 Fixed channel arbitration

In this mode, the channel service request from the highest priority channel is selected to execute.



#### 21.5.3.2 Round-robin channel arbitration

Channels are serviced starting with the highest channel number and rotating through to the lowest channel number without regard to the channel priority levels.

# 21.5.4 Performing DMA transfers

## 21.5.4.1 Single request

To perform a simple transfer of n bytes of data with one activation, set the major loop to one (TCDn\_CITER = TCDn\_BITER = 1). The data transfer begins after the channel service request is acknowledged and the channel is selected to execute. After the transfer is complete, the TCDn\_CSR[DONE] bit is set and an interrupt generates if properly enabled.

For example, the following TCD entry is configured to transfer 16 bytes of data. The eDMA is programmed for one iteration of the major loop transferring 16 bytes per iteration. The source memory has a byte wide memory port located at 0x1000. The destination memory has a 32-bit port located at 0x2000. The address offsets are programmed in increments to match the transfer size: one byte for the source and four bytes for the destination. The final source and destination addresses are adjusted to return to their beginning values.

```
TCDn_CITER = TCDn_BITER = 1
TCDn_NBYTES = 16
TCDn_SADDR = 0x1000
TCDn_SOFF = 1
TCDn_ATTR[SSIZE] = 0
TCDn_SLAST = -16
TCDn_DADDR = 0x2000
TCDn_DADDR = 0x2000
TCDn_DATTR[DSIZE] = 2
TCDn_DATTR[DSIZE] = 2
TCDn_DLAST_SGA= -16
TCDn_CSR[INT_MAJ] = 1
TCDn_CSR[START] = 1 (Should be written last after all other fields have been initialized)
All other TCDn fields = 0
```

This generates the following event sequence:

- 1. User write to the TCDn\_CSR[START] bit requests channel service.
- 2. The channel is selected by arbitration for servicing.
- 3. eDMA engine writes:  $TCDn_CSR[DONE] = 0$ ,  $TCDn_CSR[START] = 0$ ,  $TCDn_CSR[ACTIVE] = 1$ .



#### unualization/application information

- 4. eDMA engine reads: channel TCD data from local memory to internal register file.
- 5. The source-to-destination transfers are executed as follows:
  - a. Read byte from location 0x1000, read byte from location 0x1001, read byte from 0x1002, read byte from 0x1003.
  - b. Write 32-bits to location  $0x2000 \rightarrow$  first iteration of the minor loop.
  - c. Read byte from location 0x1004, read byte from location 0x1005, read byte from 0x1006, read byte from 0x1007.
  - d. Write 32-bits to location  $0x2004 \rightarrow$  second iteration of the minor loop.
  - e. Read byte from location 0x1008, read byte from location 0x1009, read byte from 0x100A, read byte from 0x100B.
  - f. Write 32-bits to location  $0x2008 \rightarrow$  third iteration of the minor loop.
  - g. Read byte from location 0x100C, read byte from location 0x100D, read byte from 0x100E, read byte from 0x100F.
  - h. Write 32-bits to location  $0x200C \rightarrow last$  iteration of the minor loop  $\rightarrow$  major loop complete.
- 6. The eDMA engine writes:  $TCDn\_SADDR = 0x1000$ ,  $TCDn\_DADDR = 0x2000$ ,  $TCDn\_CITER = 1$  ( $TCDn\_BITER$ ).
- 7. The eDMA engine writes:  $TCDn_CSR[ACTIVE] = 0$ ,  $TCDn_CSR[DONE] = 1$ , INT[n] = 1.
- 8. The channel retires and the eDMA goes idle or services the next channel.

## 21.5.4.2 Multiple requests

The following example transfers 32 bytes via two hardware requests, but is otherwise the same as the previous example. The only fields that change are the major loop iteration count and the final address offsets. The eDMA is programmed for two iterations of the major loop transferring 16 bytes per iteration. After the channel's hardware requests are enabled in the ERQ register, the slave device initiates channel service requests.

```
TCDn_CITER = TCDn_BITER = 2
TCDn_SLAST = -32
TCDn_DLAST_SGA = -32
```

This would generate the following sequence of events:

1. First hardware, that is, eDMA peripheral, request for channel service.



- 2. The channel is selected by arbitration for servicing.
- 3. eDMA engine writes:  $TCDn\_CSR[DONE] = 0$ ,  $TCDn\_CSR[START] = 0$ ,  $TCDn\_CSR[ACTIVE] = 1$ .
- 4. eDMA engine reads: channel TCDn data from local memory to internal register file.
- 5. The source to destination transfers are executed as follows:
  - a. Read byte from location 0x1000, read byte from location 0x1001, read byte from 0x1002, read byte from 0x1003.
  - b. Write 32-bits to location  $0x2000 \rightarrow$  first iteration of the minor loop.
  - c. Read byte from location 0x1004, read byte from location 0x1005, read byte from 0x1006, read byte from 0x1007.
  - d. Write 32-bits to location  $0x2004 \rightarrow$  second iteration of the minor loop.
  - e. Read byte from location 0x1008, read byte from location 0x1009, read byte from 0x100A, read byte from 0x100B.
  - f. Write 32-bits to location  $0x2008 \rightarrow$  third iteration of the minor loop.
  - g. Read byte from location 0x100C, read byte from location 0x100D, read byte from 0x100E, read byte from 0x100F.
  - h. Write 32-bits to location  $0x200C \rightarrow last$  iteration of the minor loop.
- 6. eDMA engine writes:  $TCDn\_SADDR = 0x1010$ ,  $TCDn\_DADDR = 0x2010$ ,  $TCDn\_CITER = 1$ .
- 7. eDMA engine writes:  $TCDn_CSR[ACTIVE] = 0$ .
- 8. The channel retires → one iteration of the major loop. The eDMA goes idle or services the next channel.
- 9. Second hardware, that is, eDMA peripheral, requests channel service.
- 10. The channel is selected by arbitration for servicing.
- 11. eDMA engine writes:  $TCDn\_CSR[DONE] = 0$ ,  $TCDn\_CSR[START] = 0$ ,  $TCDn\_CSR[ACTIVE] = 1$ .
- 12. eDMA engine reads: channel TCD data from local memory to internal register file.
- 13. The source to destination transfers are executed as follows:
  - a. Read byte from location 0x1010, read byte from location 0x1011, read byte from 0x1012, read byte from 0x1013.



#### unualization/application information

- b. Write 32-bits to location  $0x2010 \rightarrow$  first iteration of the minor loop.
- c. Read byte from location 0x1014, read byte from location 0x1015, read byte from 0x1016, read byte from 0x1017.
- d. Write 32-bits to location  $0x2014 \rightarrow$  second iteration of the minor loop.
- e. Read byte from location 0x1018, read byte from location 0x1019, read byte from 0x101A, read byte from 0x101B.
- f. Write 32-bits to location  $0x2018 \rightarrow$  third iteration of the minor loop.
- g. Read byte from location 0x101C, read byte from location 0x101D, read byte from 0x101E, read byte from 0x101F.
- h. Write 32-bits to location  $0x201C \rightarrow last$  iteration of the minor loop  $\rightarrow$  major loop complete.
- 14. eDMA engine writes:  $TCDn_SADDR = 0x1000$ ,  $TCDn_DADDR = 0x2000$ ,  $TCDn_CITER = 2$  ( $TCDn_BITER$ ).
- 15. eDMA engine writes:  $TCDn\_CSR[ACTIVE] = 0$ ,  $TCDn\_CSR[DONE] = 1$ , INT[n] = 1.
- 16. The channel retires → major loop complete. The eDMA goes idle or services the next channel.

# 21.5.4.3 Using the modulo feature

The modulo feature of the eDMA provides the ability to implement a circular data queue in which the size of the queue is a power of 2. MOD is a 5-bit field for the source and destination in the TCD, and it specifies which lower address bits increment from their original value after the address+offset calculation. All upper address bits remain the same as in the original value. A setting of 0 for this field disables the modulo feature.

The following table shows how the transfer addresses are specified based on the setting of the MOD field. Here a circular buffer is created where the address wraps to the original value while the 28 upper address bits (0x1234567x) retain their original value. In this example the source address is set to 0x12345670, the offset is set to 4 bytes and the MOD field is set to 4, allowing for a  $2^4$  byte (16-byte) size queue.

Table 21-298. Modulo example

Transfer Number	Address
1	0x12345670



#### Table 21-298. Modulo example (continued)

Transfer Number	Address
2	0x12345674
3	0x12345678
4	0x1234567C
5	0x12345670
6	0x12345674

# 21.5.5 Monitoring transfer descriptor status

## 21.5.5.1 Testing for minor loop completion

There are two methods to test for minor loop completion when using software initiated service requests. The first is to read the TCD*n*\_CITER field and test for a change. Another method may be extracted from the sequence shown below. The second method is to test the TCD*n*\_CSR[START] bit and the TCD*n*\_CSR[ACTIVE] bit. The minor-loop-complete condition is indicated by both bits reading zero after the TCD*n*\_CSR[START] was set. Polling the TCD*n*\_CSR[ACTIVE] bit may be inconclusive, because the active status may be missed if the channel execution is short in duration.

The TCD status bits execute the following sequence for a software activated channel:

Stage	TCDn_CSR bits			State
Stage	START	ACTIVE DONE		State
1	1	0	0	Channel service request via software
2	0	1	0 Channel is executing	
3a	0	0	0	Channel has completed the minor loop and is idle
3b	0	0	1	Channel has completed the major loop and is idle

The best method to test for minor-loop completion when using hardware, that is, peripheral, initiated service requests is to read the TCD*n*\_CITER field and test for a change. The hardware request and acknowledge handshake signals are not visible in the programmer's model.

The TCD status bits execute the following sequence for a hardware-activated channel:



#### unualization/application information

Stone	TCDn_CSR bits			State
Stage	START	ACTIVE	DONE	- State
1	0	0	0	Channel service request via hardware (peripheral request asserted)
2	0	1	0	Channel is executing
3a	0	0	0	Channel has completed the minor loop and is idle
3b	0	0	1	Channel has completed the major loop and is idle

For both activation types, the major-loop-complete status is explicitly indicated via the TCD*n*\_CSR[DONE] bit.

The  $TCDn\_CSR[START]$  bit is cleared automatically when the channel begins execution regardless of how the channel activates.

## 21.5.5.2 Reading the transfer descriptors of active channels

The eDMA reads back the true TCD*n*\_SADDR, TCD*n*\_DADDR, and TCD*n*\_NBYTES values if read while a channel executes. The true values of the SADDR, DADDR, and NBYTES are the values the eDMA engine currently uses in its internal register file and not the values in the TCD local memory for that channel. The addresses, SADDR and DADDR, and NBYTES, decrements to zero as the transfer progresses, can give an indication of the progress of the transfer. All other values are read back from the TCD local memory.

# 21.5.5.3 Checking channel preemption status

Preemption is available only when fixed arbitration is selected as the channel arbitration mode. A preemptive situation is one in which a preempt-enabled channel runs and a higher priority request becomes active. When the eDMA engine is not operating in fixed channel arbitration mode, the determination of the actively running relative priority outstanding requests become undefined. Channel priorities are treated as equal, that is, constantly rotating, when Round-Robin Arbitration mode is selected.

The TCD*n*\_CSR[ACTIVE] bit for the preempted channel remains asserted throughout the preemption. The preempted channel is temporarily suspended while the preempting channel executes one major loop iteration. If two TCD*n*\_CSR[ACTIVE] bits are set simultaneously in the global TCD map, a higher priority channel is actively preempting a lower priority channel.



## 21.5.6 Channel Linking

Channel linking (or chaining) is a mechanism where one channel sets the TCDn\_CSR[START] bit of another channel (or itself), therefore initiating a service request for that channel. When properly enabled, the EDMA engine automatically performs this operation at the major or minor loop completion.

The minor loop channel linking occurs at the completion of the minor loop (or one iteration of the major loop). The TCDn\_CITER[E\_LINK] field determines whether a minor loop link is requested. When enabled, the channel link is made after each iteration of the major loop except for the last. When the major loop is exhausted, only the major loop channel link fields are used to determine if a channel link should be made. For example, the initial fields of:

```
TCDn_CITER[E_LINK] = 1
TCDn_CITER[LINKCH] = 0xC
TCDn_CITER[CITER] value = 0x4
TCDn_CSR[MAJOR_E_LINK] = 1
TCDn_CSR[MAJOR_LINKCH] = 0x7
```

#### executes as:

- 1. Minor loop done  $\rightarrow$  set TCD12\_CSR[START] bit
- 2. Minor loop done  $\rightarrow$  set TCD12\_CSR[START] bit
- 3. Minor loop done  $\rightarrow$  set TCD12\_CSR[START] bit
- 4. Minor loop done, major loop done→ set TCD7\_CSR[START] bit

When minor loop linking is enabled (TCDn\_CITER[E\_LINK] = 1), the TCDn\_CITER[CITER] field uses a nine bit vector to form the current iteration count. When minor loop linking is disabled (TCDn\_CITER[E\_LINK] = 0), the TCDn\_CITER[CITER] field uses a 15-bit vector to form the current iteration count. The bits associated with the TCDn\_CITER[LINKCH] field are concatenated onto the CITER value to increase the range of the CITER.

#### **Note**

The TCD*n*\_CITER[E\_LINK] bit and the TCD*n*\_BITER[E\_LINK] bit must equal or a configuration error is reported. The CITER and BITER vector widths must be equal to calculate the major loop, half-way done interrupt point.

The following table summarizes how a DMA channel can link to another DMA channel, i.e, use another channel's TCD, at the end of a loop.



### Table 21-299. Channel Linking Parameters

Desired Link Behavior	TCD Control Field Name	Description
Link at end of	CITER[E_LINK]	Enable channel-to-channel linking on minor loop completion (current iteration)
Minor Loop	CITER[LINKCH]	Link channel number when linking at end of minor loop (current iteration)
Link at end of	CSR[MAJOR_E_LINK]	Enable channel-to-channel linking on major loop completion
Major Loop	CSR[MAJOR_LINKCH]	Link channel number when linking at end of major loop

# 21.5.7 Dynamic programming

# 21.5.7.1 Dynamically changing the channel priority

The following two options are recommended for dynamically changing channel priority levels:

- 1. Switch to Round-Robin Channel Arbitration mode, change the channel priorities, then switch back to Fixed Arbitration mode,
- 2. Disable all the channels, change the channel priorities, then enable the appropriate channels.

# 21.5.7.2 Dynamically changing the channel linking and scatter/gather options

Dynamic channel linking and dynamic scatter/gather is the process of changing the TCD*n*\_CSR[MAJOR\_E\_LINK] or TCD*n*\_CSR[E\_SG] bits during channel execution. These bits are read from the TCD local memory at the end of channel execution, therefore allowing software to enable either feature during channel execution.

Because software can change the configuration during execution, a coherency sequence must be followed. Consider the scenario the user attempts to execute a dynamic channel link by enabling the TCDn\_CSR[MAJOR\_E\_LINK] bit as the eDMA engine retires the channel. The TCDn\_CSR[MAJOR\_E\_LINK] would be set in the programmer's model, but it would be indeterminate whether the actual link was made before the channel retired.

The following coherency sequence is recommended when executing a dynamic channel link or dynamic scatter/gather request:



- 1. Set the TCD*n*\_CSR[MAJOR\_E\_LINK] bit.
- 2. Read back the TCDn\_CSR[MAJOR\_E\_LINK] bit.
- 3. Test the TCD*n*\_CSR[MAJOR\_E\_LINK] request status.
  - a. If the bit is set, the dynamic link attempt was successful.
  - b. If the bit is cleared, the attempted dynamic link did not succeed, the channel was already retiring.

This coherency model is true for dynamic scatter/gather operations. For both dynamic requests, the TCD local memory controller forces the TCD*n*\_CSR[MAJOR\_E\_LINK] and TCD*n*\_CSR[E\_SG] bits to zero on any writes to a TCD*n* after the TCD*n*\_CSR[DONE] bit for that channel is set, indicating that the major loop is complete.

#### **Note**

Software must clear the TCD*n*\_CSR[DONE] bit before writing the TCD*n*\_CSR[MAJOR\_E\_LINK] or TCD*n*\_CSR[E\_SG] bits. The TCD*n*\_CSR[DONE] bit is cleared automatically by the eDMA engine after a channel begins execution.



mualization/application information



# **Chapter 22 External Watchdog Monitor (EWM)**

## 22.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The watchdog is generally used to monitor the flow and execution of embedded software within an MCU. The watchdog consists of a counter that if allowed to overflow, forces an internal reset (asynchronous) to all on-chip peripherals and optionally assert the RESET pin to reset external devices/circuits. The overflow of the watchdog counter must not occur if the software code works well and services the watchdog to re-start the actual counter.

For safety, a redundant watchdog system, External Watchdog Monitor (EWM), is designed to monitor external circuits, as well as the MCU software flow. This provides a back-up mechanism to the internal watchdog that resets the MCU's CPU and peripherals.

The EWM differs from the internal watchdog in that it does not reset the MCU's CPU and peripherals. The EWM if allowed to time-out, provides an independent EWM\_out pin that when asserted resets or places an external circuit into a safe mode. The CPU resets the EWM counter that is logically ANDed with an external digital input pin. This pin allows an external circuit to influence the reset\_out signal.

## 22.1.1 Features

Features of EWM module include:

- Independent LPO clock source
- Programmable time-out period specified in terms of number of EWM LPO clock cycles.



#### muroduction

- Windowed refresh option
  - Provides robust check that program flow is faster than expected.
  - Programmable window.
  - Refresh outside window leads to assertion of EWM\_out.
- Robust refresh mechanism
  - Write values of 0xB4 and 0x2C to EWM Refresh Register within 15 (EWM\_service\_time) peripheral bus clock cycles.
- One output port, <u>EWM\_out</u>, when asserted is used to reset or place the external circuit into safe mode.
- One Input port, EWM\_in, allows an external circuit to control the EWM\_out signal.

## 22.1.2 Modes of Operation

This section describes the module's operating modes.

## 22.1.2.1 Stop Mode

When the EWM is in stop mode, the CPU services to the EWM cannot occur. On entry to stop mode, the EWM's counter freezes.

There are two possible ways to exit from Stop mode:

- On exit from stop mode through a reset, the EWM remains disabled.
- On exit from stop mode by an interrupt, the EWM is re-enabled, and the counter continues to be clocked from the same value prior to entry to stop mode.

Note the following if the EWM enters the stop mode during CPU service mechanism: At the exit from stop mode by an interrupt, refresh mechanism state machine starts from the previous state which means, if first service command is written correctly and EWM enters the stop mode immediately, the next command has to be written within the next 15 (EWM\_service\_time) peripheral bus clocks after exiting from stop mode. User must mask all interrupts prior to executing EWM service instructions.



#### 22.1.2.2 Wait Mode

The EWM module treats the stop and wait modes as the same. EWM functionality remains the same in both of these modes.


## 22.1.2.3 **Debug Mode**

Entry to debug mode has no effect on the EWM.

- If the EWM is enabled prior to entry of debug mode, it remains enabled.
- If the EWM is disabled prior to entry of debug mode, it remains disabled.

# 22.1.3 Block Diagram

This figure shows the EWM block diagram.



<sup>&</sup>lt;sup>1</sup>Compare High > Counter > Compare Low

Figure 22-1. EWM Block Diagram

# 22.2 EWM Signal Descriptions

The EWM has two external signals, as shown in the following table.

**Table 22-1. EWM Signal Descriptions** 

Signal	Description	I/O
EWM_in	EWM input for safety status of external safety circuits. The polarity of EWM_in is programmable using the CTRL[ASSIN] bit. The default polarity is active-low.	I
EWM_out	EWM reset out signal	0

# 22.3 Memory Map/Register Definition

This section contains the module memory map and registers.

#### **EWM** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_1000	Control Register (EWM_CTRL)	8	R/W	00h	22.3.1/498
4006_1001	Service Register (EWM_SERV)	8	W (always reads zero)	00h	22.3.2/499
4006_1002	Compare Low Register (EWM_CMPL)	8	R/W	00h	22.3.3/500
4006_1003	Compare High Register (EWM_CMPH)	8	R/W	FFh	22.3.4/500

# 22.3.1 Control Register (EWM\_CTRL)

The CTRL register is cleared by any reset.

#### NOTE

This register can be written only once after a CPU reset. Writing this register more than once, generates a bus transfer error.



Address: EWM\_CTRL is 4006\_1000h base + 0h offset = 4006\_1000h




## **EWM\_CTRL** field descriptions

Field	Description
7–3 Reserved	This read-only field is reserved and always has the value zero.
2 INEN	Input Enable.  This bit when set, enables the EWM_in port.
1 ASSIN	EWM_in's Assertion State Select.  Default assert state of the EWM_in signal is logic zero. Setting ASSIN bit inverts the assert state to a logic one.
0 EWMEN	EWM enable.  This bit when set, enables the EWM module. This resets the EWM counter to zero and deasserts the EWM_out signal. Clearing EWMEN bit disables the EWM, and therefore it cannot be enabled until a reset occurs, due to the write-once nature of this bit.

# 22.3.2 Service Register (EWM\_SERV)

The SERV register provides the interface from the CPU to the EWM module. It is write-only and reads of this register return zero.

Address: EWM\_SERV is 4006\_1000h base + 1h offset = 4006\_1001h



## **EWM\_SERV** field descriptions

Field	Description
7–0 SERVICE	The EWM service mechanism requires the CPU to write two values to the SERV register: a first data byte of 0xB4, followed by a second data byte of 0x2C. The EWM service is illegal if either of the following conditions is true.  • The first or second data byte is not written correctly.  • The second data byte is not written within a fixed number of peripheral bus cycles of the first data byte. This fixed number of cycles is called <i>EWM_service_time</i> .





## 22.3.3 Compare Low Register (EWM\_CMPL)

The CMPL register is reset to zero after a CPU reset. This provides no minimum time for the CPU to service the EWM counter.

#### NOTE

This register can be written only once after a CPU reset. Writing this register more than once generates a bus transfer error.





#### **EWM\_CMPL** field descriptions

Field	Description
7–0 COMPAREL	To prevent runaway code from changing this field, software should write to this field after a CPU reset even if the (default) minimum service time is required.

## 22.3.4 Compare High Register (EWM\_CMPH)

The CMPH register is reset to 0xFF after a CPU reset. This provides a maximum of 256 clocks time, for the CPU to service the EWM counter.


#### NOTE

This register can be written only once after a CPU reset. Writing this register more than once generates a bus transfer error.

#### NOTE

The valid values for CMPH are up to 0xFE because the EWM counter never expires when CMPH = 0xFF. The expiration happens only if EWM counter is greater than CMPH.

Address: EWM\_CMPH is 4006\_1000h base + 3h offset = 4006\_1003h



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### **EWM\_CMPH** field descriptions

Field	Description
	To prevent runaway code from changing this field, software should write to this field after a CPU reset even if the (default) maximum service time is required.

# 22.4 Functional Description

The following sections describe functional details of the EWM module.

# 22.4.1 The EWM\_out Signal

The EWM\_out is a digital output signal used to gate an external circuit (application specific) that controls critical safety functions. For example, the EWM\_out could be connected to the high voltage transistors circuits that control an AC motor in a large appliance.

The EWM\_out signal remains deasserted when the EWM is being regularly serviced by the CPU within the programmable service window, indicating that the application code is executed as expected.

The EWM\_out signal is asserted in any of the following conditions:

- Servicing the EWM when the counter value is less than CMPL value.
- If the EWM counter value reaches the CMPH value, and no EWM service has occurred.
- Servicing the EWM when the counter value is more than CMPL and less than CMPH values and EWM\_in signal is asserted.
- After any reset (by the virtue of the external pull-down mechanism on the EWM\_out pin)

On a normal reset, the  $\overline{EWM}$ \_out is asserted. To deassert the  $\overline{EWM}$ \_out, set EWMEN bit in the CTRL register to enable the EWM.

If the EWM\_out signal shares its pad with a digital I/O pin, on reset this actual pad defers to being an input signal. It takes the EWM\_out output condition only after you enable the EWM by the EWMEN bit in the CTRL register.

When the EWM\_out pin is asserted, it can only be deasserted by forcing a MCU reset.



#### **Note**

EWM\_out pad must be in pull down state when EWM functionality is used and when EWM is under Reset.

## 22.4.2 The EWM\_in Signal

The EWM\_in is a digital input signal that allows an external circuit to control the EWM\_out signal. For example, in the application, an external circuit monitors a critical safety function, and if there is fault with this circuit's behavior, it can then actively initiate the EWM\_out signal that controls the gating circuit.

The EWM\_in signal is ignored if the EWM is disabled, or if INEN bit of CTRL register is cleared, as after any reset.

On enabling the EWM (setting the CTRL[EWMEN] bit) and enabling EWM\_in functionality (setting the CTRL[INEN] bit), the EWM\_in signal must be in the deasserted state prior to the CPU servicing the EWM. This ensures that the EWM\_out stays in the deasserted state; otherwise, the EWM\_out pin is asserted.

#### Note

You must update the CMPH and CMPL registers prior to enabling the EWM. After enabling the EWM, the counter resets to zero, therefore providing a reasonable time after a power-on reset for the external monitoring circuit to stabilize and ensure that the EWM\_in pin is deasserted.

## 22.4.3 EWM Counter

It is an 8-bit ripple counter fed from a clock source that is independent of the peripheral bus clock source. As the preferred time-out is between 1 ms and 100 ms the actual clock source should be in the kHz range.

The counter is reset to zero, after a CPU reset, or a EWM refresh cycle. The counter value is not accessible to the CPU.

## 22.4.4 EWM Compare Registers

The compare registers CMPL and CMPH are write-once after a CPU reset and cannot be modified until another CPU reset occurs.



The EWM compare registers are used to create a service window, which is used by the CPU to service/refresh the EWM module.

- If the CPU services the EWM when the counter value lies between CMPL value and CMPH value, the counter is reset to zero. This is a legal service operation.
- If the CPU executes a EWM service/refresh action outside the legal service window, EWM\_out is asserted.

It is illegal to program CMPL and CMPH with same value. In this case, as soon as counter reaches (CMPL + 1), EWM\_out is asserted.

## 22.4.5 EWM Refresh Mechanism

Other than the initial configuration of the EWM, the CPU can only access the EWM by the EWM Service Register. The CPU must access the EWM service register with correct write of unique data within the windowed time frame as determined by the CMPL and CMPH registers. Therefore, three possible conditions can occur:

Table 22-7. EWM Refresh Mechanisms

Condition	Mechanism
A unique EWM service occurs when CMPL < Counter < CMPH.	The software behaves as expected and the counter of the EWM is reset to zero, and EWM_out pin remains in the deasserted state.
	Note: EWM_in pin is also assumed to be in the deasserted state.
A unique EWM service occurs when Counter < CMPL	The software services the EWM and therefore resets the counter to zero and asserts the EWM_out pin (irrespective of the EWM_in pin). The EWM_out pin is expected to gate critical safety circuits.
Counter value reaches CMPH prior to a unique EWM service	The counter value reaches the CMPH value and no service of the EWM resets the counter to zero and assert the EWM_out pin (irrespective of the EWM_in pin). The EWM_out pin is expected to gate critical safety circuits.

Any illegal service on EWM has no effect on EWM\_out.



**runctional Description** 



# **Chapter 23 Watchdog Timer (WDOG)**

#### 23.1 Introduction

#### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The Watchdog Timer (WDOG) keeps a watch on the system functioning and resets it in case of its failure. Some reasons for such failures are: run-away software code and the stoppage of the system clock that in a safety critical system can lead to serious consequences. In such cases, the watchdog brings the system into a safe state of operation. The watchdog monitors the operation of the system by expecting periodic communication from the software, generally known as servicing or refreshing the watchdog. If this periodic refreshing does not occur, the watchdog resets the system.

## 23.2 Features

The features of the Watchdog Timer (WDOG) include:

- Independent clock source input (independent from CPU/bus clock). Choice between two clock sources:
  - LPO Oscillator
  - External system clock
- Unlock sequence for allowing updates to write-once WDOG control/configuration bits.
- All WDOG control/configuration bits are writable once only within 256 bus clock cycles of being unlocked.



#### reautres

- You need to always update these bits after unlocking within 256 bus clock cycles. Failure to update these bits, resets the system.
- Programmable time-out period specified in terms of number of WDOG clock cycles.
- Ability to test WDOG timer and reset with a flag indicating watchdog test.
  - Quick test—Small time-out value programmed for quick test.
  - Byte test—Individual bytes of timer tested one at a time.
  - Read-only access to the WDOG timer—Allows dynamic check that WDOG timer is operational.

#### NOTE

Reading the watchdog timer counter while running the watchdog on the bus clock might not give the accurate counter value.

- Windowed refresh option
  - Provides robust check that program flow is faster than expected.
  - Programmable window.
  - Refresh outside window leads to reset.
- Robust refresh mechanism
  - Write values of 0xA602 and 0xB480 to WDOG Refresh Register within 20 bus clock cycles.
- Count of WDOG resets as they occur.
- Configurable interrupt on time-out to provide debug breadcrumbs. This is followed by a reset after 256 bus clock cycles.



#### 23.3 Functional Overview




Figure 23-1. WDOG Operation

The preceding figure shows the operation of the watchdog. The values for N and K are:

- N = 256
- K = 20

The watchdog is a fail safe mechanism that brings the system into a known initial state in case of its failure due to CPU clock stopping or a run away condition in code execution. In its simplest form, the watchdog timer runs continuously off a clock source and expects



#### **runctional Overview**

to be serviced periodically, failing which it resets the system. This ensures that the software is executing correctly and has not run away in an unintended direction. Software can adjust the period of servicing or the time-out value for the watchdog timer to meet the needs of the application.

You can select a windowed mode of operation that expects the servicing to be done only in a particular window of the time-out period. An attempted servicing of the watchdog outside this window results in a reset. By operating in this mode, you can get an indication of whether the code is running faster than expected. The window length is also user programmable.

If a system fails to update/refresh the watchdog due to an unknown and persistent cause, it will be caught in an endless cycle of resets from the watchdog. To analyze the cause of such conditions, you can program the watchdog to first issue an interrupt, followed a little later by a reset. In the interrupt service routine, the software can analyze the system stack to aid debugging.

To enhance the independence of watchdog from the system, it runs off an independent LPO oscillator clock. You can also switch over to an alternate clock source if required, through a control register bit.

## 23.3.1 Unlocking and Updating the Watchdog

You can unlock the write-once-only control and configuration registers for updating them. As a pre-condition, the ALLOW\_UPDATE bit in the watchdog control register must be set. The actual unlock is accomplished by writing 0xC520 followed by 0xD928 within 20 bus clock cycles to a specific unlock register (WDOG\_UNLOCK). This opens up an update window equal in length to the watchdog configuration time (WCT) within which you can update the configuration and control register bits. You can not update registers on the bus clock cycle immediately following the write of the unlock sequence, but one cycle later. These register bits can be modified only once after unlocking.

If none of the configuration and control registers is updated within the update window, the watchdog issues a reset (or interrupt-then-reset) to the system. Trying to unlock the watchdog within the WCT time after an initial unlock, has no effect. During the update operation, the watchdog timer is not paused and keeps running in the background. After the update window closes, the watchdog timer restarts and the watchdog functions as per the new configuration.



The update feature is useful for applications that have an initial, non-safety critical part, where the watchdog is kept disabled or with a conveniently long time-out period. This means the application coder does not have to bother with frequently servicing the watchdog. After the critical part of the application begins, the watchdog can be reconfigured as per need.

The watchdog issues a reset (or interrupt-then-reset if enabled) to the system for any of these invalid unlock sequences:

- You write any value other than 0xC520 or 0xD928 to the unlock register.
- ALLOW\_UPDATE is set and you allow a gap of more than 20 bus clock cycles between the writing of the unlock sequence values.

Also, an attempted refresh operation between the two writes of the unlock sequence and in the WCT time following a successful unlock, goes undetected. Also, see Watchdog Operation with 8-bit access for guidelines related to 8-bit accesses to the unlock register.

#### **Note**

A context switch during unlocking and refreshing may lead to a watchdog reset.

## 23.3.2 The Watchdog Configuration Time (WCT)

To prevent unintended modification of the watchdog's control and configuration register bits, you are allowed to update them only within a period of 256 bus clock cycles after unlocking. This window period is known as the watchdog configuration time (WCT). In addition, these register bits can be modified only once after unlocking them for editing (even after reset).

You must unlock the registers within WCT time after system reset, failing which the WDOG issues a reset to the system. To be more precise, you must write at least the first word of the unlocking sequence within the WCT time after reset. Once this is done, you get a further 20 bus clock cycles (the maximum allowed gap between the words of the unlock sequence) to complete the unlocking operation. Thereafter, to make sure that you do not forget to configure the watchdog, the watchdog issues a reset if none of the WDOG control and configuration registers is updated in the WCT time after unlock. After the close of this window or after the first write, these register bits are locked out from any further changes.

The watchdog timer keeps running as per its default configuration through unlocking and update operations that can extend up to a maximum total of 2xWCT time + 20 bus clock cycles. Therefore, it must be ensured that the time-out value for the watchdog is always greater than 2xWCT time + 20 bus clock cycles.



#### **runctional Overview**

Updates in the write—once registers take effect only after the WCT window closes with the following exceptions for which changes take effect immediately:

- the stop, wait, and debug mode enable bits
- the standby mode enable bit
- the IRQ\_RST\_EN bit

The operations of refreshing the watchdog goes undetected during the WCT.

## 23.3.3 Refreshing the Watchdog

A robust refreshing mechanism has been chosen for the watchdog. A valid refresh is a write of 0xA602 followed by 0xB480 within 20 bus clock cycles to watchdog refresh register. If these two values are written more than 20 bus cycles apart or if something other than these two values is written to the register, a watchdog reset (or interrupt-then-reset if enabled) is issued to the system. A valid refresh makes the watchdog timer restart on the next bus clock. Also, an attempted unlock operation, in between the two writes of the refresh sequence goes undetected. See Watchdog Operation with 8-bit access for guidelines related to 8-bit accesses to the refresh register.

## 23.3.4 Windowed Mode of Operation

In this mode of operation a restriction is placed on the point in time within the time-out period at which the watchdog can be refreshed. The refresh is considered valid only when the watchdog timer increments beyond a certain count as specified by the watchdog window register. This is known as refreshing the watchdog within a window of the total time-out period. If a refresh is attempted before the timer reaches the window value, the watchdog generates a reset (or interrupt-then-reset if enabled). Of course, if there is no refresh at all, the watchdog times out and generates a reset or interrupt-then-reset if enabled.

## 23.3.5 Watchdog Disabled Mode of Operation

When the watchdog is disabled through the WDOG\_EN bit in the watchdog status and control register, the watchdog timer is reset to zero and is disabled from counting until you enable it or it is again enabled by the system reset. In this mode the watchdog timer cannot be refreshed (there is no requirement to do so while the timer is disabled). However, the watchdog still generates a reset (or interrupt-then-reset if enabled) on a



non-time-out exception (see Generated Resets and Interrupts). You need to unlock the watchdog before enabling it. A system reset brings the watchdog out of the disabled mode.

## 23.3.6 Low Power Modes of Operation

- In Wait mode, if the WDOG is enabled (WAIT\_EN = 1), it can run on bus clock or low power oscillator clock (CLK\_SRC = x) to generate interrupt (IRQ\_RST\_EN=1) followed by a reset on time-out. After reset the WDOG reset counter increments by one.
- In Stop mode where the bus clock is gated, the WDOG can run only on low power oscillator clock (CLK\_SRC=0) if it is enabled in stop (STOP\_EN=1). In this case, the WDOG runs to time-out twice, and then generates a reset from its backup circuitry. Therefore, if you program the watchdog to time-out after 100 ms and then enter such a stop mode, the reset will occur after 200 ms. Also, in this case no interrupt will be generated irrespective of the value of IRQ\_RST\_EN bit. After WDOG reset, the WDOG reset counter will also not increment.
- In Power-down mode, the watchdog is powered off.

## 23.3.7 Debug Modes of Operation

You can program the watchdog to disable in debug modes (through DBG\_EN bit in the watchdog control register). This results in the watchdog timer pausing for the duration of the mode. Register read/writes are still allowed, which means that operations like: refresh, unlock etc. are allowed. On exit from the mode, the timer resumes its operation from the point of pausing.

The entry of the system into the debug mode does not excuse it from compulsorily configuring the watchdog in the WCT time after unlock (unless the system bus clock is gated off, in which case the internal state machine pauses too). Failing to do so still results in a reset (or interrupt-then-reset, if enabled) to the system. Also, all the exception conditions that result in a reset to the system (see Generated Resets and Interrupts) are still valid in this mode. So, if an exception condition occurs and the system bus clock is on, a reset occurs (or interrupt-then-reset, if enabled).



#### resung the Watchdog

The entry into Debug mode within WCT time after reset is treated differently. The WDOG timer is kept reset to zero and there is no need to unlock and configure it within WCT time. You must not try to refresh or unlock the WDOG in this state or unknown behavior may result. Upon exit from this mode, the WDOG timer restarts and the WDOG has to be unlocked and configured within WCT time.

## 23.4 Testing the Watchdog

For IEC 60730 and other safety standards, the expectation is that anything that monitors a safety function must be tested and this test is required to be fault tolerant. To test the watchdog, its main timer and its associated compare and reset logic must be tested. Towards this end, two tests are implemented for the watchdog that are described in Quick Test and Byte Test. While there is a control bit provided to put the watchdog into the test mode (functional), there is an overriding test-disable control bit which once set, disables the test mode permanently until reset.

For running a particular test, first select that test. Thereafter, set a certain test mode bit to put the watchdog in the functional test mode. Setting this bit automatically switches the watchdog timer to a fast clock source. The switching of the clock source is done to achieve a faster time-out and hence a faster test. In a successful test, the timer times out after reaching the programmed time-out value and generates a system reset.

#### Note

After emerging from a reset due to a watchdog test, you must follow the mandatory steps of unlocking and configuring the watchdog. The refresh and unlock operations and interrupt are not automatically disabled in the test mode.

#### 23.4.1 Quick Test

In this test the time-out value of watchdog timer is programmed to a very low value to achieve quick time-out. The only difference between the quick test and the normal mode of functioning of the watchdog is that the test mode bit is set for the quick test. This allows quick test of the watchdog reset mechanism.



## **23.4.2** Byte Test

The byte test implements more thorough a test of the watchdog timer. In this test, the timer is split up into its constituent byte-wide stages that are run independently and tested for time-out against the corresponding byte of the time-out value register. The following figure explains the splitting concept:




Figure 23-2. Watchdog Timer Byte Splitting

Each stage is an 8-bit synchronous counter followed by combinational logic that generates an overflow signal. The overflow signal acts as an enable to the N + 1th stage.

In the test mode, when an individual byte, N, is tested, byte N-1 is loaded forcefully with 0xFF, and both these bytes are allowed to run off the clock source. By doing so the overflow signal from stage N-1 is generated immediately, enabling counter stage N. The Nth stage runs and compares with the Nth byte of the time-out value register. In this way, the byte N is also tested along with the link between it and the preceding stage. No other stages, N-2, N-3... and N+1, N+2... are enabled for the test on byte N. These disabled stages (except the most significant stage of the counter) are loaded with a value of 0xFF.

These two testing schemes achieve the overall aim of testing the counter functioning and the compare and reset logic.



#### **Note**

Do not enable the watchdog interrupt during these tests. If required, you must ensure that the effective time-out value is greater than WCT time. See Generated Resets and Interrupts for more details.

## 23.5 Backup Reset Generator

The backup reset generator generates the final reset which goes out to the system. It has a backup mechanism which takes care that in case the bus clock stops and prevents the main state machine from generating a reset exception/interrupt, the watchdog timer's time-out is separately routed out as a reset to the system. Two successive timer time-outs without an intervening system reset result in the backup reset generator routing out the time-out signal as a reset to the system.

## 23.6 Generated Resets and Interrupts

The watchdog generates a reset on the following events (referred to as exceptions at some places in this document):

- A watchdog time-out.
- Failure to unlock the watchdog within WCT time after system reset deassertion.
- No update of the control and configuration registers within the WCT window after unlocking. At least one of the following registers must be written to within the WCT window to avoid reset:
  - WDOG\_ST\_CTRL\_H, WDOG\_ST\_CTRL\_L
  - WDOG\_TO\_VAL\_H, WDOG\_TO\_VAL\_L
  - WDOG\_WIN\_H, WDOG\_WIN\_L
  - WDOG\_PRESCALER
- A value other than the unlock sequence or the refresh sequence is written to the unlock and/or refresh registers, respectively.



- A gap of more than 20 bus cycles exists between the writes of two values of the unlock sequence.
- A gap of more than 20 bus cycles exists between the writes of two values of the refresh sequence.

The watchdog can also generate an interrupt. If IRQ\_RST\_EN is set, then on the above mentioned events WDOG\_ST\_CTRL\_L[INT\_FLG] is set, generating an interrupt. A watchdog reset is also generated WCT time later to ensure the watchdog is fault tolerant. The interrupt can be cleared by writing 1 to INT\_FLG.

The gap of WCT time between interrupt and reset means that the WDOG time-out value must be greater than WCT. Otherwise, if the interrupt was generated due to a time-out, a second consecutive time-out will occur in that WCT gap. This will trigger the backup reset generator to generate a reset to the system, prematurely ending the interrupt service routine execution. Also, the jobs like counting the number of watchdog resets would not be done.

## 23.7 Memory Map and Register Definition

This section consists of the memory map and register descriptions.

#### WDOG memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4005_2000	Watchdog Status and Control Register High (WDOG_STCTRLH)	16	R/W	01D3h	23.7.1/ 516
4005_2002	Watchdog Status and Control Register Low (WDOG_STCTRLL)	16	R/W	0001h	23.7.2/ 518
4005_2004	Watchdog Time-out Value Register High (WDOG_TOVALH)	16	R/W	004Ch	23.7.3/ 518
4005_2006	Watchdog Time-out Value Register Low (WDOG_TOVALL)	16	R/W	4B4Ch	23.7.4/ 519
4005_2008	Watchdog Window Register High (WDOG_WINH)	16	R/W	0000h	23.7.5/ 519
4005_200A	Watchdog Window Register Low (WDOG_WINL)	16	R/W	0010h	23.7.6/ 520
4005_200C	Watchdog Refresh Register (WDOG_REFRESH)	16	R/W	B480h	23.7.7/ 520




## WDOG memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4005_200E	Watchdog Unlock Register (WDOG_UNLOCK)	16	R/W	D928h	23.7.8/ 520
4005_2010	Watchdog Timer Output Register High (WDOG_TMROUTH)	16	R/W	0000h	23.7.9/ 521
4005_2012	Watchdog Timer Output Register Low (WDOG_TMROUTL)	16	R/W	0000h	23.7.10/ 521
4005_2014	Watchdog Reset Count Register (WDOG_RSTCNT)	16	R/W	0000h	23.7.11/ 522
4005_2016	Watchdog Prescaler Register (WDOG_PRESC)	16	R/W	0400h	23.7.12/ 522

## 23.7.1 Watchdog Status and Control Register High (WDOG\_STCTRLH)

Address: WDOG\_STCTRLH is 4005\_2000h base + 0h offset = 4005\_2000h



#### WDOG\_STCTRLH field descriptions

Field	Description
15 Reserved	This read-only field is reserved and always has the value zero.
14 DISTESTWDOG	Allows the WDOG's functional test mode to be disabled permanently. Once set, it can only be cleared by a reset. It cannot be unlocked for editing once it is set.
	0 WDOG functional test mode is not disabled.
	1 WDOG functional test mode is disabled permanently until reset.
13–12 BYTESEL[1:0]	This 2-bit field select the byte to be tested when the watchdog is in the byte test mode.
2 2 [ ]	00 Byte 0 selected
	01 Byte 1 selected
	10 Byte 2 selected
	11 Byte 3 selected
11 TESTSEL	Selects the test to be run on the watchdog timer. Effective only if TESTWDOG is set.



## WDOG\_STCTRLH field descriptions (continued)

Field	Description
i leiu	O Quick test. The timer runs in normal operation. You can load a small time-out value to do a quick test.
	Byte test. Puts the timer in the byte test mode where individual bytes of the timer are enabled for operation and are compared for time-out against the corresponding byte of the programmed time-out value. Select the byte through BYTESEL[1:0] for testing.
10 TESTWDOG	Puts the watchdog in the functional test mode. In this mode the watchdog timer and the associated compare and reset generation logic is tested for correct operation. The clock for the timer is switched from the main watchdog clock to the fast clock input for watchdog functional test. The TESTSEL bit selects the test to be run.
9 Reserved	This read-only field is reserved and always has the value zero.
8 STNDBYEN	Enables or disables WDOG in Standby mode.
	<ul><li>0 WDOG is disabled in system Standby mode.</li><li>1 WDOG is enabled in system Standby mode.</li></ul>
7	Enables or disables WDOG in wait mode.
WAITEN	0 WDOG is disabled in CPU wait mode. 1 WDOG is enabled in CPU wait mode.
6	Enables or disables WDOG in stop mode.
STOPEN	0 WDOG is disabled in CPU stop mode.
E	1 WDOG is enabled in CPU stop mode.
5 DBGEN	Enables or disables WDOG in Debug mode.  0 WDOG is disabled in CPU Debug mode.
	1 WDOG is enabled in CPU Debug mode.
4 ALLOWUPDATE	Enables updates to watchdog write once registers, after initial configuration window (WCT) closes, through unlock sequence.
	<ul> <li>No further updates allowed to WDOG write once registers.</li> <li>WDOG write once registers can be unlocked for updating.</li> </ul>
3 WINEN	Enable windowing mode.
VVIIV⊏IV	<ul><li>0 Windowing mode is disabled.</li><li>1 Windowing mode is enabled.</li></ul>
2 IRQRSTEN	Used to enable the debug breadcrumbs feature. A change in this bit is updated immediately, as opposed to updating after WCT.
	<ul> <li>WDOG time-out generates reset only.</li> <li>WDOG time-out initially generates an interrupt. After WCT time, it generates a reset.</li> </ul>
1	Selects clock source for the WDOG timer and other internal timing operations.
CLKSRC	Dedicated clock source selected as WDOG clock (LPO Oscillator).
	1 WDOG clock sourced from alternate clock source.
0 WDOGEN	Enables or disables the WDOG's operation. In the disabled state, the watchdog timer is kept in the reset state, but the other exception conditions can still trigger a reset/interrupt. A change in the value of this bit must be held for more than one WDOG_CLK cycle for the WDOG to be enabled or disabled.




#### wemory Map and Register Definition

#### WDOG\_STCTRLH field descriptions (continued)

Field	Description
	0 WDOG is disabled.
	1 WDOG is enabled.

## 23.7.2 Watchdog Status and Control Register Low (WDOG\_STCTRLL)

Address: WDOG\_STCTRLL is 4005\_2000h base + 2h offset = 4005\_2002h




#### WDOG\_STCTRLL field descriptions

Field	Description
15 INTFLG	Interrupt flag. It is set when an exception occurs. IRQRSTEN = 1 is a precondition to set this flag. INTFLG = 1 results in an interrupt being issued followed by a reset, WCT time later. The interrupt can be cleared by writing 1 to this bit. It also gets cleared on a system reset.
14–0 Reserved	This field is reserved.
	NOTE: Do not modify this bitfield value.

## 23.7.3 Watchdog Time-out Value Register High (WDOG\_TOVALH)

Address: WDOG\_TOVALH is 4005\_2000h base + 4h offset = 4005\_2004h



#### WDOG\_TOVALH field descriptions


Field	Description
	Defines the upper 16 bits of the 32-bit time-out value for the watchdog timer. It is defined in terms of cycles of the watchdog clock.



## 23.7.4 Watchdog Time-out Value Register Low (WDOG\_TOVALL)

The time-out value of the watchdog must be set to a minimum of four watchdog clock cycles. This is to take into account the delay in new settings taking effect in the watchdog clock domain.





#### WDOG\_TOVALL field descriptions

Field	Description
15–0 TOVALLOW	Defines the lower 16 bits of the 32-bit time-out value for the watchdog timer. It is defined in terms of cycles of the watchdog clock.

## 23.7.5 Watchdog Window Register High (WDOG\_WINH)

You must set the Window Register value lower than the Time-out Value Register.

Address: WDOG\_WINH is 4005\_2000h base + 8h offset = 4005\_2008h



#### WDOG\_WINH field descriptions


Field	Description
15–0 WINHIGH	Defines the upper 16 bits of the 32-bit window for the windowed mode of operation of the watchdog. It is defined in terms of cycles of the watchdog clock. In this mode the watchdog can be refreshed only when the timer has reached a value greater than or equal to this window length. A refresh outside this window resets the system or if IRQRSTEN is set, it interrupts and then resets the system.



## 23.7.6 Watchdog Window Register Low (WDOG\_WINL)

You must set the Window Register value lower than the Time-out Value Register.

Address: WDOG\_WINL is 4005\_2000h base + Ah offset = 4005\_200Ah



#### WDOG\_WINL field descriptions

Field	Description
	Defines the lower 16 bits of the 32-bit window for the windowed mode of operation of the watchdog. It is defined in terms of cycles of the pre-scaled watchdog clock. In this mode, the watchdog can be refreshed only when the timer reaches a value greater than or equal to this window length value. A refresh outside this window resets the system or if IRQRSTEN is set, it interrupts and then resets the system.

## 23.7.7 Watchdog Refresh Register (WDOG\_REFRESH)

Address: WDOG\_REFRESH is 4005\_2000h base + Ch offset = 4005\_200Ch




#### WDOG\_REFRESH field descriptions

Field	Description
15–0 WDOGREFRES H	Watchdog refresh register. A sequence of 0xA602 followed by 0xB480 within 20 bus clock cycles when written to this register, refreshes the WDOG and prevents it from resetting the system. Writing a value other than the above mentioned sequence or if the sequence is longer than 20 bus cycles, resets the system or if IRQRSTEN is set, it interrupts and then resets the system).

## 23.7.8 Watchdog Unlock Register (WDOG\_UNLOCK)

Address: WDOG\_UNLOCK is 4005\_2000h base + Eh offset = 4005\_200Eh






#### WDOG\_UNLOCK field descriptions

Field	Description
15–0 WDOGUNLOCK	You can write the unlock sequence values to this register to make the watchdog write once registers writable again. The required unlock sequence is 0xC520 followed by 0xD928 within 20 bus clock cycles. A valid unlock sequence opens up a window equal in length to the WCT within which you can update the registers. Writing a value other than the above mentioned sequence or if the sequence is longer than 20 bus cycles, resets the system or if IRQRSTEN is set, it interrupts and then resets the system). The unlock sequence is effective only if ALLOWUPDATE is set.

## 23.7.9 Watchdog Timer Output Register High (WDOG\_TMROUTH)

Address: WDOG\_TMROUTH is 4005\_2000h base + 10h offset = 4005\_2010h




#### WDOG\_TMROUTH field descriptions

Field	Description
15–0	Shows the value of the upper 16 bits of the watchdog timer.
TIMEROUTHIGH	

## 23.7.10 Watchdog Timer Output Register Low (WDOG\_TMROUTL)

During stop mode, the WDOG\_TIMER\_OUT will be caught at the pre-stop value of the watchdog timer. After exiting stop mode, a maximum delay of 1 WDOG\_CLK cycle + 3 bus clock cycles will occur before the WDOG\_TIMER\_OUT starts following the watchdog timer.

Address: WDOG\_TMROUTL is 4005\_2000h base + 12h offset = 4005\_2012h




#### WDOG\_TMROUTL field descriptions

Field	Description
15–0 TIMEROUTLOW	Shows the value of the lower 16 bits of the watchdog timer.



## 23.7.11 Watchdog Reset Count Register (WDOG\_RSTCNT)

Address: WDOG\_RSTCNT is 4005\_2000h base + 14h offset = 4005\_2014h




#### WDOG\_RSTCNT field descriptions

Field	Description
15–0 RSTCNT	Counts the number of times the watchdog resets the system. This register is reset only on a POR. Writing 1 to the bit to be cleared, enables you to clear the contents of this register.

## 23.7.12 Watchdog Prescaler Register (WDOG\_PRESC)

Address: WDOG\_PRESC is 4005\_2000h base + 16h offset = 4005\_2016h



#### WDOG\_PRESC field descriptions

Field	Description
15–11 Reserved	This read-only field is reserved and always has the value zero.
10–8 PRESCVAL	3-bit prescaler for the watchdog clock source. A value of zero indicates no division of the input WDOG clock. The watchdog clock is divided by (PRESCVAL + 1) to provide the prescaled WDOG_CLK.
7–0 Reserved	This read-only field is reserved and always has the value zero.

## 23.8 Watchdog Operation with 8-bit access

This section discusses 8-bit access considerations.



#### 23.8.1 General Guideline

When performing 8-bit accesses to the watchdog's 16-bit registers where the intention is to access both the bytes of a register, you must try to place the two 8-bit accesses one after the other in your code.

## 23.8.2 Refresh and Unlock operations with 8-bit access

One exception condition that generates a reset to the system, is the write of any value other than those required for a legal refresh/update sequence to the respective refresh and unlock registers.

For an 8-bit access to these registers, writing a correct value requires at least two bus clock cycles that means there is an invalid value in the registers for one cycle. Therefore, the system is reset even if the intention is to write a correct value to the refresh/unlock register. Keeping this in mind the exception condition for 8-bit accesses is slightly modified. Whereas the match for a correct value for a refresh/unlock sequence is as per the original definition, the match for an incorrect value is done byte-wise on the refresh/unlock rather than for the whole 16-bit value. This means that if the high byte of the refresh/unlock register contains any value other than high bytes of the two values making up the sequence, it is treated as an exception condition, leading to a reset or interrupt-then-reset. The same holds true for the lower byte of the refresh or unlock register. Let us take the refresh operation that expects a write of 0xA602 followed by 0xB480 to the refresh register, as an example.

	WDOG_REFRESH[15:8]	WDOG_REFRESH[7:0]	Sequence value1 or value2 match	Mismatch exception
<b>Current Value</b>	0xB4	0x80	Value2 match	No
Write 1	0xB4	0x02	No match	No
Write 2	0xA6	0x02	Value1 match	No
Write 3	0xB4	0x02	No match	No
Write 4	0xB4	0x80	Value2 match. Sequence complete.	No
Write 5	0x02	0x80	No match	Yes

Table 23-14. Refresh for 8-bit Access

As shown in the preceding table, the refresh register holds its reset value initially. Thereafter, two 8-bit accesses are performed on the register to write the first value of the refresh sequence. No mismatch exception is registered on the intermediate write, Write1. The sequence is completed by performing two more 8-bit accesses, writing in the second value of the sequence for a successful refresh. It must be noted that the match of value2



#### nestrictions on Watchdog Operation

takes place only when the complete 16-bit value is correctly written, write4. Hence, the requirement of writing value2 of the sequence within 20 bus clock cycles of value1 is checked by measuring the gap between write2 and write4.

It is reiterated that the condition for matching values 1 and 2 of the refresh or unlock sequence remains unchanged. It is just the criterion for detecting a wrong value in these registers which has been relaxed, as explained, for 8-bit accesses. Any 16-bit access still needs to adhere to the original guidelines, mentioned in the sections Refreshing the Watchdog.

## 23.9 Restrictions on Watchdog Operation

This section mentions some exceptions to the watchdog operation that may not be apparent to you.

- Restriction on unlock / refresh operations—In the period between the closure of the WCT window (after unlock) and the actual reload of the watchdog timer, unlock and refresh operations need not be attempted.
- The update and reload of the watchdog timer happens two to three watchdog clocks after WCT window closes, following a successful configuration on unlock.
- Clock Switching Delay—The watchdog uses glitch free multiplexers at two places one to choose between the LPO oscillator input and alternate clock input and the other to choose between the watchdog functional clock and fast clock input for watchdog functional test. A maximum time period of ~ 2 clock A cycles plus ~2 clock B cycles elapses from the time a switch is requested to the occurrence of the actual clock switch (clock A and B are the two input clocks to the clock mux).
- For the windowed mode, there is a two to three bus clock latency between the watchdog counter going past the window value and the same registering in the bus clock domain.
- For proper operation of the watchdog, the watchdog clock must be at least five times slower than the system bus clock at all times. An exception is the case when the watchdog clock is synchronous to the bus clock wherein the watchdog clock can be as fast as the bus clock.
- WCT must be equivalent to at least three watchdog clock cycles. If not ensured, this means that even after the close of the WCT window, you have to wait for the synchronized system reset to deassert in the watchdog clock domain, before expecting the configuration updates to take effect.



- The time-out value of the watchdog should be set to a minimum of four watchdog clock cycles. This is to take into account the delay in new settings taking effect in the watchdog clock domain.
- You must take care not only to refresh the watchdog within the watchdog timer's actual time-out period, but also provide enough allowance for the time it takes for the refresh sequence to be detected by the watchdog timer, on the watchdog clock.
- Updates cannot be made in the bus clock cycle immediately following the write of the unlock sequence, but one bus clock cycle later.
- It should be ensured that the time-out value for the watchdog is always greater than 2xWCT time + 20 bus clock cycles.
- An attempted refresh operation, in between the two writes of the unlock sequence and in the WCT time following a successful unlock, will go undetected.
- Trying to unlock the watchdog within the WCT time after an initial unlock has no effect.
- The refresh and unlock operations and interrupt are not automatically disabled in the watchdog functional test mode.
- After emerging from a reset due to a watchdog functional test, you are still expected to go through the mandatory steps of unlocking and configuring the watchdog. The watchdog continues to be in its functional test mode and therefore you should pull the watchdog out of the functional test mode within WCT time of reset.
- After emerging from a reset due to a watchdog functional test, you still need to go through the mandatory steps of unlocking and configuring the watchdog.
- You must ensure that both the clock inputs to the glitchless clock multiplexers are alive during the switching of clocks. Failure to do so results in a loss of clock at their outputs.
- There is a gap of two to three watchdog clock cycles from the point that stop mode is entered to the watchdog timer actually pausing, due to synchronization. The same holds true for an exit from the stop mode, this time resulting in a two to three watchdog clock cycle delay in the timer restarting. In case the duration of the stop mode is less than one watchdog clock cycle, the watchdog timer is not guaranteed to pause.
- Consider the case when the first refresh value is written, following which the system enters stop mode (with system bus clk still on). Now, if the second refresh value is not written within 20 bus cycles of the first value, the system is reset (or interrupt-then-reset if enabled).



nestrictions on Watchdog Operation



# **Chapter 24 Multipurpose Clock Generator (MCG)**

#### 24.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The multipurpose clock generator (MCG) module provides several clock source choices for the MCU. The module contains a frequency-locked loop (FLL) and a phase-locked loop (PLL). The FLL is controllable by either an internal or an external reference clock. The PLL is controllable by the external reference clock. The module can select either of the FLL or PLL output clocks, or either of the internal or external reference clocks as a source for the MCU system clock. The MCG operates in conjuction with a crystal oscillator, which allows an external crystal, ceramic resonator, or another external clock source to produce the external reference clock.

#### 24.1.1 Features

Key features of the MCG module are:

- Frequency-locked loop (FLL)
  - Digitally-controlled oscillator (DCO)
  - DCO frequency range is programmable for up to four different frequency ranges.
  - Option to program and maximize DCO output frequency for a low frequency external reference clock source.
  - Option to prevent FLL from resetting its current locked frequency when switching clock modes if FLL reference frequency is not changed.



#### muroduction

- Internal or external reference clock can be used as the FLL source.
- Can be used as a clock source for other on-chip peripherals.
- Phase-locked loop (PLL)
  - Voltage-controlled oscillator (VCO)
  - External reference clock is used as the PLL source
  - Modulo VCO frequency divider
  - Phase/Frequency detector
  - Integrated loop filter
  - Can be used as a clock source for other on-chip peripherals.
- Internal reference clock generator
  - Slow clock with nine trim bits for accuracy
  - Fast clock with four trim bits
  - Can be used as source clock for the FLL. In FEI mode, only the slow Internal Reference Clock (IRC) can be used as the FLL source.
  - Either the slow or the fast clock can be selected as the clock source for the MCU
  - Can be used as a clock source for other on-chip peripherals
- Control signals for "the MCG external reference low power oscillator clock generators are provided:
  - HGO, RANGE, EREFS
- External clock from the Crystal Oscillator
  - Can be used as a source for the FLL and/or the PLL.
  - Can be selected as the clock source for the MCU
- External clock from the Real Time Counter (RTC)
  - Can only be used as a source for the FLL.
  - Can be selected as the clock source for the MCU
- External clock monitor with reset and interrupt request capability to check for external clock failure when running in FBE, PEE, BLPE, or FEE modes
- Lock detector with interrupt request capability for use with the PLL



- Internal Reference Clocks Auto Trim Machine (ATM) capability using an external clock as a reference
- Reference dividers for both the FLL and PLL are provided
- Reference dividers for the Fast Internal Reference Clock are provided
- MCG PLL Clock (MCGPLLCLK) is provided as a clock source for other on-chip peripherals
- MCG FLL Clock (MCGFLLCLK) is provided as a clock source for other on-chip peripherals
- MCG Fixed Frequency Clock (MCGFFCLK) is provided as a clock source for other on-chip peripherals
- MCG Internal Reference Clock (MCGIRCLK) is provided as a clock source for other on-chip peripherals.



#### ınıroduction




Figure 24-1. Multipurpose Clock Generator (MCG) Block Diagram



## 24.1.2 Modes of Operation

There are nine modes of operation for the MCG: FEI, FEE, FBI, FBE, PBE, PEE, BLPI, BLPE, and Stop. For details, see MCG Modes of Operation.

## 24.2 External Signal Description

There are no MCG signals that connect off chip.

## 24.3 Memory Map/Register Definition

This section includes the memory map and register definition.

The MCG registers can only be written to when in supervisor mode. Write accesses when in user mode will result in a bus error. Read accesses may be performed in both supervisor and user modes.


#### MCG memory map

Absolute address (hex)	Register name		Access	Reset value	Section/ page
4006_4000	MCG Control 1 Register (MCG_C1)	8	R/W	04h	24.3.1/ 532
4006_4001	MCG Control 2 Register (MCG_C2)	8	R/W	See section	24.3.2/ 533
4006_4002	MCG Control 3 Register (MCG_C3)	8	R/W	Undefined	24.3.3/ 534
4006_4003	MCG Control 4 Register (MCG_C4)	8	R/W	Undefined	24.3.4/ 535
4006_4004	MCG Control 5 Register (MCG_C5)	8	R/W	00h	24.3.5/ 536
4006_4005	MCG Control 6 Register (MCG_C6)	8	R/W	00h	24.3.6/ 538
4006_4006	MCG Status Register (MCG_S)	8	R	10h	24.3.7/ 539
4006_4008	MCG Auto Trim Control Register (MCG_ATC)	8	R/W	00h	24.3.8/ 541
4006_400A	MCG Auto Trim Compare Value High Register (MCG_ATCVH)	8	R/W	00h	24.3.9/ 541
4006_400B	MCG Auto Trim Compare Value Low Register (MCG_ATCVL)	8	R/W	00h	24.3.10/ 542



## 24.3.1 MCG Control 1 Register (MCG\_C1)

Address: MCG\_C1 is 4006\_4000h base + 0h offset = 4006\_4000h



#### MCG\_C1 field descriptions

Field	Description				
7–6 CLKS	Clock Source Select  Selects the clock source for MCGOUTCLK.  00 Encoding 0 — Output of FLL or PLL is selected (depends on PLLS control bit).  01 Encoding 1 — Internal reference clock is selected.  10 Encoding 2 — External reference clock is selected.				
	11 Encoding 3 — Reserved, defaults to 00.				
5–3 FRDIV	FLL External Reference Divider  Selects the amount to divide down the external reference clock for the FLL. The resulting frequency must be in the range 31.25 kHz to 39.0625 kHz (This is required when FLL/DCO is the clock source for MCGOUTCLK. In FBE mode, it is not required to meet this range, but it is recommended in the cases when trying to enter a FLL mode from FBE).				
	<ul> <li>If RANGE = 0 , Divide Factor is 1; for all other RANGE values, Divide Factor is 32.</li> <li>If RANGE = 0 , Divide Factor is 2; for all other RANGE values, Divide Factor is 64.</li> <li>If RANGE = 0 , Divide Factor is 4; for all other RANGE values, Divide Factor is 128.</li> <li>If RANGE = 0 , Divide Factor is 8; for all other RANGE values, Divide Factor is 256.</li> <li>If RANGE = 0 , Divide Factor is 16; for all other RANGE values, Divide Factor is 512.</li> <li>If RANGE = 0 , Divide Factor is 32; for all other RANGE values, Divide Factor is 1024.</li> <li>If RANGE = 0 , Divide Factor is 64; for all other RANGE values, Divide Factor is Reserved .</li> <li>If RANGE = 0 , Divide Factor is 128; for all other RANGE values, Divide Factor is Reserved .</li> </ul>				
2 IREFS	Internal Reference Select Selects the reference clock source for the FLL.				
	<ul><li>0 External reference clock is selected.</li><li>1 The slow internal reference clock is selected.</li></ul>				
1 IRCLKEN	Internal Reference Clock Enable  Enables the internal reference clock for use as MCGIRCLK.  0 MCGIRCLK inactive.  1 MCGIRCLK active.				
0 IREFSTEN	Internal Reference Stop Enable  Controls whether or not the internal reference clock remains enabled when the MCG enters Stop mode.				




#### MCG\_C1 field descriptions (continued)

Field	Description				
	0 Internal reference clock is disabled in Stop mode.				
	1 Internal reference clock is enabled in Stop mode if IRCLKEN is set or if MCG is in FEI, FBI, or BLPI modes before entering Stop mode.				

## 24.3.2 MCG Control 2 Register (MCG\_C2)

Address: MCG\_C2 is 4006\_4000h base + 1h offset = 4006\_4001h



#### MCG\_C2 field descriptions

Field	Description
7 Reserved	This read-only field is reserved and always has the value zero.
6 Reserved	This read-only field is reserved and always has the value zero.
5–4 RANGE	Frequency Range Select  Selects the frequency range for the crystal oscillator or external clock source. Refer to the Oscillator (OSC) chapter for more details and the device data sheet for the frequency ranges used.  00 Encoding 0 — Low frequency range selected for the crystal oscillator.  01 Encoding 1 — High frequency range selected for the crystal oscillator.  1X Encoding 2 — Very high frequency range selected for the crystal oscillator.
3 HGO	High Gain Oscillator Select  Controls the crystal oscillator mode of operation. Refer to the Oscillator (OSC) chapter for more details.  O Configure crystal oscillator for low-power operation.  Configure crystal oscillator for high-gain operation.
2 EREFS	External Reference Select  Selects the source for the external reference clock. Refer to the Oscillator (OSC) chapter for more details.  0 External reference clock requested.  1 Oscillator requested.
1 LP	Low Power Select  Controls whether the FLL (or PLL) is disabled in BLPI and BLPE modes. In FBE or PBE modes, setting this bit to 1 will transition the MCG into BLPE mode; in FBI mode, setting this bit to 1 will transition the MCG into BLPI mode. In any other MCG mode, LP bit has no affect.




#### wemory Map/Register Definition

## MCG\_C2 field descriptions (continued)

Field	Description					
	O FLL (or PLL) is not disabled in bypass modes.  FLL (or PLL) is disabled in bypass modes (lower power)					
0 IRCS	Internal Reference Clock Select Selects between the fast or slow internal reference clock source.					
	O Slow internal reference clock selected.  Tast internal reference clock selected.					

## 24.3.3 MCG Control 3 Register (MCG\_C3)

Address: MCG\_C3 is 4006\_4000h base + 2h offset = 4006\_4002h



<sup>\*</sup> Notes:

#### MCG\_C3 field descriptions

Field	Description
7-0 SCTRIM	Slow Internal Reference Clock Trim Setting  SCTRIM <sup>1</sup> controls the slow internal reference clock frequency by controlling the slow internal reference clock period. The SCTRIM bits are binary weighted (that is, bit 1 adjusts twice as much as bit 0). Increasing the binary value increases the period, and decreasing the value decreases the period.
	An additional fine trim bit is available in C4 register as the SCFTRIM bit. Upon reset this value is loaded with a factory trim value.
	If an SCTRIM value stored in nonvolatile memory is to be used, it is your responsibility to copy that value from the nonvolatile memory location to this register.

1. A value for SCTRIM is loaded during reset from a factory programmed location .


<sup>•</sup> x = Undefined at reset.



## 24.3.4 MCG Control 4 Register (MCG\_C4)

Reset values for DRST and DMX32 bits are 0.

Address: MCG\_C4 is 4006\_4000h base + 3h offset = 4006\_4003h



<sup>\*</sup> Notes:

- x = Undefined at reset.
- A value for FCTRIM is loaded during reset from a factory programmed location . x = Undefined at reset.

#### MCG\_C4 field descriptions

Field	Description				
7	DCO Maximum Frequency with 32.768 kHz Reference				
DMX32	The DMX32 bit controls whether or not the DCO frequency range is narrowed to its maximum frequency with a 32.768 kHz reference.				
	The following table id	dentifies settings for th	ne DCO frequency rar	nge.	
	NOTE: The system	clocks derived from t	his source should not	exceed their specifie	ed maximums.
	DRST_DRS	DMX32	Reference Range	FLL Factor	DCO Range
	00	0	31.25-39.0625 kHz	640	20-25 MHz
		1	32.768 kHz	732	24 MHz
	01	0	31.25-39.0625 kHz	1280	40-50 MHz
		1	32.768 kHz	1464	48 MHz
	10	0	31.25-39.0625 kHz	1920	60-75 MHz
		1	32.768 kHz	2197	72 MHz
	11	0	31.25-39.0625 kHz	2560	80-100 MHz
		1	32.768 kHz	2929	96 MHz
	<ul> <li>0 DCO has a default range of 25%.</li> <li>1 DCO is fine-tuned for maximum frequency with 32.768 kHz reference.</li> </ul>				
6–5	DCO Range Select				
DRST_DRS	The DRS bits select the frequency range for the FLL output, DCOOUT. When the LP bit is set, writes to the DRS bits are ignored. The DRST read field indicates the current frequency range for DCOOUT. The DRST field does not update immediately after a write to the DRS field due to internal synchronization between clock domains. Refer to DCO Frequency Range table for more details.				
	<ul><li>00 Encoding 0 — Low range (reset default).</li><li>01 Encoding 1 — Mid range.</li></ul>				



#### wemory Map/Register Definition


#### MCG\_C4 field descriptions (continued)

Field	Description
	<ul> <li>10 Encoding 2 — Mid-high range.</li> <li>11 Encoding 3 — High range.</li> </ul>
4–1	Fast Internal Reference Clock Trim Setting
FCTRIM	FCTRIM <sup>1</sup> controls the fast internal reference clock frequency by controlling the fast internal reference clock period. The FCTRIM bits are binary weighted (that is, bit 1 adjusts twice as much as bit 0). Increasing the binary value increases the period, and decreasing the value decreases the period.
	If an FCTRIM[3:0] value stored in nonvolatile memory is to be used, it is your responsibility to copy that value from the nonvolatile memory location to this register.
0 SCFTRIM	Slow Internal Reference Clock Fine Trim  SCFTRIM <sup>2</sup> controls the smallest adjustment of the slow internal reference clock frequency. Setting SCFTRIM increases the period and clearing SCFTRIM decreases the period by the smallest amount possible.
	If an SCFTRIM value stored in nonvolatile memory is to be used, it is your responsibility to copy that value from the nonvolatile memory location to this bit.

- 1. A value for FCTRIM is loaded during reset from a factory programmed location .
- 2. A value for SCFTRIM is loaded during reset from a factory programmed location .

## 24.3.5 MCG Control 5 Register (MCG\_C5)

Address: MCG\_C5 is 4006\_4000h base + 4h offset = 4006\_4004h



#### MCG\_C5 field descriptions

Field	Description
7 Reserved	This read-only field is reserved and always has the value zero.
6 PLLCLKEN	PLL Clock Enable  Enables the PLL independent of PLLS and enables the PLL clock for use as MCGPLLCLK. (PRDIV needs to be programmed to the correct divider to generate a PLL reference clock in the range of 2 - 4 MHz range prior to setting the PLLCLKEN bit). Setting PLLCLKEN will enable the external oscillator if not already enabled. Whenever the PLL is being enabled by means of the PLLCLKEN bit, and the external oscillator is being used as the reference clock, the OSCINIT bit should be checked to make sure it is set.




## MCG\_C5 field descriptions (continued)

Field	Description							
	1 MCG	PLLCLK is	active.					
5	PLL Stop	Enable						
PLLSTEN	even if P		ock during Norma ). All other power ritten to 1.					
	0 MCG	PLLCLK is	disabled in any o	of the Stop mo	odes.			
	1 MCG	PLLCLK is	enabled if systen	n is in Norma	Stop mode.			
4–0 PRDIV	PLL Exte	ernal Refere	nce Divider					
	Selects the amount to divide down the external reference clock for the PLL. The resulting freque must be in the range of 2 MHz to 4 MHz. After the PLL is enabled (by setting either PLLCLKEN of PLLS), the PRDIV value must not be changed when LOCK is zero.  Table 24-7. PLL External Reference Divide Factor							
	PRDIV	Divide Factor	PRDIV	Divide Factor	PRDIV	Divide Factor	PRDIV	Divide Factor
	00000	1	01000	9	10000	17	11000	25
	00001	2	01001	10	10001	18	11001	Reserv ed
	00010	3	01010	11	10010	19	11010	Reserv ed
	00011	4	01011	12	10011	20	11011	Reserv ed
	00100	5	01100	13	10100	21	11100	Reserv ed
	00101	6	01101	14	10101	22	11101	Reserv ed
	00110	7	01110	15	10110	23	11110	Reserv ed
	00111	8	01111	16	10111	24	11111	Reserv ed



## 24.3.6 MCG Control 6 Register (MCG\_C6)

Address: MCG\_C6 is 4006\_4000h base + 5h offset = 4006\_4005h



#### MCG\_C6 field descriptions

Field				Des	cription			
7 LOLIE	Loss of Lock Interrrupt Enable  Determines if an interrupt request is made following a loss of lock indication. This bit only has an effective them.						n effect	
		nterrupt request erate an interru	-		<b>⟨</b> .			
6 PLLS	bit is cleadisabled  0 FLL i	whether the PL ared and PLLCI in all modes. is selected.	_KEN is not se	et, the PLL is one	as the MCG so disabled in all m d to the correct ne PLLS bit).	nodes. If the PL	LS is set, the	FLL is
5 CME	Clock Monitor Enable  Determines if a reset request is made following a loss of external clock indication. The CME bit should only be set to a logic 1 when the MCG is in an operational mode that uses the external clock (FEE, FBE, PEE, PBE, or BLPE). Whenever the CME bit is set to a logic 1, the value of the RANGE bits in the C2 register should not be changed. CME bit should be set to a logic 0 before the MCG enters any Stop mode. Otherwise, a reset request may occur while in Stop mode. CME should also be set to a logic 0 before entering VLPR or VLPW power modes if the MCG is in BLPE mode.  0 External clock monitor is disabled. 1 Generate a reset request on loss of external clock.							
4–0 VDIV	VCO Divider  Selects the amount to divide the VCO output of the PLL. The VDIV bits establish the multiplication factor (M) applied to the reference clock frequency. After the PLL is enabled (by setting either PLLCLKEN or PLLS), the VDIV value must not be changed when LOCK is zero.  Table 24-9. PLL VCO Divide Factor							
	VDIV	Multiply Factor	VDIV	Multiply Factor	VDIV	Multiply Factor	VDIV	Multiply
	11							




## MCG\_C6 field descriptions (continued)

Field		Description									
			Table 24-9	. PLL V	CO Divide Fac	ctor (con	ntinued)				
	00001	25	0100	I 33	10001	41	11001	49			
	00010	26	01010	34	10010	42	11010	50			
	00011	27	0101	35	10011	43	11011	51			
	00100	28	01100	36	10100	44	11100	52			
	00101	29	0110	37	10101	45	11101	53			
	00110	30	01110	38	10110	46	11110	54			
	00111	31	0111	39	10111	47	11111	55			
		1									

## 24.3.7 MCG Status Register (MCG\_S)

Address: MCG\_S is 4006\_4000h base + 6h offset = 4006\_4006h



#### MCG\_S field descriptions

Field	Description
7	Loss of Lock Status
LOLS	This bit is a sticky bit indicating the lock status for the PLL. LOLS is set if after acquiring lock, the PLL output frequency has fallen outside the lock exit frequency tolerance, D <sub>unl</sub> . LOLIE determines whether an interrupt request is made when LOLS is set. LOLRE determines whether a reset request is made when LOLS0 is set. This bit is cleared by reset or by writing a logic 1 to it when set. Writing a logic 0 to this bit has no effect.
	0 PLL has not lost lock since LOLS was last cleared.
	1 PLL has lost lock since LOLS was last cleared.
6	Lock Status
LOCK	This bit indicates whether the PLL has acquired lock. Lock detection is disabled when not operating in either PBE or PEE mode unless PLLCLKEN =1 and the MCG is not configured in BLPI or BLPE mode.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory Map/Register Definition


## MCG\_S field descriptions (continued)

Field	Description
	While the PLL clock is locking to the desired frequency, the MCG PLL clock (MCGPLLCLK) will be gated off until the LOCK bit gets asserted. If the lock status bit is set, changing the value of the PRDIV [4:0] bits in the C5 register or the VDIV0[4:0] bits in the C6 register causes the lock status bit to clear and stay cleared until the PLL has reacquired lock. Entry into LLS, VLPS, or regular Stop with PLLSTEN =0 also causes the lock status bit to clear and stay cleared until the Stop mode is exited and the PLL has reacquired lock. Any time the PLL is enabled and the LOCK bit is cleared, the MCGPLLCLK will be gated off until the LOCK bit is asserted again.
	O PLL is currently unlocked.  PLL is currently locked.
5 PLLST	PLL Select Status
	This bit indicates the clock source selected by PLLS . The PLLST bit does not update immediately after a write to the PLLS bit due to internal synchronization between clock domains.
	0 Source of PLLS clock is FLL clock.
	Source of PLLS clock is PLL clock.
4 IREFST	Internal Reference Status
IIILI OI	This bit indicates the current source for the FLL reference clock. The IREFST bit does not update immediately after a write to the IREFS bit due to internal synchronization between clock domains.
	0 Source of FLL reference clock is the external reference clock.
	1 Source of FLL reference clock is the internal reference clock.
3–2 CLKST	Clock Mode Status
02.0	These bits indicate the current clock mode. The CLKST bits do not update immediately after a write to the CLKS bits due to internal synchronization between clock domains.
	00 Encoding 0 — Output of the FLL is selected (reset default).
	01 Encoding 1 — Internal reference clock is selected.
	<ul> <li>10 Encoding 2 — External reference clock is selected.</li> <li>11 Encoding 3 — Output of the PLL is selected.</li> </ul>
1	OSC Initialization
OSCINIT	This bit, which resets to 0, is set to 1 after the initialization cycles of the crystal oscillator clock have completed. After being set, the bit is cleared to 0 if the OSC is subsequently disabled. Refer to the OSC module's detailed description for more information.
0 IRCST	Internal Reference Clock Status
incəi	The IRCST bit indicates the current source for the internal reference clock select clock (IRCSCLK). The IRCST bit does not update immediately after a write to the IRCS bit due to internal synchronization between clock domains. The IRCST bit will only be updated if the internal reference clock is enabled, either by the MCG being in a mode that uses the IRC or by setting the C1[IRCLKEN] bit.
	0 Source of internal reference clock is the slow clock (32 kHz IRC).
	1 Source of internal reference clock is the fast clock (2 MHz IRC).



## 24.3.8 MCG Auto Trim Control Register (MCG\_ATC)

Address: MCG\_ATC is 4006\_4000h base + 8h offset = 4006\_4008h




#### MCG\_ATC field descriptions

Field	Description
7 ATME	Automatic Trim Machine Enable
, <u> </u>	Enables the Auto Trim Machine to start automatically trimming the selected Internal Reference Clock.
	NOTE: ATME deasserts after the Auto Trim Machine has completed trimming all trim bits of the IRCS clock selected by the ATMS bit.
	Writing to C1, C3, C4, and ATC registers or entering Stop mode aborts the auto trim operation and clears this bit.
	Auto Trim Machine disabled.
	1 Auto Trim Machine enabled.
6 ATMS	Automatic Trim Machine Select
	Selects the IRCS clock for Auto Trim Test.
	0 32 kHz Internal Reference Clock selected.
	1 4 MHz Internal Reference Clock selected.
5 ATMF	Automatic Trim machine Fail Flag
	Fail flag for the Automatic Trim Machine (ATM). This bit asserts when the Automatic Trim Machine is enabled (ATME=1) and a write to the C1, C3, C4, and ATC registers is detected or the MCG enters into any Stop mode. A write to ATMF clears the flag.
	Automatic Trim Machine completed normally.
	1 Automatic Trim Machine failed.
4–0 Reserved	This read-only field is reserved and always has the value zero.

## 24.3.9 MCG Auto Trim Compare Value High Register (MCG\_ATCVH)

Address: MCG\_ATCVH is 4006\_4000h base + Ah offset = 4006\_400Ah



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




#### runctional Description

#### MCG\_ATCVH field descriptions

Field	Description
7–0 ATCVH	ATM Compare Value High  Values are used by Auto Trim Machine to compare and adjust Internal Reference trim values during ATM SAR conversion.

## 24.3.10 MCG Auto Trim Compare Value Low Register (MCG\_ATCVL)

Address: MCG\_ATCVL is 4006\_4000h base + Bh offset = 4006\_400Bh



#### MCG\_ATCVL field descriptions

Field	Description
7–0 ATCVL	ATM Compare Value Low  Values are used by Auto Trim Machine to compare and adjust Internal Reference trim values during ATM SAR conversion.

## 24.4 Functional Description

## 24.4.1 MCG Mode State Diagram

The nine states of the MCG are shown in the following figure and are described in Table 24-14. The arrows indicate the permitted MCG mode transitions.






Figure 24-12. MCG Mode State Diagram

#### NOTE

- During exits from LLS or VLPS when the MCG is in PEE mode, the MCG will reset to PBE clock mode and the C1[CLKS] and S[CLKST] will automatically be set to 2'b10.
- If entering Normal Stop mode when the MCG is in PEE mode with C5[PLLSTEN]=0, the MCG will reset to PBE clock mode and C1[CLKS] and S[CLKST] will automatically be set to 2'b10.

## 24.4.1.1 MCG Modes of Operation

The MCG operates in one of the following modes.

#### **Note**

The MCG restricts transitions between modes. For the permitted transitions, see Figure 24-12.



#### runctional Description

## Table 24-14. MCG Modes of Operation

Mode	Description
FLL Engaged Internal (FEI)	FLL engaged internal (FEI) is the default mode of operation and is entered when all the following condtions occur:
	C1[CLKS] bits are written to 00
	C1[IREFS] bit is written to 1
	C6[PLLS] bit is written to 0
	In FEI mode, MCGOUTCLK is derived from the FLL clock (DCOCLK) that is controlled by the 32 kHz Internal Reference Clock (IRC). The FLL loop will lock the DCO frequency to the FLL factor, as selected by the C4[DRST_DRS] and C4[DMX32] bits, times the internal reference frequency . Refe to the C4[DMX32] bit description for more details. In FEI mode, the PLL is disabled in a low-power state unless C5[PLLCLKEN] is set.
FLL Engaged External	FLL engaged external (FEE) mode is entered when all the following conditions occur:
(FEE)	C1[CLKS] bits are written to 00
	C1[IREFS] bit is written to 0
	C1[FRDIV] must be written to divide external reference clock to be within the range of 31.25 kHz to 39.0625 kHz
	C6[PLLS] bit is written to 0
	In FEE mode, MCGOUTCLK is derived from the FLL clock (DCOCLK) that is controlled by the external reference clock. The FLL loop will lock the DCO frequency to the FLL factor, as selected by C4[DRST_DRS] and C4[DMX32] bits, times the external reference frequency, as specified by the C1[FRDIV] and C2[RANGE]. Refer to the C4[DMX32] bit description for more details. In FEE mode, the PLL is disabled in a low-power state unless C5[PLLCLKEN] is set.
FLL Bypassed Internal	FLL bypassed internal (FBI) mode is entered when all the following conditions occur:
(FBI)	C1[CLKS] bits are written to 01
	C1[IREFS] bit is written to 1
	C6[PLLS] is written to 0
	C2[LP] is written to 0
	In FBI mode, the MCGOUTCLK is derived either from the slow (32 kHz IRC) or fast (2 MHz IRC) internal reference clock, as selected by the C2[IRCS] bit. The FLL is operational but its output is no used. This mode is useful to allow the FLL to acquire its target frequency while the MCGOUTCLK is driven from the C2[IRCS] selected internal reference clock. The FLL clock (DCOCLK) is controlled by the slow internal reference clock, and the DCO clock frequency locks to a multiplication factor, as selected by the C4[DRST_DRS] and C4[DMX32] bits, times the internal reference frequency. Refer to the C4[DMX32] bit description for more details. In FBI mode, the PLL is disabled in a low-power state unless C5[PLLCLKEN] is set.

Table continues on the next page...



## Table 24-14. MCG Modes of Operation (continued)

Mode	Description
FLL Bypassed External	FLL bypassed external (FBE) mode is entered when all the following conditions occur:
(FBE)	C1[CLKS] bits are written to 10
	C1[IREFS] bit is written to 0
	C1[FRDIV] must be written to divide external reference clock to be within the range of 31.25 kHz to 39.0625 kHz.
	C6[PLLS] bit is written to 0
	C2[LP] is written to 0
	In FBE mode, the MCGOUTCLK is derived from the OSCSEL external reference clock. The FLL is operational but its output is not used. This mode is useful to allow the FLL to acquire its target frequency while the MCGOUTCLK is driven from the external reference clock. The FLL clock (DCOCLK) is controlled by the external reference clock, and the DCO clock frequency locks to a multiplication factor, as selected by the C4[DRST_DRS] and C4[DMX32] bits, times the divided external reference frequency. Refer to the C4[DMX32] bit description for more details. In FBI mode the PLL is disabled in a low-power state unless C5[PLLCLKEN] is set.
PLL Engaged External	PLL Engaged External (PEE) mode is entered when all the following conditions occur:
(PEE)	C1[CLKS] bits are written to 00
	C1[IREFS] bit is written to 0
	C6[PLLS] bit is written to 1
	In PEE mode, the MCGOUTCLK is derived from the PLL clock, which is controlled by the external reference clock. The PLL clock frequency locks to a multiplication factor, as specified by C6[VDIV], times the external reference frequency, as specified by C5[PRDIV]. The PLL's programmable reference divider must be configured to produce a valid PLL reference clock. The FLL is disabled in a low-power state.
PLL Bypassed External	PLL Bypassed External (PBE) mode is entered when all the following conditions occur:
(PBE)	C1[CLKS] bits are written to 10
	C1[IREFS] bit is written to 0
	C6[PLLS] bit is written to 1
	C2[LP] bit is written to 0
	In PBE mode, MCGOUTCLK is derived from the OSCSEL external reference clock; the PLL is operational, but its output clock is not used. This mode is useful to allow the PLL to acquire its target frequency while MCGOUTCLK is driven from the external reference clock. The PLL clock frequency locks to a multiplication factor, as specified by its [VDIV], times the PLL reference frequency, as specified by its [PRDIV]. In preparation for transition to PEE, the PLL's programmable reference divider must be configured to produce a valid PLL reference clock. The FLL is disabled in a low-power state.

Table continues on the next page...



#### **runctional Description**

#### **Table 24-14. MCG Modes of Operation (continued)**

Mode	Description				
Bypassed Low Power	Bypassed Low Power Internal (BLPI) mode is entered when all the following conditions occur:				
Internal (BLPI)1	C1[CLKS] bits are written to 01				
	C1[IREFS] bit is written to 1				
	C6[PLLS] bit is written to 0				
	C2[LP] bit is written to 1				
	In BLPI mode, MCGOUTCLK is derived from the internal reference clock. The FLL is disabled and PLL is disabled even if the C5[PLLCLKEN] is set to 1.				
Bypassed Low Power	Bypassed Low Power External (BLPE) mode is entered when all the following conditions occur:				
External (BLPE)	C1[CLKS] bits are written to 10				
	C1[IREFS] bit is written to 0				
	C2[LP] bit is written to 1				
	In BLPE mode, MCGOUTCLK is derived from the OSCSEL external reference clock. The FLL is disabled and PLL is disabled even if the C5[PLLCLKEN] is set to 1.				
Stop	Entered whenever the MCU enters a Stop state. The power modes are chip specific. For power mode assignments, see the chapter that describes how modules are configured and MCG behavior during Stop recovery. Entering Stop mode, the FLL is disabled, and all MCG clock signals are static except in the following case:				
	MCGPLLCLK is active in Normal Stop mode when PLLSTEN=1				
	MCGIRCLK is active in Stop mode when all the following conditions become true:				
	• C1[IRCLKEN] = 1				
	• C1[IREFSTEN] = 1				
	NOTE:  • When entering Low Power Stop modes (LLS or VLPS) from PEE mode, on exit the MCG clock mode is forced to PBE clock mode, the C1[CLKS] and S[CLKST] will be configured to 2'b10 and S[LOCK] bit will be cleared without setting S[LOLS].				
	<ul> <li>When entering Normal Stop mode from PEE mode and if C5[PLLSTEN]=0, on exit the MCG clock mode is forced to PBE mode, the C1[CLKS] and S[CLKST] will be configured to 2'b10 and S[LOCK] bit will clear without setting S[LOLS]. If C5[PLLSTEN]=1, the S[LOCK] bit will not get cleared and on exit the MCG will continue to run in PEE mode.</li> </ul>				

<sup>1.</sup> If entering VLPR mode, MCG has to be configured and enter BLPE mode or BLPI mode with the 4 MHz IRC clock selected (C2[IRCS]=1). Once in VLPR mode, writes to any of the MCG control registers that can cause a MCG clock mode switch to a non low power clock mode must be avoided.

#### NOTE

For the chip-specific modes of operation, refer to the power management chapter of this MCU.



#### 24.4.1.2 MCG Mode Switching

The C1[IREFS] bit can be changed at any time, but the actual switch to the newly selected reference clocks is shown by the S[IREFST] bit. When switching between engaged internal and engaged external modes, the FLL will begin locking again after the switch is completed.

The C1[CLKS] bits can also be changed at anytime, but the actual switch to the newly selected clock is shown by the S[CLKST] bits. If the newly selected clock is not available, the previous clock will remain selected.

The C4[DRST\_DRS] write bits can be changed at anytime except when C2[LP] bit is 1. If the C4[DRST\_DRS] write bits are changed while in FLL engaged internal (FEI) or FLL engaged external (FEE), the MCGOUTCLK will switch to the new selected DCO range within three clocks of the selected DCO clock. After switching to the new DCO, the FLL remains unlocked for several reference cycles. DCO startup time is equal to the FLL acquisition time. After the selected DCO startup time is over, the FLL is locked. The completion of the switch is shown by the C4[DRST\_DRS] read bits.

## 24.4.2 Low Power Bit Usage

The C2[LP] bit is provided to allow the FLL or PLL to be disabled and thus conserve power when these systems are not being used. The C4[DRST\_DRS] can not be written while C2[LP] bit is 1. However, in some applications, it may be desirable to enable the FLL or PLL and allow it to lock for maximum accuracy before switching to an engaged mode. Do this by writing C2[LP] to 0.

#### 24.4.3 MCG Internal Reference Clocks

This module supports two internal reference clocks with nominal frequencies of 32 kHz (slow IRC) and 4 MHz (fast IRC).

#### 24.4.3.1 MCG Internal Reference Clock

The MCG Internal Reference Clock (MCGIRCLK) provides a clock source for other onchip peripherals and is enabled when C1[IRCLKEN]=1. When enabled, MCGIRCLK is driven by either the fast internal reference clock (2 MHz IRC) or the slow internal reference clock (32 kHz IRC). The IRCS clock frequency can be re-targeted by trimming the period of its IRCS selected internal reference clock. This can be done by writing a new trim value to the C3[SCTRIM]:C4[SCFTRIM] bits when the slow IRC clock is



#### runctional Description

selected or by writing a new trim value to the C4[FCTRIM] bits when the fast IRC clock is selected. The internal reference clock period is proportional to the trim value written. C3[SCTRIM]:C4[SCFTRIM] (if C2[IRCS]=0) and C4[FCTRIM] (if C2[IRCS]=1) bits affect the MCGOUTCLK frequency if the MCG is in FBI or BLPI modes. C3[SCTRIM]:C4[SCFTRIM] (if C2[IRCS]=0) bits also affect the MCGOUTCLK frequency if the MCG is in FEI mode.

Additionally, this clock can be enabled in Stop mode by setting C1[IRCLKEN] and C1[IREFSTEN], otherwise this clock is disabled in Stop mode.

#### 24.4.4 External Reference Clock

The MCG module can support an external reference clock in all modes. Refer to the device datasheet for external reference frequency range. When C1[IREFS] is set, the external reference clock will not be used by the FLL or PLL. In these modes, the frequency can be equal to the maximum frequency the chip-level timing specifications will support.

If the CME is asserted the slow internal reference clock is enabled along with the enabled external clock monitor. For the case when C6[CME]=1, a loss of clock is detected if the OSC external reference falls below a minimum frequency ( $f_{loc\_high}$  or  $f_{loc\_low}$  depending on C2[RANGE]).

Upon detect of a loss of clock event, the MCU generates a system reset if the respective LOCRE bit is set. Otherwise the MCG sets the respective LOCS bit and the MCG generates a LOCS interrupt request.

## 24.4.5 MCG Fixed Frequency Clock

The MCG Fixed Frequency Clock (MCGFFCLK) provides a fixed frequency clock source for other on-chip peripherals. This clock is driven by either the slow clock from the internal reference clock generator or the external reference clock from the Crystal Oscillator, divided by the FLL reference clock divider. The source of MCGFFCLK is selected by C1[IREFS]. Additionally, this clock is divided by two.

This clock is synchronized to the peripheral bus clock and is only valid when it's frequency is not more than 1/8 of the MCGOUTCLK frequency. When it is not valid, it is disabled and held high. The MCGFFCLK is not available when the MCG is in BLPI mode. This clock is also disabled in Stop mode. The FLL reference clock must be set within the valid frequency range for the MCGFFCLK.



#### 24.4.6 MCG PLL Clock

The MCG PLL Clock (MCGPLLCLK) is available depending on the device's configuration of the MCG module. For more details, refer to the clock distribution chapter of this MCU. The MCGPLLCLK is prevented from coming out of the MCG until it is enabled and S[LOCK] is set.

## 24.4.7 MCG Auto TRIM (ATM)

The MCG Auto Trim (ATM) is a MCG feature that when enabled, it configures the MCG hardware to automatically trim the MCG Internal Reference Clocks using an external clock as a reference. The selection between which MCG IRC clock gets tested and enabled is controlled by the ATC[ATMS] control bit (ATC[ATMS]=0 selects the 32 kHz IRC and ATC[ATMS]=1 selects the 4 MHz IRC). If 4 MHz IRC is selected for the ATM, a divide by 128 is enabled to divide down the 4 MHz IRC to a range of 31.250 kHz.

When MCG ATM is enabled by writing ATC[ATME] bit to 1, The ATM machine will start auto trimming the selected IRC clock. During the autotrim process, ATC[ATME] will remain asserted and will deassert after ATM is completed or an abort occurs. The MCG ATM is aborted if a write to any of the following control registers is detected including: C1, C3, C4, or ATC or if Stop mode is entered. If an abort occurs, ATC[ATMF] fail flag is asserted.

The ATM machine uses the bus clock as the external reference clock to perform the IRC auto-trim. Therefore, it is required that the MCG is configured in a clock mode where the reference clock used to generate the system clock is the external reference clock such as FBE clock mode. The MCG must not be configured in a clock mode where selected IRC ATM clock is used to generate the system clock. The bus clock is also required to be running with in the range of 8 - 16 MHz.

To perform the ATM on the selected IRC, the ATM machine uses the successive approximation technique to adjust the IRC trim bits to generate the desired IRC trimmed frequency. The ATM SARs each of the ATM IRC trim bits starting with the MSB. For each trim bit test, the ATM uses a pulse that is generated by the ATM selected IRC clock to enable a counter that counts number of ATM external clocks. At end of each trim bit, the ATM external counter value is compared to the ATCV[15:0] register value. Based on the comparison result, the ATM trim bit under test will get cleared or stay asserted. This is done until all trim bits have been tested by ATM SAR machine.



#### **mualization / Application Information**

Before the ATM can be enabled, the ATM expected count needs to get derived and stored into the ATCV register. The ATCV expected count is derived based on the required target Internal Reference Clock (IRC) frequency, the frequency of the external reference clock, and using the following formula:

ATCV Expected Count Value = 
$$21*(Fe/Fr)$$

- Fr = Target Internal Reference Clock (IRC) Trimmed Frequency
- Fe = External Clock Frequency

If the auto trim is being performed on the 4 MHz IRC, the calculated expected count value must be multiplied by 128 before storing it in the ATCV register. Therefore, the ATCV Expected Count Value for trimming the 4 MHz IRC is calculated using the following formula.

Expected Count Value = (Fe/Fr) \*21\*(128)

## 24.5 Initialization / Application Information

This section describes how to initialize and configure the MCG module in an application. The following sections include examples on how to initialize the MCG and properly switch between the various available modes.

## 24.5.1 MCG Module Initialization Sequence

The MCG comes out of reset configured for FEI mode. The internal reference will stabilize in  $t_{irefsts}$  microseconds before the FLL can acquire lock. As soon as the internal reference is stable, the FLL will acquire lock in  $t_{fll}$  acquire milliseconds.

## 24.5.1.1 Initializing the MCG

Because the MCG comes out of reset in FEI mode, the only MCG modes that can be directly switched to upon reset are FEE, FBE, and FBI modes (see Figure 24-12). Reaching any of the other modes requires first configuring the MCG for one of these three intermediate modes. Care must be taken to check relevant status bits in the MCG status register reflecting all configuration changes within each mode.

To change from FEI mode to FEE or FBE modes, follow this procedure:

1. Enable the external clock source by setting the appropriate bits in C2 register.



- 2. Write to C1 register to select the clock mode.
  - If entering FEE mode, set C1[FRDIV] appropriately, clear the C1[IREFS] bit to switch to the external reference, and leave the C1[CLKS] bits at 2'b00 so that the output of the FLL is selected as the system clock source.
  - If entering FBE, clear the C1[IREFS] bit to switch to the external reference and change the C1[CLKS] bits to 2'b10 so that the external reference clock is selected as the system clock source. The C1[FRDIV] bits should also be set appropriately here according to the external reference frequency to keep the FLL reference clock in the range of 31.25 kHz to 39.0625 kHz. Although the FLL is bypassed, it is still on in FBE mode.
  - The internal reference can optionally be kept running by setting the C1[IRCLKEN] bit. This is useful if the application will switch back and forth between internal and external modes. For minimum power consumption, leave the internal reference disabled while in an external clock mode.
- 3. Once the proper configuration bits have been set, wait for the affected bits in the MCG status register to be changed appropriately, reflecting that the MCG has moved into the proper mode.
  - If the MCG is in FEE, FBE, PEE, PBE, or BLPE mode, and C2[EREFS] was also set in step 1, wait here for S[OSCINIT] bit to become set indicating that the external clock source has finished its initialization cycles and stabilized.
  - If in FEE mode, check to make sure the S[IREFST] bit is cleared before moving on.
  - If in FBE mode, check to make sure the S[IREFST] bit is cleared and S[CLKST] bits have changed to 2'b10 indicating the external reference clock has been appropriately selected. Although the FLL is bypassed, it is still on in FBE mode.
- 4. Write to the C4 register to determine the DCO output (MCGFLLCLK) frequency range.
  - By default, with C4[DMX32] cleared to 0, the FLL multiplier for the DCO output is 640. For greater flexibility, if a mid-low-range FLL multiplier of 1280 is desired instead, set C4[DRST\_DRS] bits to 2'b01 for a DCO output frequency of 40 MHz. If a mid high-range FLL multiplier of 1920 is desired instead, set the C4[DRST\_DRS] bits to 2'b10 for a DCO output frequency of 60 MHz. If a high-range FLL multiplier of 2560 is desired instead, set the C4[DRST\_DRS] bits to 2'b11 for a DCO output frequency of 80 MHz.



#### mualization / Application Information

- When using a 32.768 kHz external reference, if the maximum low-range DCO frequency that can be achieved with a 32.768 kHz reference is desired, set C4[DRST\_DRS] bits to 2'b00 and set C4[DMX32] bit to 1. The resulting DCO output (MCGOUTCLK) frequency with the new multiplier of 732 will be 24 MHz.
- When using a 32.768 kHz external reference, if the maximum mid-range DCO frequency that can be achieved with a 32.768 kHz reference is desired, set C4[DRST\_DRS] bits to 2'b01 and set C4[DMX32] bit to 1. The resulting DCO output (MCGOUTCLK) frequency with the new multiplier of 1464 will be 48 MHz.
- When using a 32.768 kHz external reference, if the maximum mid high-range DCO frequency that can be achieved with a 32.768 kHz reference is desired, set C4[DRST\_DRS] bits to 2'b10 and set C4[DMX32] bit to 1. The resulting DCO output (MCGOUTCLK) frequency with the new multiplier of 2197 will be 72 MHz.
- When using a 32.768 kHz external reference, if the maximum high-range DCO frequency that can be achieved with a 32.768 kHz reference is desired, set C4[DRST\_DRS] bits to 2'b11 and set C4[DMX32] bit to 1. The resulting DCO output (MCGOUTCLK) frequency with the new multiplier of 2929 will be 96 MHz.
- 5. Wait for the FLL lock time to guarantee FLL is running at new C4[DRST\_DRS] and C4[DMX32] programmed frequency.

To change from FEI clock mode to FBI clock mode, follow this procedure:

- 1. Change C1[CLKS] bits in C1 register to 2'b01 so that the internal reference clock is selected as the system clock source.
- 2. Wait for S[CLKST] bits in the MCG status register to change to 2'b01, indicating that the internal reference clock has been appropriately selected.
- 3. Write to the C2 register to determine the IRCS output (IRCSCLK) frequency range.
  - By default, with C2[IRCS] cleared to 0, the IRCS selected output clock is the slow internal reference clock (32 kHz IRC). If the faster IRC is desired, set C2[IRCS] bit to 1 for a IRCS clock derived from the 4 MHz IRC source.



## 24.5.2 Using a 32.768 kHz Reference

In FEE and FBE modes, if using a 32.768 kHz external reference, at the default FLL multiplication factor of 640, the DCO output (MCGFLLCLK) frequency is 20.97 MHz at low-range. If C4[DRST\_DRS] bits are set to 2'b01, the multiplication factor is doubled to 1280, and the resulting DCO output frequency is 41.94 Mhz at mid-low-range. If C4[DRST\_DRS] bits are set to 2'b10, the multiplication factor is set to 1920, and the resulting DCO output frequency is 62.91 MHz at mid high-range. If C4[DRST\_DRS] bits are set to 2'b11, the multiplication factor is set to 2560, and the resulting DCO output frequency is 83.89 MHz at high-range.

In FBI and FEI modes, setting C4[DMX32] bit is not recommended. If the internal reference is trimmed to a frequency above 32.768 kHz, the greater FLL multiplication factor could potentially push the microcontroller system clock out of specification and damage the part.

The RTC 32 kHz oscillator may be used as the FLL reference clock. Refer to the SIM chapter on how this can be selected. The MCG must be in an internal clocking mode (FEI, FBI or BLPI) when the external clock selection mux is switched. The C2[RANGE] bits must be set to 2'b00 and the C1[FRDIV] bits must be set to 3'b000 to ensure this clock is divided by 1 to keep it within the allowed FLL reference clock range.

## 24.5.3 MCG Mode Switching

When switching between operational modes of the MCG, certain configuration bits must be changed in order to properly move from one mode to another. Each time any of these bits are changed (C6[PLLS], C1[IREFS], C1[CLKS], C2[IRCS], or C2[EREFS]), the corresponding bits in the MCG status register (PLLST, IREFST, CLKST, IRCST, or OSCINIT) must be checked before moving on in the application software.

Additionally, care must be taken to ensure that the reference clock divider (C1[FRDIV] and C5[PRDIV]) is set properly for the mode being switched to. For instance, in PEE mode, if using a 4 MHz crystal, C5[PRDIV] must be set to 5'b000 (divide-by-1) or 5'b001 (divide -by-2) in order to divide the external reference down to the required frequency between 2 and 4 MHz.

In FBE, FEE, FBI, and FEI modes, at any time, the application can switch the FLL multiplication factor between 640, 1280, 1920, and 2560 with C4[DRST\_DRS] bits. Writes to C4[DRST\_DRS] bits will be ignored if C2[LP]=1.

The table below shows MCGOUTCLK frequency calculations using C1[FRDIV], C5[PRDIV], and C6[VDIV] settings for each clock mode.

#### mualization / Application Information

**Table 24-15. MCGOUTCLK Frequency Calculation Options** 

Clock Mode	f <sub>MCGOUTCLK</sub> 1	Note
FEI (FLL engaged internal)	(f <sub>int</sub> * F)	Typical f <sub>MCGOUTCLK</sub> = 20 MHz immediately after reset.
FEE (FLL engaged external)	(f <sub>ext</sub> / FLL_R) *F	f <sub>ext</sub> / FLL_R must be in the range of 31.25 kHz to 39.0625 kHz
FBE (FLL bypassed external)	f <sub>ext</sub>	f <sub>ext</sub> / FLL_R must be in the range of 31.25 kHz to 39.0625 kHz
FBI (FLL bypassed internal)	f <sub>int</sub>	Typical f <sub>int</sub> = 32 kHz
PEE (PLL engaged external)	(f <sub>ext</sub> / PLL_R) * M	f <sub>ext</sub> / PLL_R must be in the range of 2 – 4 MHz
PBE (PLL bypassed external)	f <sub>ext</sub>	f <sub>ext</sub> / PLL_R must be in the range of 2 – 4 MHz
BLPI (Bypassed low power internal)	f <sub>int</sub>	
BLPE (Bypassed low power external)	f <sub>ext</sub>	

<sup>1.</sup> FLL\_R is the reference divider selected by the C1[FRDIV] bits, PLL\_R is the reference divider selected by C5[PRDIV] bits, F is the FLL factor selected by C4[DRST\_DRS] and C4[DMX32] bits, and M is the multiplier selected by C6[VDIV] bits.

This section will include 3 mode switching examples using an 4 MHz external crystal. If using an external clock source less than 2 MHz, the MCG should not be configured for any of the PLL modes (PEE and PBE).

## 24.5.3.1 Example 1: Moving from FEI to PEE Mode : External Crystal = 4 MHz, MCGOUTCLK Frequency = 48 MHz

In this example, the MCG will move through the proper operational modes from FEI to PEE to achieve 48 MHz MCGOUTCLK frequency from 4 MHz external crystal reference. First, the code sequence will be described. Then a flowchart will be included which illustrates the sequence.

- 1. First, FEI must transition to FBE mode:
  - a. C2 = 0x1C
    - C2[RANGE] set to 2'b01 because the frequency of 4 MHz is within the high frequency range
    - C2[HGO] set to 1 to configure the crystal oscillator for high gain operation
    - C2[EREFS] set to 1, because a crystal is being used
  - b. C1 = 0x90



- C1[CLKS] set to 2'b10 in order to select external reference clock as system clock source
- C1[FRDIV] set to 3'b010, or divide-by-128 because 4 MHz / 128 = 31.25 kHz which is in the 31.25 kHz to 39.0625 kHz range required by the FLL
- C1[IREFS] cleared to 0, selecting the external reference clock and enabling the external oscillator.
- c. Loop until S[OSCINIT] is 1, indicating the crystal selected by C2[EREFS] has been initialized..
- d. Loop until S[IREFST] is 0, indicating the external reference is the current source for the reference clock
- e. Loop until S[CLKST] is 2'b10, indicating that the external reference clock is selected to feed MCGOUTCLK
- 2. Then configure C5[PRDIV] to generate correct PLL reference frequency.
  - a. C5 = 0x01
    - C5[PRDIV] set to 5'b001, or divide-by-2 resulting in a pll reference frequency of 4 MHz/2 = 2 MHz.
- 3. Then, FBE must transition either directly to PBE mode or first through BLPE mode and then to PBE mode:
  - a. BLPE: If a transition through BLPE mode is desired, first set C2[LP] to 1.
  - b. BLPE/PBE: C6 = 0x40
    - C6[PLLS] set to 1, selects the PLL. At this time, with a C1[PRDIV] value of 2'b001, the PLL reference divider is 2 (see PLL External Reference Divide Factor table), resulting in a reference frequency of 4 MHz/ 2 = 2 MHz. In BLPE mode, changing the C6[PLLS] bit only prepares the MCG for PLL usage in PBE mode.
    - C6[VDIV] set to 5'b0000, or multiply-by-24 because 2 MHz reference \* 24 = 48 MHz. In BLPE mode, the configuration of the VDIV bits does not matter because the PLL is disabled. Changing them only sets up the multiply value for PLL usage in PBE mode.
  - c. BLPE: If transitioning through BLPE mode, clear C2[LP] to 0 here to switch to PBE mode.
  - d. PBE: Loop until S[PLLST] is set, indicating that the current source for the PLLS clock is the PLL.



#### mualization / Application Information

- e. PBE: Then loop until S[LOCK] is set, indicating that the PLL has acquired lock.
- 4. Lastly, PBE mode transitions into PEE mode:
  - a. C1 = 0x10
    - C1[CLKS] set to 2'b00 in order to select the output of the PLL as the system clock source.
  - b. Loop until S[CLKST] are 2'b11, indicating that the PLL output is selected to feed MCGOUTCLK in the current clock mode.
    - Now, With PRDIV of divide-by-2, and C6[VDIV] of multiply-by-24, MCGOUTCLK = [(4 MHz / 2) \* 24] = 48 MHz.






Figure 24-13. Flowchart of FEI to PEE Mode Transition using an 4 MHz crystal K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## 24.5.3.2 Example 2: Moving from PEE to BLPI Mode: MCGOUTCLK Frequency =32 kHz

In this example, the MCG will move through the proper operational modes from PEE mode with a 4 MHz crystal configured for a 48 MHz MCGOUTCLK frequency (see previous example) to BLPI mode with a 32 kHz MCGOUTCLK frequency. First, the code sequence will be described. Then a flowchart will be included which illustrates the sequence.

- 1. First, PEE must transition to PBE mode:
  - a. C1 = 0x90
    - C1[CLKS] set to 2'b10 in order to switch the system clock source to the external reference clock.
  - b. Loop until S[CLKST] are 2'b10, indicating that the external reference clock is selected to feed MCGOUTCLK.
- 2. Then, PBE must transition either directly to FBE mode or first through BLPE mode and then to FBE mode:
  - a. BLPE: If a transition through BLPE mode is desired, first set C2[LP] to 1
  - b. BLPE/FBE: C6 = 0x00
    - C6[PLLS] clear to 0 to select the FLL. At this time, with C1[FRDIV] value of 3'b010, the FLL divider is set to 128, resulting in a reference frequency of 4 MHz / 128 = 31.25 kHz. If C1[FRDIV] was not previously set to 3'b010 (necessary to achieve required 31.25-39.06 kHz FLL reference frequency with an 4 MHz external source frequency), it must be changed prior to clearing C6[PLLS] bit. In BLPE mode, changing this bit only prepares the MCG for FLL usage in FBE mode. With C6[PLLS] = 0, the C6[VDIV] value does not matter.
  - c. BLPE: If transitioning through BLPE mode, clear C2[LP] to 0 here to switch to FBE mode.
  - d. FBE: Loop until S[PLLST] is cleared, indicating that the current source for the PLLS clock is the FLL.
- 3. Next, FBE mode transitions into FBI mode:
  - a. C1 = 0x54



- C1[CLKS] set to 2'b01 in order to switch the system clock to the internal reference clock.
- C1[IREFS] set to 1 to select the internal reference clock as the reference clock source.
- C1[FRDIV] remain unchanged because the reference divider does not affect the internal reference.
- b. Loop until S[IREFST] is 1, indicating the internal reference clock has been selected as the reference clock source.
- c. Loop until S[CLKST] are 2'b01, indicating that the internal reference clock is selected to feed MCGOUTCLK.
- 4. Lastly, FBI transitions into BLPI mode.
  - a. C2 = 0x02
    - C2[LP] is 1
    - C2[RANGE], C2[HGO], C2[EREFS], C1[IRCLKEN], and C1[IREFSTEN] bits are ignored when the C1[IREFS] bit is set. They can remain set, or be cleared at this point.



#### mualization / Application Information




Figure 24-14. Flowchart of PEE to BLPI Mode Transition using an 4 MHz crystal



## 24.5.3.3 Example 3: Moving from BLPI to FEE Mode

In this example, the MCG will move through the proper operational modes from BLPI mode at a 32 kHz MCGOUTCLK frequency running off the internal reference clock (see previous example) to FEE mode using a 4 MHz crystal configured for a 20 MHz MCGOUTCLK frequency. First, the code sequence will be described. Then a flowchart will be included which illustrates the sequence.

- 1. First, BLPI must transition to FBI mode.
  - a. C2 = 0x00
    - C2[LP] is 0
- 2. Next, FBI will transition to FEE mode.
  - a. C2 = 0x1C
    - C2[RANGE] set to 2'b01 because the frequency of 4 MHz is within the high frequency range.
    - C2[HGO] set to 1 to configure the crystal oscillator for high gain operation.
    - C2[EREFS] set to 1, because a crystal is being used.
  - b. C1 = 0x10
    - C1[CLKS] set to 2'b00 in order to select the output of the FLL as system clock source.
    - C1[FRDIV] remain at 3'b010, or divide-by-128 for a reference of 4 MHz / 128 = 31.25 kHz.
    - C1[IREFS] cleared to 0, selecting the external reference clock.
  - c. Loop until S[OSCINIT] is 1, indicating the crystal selected by the C2[EREFS] bit has been initialized.
  - d. Loop until S[IREFST] is 0, indicating the external reference clock is the current source for the reference clock.
  - e. Loop until S[CLKST] are 2'b00, indicating that the output of the FLL is selected to feed MCGOUTCLK.
  - f. Now, with a 31.25 kHz reference frequency, a fixed DCO multiplier of 640, MCGOUTCLK = 31.25 kHz \* 640 / 1 = 20 MHz.
  - g. At this point, by default, the C4[DRST\_DRS] bits are set to 2'b00 and C4[DMX32] is cleared to 0. If the MCGOUTCLK frequency of 40 MHz is desired instead, set the C4[DRST\_DRS] bits to 0x01 to switch the FLL



#### mualization / Application Information

multiplication factor from 640 to 1280. To return the MCGOUTCLK frequency to 20 MHz, set C4[DRST\_DRS] bits to 2'b00 again, and the FLL multiplication factor will switch back to 640.




Figure 24-15. Flowchart of BLPI to FEE Mode Transition using an 4 MHz crystal



# **Chapter 25 Oscillator (OSC)**

#### 25.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The OSC module is a crystal oscillator. The module, in conjunction with an external crystal or resonator, generates a reference clock for the MCU.

#### 25.2 Features and Modes

Key features of the module are:

- Supports 32 kHz crystals (Low Range mode)
- Supports 3–8 MHz, 8–32 MHz crystals and resonators (High Range mode)
- Automatic Gain Control (AGC) to optimize power consumption in high frequency ranges 3–8 MHz, 8–32 MHz using low-power mode
- High gain option in frequency ranges: 32 kHz, 3–8 MHz, and 8–32 MHz
- Voltage and frequency filtering to guarantee clock frequency and stability
- Optionally external input bypass clock from EXTAL signal directly
- One clock for MCU clock system
- Two clocks for on-chip peripherals that can work in Stop modes

Functional Description describes the module's operation in more detail.



## 25.3 Block Diagram

The OSC module uses a crystal or resonator to generate three filtered oscillator clock signals. Three clocks are output from OSC module: OSCCLK for MCU system, OSCERCLK for on-chip peripherals, and OSC32KCLK. The OSCCLK can only work in run mode. OSCERCLK and OSC32KCLK can work in low power modes. For the clock source assignments, refer to the clock distribution information of this MCU.

Refer to the chip configuration chapter for the external reference clock source in this MCU.

The following figure shows the block diagram of the OSC module.




Figure 25-1. OSC Module Block Diagram

## 25.4 OSC Signal Descriptions

The following table shows the user-accessible signals available for the OSC module. Refer to signal multiplexing information for this MCU for more details.



Table 25-1. OSC Signal De	scriptions
---------------------------	------------

Signal	Description	I/O
EXTAL	External clock/Oscillator input	I
XTAL	Oscillator output	0

## 25.5 External Crystal / Resonator Connections

The connections for a crystal/resonator frequency reference are shown in the following figures. When using low-frequency, low-power mode, the only external component is the crystal or ceramic resonator itself. In the other oscillator modes, load capacitors  $(C_x, C_y)$  and feedback resistor  $(R_F)$  are required. The following table shows all possible connections.

Table 25-2. External Caystal/Resonator Connections

Oscillator Mode	Connections
Low-frequency (32 kHz), low-power	Connection 1
Low-frequency (32 kHz), high-gain	Connection 2/Connection 3 <sup>1</sup>
High-frequency (3~32 MHz), low-power	Connection 1/Connection 3 <sup>2,2</sup>
High-frequency (3~32 MHz), high-gain	Connection 2/Connection 3 <sup>2</sup>

- 1. When the load capacitors (Cx, Cy) are greater than 30 pF, use Connection 3.
- 2. With the low-power mode, the oscillator has the internal feedback resistor R<sub>F</sub>. Therefore, the feedback resistor must not be externally with the Connection 3.




Figure 25-2. Crystal/Ceramic Resonator Connections - Connection 1






Figure 25-3. Crystal/Ceramic Resonator Connections - Connection 2

#### **NOTE**

Connection 1 and Connection 2 should use internal capacitors as the load of the oscillator by configuring the CR[SCxP] bits.




Figure 25-4. Crystal/Ceramic Resonator Connections - Connection 3

#### 25.6 External Clock Connections

In external clock mode, the pins can be connected as shown below.

#### **NOTE**

XTAL can be used as a GPIO when the GPIO alternate function is configured for it.






Figure 25-5. External Clock Connections

## 25.7 Memory Map/Register Definitions

Some oscillator module register bits are typically incorporated into other peripherals such as MCG or SIM.

## 25.7.1 OSC Memory Map/Register Definition


#### **OSC** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_5000	OSC Control Register (OSC_CR)		R/W	00h	25.71.1/ 567

## 25.71.1 OSC Control Register (OSC\_CR)

After OSC is enabled and starts generating the clocks, the configurations such as low power and frequency range, must not be changed.

Address: OSC\_CR is 4006\_5000h base + 0h offset = 4006\_5000h



OSC\_CR field descriptions

Field	Description
7	External Reference Enable
ERCLKEN	Enables external reference clock (OSCERCLK).

Table continues on the next page...



#### runctional Description

## **OSC\_CR** field descriptions (continued)

Field	Description
	External reference clock is inactive.
	1 External reference clock is enabled.
6 Reserved	This read-only field is reserved and always has the value zero.
5 EREFSTEN	External Reference Stop Enable
	Controls whether or not the external reference clock (OSCERCLK) remains enabled when MCU enters Stop mode.
	0 External reference clock is disabled in Stop mode.
	1 External reference clock stays enabled in Stop mode if ERCLKEN is set before entering Stop mode.
4 Reserved	This read-only field is reserved and always has the value zero.
3 SC2P	Oscillator 2 pF Capacitor Load Configure
302F	Configures the oscillator load.
	0 Disable the selection.
	1 Add 2 pF capacitor to the oscillator load.
2	Oscillator 4 pF Capacitor Load Configure
SC4P	Configures the oscillator load.
	0 Disable the selection.
	1 Add 4 pF capacitor to the oscillator load.
1 SC8P	Oscillator 8 pF Capacitor Load Configure
	Configures the oscillator load.
	0 Disable the selection.
	1 Add 8 pF capacitor to the oscillator load.
0 SC16P	Oscillator 16 pF Capacitor Load Configure
	Configures the oscillator load.
	0 Disable the selection.
	1 Add 16 pF capacitor to the oscillator load.

## 25.8 Functional Description

This following sections provide functional details of the module.



#### 25.8.1 OSC Module States

The states of the OSC module are shown in the following figure. The states and their transitions between each other are described in this section.




Figure 25-7. OSC Module State Diagram
NOTE

XTL\_CLK is the clock generated internally from OSC circuits.

#### 25.8.1.1 Off

The OSC enters the Off state when the system does not require OSC clocks. Upon entering this state, XTL\_CLK is static unless OSC is configured to select the clock from the EXTAL pad by clearing the external reference clock selection bit. For details regarding the external reference clock source in this MCU, refer to the chip configuration chapter. The EXTAL and XTAL pins are also decoupled from all other oscillator circuitry in this state. The OSC module circuitry is configured to draw minimal current.



#### 25.8.1.2 Oscillator Start-Up

The OSC enters start-up state when it is configured to generate clocks (internally the OSC\_EN transitions high) using the internal oscillator circuits by setting the external reference clock selection bit. In this state, the OSC module is enabled and oscillations are starting up, but have not yet stabilized. When the oscillation amplitude becomes large enough to pass through the input buffer, XTL\_CLK begins clocking the counter. When the counter reaches 4096 cycles of XTL\_CLK, the oscillator is considered stable and XTL\_CLK is passed to the output clock OSC\_CLK\_OUT.

#### 25.8.1.3 Oscillator Stable

The OSC enters stable state when it is configured to generate clocks (internally the OSC\_EN transitions high) using the internal oscillator circuits by setting the external reference clock selection bit and the counter reaches 4096 cycles of XTL\_CLK (when CNT\_DONE\_4096 is high). In this state, the OSC module is producing a stable output clock on OSC\_CLK\_OUT. Its frequency is determined by the external components being used.

#### 25.8.1.4 External Clock Mode

The OSC enters external clock state when it is enabled and external reference clock selection bit is cleared. For details regarding external reference clock source in this MCU, refer to the chip configuration chapter. In this state, the OSC module is set to buffer (with hysteresis) a clock from EXTAL onto the OSC\_CLK\_OUT. Its frequency is determined by the external clock being supplied.

#### 25.8.2 OSC Module Modes

The OSC is a Pierce-type oscillator that supports external crystals or resonators operating over the frequency ranges shown in Table 25-5. These modes assume the following conditions: OSC is enabled to generate clocks (OSC\_EN=1), configured to generate clocks internally (MCG\_C2[EREFS] = 1), and some or one of the other peripherals (MCG, Timer, and so on) is configured to use the oscillator output clock (OSC\_CLK\_OUT).



#### Table 25-5. Oscillator Modes

Mode	Frequency Range	
Low-frequency, high-gain	f <sub>osc_lo</sub> (1 kHz) up to f <sub>osc_lo</sub> (32.768 kHz)	
Low-frequency, low-power (VLP)		
High-frequency mode1, high-gain	f <sub>osc_hi_1</sub> (3 MHz) up to f <sub>osc_hi_1</sub> (8 MHz)	
High-frequency mode1, low-power		
High-frequency mode2, high-gain	f <sub>osc_hi_2</sub> (8 MHz) up to f <sub>osc_hi_2</sub> (32 MHz)	
High-frequency mode2, low-power		

#### NOTE

For information about low power modes of operation used in this chip and their alignment with some OSC modes, refer to the chip's Power Management details.

## 25.8.2.1 Low-Frequency, High-Gain Mode

In Low-frequency, high-gain mode, the oscillator uses a simple inverter-style amplifier. The gain is set to achieve rail-to-rail oscillation amplitudes.

The oscillator input buffer in this mode is single-ended. It provides low pass frequency filtering as well as hysteresis for voltage filtering and converts the output to logic levels. In this mode, the internal capacitors could be used.

#### 25.8.2.2 Low-Frequency, Low-Power Mode

In low-frequency, low-power mode, the oscillator uses a gain control loop to minimize power consumption. As the oscillation amplitude increases, the amplifier current is reduced. This continues until a desired amplitude is achieved at steady-state. This mode provides low pass frequency filtering as well as hysteresis for voltage filtering and converts the output to logic levels. In this mode, the internal capacitors could be used, the internal feedback resistor is connected, and no external resistor should be used.

In this mode, the amplifier inputs, gain-control input, and input buffer input are all capacitively coupled for leakage tolerance (not sensitive to the DC level of EXTAL).

Also in this mode, all external components except for the resonator itself are integrated, which includes the load capacitors and feeback resistor that biases EXTAL.



nese

#### 25.8.2.3 High-Frequency, High-Gain Mode

In high-frequency, high-gain mode, the oscillator uses a simple inverter-style amplifier. The gain is set to achieve rail-to-rail oscillation amplitudes. This mode provides low pass frequency filtering as well as hysteresis for voltage filtering and converts the output to logic levels. In this mode, the internal capacitors could be used.

#### 25.8.2.4 High-Frequency, Low-Power Mode

In high-frequency, low-power mode, the oscillator uses a gain control loop to minimize power consumption. As the oscillation amplitude increases, the amplifier current is reduced. This continues until a desired amplitude is achieved at steady-state. In this mode, the internal capacitors could be used, the internal feedback resistor is connected, and no external resistor should be used.

The oscillator input buffer in this mode is differential. It provides low pass frequency filtering as well as hysteresis for voltage filtering and converts the output to logic levels.

#### 25.8.3 Counter

The oscillator output clock (OSC\_CLK\_OUT) is gated off until the counter has detected 4096 cycles of its input clock (XTL\_CLK). After 4096 cycles are completed, the counter passes XTL\_CLK onto OSC\_CLK\_OUT. This counting time-out is used to guarantee output clock stability.

## 25.8.4 Reference Clock Pin Requirements

The OSC module requires use of both the EXTAL and XTAL pins to generate an output clock in Oscillator mode, but requires only the EXTAL pin in External clock mode. The EXTAL and XTAL pins are available for I/O. For the implementation of these pins on this device, refer to the Signal Multiplexing chapter.

#### 25.9 Reset

There is no reset state associated with the OSC module. The counter logic is reset when the OSC is not configured to generate clocks.

There are no sources of reset requests for the OSC module.



## 25.10 Low Power Modes Operation

When the MCU enters Stop modes, the OSC is functional depending on ERCLKEN and EREFSETN bit settings. If both these bits are set, the OSC is in operation. In Low Leakage Stop (LLS) modes, the OSC holds all register settings. If ERCLKEN and EREFSTEN bits are set before entry to Low Leakage Stop modes, the OSC is still functional in these modes. After waking up from Very Low Leakage Stop (VLLSx) modes, all OSC register bits are reset and initialization is required through software.

## 25.11 Interrupts

The OSC module does not generate any interrupts.



merrupts



# Chapter 26 RTC Oscillator

#### 26.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The RTC oscillator module provides the clock source for the RTC. The RTC oscillator module, in conjunction with an external crystal, generates a reference clock for the RTC.

#### 26.1.1 Features and Modes

The key features of the RTC oscillator are as follows:

- Supports 32 kHz crystals with very low power
- Consists of internal feed back resistor
- Consists of internal programmable capacitors as the Cload of the oscillator
- Automatic Gain Control (AGC) to optimize power consumption

The RTC oscillator operations are described in detail in Functional Description.

## 26.1.2 Block Diagram

The following is the block diagram of the RTC oscillator.






Figure 26-1. RTC Oscillator Block Diagram

## 26.2 RTC Signal Descriptions

The following table shows the user-accessible signals available for the RTC oscillator. See the chip-level specification to find out which signals are actually connected to the external pins.

Table 26-1. RTC Signal Descriptions

Signal	Description	I/O
EXTAL32	Oscillator Input	1
XTAL32	Oscillator Output	0

## 26.2.1 EXTAL32 — Oscillator Input

This signal is the analog input of the RTC oscillator.

## 26.2.2 XTAL32 — Oscillator Output

This signal is the analog output of the RTC oscillator module.



# 26.3 External Crystal Connections

The connections with a crystal is shown in the following figure. External load capacitors and feedback resistor are not required.




Figure 26-2. Crystal Connections

# 26.4 Memory Map/Register Descriptions

RTC oscillator control bits are part of the RTC registers. Refer to RTC\_CR for more details.

# 26.5 Functional Description

As shown in Figure 26-1, the module includes an amplifier which supplies the negative resistor for the RTC oscillator. The gain of the amplifier is controlled by the amplitude detector, which optimizes the power consumption. A schmitt trigger is used to translate the sine-wave generated by this oscillator to a pulse clock out, which is a reference clock for the RTC digital core.

The oscillator includes an internal feedback resistor of approximately  $100 \text{ M}\Omega$  between EXTAL32 and XTAL32.

In addition, there are two programmable capacitors with this oscillator, which can be used as the Cload of the oscillator. The programmable range is from 0pF to 30pF.



# 26.6 Reset Overview

There is no reset state associated with the RTC oscillator.

# 26.7 Interrupts

The RTC oscillator does not generate any interrupts.



# **Chapter 27 Flash Memory Controller (FMC)**

### 27.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The Flash Memory Controller (FMC) is a memory acceleration unit that provides:

- an interface between the device and the dual-bank nonvolatile memory.
- buffers that can accelerate flash memory transfers.

### **27.1.1 Overview**

The Flash Memory Controller manages the interface between the device and the dualbank flash memory. The FMC receives status information detailing the configuration of the memory and uses this information to ensure a proper interface. The following table shows the supported 8-bit, 16-bit, and 32-bit read/write operations.

Flash memory type	Read	Write
Program flash memory	x	_1

<sup>1.</sup> A write operation to program flash memory results in a bus error.

In addition, for bank 0 and bank 1, the FMC provides three separate mechanisms for accelerating the interface between the device and the flash memory. A 64-bit speculation buffer can prefetch the next 64-bit flash memory location, and both a 4-way, 8-set cache and a single-entry 64-bit buffer can store previously accessed flash memory data for quick access times.

### 27.1.2 Features

The FMC's features include:



#### woues of operation

- Interface between the device and the dual-bank flash memory:
  - 8-bit, 16-bit, and 32-bit read operations to program flash memory.
  - For bank 0 and bank 1: Read accesses to consecutive 32-bit spaces in memory return the second read data with no wait states. The memory returns 64 bits via the 32-bit bus access.
  - Crossbar master access protection for setting no access, read only access, write only access, or read/write access for each crossbar master.
- For bank 0 and bank 1: Acceleration of data transfer from program flash memory to the device:
  - 64-bit prefetch speculation buffer with controls for instruction/data access per master and bank
  - 4-way, 8-set, 64-bit line size cache for a total of thirty-two 64-bit entries with controls for replacement algorithm and lock per way for each bank
  - Single-entry buffer with enable per bank
  - Invalidation control for the speculation buffer and the single-entry buffer

# 27.2 Modes of operation

The FMC only operates when the device accesses the flash memory.

In terms of device power modes, the FMC only operates in run and wait modes, including VLPR and VLPW modes.

For any device power mode where the flash memory cannot be accessed, the FMC is disabled.

# 27.3 External signal description

The FMC has no external signals.

# 27.4 Memory map and register descriptions

The programming model consists of the FMC control registers and the program visible cache (data and tag/valid entries).



#### NOTE

Program the registers only while the flash controller is idle (for example, execute from RAM). Changing configuration settings while a flash access is in progress can lead to non-deterministic behavior.

Table 27-2. FMC register access

Registers	Read	access	Write access		
	Mode	Length	Mode	Length	
Control registers: PFAPR, PFB0CR, PFB1CR	Supervisor (privileged) mode or user mode	32 bits	Supervisor (privileged) mode only	8, 16, or 32 bits	
Cache registers	Supervisor (privileged) mode or user mode	32 bits	Supervisor (privileged) mode only	32 bits	

#### NOTE

Accesses to unimplemented registers within the FMC's 4 KB address space return a bus error.

The cache entries, both data and tag/valid, can be read at any time.

#### NOTE

System software is required to maintain memory coherence when any segment of the flash cache is programmed. For example, all buffer data associated with the reprogrammed flash should be invalidated. Accordingly, cache program visible writes must occur after a programming or erase event is completed and before the new memory image is accessed.

The cache is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. The following table elaborates on the tag/valid and data entries.

Table 27-3. Program visible cache registers

Cache storage	Based at offset	Contents of 32-bit read	Nomenclature	Nomenclature example
Tag	100h	13'h0, tag[18:6], 5'h0, valid	In TAGVDWxSy, x denotes the way and y denotes the set.	TAGVDW2S0 is the 13-bit tag and 1-bit valid for cache entry way 2, set 0.
Data	200h	Upper or lower word of data	In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively.	DATAW1S0U represents bits [63:32] of data entry way 1, set 0, and DATAW1S0L represents bits [31:0] of data entry way 1, set 0.



#### wemory map and register descriptions

### **FMC** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4001_F000	Flash Access Protection Register (FMC_PFAPR)	32	R/W	00F8_003Fh	27.4.1/ 587
4001_F004	Flash Bank 0 Control Register (FMC_PFB0CR)	32	R/W	3002_001Fh	27.4.2/ 590
4001_F008	Flash Bank 1 Control Register (FMC_PFB1CR)	32	R/W	3002_001Fh	27.4.3/ 592
4001_F100	Cache Tag Storage (FMC_TAGVDW0S0)	32	R/W	0000_0000h	27.4.4/ 594
4001_F104	Cache Tag Storage (FMC_TAGVDW0S1)	32	R/W	0000_0000h	27.4.4/ 594
4001_F108	Cache Tag Storage (FMC_TAGVDW0S2)	32	R/W	0000_0000h	27.4.4/ 594
4001_F10C	Cache Tag Storage (FMC_TAGVDW0S3)	32	R/W	0000_0000h	27.4.4/ 594
4001_F110	Cache Tag Storage (FMC_TAGVDW0S4)	32	R/W	0000_0000h	27.4.4/ 594
4001_F114	Cache Tag Storage (FMC_TAGVDW0S5)	32	R/W	0000_0000h	27.4.4/ 594
4001_F118	Cache Tag Storage (FMC_TAGVDW0S6)	32	R/W	0000_0000h	27.4.4/ 594
4001_F11C	Cache Tag Storage (FMC_TAGVDW0S7)	32	R/W	0000_0000h	27.4.4/ 594
4001_F120	Cache Tag Storage (FMC_TAGVDW1S0)	32	R/W	0000_0000h	27.4.5/ 595
4001_F124	Cache Tag Storage (FMC_TAGVDW1S1)	32	R/W	0000_0000h	27.4.5/ 595
4001_F128	Cache Tag Storage (FMC_TAGVDW1S2)	32	R/W	0000_0000h	27.4.5/ 595
4001_F12C	Cache Tag Storage (FMC_TAGVDW1S3)	32	R/W	0000_0000h	27.4.5/ 595
4001_F130	Cache Tag Storage (FMC_TAGVDW1S4)	32	R/W	0000_0000h	27.4.5/ 595
4001_F134	Cache Tag Storage (FMC_TAGVDW1S5)	32	R/W	0000_0000h	27.4.5/ 595
4001_F138	Cache Tag Storage (FMC_TAGVDW1S6)	32	R/W	0000_0000h	27.4.5/ 595
4001_F13C	Cache Tag Storage (FMC_TAGVDW1S7)	32	R/W	0000_0000h	27.4.5/ 595
4001_F140	Cache Tag Storage (FMC_TAGVDW2S0)	32	R/W	0000_0000h	27.4.6/ 596



# FMC memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4001_F144	Cache Tag Storage (FMC_TAGVDW2S1)	32	R/W	0000_0000h	27.4.6/ 596
4001_F148	Cache Tag Storage (FMC_TAGVDW2S2)	32	R/W	0000_0000h	27.4.6/ 596
4001_F14C	Cache Tag Storage (FMC_TAGVDW2S3)	32	R/W	0000_0000h	27.4.6/ 596
4001_F150	Cache Tag Storage (FMC_TAGVDW2S4)	32	R/W	0000_0000h	27.4.6/ 596
4001_F154	Cache Tag Storage (FMC_TAGVDW2S5)	32	R/W	0000_0000h	27.4.6/ 596
4001_F158	Cache Tag Storage (FMC_TAGVDW2S6)	32	R/W	0000_0000h	27.4.6/ 596
4001_F15C	Cache Tag Storage (FMC_TAGVDW2S7)	32	R/W	0000_0000h	27.4.6/ 596
4001_F160	Cache Tag Storage (FMC_TAGVDW3S0)	32	R/W	0000_0000h	27.4.7/ 597
4001_F164	Cache Tag Storage (FMC_TAGVDW3S1)	32	R/W	0000_0000h	27.4.7/ 597
4001_F168	Cache Tag Storage (FMC_TAGVDW3S2)	32	R/W	0000_0000h	27.4.7/ 597
4001_F16C	Cache Tag Storage (FMC_TAGVDW3S3)	32	R/W	0000_0000h	27.4.7/ 597
4001_F170	Cache Tag Storage (FMC_TAGVDW3S4)	32	R/W	0000_0000h	27.4.7/ 597
4001_F174	Cache Tag Storage (FMC_TAGVDW3S5)	32	R/W	0000_0000h	27.4.7/ 597
4001_F178	Cache Tag Storage (FMC_TAGVDW3S6)	32	R/W	0000_0000h	27.4.7/ 597
4001_F17C	Cache Tag Storage (FMC_TAGVDW3S7)	32	R/W	0000_0000h	27.4.7/ 597
4001_F200	Cache Data Storage (upper word) (FMC_DATAW0S0U)	32	R/W	0000_0000h	27.4.8/ 598
4001_F204	Cache Data Storage (lower word) (FMC_DATAW0S0L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F208	Cache Data Storage (upper word) (FMC_DATAW0S1U)	32	R/W	0000_0000h	27.4.8/ 598
4001_F20C	Cache Data Storage (lower word) (FMC_DATAW0S1L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F210	Cache Data Storage (upper word) (FMC_DATAW0S2U)	32	R/W	0000_0000h	27.4.8/ 598



#### wemory map and register descriptions

# FMC memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4001_F214	Cache Data Storage (lower word) (FMC_DATAW0S2L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F218	Cache Data Storage (upper word) (FMC_DATAW0S3U)	32	R/W	0000_0000h	27.4.8/ 598
4001_F21C	Cache Data Storage (lower word) (FMC_DATAW0S3L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F220	Cache Data Storage (upper word) (FMC_DATAW0S4U)	32	R/W	0000_0000h	27.4.8/ 598
4001_F224	Cache Data Storage (lower word) (FMC_DATAW0S4L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F228	Cache Data Storage (upper word) (FMC_DATAW0S5U)	32	R/W	0000_0000h	27.4.8/ 598
4001_F22C	Cache Data Storage (lower word) (FMC_DATAW0S5L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F230	Cache Data Storage (upper word) (FMC_DATAW0S6U)	32	R/W	0000_0000h	27.4.8/ 598
4001_F234	Cache Data Storage (lower word) (FMC_DATAW0S6L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F238	Cache Data Storage (upper word) (FMC_DATAW0S7U)	32	R/W	0000_0000h	27.4.8/ 598
4001_F23C	Cache Data Storage (lower word) (FMC_DATAW0S7L)	32	R/W	0000_0000h	27.4.9/ 599
4001_F240	Cache Data Storage (upper word) (FMC_DATAW1S0U)	32	R/W	0000_0000h	27.4.10/ 600
4001_F244	Cache Data Storage (lower word) (FMC_DATAW1S0L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F248	Cache Data Storage (upper word) (FMC_DATAW1S1U)	32	R/W	0000_0000h	27.4.10/ 600
4001_F24C	Cache Data Storage (lower word) (FMC_DATAW1S1L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F250	Cache Data Storage (upper word) (FMC_DATAW1S2U)	32	R/W	0000_0000h	27.4.10/ 600
4001_F254	Cache Data Storage (lower word) (FMC_DATAW1S2L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F258	Cache Data Storage (upper word) (FMC_DATAW1S3U)	32	R/W	0000_0000h	27.4.10/ 600
4001_F25C	Cache Data Storage (lower word) (FMC_DATAW1S3L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F260	Cache Data Storage (upper word) (FMC_DATAW1S4U)	32	R/W	0000_0000h	27.4.10/ 600



# FMC memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4001_F264	Cache Data Storage (lower word) (FMC_DATAW1S4L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F268	Cache Data Storage (upper word) (FMC_DATAW1S5U)	32	R/W	0000_0000h	27.4.10/ 600
4001_F26C	Cache Data Storage (lower word) (FMC_DATAW1S5L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F270	Cache Data Storage (upper word) (FMC_DATAW1S6U)	32	R/W	0000_0000h	27.4.10/ 600
4001_F274	Cache Data Storage (lower word) (FMC_DATAW1S6L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F278	Cache Data Storage (upper word) (FMC_DATAW1S7U)	32	R/W	0000_0000h	27.4.10/ 600
4001_F27C	Cache Data Storage (lower word) (FMC_DATAW1S7L)	32	R/W	0000_0000h	27.4.11/ 601
4001_F280	Cache Data Storage (upper word) (FMC_DATAW2S0U)	32	R/W	0000_0000h	27.4.12/ 602
4001_F284	Cache Data Storage (lower word) (FMC_DATAW2S0L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F288	Cache Data Storage (upper word) (FMC_DATAW2S1U)	32	R/W	0000_0000h	27.4.12/ 602
4001_F28C	Cache Data Storage (lower word) (FMC_DATAW2S1L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F290	Cache Data Storage (upper word) (FMC_DATAW2S2U)	32	R/W	0000_0000h	27.4.12/ 602
4001_F294	Cache Data Storage (lower word) (FMC_DATAW2S2L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F298	Cache Data Storage (upper word) (FMC_DATAW2S3U)	32	R/W	0000_0000h	27.4.12/ 602
4001_F29C	Cache Data Storage (lower word) (FMC_DATAW2S3L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F2A0	Cache Data Storage (upper word) (FMC_DATAW2S4U)	32	R/W	0000_0000h	27.4.12/ 602
4001_F2A4	Cache Data Storage (lower word) (FMC_DATAW2S4L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F2A8	Cache Data Storage (upper word) (FMC_DATAW2S5U)	32	R/W	0000_0000h	27.4.12/ 602
4001_F2AC	Cache Data Storage (lower word) (FMC_DATAW2S5L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F2B0	Cache Data Storage (upper word) (FMC_DATAW2S6U)	32	R/W	0000_0000h	27.4.12/ 602



#### wemory map and register descriptions


# FMC memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4001_F2B4	Cache Data Storage (lower word) (FMC_DATAW2S6L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F2B8	Cache Data Storage (upper word) (FMC_DATAW2S7U)	32	R/W	0000_0000h	27.4.12/ 602
4001_F2BC	Cache Data Storage (lower word) (FMC_DATAW2S7L)	32	R/W	0000_0000h	27.4.13/ 603
4001_F2C0	Cache Data Storage (upper word) (FMC_DATAW3S0U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2C4	Cache Data Storage (lower word) (FMC_DATAW3S0L)	32	R/W	0000_0000h	27.4.15/ 605
4001_F2C8	Cache Data Storage (upper word) (FMC_DATAW3S1U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2CC	Cache Data Storage (lower word) (FMC_DATAW3S1L)	32	R/W	0000_0000h	27.4.15/ 605
4001_F2D0	Cache Data Storage (upper word) (FMC_DATAW3S2U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2D4	Cache Data Storage (lower word) (FMC_DATAW3S2L)	32	R/W	0000_0000h	27.4.15/ 605
4001_F2D8	Cache Data Storage (upper word) (FMC_DATAW3S3U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2DC	Cache Data Storage (lower word) (FMC_DATAW3S3L)	32	R/W	0000_0000h	27.4.15/ 605
4001_F2E0	Cache Data Storage (upper word) (FMC_DATAW3S4U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2E4	Cache Data Storage (lower word) (FMC_DATAW3S4L)	32	R/W	0000_0000h	27.4.15/ 605
4001_F2E8	Cache Data Storage (upper word) (FMC_DATAW3S5U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2EC	Cache Data Storage (lower word) (FMC_DATAW3S5L)	32	R/W	0000_0000h	27.4.15/ 605
4001_F2F0	Cache Data Storage (upper word) (FMC_DATAW3S6U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2F4	Cache Data Storage (lower word) (FMC_DATAW3S6L)	32	R/W	0000_0000h	27.4.15/ 605
4001_F2F8	Cache Data Storage (upper word) (FMC_DATAW3S7U)	32	R/W	0000_0000h	27.4.14/ 604
4001_F2FC	Cache Data Storage (lower word) (FMC_DATAW3S7L)	32	R/W	0000_0000h	27.4.15/ 605



# 27.4.1 Flash Access Protection Register (FMC\_PFAPR)

Address: FMC\_PFAPR is 4001\_F000h base + 0h offset = 4001\_F000h



#### **FMC\_PFAPR** field descriptions

Field	Description
31–24 Reserved	This read-only field is reserved and always has the value zero.
23 M7PFD	Master 7 Prefetch Disable  These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.  O Prefetching for this master is enabled.  1 Prefetching for this master is disabled.
22 M6PFD	Master 6 Prefetch Disable  These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.  0 Prefetching for this master is enabled.  1 Prefetching for this master is disabled.
21 M5PFD	Master 5 Prefetch Disable  These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.  0 Prefetching for this master is enabled. 1 Prefetching for this master is disabled.
20 M4PFD	Master 4 Prefetch Disable  These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.



#### wemory map and register descriptions

# FMC\_PFAPR field descriptions (continued)

Field	Description
	0 Prefetching for this master is enabled.
	1 Prefetching for this master is disabled.
19 M3PFD	Master 3 Prefetch Disable
IIIOI I D	These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.
	0 Prefetching for this master is enabled.
	1 Prefetching for this master is disabled.
18 M2PFD	Master 2 Prefetch Disable
	These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.
	0 Prefetching for this master is enabled.
	1 Prefetching for this master is disabled.
17 M1PFD	Master 1 Prefetch Disable
WIIITD	These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.
	0 Prefetching for this master is enabled.
	1 Prefetching for this master is disabled.
16 M0PFD	Master 0 Prefetch Disable
WOLLD	These bits control whether prefetching is enabled based on the logical number of the requesting crossbar switch master. This field is further qualified by the PFBnCR[BxDPE,BxIPE] bits.
	0 Prefetching for this master is enabled.
	1 Prefetching for this master is disabled.
15–14 MZADI1:01	Master 7 Access Protection
M7AP[1:0]	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master.
	01 Only read accesses may be performed by this master.
	10 Only write accesses may be performed by this master.
	11 Both read and write accesses may be performed by this master.
13–12 M6AP[1:0]	Master 6 Access Protection
	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master
	01 Only read accesses may be performed by this master
	10 Only write accesses may be performed by this master
	11 Both read and write accesses may be performed by this master
11–10 M5AP[1:0]	Master 5 Access Protection



# FMC\_PFAPR field descriptions (continued)

Field	Description
	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master
	01 Only read accesses may be performed by this master
	10 Only write accesses may be performed by this master
	11 Both read and write accesses may be performed by this master
9–8 M4AP[1:0]	Master 4 Access Protection
	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master
	01 Only read accesses may be performed by this master
	10 Only write accesses may be performed by this master
	11 Both read and write accesses may be performed by this master
7–6	Master 3 Access Protection
M3AP[1:0]	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master
	01 Only read accesses may be performed by this master
	10 Only write accesses may be performed by this master
	11 Both read and write accesses may be performed by this master
5–4	Master 2 Access Protection
M2AP[1:0]	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master
	01 Only read accesses may be performed by this master
	10 Only write accesses may be performed by this master
	11 Both read and write accesses may be performed by this master
3–2 M1AP[1:0]	Master 1 Access Protection
	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master
	01 Only read accesses may be performed by this master
	10 Only write accesses may be performed by this master
	11 Both read and write accesses may be performed by this master
1–0 M0AP[1:0]	Master 0 Access Protection
	This field controls whether read and write access to the flash are allowed based on the logical master number of the requesting crossbar switch master.
	00 No access may be performed by this master
	01 Only read accesses may be performed by this master




#### wemory map and register descriptions

### FMC\_PFAPR field descriptions (continued)

Field	Description
	10 Only write accesses may be performed by this master
	11 Both read and write accesses may be performed by this master

### 27.4.2 Flash Bank 0 Control Register (FMC\_PFB0CR)

Address: FMC\_PFB0CR is 4001\_F000h base + 4h offset = 4001\_F004h



### FMC\_PFB0CR field descriptions

Field	Description
31–28	Bank 0 Read Wait State Control
B0RWSC[3:0]	This read-only field defines the number of wait states required to access the bank 0 flash memory.
	The relationship between the read access time of the flash array (expressed in system clock cycles) and RWSC is defined as:
	Access time of flash array [system clocks] = RWSC + 1
	The FMC automatically calculates this value based on the ratio of the system clock speed to the flash clock speed. For example, when this ratio is 4:1, the field's value is 3h.
27–24	Cache Lock Way x
CLCK_WAY[3:0]	These bits determine if the given cache way is locked such that its contents will not be displaced by future misses.
	The bit setting definitions are for each bit in the field.
	0 Cache way is unlocked and may be displaced
	1 Cache way is locked and its contents are not displaced
23–20	Cache Invalidate Way x
CINV_WAY[3:0]	These bits determine if the given cache way is to be invalidated (cleared). When a bit within this field is written, the corresponding cache way is immediately invalidated: the way's tag, data, and valid contents are cleared. This field always reads as zero.



# FMC\_PFB0CR field descriptions (continued)

Field	Description
	Cache invalidation takes precedence over locking. The cache is invalidated by system reset. System software is required to maintain memory coherency when any segment of the flash memory is programmed or erased. Accordingly, cache invalidations must occur after a programming or erase event is completed and before the new memory image is accessed.
	The bit setting definitions are for each bit in the field.
	<ul> <li>No cache way invalidation for the corresponding cache</li> <li>Invalidate cache way for the corresponding cache: clear the tag, data, and vld bits of ways selected</li> </ul>
19 S_B_INV	Invalidate Prefetch Speculation Buffer
0_8_1111	This bit determines if the FMC's prefetch speculation buffer and the single entry page buffer are to be invalidated (cleared). When this bit is written, the speculation buffer and single entry buffer are immediately cleared. This bit always reads as zero.
	Speculation buffer and single entry buffer are not affected.
	1 Invalidate (clear) speculation buffer and single entry buffer.
18–17	Bank 0 Memory Width
B0MW[1:0]	This read-only field defines the width of the bank 0 memory.
	00 32 bits
	01 64 bits
	1x Reserved
16 Reserved	This read-only field is reserved and always has the value zero.
15–8 Reserved	This read-only field is reserved and always has the value zero.
7–5	Cache Replacement Control
CRC[2:0]	This 3-bit field defines the replacement algorithm for accesses that are cached.
	000 LRU replacement algorithm per set across all four ways
	001 Reserved 010 Independent LRU with ways [0-1] for ifetches, [2-3] for data
	011 Independent LRU with ways [0-2] for ifetches, [3] for data
	1xx Reserved
4 B0DCE	Bank 0 Data Cache Enable
DUDUE	This bit controls whether data references are loaded into the cache.
	0 Do not cache data references.
	1 Cache data references.
3 BOICE	Bank 0 Instruction Cache Enable
BOIOL	This bit controls whether instruction fetches are loaded into the cache.
	0 Do not cache instruction fetches.
	1 Cache instruction fetches.



#### wemory map and register descriptions


### FMC\_PFB0CR field descriptions (continued)

Field	Description
2 B0DPE	Bank 0 Data Prefetch Enable
	This bit controls whether prefetches (or speculative accesses) are initiated in response to data references.
	0 Do not prefetch in response to data references.
	1 Enable prefetches in response to data references.
1 BOIPE	Bank 0 Instruction Prefetch Enable
BOIFE	This bit controls whether prefetches (or speculative accesses) are initiated in response to instruction fetches.
	0 Do not prefetch in response to instruction fetches.
	1 Enable prefetches in response to instruction fetches.
0	Bank 0 Single Entry Buffer Enable
BOSEBE	This bit controls whether the single entry page buffer is enabled in response to flash read accesses. Its operation is independent from bank 1's cache.
	A high-to-low transition of this enable forces the page buffer to be invalidated.
	0 Single entry buffer is disabled.
	1 Single entry buffer is enabled.

# 27.4.3 Flash Bank 1 Control Register (FMC\_PFB1CR)

This register has a format similar to that for PFB0CR, except it controls the operation of flash bank 1, and the "global" cache control fields are empty.

Address: FMC\_PFB1CR is 4001\_F000h base + 8h offset = 4001\_F008h



### FMC\_PFB1CR field descriptions

Field	Description
31–28 B1RWSC[3:0]	Bank 1 Read Wait State Control

Table continues on the next page...

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# FMC\_PFB1CR field descriptions (continued)

This read-only field defines the number of wait states required to access the bank 1 flash memory. The relationship between the read access time of the flash array (expressed in system clock cycles) a RWSC is defined as:  Access time of flash array [system clocks] = RWSC + 1  The FMC automatically calculates this value based on the ratio of the system clock speed to the flash clock speed. For example, when this ratio is 4:1, the field's value is 3h.  27–19 Reserved  18–17 B1MW[1:0]  Bank 1 Memory Width  This read-only field defines the width of the bank 1 memory.  00 32 bits 01 64 bits 10 Reserved 11 Reserved  16-Reserved  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  Reserved  4 Bank 1 Data Cache Enable  This bit controls whether data references are loaded into the cache.  0 Do not cache data references.  1 Cache data references.  2 Bank 1 Instruction Cache Enable  This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.  1 Cache instruction fetches.  1 Cache instruction fetches.	Field	Description
RWSC is defined as: Access time of flash array [system clocks] = RWSC + 1 The FMC automatically calculates this value based on the ratio of the system clock speed to the flash clock speed. For example, when this ratio is 4:1, the field's value is 3h.  27–19 Reserved  18–17 B1MW[1:0]  Bank 1 Memory Width This read-only field defines the width of the bank 1 memory.  00 32 bits 01 64 bits 10 Reserved 11 Reserved  15–8 Reserved  7–5 Reserved  7–5 Reserved  4 B1DCE  Bank 1 Data Cache Enable This bit controls whether data references. 1 Cache data references. 1 Cache data references. 1 Cache data references. This it controls whether instruction fetches are loaded into the cache. 0 Do not cache instruction fetches.		This read-only field defines the number of wait states required to access the bank 1 flash memory.
The FMC automatically calculates this value based on the ratio of the system clock speed to the flash clock speed. For example, when this ratio is 4:1, the field's value is 3h.  27–19 Reserved  18–17 B1MW[1:0]  Bank 1 Memory Width This read-only field defines the width of the bank 1 memory.  00 32 bits 01 64 bits 10 Reserved 11 Reserved  This read-only field is reserved and always has the value zero.  15–8 Reserved  7–5 Reserved  4 B1DCE  Bank 1 Data Cache Enable This bit controls whether data references. 1 Cache data references. 1 Cache data references. 2 Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache. 0 Do not cache instruction fetches are loaded into the cache. 0 Do not cache instruction fetches.		The relationship between the read access time of the flash array (expressed in system clock cycles) and RWSC is defined as:
clock speed. For example, when this ratio is 4:1, the field's value is 3h.  27–19 Reserved  18–17 B1MW[1:0]  Bank 1 Memory Width  This read-only field defines the width of the bank 1 memory.  00 32 bits 01 64 bits 10 Reserved 11 Reserved  16 Reserved  15–8 Reserved  7–5 Reserved  4 B1DCE  Bank 1 Data Cache Enable This bit controls whether instruction fetches are loaded into the cache.  3 B1ICE  This read-only whether instruction fetches.		Access time of flash array [system clocks] = RWSC + 1
Reserved  18–17 B1MW[1:0]  Bank 1 Memory Width  This read-only field defines the width of the bank 1 memory.  00 32 bits 01 64 bits 10 Reserved 11 Reserved  11 Reserved  This read-only field is reserved and always has the value zero.  Reserved  15–8 Reserved  7–5 Reserved  4 B1DCE  Bank 1 Data Cache Enable  This bit controls whether data references are loaded into the cache.  0 Do not cache data references. 1 Cache data references.  3 B1ICE  Bank 1 Instruction Cache Enable  This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches are loaded into the cache.		
B1MW[1:0]  This read-only field defines the width of the bank 1 memory.  00 32 bits 01 64 bits 10 Reserved 11 Reserved  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  T-5 Reserved  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  Bank 1 Data Cache Enable  This bit controls whether data references are loaded into the cache.  0 Do not cache data references.  1 Cache data references.  Bank 1 Instruction Cache Enable  This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.	-	This read-only field is reserved and always has the value zero.
This read-only field defines the width of the bank 1 memory.  00 32 bits 01 64 bits 10 Reserved 11 Reserved  This read-only field is reserved and always has the value zero.  Reserved  15–8 Reserved  7–5 Reserved  4 B1DCE  Bank 1 Data Cache Enable This bit controls whether data references. 1 Cache data references. 1 Cache data references. 3 B1ICE  This read-only field is reserved and always has the value zero. 0 Do not cache Enable This bit controls whether data references are loaded into the cache. 0 Do not cache data references.	-	Bank 1 Memory Width
01 64 bits 10 Reserved 11 Reserved  16 Reserved  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  Bank 1 Data Cache Enable This bit controls whether data references are loaded into the cache.  Do not cache data references.  Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache.  Do not cache instruction fetches.	B1MW[1:0]	This read-only field defines the width of the bank 1 memory.
01 64 bits 10 Reserved 11 Reserved  16 Reserved  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  Reserved  Bank 1 Data Cache Enable This bit controls whether data references are loaded into the cache.  Do not cache data references. 1 Cache data references. 3 Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache.  Do not cache instruction fetches.		00 32 bits
11 Reserved  16 Reserved  15–8 Reserved  7–5 Reserved  4 B1DCE  This read-only field is reserved and always has the value zero.  8 Bank 1 Data Cache Enable  This bit controls whether data references are loaded into the cache.  0 Do not cache data references. 1 Cache data references. 2 Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache. 0 Do not cache instruction fetches.		
This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  This read-only field is reserved and always has the value zero.  Bank 1 Data Cache Enable  This bit controls whether data references are loaded into the cache.  Do not cache data references.  Cache data references.  Bank 1 Instruction Cache Enable  This bit controls whether instruction fetches are loaded into the cache.  Do not cache instruction fetches.		10 Reserved
Reserved  15–8 Reserved  7–5 Reserved  4 B1DCE  Bank 1 Data Cache Enable This bit controls whether data references are loaded into the cache.  0 Do not cache data references. 1 Cache data references. 2 Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.		11 Reserved
Reserved  7–5 Reserved  4 Bank 1 Data Cache Enable This bit controls whether data references are loaded into the cache.  0 Do not cache data references. 1 Cache data references. 1 Data Cache Enable This bit controls whether data references. 1 Cache data references. 1 Data Cache Enable This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.	-	This read-only field is reserved and always has the value zero.
Reserved  4 B1DCE  Bank 1 Data Cache Enable  This bit controls whether data references are loaded into the cache.  0 Do not cache data references.  1 Cache data references.  3 B1ICE  Bank 1 Instruction Cache Enable  This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.		This read-only field is reserved and always has the value zero.
B1DCE  This bit controls whether data references are loaded into the cache.  0 Do not cache data references. 1 Cache data references.  Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.	-	This read-only field is reserved and always has the value zero.
This bit controls whether data references are loaded into the cache.  0 Do not cache data references. 1 Cache data references.  3 Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.	-	Bank 1 Data Cache Enable
1 Cache data references.  3 Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.	B1DCE	This bit controls whether data references are loaded into the cache.
Bank 1 Instruction Cache Enable This bit controls whether instruction fetches are loaded into the cache.  Do not cache instruction fetches.		
B1ICE This bit controls whether instruction fetches are loaded into the cache.  0 Do not cache instruction fetches.		1 Cache data references.
This bit controls whether instruction fetches are loaded into the cache.  O Do not cache instruction fetches.		Bank 1 Instruction Cache Enable
	BIICE	This bit controls whether instruction fetches are loaded into the cache.
1 Cache instruction fetches.		
2 Bank 1 Data Prefetch Enable B1DPE		Bank 1 Data Prefetch Enable
	DIDFE	This bit controls whether prefetches (or speculative accesses) are initiated in response to data references.
0 Do not prefetch in response to data references.		
1 Enable prefetches in response to data references.		1 Enable prefetches in response to data references.
1 Bank 1 Instruction Prefetch Enable B1IPE		Bank 1 Instruction Prefetch Enable
This bit controls whether prefetches (or speculative accesses) are initiated in response to instruction fetches.	DIIPE	
0 Do not prefetch in response to instruction fetches.		0 Do not prefetch in response to instruction fetches.
1 Enable prefetches in response to instruction fetches.		




#### memory map and register descriptions

#### FMC\_PFB1CR field descriptions (continued)

Field	Description
0 B1SEBE	Bank 1 Single Entry Buffer Enable  This bit controls whether the single entry buffer is enabled in response to flash read accesses. Its operation is independent from bank 0's cache.  A high-to-low transition of this enable forces the page buffer to be invalidated.  O Single entry buffer is disabled.
	<ul><li>Single entry buffer is disabled.</li><li>Single entry buffer is enabled.</li></ul>

### 27.4.4 Cache Tag Storage (FMC\_TAGVDW0Sn)

The 32-entry cache is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In TAGVDWxSy, x denotes the way, and y denotes the set. This section represents tag/vld information for all 8 sets (n=0-7) in way 0.



### FMC\_TAGVDW0Sn field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18–6 tag[18:6]	13-bit tag for cache entry
5–1 Reserved	This read-only field is reserved and always has the value zero.
0 valid	1-bit valid for cache entry



# 27.4.5 Cache Tag Storage (FMC\_TAGVDW1Sn)

The 32-entry cache is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In TAGVDWxSy, x denotes the way, and y denotes the set. This section represents tag/vld information for all 8 sets (n=0-7) in way 1.

```
Addresses: FMC_TAGVDW1S0 is 4001_F000h base + 120h offset = 4001_F120h
           FMC_TAGVDW1S1 is 4001_F000h base + 124h offset = 4001_F124h
           FMC_TAGVDW1S2 is 4001_F000h base + 128h offset = 4001_F128h
           FMC_TAGVDW1S3 is 4001_F000h base + 12Ch offset = 4001_F12Ch
           FMC_TAGVDW1S4 is 4001_F000h base + 130h offset = 4001_F130h
           FMC_TAGVDW1S5 is 4001_F000h base + 134h offset = 4001_F134h
           FMC_TAGVDW1S6 is 4001_F000h base + 138h offset = 4001_F138h
           FMC_TAGVDW1S7 is 4001_F000h base + 13Ch offset = 4001_F13Ch
    31 30 29 28 27 26 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10
 Bit
 R
                        0
                                                                                                0
                                                                                                          valid
                                                               tag[18:6]
 W
Reset 0
                                                     0 0
```


#### FMC\_TAGVDW1Sn field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18-6 tag[18:6]	13-bit tag for cache entry
5–1 Reserved	This read-only field is reserved and always has the value zero.
0 valid	1-bit valid for cache entry



# 27.4.6 Cache Tag Storage (FMC\_TAGVDW2Sn)

The 32-entry cache is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In TAGVDWxSy, x denotes the way, and y denotes the set. This section represents tag/vld information for all 8 sets (n=0-7) in way 2.



### FMC\_TAGVDW2Sn field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18-6 tag[18:6]	13-bit tag for cache entry
5–1 Reserved	This read-only field is reserved and always has the value zero.
0 valid	1-bit valid for cache entry



# 27.4.7 Cache Tag Storage (FMC\_TAGVDW3Sn)

The 32-entry cache is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In TAGVDWxSy, x denotes the way, and y denotes the set. This section represents tag/vld information for all 8 sets (n=0-7) in way 3.

```
Addresses: FMC_TAGVDW3S0 is 4001_F000h base + 160h offset = 4001_F160h
           FMC_TAGVDW3S1 is 4001_F000h base + 164h offset = 4001_F164h
           FMC_TAGVDW3S2 is 4001_F000h base + 168h offset = 4001_F168h
           FMC_TAGVDW3S3 is 4001_F000h base + 16Ch offset = 4001_F16Ch
           FMC_TAGVDW3S4 is 4001_F000h base + 170h offset = 4001_F170h
           FMC_TAGVDW3S5 is 4001_F000h base + 174h offset = 4001_F174h
           FMC_TAGVDW3S6 is 4001_F000h base + 178h offset = 4001_F178h
           FMC_TAGVDW3S7 is 4001_F000h base + 17Ch offset = 4001_F17Ch
    31 30 29 28 27 26 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10
 Bit
 R
                        0
                                                                                                0
                                                                                                          valid
                                                               tag[18:6]
 W
Reset 0
                                                     0 0
```

#### FMC\_TAGVDW3Sn field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18-6 tag[18:6]	13-bit tag for cache entry
5–1 Reserved	This read-only field is reserved and always has the value zero.
0 valid	1-bit valid for cache entry



### 27.4.8 Cache Data Storage (upper word) (FMC\_DATAW0SU)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the upper word (bits [63:32]) of all 8 sets (n=0-7) in way 0.

### FMC\_DATAW0SnU field descriptions

Field	Description
31-0 data[63:32]	Bits [63:32] of data entry



### 27.4.9 Cache Data Storage (lower word) (FMC\_DATAW0SL)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the lower word (bits [31:0]) of all 8 sets (n=0-7) in way 0.

#### FMC\_DATAW0SnL field descriptions

Field	Description
31-0 data[31:0]	Bits [31:0] of data entry



### 27.4.10 Cache Data Storage (upper word) (FMC\_DATAW1SU)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the upper word (bits [63:32]) of all 8 sets (n=0-7) in way 1.

### FMC\_DATAW1SnU field descriptions

Field	Description
31-0 data[63:32]	Bits [63:32] of data entry



### 27.4.11 Cache Data Storage (lower word) (FMC\_DATAW1SL)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the lower word (bits [31:0]) of all 8 sets (n=0-7) in way 1.

### FMC\_DATAW1SnL field descriptions

Field	Description
31-0 data[31:0]	Bits [31:0] of data entry



### 27.4.12 Cache Data Storage (upper word) (FMC\_DATAW2SU)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the upper word (bits [63:32]) of all 8 sets (n=0-7) in way 2.

### FMC\_DATAW2SnU field descriptions

Field	Description
31-0 data[63:32]	Bits [63:32] of data entry



### 27.4.13 Cache Data Storage (lower word) (FMC\_DATAW2SL)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the lower word (bits [31:0]) of all 8 sets (n=0-7) in way 2.

### FMC\_DATAW2SnL field descriptions

Field	Description
31-0 data[31:0]	Bits [31:0] of data entry



### 27.4.14 Cache Data Storage (upper word) (FMC\_DATAW3SU)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the upper word (bits [63:32]) of all 8 sets (n=0-7) in way 3.

### FMC\_DATAW3SnU field descriptions

Field	Description
31-0 data[63:32]	Bits [63:32] of data entry



### 27.4.15 Cache Data Storage (lower word) (FMC\_DATAW3SL)

The cache of 64-bit entries is a 4-way, set-associative cache with 8 sets. The ways are numbered 0-3 and the sets are numbered 0-7. In DATAWxSyU and DATAWxSyL, x denotes the way, y denotes the set, and U and L represent upper and lower word, respectively. This section represents data for the lower word (bits [31:0]) of all 8 sets (n=0-7) in way 3.

### FMC\_DATAW3SnL field descriptions

Field	Description
31-0 data[31:0]	Bits [31:0] of data entry

# 27.5 Functional description

The FMC is a flash acceleration unit with flexible buffers for user configuration. Besides managing the interface between the device and the flash memory, the FMC can be used to restrict access from crossbar switch masters and customize the cache and buffers to provide single-cycle system-clock data-access times. Whenever a hit occurs for the prefetch speculation buffer, the cache, or the single-entry buffer, the requested data is transferred within a single system clock.

Upon system reset, the FMC is configured to provide a significant level of buffering for transfers from the flash memory:

- Crossbar masters 0, 1, 2 have read access to bank 0 and bank 1.
- For bank 0 and bank 1:
  - Prefetch support for data and instructions is enabled for crossbar masters 0, 1, 2.



#### runctional description

- The cache is configured for least recently used (LRU) replacement for all four ways.
- The cache is configured for data or instruction replacement.
- The single-entry buffer is enabled.

Though the default configuration provides a high degree of flash acceleration, advanced users may desire to customize the FMC buffer configurations to maximize throughput for their use cases. When reconfiguring the FMC for custom use cases, do not program the FMC's control registers while the flash memory is being accessed. Instead, change the control registers with a routine executing from RAM in supervisor mode.

The FMC's cache and buffering controls within PFB0CR and PFB1CR allow the tuning of resources to suit particular applications' needs. The cache and two buffers are each controlled individually. The register controls enable buffering and prefetching per memory bank and access type (instruction fetch or data reference). The cache also supports three types of LRU replacement algorithms:

- LRU per set across all four ways,
- LRU with ways [0-1] for instruction fetches and ways [2-3] for data fetches, and
- LRU with ways [0-2] for instruction fetches and way [3] for data fetches.

As an application example: if both instruction fetches and data references are accessing bank 0, control is available to send instruction fetches, data references, or both to the cache or the single-entry buffer. Likewise, speculation can be enabled or disabled for either type of access. If both instruction fetches and data references are cached, the cache's way resources may be divided in several ways between the instruction fetches and data references.

In another application example, the cache can be configured for replacement from bank 0, while the single-entry buffer can be enabled for bank 1 only. This configuration is ideal for applications that use bank 0 for program space and bank 1 for data space.



# **Chapter 28 Flash Memory Module (FTFL)**

### 28.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The FTFL module includes the following accessible memory regions:

- Program flash memory for vector space and code store
- Programming acceleration RAM to speed flash programming

Flash memory is ideal for single-supply applications, permitting in-the-field erase and reprogramming operations without the need for any external high voltage power sources.

The FTFL module includes a memory controller that executes commands to modify flash memory contents. An erased bit reads '1' and a programmed bit reads '0'. The programming operation is unidirectional; it can only move bits from the '1' state (erased) to the '0' state (programmed). Only the erase operation restores bits from '0' to '1'; bits cannot be programmed from a '0' to a '1'.

#### **CAUTION**

A flash memory location must be in the erased state before being programmed. Cumulative programming of bits (back-to-back program operations without an intervening erase) within a flash memory location is not allowed. Re-programming of existing 0s to 0 is not allowed as this overstresses the device.

The standard shipping condition for flash memory is erased with security disabled. Data loss over time may occur due to degradation of the erased ('1') states and/or programmed ('0')



muroduction

states. Therefore, it is recommended that each flash block or sector be re-erased immediately prior to factory programming to ensure that the full data retention capability is achieved.

#### **28.1.1 Features**

The FTFL module includes the following features.

#### NOTE

See the device's Chip Configuration details for the exact amount of flash memory available on your device.

### 28.1.1.1 Program Flash Memory Features

- Sector size of 2 Kbytes
- Program flash protection scheme prevents accidental program or erase of stored data
- Automated, built-in, program and erase algorithms with verify
- Section programming for faster bulk programming times
- Read access to one logical program flash block is possible while programming or erasing data in the other logical program flash block

### 28.1.1.2 Program Acceleration RAM Features

• RAM to support section programming

### 28.1.1.3 Other FTFL Module Features

- Internal high-voltage supply generator for flash memory program and erase operations
- Optional interrupt generation upon flash command completion
- Supports MCU security mechanisms which prevent unauthorized access to the flash memory contents



### 28.1.2 Block Diagram

The block diagram of the FTFL module is shown in the following figure.




Figure 28-1. FTFL Block Diagram

# 28.1.3 Glossary

**Command write sequence** — A series of MCU writes to the Flash FCCOB register group that initiates and controls the execution of Flash algorithms that are built into the FTFL module.

**Endurance** — The number of times that a flash memory location can be erased and reprogrammed.

**FCCOB** (**Flash Common Command Object**) — A group of flash registers that are used to pass command, address, data, and any associated parameters to the memory controller in the FTFL module.

**Flash block** — A macro within the FTFL module which provides the nonvolatile memory storage.

**FTFL Module** — All flash blocks plus a flash management unit providing high-level control and an interface to MCU buses.



#### **External Signal Description**

**IFR** — Nonvolatile information register found in each flash block, separate from the main memory array.

**NVM** — Nonvolatile memory. A memory technology that maintains stored data during power-off. The flash array is an NVM using NOR-type flash memory technology.

**NVM Normal Mode** — An NVM mode that provides basic user access to FTFL resources. The CPU or other bus masters initiate flash program and erase operations (or other FTFL commands) using writes to the FCCOB register group in the FTFL module.

**NVM Special Mode** — An NVM mode enabling external, off-chip access to the memory resources in the FTFL module. A reduced FTFL command set is available when the MCU is secured. See the Chip Configuration details for information on when this mode is used.

**Phrase** — 64 bits of data with an aligned phrase having byte-address[2:0] = 000.

**Longword** — 32 bits of data with an aligned longword having byte-address[1:0] = 00.

**Word** — 16 bits of data with an aligned word having byte-address[0] = 0.

**Program flash** — The program flash memory provides nonvolatile storage for vectors and code store.

**Program flash Sector** — The smallest portion of the program flash memory (consecutive addresses) that can be erased.

**Retention** — The length of time that data can be kept in the NVM without experiencing errors upon readout. Since erased (1) states are subject to degradation just like programmed (0) states, the data retention limit may be reached from the last erase operation (not from the programming time).

**RWW**— Read-While-Write. The ability to simultaneously read from one memory resource while commanded operations are active in another memory resource.

**Section Program Buffer** — Lower half of the programming acceleration RAM allocated for storing large amounts of data for programming via the Program Section command.

**Secure** — An MCU state conveyed to the FTFL module as described in the Chip Configuration details for this device. In the secure state, reading and changing NVM contents is restricted.

## 28.2 External Signal Description

The FTFL module contains no signals that connect off-chip.



# 28.3 Memory Map and Registers

This section describes the memory map and registers for the FTFL module. Data read from unimplemented memory space in the FTFL module is undefined. Writes to unimplemented or reserved memory space (registers) in the FTFL module are ignored.

## 28.3.1 Flash Configuration Field Description

The program flash memory contains a 16-byte flash configuration field that stores default protection settings (loaded on reset) and security information that allows the MCU to restrict access to the FTFL module.

Flash Configuration Field Byte Address	Size (Bytes)	Field Description
0x0_0400 - 0x0_0407	8	Backdoor Comparison Key. Refer to Verify Backdoor Access Key Command and Unsecuring the Chip Using Backdoor Key Access.
0x0_0408 - 0x0_040B	4	Program flash protection bytes. Refer to the description of the Program Flash Protection Registers (FPROT0-3).
0x0_040F	1	Program flash only devices: Reserved
0x0_040E	1	Program flash only devices: Reserved
0x0_040D	1	Flash nonvolatile option byte. Refer to the description of the Flash Option Register (FOPT).
0x0_040C	1	Flash security byte. Refer to the description of the Flash Security Register (FSEC).

# 28.3.2 Program Flash IFR Map

The program flash IFR is nonvolatile information memory that can be read freely, but the user has no erase and limited program capabilities (see the Read Once, Program Once, and Read Resource commands in Read Once Command, Program Once Command and Read Resource Command). The contents of the program flash IFR are summarized in the following table and further described in the subsequent paragraphs.

For devices that only contain program flash, the program flash IFR is located within the program flash 0 memory block.



#### wemory Map and Registers

Address Range	Size (Bytes)	Field Description	
0x00 – 0xBF	192	Reserved	
0xC0 - 0xFF	64 Program Once Field		

### 28.3.2.1 Program Once Field

The Program Once Field in the program flash IFR provides 64 bytes of user data storage separate from the program flash main array. The user can program the Program Once Field one time only as there is no program flash IFR erase mechanism available to the user. The Program Once Field can be read any number of times. This section of the program flash IFR is accessed in 4-Byte records using the Read Once and Program Once commands (see Read Once Command and Program Once Command).

### 28.3.3 Register Descriptions

The FTFL module contains a set of memory-mapped control and status registers.

#### NOTE

While a command is running (FSTAT[CCIF]=0), register writes are not accepted to any register except FCNFG and FSTAT. The no-write rule is relaxed during the start-up reset sequence, prior to the initial rise of CCIF. During this initialization period the user may write any register. All register writes are also disabled (except for registers FCNFG and FSTAT) whenever an erase suspend request is active (FCNFG[ERSSUSP]=1).

#### FTFL memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4002_0000	Flash Status Register (FTFL_FSTAT)	8	R/W	00h	28.33.1/ 613
4002_0001	Flash Configuration Register (FTFL_FCNFG)	8	R/W	00h	28.33.2/ 615
4002_0002	Flash Security Register (FTFL_FSEC)	8	R	Undefined	28.33.3/ 616
4002_0003	Flash Option Register (FTFL_FOPT)	8	R	Undefined	28.33.4/ 618



### FTFL memory map (continued)

Absolute address (hex)	Register name		Access	Reset value	Section/ page
4002_0004	Flash Common Command Object Registers (FTFL_FCCOB3)	8	R/W	00h	28.33.5/ 619
4002_0005	Flash Common Command Object Registers (FTFL_FCCOB2)		R/W	00h	28.33.5/ 619
4002_0006	Flash Common Command Object Registers (FTFL_FCCOB1)	8	R/W	00h	28.33.5/ 619
4002_0007	Flash Common Command Object Registers (FTFL_FCCOB0)	8	R/W	00h	28.33.5/ 619
4002_0008	Flash Common Command Object Registers (FTFL_FCCOB7)	8	R/W	00h	28.33.5/ 619
4002_0009	Flash Common Command Object Registers (FTFL_FCCOB6)	8	R/W	00h	28.33.5/ 619
4002_000A	Flash Common Command Object Registers (FTFL_FCCOB5)		R/W	00h	28.33.5/ 619
4002_000B	Flash Common Command Object Registers (FTFL_FCCOB4)		R/W	00h	28.33.5/ 619
4002_000C	Flash Common Command Object Registers (FTFL_FCCOBB)		R/W	00h	28.33.5/ 619
4002_000D	Flash Common Command Object Registers (FTFL_FCCOBA)		R/W	00h	28.33.5/ 619
4002_000E	Flash Common Command Object Registers (FTFL_FCCOB9)		R/W	00h	28.33.5/ 619
4002_000F	Flash Common Command Object Registers (FTFL_FCCOB8)	8	R/W	00h	28.33.5/ 619
4002_0010	Program Flash Protection Registers (FTFL_FPROT3)		R/W	Undefined	28.33.6/ 620
4002_0011	Program Flash Protection Registers (FTFL_FPROT2)		R/W	Undefined	28.33.6/ 620
4002_0012	Program Flash Protection Registers (FTFL_FPROT1)		R/W	Undefined	28.33.6/ 620
4002_0013	Program Flash Protection Registers (FTFL_FPROT0)		R/W	Undefined	28.33.6/ 620

# 28.33.1 Flash Status Register (FTFL\_FSTAT)

The FSTAT register reports the operational status of the FTFL module.

The CCIF, RDCOLERR, ACCERR, and FPVIOL bits are readable and writable. The MGSTAT0 bit is read only. The unassigned bits read 0 and are not writable.



#### wemory Map and Registers

### **NOTE**

When set, the Access Error (ACCERR) and Flash Protection Violation (FPVIOL) bits in this register prevent the launch of any more commands until the flag is cleared (by writing a one to it).

Address: FTFL\_FSTAT is 4002\_0000h base + 0h offset = 4002\_0000h

Bit	7	6	5	4	3	2	1	0
Read	CCIF	RDCOLERR	ACCERR	FPVIOL		0		MGSTAT0
Write	w1c	w1c	w1c	w1c				
Reset	0	0	0	0	0	0	0	0

### FTFL\_FSTAT field descriptions

Field	Description		
7	Command Complete Interrupt Flag		
CCIF	The CCIF flag indicates that a FTFL command has completed. The CCIF flag is cleared by writing a 1 to CCIF to launch a command, and CCIF stays low until command completion or command violation.		
	The CCIF bit is reset to 0 but is set to 1 by the memory controller at the end of the reset initialization sequence. Depending on how quickly the read occurs after reset release, the user may or may not see the 0 hardware reset value.		
	0 FTFL command in progress		
	1 FTFL command has completed		
6	FTFL Read Collision Error Flag		
RDCOLERR	The RDCOLERR error bit indicates that the MCU attempted a read from an FTFL resource that was being manipulated by an FTFL command (CCIF=0). Any simultaneous access is detected as a collision error by the block arbitration logic. The read data in this case cannot be guaranteed. The RDCOLERR bit is cleared by writing a 1 to it. Writing a 0 to RDCOLERR has no effect.		
	0 No collision error detected		
	1 Collision error detected		
5	Flash Access Error Flag		
ACCERR	The ACCERR error bit indicates an illegal access has occurred to an FTFL resource caused by a violation of the command write sequence or issuing an illegal FTFL command. While ACCERR is set, the CCIF flag cannot be cleared to launch a command. The ACCERR bit is cleared by writing a 1 to it. Writing a 0 to the ACCERR bit has no effect.		
	0 No access error detected		
	1 Access error detected		
4	Flash Protection Violation Flag		
FPVIOL	The FPVIOL error bit indicates an attempt was made to program or erase an address in a protected area of program flash memory during a command write sequence. While FPVIOL is set, the CCIF flag cannot be cleared to launch a command. The FPVIOL bit is cleared by writing a 1 to it. Writing a 0 to the FPVIOL bit has no effect.		
	0 No protection violation detected		
	1 Protection violation detected		



### FTFL\_FSTAT field descriptions (continued)


Field	Description
3–1 Reserved	This read-only field is reserved and always has the value zero.
0 MGSTAT0	Memory Controller Command Completion Status Flag  The MGSTAT0 status flag is set if an error is detected during execution of an FTFL command or during the flash reset sequence. As a status flag, this bit cannot (and need not) be cleared by the user like the other error flags in this register.
	The value of the MGSTAT0 bit for "command-N" is valid only at the end of the "command-N" execution when CCIF=1 and before the next command has been launched. At some point during the execution of "command-N+1," the previous result is discarded and any previous error is cleared.

# 28.33.2 Flash Configuration Register (FTFL\_FCNFG)

This register provides information on the current functional state of the FTFL module.

The erase control bits (ERSAREQ and ERSSUSP) have write restrictions. SWAP, PFLSH, RAMRDY are read-only status bits. The unassigned bits read as noted and are not writable. The reset values for the SWAP, PFLASH, RAMRDY bits are determined during the reset sequence.

Address: FTFL\_FCNFG is 4002\_0000h base + 1h offset = 4002\_0001h



#### FTFL\_FCNFG field descriptions

Field	Description
7	Command Complete Interrupt Enable
CCIE	The CCIE bit controls interrupt generation when an FTFL command completes.
	0 Command complete interrupt disabled
	Command complete interrupt enabled. An interrupt request is generated whenever the FSTAT[CCIF] flag is set.
6	Read Collision Error Interrupt Enable
RDCOLLIE	The RDCOLLIE bit controls interrupt generation when an FTFL read collision error occurs.
	0 Read collision error interrupt disabled
	Read collision error interrupt enabled. An interrupt request is generated whenever an FTFL read collision error is detected (see the description of FSTAT[RDCOLERR]).
5 ERSAREQ	Erase All Request

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory Map and Registers

## FTFL\_FCNFG field descriptions (continued)

Field	Description
	This bit issues a request to the memory controller to execute the Erase All Blocks command and release security. ERSAREQ is not directly writable but is under indirect user control. Refer to the device's Chip Configuration details on how to request this command.
	The ERSAREQ bit sets when an erase all request is triggered external to the FTFL and CCIF is set (no command is currently being executed). ERSAREQ is cleared by the FTFL when the operation completes.
	0 No request or request complete 1 Request to:     1. run the Erase All Blocks command, 2. verify the erased state, 3. program the security byte in the Flash Configuration Field to the unsecure state, and 4. release MCU security by setting the FSEC[SEC] field to the unsecure state.
4	Erase Suspend
ERSSUSP	The ERSSUSP bit allows the user to suspend (interrupt) the Erase Flash Sector command while it is executing.
	0 No suspend requested
	1 Suspend the current Erase Flash Sector command execution.
3 SWAP	Swap
	For program flash only configurations, the SWAP flag indicates which physical program flash block is located at relative address 0x0000. The state of the SWAP flag is set by the FTFL during the reset sequence . See the Swap Control command section for information on swap management.
	0 Physical program flash 0 is located at relative address 0x0000
	1 If the PFLSH flag is set, physical program flash 1 is located at relative address 0x0000. If the PFLSH flag is not set, physical program flash 0 is located at relative address 0x0000
2 PFLSH	FTFL configuration
	0 Reserved 1 FTFL configured for program flash only, without support for data flash and/or EEPROM
1	RAM Ready
RAMRDY	This flag indicates the current status of the programming acceleration RAM .
	This bit should always be set.
	<ul> <li>0 Programming acceleration RAM is not available.</li> <li>1 Programming acceleration RAM is available.</li> </ul>
0	This field is reserved.
EEERDY	0
	1

# 28.33.3 Flash Security Register (FTFL\_FSEC)

This read-only register holds all bits associated with the security of the MCU and FTFL module.



During the reset sequence, the register is loaded with the contents of the flash security byte in the Flash Configuration Field located in program flash memory. The Flash basis for the values is signified by X in the reset value.

Address: FTFL\_FSEC is 4002\_0000h base + 2h offset = 4002\_0002h

Bit	7	6	5	4	3	2	1	0
Read	KE	YEN	МЕ	EN	FSL	_ACC	S	SEC
Write								
Reset	X*	X*	x*	x*	x*	X*	x*	

<sup>\*</sup> Notes:

### FTFL\_FSEC field descriptions

Field	Description
7–6	Backdoor Key Security Enable
KEYEN	These bits enable and disable backdoor key access to the FTFL module.
	00 Backdoor key access disabled
	01 Backdoor key access disabled (preferred KEYEN state to disable backdoor key access)
	10 Backdoor key access enabled
	11 Backdoor key access disabled
5–4 MEEN	Mass Erase Enable Bits
IVILLIN	Enables and disables mass erase capability of the FTFL module. The state of the MEEN bits is only relevant when the SEC bits are set to secure outside of NVM Normal Mode. When the SEC field is set to unsecure, the MEEN setting does not matter.
	00 Mass erase is enabled
	01 Mass erase is enabled
	10 Mass erase is disabled
	11 Mass erase is enabled
3–2	Freescale Failure Analysis Access Code
FSLACC	These bits enable or disable access to the flash memory contents during returned part failure analysis at Freescale. When SEC is secure and FSLACC is denied, access to the program flash contents is denied and any failure analysis performed by Freescale factory test must begin with a full erase to unsecure the part.
	When access is granted (SEC is unsecure, or SEC is secure and FSLACC is granted), Freescale factory testing has visibility of the current flash contents. The state of the FSLACC bits is only relevant when the SEC bits are set to secure. When the SEC field is set to unsecure, the FSLACC setting does not matter.
	00 Freescale factory access granted
	01 Freescale factory access denied
	10 Freescale factory access denied
	11 Freescale factory access granted
1–0 SEC	Flash Security

<sup>•</sup> x = Undefined at reset.



#### wemory Map and Registers

#### FTFL\_FSEC field descriptions (continued)

Field	Description		
	These bits define the security state of the MCU. In the secure state, the MCU limits access to FTFL		
	module resources. The limitations are defined per device and are detailed in the Chip Configuration details. If the FTFL module is unsecured using backdoor key access, the SEC bits are forced to 10b.		
	00 MCU security status is secure		
	01 MCU security status is secure		
	10 MCU security status is unsecure (The standard shipping condition of the FTFL is unsecure.)		
	11 MCU security status is secure		


# 28.33.4 Flash Option Register (FTFL\_FOPT)

The flash option register allows the MCU to customize its operations by examining the state of these read-only bits, which are loaded from NVM at reset. The function of the bits is defined in the device's Chip Configuration details.

All bits in the register are read-only.

During the reset sequence, the register is loaded from the flash nonvolatile option byte in the Flash Configuration Field located in program flash memory. The flash basis for the values is signified by X in the reset value.

Address: FTFL\_FOPT is 4002\_0000h base + 3h offset = 4002\_0003h



<sup>\*</sup> Notes:

#### FTFL\_FOPT field descriptions


Field	Description
7–0 OPT	Nonvolatile Option  These bits are loaded from flash to this register at reset. Refer to the device's Chip Configuration details for the definition and use of these bits.


<sup>•</sup> x = Undefined at reset.



# 28.33.5 Flash Common Command Object Registers (FTFL\_FCCOBn)

The FCCOB register group provides 12 bytes for command codes and parameters. The individual bytes within the set append a 0-B hex identifier to the FCCOB register name: FCCOB0, FCCOB1, ..., FCCOBB.





#### FTFL FCCOBn field descriptions

1 11 L_1 CCODII field descriptions				
Field		Description		
7–0 COBn	The FCCOB register provides a command code and relevant parameters to the memory controller. The individual registers that compose the FCCOB data set can be written in any order, but you must provide all needed values, which vary from command to command. First, set up all required FCCOB fields and then initiate the command's execution by writing a 1 to the FSTAT[CCIF] bit. This clears the CCIF bit, which locks all FCCOB parameter fields and they cannot be changed by the user until the command completes (CCIF returns to 1). No command buffering or queueing is provided; the next command can be loaded only after the current command completes.			
		nformation to the FCCOB registers. Any values returned to FCCOB are available T[CCIF] flag returns to 1 by the memory controller.		
The following table shows a generic FTFL command format. The first FCCOB register, FCC contains the command code. This 8-bit value defines the command to be executed. The cor is followed by the parameters required for this specific FTFL command, typically an address values.				
	NOTE: The command parameter table is written in terms of FCCOB Number (which is equivalen byte number). This number is a reference to the FCCOB register name and is not the reg address.			
	FCCOB Number	Typical Command Parameter Contents [7:0]		
	0	FCMD (a code that defines the FTFL command)		
	1	Flash address [23:16]		
	2	Flash address [15:8]		
	3	Flash address [7:0]		
	4	Data Byte 0		
	5	Data Byte 1		
	6	Data Byte 2		
	7	Data Byte 3		
	8	Data Byte 4		

Data Byte 5



#### wemory Map and Registers

#### FTFL\_FCCOBn field descriptions (continued)

Field	Description			
	FCCOB Number	Typical Command Parameter Contents [7:0]		
	А	Data Byte 6		
	В	Data Byte 7		
	FCCOB Endianness and	Multi-Byte Access :		
	The FCCOB register group uses a big endian addressing convention. For all command parameter larger than 1 byte, the most significant data resides in the lowest FCCOB register number. The register group may be read and written as individual bytes, aligned words (2 bytes) or aligned lot (4 bytes).			

# 28.33.6 Program Flash Protection Registers (FTFL\_FPROT*n*)

The FPROT registers define which logical program flash regions are protected from program and erase operations. Protected flash regions cannot have their content changed; that is, these regions cannot be programmed and cannot be erased by any FTFL command. Unprotected regions can be changed by program and erase operations.

The four FPROT registers allow 32 protectable regions. Each bit protects a 1/32 region of the program flash memory. The bitfields are defined in each register as follows:


Program flash protection register	Program flash protection bits
FPROT0	PROT[31:24]
FPROT1	PROT[23:16]
FPROT2	PROT[15:8]
FPROT3	PROT[7:0]

During the reset sequence, the FPROT registers are loaded with the contents of the program flash protection bytes in the Flash Configuration Field as indicated in the following table.

Program flash protection register	Flash Configuration Field offset address
FPROT0	0x0008
FPROT1	0x0009
FPROT2	0x000A
FPROT3	0x000B

To change the program flash protection that is loaded during the reset sequence, unprotect the sector of program flash memory that contains the Flash Configuration Field. Then, reprogram the program flash protection byte.





<sup>\*</sup> Notes:

### FTFL\_FPROTn field descriptions

Field	Description
7–0	Program Flash Region Protect
PROT	Each program flash region can be protected from program and erase operations by setting the associated PROT bit.
	In NVM Normal mode: The protection can only be increased, meaning that currently unprotected memory can be protected, but currently protected memory cannot be unprotected. Since unprotected regions are marked with a 1 and protected regions use a 0, only writes changing 1s to 0s are accepted. This 1-to-0 transition check is performed on a bit-by-bit basis. Those FPROT bits with 1-to-0 transitions are accepted while all bits with 0-to-1 transitions are ignored.
	In NVM Special mode: All bits of FPROT are writable without restriction. Unprotected areas can be protected and protected areas can be unprotected.
	Restriction: The user must never write to any FPROT register while a command is running (CCIF=0).
	Trying to alter data in any protected area in the program flash memory results in a protection violation error and sets the FSTAT[FPVIOL] bit. A full block erase of a program flash block is not possible if it contains any protected region.
	Each bit in the 32-bit protection register represents 1/32 of the total program flash .
	<ul><li>0 Program flash region is protected.</li><li>1 Program flash region is not protected</li></ul>

# 28.4 Functional Description

The following sections describe functional details of the FTFL module.

x = Undefined at reset.

гіазії Operation in Low-Power Modes

# 28.4.1 Program Flash Memory Swap

For devices that only contain program flash memory: The user can configure the logical memory map of the program flash space such that either of the two physical program flash blocks can exist at relative address 0x0000. This swap feature enables the lower half of the logical program flash space to be operational while the upper half is being updated for future use.

The Swap Control command handles swapping the two logical P-Flash memory blocks within the memory map. See Swap Control Command for details.

# 28.4.2 Interrupts

The FTFL module can generate interrupt requests to the MCU upon the occurrence of various FTFL events. These interrupt events and their associated status and control bits are shown in the following table.

Table 28-24. FTFL Interrupt Sources

FTFL Event	Readable	Interrupt
	Status Bit	Enable Bit
FTFL Command Complete	FSTAT[CCIF]	FCNFG[CCIE]
FTFL Read Collision Error	FSTAT[RDCOLERR]	FCNFG[RDCOLLIE]

#### Note

Vector addresses and their relative interrupt priority are determined at the MCU level.

# 28.4.3 Flash Operation in Low-Power Modes

### 28.4.3.1 Wait Mode

When the MCU enters wait mode, the FTFL module is not affected. The FTFL module can recover the MCU from wait via the command complete interrupt (see Interrupts).

### 28.4.3.2 Stop Mode

When the MCU requests stop mode, if an FTFL command is active (CCIF = 0) the command execution completes before the MCU is allowed to enter stop mode.



#### **CAUTION**

The MCU should never enter stop mode while any FTFL command is running (CCIF = 0).

#### NOTE

While the MCU is in very-low-power modes (VLPR, VLPW, VLPS), the FTFL module does not accept flash commands.

# 28.4.4 Functional Modes of Operation

The FTFL module has two operating modes: NVM Normal and NVM Special. The operating mode affects the command set availability (see Table 28-25). Refer to the Chip Configuration details of this device for how to activate each mode.

# 28.4.5 Flash Reads and Ignored Writes

The FTFL module requires only the flash address to execute a flash memory read. MCU read access is available to all flash blocks.

The MCU must not read from the flash memory while commands are running (as evidenced by CCIF=0) on that block. Read data cannot be guaranteed from a flash block while any command is processing within that block. The block arbitration logic detects any simultaneous access and reports this as a read collision error (see the FSTAT[RDCOLERR] bit).

# 28.4.6 Read While Write (RWW)

The following simultaneous accesses are allowed:

• The user may read from one logical program flash memory space while commands (typically program and erase operations) are active in the other logical program flash memory space.

Simultaneous operations are further discussed in Allowed Simultaneous Flash Operations.



гіазп Operation in Low-Power Modes

# 28.4.7 Flash Program and Erase

All flash functions except read require the user to setup and launch an FTFL command through a series of peripheral bus writes. The user cannot initiate any further FTFL commands until notified that the current command has completed. The FTFL command structure and operation are detailed in FTFL Command Operations.

# 28.4.8 FTFL Command Operations

FTFL command operations are typically used to modify flash memory contents. The next sections describe:

- The command write sequence used to set FTFL command parameters and launch execution
- A description of all FTFL commands available

### 28.4.8.1 Command Write Sequence

FTFL commands are specified using a command write sequence illustrated in Figure 28-24. The FTFL module performs various checks on the command (FCCOB) content and continues with command execution if all requirements are fulfilled.

Before launching a command, the ACCERR and FPVIOL bits in the FSTAT register must be zero and the CCIF flag must read 1 to verify that any previous command has completed. If CCIF is zero, the previous command execution is still active, a new command write sequence cannot be started, and all writes to the FCCOB registers are ignored.

### 28.4.8.1.1 Load the FCCOB Registers

The user must load the FCCOB registers with all parameters required by the desired FTFL command. The individual registers that make up the FCCOB data set can be written in any order.

### 28.4.8.1.2 Launch the Command by Clearing CCIF

Once all relevant command parameters have been loaded, the user launches the command by clearing the FSTAT[CCIF] bit by writing a '1' to it. The CCIF flag remains zero until the FTFL command completes.



The FSTAT register contains a blocking mechanism, which prevents a new command from launching (can't clear CCIF) if the previous command resulted in an access error (FSTAT[ACCERR]=1) or a protection violation (FSTAT[FPVIOL]=1). In error scenarios, two writes to FSTAT are required to initiate the next command: the first write clears the error flags, the second write clears CCIF.

### 28.4.8.1.3 Command Execution and Error Reporting

The command processing has several steps:

1. The FTFL reads the command code and performs a series of parameter checks and protection checks, if applicable, which are unique to each command.

If the parameter check fails, the FSTAT[ACCERR] (access error) flag is set. ACCERR reports invalid instruction codes and out-of bounds addresses. Usually, access errors suggest that the command was not set-up with valid parameters in the FCCOB register group.

Program and erase commands also check the address to determine if the operation is requested to execute on protected areas. If the protection check fails, the FSTAT[FPVIOL] (protection error) flag is set.

Command processing never proceeds to execution when the parameter or protection step fails. Instead, command processing is terminated after setting the FSTAT[CCIF] bit.

- 2. If the parameter and protection checks pass, the command proceeds to execution. Run-time errors, such as failure to erase verify, may occur during the execution phase. Run-time errors are reported in the FSTAT[MGSTAT0] bit. A command may have access errors, protection errors, and run-time errors, but the run-time errors are not seen until all access and protection errors have been corrected.
- 3. Command execution results, if applicable, are reported back to the user via the FCCOB and FSTAT registers.
- 4. The FTFL sets the FSTAT[CCIF] bit signifying that the command has completed.

The flow for a generic command write sequence is illustrated in the following figure.

#### гіамі Operation in Low-Power Modes




Figure 28-24. Generic FTFL Command Write Sequence Flowchart

### 28.4.8.2 FTFL Commands

The following table summarizes the function of all FTFL commands.

FCMD	Command	Program flash 0	Program flash 1	Function
0x00	Read 1s Block	×	×	Verify that a program flash block is erased.
0x01	Read 1s Section	×	×	Verify that a given number of program flash locations from a starting address are erased.
0x02	Program Check	×	×	Tests previously- programmed locations at margin read levels.





FCMD	Command	Program flash 0	Program flash 1	Function
0x03	Read Resource	IFR, ID	IFR	Read 4 bytes from program flash IFR or version ID.
0x06	Program Longword	×	×	Program 4 bytes in a program flash block.
0x08	Erase Flash Block	×	×	Erase a program flash block. An erase of any flash block is only possible when unprotected.
0x09	Erase Flash Sector	×	×	Erase all bytes in a program flash sector.
0x0B	Program Section	×	×	Program data from the Section Program Buffer to a program flash block.
0x40	Read 1s All Blocks	×	×	Verify that all program flash blocks are erased then release MCU security.
0x41	Read Once	IFR		Read 4 bytes of a dedicated 64 byte field in the program flash 0 IFR.
0x43	Program Once	IFR		One-time program of 4 bytes of a dedicated 64-byte field in the program flash 0 IFR.
0x44	Erase All Blocks	×	×	Erase all program flash blocks, program flash 1 IFR. Then, verify-erase and release MCU security.
				NOTE: An erase is only possible when all memory locations are unprotected.
0x45	Verify Backdoor Access Key	×	×	Release MCU security after comparing a set of user-supplied security keys to those stored in the program flash.
0x46	Swap Control	×	×	Handles swap-related activities



าเสรา Operation in Low-Power Modes

# 28.4.8.3 FTFL Commands by Mode

The following table shows the FTFL commands that can be executed in each flash operating mode.

Table 28-25. FTFL Commands by Mode

FCMD	Command	NVM Normal			NVM Special		
FCMD	Command	Unsecure	Secure	MEEN=10	Unsecure	Secure	MEEN=10
0x00	Read 1s Block	×	×	×	×	_	_
0x01	Read 1s Section	×	×	×	×	_	_
0x02	Program Check	×	×	×	×	_	_
0x03	Read Resource	×	×	×	×	_	_
0x06	Program Longword	×	×	×	×	_	_
0x08	Erase Flash Block	×	×	×	×	_	_
0x09	Erase Flash Sector	×	×	×	×	_	_
0x0B	Program Section	×	×	×	×	_	_
0x40	Read 1s All Blocks	×	×	×	×	×	_
0x41	Read Once	×	×	×	×	_	_
0x43	Program Once	×	×	×	×	_	_
0x44	Erase All Blocks	×	×	×	×	×	_
0x45	Verify Backdoor Access Key	×	×	×	×	_	_

# 28.4.8.4 Allowed Simultaneous Flash Operations

Only the operations marked 'OK' in the following table are permitted to run simultaneously on the program flash memories. Some operations cannot be executed simultaneously because certain hardware resources are shared by the memories.

**Table 28-26. Allowed Simultaneous Memory Operations** 

			Program Flash 0		Program Flash 1		
		Read	Program	Sector Erase	Read	Program	Sector Erase
	Read	_				ОК	ОК
Program flash 0	Program		_		OK		
	Sector Erase			_	OK		
	Read		ОК	OK	_		
Program flash 1	Program	OK				_	
	Sector Erase	OK					_



# 28.4.9 Margin Read Commands

The Read-1s commands (Read 1s All Blocks, Read 1s Block, and Read 1s Section) and the Program Check command have a margin choice parameter that allows the user to apply non-standard read reference levels to the program flash array reads performed by these commands. Using the preset 'user' and 'factory' margin levels, these commands perform their associated read operations at tighter tolerances than a 'normal' read. These non-standard read levels are applied only during the command execution. All simple (uncommanded) flash array reads to the MCU always use the standard, un-margined, read reference level.

Only the 'normal' read level should be employed during normal flash usage. The non-standard, 'user' and 'factory' margin levels should be employed only in special cases. They can be used during special diagnostic routines to gain confidence that the device is not suffering from the end-of-life data loss customary of flash memory devices.

Erased ('1') and programmed ('0') bit states can degrade due to elapsed time and data cycling (number of times a bit is erased and re-programmed). The lifetime of the erased states is relative to the last erase operation. The lifetime of the programmed states is measured from the last program time.

The 'user' and 'factory' levels become, in effect, a minimum safety margin; i.e. if the reads pass at the tighter tolerances of the 'user' and 'factory' margins, then the 'normal' reads have at least this much safety margin before they experience data loss.

The 'user' margin is a small delta to the normal read reference level. 'User' margin levels can be employed to check that flash memory contents have adequate margin for normal level read operations. If unexpected read results are encountered when checking flash memory contents at the 'user' margin levels, loss of information might soon occur during 'normal' readout.

The 'factory' margin is a bigger deviation from the norm, a more stringent read criteria that should only be attempted immediately (or very soon) after completion of an erase or program command, early in the cycling life. 'Factory' margin levels can be used to check that flash memory contents have adequate margin for long-term data retention at the normal level setting. If unexpected results are encountered when checking flash memory contents at 'factory' margin levels, the flash memory contents should be erased and reprogrammed.

#### **CAUTION**

Factory margin levels must only be used during verify of the initial factory programming.



# 28.4.10 FTFL Command Description

This section describes all FTFL commands that can be launched by a command write sequence. The FTFL sets the FSTAT[ACCERR] bit and aborts the command execution if any of the following illegal conditions occur:

- There is an unrecognized command code in the FCCOB FCMD field.
- There is an error in a FCCOB field for the specific commands. Refer to the error handling table provided for each command.

Ensure that the ACCERR and FPVIOL bits in the FSTAT register are cleared prior to starting the command write sequence. As described in Launch the Command by Clearing CCIF, a new command cannot be launched while these error flags are set.

Do not attempt to read a flash block while the FTFL is running a command (CCIF = 0) on that same block. The FTFL may return invalid data to the MCU with the collision error flag (FSTAT[RDCOLERR]) set.

When required by the command, address bit 23 selects between:

- program flash 0 (=0) block
- program flash 1 (=1) block

#### CAUTION

Flash data must be in the erased state before being programmed. Cumulative programming of bits (adding more zeros) is not allowed.

### 28.4.10.1 Read 1s Block Command

The Read 1s Block command checks to see if an entire program flash block has been erased to the specified margin level. The FCCOB flash address bits determine which logical block is erase-verified.

Table 28-27. Read 1s Block Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x00 (RD1BLK)
1	Flash address [23:16] in the flash block to be verified
2	Flash address [15:8] in the flash block to be verified



### Table 28-27. Read 1s Block Command FCCOB Requirements (continued)

FCCOB Number	FCCOB Contents [7:0]		
3	Flash address [7:0] <sup>1</sup> in the flash block to be verified		
4	Read-1 Margin Choice		

<sup>1.</sup> Must be longword aligned (Flash address [1:0] = 00).

After clearing CCIF to launch the Read 1s Block command, the FTFL sets the read margin for 1s according to Table 28-28 and then reads all locations within the selected program flash block.

Table 28-28. Margin Level Choices for Read 1s Block

Read Margin Choice	Margin Level Description
0x00	Use the 'normal' read level for 1s
0x01	Apply the 'User' margin to the normal read-1 level
0x02	Apply the 'Factory' margin to the normal read-1 level

Table 28-29. Read 1s Block Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid margin choice is specified	FSTAT[ACCERR]
Program flash is selected and the address is out of program flash range	FSTAT[ACCERR]
Flash address is not longword aligned	FSTAT[ACCERR]
Read-1s fails	FSTAT[MGSTAT0]

#### 28.4.10.2 Read 1s Section Command

The Read 1s Section command checks if a section of program flash memory is erased to the specified read margin level. The Read 1s Section command defines the starting address and the number of phrases to be verified.

Table 28-30. Read 1s Section Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]	
0	0x01 (RD1SEC)	
1	Flash address [23:16] of the first phrase to be verified	
2	Flash address [15:8] of the first phrase to be verified	
3	Flash address [7:0] <sup>1</sup> of the first phrase to be verified	
4	Number of phrases to be verified [15:8]	
5	Number of phrases to be verified [7:0]	



riasii Operation in Low-Power Modes

Table 28-30. Read 1s Section Command FCCOB Requirements (continued)

FCCOB Number	FCCOB Contents [7:0]
6	Read-1 Margin Choice

<sup>1.</sup> Must be phrase aligned (Flash address [2:0] = 000).

Upon clearing CCIF to launch the Read 1s Section command, the FTFL sets the read margin for 1s according to Table 28-31 and then reads all locations within the specified section of flash memory. If the FTFL fails to read all 1s (i.e. the flash section is not erased), the FSTAT(MGSTAT0) bit is set. The CCIF flag sets after the Read 1s Section operation completes.

Table 28-31. Margin Level Choices for Read 1s Section

Read Margin Choice	Margin Level Description	
0x00	Use the 'normal' read level for 1s	
0x01	Apply the 'User' margin to the normal read-1 level	
0x02	Apply the 'Factory' margin to the normal read-1 level	

Table 28-32. Read 1s Section Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid margin code is supplied	FSTAT[ACCERR]
An invalid flash address is supplied	FSTAT[ACCERR]
Flash address is not phrase aligned	FSTAT[ACCERR]
The requested section crosses a Flash block boundary	FSTAT[ACCERR]
The requested number of phrases is zero	FSTAT[ACCERR]
Read-1s fails	FSTAT[MGSTAT0]

### 28.4.10.3 Program Check Command

The Program Check command tests a previously programmed program flash longword to see if it reads correctly at the specified margin level.

Table 28-33. Program Check Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x02 (PGMCHK)
1	Flash address [23:16]
2	Flash address [15:8]
3	Flash address [7:0] <sup>1</sup>



Table 28-33. Program Check Command FCCOB Requirements (continue
---

FCCOB Number	FCCOB Contents [7:0]	
4	Margin Choice	
8	Byte 0 expected data	
9	Byte 1 expected data	
А	Byte 2 expected data	
В	Byte 3 expected data	

<sup>1.</sup> Must be longword aligned (Flash address [1:0] = 00).

Upon clearing CCIF to launch the Program Check command, the FTFL sets the read margin for 1s according to Table 28-34, reads the specified longword, and compares the actual read data to the expected data provided by the FCCOB. If the comparison at margin-1 fails, the MGSTAT0 bit is set.

The FTFL then sets the read margin for 0s, re-reads, and compares again. If the comparison at margin-0 fails, the MGSTAT0 bit is set. The CCIF flag is set after the Program Check operation completes.

The supplied address must be longword aligned (the lowest two bits of the byte address must be 00):

- Byte 0 data is expected at the supplied address ('start'),
- Byte 1 data is expected at byte address start + 0b01,
- Byte 2 data is expected at byte address start + 0b10, and
- Byte 3 data is expected at byte address start + 0b11.

#### NOTE

See the description of margin reads, Margin Read Commands

Table 28-34. Margin Level Choices for Program Check

Read Margin Choice	Margin Level Description	
0x01	Read at 'User' margin-1 and 'User' margin-0	
0x02	Read at 'Factory' margin-1 and 'Factory' margin-0	

**Table 28-35. Program Check Command Error Handling** 

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid flash address is supplied	FSTAT[ACCERR]
Flash address is not longword aligned	FSTAT[ACCERR]
An invalid margin choice is supplied	FSTAT[ACCERR]
Either of the margin reads does not match the expected data	FSTAT[MGSTAT0]



#### 28.4.10.4 Read Resource Command

The Read Resource command allows the user to read data from special-purpose memory resources located within the FTFL module. The special-purpose memory resources available include program flash IFR space and the Version ID field. Each resource is assigned a select code as shown in Table 28-37.

**FCCOB Number** FCCOB Contents [7:0] 0 0x03 (RDRSRC) 1 Flash address [23:16] 2 Flash address [15:8] Flash address [7:0]<sup>1</sup> Returned Values 4 Read Data [31:24] 5 Read Data [23:16] 6 Read Data [15:8] 7 Read Data [7:0] User-provided values

Table 28-36. Read Resource Command FCCOB Requirements

8

Table 28-37. Read Resource Select Codes

Resource Select Code (see Table 28-37)

Resource Select Code	Description	Resource Size	Local Address Range
0x00	IFR	256 Bytes	0x0000 - 0x00FF
0x01 <sup>1</sup>	Version ID	8 Bytes	0x0000 - 0x0007

<sup>1.</sup> Located in program flash 0 reserved space; Flash address [23] = 0

After clearing CCIF to launch the Read Resource command, four consecutive bytes are read from the selected resource at the provided relative address and stored in the FCCOB register. The CCIF flag sets after the Read Resource operation completes. The Read Resource command exits with an access error if an invalid resource code is provided or if the address for the applicable area is out-of-range.

Table 28-38. Read Resource Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid resource code is entered	FSTAT[ACCERR]

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

<sup>1.</sup> Must be longword aligned (Flash address [1:0] = 00).



### Table 28-38. Read Resource Command Error Handling (continued)

Error Condition	Error Bit
Flash address is out-of-range for the targeted resource.	FSTAT[ACCERR]
Flash address is not longword aligned	FSTAT[ACCERR]

### 28.4.10.5 Program Longword Command

The Program Longword command programs four previously-erased bytes in the program flash memory using an embedded algorithm.

#### **CAUTION**

A Flash memory location must be in the erased state before being programmed. Cumulative programming of bits (back-to-back program operations without an intervening erase) within a Flash memory location is not allowed. Re-programming of existing 0s to 0 is not allowed as this overstresses the device.

**Table 28-39. Program Longword Command FCCOB Requirements** 

FCCOB Number	FCCOB Contents [7:0]
0	0x06 (PGM4)
1	Flash address [23:16]
2	Flash address [15:8]
3	Flash address [7:0] <sup>1</sup>
4	Byte 0 program value
5	Byte 1 program value
6	Byte 2 program value
7	Byte 3 program value

<sup>1.</sup> Must be longword aligned (Flash address [1:0] = 00).

Upon clearing CCIF to launch the Program Longword command, the FTFL programs the data bytes into the flash using the supplied address. The swap indicator address in each program flash block is implicitly protected from programming. The targeted flash locations must be currently unprotected (see the description of the FPROT registers) to permit execution of the Program Longword operation.

The programming operation is unidirectional. It can only move NVM bits from the erased state ('1') to the programmed state ('0'). Erased bits that fail to program to the '0' state are flagged as errors in MGSTAT0. The CCIF flag is set after the Program Longword operation completes.



#### **Fiash Operation in Low-Power Modes**

The supplied address must be longword aligned (flash address [1:0] = 00):

- Byte 0 data is written to the supplied address ('start'),
- Byte 1 data is programmed to byte address start+0b01,
- Byte 2 data is programmed to byte address start+0b10, and
- Byte 3 data is programmed to byte address start+0b11.

Table 28-40. Program Longword Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid flash address is supplied	FSTAT[ACCERR]
Flash address is not longword aligned FSTAT[ACCERF	
Flash address points to a protected area FSTAT[FPVIO	
Any errors have been encountered during the verify operation FSTAT[I	

### 28.4.10.6 Erase Flash Block Command

The Erase Flash Block operation erases all addresses in a single program flash.

Table 28-41. Erase Flash Block Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x08 (ERSBLK)
1	Flash address [23:16] in the flash block to be erased
2	Flash address [15:8] in the flash block to be erased
3	Flash address [7:0] <sup>1</sup> in the flash block to be erased

<sup>1.</sup> Must be longword aligned (Flash address [1:0] = 00).

Upon clearing CCIF to launch the Erase Flash Block command, the FTFL erases the main array of the selected flash block and verifies that it is erased. The Erase Flash Block command aborts and sets the FSTAT[FPVIOL] bit if any region within the block is protected (see the description of the FPROT registers). The swap indicator address in each program flash block is implicitly protected from block erase unless the swap system is in the UPDATE or UPDATE-ERASED state and the program flash block being erased is the non-active block. If the erase verify fails, the MGSTAT0 bit in FSTAT is set. The CCIF flag will set after the Erase Flash Block operation has completed.

Table 28-42. Erase Flash Block Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]



Table 28-42. Erase Flash Block Command Error Handling (continued)

Error Condition	Error Bit
Program flash is selected and the address is out of program flash range	FSTAT[ACCERR]
Flash address is not longword aligned	FSTAT[ACCERR]
Any area of the selected flash block is protected	FSTAT[FPVIOL]
Any errors have been encountered during the verify operation	FSTAT[MGSTAT0]

#### 28.4.10.7 Erase Flash Sector Command

The Erase Flash Sector operation erases all addresses in a Flash sector.

Table 28-43. Erase Flash Sector Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x09 (ERSSCR)
1	Flash address [23:16] in the flash sector to be erased
2	Flash address [15:8] in the flash sector to be erased
3	Flash address [7:0] <sup>1</sup> in the flash sector to be erased

<sup>1.</sup> Must be phrase aligned (flash address [2:0] = 000).

After clearing CCIF to launch the Erase Flash Sector command, the FTFL erases the selected program flash sector and then verifies that it is erased. The Erase Flash Sector command aborts if the selected sector is protected (see the description of the FPROT registers). The swap indicator address in each program flash block is implicitly protected from sector erase unless the swap system is in the UPDATE or UPDATE-ERASED state and the program flash sector containing the swap indicator address being erased is the non-active block. If the erase-verify fails the FSTAT[MGSTAT0] bit is set. The CCIF flag is set after the Erase Flash Sector operation completes. The Erase Flash Sector command is suspendable (see the FCNFG[ERSSUSP] bit and Figure 28-25).

Table 28-44. Erase Flash Sector Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid Flash address is supplied	FSTAT[ACCERR]
Flash address is not phrase aligned	FSTAT[ACCERR]
The selected program flash sector is protected	FSTAT[FPVIOL]
Any errors have been encountered during the verify operation	FSTAT[MGSTAT0]



**Fiasil Operation in Low-Power Modes** 

### 28.4.10.7.1 Suspending an Erase Flash Sector Operation

To suspend an Erase Flash Sector operation set the FCNFG[ERSSUSP] bit (see Flash Configuration Field Description) when CCIF is clear and the CCOB command field holds the code for the Erase Flash Sector command. During the Erase Flash Sector operation (see Erase Flash Sector Command), the FTFL samples the state of the ERSSUSP bit at convenient points. If the FTFL detects that the ERSSUSP bit is set, the Erase Flash Sector operation is suspended and the FTFL sets CCIF. While ERSSUSP is set, all writes to FTFL registers are ignored except for writes to the FSTAT and FCNFG registers.

If an Erase Flash Sector operation effectively completes before the FTFL detects that a suspend request has been made, the FTFL clears the ERSSUSP bit prior to setting CCIF. When an Erase Flash Sector operation has been successfully suspended, the FTFL sets CCIF and leaves the ERSSUSP bit set. While CCIF is set, the ERSSUSP bit can only be cleared to prevent the withdrawal of a suspend request before the FTFL has acknowledged it.

### 28.4.10.7.2 Resuming a Suspended Erase Flash Sector Operation

If the ERSSUSP bit is still set when CCIF is cleared to launch the next command, the previous Erase Flash Sector operation resumes. The FTFL acknowledges the request to resume a suspended operation by clearing the ERSSUSP bit. A new suspend request can then be made by setting ERSSUSP. A single Erase Flash Sector operation can be suspended and resumed multiple times.

There is a minimum elapsed time limit between the request to resume the Erase Flash Sector operation (CCIF is cleared) and the request to suspend the operation again (ERSSUSP is set). This minimum time period is required to ensure that the Erase Flash Sector operation will eventually complete. If the minimum period is continually violated, i.e. the suspend requests come repeatedly and too quickly, no forward progress is made by the Erase Flash Sector algorithm. The resume/suspend sequence runs indefinitely without completing the erase.

### 28.4.10.7.3 Aborting a Suspended Erase Flash Sector Operation

The user may choose to abort a suspended Erase Flash Sector operation by clearing the ERSSUSP bit prior to clearing CCIF for the next command launch. When a suspended operation is aborted, the FTFL starts the new command using the new FCCOB contents.

#### Note

Aborting the erase leaves the bitcells in an indeterminate, partially-erased state. Data in this sector is not reliable until a new erase command fully completes.



The following figure shows how to suspend and resume the Erase Flash Sector operation.




Figure 28-25. Suspend and Resume of Erase Flash Sector Operation



### 28.4.10.8 Program Section Command

The Program Section operation programs the data found in the section program buffer to previously erased locations in the flash memory using an embedded algorithm. Data is preloaded into the section program buffer (see Flash Sector Programming).

The section program buffer is limited to the lower half of the RAM. Data written to the upper half of the RAM is ignored and may be overwritten during Program Section command execution.

#### **CAUTION**

A flash memory location must be in the erased state before being programmed. Cumulative programming of bits (back-to-back program operations without an intervening erase) within a flash memory location is not allowed. Re-programming of existing 0s to 0 is not allowed as this overstresses the device.

Table 28-45.	Program Section (	Command FCCOB	Requirements
--------------	-------------------	---------------	--------------

FCCOB Number	FCCOB Contents [7:0]
0	0x0B (PGMSEC)
1	Flash address [23:16]
2	Flash address [15:8]
3	Flash address [7:0] <sup>1</sup>
4	Number of phrases to program [15:8]
5	Number of phrases to program [7:0]

<sup>1.</sup> Must be phrase aligned (Flash address [2:0] = 000).

After clearing CCIF to launch the Program Section command, the FTFL blocks access to the programming acceleration RAM and programs the data residing in the section program buffer into the flash memory starting at the flash address provided.

The starting address must be unprotected (see the description of the FPROT registers) to permit execution of the Program Section operation. The swap indicator address in each program flash block is implicitly protected from erase. If the swap indicator address is encountered during the Program Section operation, it is bypassed without setting FPVIOL and the contents are not programmed. Programming, which is not allowed to cross a flash sector boundary, continues until all requested phrases have been programmed. The Program Section command also verifies that after programming, all bits requested to be programmed are programmed.



After the Program Section operation completes, the CCIF flag is set. The contents of the section program buffer may be changed by the Program Section operation.

Table 28-46. Program Section Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid flash address is supplied	FSTAT[ACCERR]
Flash address is not phrase aligned	FSTAT[ACCERR]
The requested section crosses a program flash sector boundary	FSTAT[ACCERR]
The requested number of phrases is zero	FSTAT[ACCERR]
The space required to store data for the requested number of phrases is more than half the size of the programming acceleration RAM	FSTAT[ACCERR]
The flash address falls in a protected area FSTAT[FPVIC	
Any errors have been encountered during the verify operation	FSTAT[MGSTAT0]

### 28.4.10.8.1 Flash Sector Programming

The process of programming an entire flash sector using the Program Section command is as follows:

- 1. Launch the Erase Flash Sector command to erase the flash sector to be programmed.
- 2. Beginning with the starting address of the programming acceleration RAM, sequentially write enough data to the RAM to fill an entire flash sector. This area of the RAM serves as the section program buffer. The section program buffer can be written to while the operation launched in step 1 is executing, i.e. while CCIF = 0.
- 3. Execute the Program Section command to program the contents of the section program buffer into the selected flash sector.
- 4. To program additional flash sectors, repeat steps 1 through 3.

### 28.4.10.9 Read 1s All Blocks Command

The Read 1s All Blocks command checks if the program flash blocks have been erased to the specified read margin level, if applicable, and releases security if the readout passes, i.e. all data reads as '1'.

Table 28-47. Read 1s All Blocks Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x40 (RD1ALL)
1	Read-1 Margin Choice



#### **Fiash Operation in Low-Power Modes**

After clearing CCIF to launch the Read 1s All Blocks command, the FTFL:

- sets the read margin for 1s according to Table 28-48,
- checks the contents of the program flash are in the erased state.

If the FTFL confirms that these memory resources are erased, security is released by setting the FSEC[SEC] field to the unsecure state. The security byte in the flash configuration field (see Flash Configuration Field Description) remains unaffected by the Read 1s All Blocks command. If the read fails, i.e. all memory resources are not in the fully erased state, the FSTAT[MGSTAT0] bit is set.

The EEERDY and RAMRDY bits are clear during the Read 1s All Blocks operation and are restored at the end of the Read 1s All Blocks operation.

The CCIF flag sets after the Read 1s All Blocks operation has completed.

Table 28-48. Margin Level Choices for Read 1s All Blocks

Read Margin Choice	Margin Level Description
0x00	Use the 'normal' read level for 1s
0x01	Apply the 'User' margin to the normal read-1 level
0x02	Apply the 'Factory' margin to the normal read-1 level

Table 28-49. Read 1s All Blocks Command Error Handling

Error Condition	Error Bit
An invalid margin choice is specified	FSTAT[ACCERR]
Read-1s fails FSTAT[MGS	

#### 28.4.10.10 Read Once Command

The Read Once command provides read access to a reserved 64-byte field located in the program flash 0 IFR (see Program Flash IFR Map and Program Once Field). Access to this field is via 16 records, each 4 bytes long. The Read Once field is programmed using the Program Once command described in Program Once Command.

Table 28-50. Read Once Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x41 (RDONCE)
1	Read Once record index (0x00 - 0x0F)
2	Not used
3	Not used



Table 28-50. Read Once Command FCCOB Requirements (continued)

FCCOB Number	FCCOB Contents [7:0]	
	Returned Values	
4	Read Once byte 0 value	
5	Read Once byte 1 value	
6	Read Once byte 2 value	
7	Read Once byte 3 value	

After clearing CCIF to launch the Read Once command, a 4-byte Read Once record is read from the program flash IFR and stored in the FCCOB register. The CCIF flag is set after the Read Once operation completes. Valid record index values for the Read Once command range from 0x00 to 0x0F. During execution of the Read Once command, any attempt to read addresses within the program flash block containing this 64-byte field returns invalid data. The Read Once command can be executed any number of times.

Table 28-51. Read Once Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid record index is supplied	FSTAT[ACCERR]

# 28.4.10.11 Program Once Command

The Program Once command enables programming to a reserved 64-byte field in the program flash 0 IFR (see Program Flash IFR Map and Program Once Field). Access to the Program Once field is via 16 records, each 4 bytes long. The Program Once field can be read using the Read Once command (see Read Once Command) or using the Read Resource command (see Read Resource Command). Each Program Once record can be programmed only once since the program flash 0 IFR cannot be erased.

Table 28-52. Program Once Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x43 (PGMONCE)
1	Program Once record index (0x00 - 0x0F)
2	Not Used
3	Not Used
4	Program Once Byte 0 value
5	Program Once Byte 1 value
6	Program Once Byte 2 value



riasi) Operation in Low-Power Modes

Table 28-52. Program Once Command FCCOB Requirements (continued)

FCCOB Number	FCCOB Contents [7:0]
7	Program Once Byte 3 value

After clearing CCIF to launch the Program Once command, the FTFL first verifies that the selected record is erased. If erased, then the selected record is programmed using the values provided. The Program Once command also verifies that the programmed values read back correctly. The CCIF flag is set after the Program Once operation has completed.

The reserved program flash 0 IFR location accessed by the Program Once command cannot be erased and any attempt to program one of these records when the existing value is not Fs (erased) is not allowed. Valid record index values for the Program Once command range from 0x00 to 0x0F. During execution of the Program Once command, any attempt to read addresses within program flash 0 returns invalid data.

**Table 28-53. Program Once Command Error Handling** 

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
An invalid record index is supplied	FSTAT[ACCERR]
The requested record has already been programmed to a non-FFFF value <sup>1</sup>	FSTAT[ACCERR]
Any errors have been encountered during the verify operation	FSTAT[MGSTAT0]

<sup>1.</sup> If a Program Once record is initially programmed to 0xFFFF\_FFFF, the Program Once command is allowed to execute again on that same record.

#### 28.4.10.12 Erase All Blocks Command

The Erase All Blocks operation erases all flash memory, verifies all memory contents, and releases MCU security.

Table 28-54. Erase All Blocks Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x44 (ERSALL)

After clearing CCIF to launch the Erase All Blocks command, the FTFL erases all program flash memory, program flash 1 IFR space, then verifies that all are erased.

If the FTFL verifies that all flash memories were properly erased, security is released by setting the FSEC[SEC] field to the unsecure state and the FCNFG[RAMRDY] bit is set. The Erase All Blocks command aborts if any flash region is protected. The swap indicator address in each program flash block is not implicitly protected from the Erase



All Blocks operation. The security byte and all other contents of the flash configuration field (see Flash Configuration Field Description) are erased by the Erase All Blocks command. If the erase-verify fails, the FSTAT[MGSTAT0] bit is set. The CCIF flag is set after the Erase All Blocks operation completes.

Table 28-55. Erase All Blocks Command Error Handling

Error Condition	Error Bit
Command not available in current mode/security	FSTAT[ACCERR]
Any region of the program flash memory is protected	FSTAT[FPVIOL]
Any errors have been encountered during the verify operation	FSTAT[MGSTAT0]

### 28.4.10.12.1 Triggering an Erase All External to the FTFL

The functionality of the Erase All Blocks command is also available in an uncommanded fashion outside of the flash memory. Refer to the device's Chip Configuration details for information on this functionality.

Before invoking the external erase all function, the FSTAT[ACCERR and PVIOL] flags must be cleared and the FCCOB0 register must not contain 0x44. When invoked, the erase-all function erases all program flash memory, program flash 1 IFR space regardless of the protection settings or if the swap system has been initialized. If the post-erase verify passes, the routine then releases security by setting the FSEC[SEC] field register to the unsecure state and the FCNFG[RAMRDY] bit sets. The security byte in the Flash Configuration Field is also programmed to the unsecure state. The status of the erase-all request is reflected in the FCNFG[ERSAREQ] bit. The FCNFG[ERSAREQ] bit is cleared once the operation completes and the normal FSTAT error reporting is available as described in Erase All Blocks Command.

# 28.4.10.13 Verify Backdoor Access Key Command

The Verify Backdoor Access Key command only executes if the mode and security conditions are satisfied (see FTFL Commands by Mode). Execution of the Verify Backdoor Access Key command is further qualified by the FSEC[KEYEN] bits. The Verify Backdoor Access Key command releases security if user-supplied keys in the FCCOB match those stored in the Backdoor Comparison Key bytes of the Flash Configuration Field (see Flash Configuration Field Description). The column labelled Flash Configuration Field offset address shows the location of the matching byte in the Flash Configuration Field.

**Fiash Operation in Low-Power Modes** 

Table 28-56. Verify Backdoor Access Key Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]	Flash Configuration Field Offset Address
0	0x45 (VFYKEY)	
1-3	Not Used	
4	Key Byte 0	0x0_0000
5	Key Byte 1	0x0_0001
6	Key Byte 2	0x0_0002
7	Key Byte 3	0x0_0003
8	Key Byte 4	0x0_0004
9	Key Byte 5	0x0_0005
А	Key Byte 6	0x0_0006
В	Key Byte 7	0x0_0007

After clearing CCIF to launch the Verify Backdoor Access Key command, the FTFL checks the FSEC[KEYEN] bits to verify that this command is enabled. If not enabled, the FTFL sets the FSTAT[ACCERR] bit and terminates. If the command is enabled, the FTFL compares the key provided in FCCOB to the backdoor comparison key in the Flash Configuration Field. If the backdoor keys match, the FSEC[SEC] field is changed to the unsecure state and security is released. If the backdoor keys do not match, security is not released and all future attempts to execute the Verify Backdoor Access Key command are immediately aborted and the FSTAT[ACCERR] bit is (again) set to 1 until a reset of the FTFL module occurs. If the entire 8-byte key is all zeros or all ones, the Verify Backdoor Access Key command fails with an access error. The CCIF flag is set after the Verify Backdoor Access Key operation completes.

Table 28-57. Verify Backdoor Access Key Command Error Handling

Error Condition	Error Bit
The supplied key is all-0s or all-Fs	FSTAT[ACCERR]
An incorrect backdoor key is supplied	FSTAT[ACCERR]
Backdoor key access has not been enabled (see the description of the FSEC register)	FSTAT[ACCERR]
This command is launched and the backdoor key has mismatched since the last power down reset	FSTAT[ACCERR]

# 28.4.10.14 Swap Control Command

The Swap Control command handles specific activities associated with swapping the two logical program flash memory blocks within the memory map.



Table 28-58. Swap Control Command FCCOB Requirements

FCCOB Number	FCCOB Contents [7:0]
0	0x46 (SWAP)
1	Flash address [23:16]
2	Flash address [15:8]
3	Flash address [7:0] 1
	Swap Control Code:
	0x01 - Initialize Swap System
4	0x02 - Set Swap in Update State
	0x04 - Set Swap in Complete State
	0x08 - Report Swap Status
Returned values	
	Current Swap State:
	0x00 - Uninitialized
F	0x01 - Ready
5	0x02 - Update
	0x03 - Update-Erased
	0x04 - Complete
	Current Swap Block Status:
6	0x00 - Program flash block 0 at 0x0_0000
	0x01 - Program flash block 1 at 0x0_0000
	Next Swap Block Status (after any reset):
7	0x00 - Program flash block 0 at 0x0_0000
	0X01 - Program flash block 1 at 0x0_0000

<sup>1.</sup> Must be phrase-aligned (Flash address [2:0] = 000).

Upon clearing CCIF to launch the Swap Control command, the FTFL will handle swap-related activities based on the swap control code provided in FCCOB4 as follows:

- 0x01 (Initialize Swap System to UPDATE-ERASED State) After verifying that the current swap state is UNINITIALIZED and that the flash address provided is in Program flash block 0 but not in the Flash Configuration Field, the flash address (shifted with bits[2:0] removed) will be programmed into the IFR Swap Field found in program flash 1 IFR. After the swap indicator address has been programmed into the IFR Swap Field, the swap enable word will be programmed to 0x0000. After the swap enable word has been programmed, the swap indicator, located within the Program flash block 0 address provided, will be programmed to 0xFF00.
- 0x02 (Progress Swap to UPDATE State) After verifying that the current swap state is READY and that the flash address provided matches the one stored in the IFR Swap Field, the swap indicator located within bits [15:0] of the flash address in the currently active program flash block will be programmed to 0xFF00.



#### **Fiash Operation in Low-Power Modes**

- 0x04 (Progress Swap to COMPLETE State) After verifying that the current swap state is UPDATE-ERASED and that the flash address provided matches the one stored in the IFR Swap Field, the swap indicator located within bits [15:0] of the flash address in the currently active program flash block will be programmed to 0x0000. Before executing with this swap control code, the user must erase the non-active swap indicator using the Erase Flash Block or Erase Flash Sector commands and update the application code or data as needed. The non-active swap indicator will be checked at the erase verify level and if the check fails, the current swap state will be changed to UPDATE with ACCERR set.
- 0x08 (Report Swap System Status) After verifying that the flash address provided matches the one stored in the IFR Swap Field, the status of the swap system will be reported as follows:
  - FCCOB5 (Current Swap State) indicates the current swap state based on the status of the swap enable word and the swap indicators. If the MGSTATO flag is set after command completion, the swap state returned was not successfully transitioned from and the appropriate swap command code must be attempted again. If the current swap state is UPDATE and the non-active swap indicator is 0xFFFF, the current swap state is changed to UPDATE-ERASED.
  - FCCOB6 (Current Swap Block Status) indicates which program flash block is currently located at relative flash address 0x0\_0000.
  - FCCOB7 (Next Swap Block Status) indicates which program flash block will be located at relative flash address 0x0\_0000 after the next reset of the FTFL module.

#### NOTE

It is recommended that the user execute the Swap Control command to report swap status (code 0x08) after any reset to determine if issues with the swap system were detected during the swap state determination procedure.

#### NOTE

It is recommended that the user write 0xFF to FCCOB5, FCCOB6, and FCCOB7 since the Swap Control command will not always return the swap state and status fields when an ACCERR is detected.

The swap indicators are implicitly protected from being programmed during Program Longword or Program Section command operations and are implicitly unprotected during Swap Control command operations. The swap indicators are implicitly protected from being erased during Erase Flash Block and Erase Flash Sector command operations unless the swap indicator being erased is in the non-active program flash block and the



swap system is in the UPDATE or UPDATE-ERASED state. Once the swap system has been initialized, the Erase All Blocks command can be used to uninitialize the swap system.

Table 28-59. Swap Control Command Error Handling

Error Condition	Swap Control Code	Error Bit
Command not available in current mode/security <sup>1</sup>	All	FSTAT[ACCERR]
Flash address is not in program flash block 0	All	FSTAT[ACCERR]
Flash address is in the Flash Configuration Field	All	FSTAT[ACCERR]
Flash address is not phrase aligned	All	FSTAT[ACCERR]
Flash address does not match the swap indicator address in the IFR	2, 4	FSTAT[ACCERR]
Swap initialize requested when swap system is not in the uninitialized state	1	FSTAT[ACCERR]
Swap update requested when swap system is not in the ready state	2	FSTAT[ACCERR]
Swap complete requested when swap system is not in the update-erased state	4	FSTAT[ACCERR]
An undefined swap control code is provided	-	FSTAT[ACCERR]
Any errors have been encountered during the swap determination and program-verify operations	1, 2, 4	FSTAT[MGSTAT0]
Any brownouts were detected during the swap determination procedure	8	FSTAT[MGSTAT0]

<sup>1.</sup> Returned fields will not be updated, i.e. no swap state or status reporting






Figure 28-26. Valid Swap State Sequencing



### Table 28-60. Swap State Report Mapping

Case	Swap Enable Field <sup>1</sup>	Swap Indicator 01	Swap Indicator 11	Swap State <sup>2</sup>	State Code	MGST AT0	Active Block
1	0xFFFF	-	-	Uninitialized	0	0	0
2	0x0000	0xFF00	0x0000	Update	2	0	0
3	0x0000	0xFF00-	0xFFFF	Update-Erased	3	0	0
4	0x0000	0x0000	0xFFFF <sup>3</sup>	Complete <sup>4</sup>	4	0	0
5	0x0000	0x0000	0xFFFF	Ready <sup>5</sup>	1	0	1
6	0x0000	0x0000	0xFF00	Update	2	0	1
7	0x0000	0xFFFF	0xFF00	Update-Erased	3	0	1
8	0x0000	0xFFFF <sup>3</sup>	0x0000	Complete <sup>4</sup>	4	0	1
9	0x0000	0xFFFF	0x0000	Ready <sup>5</sup>	1	0	0
10	0xXXXX	-	-	Uninitialized	0	1	0
11	0x0000	0xFFFF	0xFFFF	Uninitialized	0	1	0
12	0x0000	0xFFXX	0xFFFF	Ready	1	1	0
13	0x0000	0xFFXX	0x0000	Ready	1	1	0
14 <sup>6</sup>	0x0000	0xXXXX	0x0000	Ready	1	1	0
15 <sup>6</sup>	0x0000	0xFFFF	0xFFXX	Ready	1	1	1
16	0x0000	0x0000	0xFFXX	Ready	1	1	1
17 <sup>6</sup>	0x0000	0x0000	0xXXXX	Ready	1	1	1
18	0x0000	0xFF00	0xFFFF <sup>7</sup>	Update	2	1	0
19	0x0000	0xFF00	0xXXXX	Update	2	1	0
20	0x0000	0xFF(00)	0xFFXX	Update	2	1	0
21 <sup>6</sup>	0x0000	0x0000	0x0000	Update	2	1	0
22 <sup>6</sup>	0x0000	0xXXXX	0xXXXX	Update	2	1	0
23	0x0000	0xFFFF <sup>7</sup>	0xFF00	Update	2	1	1
24	0x0000	0xXXXX	0xFF00	Update	2	1	1
25	0x0000	0xFFXX	0xFF(00)	Update	2	1	1
26	0x0000	0xXX00	0xFFFF	Update-Erased	3	1	0
27	0x0000	0xXXXX	0xFFFF	Update-Erased	3	1	0
28	0x0000	0xFFFF	0xXX00	Update-Erased	3	1	1
29	0x0000	0xFFFF	0xXXXX	Update-Erased	3	1	1

<sup>1. 0</sup>xXXXX, 0xFFXX, 0xXX00 indicates a non-valid value was read; 0xFF(00) indicates more 0's than other indicator (if same number of 0's, then swap system defaults to block 0 active)

<sup>2.</sup> Cases 10-29 due to brownout (abort) detected during program or erase steps related to swap

<sup>3.</sup> Must read 0xFFFF with erase verify level before transition to Complete allowed

<sup>4.</sup> No reset since successful Swap Complete execution

<sup>5.</sup> Reset after successful Swap Complete execution

<sup>6.</sup> Not a valid case

<sup>7.</sup> Fails to read 0xFFFF at erase verify level



## 28.4.10.14.1 Swap State Determination

During the reset sequence, the state of the swap system is determined by evaluating the IFR Swap Field in the program flash 1 IFR and the swap indicators located in each of the program flash blocks at the swap indicator address stored in the IFR Swap Field.

 Address Range
 Size (Bytes)
 Field Description

 0x00 – 0x01
 2
 Swap Enable Word

 0x02 – 0x03
 2
 Swap Indicator Address

 0x04 – 0xFF
 252
 Reserved

Table 28-61. Program Flash 1 IFR Swap Field

## 28.4.11 **Security**

The FTFL module provides security information to the MCU based on contents of the FSEC security register. The MCU then limits access to FTFL resources as defined in the device's Chip Configuration details. During reset, the FTFL module initializes the FSEC register using data read from the security byte of the Flash Configuration Field (see Flash Configuration Field Description).

The following fields are available in the FSEC register. The settings are described in the Flash Security Register (FTFL\_FSEC) details.

FSEC field

Description

KEYEN

Backdoor Key Access

MEEN

Mass Erase Capability

FSLACC

Freescale Factory Access

SEC

MCU security

Table 28-62. FSEC register fields

## 28.4.11.1 FTFL Access by Mode and Security

The following table summarizes how access to the FTFL module is affected by security and operating mode.



#### Table 28-63. FTFL Access Summary

Operating Mode	Chip Security State		
Operating wode	Unsecure	Secure	
NVM Normal	Full command set		
NVM Special	Full command set  Only the Erase All Blocks and Read Blocks commands.		

## 28.4.11.2 Changing the Security State

The security state out of reset can be permanently changed by programming the security byte of the flash configuration field. This assumes that you are starting from a mode where the necessary program flash erase and program commands are available and that the region of the program flash containing the flash configuration field is unprotected. If the flash security byte is successfully programmed, its new value takes affect after the next chip reset.

## 28.4.11.2.1 Unsecuring the Chip Using Backdoor Key Access

The chip can be unsecured by using the backdoor key access feature, which requires knowledge of the contents of the 8-byte backdoor key value stored in the Flash Configuration Field (see Flash Configuration Field Description). If the FSEC[KEYEN] bits are in the enabled state, the Verify Backdoor Access Key command (see Verify Backdoor Access Key Command) can be run; it allows the user to present prospective keys for comparison to the stored keys. If the keys match, the FSEC[SEC] bits are changed to unsecure the chip. The entire 8-byte key cannot be all 0s or all 1s; that is,  $0000\_0000\_0000\_0000$  and FFFF\_FFFF\_FFFFFFFFFFFF are not accepted by the Verify Backdoor Access Key command as valid comparison values. While the Verify Backdoor Access Key command is active, program flash memory is not available for read access and returns invalid data.

The user code stored in the program flash memory must have a method of receiving the backdoor keys from an external stimulus. This external stimulus would typically be through one of the on-chip serial ports.

If the KEYEN bits are in the enabled state, the chip can be unsecured by the following backdoor key access sequence:

- 1. Follow the command sequence for the Verify Backdoor Access Key command as explained in Verify Backdoor Access Key Command
- 2. If the Verify Backdoor Access Key command is successful, the chip is unsecured and the FSEC[SEC] bits are forced to the unsecure state



#### **Fiash Operation in Low-Power Modes**

An illegal key provided to the Verify Backdoor Access Key command prohibits further use of the Verify Backdoor Access Key command. A reset of the chip is the only method to re-enable the Verify Backdoor Access Key command when a comparison fails.

After the backdoor keys have been correctly matched, the chip is unsecured by changing the FSEC[SEC] bits. A successful execution of the Verify Backdoor Access Key command changes the security in the FSEC register only. It does not alter the security byte or the keys stored in the Flash Configuration Field (Flash Configuration Field Description). After the next reset of the chip, the security state of the FTFL module reverts back to the flash security byte in the Flash Configuration Field. The Verify Backdoor Access Key command sequence has no effect on the program and erase protections defined in the program flash protection registers.

If the backdoor keys successfully match, the unsecured chip has full control of the contents of the Flash Configuration Field. The chip may erase the sector containing the Flash Configuration Field and reprogram the flash security byte to the unsecure state and change the backdoor keys to any desired value.

## 28.4.12 Reset Sequence

On each system reset the FTFL module executes a sequence which establishes initial values for the flash block configuration parameters, FPROT, FOPT, and FSEC registers and the FCNFG[SWAP, PFLSH, RAMRDY, EEERDY] bits.

CCIF is cleared throughout the reset sequence. The FTFL module holds off all CPU access for a portion of the reset sequence. Flash reads are possible when the hold is removed. Completion of the reset sequence is marked by setting CCIF which enables flash user commands.

If a reset occurs while any FTFL command is in progress, that command is immediately aborted. The state of the word being programmed or the sector/block being erased is not guaranteed. Commands and operations do not automatically resume after exiting reset.



# **Chapter 29 External Bus Interface (FlexBus)**

## 29.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

This chapter describes external bus data transfer operations and error conditions. It describes transfers initiated by the core processor (or any other bus master) and includes detailed timing diagrams showing the interaction of signals in supported bus operations.

#### **29.1.1 Overview**

A multi-function external bus interface called the FlexBus interface controller is provided on the device with basic functionality of interfacing to slave-only devices. It can be directly connected to the following asynchronous or synchronous devices with little or no additional circuitry:

- External ROMs
- Flash memories
- Programmable logic devices
- Other simple target (slave) devices

For asynchronous devices, a simple chip-select based interface can be used.

The FlexBus interface has up to six general purpose chip-selects,  $\overline{FB}$  [5:0]. The actual number of chip selects available depends upon the device and its pin configuration.



**Signal Descriptions** 

#### **29.1.2 Features**

Key FlexBus features include:

- Six independent, user-programmable chip-select signals (FB\_CS[5:0]) that can interface with external SRAM, PROM, EPROM, EEPROM, flash, and other peripherals
- 8-, 16-, and 32-bit port sizes with configuration for multiplexed or non-multiplexed address and data buses
- 8-bit, 16-bit, 32-bit, and 16-byte transfers
- Programmable burst- and burst-inhibited transfers selectable for each chip select and transfer direction
- Programmable address-setup time with respect to the assertion of chip select
- Programmable address-hold time with respect to the negation of chip select and transfer direction
- Extended address latch enable option helps with glueless connections to synchronous and asynchronous memory devices

## 29.1.3 Modes of Operation

The external interface is a configurable multiplexed bus set to one of the following modes:

- Multiplexed 32-bit address and 32-bit data
- Multiplexed 32-bit address and 16-bit data (non-multiplexed 16-bit address and 16-bit data)
- Multiplexed 32-bit address and 8-bit data (non-multiplexed 24-bit address and 8-bit data)
- Non-multiplexed 32-bit address and 32-bit data busses

## 29.2 Signal Descriptions

This section describes the external signals involved in data-transfer operations.

#### NOTE

Not all of the following signals may be available on a particular device. See the Chip Configuration details for information on which signals are available.



#### Table 29-1. FlexBus Signal Summary

Signal	Description	I/O
FB_A[31:0]	In a non-multiplexed configuration, this is the address bus.	0
FB_D[31:0]/ FB_AD[31:0]	In a non-multiplexed configuration, this is the data bus. In a multiplexed configuration this bus is the address/data bus, FB_AD[31:0]. In non-multiplexed and multiplexed configurations, during the first cycle, this bus drives the upper address byte, addr[31:24].	I/O
FB_CS[5:0]	General purpose chip-selects. The actual number of chip selects available depends upon the device and its pin configuration.	0
FB_BE_31_24	Byte enables	0
FB_BE_23_16		
FB_BE_15_8		
FB_BE_7_0		
FB_OE	Output enable	0
FB_R/W	Read/write. 1 = Read, 0 = Write	0
FB_TS	Transfer start	0
FB_ALE	Address latch enable (an inverse of FB_TS)	0
FB_TSIZ[1:0]	Transfer size	0
FB_TBST	Burst transfer indicator	0
FB_TA	Transfer acknowledge	1
FB_CLK	FlexBus clock output	0

## 29.2.1 Address and Data Buses (FB\_An, FB\_Dn, FB\_ADn)

In non-multiplexed mode, the FB\_A[31:0] and FB\_D[31:0] buses carry the address and data, respectively. The number of byte lanes carrying the data is determined by the port size associated with the matching chip select.

In multiplexed mode, the FB\_AD[31:0] bus carries the address and data. The full 32-bit address is driven on the first clock of a bus cycle (address phase). Following the first clock, the data is driven on the bus (data phase). During the data phase, the address continues driving on the pins not used for data. For example, in 16-bit mode the lower address continues driving on FB\_AD[15:0] and in 8-bit mode the lower address continues driving on FB\_AD[23:0].



orginal Descriptions

## 29.2.2 Chip Selects (FB\_CS[5:0])

The chip-select signal indicates which device is selected. A particular chip-select asserts when the transfer address is within the device's address space, as defined in the base- and mask-address registers. The actual number of chip selects available depends upon the pin configuration.

## 29.2.3 Byte Enables (FB\_BE\_31\_24, FB\_BE\_23\_16, FB\_BE\_15\_8, FB\_BE\_7\_0)

When driven low, the byte enable outputs indicate data is to be latched or driven onto a specific byte lane of the data bus. A configuration option is provided to assert these signals on reads and writes or writes only.

For external SRAM or flash devices, the  $\overline{FB}$  outputs must be connected to individual byte strobe signals.

## 29.2.4 Output Enable (FB\_OE)

The output enable signal (FB\_OE) is sent to the interfacing memory and/or peripheral to enable a read transfer. FB\_OE is only asserted during read accesses when a chip select matches the current address decode.

## 29.2.5 Read/Write (FB\_R/ $\overline{W}$ )

The processor drives the  $FB_R/\overline{W}$  signal to indicate the current bus operation direction. It is driven high during read bus cycles and low during write bus cycles.

## 29.2.6 Transfer Start/Address Latch Enable (FB\_TS/FB\_ALE)

The assertion of FB\_TS indicates that the device has begun a bus transaction and the address and attributes are valid.

In multiplexed mode, an inverted FB\_TS (FB\_ALE) is available as an address latch enable, which indicates when the address is being driven on the FB\_AD bus.

FB\_TS/FB\_ALE is asserted for one bus clock cycle.

This device can extend this signal until the first positive clock edge after FB\_CSn asserts. See CSCRn[EXTS] and Extended Transfer Start/Address Latch Enable.



## 29.2.7 Transfer Size (FB\_TSIZ[1:0])

For memory accesses, these signals, along with FB\_TBST, indicate the data transfer size of the current bus operation. The interface supports 8-, 16-, and 32-bit operand transfers and allows accesses to 8-, 16-, and 32-bit data ports.

For misaligned transfers, FB\_TSIZ[1:0] indicates the size of each transfer. For example, if a 32-bit access through a 32-bit port device occurs at a misaligned offset of 0x1, 8 bits is transferred first (FB\_TSIZ[1:0] = 01), 16 bits is transferred next at offset 0x2 (FB\_TSIZ[1:0] = 10), and the final 8 bits is transferred at offset 0x4 (FB\_TSIZ[1:0] = 01).

For aligned transfers larger than the port size, FB\_TSIZ[1:0] behaves as follows:

- If bursting is used, FB\_TSIZ[1:0] is driven to the transfer size.
- If bursting is inhibited, FB\_TSIZ[1:0] first shows the entire transfer size and then shows the port size.

FB_TSIZ[1:0]	Transfer Size
00	4 bytes
01	1 byte
10	2 bytes
11	16 bytes (line)

Table 29-2. Data Transfer Size

For burst-inhibited transfers, FB\_TSIZ[1:0] changes with each  $\overline{FB}$ \_TS assertion to reflect the next transfer size. For transfers to port sizes smaller than the transfer size, FB\_TSIZ[1:0] indicates the size of the entire transfer on the first access and the size of the current port transfer on subsequent transfers. For example, for a 32-bit write to an 8-bit port, FB\_TSIZ[1:0] equals 00 for the first transaction and 01 for the next three transactions. If bursting is used for a 32-bit write to an 8-bit port, FB\_TSIZ[1:0] is driven to 00 for the entire transfer.

## 29.2.8 Transfer Burst (FB\_TBST)

Transfer burst indicates that a burst transfer is in progress as driven by the device. A burst transfer can be two to 16 beats depending on FB\_TSIZ[1:0] and the port size.



#### **Note**

When burst ( $\overline{FB}$ \_TBST = 0), transfer size is 16 bytes (FB\_TSIZ[1:0] = 11) and the address is misaligned within the 16-byte boundary, the external device must be able to wrap around the address.

## 29.2.9 Transfer Acknowledge (FB\_TA)

This input signal indicates the external data transfer is complete. When the processor recognizes FB\_TA during a read cycle, it latches the data and then terminates the bus cycle. When the processor recognizes FB\_TA during a write cycle, the bus cycle is terminated.

If auto-acknowledge is disabled (CSCRn[AA] = 0), the external device drives  $\overline{FB\_TA}$  to terminate the bus transfer; if auto-acknowledge is enabled (CSCRn[AA] = 1),  $\overline{FB\_TA}$  is generated internally after a specified number of wait states, or the external device may assert external  $\overline{FB\_TA}$  before the wait-state countdown, terminating the cycle early. The device negates  $\overline{FB\_CSn}$  one cycle after the last  $\overline{FB\_TA}$  asserts. During read cycles, the peripheral must continue to drive data until  $\overline{FB\_TA}$  is recognized. For write cycles, the processor continues driving data one clock after  $\overline{FB\_CSn}$  is negated.

The number of wait states is determined by CSCRn or the external  $\overline{FB}$  input. If the external  $\overline{FB}$  is used, the peripheral has total control on the number of wait states.

#### **Note**

External devices should only assert  $\overline{FB}$ TA while the FBCSn signal to the external device is asserted.

The CSPMCR register controls muxing of FB\_TA with other signals. If auto-acknowledge is not used and CSPMCR does not allow FB\_TA control, the FlexBus may hang.

## 29.3 Memory Map/Register Definition

The following tables describe the registers and bit meanings for configuring chip-select operation.

The actual number of chip selects available depends upon the device and its pin configuration. If the device does not support certain chip select signals or the pin is not configured for a chip-select function, then that corresponding set of chip-select registers has no effect on an external pin.



## Note

You must set CSMR0[V] before the chip select registers take effect.

A bus error occurs when writing to reserved register locations.

## **FB** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_C000	Chip select address register (FB_CSAR0)	32	R/W	0000_0000h	29.3.1/ 662
4000_C004	Chip select mask register (FB_CSMR0)	32	R/W	0000_0000h	29.3.2/ 663
4000_C008	Chip select control register (FB_CSCR0)	32	R/W	0000_0000h	29.3.3/ 664
4000_C00C	Chip select address register (FB_CSAR1)	32	R/W	0000_0000h	29.3.1/ 662
4000_C010	Chip select mask register (FB_CSMR1)	32	R/W	0000_0000h	29.3.2/ 663
4000_C014	Chip select control register (FB_CSCR1)	32	R/W	0000_0000h	29.3.3/ 664
4000_C018	Chip select address register (FB_CSAR2)	32	R/W	0000_0000h	29.3.1/ 662
4000_C01C	Chip select mask register (FB_CSMR2)	32	R/W	0000_0000h	29.3.2/ 663
4000_C020	Chip select control register (FB_CSCR2)	32	R/W	0000_0000h	29.3.3/ 664
4000_C024	Chip select address register (FB_CSAR3)	32	R/W	0000_0000h	29.3.1/ 662
4000_C028	Chip select mask register (FB_CSMR3)	32	R/W	0000_0000h	29.3.2/ 663
4000_C02C	Chip select control register (FB_CSCR3)	32	R/W	0000_0000h	29.3.3/ 664
4000_C030	Chip select address register (FB_CSAR4)	32	R/W	0000_0000h	29.3.1/ 662
4000_C034	Chip select mask register (FB_CSMR4)	32	R/W	0000_0000h	29.3.2/ 663
4000_C038	Chip select control register (FB_CSCR4)	32	R/W	0000_0000h	29.3.3/ 664
4000_C03C	Chip select address register (FB_CSAR5)	32	R/W	0000_0000h	29.3.1/ 662



## FB memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4000_C040	Chip select mask register (FB_CSMR5)	32	R/W	0000_0000h	29.3.2/ 663
4000_C044	Chip select control register (FB_CSCR5)	32	R/W	0000_0000h	29.3.3/ 664
4000_C060	Chip select port multiplexing control register (FB_CSPMCR)	32	R/W	0000_0000h	29.3.4/ 667


## 29.3.1 Chip select address register (FB\_CSARn)

The CSARn registers specify the chip-select base addresses.

#### **NOTE**

Because the FlexBus module is one of the slaves connected to the crossbar switch, it is only accessible within a certain memory range. Refer to the device memory map for the applicable FlexBus "expansion" address range for which the chip-selects can be active. Set the CSARn registers appropriately.

Addresses: FB\_CSAR0 is 4000\_C000h base + 0h offset = 4000\_C000h FB\_CSAR1 is 4000\_C000h base + Ch offset = 4000\_C00Ch FB\_CSAR2 is 4000\_C000h base + 18h offset = 4000\_C018h FB\_CSAR3 is 4000\_C000h base + 24h offset = 4000\_C024h FB\_CSAR4 is 4000\_C000h base + 30h offset = 4000\_C030h FB\_CSAR5 is 4000\_C000h base + 3Ch offset = 4000\_C03Ch



#### FB\_CSARn field descriptions


Field	Description
31–16 BA	Base address  Defines the base address for memory dedicated to chip-select FB_CSn. BA is compared to bits 31–16 on the internal address bus to determine if chip-select memory is being accessed.
15–0 Reserved	This read-only field is reserved and always has the value zero.



## 29.3.2 Chip select mask register (FB\_CSMRn)

CSMRn registers specify the address mask and allowable access types for the respective chip-selects.

Addresses: FB\_CSMR0 is 4000\_C000h base + 4h offset = 4000\_C004h FB\_CSMR1 is 4000\_C000h base + 10h offset = 4000\_C010h FB\_CSMR2 is 4000\_C000h base + 1Ch offset = 4000\_C01Ch FB\_CSMR3 is 4000\_C000h base + 28h offset = 4000\_C028h FB\_CSMR4 is 4000\_C000h base + 34h offset = 4000\_C034h FB\_CSMR5 is 4000\_C000h base + 40h offset = 4000\_C040h



#### FB\_CSMRn field descriptions

Field	Description
31–16	Base address mask
BAM	Defines the chip-select block size by masking address bits. Setting a BAM bit causes the corresponding CSAR bit to be a don't care in the decode.
	The block size for $\overline{FB\_CSn}$ is $2^n$ ; $n = (number of bits set in respective CSMR[BAM]) + 16.$
	For example, if CSAR0[BA] equals 0x0040 and CSMR0[BAM] equals 0x0008, FB_CS0 addresses two discontinuous 64 KB memory blocks: one from 0x40_0000 – 0x40_FFFF and one from 0x48_0000 – 0x48_FFFF.
	Likewise, for FB_CS0 to access 32 MB of address space starting at location 0x00_0000, FB_CS1 must begin at the next byte after FB_CS0 for a 16 MB address space. Therefore, CSAR0[BA] equals 0x0000, CSMR0[BAM] equals 0x01FF, CSAR1[BA] equals 0x0200, and CSMR1[BAM] equals 0x00FF.
	0 Corresponding address bit is used in chip-select decode
	1 Corresponding address bit is a don't care in chip-select decode.
15–9 Reserved	This read-only field is reserved and always has the value zero.
8	Write protect
WP	Controls write accesses to the address range in the corresponding CSAR. Attempting to write to the range of addresses for which CSARn[WP] is set results in a bus error termination of the internal cycle and no external cycle.
	0 Read and write accesses are allowed
	1 Only read accesses are allowed
7–1 Reserved	This read-only field is reserved and always has the value zero.
0 V	Valid



#### wemory Map/Register Definition

#### FB\_CSMRn field descriptions (continued)

Field	Description
	Indicates whether the corresponding CSAR, CSMR, and CSCR contents are valid. Programmed chip-selects do not assert until V bit is set (except for FB_CS0, which acts as the global chip-select). Reset clears each CSMRn[V].
	<b>NOTE:</b> At reset, no chip-select other than FB_CS0 can be used until the CSMR0[V] is set. Afterward, FB_CS[5:0] functions as programmed.
	O Chip select invalid Chip select valid

## 29.3.3 Chip select control register (FB\_CSCRn)

Each CSCRn controls the auto-acknowledge, address setup and hold times, port size, burst capability, and number of wait states. To support the global chip-select (FB\_CSO) the CSCR0 reset values differ from the other CSCRs.


#### NOTE

The reset value of CSCR0 is as follows:

- Bits 31-24 are 0
- Bit 23-3 are device-dependent
- Bits 3-0 are 0

See the Chip Configuration details for your particular device for information on the exact CSCR0 reset value.

Addresses: FB\_CSCR0 is 4000\_C000h base + 8h offset = 4000\_C008h
FB\_CSCR1 is 4000\_C000h base + 14h offset = 4000\_C014h
FB\_CSCR2 is 4000\_C000h base + 20h offset = 4000\_C020h
FB\_CSCR3 is 4000\_C000h base + 2Ch offset = 4000\_C02Ch
FB\_CSCR4 is 4000\_C000h base + 38h offset = 4000\_C038h
FB\_CSCR5 is 4000\_C000h base + 44h offset = 4000\_C044h



## FB\_CSCRn field descriptions

Field	Description
SWS	Secondary wait states  If the SWSEN bit is set, the number of wait states inserted before an internal transfer acknowledge is generated for a burst transfer except for the first termination, which is controlled by the wait state count

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## FB\_CSCRn field descriptions (continued)

Field	Description
	(CSCRn[WS]). If the SWSEN bit is cleared, the WS value is used for all burst transfers and this field is ignored.
25–24 Reserved	This read-only field is reserved and always has the value zero.
23 SWSEN	Secondary wait state enable  O The WS value inserts wait states before an internal transfer acknowledge is generated for all transfers  The SWS value inserts wait states before an internal transfer acknowledge is generated for burst
	transfer secondary terminations
22 EXTS	Extended address latch enable
EXIS	0 FB_TS/FB_ALE asserts for one bus clock cycle
	FB_TS/FB_ALE remains asserted until the first positive clock edge after FB_CSn asserts
21–20 ASET	Address setup
7.021	Controls the assertion of the chip-select with respect to assertion of a valid address and attributes. The address and attributes are considered valid at the same time FB_TS/FB_ALE asserts.
	00 Assert FB_CSn on first rising clock edge after address is asserted. (Default FB_CSn)
	<ul> <li>O1 Assert FB_CSn on second rising clock edge after address is asserted.</li> <li>10 Assert FB_CSn on third rising clock edge after address is asserted.</li> </ul>
	11 Assert FB_CSn on fourth rising clock edge after address is asserted. (Default FB_CSo)
19–18	Read address hold or deselect
RDAH	This field controls the address and attribute hold time after the termination during a read cycle that hits in the chip-select address space.
	<b>NOTE:</b> The hold time applies only at the end of a transfer. Therefore, during a burst transfer or a transfer to a port size smaller than the transfer size, the hold time is only added after the last bus cycle.
	The number of cycles the address and attributes are held after FB_CSn negation depends on the value of CSCRn[AA].
	00 If AA is cleared, 1 cycle. If AA is set, 0 cycles.
	01 If AA is cleared, 2 cycles. If AA is set, 1 cycle.
	<ul><li>10 If AA is cleared, 3 cycles. If AA is set, 2 cycles.</li><li>11 If AA is cleared, 4 cycles. If AA is set, 3 cycles.</li></ul>
17–16	Write address hold or deselect
WRAH	Write address hold or deselect. This field controls the address, data, and attribute hold time after the termination of a write cycle that hits in the chip-select address space.
	<b>NOTE:</b> The hold time applies only at the end of a transfer. Therefore, during a burst transfer or a transfer to a port size smaller than the transfer size, the hold time is only added after the last bus cycle.
	00 Hold address and attributes one cycle after FB_CSn negates on writes. (Default FB_CSn)
	01 Hold address and attributes two cycles after FB_CSn negates on writes.
	<ul> <li>Hold address and attributes three cycles after FB_CSn negates on writes.</li> <li>Hold address and attributes four cycles after FB_CSn negates on writes. (Default FB_CS0)</li> </ul>
15–10 WS	Wait states



#### wemory Map/Register Definition

## FB\_CSCRn field descriptions (continued)

Field	Description
	The number of wait states inserted after FB_CSn asserts and before an internal transfer acknowledge is generated (WS = 0 inserts zero wait states, WS = 0x3F inserts 63 wait states).
	If AA is reserved, FB_TA must be asserted by the external system regardless of the number of generated wait states. In that case, the external transfer acknowledge ends the cycle. An external FB_TA supersedes the generation of an internal FB_TA.
9	Byte-lane shift
BLS	Determines if data on FB_AD appears left-justified or right-justified during the data phase of a FlexBus access.
	0 Not shifted. Data is left-justfied on FB_AD.
	1 Shifted. Data is right justified on FB_AD.
8 AA	Auto-acknowledge enable
AA	Determines the assertion of the internal transfer acknowledge for accesses specified by the chip-select address.
	<b>NOTE:</b> If AA is set for a corresponding FB_CSn and the external system asserts an external FB_TA before the wait-state countdown asserts the internal FB_TA, the cycle is terminated. Burst cycles increment the address bus between each internal termination.
	NOTE: This bit must be set if CSPMCR disables FB_TA.
	0 No internal FB_TA is asserted. Cycle is terminated externally
	1 Internal transfer acknowledge is asserted as specified by WS
7–6	Port size
PS	Specifies the data port width associated with each chip-select. It determines where data is driven during write cycles and where data is sampled during read cycles.
	00 32-bit port size. Valid data sampled and driven on FB_D[31:0]
	8-bit port size. Valid data sampled and driven on FB_D[31:24] if BLS = 0 or FB_D[7:0] if BLS = 1  10 16-bit port size. Valid data sampled and driven on FB_D[31:16] if BLS = 0 or FB_D[15:0] if BLS = 1  11 16-bit port size. Valid data sampled and driven on FB_D[31:16] if BLS = 0 or FB_D[15:0] if BLS = 1
5	Byte-enable mode
BEM	Specifies the byte enable operation. Certain memories have byte enables that must be asserted during reads and writes. BEM can be set in the relevant CSCR to provide the appropriate mode of byte enable support for these SRAMs.
	<ul> <li>The FB_BEn signals are not asserted for reads. The FB_BEn signals are asserted for data write only.</li> <li>The FB_BEn signals are asserted for read and write accesses</li> </ul>
4	Burst-read enable
BSTR	Specifies whether burst reads are used for memory associated with each FB_CSn.
	O Data exceeding the specified port size is broken into individual, port-sized, non-burst reads. For example, a longword read from an 8-bit port is broken into four 8-bit reads.
	1 Enables data burst reads larger than the specified port size, including longword reads from 8- and 16-bit ports, word reads from 8-bit ports, and line reads from 8, 16-, and 32-bit ports.
3 BSTW	Burst-write enable



## FB\_CSCRn field descriptions (continued)

Field	Description			
	Specifies whether burst writes are used for memory associated with each FB_CSn.			
	O Break data larger than the specified port size into individual, port-sized, non-burst writes. For example, a longword write to an 8-bit port takes four byte writes.			
	1 Enables burst write of data larger than the specified port size, including longword writes to 8 and 16-bit ports, word writes to 8-bit ports, and line writes to 8-, 16-, and 32-bit ports.			
2–0 Reserved	This read-only field is reserved and always has the value zero.			

## 29.3.4 Chip select port multiplexing control register (FB\_CSPMCR)


The CSPMCR register controls the multiplexing of the FlexBus signals.

#### **NOTE**

A bus error occurs when:

- writing a reserved value,
- writing to a reserved bit location in this register, or
- not accessing this register as 32-bit.

Address: FB\_CSPMCR is 4000\_C000h base + 60h offset = 4000\_C060h



#### FB\_CSPMCR field descriptions

Field	Description		
31–28 GROUP1	FlexBus signal group 1 multiplex control		
	Controls the multiplexing of the FB_ALE, FB_CS1, and FB_TS signals.		
	0000 FB_ALE		
	0001 FB_CS1		
	0010 FB_TS		
	Else Reserved		
27–24 GROUP2	FlexBus signal group 2 multiplex control		
3	Controls the multiplexing of the FB_CS4, FB_TSIZ0, and FB_BE_31_24 signals.		
	0000 FB_CS4		
	0001 FB_TSIZ0		
	0010 FB_BE_31_24		
	Else Reserved		



## FB\_CSPMCR field descriptions (continued)

Field	Description
23–20 GROUP3	FlexBus signal group 3 multiplex control
ario or o	Controls the multiplexing of the FB_CS5, FB_TSIZ1, and FB_BE_23_16 signals.
	0000 FB_CS5
	0001 FB_TSIZ1
	0010 FB_BE_23_16
	Else Reserved
19–16 GROUP4	FlexBus signal group 4 multiplex control
	Controls the multiplexing of the FB_TBST, FB_CS2, and FB_BE_15_8 signals.
	0000 FB_TBST
	0001 FB_CS2
	0010 FB_BE_15_8
	Else Reserved
15–12 GROUP5	FlexBus signal group 5 multiplex control
G 10 C. C	Controls the multiplexing of the FB_TA, FB_CS3, and FB_BE_7_0 signals.
	<b>NOTE:</b> When GROUP5 is not 0000, you must set the CSCRn[AA] bit. Else, the bus hangs during a transfer.
	0000 FB_TA
	0001 FB_CS3. You must also set CSCRn[AA].
	0010 FB_BE_7_0. You must also set CSCRn[AA].
	Else Reserved
11–0 Reserved	This read-only field is reserved and always has the value zero.

## 29.4 Functional Description

This section provides the functional description of the module.

## 29.4.1 Chip-Select Operation

Each chip-select has a dedicated set of registers for configuration and control:

• Chip-select address registers (CSARn) control the base address space of the chip-select.



- Chip-select mask registers (CSMRn) provide 16-bit address masking and access control.
- Chip-select control registers (CSCRn) provide port size and burst capability indication, wait-state generation, address setup and hold times, and automatic acknowledge generation features.

## 29.4.1.1 General Chip-Select Operation

When a bus cycle is routed to the FlexBus, the device first compares its address with the base address and mask configurations programmed for chip-selects 0 to 5 (configured in CSCRn). The results depend on if the address matches or not as shown in the following table.

Address Matches CSARn?	Result
Yes,	The appropriate chip-select is asserted, generating a FlexBus bus cycle as defined in the chip-select control register.
one CSAR	If CSMR[WP] is set and a write access is performed, the internal bus cycle terminates with a bus error, no chip select is asserted, and no external bus cycle is performed.
No	The access is terminated with a bus error response, no chip select is asserted and no FlexBus cycle is performed.
Yes, multiple CSARs	The access is terminated with a bus error response, no chip select is asserted and no FlexBus cycle is performed.

Table 29-26. Results of Address Comparison

## 29.4.1.2 8-, 16-, and 32-Bit Port Sizing

Static bus sizing is programmable through the port size bits, CSCR[PS]. The processor always drives a 32-bit address on the FB\_AD bus regardless of the external device's address size. The external device must connect its address/data lines as follows:

- Address lines
  - FB\_AD from FB\_AD0 upward
- Data lines
  - If CSCR[BLS] = 0, FB\_AD from FB\_AD31 downward
  - If CSCR[BLS] = 1, FB\_AD from FB\_AD0 upward



No bit ordering is required when connecting address and data lines to the FB\_AD bus. For example, a full 16-bit address/16-bit data device connects its addr[15:0] to FB\_AD[16:1] and data[15:0] to FB\_AD[31:16]. See Data Byte Alignment and Physical Connections for a graphical connection.

## 29.4.2 Data Transfer Operation

Data transfers between the chip and other devices involve these signals:

- Address/data bus (FB\_AD[31:0])
- Control signals (FB\_TS/FB\_ALE, FB\_TA, FB\_CSn, FB\_OE, FB\_BEn)
- Attribute signals (FB\_R/\overline{W}, \overline{FB\_TBST}, FB\_TSIZ[1:0])

The address, write data, FB\_TS/FB\_ALE, FB\_CSn, and all attribute signals change on the rising edge of the FlexBus clock (FB\_CLK). Read data is latched into the device on the rising edge of the clock.

The FlexBus supports 8-bit, 16-bit, 32-bit, and 16-byte (line) operand transfers and allows accesses to 8-, 16-, and 32-bit data ports. Transfer parameters (address setup and hold, port size, the number of wait states for the external device being accessed, automatic internal transfer termination enable or disable, and burst enable or disable) are programmed in the chip-select control registers (CSCRs).

## 29.4.3 Data Byte Alignment and Physical Connections

The device aligns data transfers in FlexBus byte lanes with the number of lanes depending on the data port width.

The following figure shows the byte lanes that external memory connects to and the sequential transfers of a 32-bit transfer for the supported port sizes when byte lane shift is disabled. For example, an 8-bit memory connects to the single lane FB\_AD[31:24] (FB\_BE\_31\_24). A 32-bit transfer through this 8-bit port takes four transfers, starting with the LSB to the MSB. A 32-bit transfer through a 32-bit port requires one transfer on each four-byte lane of the FlexBus.






Figure 29-23. Connections for External Memory Port Sizes (CSCRn[BLS] = 0)

The following figure shows the byte lanes that external memory connects to and the sequential transfers of a 32-bit transfer for the supported port sizes when byte lane shift is enabled.




Figure 29-24. Connections for External Memory Port Sizes (CSCRn[BLS] = 1)

## 29.4.4 Address/Data Bus Multiplexing

The interface supports a single 32-bit wide multiplexed address and data bus (FB\_AD[31:0]). The full 32-bit address is always driven on the first clock of a bus cycle. During the data phase, the FB\_AD[31:0] lines used for data are determined by the programmed port size for the corresponding chip select. The device continues to drive the address on any FB\_AD[31:0] lines not used for data.

The tables below lists the supported combinations of address and data bus widths for each CSCRn[BLS] setting.



Table 29-27. FlexBus Multiplexed Operating Modes for CSCRn[BLS]=0

Port Size and Phase		FB_AD				
	FUIT SIZE AND PHASE		[23:16]	[15:8]	[7:0]	
Ħ	Address phase	Address				
32-bit	Data phase	Data				
Ħ	Address phase	Address				
16-bit	Data phase	Data		Add	Address	
±	Address phase	Address				
8-bit	Data phase	Data Address				

Table 29-28. FlexBus Multiplexed Operating Modes for CSCRn[BLS]=1

Port Size and Phase		FB_AD			
	Fort Size and Filase		[23:16]	[15:8]	[7:0]
Ħ	Address phase	Address			
Data phase		Da	Data		
Ħ	Address phase	·			
16-bit	Data phase			ata	
Ħ	Address phase	Address			
8-bit	Data phase	Address			Data

## 29.4.5 Bus Cycle Execution

As shown in Figure 29-27 and Figure 29-29, basic bus operations occur in four clocks:

- 1. S0: At the first clock edge, the address, attributes, and FB\_TS/FB\_ALE are driven.
- 2. S1: FB\_CSn is asserted at the second rising clock edge to indicate the device selected; by that time, the address and attributes are valid and stable. FB\_TS/FB\_ALE is negated at this edge.

For a write transfer, data is driven on the bus at this clock edge and continues to be driven until one clock cycle after  $\overline{FB\_CSn}$  negates. For a read transfer, data is also driven into the device during this cycle.

External slave asserts FB\_TA at this clock edge.

3. S2: Read data and FB\_TA are sampled on the third clock edge. FB\_TA can be negated after this edge and read data can then be tri-stated.



4. S3: FB\_CSn is negated at the fourth rising clock edge. This last clock of the bus cycle uses what would be an idle clock between cycles to provide hold time for address, attributes, and write data.

## 29.4.5.1 Data Transfer Cycle States

An on-chip state machine controls the data-transfer operation in the device. The following figure shows the state-transition diagram for basic read and write cycles.




Figure 29-25. Data-Transfer-State-Transition Diagram

The following table describes the states as they appear in subsequent timing diagrams.

State	Cycle	Description	
S0	All	The read or write cycle is initiated. On the rising clock edge, the device places a valid address on FB_ADn, asserts FB_TS/FB_ALE, and drives FB_R/W high for a read and low for a write.	
S1 All		FB_TS/FB_ALE is negated on the rising edge of FB_CLK, and FB_CSn is asserted. Data is driven on FB_AD[31:X] for writes, and FB_AD[31:X] is tristated for reads. Address continues to be driven on the FB_AD pins that are unused for data.	
		If FB_TA is recognized asserted, then the cycle moves on to S2. If FB_TA is not asserted internally or externally, then the S1 state continues to repeat.	
	Read	Data is driven by the external device before the next rising edge of FB_CLK (the rising edge that begins S2) with FB_TA asserted.	
S2 All		For internal termination, FB_CSn is negated and the internal system bus transfer is completed. For external termination, the external device should negate FB_TA, and the FB_CSn chip select negates after the rising edge of FB_CLK at the end of S2.	
	Read	The processor latches data on the rising clock edge entering S2. The external device can stop driving data after this edge. However, data can be driven until the end of S3 or any additional address hold cycles.	
S3	All	Address, data, and FB_R/W go invalid off the rising edge of FB_CLK at the	

Table 29-29. Bus Cycle States

beginning of S3, terminating the read or write cycle.

## 29.4.6 FlexBus Timing Examples

#### **Note**

The timing diagrams throughout this section use signal names that may not be included on your particular device. Ignore these extraneous signals.

#### **Note**

Throughout this section:

- FB\_D[X] indicates a 32-, 16-, or 8-bit wide data bus
- FB\_A[Y] indicates an address bus that can be 32, 24, or 16 bits wide.

## 29.4.6.1 Basic Read Bus Cycle

During a read cycle, the MCU receives data from memory or a peripheral device. The following figure shows a read cycle flowchart.




Figure 29-26. Read Cycle Flowchart

The read cycle timing diagram is shown in the following figure.



#### **Note**

FB\_TA does not have to be driven by the external device for internally-terminated bus cycles.

#### **Note**

The processor drives the data lines during the first clock cycle of the transfer with the full 32-bit address. This may be ignored by standard connected devices using non-multiplexed address and data buses. However, some applications may find this feature beneficial.

The address and data busses are muxed between the FlexBus and another module. At the end of the read bus cycles the address signals are indeterminate.




Figure 29-27. Basic Read-Bus Cycle

## 29.4.6.2 Basic Write Bus Cycle

During a write cycle, the device sends data to memory or to a peripheral device. The following figure shows the write cycle flowchart.






Figure 29-28. Write-Cycle Flowchart

The following figure shows the write cycle timing diagram.

#### **Note**

The address and data busses are muxed between the FlexBus and another module. At the end of the write bus cycles, the address signals are indeterminate.






Figure 29-29. Basic Write-Bus Cycle

## 29.4.6.3 Bus Cycle Sizing

This section shows timing diagrams for various port size scenarios.

## 29.4.6.3.1 Bus Cycle Sizing—Byte Transfer, 8-bit Device, No Wait States

The following figure illustrates the basic byte read transfer to an 8-bit device with no wait states:

- The address is driven on the full FB\_AD[31:8] bus in the first clock.
- The device tristates FB\_AD[31:24] on the second clock and continues to drive address on FB\_AD[23:0] throughout the bus cycle.
- The external device returns the read data on FB\_AD[31:24] and may tristate the data line or continue driving the data one clock after FB\_TA is sampled asserted.






Figure 29-30. Single Byte-Read Transfer

The following figure shows the similar configuration for a write transfer. The data is driven from the second clock on FB\_AD[31:24].






Figure 29-31. Single Byte-Write Transfer

## 29.4.6.3.2 Bus Cycle Sizing—Word Transfer, 16-bit Device, No Wait States

The following figure illustrates the basic word read transfer to a 16-bit device with no wait states.

- The address is driven on the full FB\_AD[31:8] bus in the first clock.
- The device tristates FB\_AD[31:16] on the second clock and continues to drive address on FB\_AD[15:0] throughout the bus cycle.
- The external device returns the read data on FB\_AD[31:16] and may tristate the data line or continue driving the data one clock after FB\_TA is sampled asserted.






Figure 29-32. Single Word-Read Transfer

The following figure shows the similar configuration for a write transfer. The data is driven from the second clock on FB\_AD[31:16].






Figure 29-33. Single Word-Write Transfer

## 29.4.6.3.3 Bus Cycle Sizing—Longword Transfer, 32-bit Device, No Wait States

The following figure depicts a longword read from a 32-bit device.






Figure 29-34. Longword-Read Transfer

The following figure illustrates the longword write to a 32-bit device.






Figure 29-35. Longword-Write Transfer

## 29.4.6.4 Timing Variations

The FlexBus module has several features that can change the timing characteristics of a basic read- or write-bus cycle to provide additional address setup, address hold, and time for a device to provide or latch data.

#### 29.4.6.4.1 Wait States

Wait states can be inserted before each beat of a transfer by programming the CSCR*n* registers. Wait states can give the peripheral or memory more time to return read data or sample write data.

The following figures show the basic read and write bus cycles (also shown in Figure 29-27 and Figure 29-32) with the default of no wait states respectively.






Figure 29-36. Basic Read-Bus Cycle (No Wait States)






Figure 29-37. Basic Write-Bus Cycle (No Wait States)

If wait states are used, the S1 state repeats continuously until the the chip-select auto-acknowledge unit asserts internal transfer acknowledge or the external FB\_TA is recognized as asserted. The following figures show a read and write cycle with one wait state respectively.






Figure 29-38. Read-Bus Cycle (One Wait State)






Figure 29-39. Write-Bus Cycle (One Wait State)

## 29.4.6.4.2 Address Setup and Hold

The timing of the assertion and negation of the chip selects, byte selects, and output enable can be programmed on a chip-select basis. Each chip-select can be programmed to assert one to four clocks after transfer start/address-latch enable (FB\_TS/FB\_ALE) is asserted. The following figures show read- and write-bus cycles with two clocks of address setup respectively.






Figure 29-40. Read-Bus Cycle with Two-Clock Address Setup (No Wait States)






Figure 29-41. Write-Bus Cycle with Two Clock Address Setup (No Wait States)

In addition to address setup, a programmable address hold option for each chip select exists. Address and attributes can be held one to four clocks after chip-select, byte-selects, and output-enable negate. The following figures show read and write bus cycles with two clocks of address hold respectively.






Figure 29-42. Read Cycle with Two-Clock Address Hold (No Wait States)






Figure 29-43. Write Cycle with Two-Clock Address Hold (No Wait States)

The following figure shows a bus cycle using address setup, wait states, and address hold.








Figure 29-44. Write Cycle with Two-Clock Address Setup and Two-Clock Hold (One Wait State)

# 29.4.7 Burst Cycles

The device can be programmed to initiate burst cycles if its transfer size exceeds the port size of the selected destination. The initiation of a burst cycle is encoded on the size pins. For burst transfers to smaller port sizes, FB TSIZ[1:0] indicates the size of the entire transfer. For example, with bursting enabled, a 16-bit transfer to an 8-bit port takes two beats (two byte-sized transfers), for which FB\_TSIZ[1:0] equals 10b throughout. A 32-bit transfer to an 8-bit port would take a 4-byte burst cycle, for which FB TSIZ[1:0] equals 00b throughout.

With bursting disabled, any transfer larger than the port size breaks into multiple individual transfers. With bursting enabled, an access larger than port size results in a burst cycle of multiple beats. The following table shows the result of such transfer translations.



Table 29-30. Transfer Size and Port Size Translation

Port Size PS[1:0]	Transfer Size FB_TSIZ[1:0]	Burst-Inhibited: Number of Transfers Burst Enabled: Number of Beats
01 (8-bit)	10 (16-bits)	2
	00 (32-bits)	4
	11 (16 bytes)	16
1x (16-bit)	00 (32 bits)	2
	11 (16 bytes)	8
00 (32-bit)	11 (line)	4

The FlexBus can support 2-1-1-1 burst cycles to maximize system performance. Delaying termination of the cycle can add wait states. If internal termination is used, different wait state counters can be used for the first access and the following beats.

The CSCR*n* registers enable bursting for reads, writes, or both. Memory spaces can be declared burst-inhibited for reads and writes by clearing the appropriate CSCRn[BSTR,BSTW] bits.

The following figure shows a 32-bit read to an 8-bit device programmed for burst enable. The transfer results in a 4-beat burst and the data is driven on FB\_AD[31:24]. The transfer size is driven at 32-bit (00) throughout the bus cycle.

#### Note

In non-multiplexed address/data mode, the address on FB\_A increments only during internally-terminated burst cycles. The first address is driven throughout the entire burst for externally-terminated cycles.

In multiplexed address/data mode, the address is driven on FB\_AD only during the first cycle for all terminated cycles.






Figure 29-45. 32-bit-Read Burst from 8-Bit Port 2-1-1-1 (No Wait States)

The following figure shows a 32-bit write to an 8-bit device with burst enabled. The transfer results in a 4-beat burst and the data is driven on FB\_AD[31:24]. The transfer size is driven at 32-bit (00) throughout the bus cycle.

### **Note**

The first beat of any write burst cycle has at least one wait state. If the bus cycle is programmed for zero wait states (CSCRn[WS] = 0), one wait state is added. Otherwise, the programmed number of wait states are used.






Figure 29-46. 32-bit-Write Burst to 8-Bit Port 3-1-1-1 (No Wait States)

The following figure shows a 32-bit read from an 8-bit device with burst inhibited. The transfer results in four individual transfers. The transfer size is driven at 32-bit (00) during the first transfer and at byte (01) during the next three transfers.

## **Note**

There is an extra clock of address setup (AS) for each burst-inhibited transfer between states S0 and S1.






Figure 29-47. 32-bit-Read Burst-Inhibited from 8-Bit Port (No Wait States)

The following figure shows a 32-bit write to an 8-bit device with burst inhibited. The transfer results in four individual transfers. The transfer size is driven at 32-bit (00) during the first transfer and at byte (01) during the next three transfers.






Figure 29-48. 32-bit-Write Burst-Inhibited to 8-Bit Port (No Wait States)

The following figure illustrates another read burst transfer, but in this case a wait state is added between individual beats.

## **Note**

CSCR*n*[WS] determines the number of wait states in the first beat. However, for subsequent beats, the CSCR*n*[WS] (or CSCR*n*[SWS] if CSCR*n*[SWSEN] is set) determines the number of wait states.






Figure 29-49. 32-bit-Read Burst from 8-Bit Port 3-2-2-2 (One Wait State)

The following figure illustrates a write burst transfer with one wait state.






Figure 29-50. 32-bit-Write Burst to 8-Bit Port 3-2-2-2 (One Wait State)

If address setup and hold are used, only the first and last beat of the burst cycle are affected. The following figure shows a read cycle with one clock of address setup and address hold.

#### **Note**

In non-multiplexed address/data mode, the address on FB\_A increments only during internally-terminated burst cycles (CSCRn[AA] = 1). The attached device must be able to account for this, or a wait state must be added. The first address is driven throughout the entire burst for externally-terminated cycles.

In multiplexed address/data mode, the address is driven on FB\_AD only during the first cycle for internally- and externally-terminated cycles.






Figure 29-51. 32-bit-Read Burst from 8-Bit Port 3-1-1-1 (Address Setup and Hold)

The following figure shows a write cycle with one clock of address setup and address hold.




Figure 29-52. 32-bit-Write Burst to 8-Bit Port 3-1-1-1 (Address Setup and Hold)



## 29.4.8 Extended Transfer Start/Address Latch Enable

The  $\overline{FB}$ \_TS/FB\_ALE signal indicates that a bus transaction has begun and the address and attributes are valid. By default, the  $\overline{FB}$ \_TS/FB\_ALE signal asserts for a single bus clock cycle. When CSCRn[EXTS] is set, the  $\overline{FB}$ \_TS/FB\_ALE signal asserts and remain asserted until the first positive clock edge after FB\_CSn asserts. See the following figure.

#### NOTE

When EXTS is set, CSCRn[WS] must be programmed to have at least one primary wait state.




Figure 29-53. Read-Bus Cycle with CSCRn[EXTS] = 1 (One Wait State)

## 29.4.9 Bus Errors

If the auto-acknowledge feature is not enabled for the address that generates the error, the bus cycle can be terminated by asserting FB\_TA. If the processor must manage a bus error differently, asserting an interrupt to the core along with FB\_TA when the bus error occurs can invoke an interrupt handler.



#### mualization/Application Information

The types of accesses that cause the access to terminate with a bus error are:

- Writes to write-protected region
- Address with no hit to any chip select
- Address with hits to multiple chip selects
- Writes to reserved addresses in the memory map
- Writes to reserved bits in the CSPMCR register
- FlexBus accesses when the FlexBus is secure

Also, the device can hang if the FlexBus is configured for external termination and the CSPMCR is not configured for FB\_TA.

# 29.5 Initialization/Application Information

# 29.5.1 Initializing a Chip Select

To initially use a chip select:

- 1. Configure the CSAR register.
- 2. Configure the CSCR register.
- 3. Configure the CSMR register, setting the valid bit.

The CSPMCR register is not required to be part of this procedure. However, it should only be configured when the FlexBus is idle. The corresponding chip select can be valid.

# 29.5.2 Reconfiguring a Chip Select

To reconfigure a previously-used chip select, the chip select must be specified as invalid as shown below:

- 1. Clear the CSMR register's valid bit.
- 2. Change settings in the CSAR register as necessary.
- 3. Change settings in the CSCR register as necessary.
- 4. Change settings in the CSMR register as necessary, and set the valid bit.

The CSPMCR register is not required to be part of this procedure. However, it should only be altered when the FlexBus is idle. The corresponding chip select can be valid.



# Chapter 30 EzPort

## 30.1 Overview

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

EzPort is a serial flash programming interface that allows In-System Programming (ISP) of flash memory contents on a 32 bit general purpose micro-controller. Memory contents can be read, erased and programmed from off-chip in a compatible format to many standalone flash memory chips, without necessitating the removal of the micro-controller from the system.

# 30.1.1 Introduction

The block diagram of the EzPort is as following.






Figure 30-1. EzPort Block Diagram

## 30.1.2 Features

The EzPort includes the following features:

- Serial interface that is compatible with a subset of the SPI format.
- Able to read, erase and program flash memory.
- Able to reset the micro-controller, allowing it to boot from the flash memory after the memory has been configured.

# 30.1.3 Modes of Operation

The EzPort can operate in one of two different modes, enabled or disabled.

- Enabled When enabled, the EzPort steals access to the flash memory, preventing access from other cores or peripherals. The rest of the microcontroller is disabled to avoid conflicts. The flash is configured for NVM Special Mode.
- Disabled When the EzPort is disabled, the rest of the micro-controller can access flash memory as normal.



The EzPort provides a simple interface to connect an external device to the flash memory on board a 32 bit micro-controller. The interface itself is compatible with the SPI interface (with the EzPort operating as a slave) running in either of the two following modes with data transmitted most significant bit first:

- CPOL = 0, CPHA = 0
- CPOL = 1, CPHA = 1

Commands are issued by the external device to erase, program or read the contents of the flash memory. The serial data out from the EzPort is tri-stated unless data is being driven, allowing the signal to be shared among several different EzPort (or compatible) devices in parallel, provided they have different chip selects.

# 30.2 External Signal Description

The following table contains a list of EzPort external signals, and the following sections explain them in detail.

Name	Description	I/O
EZP_CK	EzPort Clock	Input
EZP_CS	EzPort Chip Select	Input
EZP_D	EzPort Serial Data In	Input
EZP_Q	EzPort Serial Data Out	Output

Table 30-1. EzPort External Signal Descriptions

# 30.2.1 EzPort Clock (EZP\_CK)

Serial clock for data transfers. The serial data in (EZP\_D) and chip select (EZP\_CS) are registered on the rising edge of EZP\_CK while serial data out (EZP\_Q) is driven on the falling edge of EZP\_CK.

The maximum frequency of the EzPort clock is half the system clock frequency for all commands except when executing the Read Data commands. When executing these commands, the EzPort clock has a maximum frequency of one-eighth the system clock frequency.



**Command Definition** 

# 30.2.2 EzPort Chip Select (EZP\_CS)

Chip select for signalling the start and end of serial transfers. If  $\overline{EZP\_CS}$  is asserted during and when the micro-controller's reset out signal is negated, then  $\overline{EZP\_CS}$  is enabled out of reset; otherwise it is disabled. After  $\overline{EZP\_CS}$  is enabled, asserting  $\overline{EZP\_CS}$  commences a serial data transfer, which continues until  $\overline{EZP\_CS}$  is negated again. The negation of  $\overline{EZP\_CS}$  indicates the current command is finished and resets the  $\overline{EZP\_CS}$  that it is ready to receive the next command.

# 30.2.3 EzPort Serial Data In (EZP\_D)

Serial data in for data transfers. EZP\_D is registered on the rising edge of EZP\_CK. All commands, addresses, and data are shifted in most significant bit first. When the EzPort is driving output data on EZP\_Q, the data shifted in EZP\_D is ignored.

# 30.2.4 EzPort Serial Data Out (EZP\_Q)

Serial data out for data transfers. EZP\_Q is driven on the falling edge of EZP\_CK. It is tri-stated unless EZP\_CS is asserted and the EzPort is driving data out. All data is shifted out most significant bit first.

# 30.3 Command Definition

The EzPort receives commands from an external device and translates those commands into flash memory accesses. The following table lists the supported commands.

**Address** Accepted when Command Description Code **Data Bytes Bytes** secure? **WREN** Write Enable 0 0 Yes 0x06 **WRDI** Write Disable 0x04 0 0 Yes **RDSR** Read Status Register 0x05 0 1 Yes 31 **READ** Flash Read Data 0x03 1+ No 1+2 FAST\_READ Flash Read Data at High Speed 0x0B 31 No SP 33 8 - SECTION4 Flash Section Program 0x02 No 33 SE Flash Sector Erase 0xD8 0 No ΒE Flash Bulk Erase 0xC7 0 Yes<sup>5</sup>

**Table 30-2. EzPort Commands** 

Table continues on the next page...



Command	Description	Code	Address Bytes	Data Bytes	Accepted when secure?
RESET	Reset Chip	0xB9	0	0	Yes
WRFCCOB	Write FCCOB Registers	0xBA	0	12	Yes <sup>6</sup>
FAST_RDFCCOB	Read FCCOB registers at high speed	0xBB	0	1 - 12 <sup>2</sup>	No

- 1. Address must be 32-bit aligned (two LSBs must be zero).
- 2. One byte of dummy data must be shifted in before valid data is shifted out.
- 3. Address must be 64-bit aligned (three LSBs must be zero).
- 4. A section is defined as half the size of the flash sector size. Total number of data bytes programmed must be a multiple of
- 5. Bulk Erase is accepted when security is set only if the BEDIS status bit is not set.
- 6. Note that the Flash will be in NVM Special mode, restricting which types of commands can be executed through WRITE\_FCCOB when security is enabled.

## 30.3.1 Command Descriptions

This section describes the module commands.

## **30.3.1.1** Write Enable

The Write Enable command (WREN) sets the write enable register bit in the EzPort status register. The write enable bit must be set for a write command (SP, SE, BE, WRFCCOB) to be accepted. The write enable register bit clears on reset, on a Write Disable command, and at the completion of write command. This command should not be used if a write is already in progress.

## 30.3.1.2 Write Disable

The Write Disable command (WRDI) clears the write enable register bit in the status register. This command should not be used if a write is already in progress.

## 30.3.1.3 Read Status Register

The Read Status Register command (RDSR) returns the contents of the EzPort status register.



#### **Command Definition**

## Table 30-3. EzPort Status Register

	7	6	5	4	3	2	1	0
R	FS	WEF				BEDIS	WEN	WIP
W								
Reset:	0/11	0	0	0	0	0/1 <sup>2</sup>	0	1 <sup>3</sup>

- 1. Reset value reflects the status of flash security out of reset.
- 2. Reset value reflects if bulk erase is enabled or disabled out of reset
- 3. Initial value of WIP is 1, but the value clears to 0 after EzPort initialization is complete

## Table 30-4. EzPort Status Register Field Descriptions

Field	Description
0	Write in progress.
WIP	Status flag that sets after a write command (SP, SE, BE, WRFCCOB) is accepted and clears once the flash memory has completed all operations associated with that command as indicated by the Command Complete Interrupt Flag (CCIF) inside the Flash. Also asserted on reset and clears when EzPort initialization is complete. Only the Read Status Register (RDSR) command is accepted while a write is in progress.
	0 = Write is not in progress. Accept any command.
	1 = Write is in progress. Only accept RDSR command.
1	Write enable
WEN	Control bit that must be set before a write command (SP, SE, BE, WRFCCOB) is accepted. Is set by the Write Enable (WREN) command and cleared by reset or a Write Disable (WRDI) command. It also clears when the flash memory has completed all operations associated with the command.
	0 = Disables the following write command.
	1 = Enables the following write command.
2	Bulk erase disable
BEDIS	Status flag which indicates if bulk erase (BE) is disabled when Flash is secure.
	0 = Bulk Erase is enabled.
	1 = Bulk Erase is disabled if the FS bit is also set. Attempts to issue a BE command will result in the WEF flag being set.
6	Write error flag
WEF	Status flag that indicates if there has been an error while executing a write command (SP, SE, BE, WRFCCOB). The WEF flag will set if either the Flash Access Error Flag (ACCERR) or the Flash Protection Violation Flag (FPVIOL) or the Memory Controller Command Completion Status Flag (MGSTAT0) inside the flash memory is set at the completion of the write command. See the flash memory chapter for further description of these flags and their sources. The WEF flag clears after a Read Status Register (RDSR) command.
	0 = No error on previous write command.
	1 = Error on previous write command.
7	Flash security
FS	Status flag that indicates if the flash is secure. See Table 30-2 for the list of commands which will be accepted when flash is secure. Flash security can be disabled by performing a Bulk Erase (BE) command.
	0 = Flash is not secure
	1 = Flash is secure.
	0 = Flash is not secure



## 30.3.1.4 Read Data

The Read Data (READ) command returns data from the flash memory. The initial address must be 32-bit aligned (the two LSBs must be zero).

Data continues being returned for as long as the EzPort chip select (EZP\_CS) is asserted, with the address automatically incrementing. In this way, the entire contents of flash can be returned by one command. Attempts to read from an address which does not fall within the valid address range (see Flash Memory Map for EzPort Access) for the flash memory regions returns junk data.

For this command to return the correct data, the EzPort clock (EZP\_CK) must run at the internal system clock divided by eight or slower. This command is not accepted if the WEF, WIP, or FS bit in the EzPort status register is set.

## 30.3.1.5 Read Data at High Speed

The Read Data at High Speed command (FAST\_READ) is identical to the READ command, except for the inclusion of a dummy byte following the address bytes and before the first data byte is returned.

This command can be run with an EzPort clock (EZP\_CK) frequency of half the internal system clock frequency of the micro-controller or slower. This command is not accepted if the WEF, WIP, or FS bit in the EzPort status register is set.

## 30.3.1.6 Section Program

The Section Program (SP) command programs up to one section of flash memory which has previously been erased. A section is defined as the smaller of the flash sector size or half the size of the Programming Acceleration RAM. The starting address of the memory to program is sent after the command word and must be a 64-bit aligned address (the three LSBs must be zero).

As data is shifted in, the EzPort buffers the data in Programming Acceleration RAM before executing a 'Program Section' command within the flash (see Flash Block Guide for more detail). For this reason, the number of bytes to program must be a multiple of 8 and up to one flash section can be programmed at a time.

Attempts to program more than one section, across a sector boundary or from an initial address which does not fall within the valid address range (see Flash Memory Map for EzPort Access) for the flash causes the WEF flag to set.



#### **Command Definition**

This command is not accepted if the WEF, WIP, or FS bit is set or if the WEN bit is not set in the EzPort status register.

## 30.3.1.7 Sector Erase

The Sector Erase (SE) command erases the contents of one sector of flash memory. The three byte address sent after the command byte can be any address within the sector to erase, but must be a 64-bit aligned address (the three LSBs must be zero). Attempts to erase from an initial address which does not fall within the valid address range (see Flash Memory Map for EzPort Access) for the flash results in the WEF flag being set.

This command is not accepted if the WEF, WIP or FS bit is set or if the WEN bit is not set in the EzPort status register.

## **30.3.1.8 Bulk Erase**

The Bulk Erase (BE) command erases the entire contents of flash memory, ignoring any protected sectors or flash security. Flash security is disabled upon successful completion of the BE command.

Attempts to issue a BE command while the BEDIS and FS bits are set results in the WEF flag being set in the EzPort status register. Also, this command is not accepted if the WEF or WIP bit is set or if the WEN bit is not set in the EzPort status register.

# 30.3.1.9 EzPort Reset Chip

The Reset Chip (RESET) command forces the chip into the reset state. If the EzPort chip select (EZP\_CS) pin is asserted at the end of the reset period then EzPort is enabled; otherwise, it is disabled. This command allows the chip to boot up from flash memory after it has been programmed by an external source.

This command is not accepted if the WIP bit is set in the EzPort status register.

# 30.3.1.10 Write FCCOB Registers

The Write FCCOB Registers (WRFCCOB) command allows the user to write to the flash common command object registers and execute any command allowed by the flash.



#### NOTE

The flash is configured in NVM special mode, restricting which commands can be executed by the flash when security is enabled.

After receiving 12 bytes of data, EzPort writes the data to the FCCOB 0-B registers in the flash and then automatically launches the command within the flash. If greater or less than 12 bytes of data is received, this command has unexpected results and may result in the WEF flag being set.

This command is not accepted if the WEF or WIP bit is set or if the WEN bit is not set in the EzPort status register.

## 30.3.1.11 Read FCCOB Registers at High Speed

The Read FCCOB Registers at High Speed (FAST\_RDFCCOB) command allows the user to read the contents of the flash common command object registers. After receiving the command, EzPort waits for one dummy byte of data before returning FCCOB register data starting at FCCOB 0 and ending with FCCOB B.

This command can be run with an EzPort clock (EZP\_CK) frequency half the internal system clock frequency of the micro-controller or slower. Attempts to read greater than 12 bytes of data returns junk data. This command is not be accepted if the WEF, WIP, or FS bit in the EzPort status register is set.

# 30.4 Flash Memory Map for EzPort Access


The following table shows the flash memory map for access through EzPort.

#### NOTE

The flash block address map for access through EzPort may not conform to the system memory map. Changes are made to allow the EzPort address width to remain at 24-bits.

Table 30-5. Flash Memory Map for EzPort Access

Valid Start Address	Size	Flash block	Valid Commands
0x0000_0000	See device's Chip Configuration details	Flash	READ, FAST_READ, SP, SE, BE





# **Chapter 31 Cyclic redundancy check (CRC)**

## 31.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The cyclic redundancy check (CRC) module generates 16/32-bit CRC code for error detection.

The CRC module provides a programmable polynomial, WAS, and other parameters required to implement a 16-bit or 32-bit CRC standard.

The 16/32-bit code is calculated for 32 bits of data at a time.

## **31.1.1 Features**

Features of the CRC module include:

- Hardware CRC generator circuit using a 16-bit or 32-bit (programmable) shift register.
- Programmable initial seed value and polynomial.
- Option to transpose input data or output data (the CRC result) bitwise or bytewise. This option is required for certain CRC standards. A bytewise transpose operation is not possible when accessing the CRC data register via 8-bit accesses. In this case, the user's software must perform the bytewise transpose function.
- Option for inversion of final CRC result.
- 32-bit CPU register programming interface.



wemory map and register descriptions

# 31.1.2 Block diagram

This is a block diagram of the CRC.




Figure 31-1. Programmable cyclic redundancy check (CRC) block diagram

# 31.1.3 Modes of operation

Various MCU modes affect the CRC module's functionality.

## 31.1.3.1 Run mode

This is the basic mode of operation.

## 31.1.3.2 Low power modes (wait or stop)

Any CRC calculation in progress stops when the MCU enters a low power mode that disables the module clock. It resumes after the clock is enabled or via the system reset for exiting the low power mode. Clock gating for this module is MCU dependent.

# 31.2 Memory map and register descriptions



## **CRC** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_2000	CRC Data Register (CRC_CRC)	32	R/W	FFFF_ FFFFh	31.2.1/ 715
4003_2004	CRC Polynomial Register (CRC_GPOLY)	32	R/W	0000_1021h	31.2.2/ 716
4003_2008	CRC Control Register (CRC_CTRL)	32	R/W	0000_0000h	31.2.3/ 717

# 31.2.1 CRC Data Register (CRC\_CRC)

The CRC data register contains the value of the seed, data, and checksum. When the CTRL[WAS] bit is set, any write to the data register is regarded as the seed value. When the CTRL[WAS] bit is cleared, any write to the data register is regarded as data for general CRC computation.

In 16-bit CRC mode, the HU and HL fields are not used for programming the seed value, and reads of these fields return an indeterminate value. In 32-bit CRC mode, all fields are used for programming the seed value.

When programming data values, the values can be written 8 bits, 16 bits, or 32 bits at a time, provided all bytes are contiguous; with MSB of data value written first.

After all data values are written, the CRC result can be read from this data register. In 16-bit CRC mode, the CRC result is available in the LU and LL fields. In 32-bit CRC mode, all fields contain the result. Reads of this register at any time return the intermediate CRC value, provided the CRC module is configured.

Address: CRC\_CRC is 4003\_2000h base + 0h offset = 4003\_2000h



## CRC\_CRC field descriptions

Field	Description
31–24 HU	CRC High Upper Byte  In 16-bit CRC mode (the CTRL[TCRC] bit is 0), this field is not used for programming a seed value. In 32-bit CRC mode (the CTRL[TCRC] bit is 1), values written to this field are part of the seed value when the
	CTRL[WAS] bit is 1. When the CTRL[WAS] bit is 0, data written to this field is used for CRC checksum generation in both 16-bit and 32-bit CRC modes.

Table continues on the next page...



#### wemory map and register descriptions


## **CRC\_CRC** field descriptions (continued)

Field	Description
23–16 HL	CRC High Lower Byte
	In 16-bit CRC mode (the CTRL[TCRC] bit is 0), this field is not used for programming a seed value. In 32-bit CRC mode (the CTRL[TCRC] bit is 1), values written to this field are part of the seed value when the CTRL[WAS] bit is 1. When the CTRL[WAS] bit is 0, data written to this field is used for CRC checksum generation in both 16-bit and 32-bit CRC modes.
15–8 LU	CRC Low Upper Byte
	When the CTRL[WAS] bit is 1, values written to this field are part of the seed value. When the CTRL[WAS] bit is 0, data written to this field is used for CRC checksum generation.
7–0 LL	CRC Low Lower Byte
	When the CTRL[WAS] bit is 1, values written to this field are part of the seed value. When the CTRL[WAS] bit is 0, data written to this field is used for CRC checksum generation.

# 31.2.2 CRC Polynomial Register (CRC\_GPOLY)

This register contains the value of the polynomial for the CRC calculation. The HIGH field contains the upper 16 bits of the CRC polynomial, which are used only in 32-bit CRC mode. Writes to the HIGH field are ignored in 16-bit CRC mode. The LOW field contains the lower 16 bits of the CRC polynomial, which are used in both 16- and 32-bit CRC modes.

Address: CRC\_GPOLY is 4003\_2000h base + 4h offset = 4003\_2004h



## **CRC\_GPOLY** field descriptions


Field	Description
31–16 HIGH	High polynominal half-word  This field is writable and readable in 32-bit CRC mode (the CTRL[TCRC] bit is 1). This field is not writable in 16-bit CRC mode (the CTRL[TCRC] bit is 0).
15–0 LOW	Low polynominal half-word  This field is writable and readable in both 32-bit and 16-bit CRC modes.



# 31.2.3 CRC Control Register (CRC\_CTRL)

This register controls the configuration and working of the CRC module. Appropriate bits must be set before starting a new CRC calculation. A new CRC calculation is initialized by asserting the CTRL[WAS] bit and then writing the seed into the CRC data register.

Address: CRC\_CTRL is 4003\_2000h base + 8h offset = 4003\_2008h



## **CRC\_CTRL** field descriptions

Field	Description
31–30 TOT	Type of Transpose for Writes
	These bits define the transpose configuration of the data written to the CRC data register. Refer to the description of the transpose feature for the available transpose options.
	00 No transposition.
	01 Bits in bytes are transposed; bytes are not transposed.
	10 Both bits in bytes and bytes are transposed.
	11 Only bytes are transposed; no bits in a byte are transposed.
29–28 TOTR	Type of Transpose for Read
	These bits identify the transpose configuration of the value read from the CRC data register. Refer to the description of the transpose feature for the available transpose options.
	00 No transposition.
	01 Bits in bytes are transposed; bytes are not transposed.
	10 Both bits in bytes and bytes are transposed.
	11 Only bytes are transposed; no bits in a byte are transposed.
27 Reserved	This read-only field is reserved and always has the value zero.
26 FXOR	Complement Read of CRC data register
I Aon	Some CRC protocols require the final checksum to be XORed with 0xFFFFFFF or 0xFFFF. Asserting this bit enables "on the fly" complementing of read data.
	0 No XOR on reading.
	1 Invert or complement the read value of the CRC data register.
25 WAS	Write CRC data register as seed
	When this bit is asserted, a value written to the CRC data register is considered a seed value. When this bit is de-asserted, a value written to the CRC data register is taken as data for CRC computation.
	0 Writes to the CRC data register are data values.
	1 Writes to the CRC data register are seed values.

Table continues on the next page...



## CRC\_CTRL field descriptions (continued)

Field	Description
24 TCRC	Width of CRC protocol.
	0 16-bit CRC protocol.
	1 32-bit CRC protocol.
23–0 Reserved	This read-only field is reserved and always has the value zero.

# 31.3 Functional description

## 31.3.1 CRC initialization/re-initialization

To enable the CRC calculation, the user must program the WAS, POLYNOMIAL, and necessary parameters for transpose and CRC result inversion in the applicable registers. Asserting the CTRL[WAS] bit enables the programming of the seed value into the CRC data register.

After a completed CRC calculation, re-asserting the CTRL[WAS] bit and programming a seed (whether the value is new or a previously used seed value) re-initialize the CRC module for a new CRC computation. All other parameters must be set before programming the seed value and subsequent data values.

## 31.3.2 CRC calculations

In 16-bit and 32-bit CRC modes, data values can be programmed 8 bits, 16 bits, or 32 bits at a time, provided all bytes are contiguous. Non-contiguous bytes can lead to an incorrect CRC computation.

## 31.3.2.1 16-bit CRC

Compute a 16-bit CRC with the following steps:

- 1. Clear the CTRL[TCRC] bit to enable 16-bit CRC mode.
- 2. Program the transpose and complement options in the CTRL register as required for the CRC calculation. See Transpose feature and CRC result complement for details.
- 3. Write a 16-bit polynomial to the GPOLY[LOW] field. The GPOLY[HIGH] field is not usable in 16-bit CRC mode.
- 4. Set the CTRL[WAS] bit to program the seed value.



- 5. Write a 16-bit seed to CRC[LU:LL]. CRC[HU:HL] are not used.
- 6. Clear the CTRL[WAS] bit to start writing data values.
- 7. Write data values into CRC[HU:HL:LU:LL]. A CRC is computed on every data value write, and the intermediate CRC result is stored back into CRC[LU:LL].
- 8. When all values have been written, read the final CRC result from CRC[LU:LL].

Transpose and complement operations are performed "on the fly" while reading or writing values. See Transpose feature and CRC result complement for details.

#### 31.3.2.2 32-bit CRC

Compute a 32-bit CRC with the following steps:

- 1. Set the CTRL[TCRC] bit to enable 32-bit CRC mode.
- 2. Program the transpose and complement options in the CTRL register as required for the CRC calculation. See Transpose feature and CRC result complement for details.
- 3. Write a 32-bit polynomial to GPOLY[HIGH:LOW].
- 4. Set the CTRL[WAS] bit to program the seed value.
- 5. Write a 32-bit seed to CRC[HU:HL:LU:LL].
- 6. Clear the CTRL[WAS] bit to start writing data values.
- 7. Write data values into CRC[HU:HL:LU:LL]. A CRC is computed on every data value write, and the intermediate CRC result is stored back into CRC[HU:HL:LU:LL].
- 8. When all values have been written, read the final CRC result from CRC[HU:HL:LU:LL]. The CRC is calculated bytewise, and two clocks are required to complete one CRC calculation.

Transpose and complement operations are performed "on the fly" while reading or writing values. See Transpose feature and CRC result complement for details.

# 31.3.3 Transpose feature

By default, the transpose feature is not enabled. However, some CRC standards require the input data and/or the final checksum to be transposed. The user software has the option to configure each transpose operation separately, as desired by the CRC standard. The data is transposed "on the fly" while being read or written.

Some protocols use little endian format for the data stream to calculate a CRC. In this case, the transpose feature usefully flips the bits. This transpose option is one of the types supported by the CRC module.

# 31.3.3.1 Types of transpose

The CRC module provides several types of transpose functions to flip the bits and/or bytes (for both writing input data and reading the CRC result, separately using the CTRL[TOT] or CTRL[TOTR] fields) according to the CRC calculation being used.

The following types of transpose functions are available for writing to and reading from the CRC data register.

- CTRL[TOT] or CTRL[TOTR] is 00
   No transposition occurs.
- 2. CTRL[TOT] or CTRL[TOTR] is 01

Bits in a byte are transposed, while bytes are not transposed.

reg[31:0] becomes {reg[24:31], reg[16:23], reg[8:15], reg[0:7]}




Figure 31-5. Transpose type 01

3. CTRL[TOT] or CTRL[TOTR] is 10

Both bits in bytes and bytes are transposed.

reg[31:0] becomes = {reg[0:7], reg[8:15], reg[16:23], reg[24:31]}




Figure 31-6. Transpose type 10

4. CTRL[TOT] or CTRL[TOTR] is 11

Bytes are transposed, but bits are not transposed.

reg[31:0] becomes {reg[7:0], reg[15:8], reg[23:16], reg[31:24]}






Figure 31-7. Transpose type 11

#### **NOTE**

For 8-bit and 16-bit write accesses to the CRC data register, the data is transposed with zeros on the unused byte or bytes (taking 32 bits as a whole), but the CRC is calculated on the valid byte(s) only. When reading the CRC data register for a 16-bit CRC result and using transpose options 10 and 11, the resulting value after transposition resides in the CRC[HU:HL] fields. The user software must account for this situation when reading the 16-bit CRC result, so reading 32 bits is preferred.

## 31.3.4 CRC result complement

When the CTRL[FXOR] bit is set, the checksum is complemented: The CRC result complement function outputs the complement of the checksum value stored in the CRC data register every time the CRC data register is read. When the CTRL[FXOR] bit is cleared, reading the CRC data register accesses the raw checksum value.



runctional description



# **Chapter 32 Analog-to-Digital Converter (ADC)**

### 32.1 Introduction

#### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The 16-bit analog-to-digital converter (ADC) is a successive approximation ADC designed for operation within an integrated microcontroller system-on-chip.

#### **NOTE**

For the chip specific modes of operation, refer to the Power Management information for the device.

## 32.1.1 Features

Features of the ADC module include:

- Linear successive approximation algorithm with up to 16-bit resolution
- Up to 4 pairs of differential and 24 single-ended external analog inputs
- Output modes: differential 16-bit, 13-bit, 11-bit and 9-bit modes, or single-ended 16-bit, 12-bit, 10-bit and 8-bit modes
- Output formatted in 2's complement 16-bit sign extended for differential modes
- Output in right-justified unsigned format for single-ended
- Single or continuous conversion (automatic return to idle after single conversion)
- Configurable sample time and conversion speed/power
- Conversion complete / hardware average complete flag and interrupt



#### muroduction

- Input clock selectable from up to four sources
- Operation in low power modes for lower noise operation
- Asynchronous clock source for lower noise operation with option to output the clock
- Selectable hardware conversion trigger with hardware channel select
- Automatic compare with interrupt for less-than, greater-than or equal-to, within range, or out-of-range, programmable value
- Temperature sensor
- Hardware average function
- Selectable voltage reference: external or alternate
- Self-calibration mode
- Programmable Gain Amplifier (PGA) with up to x64 gain

## 32.1.2 Block diagram

The following figure is the ADC module block diagram.






Figure 32-1. ADC block diagram

## 32.2 ADC Signal Descriptions

The ADC module supports up to 4 pairs of differential inputs and up to 24 single-ended inputs. Each differential pair requires two inputs, DADPx and DADMx. The ADC also requires four supply/reference/ground connections.

Table 32-1. ADC Signal Descriptions

Signal	Description	I/O
DADP[3:0]	Differential analog channel inputs	I



#### ADC Signal Descriptions

#### Table 32-1. ADC Signal Descriptions (continued)

Signal	Description	I/O
DADM[3:0]	Differential analog channel inputs	I
AD[23:4]	Single-ended analog channel inputs	I
V <sub>REFSH</sub>	Voltage reference select high	I
V <sub>REFSL</sub>	Voltage reference select low	I
$V_{DDA}$	Analog power supply	I
V <sub>SSA</sub>	Analog ground	I

## 32.2.1 Analog power (V<sub>DDA</sub>)

The ADC analog portion uses  $V_{DDA}$  as its power connection. In some packages,  $V_{DDA}$  is connected internally to  $V_{DD}$ . If externally available, connect the  $V_{DDA}$  pin to the same voltage potential as  $V_{DD}$ . External filtering may be necessary to ensure clean  $V_{DDA}$  for good results.

## 32.2.2 Analog ground (V<sub>SSA</sub>)

The ADC analog portion uses  $V_{SSA}$  as its ground connection. In some packages,  $V_{SSA}$  is connected internally to  $V_{SS}$ . If externally available, connect the  $V_{SSA}$  pin to the same voltage potential as  $V_{SS}$ .

## 32.2.3 Voltage reference select

V<sub>REESH</sub> and V<sub>REESL</sub> are the high and low reference voltages for the converter.

The ADC can be configured to accept one of two voltage reference pairs for  $V_{REFSH}$  and  $V_{REFSL}$ . Each pair contains a positive reference that must be between the minimum Ref Voltage High and  $V_{DDA}$ , and a ground reference that must be at the same potential as  $V_{SSA}$ . The two pairs are external ( $V_{REFH}$  and  $V_{REFL}$ ) and alternate ( $V_{ALTH}$  and  $V_{ALTL}$ ). These voltage references are selected using the REFSEL bits in the SC2 register. The alternate ( $V_{ALTH}$  and  $V_{ALTL}$ ) voltage reference pair may select additional external pins or internal sources depending on MCU configuration. Refer to the Chip Configuration information on the Voltage References specific to this MCU.



In some packages,  $V_{REFH}$  is connected in the package to  $V_{DDA}$  and  $V_{REFL}$  to  $V_{SSA}$ . If externally available, the positive reference(s) may be connected to the same potential as  $V_{DDA}$  or may be driven by an external source to a level between the minimum Ref Voltage High and the  $V_{DDA}$  potential ( $V_{REFH}$  must never exceed  $V_{DDA}$ ). Connect the ground references to the same voltage potential as  $V_{SSA}$ .

## 32.2.4 Analog channel inputs (ADx)

The ADC module supports up to 24 single-ended analog inputs. A single-ended input is selected for conversion through the ADCH channel select bits when the DIFF bit in the SC1n register is low.

## 32.2.5 Differential analog channel inputs (DADx)

The ADC module supports up to 4 differential analog channel inputs. Each differential analog input is a pair of external pins (DADPx and DADMx) referenced to each other to provide the most accurate analog to digital readings. A differential input is selected for conversion through the ADCH channel select bits when the DIFF bit in the SC1n register bit is high. All DADPx inputs may be used as single-ended inputs if the DIFF bit is low. In certain MCU configurations, some DADMx inputs may also be used as single-ended inputs if the DIFF bit is low. Refer to the Chip Configuration chapter for ADC connections specific to this MCU.

## 32.3 Register Definition

This section describes the ADC registers.

### **ADC** memory map

Absolute address (hex)	Register name		Access	Reset value	Section/ page
4003_B000	ADC status and control registers 1 (ADC0_SC1A)	32	R/W	0000_001Fh	32.3.1/ 730
4003_B004	ADC status and control registers 1 (ADC0_SC1B)	32	R/W	0000_001Fh	32.3.1/ 730
4003_B008	ADC configuration register 1 (ADC0_CFG1)	32	R/W	0000_0000h	32.3.2/ 733



## **ADC** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_B00C	Configuration register 2 (ADC0_CFG2)	32	R/W	0000_0000h	32.3.3/ 735
4003_B010	ADC data result register (ADC0_RA)	32	R	0000_0000h	32.3.4/ 736
4003_B014	ADC data result register (ADC0_RB)	32	R	0000_0000h	32.3.4/ 736
4003_B018	Compare value registers (ADC0_CV1)	32	R/W	0000_0000h	32.3.5/ 737
4003_B01C	Compare value registers (ADC0_CV2)	32	R/W	0000_0000h	32.3.5/ 737
4003_B020	Status and control register 2 (ADC0_SC2)	32	R/W	0000_0000h	32.3.6/ 738
4003_B024	Status and control register 3 (ADC0_SC3)	32	R/W	0000_0000h	32.3.7/ 740
4003_B028	ADC offset correction register (ADC0_OFS)	32	R/W	0000_0004h	32.3.8/ 741
4003_B02C	ADC plus-side gain register (ADC0_PG)	32	R/W	0000_8200h	32.3.9/ 742
4003_B030	ADC minus-side gain register (ADC0_MG)	32	R/W	0000_8200h	32.3.10/ 742
4003_B034	ADC plus-side general calibration value register (ADC0_CLPD)	32	R/W	0000_000Ah	32.3.11/ 743
4003_B038	ADC plus-side general calibration value register (ADC0_CLPS)	32	R/W	0000_0020h	32.3.12/ 744
4003_B03C	ADC plus-side general calibration value register (ADC0_CLP4)	32	R/W	0000_0200h	32.3.13/ 744
4003_B040	ADC plus-side general calibration value register (ADC0_CLP3)	32	R/W	0000_0100h	32.3.14/ 745
4003_B044	ADC plus-side general calibration value register (ADC0_CLP2)	32	R/W	0000_0080h	32.3.15/ 745
4003_B048	ADC plus-side general calibration value register (ADC0_CLP1)	32	R/W	0000_0040h	32.3.16/ 746
4003_B04C	ADC plus-side general calibration value register (ADC0_CLP0)	32	R/W	0000_0020h	32.3.17/ 746
4003_B050	ADC PGA register (ADC0_PGA)	32	R/W	0000_0000h	32.3.18/ 747
4003_B054	ADC minus-side general calibration value register (ADC0_CLMD)	32	R/W	0000_000Ah	32.3.19/ 748
4003_B058	ADC minus-side general calibration value register (ADC0_CLMS)	32	R/W	0000_0020h	32.3.20/ 749



## **ADC** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)		Reset value	Section/ page
4003_B05C	ADC minus-side general calibration value register (ADC0_CLM4)	32	R/W	0000_0200h	32.3.21/ 749
4003_B060	ADC minus-side general calibration value register (ADC0_CLM3)	32	R/W	0000_0100h	32.3.22/ 750
4003_B064	ADC minus-side general calibration value register (ADC0_CLM2)	32	R/W	0000_0080h	32.3.23/ 750
4003_B068	ADC minus-side general calibration value register (ADC0_CLM1)	32	R/W	0000_0040h	32.3.24/ 751
4003_B06C	ADC minus-side general calibration value register (ADC0_CLM0)	32	R/W	0000_0020h	32.3.25/ 751
400B_B000	ADC status and control registers 1 (ADC1_SC1A)	32	R/W	0000_001Fh	32.3.1/ 730
400B_B004	ADC status and control registers 1 (ADC1_SC1B)	32	R/W	0000_001Fh	32.3.1/ 730
400B_B008	ADC configuration register 1 (ADC1_CFG1)	32	R/W	0000_0000h	32.3.2/ 733
400B_B00C	Configuration register 2 (ADC1_CFG2)	32	R/W	0000_0000h	32.3.3/ 735
400B_B010	ADC data result register (ADC1_RA)	32	R	0000_0000h	32.3.4/ 736
400B_B014	ADC data result register (ADC1_RB)	32	R	0000_0000h	32.3.4/ 736
400B_B018	Compare value registers (ADC1_CV1)	32	R/W	0000_0000h	32.3.5/ 737
400B_B01C	Compare value registers (ADC1_CV2)	32	R/W	0000_0000h	32.3.5/ 737
400B_B020	Status and control register 2 (ADC1_SC2)	32	R/W	0000_0000h	32.3.6/ 738
400B_B024	Status and control register 3 (ADC1_SC3)	32	R/W	0000_0000h	32.3.7/ 740
400B_B028	ADC offset correction register (ADC1_OFS)	32	R/W	0000_0004h	32.3.8/ 741
400B_B02C	ADC plus-side gain register (ADC1_PG)	32	R/W	0000_8200h	32.3.9/ 742
400B_B030	ADC minus-side gain register (ADC1_MG)	32	R/W	0000_8200h	32.3.10/ 742
400B_B034	ADC plus-side general calibration value register (ADC1_CLPD)	32	R/W	0000_000Ah	32.3.11/ 743
400B_B038	ADC plus-side general calibration value register (ADC1_CLPS)	32	R/W	0000_0020h	32.3.12/ 744



#### **ADC** memory map (continued)

Absolute address (hex)	Register name	Register name Width (in bits) Access		Reset value	Section/ page
400B_B03C	ADC plus-side general calibration value register (ADC1_CLP4)	32	R/W	0000_0200h	32.3.13/ 744
400B_B040	ADC plus-side general calibration value register (ADC1_CLP3)	32	R/W	0000_0100h	32.3.14/ 745
400B_B044	ADC plus-side general calibration value register (ADC1_CLP2)	32	R/W	0000_0080h	32.3.15/ 745
400B_B048	ADC plus-side general calibration value register (ADC1_CLP1)	32	R/W	0000_0040h	32.3.16/ 746
400B_B04C	ADC plus-side general calibration value register (ADC1_CLP0)	32	R/W	0000_0020h	32.3.17/ 746
400B_B050	ADC PGA register (ADC1_PGA)	32	R/W	0000_0000h	32.3.18/ 747
400B_B054	ADC minus-side general calibration value register (ADC1_CLMD)	32	R/W	0000_000Ah	32.3.19/ 748
400B_B058	ADC minus-side general calibration value register (ADC1_CLMS)	32	R/W	0000_0020h	32.3.20/ 749
400B_B05C	ADC minus-side general calibration value register (ADC1_CLM4)	32	R/W	0000_0200h	32.3.21/ 749
400B_B060	ADC minus-side general calibration value register (ADC1_CLM3)	32	R/W	0000_0100h	32.3.22/ 750
400B_B064	ADC minus-side general calibration value register (ADC1_CLM2)	32	R/W	0000_0080h	32.3.23/ 750
400B_B068	ADC minus-side general calibration value register (ADC1_CLM1)	32	R/W	0000_0040h	32.3.24/ 751
400B_B06C	ADC minus-side general calibration value register (ADC1_CLM0)	32	R/W	0000_0020h	32.3.25/ 751

## 32.3.1 ADC status and control registers 1 (ADCx SC1n)

The SC1A register is used for both software and hardware trigger modes of operation.


To allow sequential conversions of the ADC to be triggered by internal peripherals, the ADC can have more then one status and control register: one for each conversion. The SC1B-SC1n registers indicate potentially multiple SC1 registers for use only in hardware trigger mode. Refer to the Chip Configuration information about the number of SC1n registers specific to this device. The SC1n registers have identical fields, and are used in a "ping-pong" approach to control ADC operation.

At any one point in time, only one of the SC1n registers is actively controlling ADC conversions. Updating SC1A while SC1n is actively controlling a conversion is allowed (and vice-versa for any of the SC1n registers specific to this MCU).



Writing SC1A while SC1A is actively controlling a conversion aborts the current conversion. In software trigger mode (ADTRG=0), writes to the SC1A register subsequently initiate a new conversion (if the ADCH bits are equal to a value other than all 1s).

Similarly, writing any of the SC1n registers while that specific SC1n register is actively controlling a conversion aborts the current conversion. None of the SC1B-SC1n registers are used for software trigger operation and therefore writes to the SC1B - SC1n registers do not initiate a new conversion.



#### ADCx\_SC1n field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 COCO	Conversion complete flag  The COCO flag is a read-only bit that is set each time a conversion is completed when the compare function is disabled (ACFE=0) and the hardware average function is disabled (AVGE=0). When the compare function is enabled (ACFE=1), the COCO flag is set upon completion of a conversion only if the compare result is true. When the hardware average function is enabled (AVGE=1), the COCO flag is set upon completion of the selected number of conversions (determined by the AVGS bits). The COCO flag in SC1A is also set at the completion of a Calibration sequence. The COCO bit is cleared when the respective SC1n register is written or when the respective Rn register is read.  O Conversion not completed.



## ADCx\_SC1n field descriptions (continued)

Field	Description
6	Interrupt enable
AIEN	AIEN enables conversion complete interrupts. When COCO becomes set while the respective AIEN is high, an interrupt is asserted.
	0 Conversion complete interrupt disabled.
	1 Conversion complete interrupt enabled.
5	Differential mode enable
DIFF	DIFF configures the ADC to operate in differential mode. When enabled, this mode automatically selects from the differential channels, and changes the conversion algorithm and the number of cycles to complete a conversion.
	0 Single-ended conversions and input channels are selected.
	1 Differential conversions and input channels are selected.
4–0	Input channel select
ADCH	The ADCH bits form a 5-bit field that selects one of the input channels. The input channel decode depends on the value of the DIFF bit. DAD0-DAD3 are associated with the input pin pairs DADPx and DADMx.
	The successive approximation converter subsystem is turned off when the channel select bits are all set (ADCH = 11111). This feature allows for explicit disabling of the ADC and isolation of the input channel from all sources. Terminating continuous conversions this way prevents an additional single conversion from being performed. It is not necessary to set the channel select bits to all ones to place the ADC in a low-power state when continuous conversions are not enabled because the module automatically enters a low-power state when a conversion completes.
	00000 When DIFF=0, DADP0 is selected as input; when DIFF=1, DAD0 is selected as input.
	00001 When DIFF=0, DADP1 is selected as input; when DIFF=1, DAD1 is selected as input.
	00010 When DIFF=0, DADP2 is selected as input; when DIFF=1, DAD2 is selected as input.
	00011 When DIFF=0, DADP3 is selected as input; when DIFF=1, DAD3 is selected as input.
	00100 When DIFF=0, AD4 is selected as input; when DIFF=1, it is reserved.
	00101 When DIFF=0, AD5 is selected as input; when DIFF=1, it is reserved.
	00110 When DIFF=0, AD6 is selected as input; when DIFF=1, it is reserved.
	00111 When DIFF=0, AD7 is selected as input; when DIFF=1, it is reserved. 01000 When DIFF=0, AD8 is selected as input; when DIFF=1, it is reserved.
	01000 When DIFF=0, AD8 is selected as input; when DIFF=1, it is reserved.  01001 When DIFF=0, AD9 is selected as input; when DIFF=1, it is reserved.
	01010 When DIFF=0, AD10 is selected as input; when DIFF=1, it is reserved.
	01011 When DIFF=0, AD11 is selected as input; when DIFF=1, it is reserved.
	01100 When DIFF=0, AD12 is selected as input; when DIFF=1, it is reserved.
	01101 When DIFF=0, AD13 is selected as input; when DIFF=1, it is reserved.
	01110 When DIFF=0, AD14 is selected as input; when DIFF=1, it is reserved.
	01111 When DIFF=0, AD15 is selected as input; when DIFF=1, it is reserved.
	10000 When DIFF=0, AD16 is selected as input; when DIFF=1, it is reserved.
	10001 When DIFF=0, AD17 is selected as input; when DIFF=1, it is reserved.
	10010 When DIFF=0, AD18 is selected as input; when DIFF=1, it is reserved.
	10011 When DIFF=0, AD19 is selected as input; when DIFF=1, it is reserved.
	10100 When DIFF=0, AD20 is selected as input; when DIFF=1, it is reserved.
	10101 When DIFF=0, AD21 is selected as input; when DIFF=1, it is reserved.
	10110 When DIFF=0, AD22 is selected as input; when DIFF=1, it is reserved.




## ADCx\_SC1n field descriptions (continued)

Field		Description
	10111	When DIFF=0, AD23 is selected as input; when DIFF=1, it is reserved.
	11000	Reserved.
	11001	Reserved.
	11010	When DIFF=0, Temp sensor (single-ended) is selected as input; when DIFF=1, Temp sensor (differential) is selected as input.
	11011	When DIFF=0, Bandgap (single-ended) is selected as input; when DIFF=1, Bandgap (differential) is selected as input.
	11100	Reserved.
	11101	When DIFF=0, $V_{REFSH}$ is selected as input; when DIFF=1, $-V_{REFSH}$ (differential) is selected as input. Voltage reference selected is determined by the REFSEL bits in the SC2 register.
	11110	When DIFF=0, V <sub>REFSL</sub> is selected as input; when DIFF=1, it is reserved. Voltage reference selected is determined by the REFSEL bits in the SC2 register.
	11111	Module disabled.

## 32.3.2 ADC configuration register 1 (ADCx\_CFG1)

CFG1 register selects the mode of operation, clock source, clock divide, and configure for low power or long sample time.

Addresses: ADC0\_CFG1 is 4003\_B000h base + 8h offset = 4003\_B008h



### ADCx\_CFG1 field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 ADLPC	Low-power configuration  ADLPC controls the power configuration of the successive approximation converter. This optimizes power consumption when higher sample rates are not required.




## ADCx\_CFG1 field descriptions (continued)


Field	Description
	0 Normal power configuration.
	1 Low power configuration. The power is reduced at the expense of maximum clock speed.
6–5 ADIV	Clock divide select
	ADIV selects the divide ratio used by the ADC to generate the internal clock ADCK.
	00 The divide ratio is 1 and the clock rate is input clock.
	01 The divide ratio is 2 and the clock rate is (input clock)/2.
	10 The divide ratio is 4 and the clock rate is (input clock)/4.
	11 The divide ratio is 8 and the clock rate is (input clock)/8.
4 ADLSMP	Sample time configuration
	ADLSMP selects between different sample times based on the conversion mode selected. This bit adjusts the sample period to allow higher impedance inputs to be accurately sampled or to maximize conversion speed for lower impedance inputs. Longer sample times can also be used to lower overall power consumption if continuous conversions are enabled and high conversion rates are not required. When ADLSMP=1, the long sample time select bits, (ADLSTS[1:0]), can select the extent of the long sample time.
	0 Short sample time.
	1 Long sample time.
3–2 MODE	Conversion mode selection
	MODE bits are used to select the ADC resolution mode.
	00 When DIFF=0: It is single-ended 8-bit conversion; when DIFF=1, it is differential 9-bit conversion with 2's complement output.
	01 When DIFF=0: It is single-ended 12-bit conversion; when DIFF=1, it is differential 13-bit conversion with 2's complement output.
	10 When DIFF=0: It is single-ended 10-bit conversion; when DIFF=1, it is differential 11-bit conversion with 2's complement output.
	11 When DIFF=0: It is single-ended 16-bit conversion; when DIFF=1, it is differential 16-bit conversion with 2's complement output.
1–0 ADICLK	Input clock select
	ADICLK bits select the input clock source to generate the internal clock, ADCK. Note that when the ADACK clock source is selected, it is not required to be active prior to conversion start. When it is selected and it is not active prior to a conversion start (ADACKEN=0), the asynchronous clock is activated at the start of a conversion and shuts off when conversions are terminated. In this case, there is an associated clock startup delay each time the clock source is re-activated.
	00 Bus clock.
	01 Bus clock divided by 2.
	10 Alternate clock (ALTCLK).
	11 Asynchronous clock (ADACK).



## 32.3.3 Configuration register 2 (ADCx\_CFG2)

CFG2 register selects the special high speed configuration for very high speed conversions and selects the long sample time duration during long sample mode.





## ADCx\_CFG2 field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7–5 Reserved	This read-only field is reserved and always has the value zero.
4 MUXSEL	ADC Mux select  ADC Mux select bit is used to change the ADC mux setting to select between alternate sets of ADC channels.  O ADxxa channels are selected.  1 ADxxb channels are selected.
3 ADACKEN	Asynchronous clock output enable  ADACKEN enables the ADC's asynchronous clock source and the clock source output regardless of the conversion and input clock select (ADICLK bits) status of the ADC. Based on MCU configuration, the asynchronous clock may be used by other modules (see Chip Configuration information). Setting this bit allows the clock to be used even while the ADC is idle or operating from a different clock source. Also, latency of initiating a single or first-continuous conversion with the asynchronous clock selected is reduced since the ADACK clock is already operational.  O Asynchronous clock output disabled; Asynchronous clock only enabled if selected by ADICLK and a conversion is active.  Asynchronous clock and clock output enabled regardless of the state of the ADC.
2 ADHSC	High speed configuration



#### ADCx\_CFG2 field descriptions (continued)

Field	Description
	ADHSC configures the ADC for very high speed operation. The conversion sequence is altered (2 ADCK cycles added to the conversion time) to allow higher speed conversion clocks.
	0 Normal conversion sequence selected.
	1 High speed conversion sequence selected (2 additional ADCK cycles to total conversion time).
1-0 ADLSTS	Long sample time select
	ADLSTS selects between the extended sample times when long sample time is selected (ADLSMP=1). This allows higher impedance inputs to be accurately sampled or to maximize conversion speed for lower impedance inputs. Longer sample times can also be used to lower overall power consumption when continuous conversions are enabled if high conversion rates are not required.
	00 Default longest sample time (20 extra ADCK cycles; 24 ADCK cycles total).
	01 12 extra ADCK cycles; 16 ADCK cycles total sample time.
	10 6 extra ADCK cycles; 10 ADCK cycles total sample time.
	11 2 extra ADCK cycles; 6 ADCK cycles total sample time.

## 32.3.4 ADC data result register (ADCx\_Rn)

The data result registers (Rn) contain the result of an ADC conversion of the channel selected by the corresponding status and channel control register (SC1A:SC1n). For every status and channel control register, there is a corresponding data result register.

Unused bits in the Rn register are cleared in unsigned right justified modes and carry the sign bit (MSB) in sign extended 2's complement modes. For example, when configured for 10-bit single-ended mode, D[15:10] are cleared. When configured for 11-bit differential mode, D[15:10] carry the sign bit (bit 10 extended through bit 15).

The following table describes the behavior of the data result registers in the different modes of operation.

Table 32-44. Data result register description

Conversion mode	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0	Format
16-bit differential	S	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	Signed 2's complement
16-bit single- ended	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	Unsigned right justified
13-bit differential	S	S	S	S	D	D	D	D	D	D	D	D	D	D	D	D	Sign extended 2's complement
12-bit single- ended	0	0	0	0	D	D	D	D	D	D	D	D	D	D	D	D	Unsigned right justified



#### Table 32-44. Data result register description (continued)

Conversion mode	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0	Format
11-bit differential	S	S	S	S	S	S	D	D	D	D	D	D	D	D	D	D	Sign extended 2's complement
10-bit single- ended	0	0	0	0	0	0	D	D	D	D	D	D	D	D	D	D	Unsigned right justified
9-bit differential	S	S	S	S	S	S	S	S	D	D	D	D	D	D	D	D	Sign extended 2's complement
8-bit single- ended	0	0	0	0	0	0	0	0	D	D	D	D	D	D	D	D	Unsigned right justified

#### NOTE

S: Sign bit or sign bit extension;


D: Data (2's complement data if indicated)

Addresses: ADC0\_RA is 4003\_B000h base + 10h offset = 4003\_B010h

ADC0\_RB is 4003\_B000h base + 14h offset = 4003\_B014h

ADC1\_RA is 400B\_B000h base + 10h offset = 400B\_B010h

ADC1\_RB is 400B\_B000h base + 14h offset = 400B\_B014h



### ADCx\_Rn field descriptions


Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 D	Data result

## 32.3.5 Compare value registers (ADCx\_CVn)

The compare value registers (CV1 and CV2) contain a compare value used to compare with the conversion result when the compare function is enabled (ACFE=1). This register is formatted the same for both bit position definition and value format (unsigned or sign-extended 2's complement) as the data result registers (Rn) in the different modes of operation. Therefore, the compare function only uses the compare value register bits that are related to the ADC mode of operation.



The compare value 2 register (CV2) is utilized only when the compare range function is enabled (ACREN=1).




#### ADCx\_CVn field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 CV	Compare value

## 32.3.6 Status and control register 2 (ADCx\_SC2)

The SC2 register contains the conversion active, hardware/software trigger select, compare function and voltage reference select of the ADC module.





## ADCx\_SC2 field descriptions


Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7	Conversion active
ADACT	ADACT indicates that a conversion or hardware averaging is in progress. ADACT is set when a conversion is initiated and cleared when a conversion is completed or aborted.
	<ul><li>0 Conversion not in progress.</li><li>1 Conversion in progress.</li></ul>
6 ADTRG	Conversion trigger select
ADITIO	ADTRG selects the type of trigger used for initiating a conversion. Two types of trigger are selectable: software trigger and hardware trigger. When software trigger is selected, a conversion is initiated following a write to SC1A. When hardware trigger is selected, a conversion is initiated following the assertion of the ADHWT input after a pulse of the ADHWTSn input.
	0 Software trigger selected.
	1 Hardware trigger selected.
5 ACFE	Compare function enable
ACIL	ACFE enables the compare function.
	O Compare function disabled.
	1 Compare function enabled.
4 ACFGT	Compare function greater than enable  ACFGT configures the compare function to check the conversion result relative to the compare value
	register(s) (CV1 and CV2) based upon the value of ACREN. The ACFE bit must be set for ACFGT to have any effect.
	O Configures less than threshold, outside range not inclusive and inside range not inclusive functionality based on the values placed in the CV1 and CV2 registers.
	1 Configures greater than or equal to threshold, outside range inclusive and inside range inclusive functionality based on the values placed in the CV1 and CV2 registers.
3	Compare function range enable
ACREN	ACREN configures the compare function to check if the conversion result of the input being monitored is either between or outside the range formed by the compare value registers (CV1 and CV2) determined by the value of ACFGT. The ACFE bit must be set for ACFGT to have any effect.
	0 Range function disabled. Only the compare value 1 register (CV1) is compared.
	1 Range function enabled. Both compare value registers (CV1 and CV2) are compared.
2 DMAEN	DMA enable
	0 DMA is disabled.
	1 DMA is enabled and will assert the ADC DMA request during a ADC conversion complete event noted by the assertion of any of the ADC COCO flags.
1-0	Voltage reference selection
REFSEL	REFSEL bits select the voltage reference source used for conversions.


### ADCx\_SC2 field descriptions (continued)

Field	Description	
	Default voltage reference pin pair (external pins V <sub>REFH</sub> and V <sub>REFL</sub> )	
	Alternate reference pair (V <sub>ALTH</sub> and V <sub>ALTL</sub> ). This pair may be additional external pins or internal sources depending on MCU configuration. Consult the Chip Configuration information for details specific to this MCU.	3
	) Reserved	
	Reserved	

## 32.3.7 Status and control register 3 (ADCx\_SC3)

The SC3 register controls the calibration, continuous convert, and hardware averaging functions of the ADC module.





## ADCx\_SC3 field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 CAL	Calibration  CAL begins the calibration sequence when set. This bit stays set while the calibration is in progress and is cleared when the calibration sequence is completed. The CALF bit must be checked to determine the result of the calibration sequence. Once started, the calibration routine cannot be interrupted by writes to the ADC registers or the results will be invalid and the CALF bit will set. Setting the CAL bit will abort any current conversion.
6 CALF	Calibration failed flag  CALF displays the result of the calibration sequence. The calibration sequence will fail if ADTRG = 1, any ADC register is written, or any stop mode is entered before the calibration sequence completes. The CALF bit is cleared by writing a 1 to this bit.





### ADCx\_SC3 field descriptions (continued)

Field	Description
	<ul> <li>Calibration completed normally.</li> <li>Calibration failed. ADC accuracy specifications are not guaranteed.</li> </ul>
5–4 Reserved	This read-only field is reserved and always has the value zero.
3 ADCO	Continuous conversion enable  ADCO enables continuous conversions.
	One conversion or one set of conversions if the hardware average function is enabled (AVGE=1) after initiating a conversion.
	1 Continuous conversions or sets of conversions if the hardware average function is enabled (AVGE=1) after initiating a conversion.
2 AVGE	Hardware average enable  AVGE enables the hardware average function of the ADC.
	<ul><li>0 Hardware average function disabled.</li><li>1 Hardware average function enabled.</li></ul>
1-0 AVGS	Hardware average select  AVGS determines how many ADC conversions will be averaged to create the ADC average result.
	<ul> <li>4 samples averaged.</li> <li>8 samples averaged.</li> <li>16 samples averaged.</li> <li>32 samples averaged.</li> </ul>

## 32.3.8 ADC offset correction register (ADCx\_OFS)

The ADC offset correction register (OFS) contains the user selected or calibration generated offset error correction value. This register is a 2's complement, left justified, 16-bit value. The value in the offset correction registers (OFS) is subtracted from the conversion and the result is transferred into the result registers (Rn). If the result is above the maximum or below the minimum result value, it is forced to the appropriate limit for the current mode of operation.







#### ADCx\_OFS field descriptions


Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 OFS	Offset error correction value

## 32.3.9 ADC plus-side gain register (ADCx\_PG)

The plus-side gain register (PG) contains the gain error correction for the plus-side input in differential mode or the overall conversion in single-ended mode. PG, a 16-bit real number in binary format, is the gain adjustment factor, with the radix point fixed between ADPG15 and ADPG14. This register must be written by the user with the value described in the calibration procedure or the gain error specifications may not be met.

Addresses: ADC0\_PG is 4003\_B000h base + 2Ch offset = 4003\_B02Ch

ADC1\_PG is 400B\_B000h base + 2Ch offset = 400B\_B02Ch



### ADCx\_PG field descriptions


Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 PG	Plus-side gain

## 32.3.10 ADC minus-side gain register (ADCx\_MG)

The minus-side gain register (MG) contains the gain error correction for the minus-side input in differential mode. This register is ignored in single-ended mode. MG, a 16-bit real number in binary format, is the gain adjustment factor, with the radix point fixed between ADMG15 and ADMG14. This register must be written by the user with the value described in the calibration procedure or the gain error specifications may not be met.



Addresses: ADC0\_MG is 4003\_B000h base + 30h offset = 4003\_B030h ADC1\_MG is 400B\_B000h base + 30h offset = 400B\_B030h




#### ADCx\_MG field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 MG	Minus-side gain

# 32.3.11 ADC plus-side general calibration value register (ADCx\_CLPD)

The plus-side general calibration value registers (CLPx) contain calibration information that is generated by the calibration function. These registers contain seven calibration values of varying widths: CLP0[5:0], CLP1[6:0], CLP2[7:0], CLP3[8:0], CLP4[9:0], CLPS[5:0], and CLPD[5:0]. CLPx are automatically set once the self calibration sequence is done (CAL is cleared). If these registers are written by the user after calibration, the linearity error specifications may not be met.

Addresses: ADC0\_CLPD is 4003\_B000h base + 34h offset = 4003\_B034h ADC1\_CLPD is 400B\_B000h base + 34h offset = 400B\_B034h




### ADCx\_CLPD field descriptions

Field	Description
31–6 Reserved	This read-only field is reserved and always has the value zero.
5–0 CLPD	Calibration value

# 32.3.12 ADC plus-side general calibration value register (ADCx\_CLPS)

For more information, refer to CLPD register description.

Addresses: ADC0\_CLPS is 4003\_B000h base + 38h offset = 4003\_B038h ADC1\_CLPS is 400B\_B000h base + 38h offset = 400B\_B038h




#### ADCx\_CLPS field descriptions

Field	Description
31–6 Reserved	This read-only field is reserved and always has the value zero.
5–0 CLPS	Calibration value

# 32.3.13 ADC plus-side general calibration value register (ADCx\_CLP4)

For more information, refer to CLPD register description.

Addresses: ADC0\_CLP4 is 4003\_B000h base + 3Ch offset = 4003\_B03Ch ADC1\_CLP4 is 400B\_B000h base + 3Ch offset = 400B\_B03Ch



### ADCx\_CLP4 field descriptions


Field	Description
31–10 Reserved	This read-only field is reserved and always has the value zero.
9–0 CLP4	Calibration value



# 32.3.14 ADC plus-side general calibration value register (ADCx\_CLP3)

For more information, refer to CLPD register description.

Addresses: ADC0\_CLP3 is 4003\_B000h base + 40h offset = 4003\_B040h ADC1\_CLP3 is 400B\_B000h base + 40h offset = 400B\_B040h




#### ADCx\_CLP3 field descriptions

Field	Description
31–9 Reserved	This read-only field is reserved and always has the value zero.
8-0 CLP3	Calibration value

# 32.3.15 ADC plus-side general calibration value register (ADCx\_CLP2)

For more information, refer to CLPD register description.

Addresses: ADC0\_CLP2 is 4003\_B000h base + 44h offset = 4003\_B044h ADC1\_CLP2 is 4008\_B000h base + 44h offset = 4008\_B044h




### ADCx\_CLP2 field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7–0 CLP2	Calibration value

# 32.3.16 ADC plus-side general calibration value register (ADCx\_CLP1)

For more information, refer to CLPD register description.

Addresses: ADC0\_CLP1 is 4003\_B000h base + 48h offset = 4003\_B048h ADC1\_CLP1 is 400B\_B000h base + 48h offset = 400B\_B048h




#### ADCx\_CLP1 field descriptions

Field	Description
31–7 Reserved	This read-only field is reserved and always has the value zero.
6–0 CLP1	Calibration value

# 32.3.17 ADC plus-side general calibration value register (ADCx\_CLP0)

For more information, refer to CLPD register description.

Addresses: ADC0\_CLP0 is 4003\_B000h base + 4Ch offset = 4003\_B04Ch
ADC1\_CLP0 is 400B\_B000h base + 4Ch offset = 400B\_B04Ch




### ADCx\_CLP0 field descriptions

Field	Description
31–6 Reserved	This read-only field is reserved and always has the value zero.
5–0 CLP0	Calibration value



## 32.3.18 ADC PGA register (ADCx\_PGA)

Addresses: ADC0\_PGA is 4003\_B000h base + 50h offset = 4003\_B050h ADC1\_PGA is 400B\_B000h base + 50h offset = 400B\_B050h



## ADCx\_PGA field descriptions

Field	Description
31–24 Reserved	This read-only field is reserved and always has the value zero.
23 PGAEN	PGA enable  0 PGA disabled.  1 PGA enabled.
22 Reserved	This read-only field is reserved and always has the value zero.
21 Reserved	This field is reserved.
20 PGALPb	PGA low-power mode control  O PGA runs in low power mode.  1 PGA runs in normal power mode.
19–16 PGAG	PGA gain setting  PGA gain = 2^(PGAG)  0000




#### ADCx\_PGA field descriptions (continued)

Field	Description
	1000 Reserved
	1001 Reserved
	1010 Reserved
	1011 Reserved
	1100 Reserved
	1101 Reserved
	1110 Reserved
	1111 Reserved
15–0 Reserved	This read-only field is reserved and always has the value zero.

# 32.3.19 ADC minus-side general calibration value register (ADCx\_CLMD)

CLMx contain calibration information that is generated by the calibration function. These registers contain seven calibration values of varying widths: CLM0[5:0], CLM1[6:0], CLM2[7:0], CLM3[8:0], CLM4[9:0], CLMS[5:0], and CLMD[5:0]. CLMx are automatically set once the self calibration sequence is done (CAL is cleared). If these registers are written by the user after calibration, the linearity error specifications may not be met.

Addresses: ADC0\_CLMD is 4003\_B000h base + 54h offset = 4003\_B054h ADC1\_CLMD is 400B\_B000h base + 54h offset = 400B\_B054h



#### **ADCx\_CLMD** field descriptions


Field	Description
31–6 Reserved	This read-only field is reserved and always has the value zero.
5–0 CLMD	Calibration value



# 32.3.20 ADC minus-side general calibration value register (ADCx\_CLMS)

For more information, refer to CLMD register description.

Addresses: ADC0\_CLMS is 4003\_B000h base + 58h offset = 4003\_B058h ADC1\_CLMS is 400B\_B000h base + 58h offset = 400B\_B058h




#### ADCx\_CLMS field descriptions

Field	Description
31–6 Reserved	This read-only field is reserved and always has the value zero.
5–0 CLMS	Calibration value

# 32.3.21 ADC minus-side general calibration value register (ADCx\_CLM4)

For more information, refer to CLMD register description.

Addresses: ADC0\_CLM4 is 4003\_B000h base + 5Ch offset = 4003\_B05Ch ADC1\_CLM4 is 400B\_B000h base + 5Ch offset = 400B\_B05Ch




#### ADCx\_CLM4 field descriptions

Field	Description
31–10 Reserved	This read-only field is reserved and always has the value zero.
9–0 CLM4	Calibration value

# 32.3.22 ADC minus-side general calibration value register (ADCx\_CLM3)

For more information, refer to CLMD register description.

Addresses: ADC0\_CLM3 is 4003\_B000h base + 60h offset = 4003\_B060h ADC1\_CLM3 is 400B\_B000h base + 60h offset = 400B\_B060h




#### ADCx\_CLM3 field descriptions

Field	Description
31–9 Reserved	This read-only field is reserved and always has the value zero.
8-0 CLM3	Calibration value

# 32.3.23 ADC minus-side general calibration value register (ADCx\_CLM2)

For more information, refer to CLMD register description.

Addresses: ADC0\_CLM2 is 4003\_B000h base + 64h offset = 4003\_B064h ADC1\_CLM2 is 400B\_B000h base + 64h offset = 400B\_B064h



### ADCx\_CLM2 field descriptions


Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7–0 CLM2	Calibration value



# 32.3.24 ADC minus-side general calibration value register (ADCx\_CLM1)

For more information, refer to CLMD register description.

Addresses: ADC0\_CLM1 is 4003\_B000h base + 68h offset = 4003\_B068h ADC1\_CLM1 is 400B\_B000h base + 68h offset = 400B\_B068h




#### ADCx\_CLM1 field descriptions

Field	Description
31–7 Reserved	This read-only field is reserved and always has the value zero.
6–0 CLM1	Calibration value

# 32.3.25 ADC minus-side general calibration value register (ADCx\_CLM0)

For more information, refer to CLMD register description.

Addresses: ADC0\_CLM0 is 4003\_B000h base + 6Ch offset = 4003\_B06Ch ADC1\_CLM0 is 400B\_B000h base + 6Ch offset = 400B\_B06Ch



### ADCx\_CLM0 field descriptions

Field	Description
31–6 Reserved	This read-only field is reserved and always has the value zero.
5-0 CLM0	Calibration value



## 32.4 Functional description

The ADC module is disabled during reset, in low power stop mode (refer to the Power Management information for details), or when the ADCH bits in SC1n are all high. The module is idle when a conversion has completed and another conversion has not been initiated. When it is idle and the asynchronous clock output enable is disabled (ADACKEN is 0), the module is in its lowest power state. The ADC can perform an analog-to-digital conversion on any of the software selectable channels. All modes perform conversion by a successive approximation algorithm.

To meet accuracy specifications, the ADC module must be calibrated using the on chip calibration function. See Calibration function for details on how to perform calibration.

When the conversion is completed, the result is placed in the data registers (Rn). The respective conversion complete flag (COCO) is then set and an interrupt is generated if the respective conversion complete interrupt has been enabled (AIEN=1).

The ADC module has the capability of automatically comparing the result of a conversion with the contents of the compare value registers. The compare function is enabled by setting the ACFE bit and operates with any of the conversion modes and configurations.

The ADC module has the capability of automatically averaging the result of multiple conversions. The hardware average function is enabled by setting the AVGE bit and operates with any of the conversion modes and configurations.

#### NOTE

For the chip specific modes of operation, refer to the Power Management information of this MCU.

## 32.4.1 PGA functional description

The Programmable Gain Amplifier (PGA) is designed to increase the dynamic range by amplifying low-amplitude signals before they are fed to the 16-bit SAR ADC. The gain of this amplifier is ranged between 1 to 64 in (2^N) steps (1,2,4,8,16,32,64).

This block is designed to work with differential input and output with input signals that range from  $0 - 1.2 \text{ V} \pm 10 \text{ mV}$ . The output common mode of the PGA is determined based on the SAR ADC requirement.



The PGA has only one voltage reference pair. The positive reference used is chip specific and depends on the MCU configuration. Refer to the Chip Configuration chapter on the PGA Voltage Reference specific to this MCU. The ground reference is the analog ground for the PGA.

The ADC PGA register allows to control the PGA gain and modes of operation.

#### 32.4.2 Clock select and divide control

One of four clock sources can be selected as the clock source for the ADC module. This clock source is then divided by a configurable value to generate the input clock to the converter (ADCK). The clock is selected from one of the following sources by means of the ADICLK bits.

- The bus clock. This is the default selection following reset.
- The bus clock divided by two. For higher bus clock rates, this allows a maximum divide by 16 of the bus clock with using the ADIV bits.
- ALTCLK, as defined for this MCU. Refer to the Chip Configuration information.
- The asynchronous clock (ADACK). This clock is generated from a clock source within the ADC module. Note that when the ADACK clock source is selected, it is not required to be active prior to conversion start. When it is selected and it is not active prior to a conversion start (ADACKEN=0), the asynchronous clock is activated at the start of a conversion and shuts off when conversions are terminated. In this case, there is an associated clock startup delay each time the clock source is re-activated. To avoid the conversion time variability and latency associated with the ADACK clock startup, set ADACKEN=1 and wait the worst case startup time of 5 µs prior to initiating any conversions using the ADACK clock source. Conversions are possible using ADACK as the input clock source while the MCU is in Normal Stop mode. Refer to Power Control for more information.

Whichever clock is selected, its frequency must fall within the specified frequency range for ADCK. If the available clocks are too slow, the ADC may not perform according to specifications. If the available clocks are too fast, the clock must be divided to the appropriate frequency. This divider is specified by the ADIV bits and can be divide-by 1, 2, 4, or 8.



runctional description

## 32.4.3 Voltage reference selection

The ADC can be configured to accept one of the two voltage reference pairs as the reference voltage ( $V_{REFSH}$  and  $V_{REFSL}$ ) used for conversions. Each pair contains a positive reference that must be between the minimum Ref Voltage High and  $V_{DDA}$ , and a ground reference that must be at the same potential as  $V_{SSA}$ . The two pairs are external ( $V_{REFH}$  and  $V_{REFL}$ ) and alternate ( $V_{ALTH}$  and  $V_{ALTL}$ ). These voltage references are selected using the REFSEL bits in the SC2 register. The alternate ( $V_{ALTH}$  and  $V_{ALTL}$ ) voltage reference pair may select additional external pins or internal sources depending on MCU configuration. Refer to the Chip Configuration information on the Voltage References specific to this MCU.

## 32.4.4 Hardware trigger and channel selects

The ADC module has a selectable asynchronous hardware conversion trigger, ADHWT, that is enabled when the ADTRG bit is set and a hardware trigger select event (ADHWTSn) has occurred. This source is not available on all MCUs. Refer to the Chip Configuration chapter for information on the ADHWT source and the ADHWTSn configurations specific to this MCU.

When a ADHWT source is available and hardware trigger is enabled (ADTRG=1), a conversion is initiated on the rising edge of ADHWT after a hardware trigger select event (ADHWTSn) has occurred. If a conversion is in progress when a rising edge of a trigger occurs, the rising edge is ignored. In continuous convert configuration, only the initial rising edge to launch continuous conversions is observed, and until conversion gets aborted the ADC continues to do conversions on the same ADC status and control register that initiated the conversion. The hardware trigger function operates in conjunction with any of the conversion modes and configurations.

The hardware trigger select event (ADHWTSn) must be set prior to the receipt of the ADHWT signal. If these conditions are not met, the converter may ignore the trigger or use the incorrect configuration. If a hardware trigger select event gets asserted during a conversion, it must stay asserted until the end of current conversion and remain set until the receipt of the ADHWT signal to trigger a new conversion. The channel and status fields selected for the conversion depend on the active trigger select signal (ADHWTSA active selects SC1A; ADHWTSn active selects SC1n).

#### Note

Asserting more than one hardware trigger select signal (ADHWTSn) at the same time results in unknown results. To avoid this, select only one hardware trigger select signal (ADHWTSn) prior to the next intended conversion.



When the conversion is completed, the result is placed in the data registers associated with the ADHWTSn received (ADHWTSA active selects RA register; ADHWTSn active selects Rn register). The conversion complete flag associated with the ADHWTSn received (the COCO bit in SC1n register) is then set and an interrupt is generated if the respective conversion complete interrupt has been enabled (AIEN=1).

### 32.4.5 Conversion control

Conversions can be performed as determined by the CFG1[MODE] bits and the SC1n[DIFF] bit as shown in the description of CFG1[MODE].

Conversions can be initiated by a software or hardware trigger. In addition, the ADC module can be configured for low power operation, long sample time, continuous conversion, hardware average, and automatic compare of the conversion result to a software determined compare value.

## 32.4.5.1 Initiating conversions

A conversion is initiated:

- Following a write to SC1A register (with ADCH bits not all 1's) if software triggered operation is selected (ADTRG=0).
- Following a hardware trigger (ADHWT) event if hardware triggered operation is selected (ADTRG=1) and a hardware trigger select event (ADHWTSn) has occurred. The channel and status fields selected depend on the active trigger select signal (ADHWTSA active selects SC1A register; ADHWTSn active selects SC1n register; if neither is active, the off condition is selected).

#### **Note**

Selecting more than one hardware trigger select signal (ADHWTSn) prior to a conversion completion will result in unknown results. To avoid this, select only one hardware trigger select signal (ADHWTSn) prior to a conversion completion.

• Following the transfer of the result to the data registers when continuous conversion is enabled (ADCO=1).



#### runctional description

If continuous conversions are enabled, a new conversion is automatically initiated after the completion of the current conversion. In software triggered operation (ADTRG=0), continuous conversions begin after SC1A register is written and continue until aborted. In hardware triggered operation (ADTRG=1 and one ADHWTSn event has occurred), continuous conversions begin after a hardware trigger event and continue until aborted.

If hardware averaging is enabled, a new conversion is automatically initiated after the completion of the current conversion until the correct number of conversions is completed. In software triggered operation, conversions begin after SC1A register is written. In hardware triggered operation, conversions begin after a hardware trigger. If continuous conversions are also enabled, a new set of conversions to be averaged are initiated following the last of the selected number of conversions.

## 32.4.5.2 Completing conversions

A conversion is completed when the result of the conversion is transferred into the data result registers, Rn. If the compare functions are disabled, this is indicated by the setting of the COCO bit in the respective SC1n register. If hardware averaging is enabled, the respective COCO bit sets only if the last of the selected number of conversions is completed. If the compare function is enabled, the respective COCO bit sets and conversion result data is transferred only if the compare condition is true. If both hardware averaging and compare functions are enabled then the respective COCO bit sets only if the last of the selected number of conversions is completed and the compare condition is true. An interrupt is generated if the respective AIEN bit is high at the time that the respective COCO bit is set.

## 32.4.5.3 Aborting conversions

Any conversion in progress is aborted when:

- Writing to SC1A register while it is actively controlling a conversion, aborts the current conversion. In software trigger mode (ADTRG=0), a write to SC1A register initiates a new conversion (if the ADCH field in SC1A is equal to a value other than all 1s). Writing to any of the SC1(B-n) registers while that specific SC1(B-n) register is actively controlling a conversion aborts the current conversion. The SC1(B-n) registers are not used for software trigger operation and therefore writes to the SC1(B-n) registers do not initiate a new conversion.
- A write to any ADC register besides the SC1A:SC1n registers occurs. This indicates a mode of operation change has occurred and the current conversion is therefore invalid.



- The MCU is reset or enters Low Power Stop modes.
- The MCU enters Normal Stop mode with ADACK not enabled.

When a conversion is aborted, the contents of the data registers, Rn, are not altered. The data registers continue to be the values transferred after the completion of the last successful conversion. If the conversion was aborted by a reset or Low Power Stop modes, RA and R n return to their reset states.

#### 32.4.5.4 Power control

The ADC module remains in its idle state until a conversion is initiated. If ADACK is selected as the conversion clock source, but the asynchronous clock output is disabled (ADACKEN=0), the ADACK clock generator also remains in its idle state (disabled) until a conversion is initiated. If the asynchronous clock output is enabled (ADACKEN=1), it remains active regardless of the state of the ADC or the MCU power mode.

Power consumption when the ADC is active can be reduced by setting ADLPC. This results in a lower maximum value for  $f_{ADCK}$ .

## 32.4.5.5 Sample time and total conversion time

For short sample (ADLSMP=0), there is a 2-cycle adder for first conversion over the base sample time of 4 ADCK cycles. For high speed conversions (ADHSC=1), there is an additional 2-cycle adder on any conversion. The table below summarizes sample times for the possible ADC configurations.

ADC Configuration			Sample time (ADCK cycles)		
ADLSMP	ADLSTS	ADHSC	First or Single Subsequent		
0	X	0	6 4		
1	00	0	2	4	
1	01	0	16		
1	10	0	10		
1	11	0	6		
0	X	1	8 6		
1	00	1	26		
1	01	1	18		
1	10	1	12		

Table continues on the next page...



#### runctional description

ADC Configuration		Sample time (ADCK cycles)		
1	11	1	8	

The total conversion time depends upon: the sample time (as determined by ADLSMP and ADLSTS bits), the MCU bus frequency, the conversion mode (as determined by MODE and SC1n[DIFF] bits), the high speed configuration (ADHSC bit), and the frequency of the conversion clock ( $f_{ADCK}$ ).

The ADHSC bit is used to configure a higher clock input frequency. This will allow faster overall conversion times. To meet internal ADC timing requirements, the ADHSC bit adds additional ADCK cycles. Conversions with ADHSC = 1 take two more ADCK cycles. ADHSC should be used when the ADCLK exceeds the limit for ADHSC = 0.

After the module becomes active, sampling of the input begins. ADLSMP and ADLSTS select between sample times based on the conversion mode that is selected. When sampling is completed, the converter is isolated from the input channel and a successive approximation algorithm is performed to determine the digital value of the analog signal. The result of the conversion is transferred to Rn upon completion of the conversion algorithm.

If the bus frequency is less than the  $f_{ADCK}$  frequency, precise sample time for continuous conversions cannot be guaranteed when short sample is enabled (ADLSMP=0).

The maximum total conversion time is determined by the clock source chosen and the divide ratio selected. The clock source is selectable by the ADICLK bits, and the divide ratio is specified by the ADIV bits.

The maximum total conversion time for all configurations is summarized in the equation below. Refer to the following tables for the variables referenced in the equation.

 $Conversion Time = SFCAdder + Average Num \times \big(BCT + LSTAdder + HSCAdder\big)$ 

#### Figure 32-95. Conversion time equation

Table 32-107. Single or first continuous time adder (SFCAdder)

ADLSMP	ADACKE N	ADICLK	Single or first continuous time adder (SFCAdde	
1	х	0x, 10	3 ADCK cycles + 5 bus clock cycles	
1	1	11	3 ADCK cycles + 5 bus clock cycles <sup>1</sup>	
1	0	11	5 μs + 3 ADCK cycles + 5 bus clock cycles	
0	х	0x, 10	5 ADCK cycles + 5 bus clock cycles	
0	1	11	5 ADCK cycles + 5 bus clock cycles <sup>1</sup>	
0	0	11	5 μs + 5 ADCK cycles + 5 bus clock cycles	

<sup>1.</sup> To achieve this time, ADACKEN must be 1 for at least 5 µs prior to the conversion is initiated.



#### Table 32-108. Average number factor (AverageNum)

AVGE	AVGS[1:0]	Average number factor (AverageNum)
0	xx	1
1	00	4
1	01	8
1	10	16
1	11	32

#### Table 32-109. Base Conversion Time (BCT)

Mode	Base conversion time (BCT)
8b s.e.	17 ADCK cycles
9b diff	27 ADCK cycles
10b s.e.	20 ADCK cycles
11b diff	30 ADCK cycles
12b s.e.	20 ADCK cycles
13b diff	30 ADCK cycles
16b s.e.	25 ADCK cycles
16b diff	34 ADCK cycles

#### Table 32-110. Long sample time adder (LSTAdder)

ADLSMP	ADLSTS	Long sample time adder (LSTAdder)
0	xx	0 ADCK cycles
1	00	20 ADCK cycles
1	01	12 ADCK cycles
1	10	6 ADCK cycles
1	11	2 ADCK cycles

#### Table 32-111. High Speed Conversion time Adder (HSCAdder)

ADHSC	High Speed Conversion Time Adder (HSCAdder)	
0	0 ADCK cycles	
1	2 ADCK cycles	

#### **Note**

The ADCK frequency must be between  $f_{ADCK}$  minimum and  $f_{ADCK}$  maximum to meet ADC specifications.



runctional description

## 32.4.5.6 Conversion time examples

The following examples use Figure 32-95 and the information provided in Table 32-107 through Table 32-111.

## 32.4.5.6.1 Typical conversion time configuration

A typical configuration for ADC conversion is: 10-bit mode, with the bus clock selected as the input clock source, the input clock divide-by-1 ratio selected, and a bus frequency of 8 MHz, long sample time disabled and high speed conversion disabled. The conversion time for a single conversion is calculated by using Figure 32-95 and the information provided in Table 32-107 through Table 32-111. The table below list the variables of Figure 32-95.

 Variable
 Time

 SFCAdder
 5 ADCK cycles + 5 bus clock cycles

 AverageNum
 1

 BCT
 20 ADCK cycles

 LSTAdder
 0

 HSCAdder
 0

Table 32-112. Typical conversion time

The resulting conversion time is generated using the parameters listed in the proceeding table. Therefore, for a bus clock equal to 8 MHz and an ADCK equal to 8 MHz the resulting conversion time is 3.75 µs.

## 32.4.5.6.2 Long conversion time configuration

A configuration for long ADC conversion is: 16-bit differential mode with the bus clock selected as the input clock source, the input clock divide-by-8 ratio selected, a bus frequency of 8 MHz, long sample time enabled, configured for longest adder, high speed conversion disabled, and average enabled for 32 conversions. The conversion time for this conversion is calculated by using Figure 32-95 and the information provided in Table 32-107 through Table 32-111. The following table lists the variables of the Figure 32-95.

Table 32-113. Typical conversion time

Variable	Time	
SFCAdder	3 ADCK cycles + 5 bus clock cycles	
AverageNum	rageNum 32	
ВСТ	34 ADCK cycles	
LSTAdder	20 ADCK cycles	

Table continues on the next page...



#### Table 32-113. Typical conversion time (continued)

Variable	Time
HSCAdder	0

The resulting conversion time is generated using the parameters listed in the preceding table. Therefore, for bus clock equal to 8 MHz and ADCK equal to 1 MHz, the resulting conversion time is  $57.625 \,\mu s$  (AverageNum). This results in a total conversion time of  $1.844 \, ms$ .

## 32.4.5.6.3 Short conversion time configuration

A configuration for short ADC conversion is: 8-bit single ended mode with the bus clock selected as the input clock source, the input clock divide-by-1 ratio selected, a bus frequency of 20 MHz, long sample time disabled, and high speed conversion enabled. The conversion time for this conversion is calculated by using Figure 32-95 and the information provided in Table 32-107 through Table 32-111. The table below list the variables of Figure 32-95.

Table 32-114. Typical conversion time

Variable	Time	
SFCAdder	5 ADCK cycles + 5 bus clock cycles	
AverageNum	1	
ВСТ	17 ADCK cycles	
LSTAdder	0 ADCK cycles	
HSCAdder	2	

The resulting conversion time is generated using the parameters listed in in the preceding table. Therefore, for bus clock equal to 20 MHz and ADCK equal to 20 MHz, the resulting conversion time is  $1.45 \mu s$ .

## 32.4.5.7 Hardware average function

The hardware average function can be enabled (AVGE=1) to perform a hardware average of multiple conversions. The number of conversions is determined by the AVGS[1:0] bits, which select 4, 8, 16, or 32 conversions to be averaged. While the hardware average function is in progress, the ADACT bit will be set.



#### runctional description

After the selected input is sampled and converted, the result is placed in an accumulator from which an average is calculated once the selected number of conversions has been completed. When hardware averaging is selected, the completion of a single conversion will not set the COCO bit.

If the compare function is either disabled or evaluates true, after the selected number of conversions are completed, the average conversion result is transferred into the data result registers, Rn, and the COCO bit is set. An ADC interrupt is generated upon the setting of COCO if the respective ADC interrupt is enabled (AIEN=1).

#### **Note**

The hardware average function can perform conversions on a channel while the MCU is in Wait or Normal Stop modes. The ADC interrupt wakes the MCU when the hardware average is completed if SC1n[AIEN] bit was set.

# 32.4.6 Automatic compare function

The compare function can be configured to check if the result is less than or greater-than-or-equal-to a single compare value, or if the result falls within or outside a range determined by two compare values. The compare mode is determined by ACFGT, ACREN, and the values in the compare value registers (CV1 and CV2). After the input is sampled and converted, the compare values (CV1 and CV2) are used as described in the following table. There are six compare modes as shown in the following table.

Table 32-115. Compare modes

ACFGT	ACREN	ADCCV1 relative to ADCCV2	Function	Compare mode description
0	0	_	Less than threshold	Compare true if the result is less than the CV1 registers.
1	0	_	Greater than or equal to threshold	Compare true if the result is greater than or equal to CV1 registers.
0	1	Less than or equal	Outside range, not inclusive	Compare true if the result is less than CV1  Or the result is greater than CV2.
0	1	Greater than	Inside range, not inclusive	Compare true if the result is less than CV1 <b>And</b> the result is greater than CV2.
1	1	Less than or equal	Inside range, inclusive	Compare true if the result is greater than or equal to CV1 <b>And</b> the result is less than or equal to CV2.
1	1	Greater than	Outside range, inclusive	Compare true if the result is greater than or equal to CV1 <b>Or</b> the result is less than or equal to CV2.



With the ADC range enable bit set, ACREN =1, and if compare value register 1 (CV1 value) is less than or equal to the compare value register 2 (CV2 value), then setting ACFGT will select a trigger-if-inside-compare-range inclusive-of-endpoints function. Clearing ACFGT will select a trigger-if-outside-compare-range, not-inclusive-of-endpoints function.

If CV1 is greater than CV2, setting ACFGT will select a trigger-if-outside-comparerange, inclusive-of-endpoints function. Clearing ACFGT will select a trigger-if-insidecompare-range, not-inclusive-of-endpoints function.

If the condition selected evaluates true, COCO is set.

Upon completion of a conversion while the compare function is enabled, if the compare condition is not true, COCO is not set and the conversion result data will not be transferred to the result register. If the hardware averaging function is enabled, the compare function compares the averaged result to the compare values. The same compare function definitions apply. An ADC interrupt is generated upon the setting of COCO if the respective ADC interrupt is enabled (AIEN=1).

#### **Note**

The compare function can monitor the voltage on a channel while the MCU is in Wait or Normal Stop modes. The ADC interrupt wakes the MCU when the compare condition is met.

## 32.4.7 Calibration function

The ADC contains a self-calibration function that is required to achieve the specified accuracy. Calibration must be run, or valid calibration values written, after any reset and before a conversion is initiated. The calibration function sets the offset calibration value, the minus-side calibration values, and the plus-side calibration values. The offset calibration value is automatically stored in the ADC offset correction register (OFS), and the plus-side and minus-side calibration values are automatically stored in the ADC plus-side and minus-side calibration (CLPx and CLMx) registers. The user must configure the ADC correctly prior to calibration, and must generate the plus-side and minus-side gain calibration results and store them in the ADC plus-side gain register (PG) after the calibration function completes.

Prior to calibration, the user must configure the ADC's clock source and frequency, low power configuration, voltage reference selection, sample time, and high speed configuration according to the application's clock source availability and needs. If the application uses the ADC in a wide variety of configurations, the configuration for which the highest accuracy is required should be selected, or multiple calibrations can be done



#### runctional description

for the different configurations. For best calibration results, it is recommended to set hardware averaging to maximum (AVGE=1, AVGS=11 for average of 32), ADC clock frequency  $f_{ADCK}$  less than or equal to 4 MHz,  $V_{REFH}$ = $V_{DDA}$ , and to calibrate at nominal voltage and temperature. The input channel, conversion mode continuous function, compare function, resolution mode, and differential/single-ended mode are all ignored during the calibration function.

To initiate calibration, the user sets the CAL bit and the calibration will automatically begin if the ADTRG bit is 0. If ADTRG is 1, the CAL bit will not get set and the calibration fail flag (CALF) will be set. While calibration is active, no ADC register can be written and no stop mode may be entered, or the calibration routine will be aborted causing the CAL bit to clear and the CALF bit to set. At the end of a calibration sequence, the COCO bit of the SC1A register will be set. The AIEN bit can be used to allow an interrupt to occur at the end of a calibration sequence. At the end of the calibration routine, if the CALF bit is not set, the automatic calibration routine completed successfully.

To complete calibration, the user must generate the gain calibration values using the following procedure:

- 1. Initialize (clear) a 16-bit variable in RAM.
- 2. Add the plus-side calibration results CLP0, CLP1, CLP2, CLP3, CLP4, and CLPS to the variable.
- 3. Divide the variable by two.
- 4. Set the MSB of the variable.
- 5. The previous two steps can be achieved by setting the carry bit, rotating to the right through the carry bit on the high byte and again on the low byte.
- 6. Store the value in the plus-side gain calibration register (PG).
- 7. Repeat the procedure for the minus-side gain calibration value.

When calibration is complete, the user may reconfigure and use the ADC as desired. A second calibration may also be performed if desired by clearing and again setting the CAL bit.

Overall, the calibration routine may take as many as 14k ADCK cycles and 100 bus cycles, depending on the results and the clock source chosen. For an 8 MHz clock source, this length amounts to about 1.7 ms. To reduce this latency, the calibration values (offset, plus-side and minus-side gain, and plus-side and minus-side calibration values) may be



stored in flash memory after an initial calibration and recovered prior to the first ADC conversion. This method should reduce the calibration latency to 20 register store operations on all subsequent power, reset, or Low Power Stop mode recoveries.

#### 32.4.8 User defined offset function

The ADC offset correction register (OFS) contains the user selected or calibration generated offset error correction value. This register is a 2's complement, left justified. The value in the offset correction register (OFS) is subtracted from the conversion and the result is transferred into the result registers (Rn). If the result is above the maximum or below the minimum result value, it is forced to the appropriate limit for the current mode of operation.

The formatting of the ADC offset correction register is different from the data result register (Rn) to preserve the resolution of the calibration value regardless of the conversion mode selected. Lower order bits are ignored in lower resolution modes. For example, in 8-bit single-ended mode, the bits OFS[14:7] are subtracted from D[7:0]; bit OFS[15] indicates the sign (negative numbers are effectively added to the result) and bits OFS[6:0] are ignored. The same bits are used in 9-bit differential mode since bit OFS[15] indicates the sign bit, which maps to bit D[8]. For 16-bit differential mode, all bits OFS[15:0] are directly subtracted from the conversion result data D[15:0]. In 16-bit single-ended mode, there is no bit in the offset correction register corresponding to the least significant result bit D[0], so odd values (-1 or +1, and so on) cannot be subtracted from the result.

OFS is automatically set according to calibration requirements once the self calibration sequence is done (CAL is cleared). The user may write to OFS to override the calibration result if desired. If the offset correction register is written by the user to a value that is different from the calibration value, the ADC error specifications may not be met. It is recommended that the value generated by the calibration function be stored in memory before overwriting with a user specified value.

#### **Note**

There is an effective limit to the values of offset that can be set by the user. If the magnitude of the offset is too great, the results of the conversions will cap off at the limits.

The offset calibration function may be employed by the user to remove application offsets or DC bias values. The offset correction register, OFS may be written with a number in 2's complement format and this offset will be subtracted from the result (or hardware averaged value). To add an offset, store the negative offset in 2's complement



#### runctional description

format and the effect will be an addition. An offset correction that results in an out-of-range value will be forced to the minimum or maximum value (the minimum value for single-ended conversions is 0x0000; for a differential conversion it is 0x8000).

To preserve accuracy, the calibrated offset value initially stored in the OFS register must be added to the user defined offset. For applications that may change the offset repeatedly during operation, it is recommended to store the initial offset calibration value in flash so it can be recovered and added to any user offset adjustment value and the sum stored in the OFS register.

## 32.4.9 Temperature sensor

The ADC module includes a temperature sensor whose output is connected to one of the ADC analog channel inputs. The following equation provides an approximate transfer function of the temperature sensor.

Temp = 
$$25 - ((V_{TEMP} - V_{TEMP25}) \div m)$$

Figure 32-96. Approximate transfer function of the temperature sensor

#### where:

- ullet  $V_{TEMP}$  is the voltage of the temperature sensor channel at the ambient temperature.
- $V_{TEMP25}$  is the voltage of the temperature sensor channel at 25 °C.
- m is the hot or cold voltage versus temperature slope in V/°C.

For temperature calculations, use the  $V_{TEMP25}$  and m values from the ADC Electricals table.

In application code, the user reads the temperature sensor channel, calculates  $V_{TEMP}$ , and compares to  $V_{TEMP25}$ . If  $V_{TEMP}$  is greater than  $V_{TEMP25}$  the cold slope value is applied in the preceding equation. If  $V_{TEMP}$  is less than  $V_{TEMP25}$ , the hot slope value is applied in the preceding equation.

For more information on using the temperature sensor, see the application note titled *Temperature Sensor for the HCS08 Microcontroller Family* (document AN3031).



## 32.4.10 MCU wait mode operation

Wait mode is a lower power-consumption standby mode from which recovery is fast because the clock sources remain active. If a conversion is in progress when the MCU enters Wait mode, it continues until completion. Conversions can be initiated while the MCU is in Wait mode by means of the hardware trigger or if continuous conversions are enabled.

The bus clock, bus clock divided by two, and ADACK are available as conversion clock sources while in Wait mode. The use of ALTCLK as the conversion clock source in Wait is dependent on the definition of ALTCLK for this MCU. Refer to the Chip Configuration information on ALTCLK specific to this MCU.

If the compare and hardware averaging functions are disabled, a conversion complete event sets the COCO and generates an ADC interrupt to wake the MCU from Wait mode if the respective ADC interrupt is enabled (AIEN=1). If the hardware averaging function is enabled, the COCO will set (and generate an interrupt if enabled) when the selected number of conversions are completed. If the compare function is enabled, the COCO will set (and generate an interrupt if enabled) only if the compare conditions are met. If a single conversion is selected and the compare trigger is not met, the ADC will return to its idle state and cannot wake the MCU from Wait mode unless a new conversion is initiated by the hardware trigger.

## 32.4.11 MCU Normal Stop mode operation

Stop mode is a low power-consumption standby mode during which most or all clock sources on the MCU are disabled.

## 32.4.11.1 Normal Stop mode with ADACK disabled

If the asynchronous clock, ADACK, is not selected as the conversion clock, executing a stop instruction aborts the current conversion and places the ADC in its idle state. The contents of the ADC registers, including Rn, are unaffected by Normal Stop mode. After exiting from Normal Stop mode, a software or hardware trigger is required to resume conversions.



**mualization information** 

## 32.4.11.2 Normal Stop mode with ADACK enabled

If ADACK is selected as the conversion clock, the ADC continues operation during Normal Stop mode. Refer to the Chip Configuration chapter for configuration information for this MCU.

If a conversion is in progress when the MCU enters Normal Stop mode, it continues until completion. Conversions can be initiated while the MCU is in Normal Stop mode by means of the hardware trigger or if continuous conversions are enabled.

If the compare and hardware averaging functions are disabled, a conversion complete event sets the COCO and generates an ADC interrupt to wake the MCU from Normal Stop mode if the respective ADC interrupt is enabled (AIEN = 1). The result register will contain the data from the first completed conversion that occurred during Normal Stop mode. If the hardware averaging function is enabled, the COCO will set (and generate an interrupt if enabled) when the selected number of conversions are completed. If the compare function is enabled, the COCO will set (and generate an interrupt if enabled) only if the compare conditions are met. If a single conversion is selected and the compare is not true, the ADC will return to its idle state and cannot wake the MCU from Normal Stop mode unless a new conversion is initiated by another hardware trigger.

## 32.4.12 MCU Low Power Stop mode operation

The ADC module is automatically disabled when the MCU enters Low Power Stop mode. All module registers contain their reset values following exit from Low Power Stop mode. Therefore, the module must be re-enabled and re-configured following exit from Low Power Stop mode.

#### NOTE

For the chip specific modes of operation, refer to the Power Management information for the device.

## 32.5 Initialization information

This section gives an example that provides some basic direction on how to initialize and configure the ADC module. You can configure the module for 16-bit, 12-bit, 10-bit, or 8-bit single-ended resolution or 16-bit, 13-bit, 11-bit, or 9-bit differential resolution, single or continuous conversion, and a polled or interrupt approach, among many other options. Refer to Table 32-110, Table 32-111, and Table 32-112 for information used in this example.



#### **Note**

Hexadecimal values are designated by a preceding 0x, binary values designated by a preceding %, and decimal values have no preceding character.

# 32.5.1 ADC module initialization example

This section provides details about the ADC module initialization.

## 32.5.1.1 Initialization sequence

Before the ADC module can be used to complete conversions, an initialization procedure must be performed. A typical sequence is as follows:

- 1. Calibrate the ADC by following the calibration instructions in Calibration function.
- 2. Update the configuration register (CFG) to select the input clock source and the divide ratio used to generate the internal clock, ADCK. This register is also used for selecting sample time and low-power configuration.
- 3. Update status and control register 2 (SC2) to select the conversion trigger (hardware or software) and compare function options, if enabled.
- 4. Update status and control register 3 (SC3) to select whether conversions will be continuous or completed only once (ADCO) and to select whether to perform hardware averaging.
- 5. Update the status and control register (SC1:SC1n) to select whether conversions will be single-ended or differential and to enable or disable conversion complete interrupts. Also, select the input channel on which to perform conversions.
- 6. Update PGA register (PGA) to enable or disable PGA and configure appropriate gain. This register is also used for selecting power mode and whether the module is chopper stabilized.

## 32.5.1.2 Pseudo-code example

In this example, the ADC module is set up with interrupts enabled to perform a single 10-bit conversion at low power with a long sample time on input channel 1, where the internal ADCK clock is derived from the bus clock divided by 1.



#### unualization information

#### CFG1 = 0x98 (%10011000)

```
Bit 7
               ADLPC
                               Configures for low power (lowers maximum clock speed.
        Bit 6:5 ADIV
                               Sets the ADCK to the input clock \div 1.
                        00
        Bit 4 ADLSMP
                       1
                               Configures for long sample time.
        Bit 3:2
                               Selects the single-ended 10-bit conversion, differential 11-
                 MODE
                        10
bit conversion.
        Bit 1:0
                  ADICLK
                         0.0
                                 Selects the bus clock.
```

#### SC2 = 0x00 (%00000000)

```
Bit 7
                ADACT
                                  Flag indicates if a conversion is in progress.
        Bit 6
                ADTRG
                         0
                                  Software trigger selected.
        Bit 5
                ACFE
                                  Compare function disabled.
                ACFGT
                                 Not used in this example.
        Bit 4
                         0
                                 Compare range disabled.
        Bit 3
                ACREN
                         0
                DMAEN
                                 DMA request disabled.
                                 Selects default voltage reference pin pair (External pins V_{\text{REFH}}
        Bit 1:0 REFSEL 00
and V_{REFL}).
```

#### SC1A = 0x41 (%01000001)

```
Bit 7 COCO 0 Read-only flag which is set when a conversion completes. Bit 6 AIEN 1 Conversion complete interrupt enabled. Bit 5 DIFF 0 Single-ended conversion selected. Bit 4:0 ADCH 00001 Input channel 1 selected as ADC input channel.
```

#### RA = 0xxx

Holds results of conversion.

#### CV = 0xxx

Holds compare value when compare function enabled.






Figure 32-97. Initialization Flowchart for Example

# 32.6 Application information

This section contains information for using the ADC module in applications. The ADC has been designed to be integrated into a microcontroller for use in embedded control applications requiring an ADC.

## 32.6.1 External pins and routing

The following sections discuss the external pins associated with the ADC module and how they should be used for best results.

## 32.6.1.1 Analog supply pins

The ADC module has analog power and ground supplies ( $V_{DDA}$  and  $V_{SSA}$ ) available as separate pins on some devices.  $V_{SSA}$  is shared on the same pin as the MCU digital VSS on some devices. On other devices,  $V_{SSA}$  and  $V_{DDA}$  are shared with the MCU digital



#### Application information

supply pins. In these cases, there are separate pads for the analog supplies bonded to the same pin as the corresponding digital supply so that some degree of isolation between the supplies is maintained.

When available on a separate pin, both  $V_{DDA}$  and  $V_{SSA}$  must be connected to the same voltage potential as their corresponding MCU digital supply ( $V_{DD}$  and  $V_{SS}$ ) and must be routed carefully for maximum noise immunity and bypass capacitors placed as near as possible to the package.

If separate power supplies are used for analog and digital power, the ground connection between these supplies must be at the  $V_{SSA}$  pin. This should be the only ground connection between these supplies if possible. The  $V_{SSA}$  pin makes a good single point ground location.

## 32.6.1.2 Analog voltage reference pins

In addition to the analog supplies, the ADC module has connections for two reference voltage inputs used by the converter,  $V_{REFSH}$  and  $V_{REFSL}$ .  $V_{REFSH}$  is the high reference voltage for the converter.  $V_{REFSL}$  is the low reference voltage for the converter.

The ADC can be configured to accept one of two voltage reference pairs for  $V_{REFSH}$  and  $V_{REFSL}$ . Each pair contains a positive reference and a ground reference. The two pairs are external ( $V_{REFH}$  and  $V_{REFL}$ ) and alternate ( $V_{ALTH}$  and  $V_{ALTL}$ ). These voltage references are selected using the REFSEL bits in the SC2 register. The alternate ( $V_{ALTH}$  and  $V_{ALTL}$ ) voltage reference pair may select additional external pins or internal sources depending on MCU configuration. Refer to the Chip Configuration information on the Voltage References specific to this MCU.

In some packages, the external or alternate pairs are connected in the package to  $V_{DDA}$  and  $V_{SSA}$ , respectively. One of these positive references may be shared on the same pin as  $V_{DDA}$  on some devices. One of these ground references may be shared on the same pin as  $V_{SSA}$  on some devices.

If externally available, the positive reference may be connected to the same potential as  $V_{DDA}$  or may be driven by an external source to a level between the minimum Ref Voltage High and the  $V_{DDA}$  potential (the positive reference must never exceed  $V_{DDA}$ ). If externally available, the ground reference must be connected to the same voltage potential as  $V_{SSA}$ . The voltage reference pairs must be routed carefully for maximum noise immunity and bypass capacitors placed as near as possible to the package.

AC current in the form of current spikes required to supply charge to the capacitor array at each successive approximation step is drawn through the  $V_{REFH}$  and  $V_{REFL}$  loop. The best external component to meet this current demand is a 0.1  $\mu$ F capacitor with good high



frequency characteristics. This capacitor is connected between  $V_{REFH}$  and  $V_{REFL}$  and must be placed as near as possible to the package pins. Resistance in the path is not recommended because the current causes a voltage drop that could result in conversion errors. Inductance in this path must be minimum (parasitic only).

## 32.6.1.3 Analog input pins

The external analog inputs are typically shared with digital I/O pins on MCU devices.

Empirical data shows that capacitors on the analog inputs improve performance in the presence of noise or when the source impedance is high. Use of 0.01  $\mu$ F capacitors with good high-frequency characteristics is sufficient. These capacitors are not necessary in all cases, but when used they must be placed as near as possible to the package pins and be referenced to  $V_{SSA}$ .

For proper conversion, the input voltage must fall between  $V_{REFH}$  and  $V_{REFL}$ . If the input is equal to or exceeds  $V_{REFH}$ , the converter circuit converts the signal to 0xFFF (full scale 12-bit representation), 0x3FF (full scale 10-bit representation) or 0xFF (full scale 8-bit representation). If the input is equal to or less than  $V_{REFL}$ , the converter circuit converts it to 0x000. Input voltages between  $V_{REFH}$  and  $V_{REFL}$  are straight-line linear conversions. There is a brief current associated with  $V_{REFL}$  when the sampling capacitor is charging.

For minimal loss of accuracy due to current injection, pins adjacent to the analog input pins should not be transitioning during conversions.

## 32.6.2 Sources of error

Several sources of error exist for A/D conversions. These are discussed in the following sections.

## 32.6.2.1 Sampling error

For proper conversions, the input must be sampled long enough to achieve the proper accuracy.

RAS + RADIN =SC / (FMAX \* NUMTAU \* CADIN)

Figure 32-98. Sampling equation

Where:

RAS = External analog source resistance



#### **Application information**

SC = Number of ADCK cycles used during sample window

CADIN = Internal ADC input capacitance

 $NUMTAU = -ln(LSBERR / 2^{N})$ 

LSBERR = value of acceptable sampling error in LSBs

N = 8 in 8-bit mode, 10 in 10-bit mode, 12 in 12-bit mode or 16 in 16-bit mode

Higher source resistances or higher-accuracy sampling is possible by setting ADLSMP and changing the ADLSTS bits (to increase the sample window) or decreasing ADCK frequency to increase sample time.

## 32.6.2.2 Pin leakage error

Leakage on the I/O pins can cause conversion error if the external analog source resistance ( $R_{AS}$ ) is high. If this error cannot be tolerated by the application, keep  $R_{AS}$  lower than  $V_{REFH}$  / ( $4 \times I_{LEAK} \times 2^N$ ) for less than 1/4 LSB leakage error (N = 8 in 8-bit mode, 10 in 10-bit mode, 12 in 12-bit mode, or 16 in 16-bit mode).

#### 32.6.2.3 Noise-induced errors

System noise that occurs during the sample or conversion process can affect the accuracy of the conversion. The ADC accuracy numbers are guaranteed as specified only if the following conditions are met:

- There is a 0.1  $\mu F$  low-ESR capacitor from  $V_{REFH}$  to  $V_{REFL}$ .
- There is a 0.1  $\mu$ F low-ESR capacitor from  $V_{DDA}$  to  $V_{SSA}$ .
- If inductive isolation is used from the primary supply, an additional 1  $\mu F$  capacitor is placed from  $V_{DDA}$  to  $V_{SSA}$ .
- V<sub>SSA</sub> (and V<sub>REFL</sub>, if connected) is connected to V<sub>SS</sub> at a quiet point in the ground plane.
- Operate the MCU in Wait or Normal Stop mode before initiating (hardware triggered conversions) or immediately after initiating (hardware or software triggered conversions) the ADC conversion.



- For software triggered conversions, immediately follow the write to the SC1 register with a wait instruction or stop instruction.
- For Normal Stop mode operation, select ADACK as the clock source. Operation
  in Normal Stop reduces V<sub>DD</sub> noise but increases effective conversion time due to
  stop recovery.
- There is no I/O switching, input or output, on the MCU during the conversion.

There are some situations where external system activity causes radiated or conducted noise emissions or excessive  $V_{DD}$  noise is coupled into the ADC. In these situations, or when the MCU cannot be placed in Wait or Normal Stop or I/O activity cannot be halted, these recommended actions may reduce the effect of noise on the accuracy:

- Place a 0.01 µF capacitor (C<sub>AS</sub>) on the selected input channel to V<sub>REFL</sub> or V<sub>SSA</sub> (this improves noise issues, but affects the sample rate based on the external analog source resistance).
- Average the result by converting the analog input many times in succession and dividing the sum of the results. Four samples are required to eliminate the effect of a 1 LSB, one-time error.
- Reduce the effect of synchronous noise by operating off the asynchronous clock (ADACK) and averaging. Noise that is synchronous to ADCK cannot be averaged out.

## 32.6.2.4 Code width and quantization error

The ADC quantizes the ideal straight-line transfer function into 65536 steps (in 16-bit mode). Each step ideally has the same height (1 code) and width. The width is defined as the delta between the transition points to one code and the next. The ideal code width for an N bit converter (in this case N can be 16, 12, 10, or 8), defined as 1 LSB, is:

$$1LSB = (V_{REFH})/2^N$$

## Figure 32-99. Ideal code width for an N bit converter

There is an inherent quantization error due to the digitization of the result. For 8-bit, 10-bit, or 12-bit conversions, the code transitions when the voltage is at the midpoint between the points where the straight line transfer function is exactly represented by the actual transfer function. Therefore, the quantization error will be  $\pm$  1/2 LSB in 8-bit, 10-bit, or 12-bit modes. As a consequence, however, the code width of the first (0x000) conversion is only 1/2 LSB and the code width of the last (0xFF or 0x3FF) is 1.5 LSB.



#### **Application information**

For 16-bit conversions, the code transitions only after the full code width is present, so the quantization error is -1 LSB to 0 LSB and the code width of each step is 1 LSB.

## 32.6.2.5 Linearity errors

The ADC may also exhibit non-linearity of several forms. Every effort has been made to reduce these errors, but the system designers should be aware of them because they affect overall accuracy. These errors are:

- Zero-scale error (E<sub>ZS</sub>) (sometimes called offset): This error is defined as the difference between the actual code width of the first conversion and the ideal code width (1/2 LSB in 8-bit, 10-bit, or 12-bit modes and 1 LSB in 16-bit mode). If the first conversion is 0x001, the difference between the actual 0x001 code width and its ideal (1 LSB) is used.
- Full-scale error (E<sub>FS</sub>): This error is defined as the difference between the actual code width of the last conversion and the ideal code width (1.5 LSB in 8-bit, 10-bit, or 12-bit modes and 1 LSB in 16-bit mode). If the last conversion is 0x3FE, the difference between the actual 0x3FE code width and its ideal (1 LSB) is used.
- Differential non-linearity (DNL): This error is defined as the worst-case difference between the actual code width and the ideal code width for all conversions.
- Integral non-linearity (INL): This error is defined as the highest-value the (absolute value of the) running sum of DNL achieves. More simply, this is the worst-case difference of the actual transition voltage to a given code and its corresponding ideal transition voltage, for all codes.
- Total unadjusted error (TUE): This error is defined as the difference between the actual transfer function and the ideal straight-line transfer function and includes all forms of error.

# 32.6.2.6 Code jitter, non-monotonicity, and missing codes

Analog-to-digital converters are susceptible to three special forms of error. These are code jitter, non-monotonicity, and missing codes.

Code jitter is when, at certain points, a given input voltage converts to one of two values when sampled repeatedly. Ideally, when the input voltage is infinitesimally smaller than the transition voltage, the converter yields the lower code (and vice-versa). However, even small amounts of system noise can cause the converter to be indeterminate (between two codes) for a range of input voltages around the transition voltage.





This error may be reduced by repeatedly sampling the input and averaging the result. Additionally, the techniques discussed in Noise-induced errors reduces this error.

Non-monotonicity is defined as when, except for code jitter, the converter converts to a lower code for a higher input voltage. Missing codes are those values never converted for any input value.

In 8-bit or 10-bit mode, the ADC is guaranteed to be monotonic and have no missing codes.



Application information



# **Chapter 33 Comparator (CMP)**

#### 33.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The Comparator module (CMP) provides a circuit for comparing two analog input voltages. The comparator circuit is designed to operate across the full range of the supply voltage (rail to rail operation).

The Analog MUX (ANMUX) provides a circuit for selecting an analog input signal from eight channels. One signal provided by the 6-bit DAC. The mux circuit is designed to operate across the full range of the supply voltage.

The 6-bit DAC is 64-tap resistor ladder network which provides a selectable voltage reference for applications where voltage reference is needed. The 64-tap resistor ladder network divides the supply reference Vin into 64 voltage level. A 6-bit digital signal input selects output voltage level, which varies from Vin to Vin/64. Vin can be selected from two voltage sources,  $V_{in1}$  and  $V_{in2}$ . The 6-bit DAC from a comparator is available as an on-chip internal signal only and is not available externally to a pin.

## 33.2 CMP Features

The CMP has the following features:

- Operates over the entire supply range
- Inputs may range from rail to rail
- Programmable hysteresis control



#### ง-มน DAC Key Features

- Selectable interrupt on rising edge, falling edge, or both rising or falling edges of comparator output
- Selectable inversion on comparator output
- Comparator output may be:
  - Sampled
  - Windowed (ideal for certain PWM zero-crossing-detection applications)
  - Digitally Filtered
    - Filter can be bypassed
    - Can be clocked via external SAMPLE signal or scaled bus clock
- External hysteresis can be used at the same time that the output filter is used for internal functions.
- Two software selectable performance levels:
  - Shorter propagation delay at the expense of higher power
  - Low power, with longer propagation delay
- Support DMA transfer
  - A comparison event can be selected to trigger a DMA transfer.
- Functional in all modes of operation.
- The window and filter functions are not available in Stop, VLPS, LLS and VLLSx modes.

# 33.3 6-bit DAC Key Features

- 6-bit resolution
- Selectable supply reference source
- Power down mode to conserve power when it is not being used
- Output can be routed to internal comparator input



# 33.4 ANMUX Key Features

- Two 8 to 1 channel mux
- Operates the entire supply range

# 33.5 CMP, DAC, and ANMUX Diagram

The following figure shows the block diagram for the High Speed Comparator, Digital to Analog Converter, and Analog MUX modules.

#### **└พ** Block Diagram




Figure 33-1. CMP, DAC and ANMUX Blocks Diagram

# 33.6 CMP Block Diagram

The following figure shows the block diagram for the Comparator module.






Figure 33-2. Comparator Module Block Diagram

#### In the CMP block diagram:

- The Window Control block is bypassed when CR1[WE] = 0
- If CR1[WE] = 1, the comparator output will be sampled on every bus clock when WINDOW=1 to generate COUTA. Sampling does NOT occur when WINDOW = 0.
- The Filter Block is bypassed when not in use.
- The Filter Block acts as a simple sampler if the filter is bypassed and CR0[FILTER\_CNT] is set to 0x01.
- The Filter Block filters based on multiple samples when the filter is bypassed and CR0[FILTER\_CNT] is set greater than 0x01.
  - If CR1[SE] = 1, the external SAMPLE input is used as sampling clock
  - IF CR1[SE] = 0, the divided bus clock is used as sampling clock



#### wemory Map/Register Definitions

- If enabled, the Filter Block will incur up to 1 bus clock additional latency penalty on COUT due to the fact that COUT (which is crossing clock domain boundaries) must be resynchronized to the bus clock.
- CR1[WE] and CR1[SE] are mutually exclusive.

# 33.7 Memory Map/Register Definitions

#### **CMP** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4007_3000	CMP Control Register 0 (CMP0_CR0)	8	R/W	00h	33.7.1/ 785
4007_3001	CMP Control Register 1 (CMP0_CR1)	8	R/W	00h	33.7.2/ 786
4007_3002	CMP Filter Period Register (CMP0_FPR)	8	R/W	00h	33.7.3/ 787
4007_3003	CMP Status and Control Register (CMP0_SCR)	8	R/W	00h	33.7.4/ 788
4007_3004	DAC Control Register (CMP0_DACCR)	8	R/W	00h	33.7.5/ 789
4007_3005	MUX Control Register (CMP0_MUXCR)	8	R/W	00h	33.7.6/ 790
4007_3008	CMP Control Register 0 (CMP1_CR0)	8	R/W	00h	33.7.1/ 785
4007_3009	CMP Control Register 1 (CMP1_CR1)	8	R/W	00h	33.7.2/ 786
4007_300A	CMP Filter Period Register (CMP1_FPR)	8	R/W	00h	33.7.3/ 787
4007_300B	CMP Status and Control Register (CMP1_SCR)	8	R/W	00h	33.7.4/ 788
4007_300C	DAC Control Register (CMP1_DACCR)	8	R/W	00h	33.7.5/ 789
4007_300D	MUX Control Register (CMP1_MUXCR)	8	R/W	00h	33.7.6/ 790
4007_3010	CMP Control Register 0 (CMP2_CR0)	8	R/W	00h	33.7.1/ 785
4007_3011	CMP Control Register 1 (CMP2_CR1)	8	R/W	00h	33.7.2/ 786

Table continues on the next page...




## **CMP** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4007_3012	CMP Filter Period Register (CMP2_FPR)	8	R/W	00h	33.7.3/ 787
4007_3013	CMP Status and Control Register (CMP2_SCR)	8	R/W	00h	33.7.4/ 788
4007_3014	DAC Control Register (CMP2_DACCR)	8	R/W	00h	33.7.5/ 789
4007_3015	MUX Control Register (CMP2_MUXCR)	8	R/W	00h	33.7.6/ 790

# 33.7.1 CMP Control Register 0 (CMPx\_CR0)

Addresses: CMP0\_CR0 is 4007\_3000h base + 0h offset = 4007\_3000h CMP1\_CR0 is 4007\_3008h base + 0h offset = 4007\_3008h CMP2\_CR0 is 4007\_3010h base + 0h offset = 4007\_3010h



#### CMPx\_CR0 field descriptions

Field	Description
7 Reserved	This read-only field is reserved and always has the value zero.
6–4 FILTER_CNT	Filter Sample Count  These bits represent the number of consecutive samples that must agree prior to the comparator ouput filter accepting a new output state. For information regarding filter programming and latency reference the Functional Description.  000 Filter is disabled. If SE = 1, then COUT is a logic zero (this is not a legal state, and is not recommended). If SE = 0, COUT = COUTA.  001 1 consecutive sample must agree (comparator output is simply sampled).  010 2 consecutive samples must agree.  011 3 consecutive samples must agree.  100 4 consecutive samples must agree.  101 5 consecutive samples must agree.  101 6 consecutive samples must agree.  110 6 consecutive samples must agree.  111 7 consecutive samples must agree.
3 Reserved	This read-only field is reserved and always has the value zero.

Table continues on the next page...



#### wemory Map/Register Definitions


#### CMPx\_CR0 field descriptions (continued)

Field	Description
2 Reserved	This read-only field is reserved and always has the value zero.
1-0 HYSTCTR	Comparator hard block hysteresis control  Defines the programmable hysteresis level. The hysteresis values associated with each level is device-specific. See the device's data sheet for the exact values.  00 Level 0 01 Level 1 10 Level 2 11 Level 3

# 33.7.2 CMP Control Register 1 (CMPx\_CR1)

Addresses: CMP0\_CR1 is 4007\_3000h base + 1h offset = 4007\_3001h CMP1\_CR1 is 4007\_3008h base + 1h offset = 4007\_3009h

CMP2\_CR1 is 4007\_3010h base + 1h offset = 4007\_3011h



#### CMPx\_CR1 field descriptions

Field	Description
7 SE	Sample Enable  At any given time, either SE or WE can be set. If a write to this register attempts to set both, then SE is set and WE is cleared. However, avoid writing ones to both bit locations because this "11" case is reserved and may change in future implementations.  O Sampling mode not selected.  Sampling mode selected.
6 WE	Windowing Enable  At any given time, either SE or WE can be set. If a write to this register attempts to set both, then SE is set and WE is cleared. However, avoid writing ones to both bit locations because this "11" case is reserved and may change in future implementations.  0 Windowing mode not selected.  1 Windowing mode selected.
5 Reserved	This read-only field is reserved and always has the value zero.
4 PMODE	Power Mode Select

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




## CMPx\_CR1 field descriptions (continued)

Field	Description
	Refer to the device data sheet's CMP electrical specifications table for details on the impact of the modes below.
	0 Low Speed (LS) comparison mode selected. In this mode, CMP has slower output propagation delay and lower current consumption.
	1 High Speed (HS) comparison mode selected. In this mode, CMP has faster output propagation delay and higher current consumption.
3 INV	Comparator INVERT
1144	This bit allows you to select the polarity of the analog comparator function. It is also driven to the COUT output (on both the device pin and as SCR[COUT]) when CR1[OPE]=0.
	0 Does not invert the comparator output.
	1 Inverts the comparator output.
2 COS	Comparator Output Select
	0 Set CMPO to equal COUT (filtered comparator output).
	1 Set CMPO to equal COUTA (unfiltered comparator output).
1 OPE	Comparator Output Pin Enable
OLL	0 The comparator output (CMPO) is not available on the associated CMPO output pin.
	The comparator output (CMPO) is available on the associated CMPO output pin.
0	Comparator Module Enable
EN	The EN bit enables the Analog Comparator Module. When the module is not enabled, it remains in the off state, and consumes no power. When you select the same input from analog mux to the positive and negative port, the comparator is disabled automatically.
	NOTE: This bit must be set in the same time with or after the mux enables (MUXCR[PEN] and MUXCR[MEM] are set) and should be neglected in the same time or before the mux enables.
	0 Analog Comparator disabled.
	1 Analog Comparator enabled.

# 33.7.3 CMP Filter Period Register (CMPx\_FPR)

Addresses: CMP0\_FPR is 4007\_3000h base + 2h offset = 4007\_3002h CMP1\_FPR is 4007\_3008h base + 2h offset = 4007\_300Ah CMP2\_FPR is 4007\_3010h base + 2h offset = 4007\_3012h






#### wemory Map/Register Definitions

#### CMPx\_FPR field descriptions

Field	Description
7–0 FILT_PER	Filter Sample Period  When CR1[SE] is equal to zero, this field specifies the sampling period, in bus clock cycles, of the comparator output filter. Setting FILT_PER to 0x0 disables the filter. Filter programming and latency details appear in the Functional Description.
	This field has no effect when CR1[SE] is equal to one. In that case, the external SAMPLE signal is used to determine the sampling period.

# 33.7.4 CMP Status and Control Register (CMPx\_SCR)

Addresses: CMP0\_SCR is 4007\_3000h base + 3h offset = 4007\_3003h CMP1\_SCR is 4007\_3008h base + 3h offset = 4007\_3008h CMP2\_SCR is 4007\_3010h base + 3h offset = 4007\_3013h



#### CMPx\_SCR field descriptions

Field	Description
7 Reserved	This read-only field is reserved and always has the value zero.
6 DMAEN	DMA Enable Control  The DMAEN bit enables the DMA transfer triggered from the CMP module. When this bit is set, a DMA request is asserted when the CFR or CFF bit is set.  0 DMA disabled. 1 DMA enabled.
5 SMELB	Stop Mode Edge/Level Interrupt Control  This bit controls whether the CFR and CFF bits are edge sensitive or level sensitive in Stop mode.  NOTE: This bit should always be programmed to 0 to keep the comparator working and to wake up the MCU.  O CFR/CFF are level sensitive in Stop mode. CFR will be asserted when COUT is high. CFF will be asserted when COUT is low.  CFR/CFF are edge sensitive in Stop mode. An active low-to-high transition must be seen on COUT to assert CFR, and an active high-to-low transition must be seen on COUT to assert CFF.
4 IER	Comparator Interrupt Enable Rising  The IER bit enables the CFR interrupt from the CMP. When this bit is set, an interrupt will be asserted when the CFR bit is set.

Table continues on the next page...




## CMPx\_SCR field descriptions (continued)

Field	Description
	0 Interrupt disabled.
	1 Interrupt enabled.
3 IEF	Comparator Interrupt Enable Falling
	The IEF bit enables the CFF interrupt from the CMP. When this bit is set, an interrupt will be asserted when the CFF bit is set.
	0 Interrupt disabled.
	1 Interrupt enabled.
2 CFR	Analog Comparator Flag Rising
0	During normal operation, the CFR bit is set when a rising edge on COUT has been detected. The CFR bit is cleared by writing a logic one to the bit. During Stop modes, CFR can be programmed as either edge or level sensitive via the SMELB bit.
	NOTE: Edge detection during Stop mode is only supported on platforms that allow peripherals to be clocked during Stop modes. If the CFR flag is active during Stop mode, then SMELB must be set to 0 for cases where it is not receiving a clock during Stop mode.
	0 Rising edge on COUT has not been detected.
	1 Rising edge on COUT has occurred.
1	Analog Comparator Flag Falling
CFF	During normal operation, the CFF bit is set when a falling edge on COUT has been detected. The CFF bit is cleared by writing a logic one to the bit. During Stop modes, CFF can be programmed as either edge or level sensitive via the SMELB bit.
	NOTE: Edge detection during Stop mode is only supported on platforms that allow peripherals to be clocked during Stop modes. If the CFF flag is active during Stop mode, then SMELB must be set to 0 for cases where it is not receiving a clock during Stop mode.
	0 Falling edge on COUT has not been detected.
	1 Falling edge on COUT has occurred.
0 COUT	Analog Comparator Output
	Reading the COUT bit will return the current value of the analog comparator output. The register bit is reset to zero and will read as CR1[INV] when the Analog Comparator module is disabled (CR1[EN] = 0). Writes to this bit are ignored.

# 33.7.5 DAC Control Register (CMPx\_DACCR)

Addresses: CMP0\_DACCR is 4007\_3000h base + 4h offset = 4007\_3004h CMP1\_DACCR is 4007\_3008h base + 4h offset = 4007\_300Ch CMP2\_DACCR is 4007\_3010h base + 4h offset = 4007\_3014h



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory Map/Register Definitions


# CMPx\_DACCR field descriptions

Field	Description
7	DAC Enable
DACEN	This bit is used to enable the DAC. When the DAC is disabled, it is powered down to conserve power.
	0 DAC is disabled.
	1 DAC is enabled.
6 VRSEL	Supply Voltage Reference Source Select
VHOEL	0 V <sub>in1</sub> is selected as resistor ladder network supply reference Vin.
	1 V <sub>in2</sub> is selected as resistor ladder network supply reference Vin.
5–0	DAC Output Voltage Select
VOSEL	This bit selects an output voltage from one of 64 distinct levels.
	DACO = (Vin/64) * (VOSEL[5:0] + 1), so the DACO range is from Vin/64 to Vin.

## 33.7.6 MUX Control Register (CMPx\_MUXCR)

PEN and MEN bits should be enabled or disabled together with CR1[EN] bit.

Addresses: CMP0\_MUXCR is 4007\_3000h base + 5h offset = 4007\_3005h CMP1\_MUXCR is 4007\_3008h base + 5h offset = 4007\_300Dh CMP2\_MUXCR is 4007\_3010h base + 5h offset = 4007\_3015h



## CMPx\_MUXCR field descriptions

Field	Description
7	PMUX Enable
PEN	This bit is used to enable positive MUX. When the PMUX is disabled, the PMUX output is in a high impedance state. When software selects the same input for plus and minus inputs of the comparator, both PMUX and MMUX are disabled automatically.
	<ul><li>0 PMUX is disabled.</li><li>1 PMUX is enabled.</li></ul>
6 MEN	MMUX Enable  This bit is used to enable negative MUX. When the MMUX is disabled, the MMUX output is in a high impedance state. When software selects the same input for plus and minus inputs of the comparator, both PMUX and MMUX are disabled automatically.
	<ul><li>0 MMUX is disabled.</li><li>1 MMUX is enabled.</li></ul>

Table continues on the next page...



#### CMPx\_MUXCR field descriptions (continued)

Field	Description
5–3	Plus Input MUX Control
PSEL	Determines which input is selected for the plus input of the comparator. For INx inputs, refer to CMP, DAC and ANMUX Blocks Diagram.
	<b>NOTE:</b> When an inappropriate operation selects the same input for both MUXes, the comparator automatically shuts down to prevent itself from becoming a noise generator.
	000 IN0
	001 IN1
	010 IN2
	011 IN3
	100 IN4
	101 IN5
	110 IN6
	111 IN7
2–0	Minus Input MUX Control
MSEL	Determines which input is selected for the minus input of the comparator. For INx inputs, refer to CMP, DAC and ANMUX Blocks Diagram.
	NOTE: When an inappropriate operation selects the same input for both MUXes, the comparator automatically shuts down to prevent itself from becoming a noise generator.
	000 IN0
	001 IN1
	010 IN2
	011 IN3
	100 IN4
	101 IN5
	110 IN6
	111 IN7

## 33.8 CMP Functional Description

The Comparator can be used to compare two analog input voltages applied to INP and INM. The analog comparator output (CMPO) is high when the non-inverting input is greater than the inverting input, and is low when the non-inverting input is less than the inverting input. This signal can be selectively inverted by setting CR1[INV] = 1.

The SCR[IER], SCR[IEF], and SCR[SMELB] bits are used to select the condition which will cause the comparator module to assert an interrupt to the processor. SCR[CFF] is set on a falling edge and SCR[CFR] is set on rising edge of the comparator output. The (optionally filtered) comparator output can be read directly through the SCR[COUT] bit.

## 33.8.1 CMP Functional Modes

There are three main sub-blocks to the comparator module: the comparator itself, the window function and the filter function. The filter, CR0[FILTER\_CNT] can be clocked from an internally or external clock source. Additionally, the filter is programmable with respect to how many samples must agree before a change on the output is registered. In the simplest case, only 1 sample must agree. In this case, the filter acts as a simple sampler.

The external sample input is enabled using CR1[SE]. When set, the output of the comparator is sampled only on rising edges of the sample input.

The "windowing mode" is enabled by setting CR1[WE]. When set, the comparator output is sampled only when the WINDOW input signal is equal to one. This feature can be used to ignore the comparator output during time periods in which the input voltages are not valid. This is especially useful when implementing zero-crossing-detection for certain PWM applications.

The comparator filter and sampling features can be combined as shown in the following table. Individual modes are discussed below.

CR0[FILTER\_C FPR[FILT\_PER] Mode # CR1[EN] CR1[WE] CR1[SE] Operation NT] 1 0 Χ Х Х Х Disabled Refer to the Disabled Mode (# 1). Х 2A 1 0 0 0x00 **Continuous Mode** Refer to the Continuous Mode (#s 2B 0 Χ 0x00 2A & 2B). 1 0 1 Х Sampled, Non-Filtered mode ЗА 0x01 1 0 0 Refer to the Sampled, Non-Filtered 3B 0x01 > 0x00Mode (#s 3A & 3B). 4A 1 0 Х Sampled, Filtered mode > 0x014B 1 0 0 > 0x00 Refer to the Sampled, Filtered > 0x01Mode (#s 4A & 4B). Х 5A 1 1 0 0x00 Windowed mode 5B Х 0x00 Comparator output is sampled on every rising bus clock edge when SAMPLE=1 to generate COUTA Refer to the Windowed Mode (#s 5A & 5B).

Table 33-29. Comparator Sample/Filter Controls

Table continues on the next page...



Table 33-29. Comparator Sample/Filter Controls (continued)

Mode #	CR1[EN]	CR1[WE]	CR1[SE]	CR0[FILTER_C NT]	FPR[FILT_PER]	Operation
6	1	1	0	0x01	0x01 - 0xFF	Windowed/Resampled mode
						Comparator output is sampled on every rising bus clock edge when SAMPLE=1 to generate COUTA, which is then resampled on an interval determined by FILT_PER to generate COUT.
						Refer to the Windowed/Resampled Mode (# 6).
7	1	1	0	> 0x01	0x01 - 0xFF	Windowed/Filtered mode
						Comparator output is sampled on every rising bus clock edge when SAMPLE=1 to generate COUTA, which is then resampled and filtered to generate COUT.
						Refer to the Windowed/Filtered Mode (#7).
All	other combina	ations of CR	I[EN]. CR1[V	VEL CRIISEL CRO	[FILTER_CNT], an	d FPR[FILT_PFR] are illegal.

All other combinations of CR1[EN], CR1[WE], CR1[SE], CR0[FILTER\_CNT], and FPR[FILT\_PER] are illegal.

For cases where a comparator is used to drive a fault input (for example, for a motor-control module such as FTM), it should generally be configured to operate in continuous mode, so that an external fault can immediately pass through the comparator to the target fault circuitry.

#### **Note**

Filtering and sampling settings should be changed only after setting CR1[SE]=0 and CR0[FILTER\_CNT]=0x00. This has the effect of resetting the filter to a known state.

## 33.8.1.1 Disabled Mode (# 1)

In disabled mode, the analog comparator is non-functional and consumes no power. The output of the analog comparator block (CMPO) is zero in this mode.

**CMP** Functional Description

## 33.8.1.2 Continuous Mode (#s 2A & 2B)




Figure 33-27. Comparator Operation in Continuous Mode

#### NOTE

Refer to the chip configuration section for the source of sample/ window input.

The analog comparator block is powered and active. CMPO may be optionally inverted, but is not subject to external sampling or filtering. Both Window Control and Filter Blocks are completely bypassed. SCR[COUT] is updated continuously. The path from comparator inputs pins to output pin is operating in combinational (unclocked) mode. COUT and COUTA are identical.

For control configurations which result in disabling the Filter Block, refer to Filter Block Bypass Logic diagram.



## 33.8.1.3 Sampled, Non-Filtered Mode (#s 3A & 3B)




Figure 33-28. Sampled, Non-Filtered (# 3A): Sampling point externally driven

In Sampled, Non-Filtered mode, the analog comparator block is powered and active. The path from analog inputs to COUTA is combinational (unclocked). Windowing Control is completely bypassed. COUTA is sampled whenever a rising edge is detected on the Filter Block clock input.

The only difference in operation between Sampled, Non-Filtered (# 3A) and Sampled, Non-Filtered (# 3B) is in how the clock to the Filter Block is derived. In #3A, the clock to filter block is externally derived while in #3B, the clock to filter block is internally derived.

The comparator filter has no other function than sample/hold of the comparator output in this mode (# 3B).






Figure 33-29. Sampled, Non-Filtered (# 3B): Sampling interval internally derived

## 33.8.1.4 Sampled, Filtered Mode (#s 4A & 4B)

In Sampled, Filtered mode, the analog comparator block is powered and active. The path from analog inputs to COUTA is combinational (unclocked). Windowing Control is completely bypassed. COUTA is sampled whenever a rising edge is detected on the Filter Block clock input.

The only difference in operation between Sampled, Non-Filtered (# 3A) and Sampled, Filtered (# 4A) is that CR0[FILTER\_CNT] is now greater than 1, which activates filter operation.






Figure 33-30. Sampled, Filtered (# 4A): Sampling point externally driven






Figure 33-31. Sampled, Filtered (# 4B): Sampling point internally derived

The only difference in operation between Sampled, Non-Filtered (# 3B) and Sampled, Filtered (# 4B) is that CR0[FILTER\_CNT] is now greater than 1, which activates filter operation.

## 33.8.1.5 Windowed Mode (#s 5A & 5B)

The following figure illustrates comparator operation in the windowed mode, ignoring latency of the analog comparator, polarity select and Window Control block. It also assumes that the Polarity Select is set to "non-inverting". Note that the analog comparator output is passed to COUTA only when the WINDOW signal is high.

In actual operation, COUTA may lag the analog inputs by up to one bus clock cycle plus the combinational path delay through the comparator and polarity select logic.






Figure 33-32. Windowed Mode Operation




Figure 33-33. Windowed Mode

For control configurations which result in disabling the Filter Block, refer to Filter Block Bypass Logic diagram.



#### **CIVIP** Functional Description

When any windowed mode is active, COUTA is clocked by the bus clock whenever WINDOW = 1. The last latched value is held when WINDOW = 0.

## 33.8.1.6 Windowed/Resampled Mode (# 6)

The following figure uses the same input stimulus shown in Figure 33-32, and adds resampling of COUTA to generate COUT. Samples are taken at the time points indicated by the arrows. Again, prop delays and latency is ignored for clarity's sake. This example was generated solely to demonstrate operation of the comparator in windowing / resampled mode, and does not reflect any specific application. Depending upon the sampling rate and window placement, COUT may not see zero-crossing events detected by the analog comparator. Sampling period and/or window placement must be carefully considered for a given application.




Figure 33-34. Windowed / Resampled Mode Operation

This mode of operation results in an unfiltered string of comparator samples where the interval between the samples is determined by FPR[FILT\_PER] and the bus clock rate. Configuration for this mode is virtually identical to that for the Windowed/Filtered Mode shown in the next section. The only difference is that the value of CR0[FILTER\_CNT] must be exactly one.



# 33.8.1.7 Windowed/Filtered Mode (#7)

This is the most complex mode of operation for the comparator block, as it utilizes both windowing and filtering features. It also has the highest latency of any of the modes. This can be approximated: up to 1 bus clock synchronization in the window function + ((CR0[FILTER\_CNT] X FPR[FILT\_PER]) + 1) X bus clock for the filter function.

When any windowed mode is active, COUTA is clocked by the bus clock whenever WINDOW = 1. The last latched value is held when WINDOW = 0.




Figure 33-35. Windowed/Filtered Mode

## 33.8.2 Power Modes

## 33.8.2.1 Wait Mode Operation

During Wait and VLPW modes and if enabled, the CMP continues to operate normally. Also, if enabled, a CMP interrupt can wake the MCU.



**CMP** Functional Description

## 33.8.2.2 Stop Mode Operation

Subject to platform-specific clock restrictions, the MCU is brought out of stop when a compare event occurs and the corresponding interrupt is enabled. Similarly, if CR1[OPE] is enabled, the comparator output operates as in the normal operating mode and comparator output is placed onto the external pin. In stop modes, the comparator can be operational in both high speed (HS) comparison mode (CR1[PMODE] = 1) and low speed (LS) comparison mode (CR1[PMODE] = 0), but it is recommended to use the low speed mode to minimize power consumption.

If stop is exited with a reset, all comparator registers are put into their reset state.

## 33.8.2.3 Low-Leakage Mode Operation

When the chip is in low-leakage modes, the CMP module is partially functional and is limited to low speed mode (regardless of the CR1[PMODE] bit's setting). Windowed, sampled, and filtered modes are not supported. The CMP output pin is latched and does not reflect the compare output state.

The positive- and negative-input voltage can be from external pins or the DAC output. The MCU can be brought out of the low-leakage mode if a compare event occurs and the CMP interrupt is enabled. After wakeup from low-leakage modes, the CMP module is in the reset state except for the SCR[CFF] and SCR[CFR] flags.

## 33.8.3 Startup and Operation

A typical startup sequence is as follows.

The time required to stabilize COUT will be the power-on delay of the comparators plus the largest propagation delay from a selected analog source through the analog comparator, windowing function and filter. Power on delay of the comparators are available from data sheets. The windowing function has a maximum of 1 bus clock period delay. Filter delay is specified in Low Pass Filter.

During operation, the propagation delay of the selected data paths must always be considered. It can take many bus clock cycles for COUT and the CFR/CFF status bits to reflect an input change or a configuration change to one of the components involved in the data path.

When programmed for filtering modes, COUT will initially be equal to zero until sufficient clock cycles have elapsed to fill all stages of the filter. This occurs even if COUTA is at a logic one.



#### 33.8.4 Low Pass Filter

The low-pass filter operates on the unfiltered and unsynchronized and optionally inverted comparator output COUTA and generates the filtered and synchronized output COUT. Both COUTA and COUT can be configured as module outputs and are used for different purposes within the system.

Synchronization and edge detection are always used to determine status register bit values. They also apply to COUT for all sampling and windowed modes. Filtering can be performed using an internal timebase defined by FPR[FILT\_PER], or using an external SAMPLE input to determine sample time.

The need for digital filtering and the amount of filtering is dependent on user requirements. Filtering can become more useful in the absence of an external hysteresis circuit. Without external hysteresis, high frequency oscillations can be generated at COUTA when the selected INM and INP input voltages differ by less than the offset voltage of the differential comparator.

#### 33.8.4.1 Enabling Filter Modes

Filter Modes are enabled by setting CR0[FILTER\_CNT] greater than 0x01 and (setting FPR[FILT\_PER] to a non-zero value OR setting CR1[SE]=1). If using the divided bus clock to drive the filter, it will take samples of COUTA every FPR[FILT\_PER] bus clock cycles.

The filter output will be at logic zero when first initalized, and will subsequently change when CR0[FILTER\_CNT] consecutive samples all agree that the output value has changed. Said another way, SCR[COUT] will be zero for some initial period, even when COUTA is at logic one.

Setting both CR1[SE] and FPR[FILT\_PER] to 0 disables the filter and eliminates switching current associated with the filtering process.

#### Note

Always switch to this setting prior to making any changes in filter parameters. This resets the filter to a known state. Switching CR0[FILTER\_CNT] on the fly without this intermediate step can result in unexpected behavior.



#### **CIVIP** Functional Description

If CR1[SE]=1, the filter takes samples of COUTA on each positive transition of the sample input. The output state of the filter changes when CR0[FILTER\_CNT] consecutive samples all agree that the output value has changed.

#### 33.8.4.2 Latency Issues

The FPR[FILT\_PER] value (or SAMPLE period) should be set such that the sampling period is just larger than the period of the expected noise. This way a noise spike will only corrupt one sample. The CR0[FILTER\_CNT] value should be chosen to reduce the probability of noisy samples causing an incorrect transition to be recognized. The probability of an incorrect transition is defined as the probability of an incorrect sample raised to the CR0[FILTER\_CNT] power.

The following table summarizes maximum latency values for the various modes of operation *in the absence of noise*. Filtering latency is restarted each time an actual output transition is masked by noise.

The values of FPR[FILT\_PER] (or SAMPLE period) and CR0[FILTER\_CNT] must also be traded off against the desire for minimal latency in recognizing actual comparator output transitions. The probability of detecting an actual output change within the nominal latency is the probability of a correct sample raised to the CR0[FILTER\_CNT] power.

Table 33-30. Comparator Sample/Filter Maximum Latencies

Mode #	CR1[ EN]	CR1[ WE]	CR1[ SE]	CR0[FILTER _CNT]	FPR[FILT_P ER]	Operation	Maximum Latency <sup>1</sup>
1	0	Х	Х	Х	Х	Disabled	N/A
2A	1	0	0	0x00	Х	Continuous Mode	T <sub>PD</sub>
2B	1	0	0	Х	0x00		
ЗА	1	0	1	0x01	Х	Sampled, Non-Filtered mode	T <sub>PD</sub> + T <sub>SAMPLE</sub> + T <sub>per</sub>
3B	1	0	0	0x01	> 0x00		$T_{PD}$ + (FPR[FILT_PER] x $T_{per}$ ) + $T_{per}$
4A	1	0	1	> 0x01	Х	Sampled, Filtered mode	$T_{PD}$ + (CR0[FILTER_CNT] x $T_{SAMPLE}$ ) + $T_{per}$
4B	1	0	0	> 0x01	> 0x00		T <sub>PD</sub> + (CR0[FILTER_CNT] x FPR[FILT_PER] x T <sub>per</sub> ) + T <sub>per</sub>
5A	1	1	0	0x00	Х	Windowed mode	T <sub>PD</sub> + T <sub>per</sub>
5B	1	1	0	Х	0x00		T <sub>PD</sub> + T <sub>per</sub>
6	1	1	0	0x01	0x01 - 0xFF	Windowed / Resampled mode	T <sub>PD</sub> + (FPR[FILT_PER] x T <sub>per</sub> ) + 2T <sub>per</sub>



#### Table 33-30. Comparator Sample/Filter Maximum Latencies (continued)

Mode #	CR1[ EN]	CR1[ WE]	CR1[ SE]	CR0[FILTER _CNT]	FPR[FILT_P ER]	Operation	Maximum Latency <sup>1</sup>
7	1	1	0	> 0x01	0x01 - 0xFF	Windowed / Filtered mode	T <sub>PD</sub> + (CR0[FILTER_CNT] x FPR[FILT_PER] x T <sub>per</sub> ) + 2T <sub>per</sub>

T<sub>PD</sub> represents the intrinsic delay of the analog component plus the polarity select logic. T<sub>SAMPLE</sub> is the clock period of the external sample clock. T<sub>per</sub> is the period of the bus clock.

# 33.9 CMP Interrupts

The CMP module is capable of generating an interrupt on either the rising or falling edge of the comparator output (or both). The interrupt request is asserted when both SCR[IER] bit and SCR[CFR] are set. It is also asserted when both SCR[IEF] bit and SCR[CFF] are set. The interrupt is de-asserted by clearing either SCR[IER] or SCR[CFR] for a rising edge interrupt, or SCR[IEF] and SCR[CFF] for a falling edge interrupt.

# 33.10 CMP DMA Support

Normally, the CMP generates a CPU interrupt if there is a change on the COUT. When DMA support (set SCR[DMAEN]) enables and the interrupt enables (set SCR[IER] or SCR[IEF] or both), the corresponding change on COUT forces a DMA transfer request rather than a CPU interrupt instead. When the DMA has completed the transfer, it sends a dma\_done signal that de-asserts the dma\_request and clears the flag to allow a subsequent change on comparator output to occur and force another DMA request.

## 33.11 Digital to Analog Converter Block Diagram

The following figure shows the block diagram of the DAC module. It contains a 64-tap resistor ladder network and a 64-to-1 multiplexer, which selects an output voltage from one of 64 distinct levels that outputs from DACO. It is controlled through DAC Control register (DACCR). Its supply reference source can be selected from two sources  $V_{in1}$  and  $V_{in2}$ . The module can be powered down (disabled) when it is not used. When in disable mode, DACO is connected to the analog ground.



#### **DAC Functional Description**




Figure 33-36. 6-bit DAC Block Diagram

# 33.12 DAC Functional Description

This section provides DAC functional description.

## 33.12.1 Voltage Reference Source Select

- $\bullet$  V<sub>in1</sub> should be used to connect to the primary voltage source as supply reference of 64 tap resistor ladder
- $V_{in2}$  should be used to connect to alternate voltage source (or primary source if alternate voltage source is not available)

#### 33.13 DAC Resets

This module has a single reset input, corresponding to the chip-wide peripheral reset.

# 33.14 DAC Clocks

This module has a single clock input, the bus clock.



# 33.15 DAC Interrupts

This module has no interrupts.



**DAC Interrupts** 



# Chapter 34 12-bit Digital-to-Analog Converter (DAC)

#### 34.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The 12-bit digital-to-analog converter (DAC) is a low power general purpose DAC. The output of this DAC can be placed on an external pin or set as one of the inputs to the analog comparator, Op-Amps, ADC, or other peripherals.

## 34.2 Features

The DAC module features include:

- On-chip programmable reference generator output (voltage output from 1/4096 Vin to Vin, step is 1/4096 Vin)
- Vin can be selected from two reference sources
- Static operation in Normal Stop mode
- 16-word data buffer supported with configurable watermark and multiple operation modes
- DMA support

# 34.3 Block Diagram

The block diagram of the DAC module is as follows:



#### wemory Map/Register Definition




Figure 34-1. DAC Block Diagram

# 34.4 Memory Map/Register Definition

The DAC has registers to control analog comparator and programmable voltage divider to perform the digital-to-analog functions.

The address of a register is the sum of a base address and an address offset. The base address is defined at the chip level. The address offset is defined at the module level.



## **DAC** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400C_C000	DAC Data Low Register (DAC0_DAT0L)	8	R/W	00h	34.4.1/ 814
400C_C001	DAC Data High Register (DAC0_DAT0H)	8	R/W	00h	34.4.2/ 815
400C_C002	DAC Data Low Register (DAC0_DAT1L)	8	R/W	00h	34.4.1/ 814
400C_C003	DAC Data High Register (DAC0_DAT1H)	8	R/W	00h	34.4.2/ 815
400C_C004	DAC Data Low Register (DAC0_DAT2L)	8	R/W	00h	34.4.1/ 814
400C_C005	DAC Data High Register (DAC0_DAT2H)	8	R/W	00h	34.4.2/ 815
400C_C006	DAC Data Low Register (DAC0_DAT3L)	8	R/W	00h	34.4.1/ 814
400C_C007	DAC Data High Register (DAC0_DAT3H)	8	R/W	00h	34.4.2/ 815
400C_C008	DAC Data Low Register (DAC0_DAT4L)	8	R/W	00h	34.4.1/ 814
400C_C009	DAC Data High Register (DAC0_DAT4H)	8	R/W	00h	34.4.2/ 815
400C_C00A	DAC Data Low Register (DAC0_DAT5L)	8	R/W	00h	34.4.1/ 814
400C_C00B	DAC Data High Register (DAC0_DAT5H)	8	R/W	00h	34.4.2/ 815
400C_C00C	DAC Data Low Register (DAC0_DAT6L)	8	R/W	00h	34.4.1/ 814
400C_C00D	DAC Data High Register (DAC0_DAT6H)	8	R/W	00h	34.4.2/ 815
400C_C00E	DAC Data Low Register (DAC0_DAT7L)	8	R/W	00h	34.4.1/ 814
400C_C00F	DAC Data High Register (DAC0_DAT7H)	8	R/W	00h	34.4.2/ 815
400C_C010	DAC Data Low Register (DAC0_DAT8L)	8	R/W	00h	34.4.1/ 814
400C_C011	DAC Data High Register (DAC0_DAT8H)	8	R/W	00h	34.4.2/ 815
400C_C012	DAC Data Low Register (DAC0_DAT9L)	8	R/W	00h	34.4.1/ 814
400C_C013	DAC Data High Register (DAC0_DAT9H)	8	R/W	00h	34.4.2/ 815



#### wemory Map/Register Definition

# **DAC** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400C_C014	DAC Data Low Register (DAC0_DAT10L)	8	R/W	00h	34.4.1/ 814
400C_C015	DAC Data High Register (DAC0_DAT10H)	8	R/W	00h	34.4.2/ 815
400C_C016	DAC Data Low Register (DAC0_DAT11L)	8	R/W	00h	34.4.1/ 814
400C_C017	DAC Data High Register (DAC0_DAT11H)	8	R/W	00h	34.4.2/ 815
400C_C018	DAC Data Low Register (DAC0_DAT12L)	8	R/W	00h	34.4.1/ 814
400C_C019	DAC Data High Register (DAC0_DAT12H)	8	R/W	00h	34.4.2/ 815
400C_C01A	DAC Data Low Register (DAC0_DAT13L)	8	R/W	00h	34.4.1/ 814
400C_C01B	DAC Data High Register (DAC0_DAT13H)	8	R/W	00h	34.4.2/ 815
400C_C01C	DAC Data Low Register (DAC0_DAT14L)	8	R/W	00h	34.4.1/ 814
400C_C01D	DAC Data High Register (DAC0_DAT14H)	8	R/W	00h	34.4.2/ 815
400C_C01E	DAC Data Low Register (DAC0_DAT15L)	8	R/W	00h	34.4.1/ 814
400C_C01F	DAC Data High Register (DAC0_DAT15H)	8	R/W	00h	34.4.2/ 815
400C_C020	DAC Status Register (DAC0_SR)	8	R	02h	34.4.3/ 815
400C_C021	DAC Control Register (DAC0_C0)	8	R/W	00h	34.4.4/ 816
400C_C022	DAC Control Register 1 (DAC0_C1)	8	R/W	00h	34.4.5/ 817
400C_C023	DAC Control Register 2 (DAC0_C2)	8	R/W	0Fh	34.4.6/ 818
400C_D000	DAC Data Low Register (DAC1_DAT0L)	8	R/W	00h	34.4.1/ 814
400C_D001	DAC Data High Register (DAC1_DAT0H)	8	R/W	00h	34.4.2/ 815
400C_D002	DAC Data Low Register (DAC1_DAT1L)	8	R/W	00h	34.4.1/ 814
400C_D003	DAC Data High Register (DAC1_DAT1H)	8	R/W	00h	34.4.2/ 815



# **DAC** memory map (continued)


400C_D004         DAC Data Low Register (DAC1_DAT2L)         8         H/W         00h           400C_D005         DAC Data High Register (DAC1_DAT2H)         8         R/W         00h         3           400C_D006         DAC Data Low Register (DAC1_DAT3L)         8         R/W         00h         3           400C_D007         DAC Data High Register (DAC1_DAT3H)         8         R/W         00h         3           400C_D008         DAC Data Low Register (DAC1_DAT4L)         8         R/W         00h         3           400C_D009         DAC Data High Register (DAC1_DAT4H)         8         R/W         00h         3           400C_D000         DAC Data Low Register (DAC1_DAT5L)         8         R/W         00h         3           400C_D00B         DAC Data Low Register (DAC1_DAT5H)         8         R/W         00h         3           400C_D00C         DAC Data Low Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00E         DAC Data Low Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D00F         DAC Data Low Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8<	ection/ page
400C_D005         DAC Data High Register (DAC1_DAT2H)         8         R/W         00h         3           400C_D006         DAC Data Low Register (DAC1_DAT3L)         8         R/W         00h         3           400C_D007         DAC Data High Register (DAC1_DAT3H)         8         R/W         00h         3           400C_D008         DAC Data Low Register (DAC1_DAT4L)         8         R/W         00h         3           400C_D009         DAC Data High Register (DAC1_DAT4H)         8         R/W         00h         3           400C_D00A         DAC Data Low Register (DAC1_DAT5L)         8         R/W         00h         3           400C_D00B         DAC Data High Register (DAC1_DAT5H)         8         R/W         00h         3           400C_D00C         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h         3           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT	4.4.1/ 814
400C_D006         DAC Data Low Register (DAC1_DAT3L)         8         R/W         00h           400C_D007         DAC Data High Register (DAC1_DAT3H)         8         R/W         00h         3           400C_D008         DAC Data Low Register (DAC1_DAT4L)         8         R/W         00h         3           400C_D009         DAC Data High Register (DAC1_DAT4H)         8         R/W         00h         3           400C_D00A         DAC Data Low Register (DAC1_DAT5L)         8         R/W         00h         3           400C_D00B         DAC Data High Register (DAC1_DAT5H)         8         R/W         00h         3           400C_D00C         DAC Data Low Register (DAC1_DAT6L)         8         R/W         00h         3           400C_D00D         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00E         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D00F         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H) <td< td=""><td>4.4.2/ 815</td></td<>	4.4.2/ 815
400C_D007         DAC Data High Register (DAC1_DAT3H)         8         R/W         00h           400C_D008         DAC Data Low Register (DAC1_DAT4L)         8         R/W         00h           400C_D009         DAC Data High Register (DAC1_DAT4H)         8         R/W         00h           400C_D00A         DAC Data Low Register (DAC1_DAT5L)         8         R/W         00h           400C_D00B         DAC Data High Register (DAC1_DAT5H)         8         R/W         00h           400C_D00C         DAC Data Low Register (DAC1_DAT6L)         8         R/W         00h           400C_D00D         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h	4.4.1/ 814
400C_D008         DAC Data Low Register (DAC1_DAT4L)         8         R/W         00h           400C_D009         DAC Data High Register (DAC1_DAT4H)         8         R/W         00h         3           400C_D00A         DAC Data Low Register (DAC1_DAT5L)         8         R/W         00h         3           400C_D00B         DAC Data High Register (DAC1_DAT5H)         8         R/W         00h         3           400C_D00C         DAC Data Low Register (DAC1_DAT6L)         8         R/W         00h         3           400C_D00D         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h         3           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h         3	4.4.2/ 815
400C_D009         DAC Data High Register (DAC1_DAT4H)         8         R/W         00h         3           400C_D00A         DAC Data Low Register (DAC1_DAT5L)         8         R/W         00h         3           400C_D00B         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00C         DAC Data Low Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00D         DAC Data Low Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h         3           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h         3	4.4.1/ 814
400C_D00A         DAC Data Low Register (DAC1_DAT5L)         8         R/W         00h         3           400C_D00B         DAC Data High Register (DAC1_DAT6L)         8         R/W         00h         3           400C_D00C         DAC Data Low Register (DAC1_DAT6L)         8         R/W         00h         3           400C_D00D         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h         3           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h         3	4.4.2/ 815
400C_D00B         DAC Data High Register (DAC1_DAT5H)         8         R/W         00h           400C_D00C         DAC Data Low Register (DAC1_DAT6L)         8         R/W         00h           400C_D00D         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h	4.4.1/ 814
400C_D00C         DAC Data Low Register (DAC1_DAT6L)         8         R/W         00h           400C_D00D         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h         3           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h         3           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h         3	4.4.2/ 815
400C_D00D         DAC Data High Register (DAC1_DAT6H)         8         R/W         00h           400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h         3           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h         3	4.4.1/ 814
400C_D00E         DAC Data Low Register (DAC1_DAT7L)         8         R/W         00h         3           400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h         3           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h         3	4.4.2/ 815
400C_D00F         DAC Data High Register (DAC1_DAT7H)         8         R/W         00h           400C_D010         DAC Data Low Register (DAC1_DAT8L)         8         R/W         00h         3           400C_D011         DAC Data High Register (DAC1_DAT8H)         8         R/W         00h         3	4.4.1/ 814
400C_D010 DAC Data Low Register (DAC1_DAT8L) 8 R/W 00h 3 400C_D011 DAC Data High Register (DAC1_DAT8H) 8 R/W 00h 3	4.4.2/ 815
400C_D011 DAC Data High Register (DAC1_DA18H) 8 H/W 00h	4.4.1/ 814
400C_D012 DAC Data Low Register (DAC1_DAT9L) 8 R/W 00h 3	4.4.2/ 815
	4.4.1/ 814
1 400C DUT3 TDAC Data High Register (DACT DAT9H)	4.4.2/ 815
400C_D014 DAC Data Low Register (DAC1_DAT10L) 8 R/W 00h	4.4.1/ 814
1 /00(: 1005   104(: 1022 High Register (104(:1 104   10H)	4.4.2/ 815
400C, DOT6   DAC Data LOW Benister (DACT DATTIL)   8   B/W   OOD	4.4.1/ 814
AUDIC DIDI /   DAG DATA HIGH REGISTER (DAG LI DA LI IH)	4.4.2/ 815


#### wemory Map/Register Definition

# **DAC** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400C_D018	DAC Data Low Register (DAC1_DAT12L)	8	R/W	00h	34.4.1/ 814
400C_D019	DAC Data High Register (DAC1_DAT12H)	8	R/W	00h	34.4.2/ 815
400C_D01A	DAC Data Low Register (DAC1_DAT13L)	8	R/W	00h	34.4.1/ 814
400C_D01B	DAC Data High Register (DAC1_DAT13H)	8	R/W	00h	34.4.2/ 815
400C_D01C	DAC Data Low Register (DAC1_DAT14L)	8	R/W	00h	34.4.1/ 814
400C_D01D	DAC Data High Register (DAC1_DAT14H)	8	R/W	00h	34.4.2/ 815
400C_D01E	DAC Data Low Register (DAC1_DAT15L)	8	R/W	00h	34.4.1/ 814
400C_D01F	DAC Data High Register (DAC1_DAT15H)	8	R/W	00h	34.4.2/ 815
400C_D020	DAC Status Register (DAC1_SR)	8	R	02h	34.4.3/ 815
400C_D021	DAC Control Register (DAC1_C0)	8	R/W	00h	34.4.4/ 816
400C_D022	DAC Control Register 1 (DAC1_C1)	8	R/W	00h	34.4.5/ 817
400C_D023	DAC Control Register 2 (DAC1_C2)	8	R/W	0Fh	34.4.6/ 818

# 34.4.1 DAC Data Low Register (DACx\_DATL)







#### DACx\_DATnL field descriptions

Field	Description
7–0 DATA[7:0]	When the DAC Buffer is not enabled, DATA[11:0] controls the output voltage based on the following formula. Vout = Vin * (1 + DACDAT0[11:0])/4096
	When the DAC Buffer is enabled, DATA is mapped to the 16-word buffer.



## 34.4.2 DAC Data High Register (DACx\_DATH)






#### DACx DATnH field descriptions


Field	Description
7–4 Reserved	This read-only field is reserved and always has the value zero.
3–0 DATA[11:8]	When the DAC Buffer is not enabled, DATA[11:0] controls the output voltage based on the following formula. Vout = Vin * (1 + DACDAT0[11:0])/4096
	When the DAC Buffer is enabled, DATA[11:0] is mapped to the 16-word buffer.

## 34.4.3 DAC Status Register (DACx\_SR)

If DMA is enabled, the flags can be cleared automatically by DMA when the DMA request is done. Write zero to a bit to clear it. Writing one has no effect. After reset DACBFRPTF is set and can be cleared by software, if needed. The flags are set only when the data buffer status is changed.

Addresses: DAC0\_SR is 400C\_C000h base + 20h offset = 400C\_C020h





#### DACx\_SR field descriptions

Field	Description
7–3 Reserved	This read-only field is reserved and always has the value zero. Reserved
2 DACBFWMF	DAC buffer watermark flag  The DAC buffer read pointer has not reached the watermark level.  The DAC buffer read pointer has reached the watermark level.
1 DACBFRPTF	DAC buffer read pointer top position flag




#### wemory Map/Register Definition

#### **DACx\_SR** field descriptions (continued)

Field	Description
	0 The DAC buffer read pointer is not zero.
	1 The DAC buffer read pointer is zero.
0 DACBFRPBF	DAC buffer read pointer bottom position flag
	0 The DAC buffer read pointer is not equal to the DACBFUP.
	1 The DAC buffer read pointer is equal to the DACBFUP.

# 34.4.4 DAC Control Register (DACx\_C0)

Addresses: DAC0\_C0 is 400C\_C000h base + 21h offset = 400C\_C021h DAC1\_C0 is 400C\_D000h base + 21h offset = 400C\_D021h



#### DACx\_C0 field descriptions

Field	Description
7 DACEN	DAC enable
DAGLIN	The DACEN bit starts the Programmable Reference Generator operation.
	0 The DAC system is disabled.
	1 The DAC system is enabled.
6 DACRES	DAC Reference Select
	0 The DAC selets DACREF_1 as the reference voltage.
	1 The DAC selets DACREF_2 as the reference voltage.
5 DACTRGSEL	DAC trigger select
	0 The DAC hardware trigger is selected.
	1 The DAC software trigger is selected.
4 DACSWTRG	DAC software trigger
	Active high. This is a write-only bit, read it always be 0. If DAC software trigger is selected and buffer enabled, write 1 to this bit will advance the buffer read pointer once.
	0 The DAC soft trigger is not valid.
	1 The DAC soft trigger is valid.
3 LPEN	DAC low power control
	Refer to the device data sheet's 12-bit DAC electrical characteristics for details on the impact of the modes below.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




#### DACx\_C0 field descriptions (continued)

Field	Description		
	0 high power mode.		
	1 low power mode.		
2 DACBWIEN	DAC buffer watermark interrupt enable		
	0 The DAC buffer watermark interrupt is disabled.		
	1 The DAC buffer watermark interrupt is enabled.		
1 DACBTIEN	DAC buffer read pointer top flag interrupt enable		
	0 The DAC buffer read pointer top flag interrupt is disabled.		
	1 The DAC buffer read pointer top flag interrupt is enabled.		
0 DACBBIEN	DAC buffer read pointer bottom flag interrupt enable		
	0 The DAC buffer read pointer bottom flag interrupt is disabled.		
	1 The DAC buffer read pointer bottom flag interrupt is enabled.		

# 34.4.5 DAC Control Register 1 (DACx\_C1)

Addresses: DAC0\_C1 is 400C\_C000h base + 22h offset = 400C\_C022h DAC1\_C1 is 400C\_D000h base + 22h offset = 400C\_D022h



#### DACx\_C1 field descriptions

Field	Description
7 DMAEN	DMA enable select
	0 DMA disabled.
	1 DMA enabled. When DMA enabled, DMA request will be generated by original interrupts. And interrupts will not be presented on this module at the same time.
6–5 Reserved	This read-only field is reserved and always has the value zero.
4–3 DACBFWM	DAC buffer watermark select
	This bitfield controls when the DAC buffer watermark flag will be set. When the DAC buffer read pointer reaches the word defined by this bitfield, from 1 to 4 words away from the upper limit (DACBUP), the DAC buffer watermark flag will be set. This allows user configuration of the watermark interrupt.
	00 1 word
	01 2 words
	10 3 words
	11 4 words

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011


#### runctional Description

#### DACx\_C1 field descriptions (continued)

Field	Description
2–1 DACBFMD	DAC buffer work mode select
DAODI WD	00 Normal Mode
	01 Swing Mode
	10 One-Time Scan Mode
	11 Reserved
0	DAC buffer enable
DACBFEN	O. Puffer read pointer disabled. The converted data is always the first word of the buffer
	0 Buffer read pointer disabled. The converted data is always the first word of the buffer.
	1 Buffer read pointer enabled. The converted data is the word that the read pointer points to. It means converted data can be from any word of the buffer.

## 34.4.6 DAC Control Register 2 (DACx\_C2)

Addresses: DAC0\_C2 is 400C\_C000h base + 23h offset = 400C\_C023h DAC1\_C2 is 400C\_D000h base + 23h offset = 400C\_D023h



#### DACx\_C2 field descriptions

Field	Description
7–4 DACBFRP	DAC buffer read pointer
	These 4 bits keep the current value of the buffer read pointer.
3–0 DACBFUP	DAC buffer upper limit
	These 4 bits select the buffer's upper limit. The buffer read pointer cannot exceed it.

## 34.5 Functional Description

The 12-bit DAC module can select one of the two reference inputs — DACREF\_1 and DACREF\_2 as the DAC reference voltage ( $V_{in}$ ) by DACRFS bit of C0 register. Refer to the module introduction for information on the source for DACREF\_1 and DACREF\_2. When the DAC is enabled, it converts the data in DACDAT0[11:0] or the data from the DAC data buffer to a stepped analog output voltage. The output voltage range is from  $V_{in}/4096$  to  $V_{in}$ , and the step is  $V_{in}/4096$ .



## 34.5.1 DAC Data Buffer Operation

When the DAC is enabled and the buffer is not enabled, the DAC module always converts the data in DAT0 to analog output voltage.

When both the DAC and the buffer are enabled, the DAC converts the data in the data buffer to analog output voltage. The data buffer read pointer advances to the next word in the event the hardware trigger or the software trigger occurs. Refer to the PDB Module Interconnections section in Chip Configuration chapter for the hardware trigger connection.

The data buffer can be configured to operate in normal mode, swing mode or one-time scan mode. When the buffer operation is switched from one mode to another, the read pointer does not change. The read pointer can be set to any value between "0" and DACBFUP by writing DACBFRP in C2 register.

#### 34.5.1.1 DAC Data Buffer Interrupts

There are several interrupts and associated flags that can be configured for the DAC buffer. The DAC read pointer bottom position flag is set when the DAC buffer read pointer reaches the DAC buffer upper limit. (DACBFRP = DACBFUP). The DAC read pointer top position flag is set when the DAC read pointer is equal to the start position, 0. Finally, the DAC buffer watermark flag is set when the DAC buffer read pointer has reached the position defined by the DAC watermark select bit field. The DAC watermark select (DACBFWM) can be used to generate an interrupt when the DAC buffer Read pointer is between 1 to 4 words from the DAC buffer upper limit.

#### 34.5.1.2 Buffer Normal Mode

This is the default mode. The buffer works as a circular buffer. The read pointer increases by one, every time when the trigger occurs. When the read pointer reaches the upper limit, it goes to the zero directly in the next trigger event.

# 34.5.1.3 Buffer Swing Mode

This mode is similar to the normal mode. But when the read pointer reaches the upper limit, it does not go to the zero. It will descend by one in the next trigger events until zero is reached.



#### 34.5.1.4 Buffer One-time Scan Mode

The read pointer increases by one every time when the trigger occurs. When it reaches the upper limit, it stops at there. If read pointer is reset to the address other than the upper limit, it will increase to the upper address and stop at there again.

#### **Note**

If the software set the read pointer to the upper limit, the read pointer will not advance in this mode.

## 34.5.2 DMA Operation

When DMA is enabled, interrupt requests are not generated. DMA requests are generated instead. DMA done signal clears the DMA request.

The status register flags are still set and are cleared automatically when the DMA completes.

#### **34.5.3 Resets**

During reset the DAC is configured in the default mode. DAC is disabled.

## 34.5.4 Low Power Mode Operation

This section describes the wait mode and the stop mode operation of the DAC module.

## 34.5.4.1 Wait Mode Operation

In wait mode, the DAC will operate normally if enabled.

#### 34.5.4.2 Stop Mode Operation

The DAC continues to operate in Normal Stop mode if enabled, the output voltage will hold the value before stop.

In Low Power Stop modes, the DAC is fully shut-down.



#### **NOTE**

The assignment of module modes to core modes is chipspecific. For module-to-core mode assignments, see the chapter that describes how modules are configured.



**runctional Description** 



# **Chapter 35 Operational Amplifier (OPAMP)**

#### 35.1 Introduction

#### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The General Purpose Operational Amplifier (OPAMP) block is a CMOS single supply, low-input offset voltage, low-input offset, and bias current amplifier that is designed for low-voltage, low-power operation over an input voltage range of 0 to supply. The OPAMP also has several timing and control settings that can be software-configured depending on the application requirements. Timing and control consists of registers and control logic for:

- Amplifier gain programmable
- Operation in low-power modes

The general purpose amplifier contains inverting, non-inverting, buffer, and general purpose modes.

#### **35.1.1 Features**

Key features include:

- Programmable voltage gain
- On-chip generation of bias voltages
- Low-power, low-voltage CMOS technology
- Low-input offset voltage and current
- Low-input bias current
- Low-current consumption



## 35.1.2 Block Diagram

This diagram illustrates the op-amp module.

#### **NOTE**

The positive and negative inputs are specific to the device using this module. See the device's Chip Configuration details for the connections used for these inputs.




Figure 35-1. Op-Amp Block Diagram

#### 35.1.3 Low power modes

The OPAMP module supports the following low power modes:

- VLLSx off
- LLS static (register states held)
- VLPS, VLPW, VLPR full functionality
- STOP, WAIT, RUN full functionality



# 35.1.4 Operating modes

The following table shows the valid C0[MODE] and C1[AMPRI, AMPRF] settings. Using a reserved mode results in unpredictable behavior.

Table 35-1. Operating modes

C0[MODE]	C1[AMPRI]	C1[AMPRF]	Gain	Function		
00	xx	xxx	_	Buffer mode		
10	xx	xxx	_	General amplifier mode		
01	00	000	_	Reserved		
01	10		-1	Inverting PGA mode		
01	01		-2	Inverting PGA mode		
01	11		-3	Inverting PGA mode		
01	00	001	-8	Inverting PGA mode		
01	10		-9	Inverting PGA mode		
01	01		-10	Inverting PGA mode		
01	11		-11	Inverting PGA mode		
01	00	010	-4	Inverting PGA mode		
01	10		-5	Inverting PGA mode		
01	01		-6	Inverting PGA mode		
01	11		-7	Inverting PGA mode		
01	00	011	-12	Inverting PGA mode		
01	10		-13	Inverting PGA mode		
01	01		-14	Inverting PGA mode		
01	11		-15	Inverting PGA mode		
01	00	100	_	Reserved		
01	10		_	Reserved		
01	01		_	Reserved		
01	11		_	Reserved		
01	00	101	_	Reserved		
01	10		_	Reserved		
01	01		_	Reserved		
01	11		_	Reserved		



#### muroduction

Table 35-1. Operating modes (continued)

C0[MODE]	C1[AMPRI]	C1[AMPRF]	Gain	Function		
01	00	110		Reserved		
01	10		_	Reserved		
01	01		_	Reserved		
01	11		_	Reserved		
01	00	111	_	Reserved		
01	10		_	Reserved		
01	01		-16	Inverting PGA mode		
01	11		-17	Inverting PGA mode		
11	00	000	_	Reserved		
11	10		2	Non-inverting PGA mode		
11	01		3	Non-inverting PGA mode		
11	11		4	Non-inverting PGA mode		
11	00	001	9	Non-inverting PGA mode		
11	10		10	Non-inverting PGA mode		
11	01		11	Non-inverting PGA mode		
11	11		12	Non-inverting PGA mode		
11	00	010	5	Non-inverting PGA mode		
11	10		6	Non-inverting PGA mode		
11	01		7	Non-inverting PGA mode		
11	11		8	Non-inverting PGA mode		
11	00	011	13	Non-inverting PGA mode		
11	10		14	Non-inverting PGA mode		
11	01		15	Non-inverting PGA mode		
11	11		16	Non-inverting PGA mode		
11	00	100	_	Reserved		
11	10		_	Reserved		
11	01		_	Reserved		
11	11		_	Reserved		
11	00	101	_	Reserved		
11	10		_	Reserved		
11	01		_	Reserved		
11	11		_	Reserved		



Table 35-1. Operating modes (continued)

C0[MODE]	C1[AMPRI]	C1[AMPRF]	Gain	Function		
11	00	110	_	Reserved		
11	10		_	Reserved		
11	01		_	Reserved		
11	11		_	Reserved		
11	00	111	_	Reserved		
11	10		_	Reserved		
11	01		17	Non-inverting PGA mode		
11	11		18	Non-inverting PGA mode		

# 35.2 Signal Description

**Table 35-2. Signal Properties** 

Name	Description	I/O
INP <sub>x</sub> -	Amplifier positive input terminal	I
INP <sub>x</sub> +	INP <sub>x</sub> + Amplifier negative input terminal	
VOUT <sub>x</sub>	Amplifier output terminal	0

## 35.2.1 INP<sub>x</sub>+

The positive input terminal to the amplifier. This is an analog input terminal. See the *Data Sheet* for the value of input offset current and input bias current.

### 35.2.2 INP<sub>x</sub>-

The negative input terminal to the amplifier. This is an analog input terminal. See the *Data Sheet* for the value of input offset current and input bias current.

## 35.2.3 VOUT<sub>x</sub>

The output terminal of the amplifier. This is an analog output terminal.



# 35.3 Memory Map and Registers


This section provides a detailed description of all memory and registers.

#### **OPAMP** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400F_5000	Control Register 0 (OPAMP0_C0)	8	R/W	00h	35.3.1/ 828
400F_5001	Control Register 1 (OPAMP0_C1)	8	R/W	00h	35.3.2/ 829
400F_5002	Control Register 2 (OPAMP0_C2)	8	R/W	00h	35.3.3/ 830
400F_5800	Control Register 0 (OPAMP1_C0)	8	R/W	00h	35.3.1/ 828
400F_5801	Control Register 1 (OPAMP1_C1)	8	R/W	00h	35.3.2/ 829
400F_5802	Control Register 2 (OPAMP1_C2)	8	R/W	00h	35.3.3/ 830

# 35.3.1 Control Register 0 (OPAMPx\_C0)

Addresses: OPAMP0\_C0 is 400F\_5000h base + 0h offset = 400F\_5000h OPAMP1\_C0 is 400F\_5800h base + 0h offset = 400F\_5800h



## OPAMPx\_C0 field descriptions

Field	Description
7 EN	OPAMP Enable  0 OPAMP is disabled and not powered  1 OPAMP is enabled and powered
6 LPEN	Low-Power Mode Enable  Refer to the device data sheet's OPAMP electrical specifications for details on the impact of the modes below.




## **OPAMPx\_C0** field descriptions (continued)

Field	Description
	<ul> <li>High-speed mode selected. In this mode, OPAMP has faster slew rate and unity gain bandwidth performance with higher current consumption.</li> <li>Low-power mode selected. In this mode, OPAMP has lower current consumption with slower slew rate and unity gain bandwidth performance.</li> </ul>
5–2 Reserved	This read-only field is reserved and always has the value zero.
1–0 MODE	OPAMP Mode Select  00 Buffer 10 General purpose 01 Inverting PGA 11 Non-inverting PGA

# 35.3.2 Control Register 1 (OPAMPx\_C1)

Addresses: OPAMP0\_C1 is 400F\_5000h base + 1h offset = 400F\_5001h OPAMP1\_C1 is 400F\_5800h base + 1h offset = 400F\_5801h




## OPAMPx\_C1 field descriptions

Field	Description
7–5 Reserved	This read-only field is reserved and always has the value zero.
4–2 AMPRF	Gains Selector  See the Operating Modes table in a previous section for valid bitfield encodings.
1–0 AMPRI	Gains Selector  See the Operating Modes table in a previous section for valid bitfield encodings.



# 35.3.3 Control Register 2 (OPAMPx\_C2)

Addresses: OPAMP0\_C2 is 400F\_5000h base + 2h offset = 400F\_5002h OPAMP1\_C2 is 400F\_5800h base + 2h offset = 400F\_5802h



### OPAMPx\_C2 field descriptions

Field	Description
7 Reserved	This read-only field is reserved and always has the value zero.
6–4	Amplifier Positive Input Terminal Selector
AMPPSEL	Selects the positive input.
	<b>NOTE:</b> The input connections vary by device. See the Chip Configuration details for information on the connections to these inputs.
	000 Positive input 0
	001 Positive input 1
	010 Positive input 2
	011 Positive input 3
	100 Positive input 4
	101 Positive input 5
	110 Positive input 6
	111 Positive input 7
3 Reserved	This read-only field is reserved and always has the value zero.
2–0	Amplifier Negative Input Terminal Selector.
AMPNSEL	Selects the negative input.
	<b>NOTE:</b> The input connections vary by device. See the Chip Configuration details for information on the connections to these inputs.
	000 Negative input 0
	001 Negative input 1
	010 Negative input 2
	011 Negative input 3
	100 Negative input 4
	101 Negative input 5
	110 Negative input 6
	111 Negative input 7



# 35.4 Functional Description

This section provides a complete functional description of the OPAMP block, detailing the operation of the design from the end-user perspective.

# 35.4.1 Operational Amplifier Configuration

The following is a block diagram of the OPAMP module in general purpose mode.




Figure 35-11. Operational Amplifier Block Diagram in General Purpose Mode

## 35.4.2 Buffer Configuration

The following is a block diagram of the OPAMP module in buffer configuration mode.



#### runctional Description




Figure 35-12. Operational Amplifier Block Diagram in Buffered Configuration Mode

# 35.4.3 Non-Inverting/Inverting PGA Configuration

The following is a block diagram of the OPAMP module in non-inverting/inverting PGA configuration.






Figure 35-13. Operational Amplifier Block Diagram in Non-Inverting/Inverting PGA Mode



**runctional Description** 



# **Chapter 36 Transimpedance Amplifier (TRIAMP)**

#### 36.1 Introduction

#### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The TRIAMP block is a CMOS single supply, low input offset voltage, low input offset and bias current amplifier that is designed for low-voltage, low-power operation. The TRIAMP also has control settings that can be software-configured depending on application requirements. Timing and control consists of registers and control logic for operation in low-power modes.

## 36.1.1 Features

Features include:

- On-chip generation of bias voltages
- Low power, low voltage CMOS technology
- Low input offset voltage and current
- Low input bias current
- Low current consumption

# 36.1.2 Module operation in low power modes

The module operates in low power modes as follows:

- VLLSx module is off
- LLS module is static, and the register states are retained
- VLPS, VLPW, VLPR module is fully functional
- Normal stop, wait, run module is fully functional



# 36.1.3 Block Diagram

This diagram illustrates the TRIAMP module.




Figure 36-1. TRIAMP Block Diagram

# 36.1.4 Signal Description

Name

inp\_3v inn\_3v

out\_3v

The TRIAMP module has the following external pins.

Function Direction

Amplifier positive input terminal I

Amplifier negative input terminal

Amplifier output terminal

**Table 36-1. Signal Properties** 

# 36.1.5 inp\_3v

The positive input terminal to the amplifier. This is an analog input terminal.

# 36.1.6 inn\_3v

The negative input terminal to the amplifier. This is an analog input terminal.

# 36.1.7 out\_3v

The output terminal to the amplifier. This is an analog output terminal.

ı

0




# 36.2 Memory Map/Register Definition

#### **TRIAMP** memory map

Absolute address (hex)	Register name		Access	Reset value	Section/ page
400F_8000	Control Register 0 (TRIAMP0_C0) 8 R/W 00h		36.2.1/ 837		
400F_8800	Control Register 0 (TRIAMP1_C0)	8	R/W	00h	36.2.1/ 837

## 36.2.1 Control Register 0 (TRIAMPx\_C0)

Addresses: TRIAMP0\_C0 is 400F\_8000h base + 0h offset = 400F\_8000h TRIAMP1\_C0 is 400F\_8800h base + 0h offset = 400F\_8800h



#### TRIAMPx\_C0 field descriptions

Field	Description
7 TRIAMPEN	TRIAMP Enable  0 The amplifier is disabled and not powered.
	1 TRIAMP system is enabled. In this mode the amplifier is powered and enabled.
6 LPEN	Low-Power Enable  The LPEN bit is power level control bit. Refer to the device data sheet's TRIAMP electrical specifications for details on the impact of the modes below.
	<ul> <li>High-speed mode selected. In this mode, TRIAMP has faster slew rate and unity gain bandwidth performance with higher current consumption.</li> <li>Low-power mode selected. In this mode, TRIAMP has lower current consumption with slower slew rate and unity gain bandwidth performance.</li> </ul>
5–0 Reserved	This read-only field is reserved and always has the value zero.



# 36.3 Functional Description

This section provides a complete functional description of the TRIAMP block, detailing the operation of the design from the end-user perspective.

# 36.3.1 Trans-Impedance Amplifier Configuration

# 36.3.2 Photodiode Zero-Biased Operation

The following figure shows a typical application (supply is 3 V) diagram of the TRIAMP module.

#### NOTE

An ideal operational amplifier model is shown.




Figure 36-5. Zero-Biased Application Diagram

# 36.3.3 Photodiode Reverse-Biased Operation

The following figure shows a typical application (3V supply) diagram of the TRIAMP module.

#### NOTE

An ideal operational amplifier model is shown.






Figure 36-6. Reverse-Biased Application Diagram

### Table 36-8. TRIAMP Module

I <sub>photo</sub>	$R_{f}\left(\Omega\right)$	V <sub>dac</sub> (V)	$OUT = I_{photo} \times R_f + V_{dac}$
1 nA	1M	0.2	0.201 V
10 nA	1M	0.2	0.210 V
100 nA	1M	0.2	0.3 V
1 µA	1M	0.2	1.2 V
10 nA	100 k	0.2	0.201 V
100 nA	100 k	0.2	0.21 V
1 µA	100 k	0.2	0.3 V
10 µA	100 k	0.2	1.2 V
100 nA	10 k	0.2	0.201 V
1 μ <b>A</b>	10 k	0.2	0.21V
10 µA	10 k	0.2	0.3 V
100 µA	10 k	0.2	1.2 V



**runctional Description** 



# **Chapter 37 Voltage Reference (VREFV1)**

## 37.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The VREFV1 Voltage Reference is intended to supply an accurate voltage output that can be trimmed in 0.5 mV steps. The VREFV1 can be used in applications to provide a reference voltage to external devices or used internally as a reference to analog peripherals such as the ADC, DAC, or CMP. The voltage reference has two operating modes that provide different levels of supply rejection and power consumption.

The following figure is a block diagram of the Voltage Reference.



#### muroduction




Figure 37-1. Voltage reference block diagram

## 37.1.1 Overview

The Voltage Reference provides a buffered reference voltage with high output current for use as an external reference. In addition, the buffered reference is available internally for use with on chip peripherals such as ADCs and DACs. Refer to the chip configuration chapter for a description of these options. The reference voltage is output on a dedicated output pin when the VREF is enabled. The Voltage Reference output can be trimmed with a resolution of 0.5mV by means of the TRM register TRIM[5:0] bitfield.

## 37.1.2 Features

The Voltage Reference has the following features:

- Programmable trim register with 0.5 mV steps, automatically loaded with factory trimmed value upon reset
- Programmable buffer mode selection:
  - Off



- Bandgap enabled/standby (output buffer disabled)
- Tight-regulation buffer mode (output buffer enabled)
- 1.2 V output at room temperature
- Dedicated output pin, VREF\_OUT
- Load regulation in tight-regulation mode

# 37.1.3 Modes of Operation

The Voltage Reference continues normal operation in Run, Wait, and Stop modes. The Voltage Reference can also run in Very Low Power Run (VLPR), Very Low Power Wait (VLPW) and Very Low Power Stop (VLPS). The VREF regulator is not available in any Very Low Power modes and must be disabled (SC[REGEN]=0) before entering these modes. Note however that the accuracy of the output voltage will be reduced (by as much as several mVs) when the VREF regulator is not used.

#### NOTE

The assignment of module modes to core modes is chipspecific. For module-to-core mode assignments, see the chapter that describes how modules are configured.

# 37.1.4 VREF Signal Descriptions

The following table shows the Voltage Reference signals properties.

**Table 37-1. VREF Signal Descriptions** 

Signal	Description	I/O
VREF_OUT	Internally-generated Voltage Reference output	0

#### NOTE

• In Disable mode, the status of the VREF\_OUT signal is high-impedence.

# 37.2 Memory Map and Register Definition

#### wemory Map and Register Definition


## **VREF** memory map

Absolute address (hex)	Register name		Access	Reset value	Section/ page
4007_4000	VREF Trim Register (VREF_TRM)	8	R/W	Undefined	37.2.1/ 844
4007_4001	VREF Status and Control Register (VREF_SC)	8	R/W	00h	37.2.2/ 845

# 37.2.1 VREF Trim Register (VREF\_TRM)

This register contains bits that contain the trim data for the Voltage Reference.

Address: VREF\_TRM is 4007\_4000h base + 0h offset = 4007\_4000h



<sup>\*</sup> Notes:

## **VREF\_TRM** field descriptions

Field	Description
7 Reserved	This field is reserved. Upon reset this value is loaded with a factory trim value.
6 Reserved	This bit must always be written with the original reset value.  This read-only field is reserved and always has the value zero.
5–0 TRIM	Trim bits
	Upon reset this value is loaded with a factory trim value.  These bits change the resulting VREF by approximately ± 0.5 mV for each step.
	NOTE: Min = minimum and max = maximum voltage reference output. For minimum and maximum voltage reference output values, refer to the Data Sheet for this chip.
	000000 Min
	111111 Max

<sup>•</sup> x = Undefined at reset.



# 37.2.2 VREF Status and Control Register (VREF\_SC)

This register contains the control bits used to enable the internal voltage reference and to select the VREF mode to be used.

Address: VREF\_SC is 4007\_4000h base + 1h offset = 4007\_4001h



### **VREF\_SC** field descriptions

Field	Description
7 VREFEN	Internal Voltage Reference enable
VIILILIA	This bit is used to enable the bandgap reference within the Voltage Reference module.
	<b>NOTE:</b> After the VREF is enabled, turning off the clock to the VREF module via the corresponding clock gate register will not disable the VREF. VREF must be disabled via this VREFEN bit.
	<ul><li>The module is disabled.</li><li>The module is enabled.</li></ul>
6	Regulator enable
REGEN	This bit is used to enable the internal 1.75 V VREF regulator to produce a constant internal voltage supply in order to reduce the sensitivity to external supply noise and variation. The VREF regulator must not be enabled when entering VLPR, VLPW or VLPS modes.
	0 Internal 1.75 V regulator is disabled.
	1 Internal 1.75 V regulator is enabled.
5 Reserved	This field is reserved. This bit must always be written to zero.
4 Reserved	This read-only field is reserved and always has the value zero.
3 Reserved	This read-only field is reserved and always has the value zero.
2	Internal Voltage Reference has settled
VREFST	This bit indicates that the bandgap reference within the Voltage Reference module has completed its startup and stabilization.
	0 The bandgap is disabled or not ready.
	1 The bandgap is ready.
1-0	Buffer Mode selection
MODE_LV	These bits select the buffer modes for the Voltage Reference module.
	00 Bandgap on only, for stabilization and startup
	01 Reserved

Table continues on the next page...



#### **runctional Description**

#### **VREF\_SC** field descriptions (continued)

Field	Description		
	10 Tight-regulation buffer enabled		
	11 Reserved		

# 37.3 Functional Description

The Voltage Reference is a bandgap buffer system. Unity gain amplifiers are used.

The VREF\_OUT signal is available as an internal reference when it is enabled. A 100 nF capacitor must be connected between VREF\_OUT and VSSA.

The following table shows all possible function configurations of the Voltage Reference.

Table 37-5. Voltage Reference function configurations

SC[VREFEN]	SC[MODE_LV]	Configuration	Functionality
0	X	Voltage Reference disabled	Off
1	00	Voltage Reference enabled, only the VREF bandgap is on	Startup and standby
1	01	Reserved	Reserved
1	10	Voltage Reference enabled, VREF bandgap and tight- regulation buffer on	VREF_OUT available for internal and external use. 100 nF capacitor is required.
1	11	Reserved	Reserved

# 37.3.1 Voltage Reference Disabled, SC[VREFEN] = 0

When SC[VREFEN] = 0, the Voltage Reference is disabled, all bandgap and buffers are disabled. The Voltage Reference is in off mode.

# 37.3.2 Voltage Reference Enabled, SC[VREFEN] = 1

When SC[VREFEN] = 1, the Voltage Reference is enabled, and different modes can be set by the SC[MODE\_LV] bits.



## 37.3.2.1 SC[MODE\_LV]=00

The internal bandgap is enabled to generate an accurate 1.2 V output that can be trimmed with the TRM register's TRIM[5:0] bitfield. The bandgap requires some time for startup and stabilization. SC[VREFST] can be monitored to determine if the stabilization and startup is complete.

The output buffer is disabled in this mode, and there is no buffered voltage output. The Voltage Reference is in standby mode. If this mode is first selected and the tight regulation buffer mode is subsequently enabled, there will be a delay before the buffer output is settled at the final value. This is the buffer start up delay (Tstup) and the value is specified in the appropriate device data sheet.

## $37.3.2.2 SC[MODE_LV] = 01$

Reserved

## 37.3.2.3 SC[MODE\_LV] = 10

The tight regulation buffer is enabled to generate a buffered 1.2 V voltage to VREF\_OUT. If this mode is entered from the standby mode (SC[MODE\_LV] = 00, SC[VREFEN] = 1) there will be a delay before the buffer output is settled at the final value. This is the buffer start up delay (Tstup) and the value is specified in the appropriate device data sheet. If this mode is entered when the VREF module is enabled then you must wait the longer of Tstup or until SC[VREFST] = 1.

## 37.3.2.4 SC[MODE\_LV] = 11

Reserved

# 37.4 Initialization/Application Information

The Voltage Reference requires some time for startup and stabilization. After SC[VREFEN] = 1, SC[VREFST] can be monitored to determine if the stabilization and startup of the VREF bandgap is complete.



#### mualization/Application Information

When the Voltage Reference is already enabled and stabilized, changing SC[MODE\_LV] will not clear SC[VREFST] but there will be some startup time before the output voltage at the VREF\_OUT pin has settled. This is the buffer start up delay (Tstup) and the value is specified in the appropriate device data sheet. Also, there will be some settling time when a step change of the load current is applied to the VREF\_OUT pin.

When the 1.75V VREF regulator is disabled, the VREF\_OUT voltage will be more sensitive to supply voltage variation. It is recommended to use this regulator to achieve optimum VREF\_OUT performance.



# **Chapter 38**Programmable Delay Block (PDB)

#### 38.1 Introduction

#### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The programmable delay block (PDB) provides controllable delays from either an internal or an external trigger, or a programmable interval tick, to the hardware trigger inputs of ADCs and/or generates the interval triggers to DACs, so that the precise timing between ADC conversions and/or DAC updates can be achieved. The PDB can optionally provides pulse outputs (Pulse-Out's) that are used as the sample window in the CMP block.

## 38.1.1 Features

- Up to 15 trigger input sources and software trigger source
- Up to eight configurable PDB channels for ADC hardware trigger
  - One PDB channel is associated with one ADC.
  - One trigger output for ADC hardware trigger and up to eight pre-trigger outputs for ADC trigger select per PDB channel
  - Trigger outputs can be enabled or disabled independently.
  - One 16-bit delay register per pre-trigger output
  - Optional bypass of the delay registers of the pre-trigger outputs
  - Operation in One-Shot or Continuous modes



#### muroduction

- Optional back-to-back mode operation, which enables the ADC conversions complete to trigger the next PDB channel
- One programmable delay interrupt
- One sequence error interrupt
- One channel flag and one sequence error flag per pre-trigger
- DMA support
- Up to eight DAC interval triggers
  - One interval trigger output per DAC
  - One 16-bit delay interval register per DAC trigger output
  - Optional bypass the delay interval trigger registers
  - Optional external triggers
- Up to eight pulse outputs (pulse-out's)
  - Pulse-out's can be enabled or disabled independently.
  - Programmable pulse width

#### NOTE

The number of PDB input and output triggers are chip-specific. Refer to the Chip Configuration information for details.

## 38.1.2 Implementation

In this chapter, the following letters refers to the number of output triggers.

- *N* Total available number of PDB channels.
- *n* PDB channel number, valid from 0 to *N*-1.
- *M* Total available pre-trigger per PDB channel.
- *m* Pre-trigger number, valid from 0 to *M*-1.
- *X* Total number of DAC interval triggers.
- x DAC interval trigger output number, valid from 0 to X-1.



- *Y* Total number of Pulse-Out's.
- y Pulse-Out number, valid value is 0 to Y-1.

#### NOTE

The number of module output triggers to core are chip-specific. For module to core output triggers implementation, refer to the Chip Configuration information.

# 38.1.3 Back-to-back Acknowledgement Connections

PDB back-to-back operation acknowledgment connections are chip-specific. For implementation, refer to the Chip Configuration information.

# 38.1.4 DAC External Trigger Input Connections

The implementation of DAC external trigger inputs is chip-specific. Refer to the Chip Configuration information for details.

## 38.1.5 Block Diagram

This diagram illustrates the major components of the PDB.



#### muroduction




Figure 38-1. PDB Block Diagram

In this diagram, only one PDB channel *n*, one DAC interval trigger *x*, and one Pulse-Out *y* is shown. The PDB enable control logic and the sequence error interrupt logic is not shown.



## 38.1.6 Modes of Operation

PDB ADC trigger operates in the following modes.

**Disabled**: Counter is off, all pre-trigger and trigger outputs are low if PDB is not in back-to-back operation of Bypass mode.

**Debug**: Counter is paused when processor is in debug mode, the counter for dac trigger also paused in Debug mode.

**Enabled One-Shot**: Counter is enabled and restarted at count zero upon receiving a positive edge on the selected trigger input source or software trigger is selected and SC[SWTRIG] is written with 1. In each PDB channel, an enabled pre-trigger asserts once per trigger input event; the trigger output asserts whenever any of pre-triggers is asserted.

**Enabled Continuous**: Counter is enabled and restarted at count zero. The counter is rolled over to zero again when the count reaches the value specified in the modulus register, and the counting is restarted. This enables a continuous stream of pre-triggers/trigger outputs as a result of a single trigger input event.

**Enabled Bypassed**: The pre-trigger and trigger outputs assert immediately after a positive edge on the selected trigger input source or software trigger is selected and SC[SWTRIG] is written with 1, that is the delay registers are bypassed. It is possible to bypass any one or more of the delay registers; therefore this mode can be used in conjunction with One-Shot or Continuous mode.

# 38.2 PDB Signal Descriptions

This table shows the detailed description of the external signal.

Table 38-1. PDB Signal Descriptions

Signal	Description	I/O
EXTRG	External trigger input source. If the PDB is enabled and external trigger input source is selected, a positive edge on the EXTRG signal resets and starts the counter.	_

# 38.3 Memory Map and Register Definition



#### wemory Map and Register Definition


# PDB memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_6000	Status and Control Register (PDB0_SC)	32	R/W	0000_0000h	38.3.1/ 855
4003_6004	Modulus Register (PDB0_MOD)	32	R/W	0000_FFFFh	38.3.2/ 857
4003_6008	Counter Register (PDB0_CNT)	32	R	0000_0000h	38.3.3/ 858
4003_600C	Interrupt Delay Register (PDB0_IDLY)	32	R/W	0000_FFFFh	38.3.4/ 858
4003_6010	Channel n Control Register 1 (PDB0_CH0C1)	32	R/W	0000_0000h	38.3.5/ 859
4003_6014	Channel n Status Register (PDB0_CH0S)	32	w1c	0000_0000h	38.3.6/ 860
4003_6018	Channel n Delay 0 Register (PDB0_CH0DLY0)	32	R/W	0000_0000h	38.3.7/ 861
4003_601C	Channel n Delay 1 Register (PDB0_CH0DLY1)	32	R/W	0000_0000h	38.3.8/ 861
4003_6038	Channel n Control Register 1 (PDB0_CH1C1)	32	R/W	0000_0000h	38.3.5/ 859
4003_603C	Channel n Status Register (PDB0_CH1S)	32	w1c	0000_0000h	38.3.6/ 860
4003_6040	Channel n Delay 0 Register (PDB0_CH1DLY0)	32	R/W	0000_0000h	38.3.7/ 861
4003_6044	Channel n Delay 1 Register (PDB0_CH1DLY1)	32	R/W	0000_0000h	38.3.8/ 861
4003_6150	DAC Interval Trigger n Control Register (PDB0_DACINTC0)	32	R/W	0000_0000h	38.3.9/ 862
4003_6154	DAC Interval n Register (PDB0_DACINT0)	32	R/W	0000_0000h	38.3.10/ 862
4003_6158	DAC Interval Trigger n Control Register (PDB0_DACINTC1)	32	R/W	0000_0000h	38.3.9/ 862
4003_615C	DAC Interval n Register (PDB0_DACINT1)	32	R/W	0000_0000h	38.3.10/ 862
4003_6190	Pulse-Out n Enable Register (PDB0_POEN)	32	R/W	0000_0000h	38.3.11/ 863
4003_6194	Pulse-Out n Delay Register (PDB0_PO0DLY)	32	R/W	0000_0000h	38.3.12/ 863



# 38.3.1 Status and Control Register (PDBx\_SC)

Addresses: PDB0\_SC is 4003\_6000h base + 0h offset = 4003\_6000h



## PDBx\_SC field descriptions

Field	Description
31–20 Reserved	This read-only field is reserved and always has the value zero.
19–18 LDMOD	Load Mode Select  Selects the mode to load the MOD, IDLY, CHnDLYm, INTx, and POyDLY registers, after 1 is written to LDOK.  O The internal registers are loaded with the values from their buffers immediately after 1 is written to LDOK.  The internal registers are loaded with the values from their buffers when the PDB counter reaches the MOD register value after 1 is written to LDOK.  The internal registers are loaded with the values from their buffers when a trigger input event is detected after 1 is written to LDOK.  The internal registers are loaded with the values from their buffers when either the PDB counter
17 PDBEIE	reaches the MOD register value or a trigger input event is detected, after 1 is written to LDOK.  PDB Sequence Error Interrupt Enable  This bit enables the PDB sequence error interrupt. When this bit is set, any of the PDB channel sequence error flags generates a PDB sequence error interrupt.  0 PDB sequence error interrupt disabled. 1 PDB sequence error interrupt enabled.
16 SWTRIG	Software Trigger  When PDB is enabled and the software trigger is selected as the trigger input source, writing 1 to this bit reset and restarts the counter. Writing 0 to this bit has no effect. Reading this bit results 0.

Table continues on the next page...



#### wemory Map and Register Definition

# PDBx\_SC field descriptions (continued)

Field	Description	
15	DMA Enable	
DMAEN	When DMA is enabled, the PDBIF flag generates a DMA request instead of an interrupt.	
	0 DMA disabled	
	1 DMA enabled	
14–12	Prescaler Divider Select	
PRESCALER	Trescaler Divider Select	
	000 Counting uses the peripheral clock divided by multiplication factor selected by MULT.	
	001 Counting uses the peripheral clock divided by twice of the multiplication factor selected by MULT.	
	O10 Counting uses the peripheral clock divided by four times of the multiplication factor selected by MULT.	
	O11 Counting uses the peripheral clock divided by eight times of the multiplication factor selected by MULT.	
	100 Counting uses the peripheral clock divided by 16 times of the multiplication factor selected by MULT.	
	101 Counting uses the peripheral clock divided by 32 times of the multiplication factor selected by MULT.	
	Counting uses the peripheral clock divided by 64 times of the multiplication factor selected by MULT.	
	111 Counting uses the peripheral clock divided by 128 times of the multiplication factor selected by MULT.	
11–8	Trigger Input Source Select	
TRGSEL	Selects the trigger input source for the PDB. The trigger input source can be internal or external (EXTRG	
	pin), or the software trigger.	
	0000 Trigger-In 0 is selected	
	0001 Trigger-In 1 is selected	
	0010 Trigger-In 2 is selected	
	0011 Trigger-In 3 is selected	
	0100 Trigger-In 4 is selected	
	0101 Trigger-In 5 is selected	
	0110 Trigger-In 6 is selected	
	0111 Trigger-In 7 is selected	
	1000 Trigger-In 8 is selected	
	1001 Trigger-In 9 is selected	
	1010 Trigger-In 10 is selected	
	1011 Trigger-In 11 is selected	
	1100 Trigger-In 12 is selected	
	1101 Trigger-In 13 is selected	
	1110 Trigger-In 14 is selected	
	1111 Software trigger is selected	
7 PDBEN	PDB Enable	
	0 PDB disabled. Counter is off.	
	1 PDB enabled	
6	PDB Interrupt Flag	
PDBIF		

Table continues on the next page...




## PDBx\_SC field descriptions (continued)

Field	Description
	This bit is set when the counter value is equal to the IDLY register. Writing zero clears this bit.
5 PDBIE	PDB Interrupt Enable.
	This bit enables the PDB interrupt. When this bit is set and DMAEN is cleared, PDBIF generates a PDB interrupt.
	0 PDB interrupt disabled
	1 PDB interrupt enabled
4 Reserved	This read-only field is reserved and always has the value zero.
3–2	Multiplication Factor Select for Prescaler
MULT	This bit selects the multiplication factor of the prescaler divider for the counter clock.
	00 Multiplication factor is 1
	01 Multiplication factor is 10
	10 Multiplication factor is 20
	11 Multiplication factor is 40
1 CONT	Continuous Mode Enable
CONT	This bit enables the PDB operation in Continuous mode.
	0 PDB operation in One-Shot mode
	1 PDB operation in Continuous mode
0	Load OK
LDOK	Writing 1 to this bit updates the internal registers of MOD, IDLY, CHnDLYm, DACINTx, and POyDLY with the values written to their buffers. The MOD, IDLY, CHnDLYm, DACINTx, and POyDLY will take effect according to the LDMOD.
	After 1 is written to LDOK bit, the values in the buffers of above registers are not effective and the buffers cannot be written until the values in buffers are loaded into their internal registers.
	LDOK can be written only when PDBEN is set or it can be written at the same time with PDBEN being written to 1. It is automatically cleared when the values in buffers are loaded into the internal registers or the PDBEN is cleared. Writing 0 to it has no effect.

# 38.3.2 Modulus Register (PDBx\_MOD)

Addresses: PDB0\_MOD is 4003\_6000h base + 4h offset = 4003\_6004h






#### memory Map and Register Definition

## PDBx\_MOD field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 MOD	PDB Modulus.  These bits specify the period of the counter. When the counter reaches this value, it will be reset back to zero. If the PDB is in Continuous mode, the count begins anew. Reading these bits returns the value of internal register that is effective for the current cycle of PDB.

# 38.3.3 Counter Register (PDBx\_CNT)

Addresses: PDB0\_CNT is 4003\_6000h base + 8h offset = 4003\_6008h




#### PDBx\_CNT field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 CNT	PDB Counter  These read-only bits contain the current value of the counter.

# 38.3.4 Interrupt Delay Register (PDBx\_IDLY)

Addresses: PDB0\_IDLY is 4003\_6000h base + Ch offset = 4003\_600Ch



#### PDBx\_IDLY field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 IDLY	PDB Interrupt Delay

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




### PDBx\_IDLY field descriptions (continued)

Field	Description
	These bits specify the delay value to schedule the PDB interrupt. It can be used to schedule an independent interrupt at some point in the PDB cycle. If enabled, a PDB interrupt is generated, when the counter is equal to the IDLY. Reading these bits returns the value of internal register that is effective for the current cycle of the PDB.

## 38.3.5 Channel n Control Register 1 (PDBx\_CHC1)

Each PDB channel has one Control Register, CHnC1. The bits in this register control the functionality of each PDB channel operation.

Addresses: PDB0\_CH0C1 is 4003\_6000h base + 10h offset = 4003\_6010h PDB0\_CH1C1 is 4003\_6000h base + 38h offset = 4003\_6038h



#### PDBx\_CHnC1 field descriptions

Field	Description
31–24 Reserved	This read-only field is reserved and always has the value zero.
23–16 BB	PDB Channel Pre-Trigger Back-to-Back Operation Enable  These bits enable the PDB ADC pre-trigger operation as back-to-back mode. Only lower M pre-trigger bits are implemented in this MCU. Back-to-back operation enables the ADC conversions complete to trigger the next PDB channel pre-trigger and trigger output, so that the ADC conversions can be triggered on next set of configuration and results registers. Application code must only enable the back-to-back operation of the PDB pre-triggers at the leading of the back-to-back connection chain.  O PDB channel's corresponding pre-trigger back-to-back operation disabled.  PDB channel's corresponding pre-trigger back-to-back operation enabled.
15–8 TOS	PDB Channel Pre-Trigger Output Select  These bits select the PDB ADC pre-trigger outputs. Only lower M pre-trigger bits are implemented in this MCU.  O PDB channel's corresponding pre-trigger is in bypassed mode. The pre-trigger asserts one peripheral clock cycle after a rising edge is detected on selected trigger input source or software trigger is selected and SWTRIG is written with 1.  PDB channel's corresponding pre-trigger asserts when the counter reaches the channel delay register plus one peripheral clock cycle after a rising edge is detected on selected trigger input source or software trigger is selected and SETRIG is written with 1.
7–0 EN	PDB Channel Pre-Trigger Enable

Table continues on the next page...




#### wemory Map and Register Definition

## PDBx\_CHnC1 field descriptions (continued)

Field	Description
	These bits enable the PDB ADC pre-trigger outputs. Only lower M pre-trigger bits are implemented in this MCU.
	<ul><li>0 PDB channel's corresponding pre-trigger disabled.</li><li>1 PDB channel's corresponding pre-trigger enabled.</li></ul>

# 38.3.6 Channel n Status Register (PDBx\_CHS)

Addresses: PDB0\_CH0S is 4003\_6000h base + 14h offset = 4003\_6014h PDB0\_CH1S is 4003\_6000h base + 3Ch offset = 4003\_603Ch




#### PDBx\_CHnS field descriptions

Field	Description
31–24 Reserved	This read-only field is reserved and always has the value zero.
23–16 CF	PDB Channel Flags  The CF[m] bit is set when the PDB counter matches the CHnDLYm. Write 0 to clear these bits.
15–8 Reserved	This read-only field is reserved and always has the value zero.
7–0 ERR	<ul> <li>PDB Channel Sequence Error Flags</li> <li>Only the lower M bits are implemented in this MCU.</li> <li>Sequence error not detected on PDB channel's corresponding pre-trigger.</li> <li>Sequence error detected on PDB channel's corresponding pre-trigger. ADCn block can be triggered for a conversion by one pre-trigger from PDB channel n. When one conversion, which is triggered by one of the pre-triggers from PDB channel n, is in progress, new trigger from PDB channel's corresponding pre-trigger m cannot be accepted by ADCn, and ERR[m] is set. Writing 1's to clear the sequence error flags.</li> </ul>



## 38.3.7 Channel n Delay 0 Register (PDBx\_CHDLY0)

Addresses: PDB0\_CH0DLY0 is 4003\_6000h base + 18h offset = 4003\_6018h PDB0\_CH1DLY0 is 4003\_6000h base + 40h offset = 4003\_6040h




## PDBx\_CHnDLY0 field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 DLY	PDB Channel Delay  These bits specify the delay value for the channel's corresponding pre-trigger. The pre-trigger asserts when the counter is equal to DLY. Reading these bits returns the value of internal register that is effective for the current PDB cycle.

## 38.3.8 Channel n Delay 1 Register (PDBx\_CHDLY1)

Addresses: PDB0\_CH0DLY1 is 4003\_6000h base + 1Ch offset = 4003\_601Ch PDB0\_CH1DLY1 is 4003\_6000h base + 44h offset = 4003\_6044h




#### PDBx\_CHnDLY1 field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 DLY	PDB Channel Delay  These bits specify the delay value for the channel's corresponding pre-trigger. The pre-trigger asserts when the counter is equal to DLY. Reading these bits returns the value of internal register that is effective for the current PDB cycle.



# 38.3.9 DAC Interval Trigger n Control Register (PDBx\_DACINTCn)

Addresses: PDB0\_DACINTC0 is 4003\_6000h base + 150h offset = 4003\_6150h PDB0\_DACINTC1 is 4003\_6000h base + 158h offset = 4003\_6158h




#### PDBx\_DACINTCn field descriptions

Field	Description
31–2 Reserved	This read-only field is reserved and always has the value zero.
1 EXT	DAC External Trigger Input Enable
	This bit enables the external trigger for DAC interval counter.
	0 DAC external trigger input disabled. DAC interval counter is reset and started counting when a rising edge is detected on selected trigger input source or software trigger is selected and SWTRIG is written with 1.
	1 DAC external trigger input enabled. DAC interval counter is bypassed and DAC external trigger input triggers the DAC interval trigger.
0 TOE	DAC Interval Trigger Enable
IOL	This bit enables the DAC interval trigger.
	DAC interval trigger disabled.
	1 DAC interval trigger enabled.

## 38.3.10 DAC Interval n Register (PDBx\_DACINTn)

Addresses: PDB0\_DACINT0 is 4003\_6000h base + 154h offset = 4003\_6154h PDB0\_DACINT1 is 4003\_6000h base + 15Ch offset = 4003\_615Ch



#### PDBx\_DACINTn field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




### PDBx\_DACINTn field descriptions (continued)

Field	Description
15–0 INT	DAC Interval  These bits specify the interval value for DAC interval trigger. DAC interval trigger triggers DAC[1:0] update when the DAC interval counter is equal to the DACINT. Reading these bits returns the value of internal register that is effective for the current PDB cycle.

## 38.3.11 Pulse-Out n Enable Register (PDBx\_POEN)

Addresses: PDB0\_POEN is 4003\_6000h base + 190h offset = 4003\_6190h




#### PDBx\_POEN field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7–0 POEN	PDB Pulse-Out Enable  These bits enable the pulse output. Only lower Y bits are implemented in this MCU.  0 PDB Pulse-Out disabled 1 PDB Pulse-Out enabled

# 38.3.12 Pulse-Out n Delay Register (PDBx\_PODLY)

Addresses: PDB0\_PO0DLY is 4003\_6000h base + 194h offset = 4003\_6194h



#### PDBx\_POnDLY field descriptions

Field	Description
31–16 DLY1	PDB Pulse-Out Delay 1

Table continues on the next page...



#### **runctional Description**

#### PDBx\_POnDLY field descriptions (continued)

Field	Description
	These bits specify the delay 1 value for the PDB Pulse-Out. Pulse-Out goes high when the PDB counter is equal to the DLY1. Reading these bits returns the value of internal register that is effective for the current PDB cycle.
15–0 DLY2	PDB Pulse-Out Delay 2  These bits specify the delay 2 value for the PDB Pulse-Out. Pulse-Out goes low when the PDB counter is equal to the DLY2. Reading these bits returns the value of internal register that is effective for the current PDB cycle.

# 38.4 Functional Description

# 38.4.1 PDB Pre-trigger and Trigger Outputs

The PDB contains a counter whose output is compared against several different digital values. If the PDB is enabled, a trigger input event will reset the counter and make it start to count. A trigger input event is defined as a rising edge being detected on selected trigger input source or software trigger being selected and SC[SWTRIG] is written with 1. For each channel, delay *m* determines the time between assertion of the trigger input event to the point at which changes in the pre-trigger *m* output signal is initiated. The time is defined as:

- Trigger input event to pre-trigger m = (prescaler X multiplication factor X delay <math>m) + 2 peripheral clock cycles
- Add one additional peripheral clock cycle to determine the time at which the channel trigger output change.

Each channel is associated with one ADC block. PDB channel n pre-trigger outputs 0 to M and trigger output is connected to ADC hardware trigger select and hardware trigger inputs. The pre-triggers are used to precondition the ADC block prior to the actual trigger. The ADC contains M sets of configuration and result registers, allowing it to operate in a ping-pong fashion, alternating conversions between M different analog sources. The pre-trigger outputs are used to specify which signal will be sampled next. When pre-trigger m is asserted, the ADC conversion is triggered with set m of the configuration and result registers.

The waveforms shown in the following diagram illuminate the pre-trigger and trigger outputs of PDB channel n. The delays can be independently set via the CHnDLYm registers. And the pre-triggers can be enabled or disabled in CHnC1[EN[m]].






Figure 38-52. Pre-trigger and Trigger Outputs

The delay in CHnDLYm register can be optionally bypassed, if CHnC1[TOS[m]] is cleared. In this case, when the trigger input event occurs, the pre-trigger m is asserted after two peripheral clock cycles.

The PDB can be configured in back-to-back (B2B) operation. B2B operation enables the ADC conversions complete to trigger the next PDB channel pre-trigger and trigger outputs, so that the ADC conversions can be triggered on next set of configuration and results registers. When B2B is enabled by setting CHnC1[BB[m]], the delay m is ignored and the pre-trigger m is asserted two peripheral cycles after the acknowledgment m is received. The acknowledgment connections in this MCU is described in Back-to-back Acknowledgment Connections.

When an ADC conversion, which is triggered by one of the pre-triggers from PDB channel n, is in progress and ADCnSC1[COCO] is not set, a new trigger from PDB channel n pre-trigger m cannot be accepted by ADCn. Therefore every time when one PDB channel n pre-trigger and trigger output starts an ADC conversion, an internal lock associated with the corresponding pre-trigger is activated. The lock becomes inactive when the corresponding ADCnSC1[COCO] is set, or the corresponding PDB pre-trigger is disabled, or the PDB is disabled. The channel n trigger output is suppressed when any of the locks of the pre-triggers in channel n is active. If a new pre-trigger m asserts when there is active lock in the PDB channel n, a register flag bit, CHnS[ERR[m]], associated with the pre-trigger m is set. If SC[PDBEIE] is set, the sequence error interrupt is generated. Sequence error is typically happened because the delay m is set too short and the pre-trigger m asserts before the previous triggered ADC conversion is completed.

When the PDB counter reaches the value set in IDLY register, the SC[PDBIF] flag is set. A PDB interrupt can be generated if SC[PDBIE] is set and SC[DMAEN] is cleared. If SC[DMAEN] is set, PDB requests a DMA transfer when SC[PDBIF] is set.

The modulus value in MOD register, is used to reset the counter back to zero at the end of the count. If SC[CONT] bit is set, the counter will then resume a new count. Otherwise, the counter operation will cease until the next trigger input event occurs.



## 38.4.2 PDB Trigger Input Source Selection

The PDB has up to 15 trigger input sources, namely Trigger-In 0 to 14. They are connected to on-chip or off-chip event sources. The PDB can be triggered by software through the SC[SWTRIG]. SC[TRIGSEL] bits select the active trigger input source or software trigger.

For the trigger input sources implemented in this MCU, refer to Chip Configuration information.

## 38.4.3 DAC Interval Trigger Outputs

PDB can generate the interval triggers for DACs to update their outputs periodically. DAC interval counter x is reset and started when a trigger input event occurs if DACINTCx[EXT] is cleared. When the interval counter x is equal to the value set in DACINTx register, the DAC interval trigger x output generates a pulse of one peripheral clock cycle width to update the DACx. If DACINTCx[EXT] is set, the DAC interval counter is bypassed and the interval trigger output x generates a pulse following the detection of a rising edge on the DAC external trigger input. The counter and interval trigger can be disabled by clearing the DACINTCx[TOE].

DAC interval counters are also reset when the PDB counter reaches the MOD register value, therefore when the PDB counter rolls over to zero, the DAC interval counters starts anew.

Together, the DAC interval trigger pulse and the ADC pre-trigger/trigger pulses allow precise timing of DAC updates and ADC measurements. This is outlined in the typical use case described in the following diagram.






Figure 38-53. PDB ADC Triggers and DAC Interval Triggers Use Case

#### NOTE

Because the DAC interval counters share the prescaler with PDB counter, PDB must be enabled if the DAC interval trigger outputs are used in the applications.

#### 38.4.4 Pulse-Out's

PDB can generate pulse outputs of configurable width. When PDB counter reaches the value set in POyDLY[DLY1], the Pulse-Out goes high; when the counter reaches POyDLY[DLY2], it goes low. POyDLY[DLY2] can be set either greater or less than POyDLY[DLY1].

Because the PDB counter is shared by both ADC pre-trigger/trigger outputs and Pulse-Out generation, they have the same time base.

The pulse-out connections implemented in this MCU are described in the device's Chip Configuration details.

## 38.4.5 Updating the Delay Registers

The following registers control the timing of the PDB operation; and in some of the applications, they may need to become effective at the same time.



#### **runctional Description**

- PDB Modulus Register (MOD)
- PDB Interrupt Delay Register (IDLY)
- PDB Channel *n* Delay *m* Register (CH*n*DLY*m*)
- DAC Interval x Register (DACINTx)
- PDB Pulse-Out y Delay Register (POyDLY)

The internal registers of them are buffered and any values written to them are written first to their buffers. The circumstances that cause their internal registers to be updated with the values from the buffers are summarized as below table.

Update to the Delay Registers

The internal registers are loaded with the values from their buffers immediately after 1 is written to SC[LDOK].

The PDB counter reaches the MOD register value after 1 is written to SC[LDOK].

A trigger input event is detected after 1 is written to SC[LDOK].

A trigger input event is detected after 1 is written to SC[LDOK].

Either the PDB counter reaches the MOD register value, or a trigger input event is detected, after 1 is written to SC[LDOK].

Table 38-54. Circumstances of Update to the Delay Registers

After 1 is written to SC[LDOK], the buffers cannot be written until the values in buffers are loaded into their internal registers. SC[LDOK] is self-cleared when the internal registers are loaded, so the application code can read it to determine the updates of the internal registers.

The following diagrams show the cases of the internal registers being updated with SC[LDMOD] is 00 and x1.




Figure 38-54. Registers Update with SC[LDMOD] = 00






Figure 38-55. Registers Update with SC[LDMOD] = x1

## 38.4.6 Interrupts

PDB can generate two interrupts, PDB interrupt and PDB sequence error interrupt. The following table summarizes the interrupts.

 Interrupt
 Flags
 Enable Bit

 PDB Interrupt
 SC[PDBIF]
 SC[PDBIE] = 1 and SC[DMAEN] = 0

 PDB Sequence Error Interrupt
 CHnS[ERRm]
 SC[PDBEIE] = 1

Table 38-55. PDB Interrupt Summary

#### 38.4.7 DMA

If SC[DMAEN] is set, PDB can generate DMA transfer request when SC[PDBIF] is set. When DMA is enabled, the PDB interrupt will not be issued.

## 38.5 Application Information

## 38.5.1 Impact of Using the Prescaler and Multiplication Factor on Timing Resolution

Use of prescaler and multiplication factor greater than 1 limits the count/delay accuracy in terms of peripheral clock cycles (to the modulus of the prescaler X multiplication factor). If the multiplication factor is set to 1 and the prescaler is set to 2 then the only



#### Application Information

values of total peripheral clocks that can be detected are even values; if prescaler is set to 4 then the only values of total peripheral clocks that can be decoded as detected are mod(4) and so forth. If the applications need a really long delay value and use 128, then the resolution would be limited to 128 peripheral clock cycles.

Therefore, use the lowest possible prescaler and multiplication factor for a given application.



# **Chapter 39 FlexTimer (FTM)**

#### 39.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The FlexTimer Module (FTM) is a two to eight channel timer which supports input capture, output compare, and the generation of PWM signals to control electric motor and power management applications. The FTM time reference is a 16-bit counter that can be used as an unsigned or signed counter.

## 39.1.1 FlexTimer Philosophy

The FlexTimer is built upon a very simple timer (HCS08 Timer PWM Module – TPM) used for many years on Freescales 8 bit microcontrollers. The FlexTimer extends the functionality to meet the demands of motor control, digital lighting solutions and power conversion yet providing low cost and backwards compatibility with the TPM module.

Several key enhancements are made; signed up counter, deadtime insertion hardware, fault control inputs, enhanced triggering functionality and initialization and polarity control.

All the features common with the TPM module have fully backwards compatible register assignments and the FlexTimer can use code on the same core platform without change to perform the same functions.

Motor control and power conversion features have been added through a dedicated set of registers and defaults turn off all new features. The new features such as hardware deadtime insertion, polarity, fault control and output forcing and masking greatly reduce loading on the execution software and are usually each controlled by a group of registers.



#### muroduction

FlexTimer input triggers can be from comparators, ADC or other sub modules to initiate timer functions automatically. These triggers can be linked in a variety of ways during integration of the sub modules so please note carefully the options available for used FlexTimer configuration.

Several FlexTimers may be synchronized to provide a larger timer with their counters incrementing in unison, assuming the initialization, the input clocks, the initial and final counting values are the same in each FlexTimer.

All main user access registers are buffered to ease the load on the executing software. A number of trigger options exist to determine which registers are updated with this user defined data.

#### **39.1.2 Features**

The FTM features include:

- FTM source clock is selectable
  - Source clock can be the system clock, the fixed frequency clock, or an external clock
  - Fixed frequency clock is an additional clock input to allow the selection of an on chip clock source other than the system clock
  - Selecting external clock connects FTM clock to a chip level input pin therefore allowing to synchronize the FTM counter with an off chip clock source
- Prescaler divide-by 1, 2, 4, 8, 16, 32, 64, or 128
- FTM has a 16-bit counter
  - It can be a free-running counter or a counter with initial and final value
  - The counting can be up or up-down
- Each channel can be configured for input capture, output compare, or edge-aligned PWM mode
- In input capture mode
  - the capture can occur on rising edges, falling edges or both edges
  - an input filter can be selected for some channels
- In output compare mode the output signal can be set, cleared, or toggled on match
- All channels can be configured for center-aligned PWM mode



- Each pair of channels can be combined to generate a PWM signal (with independent control of both edges of PWM signal)
- The FTM channels can operate as pairs with equal outputs, pairs with complementary outputs, or independent channels (with independent outputs)
- The deadtime insertion is available for each complementary pair
- Generation of triggers (match trigger)
- Software control of PWM outputs
- Up to 4 fault inputs for global fault control
- The polarity of each channel is configurable
- The generation of an interrupt per channel
- The generation of an interrupt when the counter overflows
- The generation of an interrupt when the fault condition is detected
- Synchronized loading of write buffered FTM registers
- Write protection for critical registers
- Backwards compatible with TPM
- Testing of input captures for a stuck at zero and one conditions
- Dual edge capture for pulse and period width measurement
- Quadrature decoder with input filters, relative position counting and interrupt on position count or capture of position count on external event

## 39.1.3 Modes of Operation

When the MCU is in an active BDM mode, the FTM temporarily suspends all counting until the MCU returns to normal user operating mode. During stop mode, all FTM input clocks are stopped, so the FTM is effectively disabled until clocks resume. During wait mode, the FTM continues to operate normally. If the FTM does not need to produce a real time reference or provide the interrupt sources needed to wake the MCU from wait mode, the power can then be saved by disabling FTM functions before entering wait mode.



muroduction

## 39.1.4 Block Diagram

The FTM uses one input/output (I/O) pin per channel, CHn (FTM channel (n)) where n is the channel number (0–7).

The following figure shows the FTM structure. The central component of the FTM is the 16-bit counter with programmable initial and final values and its counting can be up or up-down.






Figure 39-1. FTM Block Diagram

## 39.2 FTM Signal Descriptions

Table 39-1 shows the user-accessible signals for the FTM.

**Table 39-1. FTM Signal Descriptions** 

Signal	Description	I/O
EXTCLK	External clock. FTM external clock can be selected to drive the FTM counter.	I
CHn	FTM channel (n), where n can be 7-0	I/O
FAULTj	Fault input (j), where j can be 3-0	I
PHA	Quadrature decoder phase A input. Input pin associated with quadrature decoder phase A.	I
PHB	Quadrature decoder phase B input. Input pin associated with quadrature decoder phase B.	I

#### 39.2.1 EXTCLK — FTM External Clock

The external clock input signal is used as the FTM counter clock if selected by CLKS[1:0] bits in the SC register. This clock signal must not exceed 1/4 of system clock frequency. The FTM counter prescaler selection and settings are also used when an external clock is selected.

## 39.2.2 CHn — FTM Channel (n) I/O Pin

Each FTM channel can be configured to operate either as input or output. The direction associated with each channel, input or output, is selected according to the mode assigned for that channel.

## 39.2.3 FAULTj — FTM Fault Input

The fault input signals are used to control the CHn channel output state. If a fault is detected, the FAULTj signal is asserted and the channel output is put in a safe state. The behavior of the fault logic is defined by the FAULTM[1:0] control bits in the MODE register and FAULTEN bit in the COMBINEm register. Note that each FAULTj input may affect all channels selectively since FAULTM[1:0] and FAULTEN control bits are



defined for each pair of channels. Since there are several FAULTj inputs, maximum of 4 for the FTM module, each one of these inputs is activated by the FAULTjEN bit in the FLTCTRL register.

## 39.2.4 PHA — FTM Quadrature Decoder Phase A Input

The quadrature decoder phase A input is used as the quadrature decoder mode is selected. The phase A input signal is one of the signals that control the FTM counter increment or decrement in the quadrature decoder mode (Quadrature Decoder Mode).

## 39.2.5 PHB — FTM Quadrature Decoder Phase B Input

The quadrature decoder phase B input is used as the quadrature decoder mode is selected. The phase B input signal is one of the signals that control the FTM counter increment or decrement in the quadrature decoder mode (Quadrature Decoder Mode).

## 39.3 Memory Map and Register Definition

This section provides a detailed description of all FTM registers.

## 39.3.1 Module Memory Map

This section presents a high-level summary of the FTM registers and how they are mapped.

The first set has the original TPM registers.

The second set has the FTM specific registers. Any second set registers (or bits within these registers) that are used by an unavailable function in the FTM configuration remain in the memory map and in the reset value, so they have no active function.

#### **Note**

Do not write to the FTM specific registers (second set registers) when FTMEN = 0.



## 39.3.2 Register Descriptions

This section consists of register descriptions in address order.

Accesses to reserved addresses result in transfer errors. Registers for absent channels are considered reserved.

#### **FTM** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_8000	Status and Control (FTM0_SC)	32	R/W	0000_0000h	39.3.3/ 884
4003_8004	Counter (FTM0_CNT)	32	R/W	0000_0000h	39.3.4/ 885
4003_8008	Modulo (FTM0_MOD)	32	R/W	0000_0000h	39.3.5/ 886
4003_800C	Channel (n) Status and Control (FTM0_C0SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_8010	Channel (n) Value (FTM0_C0V)	32	R/W	0000_0000h	39.3.7/ 890
4003_8014	Channel (n) Status and Control (FTM0_C1SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_8018	Channel (n) Value (FTM0_C1V)	32	R/W	0000_0000h	39.3.7/ 890
4003_801C	Channel (n) Status and Control (FTM0_C2SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_8020	Channel (n) Value (FTM0_C2V)	32	R/W	0000_0000h	39.3.7/ 890
4003_8024	Channel (n) Status and Control (FTM0_C3SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_8028	Channel (n) Value (FTM0_C3V)	32	R/W	0000_0000h	39.3.7/ 890
4003_802C	Channel (n) Status and Control (FTM0_C4SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_8030	Channel (n) Value (FTM0_C4V)	32	R/W	0000_0000h	39.3.7/ 890
4003_8034	Channel (n) Status and Control (FTM0_C5SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_8038	Channel (n) Value (FTM0_C5V)	32	R/W	0000_0000h	39.3.7/ 890
4003_803C	Channel (n) Status and Control (FTM0_C6SC)	32	R/W	0000_0000h	39.3.6/ 887



## FTM memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_8040	Channel (n) Value (FTM0_C6V)	32	R/W	0000_0000h	39.3.7/ 890
4003_8044	Channel (n) Status and Control (FTM0_C7SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_8048	Channel (n) Value (FTM0_C7V)	32	R/W	0000_0000h	39.3.7/ 890
4003_804C	Counter Initial Value (FTM0_CNTIN)	32	R/W	0000_0000h	39.3.8/ 891
4003_8050	Capture and Compare Status (FTM0_STATUS)	32	R/W	0000_0000h	39.3.9/ 891
4003_8054	Features Mode Selection (FTM0_MODE)	32	R/W	0000_0004h	39.3.10/ 894
4003_8058	Synchronization (FTM0_SYNC)	32	R/W	0000_0000h	39.3.11/ 895
4003_805C	Initial State for Channels Output (FTM0_OUTINIT)	32	R/W	0000_0000h	39.3.12/ 898
4003_8060	Output Mask (FTM0_OUTMASK)	32	R/W	0000_0000h	39.3.13/ 899
4003_8064	Function for Linked Channels (FTM0_COMBINE)	32	R/W	0000_0000h	39.3.14/ 901
4003_8068	Deadtime Insertion Control (FTM0_DEADTIME)	32	R/W	0000_0000h	39.3.15/ 906
4003_806C	FTM External Trigger (FTM0_EXTTRIG)	32	R/W	0000_0000h	39.3.16/ 907
4003_8070	Channels Polarity (FTM0_POL)	32	R/W	0000_0000h	39.3.17/ 909
4003_8074	Fault Mode Status (FTM0_FMS)	32	R/W	0000_0000h	39.3.18/ 911
4003_8078	Input Capture Filter Control (FTM0_FILTER)	32	R/W	0000_0000h	39.3.19/ 913
4003_807C	Fault Control (FTM0_FLTCTRL)	32	R/W	0000_0000h	39.3.20/ 915
4003_8080	Quadrature Decoder Control and Status (FTM0_QDCTRL)	32	R/W	0000_0000h	39.3.21/ 917
4003_8084	Configuration (FTM0_CONF)	32	R/W	0000_0000h	39.3.22/ 919
4003_8088	FTM Fault Input Polarity (FTM0_FLTPOL)	32	R/W	0000_0000h	39.3.23/ 920
4003_808C	Synchronization Configuration (FTM0_SYNCONF)	32	R/W	0000_0000h	39.3.24/ 922



#### wemory Map and Register Definition

## FTM memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_8090	FTM Inverting Control (FTM0_INVCTRL)	32	R/W	0000_0000h	39.3.25/ 924
4003_8094	FTM Software Output Control (FTM0_SWOCTRL)	32	R/W	0000_0000h	39.3.26/ 925
4003_8098	FTM PWM Load (FTM0_PWMLOAD)	32	R/W	0000_0000h	39.3.27/ 927
4003_9000	Status and Control (FTM1_SC)	32	R/W	0000_0000h	39.3.3/ 884
4003_9004	Counter (FTM1_CNT)	32	R/W	0000_0000h	39.3.4/ 885
4003_9008	Modulo (FTM1_MOD)	32	R/W	0000_0000h	39.3.5/ 886
4003_900C	Channel (n) Status and Control (FTM1_C0SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9010	Channel (n) Value (FTM1_C0V)	32	R/W	0000_0000h	39.3.7/ 890
4003_9014	Channel (n) Status and Control (FTM1_C1SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9018	Channel (n) Value (FTM1_C1V)	32	R/W	0000_0000h	39.3.7/ 890
4003_901C	Channel (n) Status and Control (FTM1_C2SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9020	Channel (n) Value (FTM1_C2V)	32	R/W	0000_0000h	39.3.7/ 890
4003_9024	Channel (n) Status and Control (FTM1_C3SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9028	Channel (n) Value (FTM1_C3V)	32	R/W	0000_0000h	39.3.7/ 890
4003_902C	Channel (n) Status and Control (FTM1_C4SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9030	Channel (n) Value (FTM1_C4V)	32	R/W	0000_0000h	39.3.7/ 890
4003_9034	Channel (n) Status and Control (FTM1_C5SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9038	Channel (n) Value (FTM1_C5V)	32	R/W	0000_0000h	39.3.7/ 890
4003_903C	Channel (n) Status and Control (FTM1_C6SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9040	Channel (n) Value (FTM1_C6V)	32	R/W	0000_0000h	39.3.7/ 890



## FTM memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_9044	Channel (n) Status and Control (FTM1_C7SC)	32	R/W	0000_0000h	39.3.6/ 887
4003_9048	Channel (n) Value (FTM1_C7V)	32	R/W	0000_0000h	39.3.7/ 890
4003_904C	Counter Initial Value (FTM1_CNTIN)	32	R/W	0000_0000h	39.3.8/ 891
4003_9050	Capture and Compare Status (FTM1_STATUS)	32	R/W	0000_0000h	39.3.9/ 891
4003_9054	Features Mode Selection (FTM1_MODE)	32	R/W	0000_0004h	39.3.10/ 894
4003_9058	Synchronization (FTM1_SYNC)	32	R/W	0000_0000h	39.3.11/ 895
4003_905C	Initial State for Channels Output (FTM1_OUTINIT)	32	R/W	0000_0000h	39.3.12/ 898
4003_9060	Output Mask (FTM1_OUTMASK)	32	R/W	0000_0000h	39.3.13/ 899
4003_9064	Function for Linked Channels (FTM1_COMBINE)	32	R/W	0000_0000h	39.3.14/ 901
4003_9068	Deadtime Insertion Control (FTM1_DEADTIME)	32	R/W	0000_0000h	39.3.15/ 906
4003_906C	FTM External Trigger (FTM1_EXTTRIG)	32	R/W	0000_0000h	39.3.16/ 907
4003_9070	Channels Polarity (FTM1_POL)	32	R/W	0000_0000h	39.3.17/ 909
4003_9074	Fault Mode Status (FTM1_FMS)	32	R/W	0000_0000h	39.3.18/ 911
4003_9078	Input Capture Filter Control (FTM1_FILTER)	32	R/W	0000_0000h	39.3.19/ 913
4003_907C	Fault Control (FTM1_FLTCTRL)	32	R/W	0000_0000h	39.3.20/ 915
4003_9080	Quadrature Decoder Control and Status (FTM1_QDCTRL)	32	R/W	0000_0000h	39.3.21/ 917
4003_9084	Configuration (FTM1_CONF)	32	R/W	0000_0000h	39.3.22/ 919
4003_9088	FTM Fault Input Polarity (FTM1_FLTPOL)	32	R/W	0000_0000h	39.3.23/ 920
4003_908C	Synchronization Configuration (FTM1_SYNCONF)	32	R/W	0000_0000h	39.3.24/ 922
4003_9090	FTM Inverting Control (FTM1_INVCTRL)	32	R/W	0000_0000h	39.3.25/ 924



#### wemory Map and Register Definition

## FTM memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_9094	FTM Software Output Control (FTM1_SWOCTRL)	32	R/W	0000_0000h	39.3.26/ 925
4003_9098	FTM PWM Load (FTM1_PWMLOAD)	32	R/W	0000_0000h	39.3.27/ 927
400B_8000	Status and Control (FTM2_SC)	32	R/W	0000_0000h	39.3.3/ 884
400B_8004	Counter (FTM2_CNT)	32	R/W	0000_0000h	39.3.4/ 885
400B_8008	Modulo (FTM2_MOD)	32	R/W	0000_0000h	39.3.5/ 886
400B_800C	Channel (n) Status and Control (FTM2_C0SC)	32	R/W	0000_0000h	39.3.6/ 887
400B_8010	Channel (n) Value (FTM2_C0V)	32	R/W	0000_0000h	39.3.7/ 890
400B_8014	Channel (n) Status and Control (FTM2_C1SC)	32	R/W	0000_0000h	39.3.6/ 887
400B_8018	Channel (n) Value (FTM2_C1V)	32	R/W	0000_0000h	39.3.7/ 890
400B_801C	Channel (n) Status and Control (FTM2_C2SC)	32	R/W	0000_0000h	39.3.6/ 887
400B_8020	Channel (n) Value (FTM2_C2V)	32	R/W	0000_0000h	39.3.7/ 890
400B_8024	Channel (n) Status and Control (FTM2_C3SC)	32	R/W	0000_0000h	39.3.6/ 887
400B_8028	Channel (n) Value (FTM2_C3V)	32	R/W	0000_0000h	39.3.7/ 890
400B_802C	Channel (n) Status and Control (FTM2_C4SC)	32	R/W	0000_0000h	39.3.6/ 887
400B_8030	Channel (n) Value (FTM2_C4V)	32	R/W	0000_0000h	39.3.7/ 890
400B_8034	Channel (n) Status and Control (FTM2_C5SC)	32	R/W	0000_0000h	39.3.6/ 887
400B_8038	Channel (n) Value (FTM2_C5V)	32	R/W	0000_0000h	39.3.7/ 890
400B_803C	Channel (n) Status and Control (FTM2_C6SC)	32	R/W	0000_0000h	39.3.6/ 887
400B_8040	Channel (n) Value (FTM2_C6V)	32	R/W	0000_0000h	39.3.7/ 890
400B_8044	Channel (n) Status and Control (FTM2_C7SC)	32	R/W	0000_0000h	39.3.6/ 887



## FTM memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400B_8048	Channel (n) Value (FTM2_C7V)	32	R/W	0000_0000h	39.3.7/ 890
400B_804C	Counter Initial Value (FTM2_CNTIN)	32	R/W	0000_0000h	39.3.8/ 891
400B_8050	Capture and Compare Status (FTM2_STATUS)	32	R/W	0000_0000h	39.3.9/ 891
400B_8054	Features Mode Selection (FTM2_MODE)	32	R/W	0000_0004h	39.3.10/ 894
400B_8058	Synchronization (FTM2_SYNC)	32	R/W	0000_0000h	39.3.11/ 895
400B_805C	Initial State for Channels Output (FTM2_OUTINIT)	32	R/W	0000_0000h	39.3.12/ 898
400B_8060	Output Mask (FTM2_OUTMASK)	32	R/W	0000_0000h	39.3.13/ 899
400B_8064	Function for Linked Channels (FTM2_COMBINE)	32	R/W	0000_0000h	39.3.14/ 901
400B_8068	Deadtime Insertion Control (FTM2_DEADTIME)	32	R/W	0000_0000h	39.3.15/ 906
400B_806C	FTM External Trigger (FTM2_EXTTRIG)	32	R/W	0000_0000h	39.3.16/ 907
400B_8070	Channels Polarity (FTM2_POL)	32	R/W	0000_0000h	39.3.17/ 909
400B_8074	Fault Mode Status (FTM2_FMS)	32	R/W	0000_0000h	39.3.18/ 911
400B_8078	Input Capture Filter Control (FTM2_FILTER)	32	R/W	0000_0000h	39.3.19/ 913
400B_807C	Fault Control (FTM2_FLTCTRL)	32	R/W	0000_0000h	39.3.20/ 915
400B_8080	Quadrature Decoder Control and Status (FTM2_QDCTRL)	32	R/W	0000_0000h	39.3.21/ 917
400B_8084	Configuration (FTM2_CONF)	32	R/W	0000_0000h	39.3.22/ 919
400B_8088	FTM Fault Input Polarity (FTM2_FLTPOL)	32	R/W	0000_0000h	39.3.23/ 920
400B_808C	Synchronization Configuration (FTM2_SYNCONF)	32	R/W	0000_0000h	39.3.24/ 922
400B_8090	FTM Inverting Control (FTM2_INVCTRL)	32	R/W	0000_0000h	39.3.25/ 924
400B_8094	FTM Software Output Control (FTM2_SWOCTRL)	32	R/W	0000_0000h	39.3.26/ 925





## FTM memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400B_8098	FTM PWM Load (FTM2_PWMLOAD)	32	R/W	0000_0000h	39.3.27/ 927

## 39.3.3 Status and Control (FTMx\_SC)

SC contains the overflow status flag and control bits used to configure the interrupt enable, FTM configuration, clock source, and prescaler factor. These controls relate to all channels within this module.





#### FTMx\_SC field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 TOF	Timer Overflow Flag  Set by hardware when the FTM counter passes the value in the MOD register. The TOF bit is cleared by reading the SC register while TOF is set and then writing a 0 to TOF bit. Writing a 1 to TOF has no effect.  If another FTM overflow occurs between the read and write operations, the write operation has no effect; therefore, TOF remains set indicating an overflow has occurred. In this case a TOF interrupt request is not lost due to the clearing sequence for a previous TOF.  O FTM counter has not overflowed.  1 FTM counter has overflowed.
6 TOIE	Timer Overflow Interrupt Enable Enables FTM overflow interrupts.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### FTMx\_SC field descriptions (continued)

Field	Description
	0 Disable TOF interrupts. Use software polling.
	1 Enable TOF interrupts. An interrupt is generated when TOF equals one.
5	Center-aligned PWM Select
CPWMS	Selects CPWM mode. This mode configures the FTM to operate in up-down counting mode.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 FTM counter operates in up counting mode.
	1 FTM counter operates in up-down counting mode.
4–3	Clock Source Selection
CLKS	Selects one of the three FTM counter clock sources.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	00 No clock selected (This in effect disables the FTM counter.)
	01 System clock
	10 Fixed frequency clock
	11 External clock
2–0	Prescale Factor Selection
PS	Selects one of 8 division factors for the clock source selected by CLKS. The new prescaler factor affects the clock source on the next system clock cycle after the new value is updated into the register bits.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	000 Divide by 1
	001 Divide by 2
	010 Divide by 4
	011 Divide by 8
	100 Divide by 16
	101 Divide by 32
	110 Divide by 64
	111 Divide by 128

## 39.3.4 Counter (FTMx\_CNT)

The CNT register contains the FTM counter value.


Reset clears the CNT register. Writing any value to COUNT updates the counter with its initial value (CNTIN).

When BDM is active, the FTM counter is frozen (this is the value that you may read).



#### memory Map and Register Definition

Addresses: FTM0\_CNT is 4003\_8000h base + 4h offset = 4003\_8004h FTM1\_CNT is 4003\_9000h base + 4h offset = 4003\_9004h FTM2\_CNT is 400B\_8000h base + 4h offset = 400B\_8004h



#### FTMx\_CNT field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 COUNT	Counter value

## 39.3.5 Modulo (FTMx\_MOD)


The Modulo register contains the modulo value for the FTM counter. After the FTM counter reaches the modulo value, the overflow flag (TOF) becomes set at the next clock, and the next value of FTM counter depends on the selected counting method (Counter).

Writing to the MOD register latches the value into a buffer. The MOD register is updated with the value of its write buffer according to Registers Updated from Write Buffers.

If FTMEN = 0, this write coherency mechanism may be manually reset by writing to the SC register (whether BDM is active or not).

It is recommended to initialize the FTM counter (write to CNT) before writing to the MOD register to avoid confusion about when the first counter overflow will occur.

Addresses: FTM0\_MOD is 4003\_8000h base + 8h offset = 4003\_8008h FTM1\_MOD is 4003\_9000h base + 8h offset = 4003\_9008h FTM2\_MOD is 400B\_8000h base + 8h offset = 400B\_8008h



#### FTMx\_MOD field descriptions

Field	Description
31–16 Reserved	This field is reserved.



#### FTMx\_MOD field descriptions (continued)

Field	Description
15–0 MOD	Modulo value

## 39.3.6 Channel (n) Status and Control (FTMx\_CSC)

CnSC contains the channel-interrupt-status flag and control bits used to configure the interrupt enable, channel configuration, and pin function.

Table 39-67. Mode, Edge, and Level Selection

DE	CAPEN	COMBINE	CPWMS	MSnB:MSnA	ELSnB:ELSnA	Mode	Configuration
	X	Х	Х	XX	0	None	Pin not used for FTM



#### wemory Map and Register Definition


## Table 39-67. Mode, Edge, and Level Selection (continued)


DECAPEN	COMBINE	CPWMS	MSnB:MSnA	ELSnB:ELSnA	Mode	Configuration
0	0	0	0	1	Input capture	Capture on Rising Edge Only
				10		Capture on Falling Edge Only
				11		Capture on Rising or Falling Edge
			1	1	Output compare	Toggle Output on match
				10		Clear Output on match
				11		Set Output on match
			1X	10	Edge-aligned PWM	High-true pulses (clear Output on match)
				X1		Low-true pulses (set Output on match)
		1	XX	10	Center-aligned PWM	High-true pulses (clear Output on match-up)
				X1		Low-true pulses (set Output on match-up)
	1	0	XX	10	Combine PWM	High-true pulses (set on channel (n) match, and clear on channel (n+1) match)
				X1		Low-true pulses (clear on channel (n) match, and set on channel (n +1) match)
1	0	0	X0	See the following table	Dual Edge Capture Mode	One-shot capture mode
			X1	(Table 39-8).		Continuous capture mode



Table 39-68. Dual Edge Capture Mode — Edge Polarity Selection

ELSnB	ELSnA	Channel Port Enable	Detected Edges
0	0	Disabled	No edge
0	1	Enabled	Rising edge
1	0	Enabled	Falling edge
1	1	Enabled	Rising and falling edges





#### FTMx\_CnSC field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 CHF	Channel Flag  Set by hardware when an event occurs on the channel. CHF is cleared by reading the CSC register while CHnF is set and then writing a 0 to the CHF bit. Writing a 1 to CHF has no effect.
	If another event occurs between the read and write operations, the write operation has no effect; therefore, CHF remains set indicating an event has occurred. In this case a CHF interrupt request is not lost due to the clearing sequence for a previous CHF.
	0 No channel event has occurred.
	1 A channel event has occurred.
6 CHIE	Channel Interrupt Enable Enables channel interrupts.
	Disable channel interrupts. Use software polling.
	1 Enable channel interrupts.
5	Channel Mode Select
MSB	Used for further selections in the channel logic. Its functionality is dependent on the channel mode. See Table 39-7.



#### memory Map and Register Definition

#### FTMx\_CnSC field descriptions (continued)

Field	Description
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
4 MSA	Channel Mode Select
INIOA	Used for further selections in the channel logic. Its functionality is dependent on the channel mode. See Table 39-7.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
3	Edge or Level Select
ELSB	The functionality of ELSB and ELSA depends on the channel mode. See Table 39-7.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
2	Edge or Level Select
ELSA	The functionality of ELSB and ELSA depends on the channel mode. See Table 39-7.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
1 Reserved	This read-only field is reserved and always has the value zero.
0	DMA Enable
DMA	Enables DMA transfers for the channel.
	0 Disable DMA transfers.
	1 Enable DMA transfers.


## 39.3.7 Channel (n) Value (FTMx\_CV)


These registers contain the captured FTM counter value for the input modes or the match value for the output modes.

In input capture, capture test, and dual edge capture modes, any write to a CnV register is ignored.

In output modes, writing to a CnV register latches the value into a buffer. A CnV register is updated with the value of its write buffer according to Registers Updated from Write Buffers.

If FTMEN = 0, this write coherency mechanism may be manually reset by writing to the CnSC register (whether BDM mode is active or not).







#### FTMx\_CnV field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 VAL	Channel Value  Captured FTM counter value of the input modes or the match value for the output modes


## 39.3.8 Counter Initial Value (FTMx\_CNTIN)

The Counter Initial Value register contains the initial value for the FTM counter.

Writing to the CNTIN register latches the value into a buffer. The CNTIN register is updated with the value of its write buffer according to Registers Updated from Write Buffers.

The first time that the FTM clock is selected (first write to change the CLKS bits to a non-zero value), the FTM counter starts with the value 0x0000. To avoid this behavior, before the first write to select the FTM clock, write the new value to the the CNTIN register and then initialize the FTM counter (write any value to the CNT register).

Addresses: FTM0\_CNTIN is 4003\_8000h base + 4Ch offset = 4003\_804Ch FTM1\_CNTIN is 4003\_9000h base + 4Ch offset = 4003\_904Ch FTM2\_CNTIN is 400B\_8000h base + 4Ch offset = 400B\_804Ch



#### FTMx\_CNTIN field descriptions

Field	Description
31–16 Reserved	This field is reserved.
15–0 INIT	Initial Value of the FTM Counter

## 39.3.9 Capture and Compare Status (FTMx\_STATUS)

The STATUS register contains a copy of the status flag CHnF bit (in CnSC) for each FTM channel for software convenience.



#### wemory Map and Register Definition

0

0

0

0

0


Each CHnF bit in STATUS is a mirror of CHnF bit in CnSC. All CHnF bits can be checked using only one read of STATUS. All CHnF bits can be cleared by reading STATUS followed by writing 0x00 to STATUS.

Hardware sets the individual channel flags when an event occurs on the channel. CHF is cleared by reading STATUS while CHnF is set and then writing a 0 to the CHF bit. Writing a 1 to CHF has no effect.

If another event occurs between the read and write operations, the write operation has no effect; therefore, CHF remains set indicating an event has occurred. In this case a CHF interrupt request is not lost due to the clearing sequence for a previous CHF.

#### NOTE

The STATUS register should be used only combine mode.



#### FTMx STATUS field descriptions

0

0

0

0

0

0

0

0

0

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 CH7F	Channel 7 Flag  See the register description.  0 No channel event has occurred.  1 A channel event has occurred.
6 CH6F	Channel 6 Flag  See the register description.  0 No channel event has occurred.  1 A channel event has occurred.
5 CH5F	Channel 5 Flag  See the register description.

Table continues on the next page...

Reset




## FTMx\_STATUS field descriptions (continued)


Field	Description
	0 No channel event has occurred.
	1 A channel event has occurred.
4 CH4F	Channel 4 Flag
	See the register description.
	0 No channel event has occurred.
	1 A channel event has occurred.
3 CH3F	Channel 3 Flag
0.101	See the register description.
	No channel event has occurred.
	1 A channel event has occurred.
2 CH2F	Channel 2 Flag
OFIZI	See the register description.
	No channel event has occurred.
	1 A channel event has occurred.
1	Channel 1 Flag
CH1F	See the register description.
	No channel event has occurred.
	1 A channel event has occurred.
0 CH0F	Channel 0 Flag
0.101	See the register description.
	0 No channel event has occurred.
	1 A channel event has occurred.



## 39.3.10 Features Mode Selection (FTMx\_MODE)

This register contains the control bits used to configure the fault interrupt and fault control, capture test mode, PWM synchronization, write protection, channel output initialization, and enable the enhanced features of the FTM. These controls relate to all channels within this module.





#### FTMx\_MODE field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 FAULTIE	Fault Interrupt Enable  Enables the generation of an interrupt when a fault is detected by FTM and the FTM fault control is enabled.
	0 Fault control interrupt is disabled.
	1 Fault control interrupt is enabled.
6–5 FAULTM	Fault Control Mode
PAULTWI	Defines the FTM fault control mode.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	00 Fault control is disabled for all channels.
	01 Fault control is enabled for even channels only (channels 0, 2, 4, and 6), and the selected mode is the manual fault clearing.
	10 Fault control is enabled for all channels, and the selected mode is the manual fault clearing.
	11 Fault control is enabled for all channels, and the selected mode is the automatic fault clearing.



#### FTMx\_MODE field descriptions (continued)

Field	Description
4	Capture Test Mode Enable
CAPTEST	Enables the capture test mode.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	Capture test mode is disabled.
	1 Capture test mode is enabled.
3 PWMSYNC	PWM Synchronization Mode
PWMSYNC	Selects which triggers can be used by MOD, CnV, OUTMASK, and FTM counter synchronization (PWM Synchronization). The PWMSYNC bit configures the synchronization when SYNCMODE is zero.
	No restrictions. Software and hardware triggers can be used by MOD, CnV, OUTMASK, and FTM counter synchronization.
	1 Software trigger can only be used by MOD and CnV synchronization, and hardware triggers can only be used by OUTMASK and FTM counter synchronization.
2	Write Protection Disable
WPDIS	When write protection is enabled (WPDIS = 0), write protected bits can not be written. When write protection is disabled (WPDIS = 1), write protected bits can be written. The WPDIS bit is the negation of the WPEN bit. WPDIS is cleared when 1 is written to WPEN. WPDIS is set when WPEN bit is read as a 1 and then 1 is written to WPDIS. Writing 0 to WPDIS has no effect.
	0 Write protection is enabled.
	1 Write protection is disabled.
1	Initialize the Channels Output
INIT	When a 1 is written to INIT bit the channels output is initialized according to the state of their corresponding bit in the OUTINIT register. Writing a 0 to INIT bit has no effect.
	The INIT bit is always read as 0.
0	FTM Enable
FTMEN	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	Only the TPM-compatible registers (first set of registers) can be used without any restriction. Do not use the FTM-specific registers.
	1 All registers including the FTM-specific registers (second set of registers) are available for use with no restrictions.

## 39.3.11 Synchronization (FTMx\_SYNC)

This register configures the PWM synchronization.

A synchronization event can perform the synchronized update of MOD, CV, and OUTMASK registers with the value of their write buffer and the FTM counter initialization.





#### **NOTE**

The software trigger (SWSYNC bit) and hardware triggers (TRIG0, TRIG1, and TRIG2 bits) have a potential conflict if used together when SYNCMODE = 0. It is recommended using only hardware or software triggers but not both at the same time, otherwise unpredictable behavior is likely to happen.

The selection of the loading point (CNTMAX and CNTMIN bits) is intended to provide the update of MOD, CNTIN, and CnV registers across all enabled channels simultaneously. The use of the loading point selection together with SYNCMODE = 0 and hardware trigger selection (TRIG0, TRIG1, or TRIG2 bits) is likely to result in unpredictable behavior.

The synchronization event selection also depends on the PWMSYNC (MODE register) and SYNCMODE (SYNCONF register) bits. See PWM Synchronization.





#### FTMx\_SYNC field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 SWSYNC	PWM Synchronization Software Trigger  Selects the software trigger as the PWM synchronization trigger. The software trigger happens when a 1 is written to SWSYNC bit.



## FTMx\_SYNC field descriptions (continued)

Field	Description
	0 Software trigger is not selected.
	1 Software trigger is selected.
6 TRIG2	PWM Synchronization Hardware Trigger 2
	Enables hardware trigger 2 to the PWM synchronization. Hardware trigger 2 happens when a rising edge is detected at the trigger 2 input signal.
	0 Trigger is disabled.
_	1 Trigger is enabled.
5 TRIG1	PWM Synchronization Hardware Trigger 1
THICH	Enables hardware trigger 1 to the PWM synchronization. Hardware trigger 1 happens when a rising edge is detected at the trigger 1 input signal.
	<ul><li>0 Trigger is disabled.</li><li>1 Trigger is enabled.</li></ul>
4 TRIG0	PWM Synchronization Hardware Trigger 0
111130	Enables hardware trigger 0 to the PWM synchronization. Hardware trigger 0 happens when a rising edge is detected at the trigger 0 input signal.
	0 Trigger is disabled.
	1 Trigger is enabled.
3 SYNCHOM	Output Mask Synchronization
	Selects when the OUTMASK register is updated with the value of its buffer.
	<ul> <li>OUTMASK register is updated with the value of its buffer in all rising edges of the system clock.</li> <li>OUTMASK register is updated with the value of its buffer only by the PWM synchronization.</li> </ul>
2 REINIT	FTM Counter Reinitialization by Synchronization (FTM Counter Synchronization)
DEINIT	Determines if the FTM counter is reinitialized when the selected trigger for the synchronization is detected. The REINIT bit configures the synchronization when SYNCMODE is zero.
	0 FTM counter continues to count normally.
	1 FTM counter is updated with its initial value when the selected trigger is detected.
1 CNTMAX	Maximum loading point enable
2,,,,,,	Selects the maximum loading point to PWM synchronization (Boundary Cycle and Loading Points). If CNTMAX is one, the selected loading point is when the FTM counter reaches its maximum value (MOD register).
	0 The maximum loading point is disabled.
	1 The maximum loading point is enabled.
0 CNTMIN	Minimum loading point enable
	Selects the minimum loading point to PWM synchronization (Boundary Cycle and Loading Points). If CNTMIN is one, the selected loading point is when the FTM counter reaches its minimum value (CNTIN register).





#### wemory Map and Register Definition

#### FTMx\_SYNC field descriptions (continued)

Field	Description
	0 The minimum loading point is disabled.
	1 The minimum loading point is enabled.

## 39.3.12 Initial State for Channels Output (FTMx\_OUTINIT)





#### FTMx\_OUTINIT field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 CH7OI	Channel 7 Output Initialization Value  Selects the value that is forced into the channel output when the initialization occurs.
	<ul> <li>The initialization value is 0.</li> <li>The initialization value is 1.</li> </ul>
6 CH6OI	Channel 6 Output Initialization Value  Selects the value that is forced into the channel output when the initialization occurs.
	<ul><li>0 The initialization value is 0.</li><li>1 The initialization value is 1.</li></ul>
5 CH5OI	Channel 5 Output Initialization Value  Selects the value that is forced into the channel output when the initialization occurs.
	<ul><li>0 The initialization value is 0.</li><li>1 The initialization value is 1.</li></ul>
4 CH4OI	Channel 4 Output Initialization Value  Selects the value that is forced into the channel output when the initialization occurs.
	<ul><li>0 The initialization value is 0.</li><li>1 The initialization value is 1.</li></ul>
3 CH3OI	Channel 3 Output Initialization Value




#### FTMx\_OUTINIT field descriptions (continued)

Field	Description
	Selects the value that is forced into the channel output when the initialization occurs.
	0 The initialization value is 0.
	1 The initialization value is 1.
2 CH2OI	Channel 2 Output Initialization Value
011201	Selects the value that is forced into the channel output when the initialization occurs.
	0 The initialization value is 0.
	1 The initialization value is 1.
1	Channel 1 Output Initialization Value
CH10I	Selects the value that is forced into the channel output when the initialization occurs.
	0 The initialization value is 0.
	1 The initialization value is 1.
0 CH0OI	Channel 0 Output Initialization Value
	Selects the value that is forced into the channel output when the initialization occurs.
	0 The initialization value is 0.
	1 The initialization value is 1.

## 39.3.13 Output Mask (FTMx\_OUTMASK)

This register provides a mask for each FTM channel. The mask of a channel determines if its output responds (that is, it is masked or not) when a match occurs. This feature is used for BLDC control where the PWM signal is presented to an electric motor at specific times to provide electronic commutation.

Any write to the OUTMASK register, stores the value in its write buffer. The register is updated with the value of its write buffer according to PWM Synchronization.





#### wemory Map and Register Definition

## FTMx\_OUTMASK field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7	Channel 7 Output Mask
CH7OM	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	<ul> <li>Channel output is not masked. It continues to operate normally.</li> <li>Channel output is masked. It is forced to its inactive state.</li> </ul>
6	Channel 6 Output Mask
CH6OM	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	0 Channel output is not masked. It continues to operate normally.
	1 Channel output is masked. It is forced to its inactive state.
5	Channel 5 Output Mask
CH5OM	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	O Channel output is not masked. It continues to operate normally.
	1 Channel output is masked. It is forced to its inactive state.
4	Channel 4 Output Mask
CH4OM	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	0 Channel output is not masked. It continues to operate normally.
	1 Channel output is masked. It is forced to its inactive state.
3	Channel 3 Output Mask
CH3OM	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	<ul> <li>Channel output is not masked. It continues to operate normally.</li> <li>Channel output is masked. It is forced to its inactive state.</li> </ul>
2	Channel 2 Output Mask
CH2OM	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	0 Channel output is not masked. It continues to operate normally.
	1 Channel output is masked. It is forced to its inactive state.
1	Channel 1 Output Mask
CH1OM	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	0 Channel output is not masked. It continues to operate normally.
	1 Channel output is masked. It is forced to its inactive state.




### FTMx\_OUTMASK field descriptions (continued)

Field	Description
0 CH0OM	Channel 0 Output Mask
	Defines if the channel output is masked (forced to its inactive state) or unmasked (it continues to operate normally).
	0 Channel output is not masked. It continues to operate normally.
	1 Channel output is masked. It is forced to its inactive state.

### 39.3.14 Function for Linked Channels (FTMx\_COMBINE)

This register contains the control bits used to configure the fault control, synchronization, deadtime insertion, dual edge capture mode, complementary, and combine mode for each pair of channels (n) and (n+1), where n equals 0, 2, 4, and 6.

Addresses: FTM0\_COMBINE is 4003\_8000h base + 64h offset = 4003\_8064h FTM1\_COMBINE is 4003\_9000h base + 64h offset = 4003\_9064h FTM2\_COMBINE is 400B\_8000h base + 64h offset = 400B\_8064h



### FTMx\_COMBINE field descriptions

Field	Description
31 Reserved	This read-only field is reserved and always has the value zero.
30 FAULTEN3	Fault Control Enable for n = 6  Enables the fault control in channels (n) and (n+1).  This field is write protected. It can be written only when MODE[WPDIS] = 1.  0 The fault control in this pair of channels is disabled.  1 The fault control in this pair of channels is enabled.



# FTMx\_COMBINE field descriptions (continued)

Field	Description
29	Synchronization Enable for n = 6
SYNCEN3	Enables PWM synchronization of registers C(n)V and C(n+1)V.
	0 The PWM synchronization in this pair of channels is disabled.
	1 The PWM synchronization in this pair of channels is enabled.
28 DTEN3	Deadtime Enable for n = 6
BILINO	Enables the deadtime insertion in the channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 The deadtime insertion in this pair of channels is disabled.
	1 The deadtime insertion in this pair of channels is enabled.
27 DECAP3	Dual Edge Capture Mode Captures for n = 6
BEOM	Enables the capture of the FTM counter value according to the channel (n) input event and the configuration of the dual edge capture bits.
	This field applies only when FTMEN = 1 and DECAPEN = 1.
	DECAP bit is cleared automatically by hardware if dual edge capture – one-shot mode is selected and when the capture of channel (n+1) event is made.
	0 The dual edge captures are inactive.
	1 The dual edge captures are active.
26 DECAPEN3	Dual Edge Capture Mode Enable for n = 6
DECAFENS	Enables the dual edge capture mode in the channels (n) and (n+1). This bit reconfigures the function of MSnA, ELSnB:ELSnA and ELS(n+1)B:ELS(n+1)A bits in dual edge capture mode according to Table 39-7.
	This field applies only when FTMEN = 1.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul><li>The dual edge capture mode in this pair of channels is disabled.</li><li>The dual edge capture mode in this pair of channels is enabled.</li></ul>
25	Complement of Channel (n) for n = 6
COMP3	Enables complementary mode for the combined channels. In complementary mode the channel (n+1) output is the inverse of the channel (n) output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	The channel (n+1) output is the same as the channel (n) output.
	1 The channel (n+1) output is the complement of the channel (n) output.
24 COMPINES	Combine Channels for n = 6
COMBINE3	Enables the combine feature for channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Channels (n) and (n+1) are independent.
	1 Channels (n) and (n+1) are combined.



# FTMx\_COMBINE field descriptions (continued)

Field	Description
23 Reserved	This read-only field is reserved and always has the value zero.
22	Fault Control Enable for n = 4
FAULTEN2	Enables the fault control in channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The fault control in this pair of channels is disabled.</li> <li>The fault control in this pair of channels is enabled.</li> </ul>
21 SYNCEN2	Synchronization Enable for n = 4
STINCEINZ	Enables PWM synchronization of registers C(n)V and C(n+1)V.
	<ul> <li>The PWM synchronization in this pair of channels is disabled.</li> <li>The PWM synchronization in this pair of channels is enabled.</li> </ul>
20 DTEN2	Deadtime Enable for n = 4
DIENZ	Enables the deadtime insertion in the channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The deadtime insertion in this pair of channels is disabled.</li> <li>The deadtime insertion in this pair of channels is enabled.</li> </ul>
19	Dual Edge Capture Mode Captures for n = 4
DECAP2	Enables the capture of the FTM counter value according to the channel (n) input event and the configuration of the dual edge capture bits.
	This field applies only when FTMEN = 1 and DECAPEN = 1.
	DECAP bit is cleared automatically by hardware if dual edge capture – one-shot mode is selected and when the capture of channel (n+1) event is made.
	0 The dual edge captures are inactive.
	1 The dual edge captures are active.
18 DECAPEN2	Dual Edge Capture Mode Enable for n = 4
DEO/II LIVE	Enables the dual edge capture mode in the channels (n) and (n+1). This bit reconfigures the function of MSnA, ELSnB:ELSnA and ELS(n+1)B:ELS(n+1)A bits in dual edge capture mode according to Table 39-7.
	This field applies only when FTMEN = 1.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The dual edge capture mode in this pair of channels is disabled.</li> <li>The dual edge capture mode in this pair of channels is enabled.</li> </ul>
17	Complement of Channel (n) for n = 4
COMP2	Enables complementary mode for the combined channels. In complementary mode the channel (n+1) output is the inverse of the channel (n) output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.



# FTMx\_COMBINE field descriptions (continued)

Field	Description
	0 The channel (n+1) output is the same as the channel (n) output.
	1 The channel (n+1) output is the complement of the channel (n) output.
16	Combine Channels for n = 4
COMBINE2	Enables the combine feature for channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Channels (n) and (n+1) are independent.
	1 Channels (n) and (n+1) are combined.
15 Reserved	This read-only field is reserved and always has the value zero.
14	Fault Control Enable for n = 2
FAULTEN1	Enables the fault control in channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 The fault control in this pair of channels is disabled.
	1 The fault control in this pair of channels is enabled.
13 SYNCEN1	Synchronization Enable for n = 2
STROENT	Enables PWM synchronization of registers C(n)V and C(n+1)V.
	0 The PWM synchronization in this pair of channels is disabled.
	1 The PWM synchronization in this pair of channels is enabled.
12 DTEN1	Deadtime Enable for n = 2
BILIVI	Enables the deadtime insertion in the channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 The deadtime insertion in this pair of channels is disabled.
	1 The deadtime insertion in this pair of channels is enabled.
11 DECAP1	Dual Edge Capture Mode Captures for n = 2
220/11	Enables the capture of the FTM counter value according to the channel (n) input event and the configuration of the dual edge capture bits.
	This field applies only when FTMEN = 1 and DECAPEN = 1.
	DECAP bit is cleared automatically by hardware if dual edge capture – one-shot mode is selected and when the capture of channel (n+1) event is made.
	0 The dual edge captures are inactive.
	1 The dual edge captures are active.
10 DECAPEN1	Dual Edge Capture Mode Enable for n = 2
DECAPENT	Enables the dual edge capture mode in the channels (n) and (n+1). This bit reconfigures the function of MSnA, ELSnB:ELSnA and ELS(n+1)B:ELS(n+1)A bits in dual edge capture mode according to Table 39-7.
	This field applies only when FTMEN = 1.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.



# FTMx\_COMBINE field descriptions (continued)

Field	Description
	The dual edge capture mode in this pair of channels is disabled.
	1 The dual edge capture mode in this pair of channels is enabled.
9 COMP1	Complement of Channel (n) for n = 2
COMIT	Enables complementary mode for the combined channels. In complementary mode the channel (n+1) output is the inverse of the channel (n) output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The channel (n+1) output is the same as the channel (n) output.</li> <li>The channel (n+1) output is the complement of the channel (n) output.</li> </ul>
8 COMBINE1	Combine Channels for n = 2
COMBINET	Enables the combine feature for channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Channels (n) and (n+1) are independent.
	1 Channels (n) and (n+1) are combined.
7 Reserved	This read-only field is reserved and always has the value zero.
6	Fault Control Enable for n = 0
FAULTEN0	Enables the fault control in channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul><li>The fault control in this pair of channels is disabled.</li><li>The fault control in this pair of channels is enabled.</li></ul>
5 SYNCEN0	Synchronization Enable for n = 0
STNCENO	Enables PWM synchronization of registers C(n)V and C(n+1)V.
	<ul><li>The PWM synchronization in this pair of channels is disabled.</li><li>The PWM synchronization in this pair of channels is enabled.</li></ul>
4	Deadtime Enable for n = 0
DTEN0	Enables the deadtime insertion in the channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The deadtime insertion in this pair of channels is disabled.</li> <li>The deadtime insertion in this pair of channels is enabled.</li> </ul>
3	Dual Edge Capture Mode Captures for n = 0
DECAP0	Enables the capture of the FTM counter value according to the channel (n) input event and the configuration of the dual edge capture bits.
	This field applies only when FTMEN = 1 and DECAPEN = 1.
	DECAP bit is cleared automatically by hardware if dual edge capture – one-shot mode is selected and when the capture of channel (n+1) event is made.
	0 The dual edge captures are inactive.
	1 The dual edge captures are active.





### FTMx\_COMBINE field descriptions (continued)

Field	Description
2	Dual Edge Capture Mode Enable for n = 0
DECAPEN0	Enables the dual edge capture mode in the channels (n) and (n+1). This bit reconfigures the function of MSnA, ELSnB:ELSnA and ELS(n+1)B:ELS(n+1)A bits in dual edge capture mode according to Table 39-7.
	This field applies only when FTMEN = 1.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The dual edge capture mode in this pair of channels is disabled.</li> <li>The dual edge capture mode in this pair of channels is enabled.</li> </ul>
1	Complement of Channel (n) for n = 0
COMP0	Enables complementary mode for the combined channels. In complementary mode the channel (n+1) output is the inverse of the channel (n) output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The channel (n+1) output is the same as the channel (n) output.</li> <li>The channel (n+1) output is the complement of the channel (n) output.</li> </ul>
0	Combine Channels for n = 0
COMBINE0	Enables the combine feature for channels (n) and (n+1).
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Channels (n) and (n+1) are independent.
	1 Channels (n) and (n+1) are combined.

## 39.3.15 Deadtime Insertion Control (FTMx\_DEADTIME)

This register selects the deadtime prescaler factor and deadtime value. All FTM channels use this clock prescaler and this deadtime value for the deadtime insertion.





### FTMx\_DEADTIME field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.



### FTMx\_DEADTIME field descriptions (continued)

Field	Description
7–6 DTPS	Deadtime Prescaler Value
DIFS	Selects the division factor of the system clock. This prescaled clock is used by the deadtime counter.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0x Divide the system clock by 1.
	10 Divide the system clock by 4.
	11 Divide the system clock by 16.
5–0 DTVAL	Deadtime Value
DIVAL	Selects the deadtime insertion value for the deadtime counter. The deadtime counter is clocked by a scaled version of the system clock. See the description of DTPS.
	Deadtime insert value = (DTPS $\times$ DTVAL).
	DTVAL selects the number of deadtime counts inserted as follows:
	When DTVAL is 0, no counts are inserted.
	When DTVAL is 1, 1 count is inserted.
	When DTVAL is 2, 2 counts are inserted.
	This pattern continues up to a possible 63 counts.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.

# 39.3.16 FTM External Trigger (FTMx\_EXTTRIG)


This register indicates when a channel trigger was generated, enables the generation of a trigger when the FTM counter is equal to its initial value, and selects which channels are used in the generation of the channel triggers. Several channels can be selected to generate multiple triggers in one PWM period.

Channels 6 and 7 are not used to generate channel triggers.



Addresses: FTM0\_EXTTRIG is 4003\_8000h base + 6Ch offset = 4003\_806Ch
FTM1\_EXTTRIG is 4003\_9000h base + 6Ch offset = 4003\_906Ch

FTM2\_EXTTRIG is 400B\_8000h base + 6Ch offset = 400B\_806Ch



### FTMx\_EXTTRIG field descriptions

Field	Description
31–8 Reserved	This field is reserved.
7	Channel Trigger Flag
TRIGF	Set by hardware when a channel trigger is generated. Clear TRIGF by reading EXTTRIG while TRIGF is set and then writing a 0 to TRIGF. Writing a 1 to TRIGF has no effect.
	If another channel trigger is generated before the clearing sequence is completed, the sequence is reset so TRIGF remains set after the clear sequence is completed for the earlier TRIGF.
	<ul><li>0 No channel trigger was generated.</li><li>1 A channel trigger was generated.</li></ul>
6	Initialization Trigger Enable
INITTRIGEN	Enables the generation of the trigger when the FTM counter is equal to the CNTIN register.
	0 The generation of initialization trigger is disabled.
	1 The generation of initialization trigger is enabled.
5	Channel 1 Trigger Enable
CH1TRIG	Enable the generation of the channel trigger when the FTM counter is equal to the CnV register.
	0 The generation of the channel trigger is disabled.
	1 The generation of the channel trigger is enabled.
4	Channel 0 Trigger Enable
CH0TRIG	Enable the generation of the channel trigger when the FTM counter is equal to the CnV register.
	0 The generation of the channel trigger is disabled.
	1 The generation of the channel trigger is enabled.
3 CH5TRIG	Channel 5 Trigger Enable



### FTMx\_EXTTRIG field descriptions (continued)


Field	Description
	Enable the generation of the channel trigger when the FTM counter is equal to the CnV register.
	0 The generation of the channel trigger is disabled.
	1 The generation of the channel trigger is enabled.
2	Channel 4 Trigger Enable
CH4TRIG	Enable the generation of the channel trigger when the FTM counter is equal to the CnV register.
	0 The generation of the channel trigger is disabled.
	1 The generation of the channel trigger is enabled.
1	Channel 3 Trigger Enable
CH3TRIG	Enable the generation of the channel trigger when the FTM counter is equal to the CnV register.
	0 The generation of the channel trigger is disabled.
	1 The generation of the channel trigger is enabled.
0 CH2TRIG	Channel 2 Trigger Enable
Onziria	Enable the generation of the channel trigger when the FTM counter is equal to the CnV register.
	0 The generation of the channel trigger is disabled.
	1 The generation of the channel trigger is enabled.

# 39.3.17 Channels Polarity (FTMx\_POL)

This register defines the output polarity of the FTM channels.

### **NOTE**

The safe value that is driven in a channel output when the fault control is enabled and a fault condition is detected is the inactive state of the channel. That is, the safe value of a channel is the value of its POL bit.





# FTMx\_POL field descriptions

Field	Description
31–8 Reserved	This field is reserved.
7	Channel 7 Polarity
POL7	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul><li>The channel polarity is active high.</li><li>The channel polarity is active low.</li></ul>
6 POL6	Channel 6 Polarity
POL6	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul><li>The channel polarity is active high.</li><li>The channel polarity is active low.</li></ul>
5	Channel 5 Polarity
POL5	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul><li>The channel polarity is active high.</li><li>The channel polarity is active low.</li></ul>
4	Channel 4 Polarity
POL4	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 The channel polarity is active high.
	1 The channel polarity is active low.
3	Channel 3 Polarity
POL3	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 The channel polarity is active high.
	1 The channel polarity is active low.
2 POL2	Channel 2 Polarity
. 322	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul><li>The channel polarity is active high.</li><li>The channel polarity is active low.</li></ul>
1	Channel 1 Polarity
POL1	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.




### FTMx\_POL field descriptions (continued)

Field	Description
	0 The channel polarity is active high.
	1 The channel polarity is active low.
0	Channel 0 Polarity
POL0	Defines the polarity of the channel output.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 The channel polarity is active high.
	1 The channel polarity is active low.

## 39.3.18 Fault Mode Status (FTMx\_FMS)

This register contains the fault detection flags, write protection enable bit, and the logic OR of the enabled fault inputs.

Addresses: FTM0\_FMS is 4003\_8000h base + 74h offset = 4003\_8074h FTM1\_FMS is 4003\_9000h base + 74h offset = 4003\_9074h FTM2\_FMS is 400B\_8000h base + 74h offset = 400B\_8074h



## FTMx\_FMS field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.



# FTMx\_FMS field descriptions (continued)

Field	Description
7	Fault Detection Flag
FAULTF	Represents the logic OR of the individual FAULTFj bits (where j = 3, 2, 1, 0). Clear FAULTF by reading the FMS register while FAULTF is set and then writing a 0 to FAULTF while there is no existing fault condition at the enabled fault inputs. Writing a 1 to FAULTF has no effect.
	If another fault condition is detected in an enabled fault input before the clearing sequence is completed, the sequence is reset so FAULTF remains set after the clearing sequence is completed for the earlier fault condition. FAULTF is also cleared when FAULTFj bits are cleared individually.
	<ul><li>0 No fault condition was detected.</li><li>1 A fault condition was detected.</li></ul>
6	Write Protection Enable
WPEN	The WPEN bit is the negation of the WPDIS bit. WPEN is set when 1 is written to it. WPEN is cleared when WPEN bit is read as a 1 and then 1 is written to WPDIS. Writing 0 to WPEN has no effect.
	0 Write protection is disabled. Write protected bits can be written.
	1 Write protection is enabled. Write protected bits cannot be written.
5	Fault Inputs
FAULTIN	Represents the logic OR of the enabled fault inputs after their filter (if their filter is enabled) when fault control is enabled.
	0 The logic OR of the enabled fault inputs is 0.
	1 The logic OR of the enabled fault inputs is 1.
4 Reserved	This read-only field is reserved and always has the value zero.
3	Fault Detection Flag 3
FAULTF3	Set by hardware when fault control is enabled, the corresponding fault input is enabled and a fault condition is detected at the fault input.
	Clear FAULTF3 by reading the FMS register while FAULTF3 is set and then writing a 0 to FAULTF3 while there is no existing fault condition at the the corresponding fault input. Writing a 1 to FAULTF3 has no effect. FAULTF3 bit is also cleared when FAULTF bit is cleared.
	If another fault condition is detected at the corresponding fault input before the clearing sequence is completed, the sequence is reset so FAULTF3 remains set after the clearing sequence is completed for the earlier fault condition.
	0 No fault condition was detected at the fault input.
	1 A fault condition was detected at the fault input.
2	Fault Detection Flag 2
FAULTF2	Set by hardware when fault control is enabled, the corresponding fault input is enabled and a fault condition is detected at the fault input.
	Clear FAULTF2 by reading the FMS register while FAULTF2 is set and then writing a 0 to FAULTF2 while there is no existing fault condition at the the corresponding fault input. Writing a 1 to FAULTF2 has no effect. FAULTF2 bit is also cleared when FAULTF bit is cleared.
	If another fault condition is detected at the corresponding fault input before the clearing sequence is completed, the sequence is reset so FAULTF2 remains set after the clearing sequence is completed for the earlier fault condition.



### FTMx\_FMS field descriptions (continued)

Field	Description
	0 No fault condition was detected at the fault input.
	1 A fault condition was detected at the fault input.
1 FAULTF1	Fault Detection Flag 1
FAULIFI	Set by hardware when fault control is enabled, the corresponding fault input is enabled and a fault condition is detected at the fault input.
	Clear FAULTF1 by reading the FMS register while FAULTF1 is set and then writing a 0 to FAULTF1 while there is no existing fault condition at the the corresponding fault input. Writing a 1 to FAULTF1 has no effect. FAULTF1 bit is also cleared when FAULTF bit is cleared.
	If another fault condition is detected at the corresponding fault input before the clearing sequence is completed, the sequence is reset so FAULTF1 remains set after the clearing sequence is completed for the earlier fault condition.
	<ul> <li>No fault condition was detected at the fault input.</li> <li>A fault condition was detected at the fault input.</li> </ul>
0	Fault Detection Flag 0
FAULTF0	Set by hardware when fault control is enabled, the corresponding fault input is enabled and a fault condition is detected at the fault input.
	Clear FAULTF0 by reading the FMS register while FAULTF0 is set and then writing a 0 to FAULTF0 while there is no existing fault condition at the the corresponding fault input. Writing a 1 to FAULTF0 has no effect. FAULTF0 bit is also cleared when FAULTF bit is cleared.
	If another fault condition is detected at the corresponding fault input before the clearing sequence is completed, the sequence is reset so FAULTF0 remains set after the clearing sequence is completed for the earlier fault condition.
	<ul> <li>No fault condition was detected at the fault input.</li> <li>A fault condition was detected at the fault input.</li> </ul>

# 39.3.19 Input Capture Filter Control (FTMx\_FILTER)

This register selects the filter value for the inputs of channels.


Channels 4, 5, 6 and 7 do not have an input filter.

### **NOTE**

Writing to the FILTER register has immediate effect and must be done only when the channels 0, 1, 2, and 3 are not in input modes. Failure to do this could result in a missing valid signal.



Addresses: FTM0\_FILTER is 4003\_8000h base + 78h offset = 4003\_8078h FTM1\_FILTER is 4003\_9000h base + 78h offset = 4003\_9078h FTM2\_FILTER is 400B\_8000h base + 78h offset = 400B\_8078h



### FTMx\_FILTER field descriptions


Field	Description
31–16 Reserved	This field is reserved.
15–12 CH3FVAL	Channel 3 Input Filter  Selects the filter value for the channel input.  The filter is disabled when the value is zero.
11–8 CH2FVAL	Channel 2 Input Filter  Selects the filter value for the channel input.  The filter is disabled when the value is zero.
7–4 CH1FVAL	Channel 1 Input Filter  Selects the filter value for the channel input.  The filter is disabled when the value is zero.
3–0 CH0FVAL	Channel 0 Input Filter  Selects the filter value for the channel input.  The filter is disabled when the value is zero.



#### Fault Control (FTMx\_FLTCTRL) 39.3.20

This register selects the filter value for the fault inputs, enables the fault inputs and the fault inputs filter.

Addresses: FTM0\_FLTCTRL is 4003\_8000h base + 7Ch offset = 4003\_807Ch FTM1\_FLTCTRL is 4003\_9000h base + 7Ch offset = 4003\_907Ch FTM2\_FLTCTRL is 400B\_8000h base + 7Ch offset = 400B\_807Ch Bit 31 30 23 20 21 19 0 R W



### FTMx\_FLTCTRL field descriptions

Field	Description
31–12 Reserved	This read-only field is reserved and always has the value zero.
11–8 FFVAL	Fault Input Filter
	Selects the filter value for the fault inputs.  The fault filter is disabled when the value is zero.
	NOTE: Writing to this field has immediate effect and must be done only when the fault control or all fault inputs are disabled. Failure to do this could result in a missing fault detection.
7	Fault Input 3 Filter Enable
FFLTR3EN	Enables the filter for the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input filter is disabled.
	1 Fault input filter is enabled.
6	Fault Input 2 Filter Enable
FFLTR2EN	Enables the filter for the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input filter is disabled.
	1 Fault input filter is enabled.



# FTMx\_FLTCTRL field descriptions (continued)


Field	Description
5 FFLTR1EN	Fault Input 1 Filter Enable
	Enables the filter for the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input filter is disabled.
	1 Fault input filter is enabled.
4	Fault Input 0 Filter Enable
FFLTR0EN	Enables the filter for the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input filter is disabled.
	1 Fault input filter is enabled.
3 FAULT3EN	Fault Input 3 Enable
PAULISEN	Enables the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input is disabled.
	1 Fault input is enabled.
2 FAULT2EN	Fault Input 2 Enable
TAGETZEN	Enables the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input is disabled.
	1 Fault input is enabled.
1 FAULT1EN	Fault Input 1 Enable
1710211211	Enables the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input is disabled.
	1 Fault input is enabled.
0 FAULT0EN	Fault Input 0 Enable
	Enables the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Fault input is disabled.
	1 Fault input is enabled.



# 39.3.21 Quadrature Decoder Control and Status (FTMx\_QDCTRL)

This register has the control and status bits for the quadrature decoder mode.

Addresses: FTM0\_QDCTRL is 4003\_8000h base + 80h offset = 4003\_8080h FTM1\_QDCTRL is 4003\_9000h base + 80h offset = 4003\_9080h FTM2\_QDCTRL is 400B\_8000h base + 80h offset = 400B\_8080h



### FTMx\_QDCTRL field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 PHAFLTREN	Phase A Input Filter Enable  Enables the filter for the quadrature decoder phase A input. The filter value for the phase A input is defined by the CH0FVAL field of FILTER. The phase A filter is also disabled when CH0FVAL is zero.  O Phase A input filter is disabled.  1 Phase A input filter is enabled.
6 PHBFLTREN	Phase B Input Filter Enable  Enables the filter for the quadrature decoder phase B input. The filter value for the phase B input is defined by the CH1FVAL field of FILTER. The phase B filter is also disabled when CH1FVAL is zero.  O Phase B input filter is disabled.  1 Phase B input filter is enabled.
5 PHAPOL	Phase A Input Polarity Selects the polarity for the quadrature decoder phase A input.




# FTMx\_QDCTRL field descriptions (continued)

Field	Description
	Normal polarity. Phase A input signal is not inverted before identifying the rising and falling edges of this signal.
	Inverted polarity. Phase A input signal is inverted before identifying the rising and falling edges of this signal.
4 PHBPOL	Phase B Input Polarity
	Selects the polarity for the quadrature decoder phase B input.
	0 Normal polarity. Phase B input signal is not inverted before identifying the rising and falling edges of this signal.
	1 Inverted polarity. Phase B input signal is inverted before identifying the rising and falling edges of this signal.
3 QUADMODE	Quadrature Decoder Mode
QUADIMODE	Selects the encoding mode used in the quadrature decoder mode.
	O Phase A and phase B encoding mode.
_	1 Count and direction encoding mode.
2 QUADIR	FTM Counter Direction in Quadrature Decoder Mode
	Indicates the counting direction.
	0 Counting direction is decreasing (FTM counter decrement).
	1 Counting direction is increasing (FTM counter increment).
1 TOFDIR	Timer Overflow Direction in Quadrature Decoder Mode
TOPDIN	Indicates if the TOF bit was set on the top or the bottom of counting.
	0 TOF bit was set on the bottom of counting. There was an FTM counter decrement and FTM counter
	changes from its minimum value (CNTIN register) to its maximum value (MOD register).  TOF bit was set on the top of counting. There was an FTM counter increment and FTM counter
	changes from its maximum value (MOD register) to its minimum value (CNTIN register).
0 QUADEN	Quadrature Decoder Mode Enable
	Enables the quadrature decoder mode. In this mode, the phase A and B input signals control the FTM counter direction. The quadrature decoder mode has precedence over the other modes. (See Table 39-7.)
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	0 Quadrature decoder mode is disabled.
	1 Quadrature decoder mode is enabled.



# 39.3.22 Configuration (FTMx\_CONF)

This register selects the number of times that the FTM counter overflow should occur before the TOF bit to be set, the FTM behavior in BDM modes, the use of an external global time base, and the global time base signal generation.



### FTMx\_CONF field descriptions

Field	Description
31–11 Reserved	This read-only field is reserved and always has the value zero.
10 GTBEOUT	Global time base output  Enables the global time base signal generation to other FTMs.  O A global time base signal generation is disabled.  A global time base signal generation is enabled.
9 GTBEEN	Global time base enable  Configures the FTM to use an external global time base signal that is generated by another FTM.  Use of an external global time base is disabled.  Use of an external global time base is enabled.
8 Reserved	This read-only field is reserved and always has the value zero.
7–6 BDMMODE	BDM Mode Selects the FTM behavior in BDM mode. See BDM Mode.
5 Reserved	This read-only field is reserved and always has the value zero.




## FTMx\_CONF field descriptions (continued)

Field	Description
4-0	TOF Frequency
NUMTOF	Selects the ratio between the number of counter overflows to the number of times the TOF bit is set.
	NUMTOF = 0: The TOF bit is set for each counter overflow.
	NUMTOF = 1: The TOF bit is set for the first counter overflow but not for the next overflow.
	NUMTOF = 2: The TOF bit is set for the first counter overflow but not for the next 2 overflows.
	NUMTOF = 3: The TOF bit is set for the first counter overflow but not for the next 3 overflows.
	This pattern continues up to a maximum of 31.

## 39.3.23 FTM Fault Input Polarity (FTMx\_FLTPOL)

This register defines the fault inputs polarity.

Addresses: FTM0\_FLTPOL is 4003\_8000h base + 88h offset = 4003\_8088h FTM1\_FLTPOL is 4003\_9000h base + 88h offset = 4003\_9088h FTM2\_FLTPOL is 400B\_8000h base + 88h offset = 400B\_8088h



### FTMx\_FLTPOL field descriptions

Field	Description
31–4 Reserved	This read-only field is reserved and always has the value zero.
3 FLT3POL	Fault Input 3 Polarity  Defines the polarity of the fault input.  This field is write protected. It can be written only when MODE[WPDIS] = 1.  0 The fault input polarity is active high. A one at the fault input indicates a fault.
	1 The fault input polarity is active low. A zero at the fault input indicates a fault.



# FTMx\_FLTPOL field descriptions (continued)


Field	Description
2	Fault Input 2 Polarity
FLT2POL	Defines the polarity of the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The fault input polarity is active high. A one at the fault input indicates a fault.</li> <li>The fault input polarity is active low. A zero at the fault input indicates a fault.</li> </ul>
1	Fault Input 1 Polarity
FLT1POL	Defines the polarity of the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The fault input polarity is active high. A one at the fault input indicates a fault.</li> <li>The fault input polarity is active low. A zero at the fault input indicates a fault.</li> </ul>
0	Fault Input 0 Polarity
FLT0POL	Defines the polarity of the fault input.
	This field is write protected. It can be written only when MODE[WPDIS] = 1.
	<ul> <li>The fault input polarity is active high. A one at the fault input indicates a fault.</li> <li>The fault input polarity is active low. A zero at the fault input indicates a fault.</li> </ul>



# 39.3.24 Synchronization Configuration (FTMx\_SYNCONF)

This register selects the PWM synchronization configuration, SWOCTRL, INVCTRL and CNTIN registers synchronization, if FTM clears the TRIGj bit (where j = 0, 1, 2) when the hardware trigger j is detected.

Addresses: FTM0\_SYNCONF is 4003\_8000h base + 8Ch offset = 4003\_808Ch FTM1\_SYNCONF is 4003\_9000h base + 8Ch offset = 4003\_908Ch FTM2\_SYNCONF is 400B\_8000h base + 8Ch offset = 400B\_808Ch



### FTMx\_SYNCONF field descriptions

Field	Description
31–21 Reserved	This read-only field is reserved and always has the value zero.
20 HWSOC	Software output control synchronization is activated by a hardware trigger.
	0 A hardware trigger does not activate the SWOCTRL register synchronization.
	1 A hardware trigger activates the SWOCTRL register synchronization.
19 HWINVC	Inverting control synchronization is activated by a hardware trigger.
	0 A hardware trigger does not activate the INVCTRL register synchronization.
	1 A hardware trigger activates the INVCTRL register synchronization.
18 HWOM	Output mask synchronization is activated by a hardware trigger.
	0 A hardware trigger does not activate the OUTMASK register synchronization.
	1 A hardware trigger activates the OUTMASK register synchronization.
17 HWWRBUF	MOD, CNTIN, and CV registers synchronization is activated by a hardware trigger.
	0 A hardware trigger does not activate MOD, CNTIN, and CV registers synchronization.
	1 A hardware trigger activates MOD, CNTIN, and CV registers synchronization.



# FTMx\_SYNCONF field descriptions (continued)

Field	Description
16 HWRSTCNT	FTM counter synchronization is activated by a hardware trigger.
INVITOTORI	0 A hardware trigger does not activate the FTM counter synchronization.
	1 A hardware trigger activates the FTM counter synchronization.
15–13 Reserved	This read-only field is reserved and always has the value zero.
12 SWSOC	Software output control synchronization is activated by the software trigger.
	O The software trigger does not activate the SWOCTRL register synchronization.
	1 The software trigger activates the SWOCTRL register synchronization.
11 SWINVC	Inverting control synchronization is activated by the software trigger.
	The software trigger does not activate the INVCTRL register synchronization.
	1 The software trigger activates the INVCTRL register synchronization.
10 SWOM	Output mask synchronization is activated by the software trigger.
SVVOIVI	0 The software trigger does not activate the OUTMASK register synchronization.
	1 The software trigger activates the OUTMASK register synchronization.
9 SWWRBUF	MOD, CNTIN, and CV registers synchronization is activated by the software trigger.
	0 The software trigger does not activate MOD, CNTIN, and CV registers synchronization.
	1 The software trigger activates MOD, CNTIN, and CV registers synchronization.
8 SWRSTCNT	FTM counter synchronization is activated by the software trigger.
	0 The software trigger does not activate the FTM counter synchronization.
	1 The software trigger activates the FTM counter synchronization.
7 SYNCMODE	Synchronization Mode
	Selects the PWM synchronization mode.
	0 Legacy PWM synchronization is selected.
	1 Enhanced PWM synchronization is selected.
6 Reserved	This read-only field is reserved and always has the value zero.
5 SWOC	SWOCTRL register synchronization
3000	<ul> <li>SWOCTRL register is updated with its buffer value at all rising edges of system clock.</li> <li>SWOCTRL register is updated with its buffer value by the PWM synchronization.</li> </ul>
4	INVCTRL register synchronization
INVC	<ul> <li>INVCTRL register is updated with its buffer value at all rising edges of system clock.</li> <li>INVCTRL register is updated with its buffer value by the PWM synchronization.</li> </ul>
3 Reserved	This read-only field is reserved and always has the value zero.
2 CNTINC	CNTIN register synchronization




### FTMx\_SYNCONF field descriptions (continued)

Field	Description
	CNTIN register is updated with its buffer value at all rising edges of system clock.
	1 CNTIN register is updated with its buffer value by the PWM synchronization.
1 Reserved	This read-only field is reserved and always has the value zero.
0 HWTRIGMODE	Hardware Trigger Mode
	0 FTM clears the TRIGj bit when the hardware trigger j is detected.
	1 FTM does not clear the TRIGj bit when the hardware trigger j is detected.

## 39.3.25 FTM Inverting Control (FTMx\_INVCTRL)

This register controls controls when the channel (n) output becomes the channel (n+1) output, and channel (n+1) output becomes the channel (n) output. Each INVmEN bit enables the inverting operation for the corresponding pair channels m.

This register has a write buffer. The INVmEN bit is updated by the INVCTRL register synchronization.



### FTMx\_INVCTRL field descriptions

Field	Description
31–4 Reserved	This read-only field is reserved and always has the value zero.
3 INV3EN	Pair Channels 3 Inverting Enable  Unverting is disabled.  Inverting is enabled.
2 INV2EN	Pair Channels 2 Inverting Enable  Univerting is disabled.  Inverting is enabled.
1 INV1EN	Pair Channels 1 Inverting Enable



### FTMx\_INVCTRL field descriptions (continued)


Field	Description
	0 Inverting is disabled.
	1 Inverting is enabled.
0 INV0EN	Pair Channels 0 Inverting Enable
	0 Inverting is disabled.
	1 Inverting is enabled.

## 39.3.26 FTM Software Output Control (FTMx\_SWOCTRL)

This register enables software control of channel (n) output and defines the value forced to the channel (n) output:

- The CHnOC bits enable the control of the corresponding channel (n) output by software.
- The CHnOCV bits select the value that is forced at the corresponding channel (n) output.

This register has a write buffer. The fields are updated by the SWOCTRL register synchronization.



### FTMx\_SWOCTRL field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.



# FTMx\_SWOCTRL field descriptions (continued)

Field	Description
15	Channel 7 Software Output Control Value
CH7OCV	0 The software output control forces 0 to the channel output.
	1 The software output control forces 1 to the channel output.
14	Channel 6 Software Output Control Value
CH6OCV	
	<ul> <li>The software output control forces 0 to the channel output.</li> <li>The software output control forces 1 to the channel output.</li> </ul>
10	·
13 CH5OCV	Channel 5 Software Output Control Value
	0 The software output control forces 0 to the channel output.
	1 The software output control forces 1 to the channel output.
12 CH4OCV	Channel 4 Software Output Control Value
C1140CV	0 The software output control forces 0 to the channel output.
	1 The software output control forces 1 to the channel output.
11	Channel 3 Software Output Control Value
CH3OCV	0 The software output control forces 0 to the channel output.
	1 The software output control forces 1 to the channel output.
10	Channel 2 Software Output Control Value
CH2OCV	0 The software output control forces 0 to the channel output.
	The software output control forces 0 to the channel output.  The software output control forces 1 to the channel output.
9	Channel 1 Software Output Control Value
CH1OCV	
	<ul> <li>The software output control forces 0 to the channel output.</li> <li>The software output control forces 1 to the channel output.</li> </ul>
8	
CH0OCV	Channel 0 Software Output Control Value
	0 The software output control forces 0 to the channel output.
	1 The software output control forces 1 to the channel output.
7 CH7OC	Channel 7 Software Output Control Enable
011700	0 The channel output is not affected by software output control.
	1 The channel output is affected by software output control.
6	Channel 6 Software Output Control Enable
CH6OC	The channel output is not affected by software output control.
	1 The channel output is affected by software output control.
5	Channel 5 Software Output Control Enable
CH5OC	The channel output is not affected by software output control.
	The channel output is affected by software output control.  The channel output is affected by software output control.
4	Channel 4 Software Output Control Enable
CH4OC	





### FTMx\_SWOCTRL field descriptions (continued)

Field	Description
	0 The channel output is not affected by software output control.
	1 The channel output is affected by software output control.
3 CH3OC	Channel 3 Software Output Control Enable
	0 The channel output is not affected by software output control.
	1 The channel output is affected by software output control.
2 CH2OC	Channel 2 Software Output Control Enable
	0 The channel output is not affected by software output control.
	1 The channel output is affected by software output control.
1 CH1OC	Channel 1 Software Output Control Enable
	0 The channel output is not affected by software output control.
	1 The channel output is affected by software output control.
0 CH0OC	Channel 0 Software Output Control Enable
	0 The channel output is not affected by software output control.
	1 The channel output is affected by software output control.

## 39.3.27 FTM PWM Load (FTMx\_PWMLOAD)

Enables the loading of the MOD, CNTIN, C(n)V, and C(n+1)V registers with the values of their write buffers when the FTM counter changes from the MOD register value to its next value or when a channel (j) match occurs. A match occurs for the channel (j) when FTM counter = C(j)V.







# FTMx\_PWMLOAD field descriptions

Field	Description
31–10 Reserved	This read-only field is reserved and always has the value zero.
9 LDOK	Load Enable
LDOK	Enables the loading of the MOD, CNTIN, and CV registers with the values of their write buffers.
	0 Loading updated values is disabled.
	1 Loading updated values is enabled.
8 Reserved	This read-only field is reserved and always has the value zero.
7 CH7SEL	Channel 7 Select
OI II OLL	0 Do not include the channel in the matching process.
	1 Include the channel in the matching process.
6 CH6SEL	Channel 6 Select
0110022	0 Do not include the channel in the matching process.
	1 Include the channel in the matching process.
5 CH5SEL	Channel 5 Select
	0 Do not include the channel in the matching process.
	1 Include the channel in the matching process.
4 CH4SEL	Channel 4 Select
	0 Do not include the channel in the matching process.
3	1 Include the channel in the matching process.
CH3SEL	Channel 3 Select
	<ul><li>0 Do not include the channel in the matching process.</li><li>1 Include the channel in the matching process.</li></ul>
2	Channel 2 Select
CH2SEL	
	Do not include the channel in the matching process.  Include the channel in the matching process.
1 CH1SEL	Channel 1 Select
	0 Do not include the channel in the matching process.
	1 Include the channel in the matching process.
0 CH0SEL	Channel 0 Select
	0 Do not include the channel in the matching process.
	1 Include the channel in the matching process.



# 39.4 Functional Description

The following sections describe the FTM features.

The notation used in this document to represent the counters and the generation of the signals is shown in the following figure.

FTM counting is up.
Channel (n) is in high-true EPWM mode.
PS[2:0] = 001
CNTIN = 0x0000
MOD = 0x0004
CnV = 0x0002




Figure 39-166. Notation Used

## 39.4.1 Clock Source

FTM module has only one clock domain that is the system clock.

### 39.4.1.1 Counter Clock Source

The CLKS[1:0] bits in the SC register select one of three possible clock sources for the FTM counter or disable the FTM counter. After any MCU reset, CLKS[1:0] = 0:0 so no clock source is selected.

The CLKS[1:0] bits may be read or written at any time. Disabling the FTM counter by writing 0:0 to the CLKS[1:0] bits does not affect the FTM counter value or other registers.



#### runctional Description

The fixed frequency clock is an alternative clock source for the FTM counter that allows the selection of a clock other than the system clock or an external clock. This clock input is defined by chip integration. Refer the chip specific documentation for further information. Due to FTM hardware implementation limitations, the frequency of the fixed frequency clock must not exceed 1/2 of the system clock frequency.

The external clock passes through a synchronizer clocked by the system clock to assure that counter transitions are properly aligned to system clock transitions. Therefore, to meet Nyquist criteria considering also jitter, the frequency of the external clock source must not exceed 1/4 of the system clock frequency.

### 39.4.2 Prescaler

The selected counter clock source passes through a prescaler that is a 7-bit counter. The value of the prescaler is selected by the PS[2:0] bits. The following figure shows an example of the prescaler counter and FTM counter.




Figure 39-167. Example of the Prescaler Counter

### 39.4.3 Counter

The FTM has a 16-bit counter that is used by the channels either for input or output modes. The FTM counter clock is the selected clock divided by the prescaler.

The FTM counter has these modes of operation:

- up counting (see Up Counting)
- up-down counting (see Up-Down Counting)
- quadrature mode (see Quadrature Decoder Mode)



### 39.4.3.1 **Up Counting**

Up counting is selected when (QUADEN = 0) and (CPWMS = 0).

CNTIN defines the starting value of the count and MOD defines the final value of the count (see the following figure). The value of CNTIN is loaded into the FTM counter, and the counter increments until the value of MOD is reached, at which point the counter is reloaded with the value of CNTIN.

The FTM period when using up counting is  $(MOD - CNTIN + 0x0001) \times period of the FTM counter clock.$ 

The TOF bit is set when the FTM counter changes from MOD to CNTIN.

FTM counting is up.

CNTIN = 0xFFFC (in two's complement is equal to -4)

MOD = 0x0004




Figure 39-168. Example of FTM Up and Signed Counting

If (CNTIN = 0x0000), the FTM counting is equivalent to TPM up counting (that is, up and unsigned counting) (see the following figure). If (CNTIN[15] = 1), then the initial value of the FTM counter is a negative number in two's complement, so the FTM counting is up and signed. Conversely if (CNTIN[15] = 0 and CNTIN  $\neq$  0x0000), then the initial value of the FTM counter is a positive number, so the FTM counting is up and unsigned.



#### **runctional Description**

FTM counting is up CNTIN = 0x0000 MOD = 0x0004




Figure 39-169. Example of FTM Up Counting with CNTIN = 0x0000

#### **Note**

- FTM operation is only valid when the value of the CNTIN register is less than the value of the MOD register (either in the unsigned counting or signed counting). It is the responsibility of the software to ensure that the values in the CNTIN and MOD registers meet this requirement. Any values of CNTIN and MOD that do not satisfy this criteria can result in unpredictable behavior.
- MOD = CNTIN is a redundant condition. In this case, the FTM counter is always equal to MOD and the TOF bit is set in each rising edge of the FTM counter clock.
- When MOD = 0x0000, CNTIN = 0x0000 (for example after reset), and FTMEN = 1, the FTM counter remains stopped at 0x0000 until a non-zero value is written into the MOD or CNTIN registers.
- Setting CNTIN to be greater than the value of MOD is not recommended as this unusual setting may make the FTM operation difficult to comprehend. However, there is no restriction on this configuration, and an example is shown in the following figure.



FTM counting is up MOD = 0x0005 CNTIN = 0x0015




Figure 39-170. Example of Up Counting When the Value of CNTIN Is Greater Than the Value of MOD

### 39.4.3.2 Up-Down Counting

Up-down counting is selected when (QUADEN = 0) and (CPWMS = 1).

CNTIN defines the starting value of the count and MOD defines the final value of the count. The value of CNTIN is loaded into the FTM counter, and the counter increments until the value of MOD is reached, at which point the counter is decremented until it returns to the value of CNTIN and the up-down counting restarts.

The FTM period when using up-down counting is  $2 \times (MOD - CNTIN) \times period of the FTM counter clock.$ 

The TOF bit is set when the FTM counter changes from MOD to (MOD - 1).

If (CNTIN = 0x0000), the FTM counting is equivalent to TPM up-down counting (that is, up-down and unsigned counting) (see the following figure).



#### runctional Description

FTM counting is up-down CNTIN = 0x0000 MOD = 0x0004




Figure 39-171. Example of Up-Down Counting When CNTIN = 0x0000

Note

It is expected that the up-down counting be used only with CNTIN = 0x0000.

## 39.4.3.3 Free Running Counter

If (FTMEN = 0) and (MOD = 0x0000 or MOD = 0xFFFF), the FTM counter is a free running counter. In this case, the FTM counter runs free from 0x0000 through 0xFFFF and the TOF bit is set when the FTM counter changes from 0xFFFF to 0x0000 (see the following figure).




Figure 39-172. Example When the FTM Counter Is a Free Running

If (FTMEN = 1), (QUADEN = 0), (CPWMS = 0), (CNTIN = 0x0000), and (MOD = 0xFFFF), the FTM counter is a free running counter. In this case, the FTM counter runs free from 0x0000 through 0xFFFF and the TOF bit is set when the FTM counter changes from 0xFFFF to 0x0000.



### 39.4.3.4 Counter Reset

Any write to CNT resets the FTM counter to the value in the CNTIN register and the channels output to its initial value (except for channels in output compare mode).

The FTM counter synchronization (see FTM Counter Synchronization) can also be used to force the value of CNTIN into the FTM counter and the channels output to its initial value (except for channels in output compare mode).

### 39.4.3.5 When the TOF Bit is Set

The NUMTOF[4:0] bits define the number of times that the FTM counter overflow should occur before the TOF bit to be set. If NUMTOF[4:0] = 0x00, then the TOF bit is set at each FTM counter overflow.




Figure 39-173. Periodic TOF When NUMTOF = 0x02




Figure 39-174. Periodic TOF When NUMTOF = 0x00

# 39.4.4 Input Capture Mode

The input capture mode is selected when (DECAPEN = 0), (COMBINE = 0), (CPWMS = 0), (MSnB:MSnA = 0:0), and (ELSnB:ELSnA  $\neq$  0:0).



#### **runctional Description**

When a selected edge occurs on the channel input, the current value of the FTM counter is captured into the CnV register, at the same time the CHnF bit is set and the channel interrupt is generated if enabled by CHnIE = 1 (see the following figure).

When a channel is configured for input capture, the FTMxCHn pin is an edge-sensitive input. ELSnB:ELSnA control bits determine which edge, falling or rising, triggers input-capture event. Note that the maximum frequency for the channel input signal to be detected correctly is system clock divided by 4, which is required to meet Nyquist criteria for signal sampling.

Writes to the CnV register is ignored in input capture mode.

While in BDM, the input capture function works as configured. When a selected edge event occurs, the FTM counter value (which is frozen because of BDM) is captured into the CnV register and the CHnF bit is set.




Figure 39-175. Input Capture Mode

If the channel input does not have a filter enabled, then the input signal is always delayed 3 rising edges of the system clock (two rising edges to the synchronizer plus one more rising edge to the edge detector). In other words, the CHnF bit is set on the third rising edge of the system clock after a valid edge occurs on the channel input.

#### Note

It is expected that the input capture mode be used only with CNTIN = 0x0000.

### 39.4.4.1 Filter for Input Capture Mode

The filter function is only available on channels 0, 1, 2, and 3.



Firstly the input signal is synchronized by the system clock. Following synchronization, the input signal enters the filter block (see the following figure). When there is a state change in the input signal, the 5-bit counter is reset and starts counting up. As long as the new state is stable on the input, the counter continues to increment. If the 5-bit counter overflows (the counter exceeds the value of the CHnFVAL[3:0] bits), the state change of the input signal is validated. It is then transmitted as a pulse edge to the edge detector.




Figure 39-176. Channel Input Filter

If the opposite edge appears on the input signal before validation (counter overflow), the counter is reset. At the next input transition, the counter starts counting again. Any pulse that is shorter than the minimum value selected by CHnFVAL[3:0] bits (× 4 system clocks) is regarded as a glitch and is not passed on to the edge detector. A timing diagram of the input filter is shown in the following figure.

The filter function is disabled when CHnFVAL[3:0] bits are zero. In this case, the input signal is delayed 3 rising edges of the system clock. If (CHnFVAL[3:0]  $\neq$  0000), then the input signal is delayed by the minimum pulse width (CHnFVAL[3:0]  $\times$  4 system clocks) plus a further 4 rising edges of the system clock (two rising edges to the synchronizer, one rising edge to the filter output plus one more to the edge detector). In other words, CHnF is set (4 + 4  $\times$  CHnFVAL[3:0]) system clock periods after a valid edge occurs on the channel input.

The clock for the 5-bit counter in the channel input filter is the system clock divided by 4.




Figure 39-177. Channel Input Filter Example

## 39.4.5 Output Compare Mode

The output compare mode is selected when (DECAPEN = 0), (COMBINE = 0), (CPWMS = 0), and (MSnB:MSnA = 0:1).

In output compare mode, the FTM can generate timed pulses with programmable position, polarity, duration, and frequency. When the counter matches the value in the CnV register of an output compare channel, the channel (n) output can be set, cleared, or toggled.

When a channel is initially configured to toggle mode, the previous value of the channel output is held until the first output compare event occurs.

The CHnF bit is set and the channel (n) interrupt is generated (if CHnIE = 1) at the channel (n) match (FTM counter = CnV).




Figure 39-178. Example of the Output Compare Mode when the Match Toggles the Channel Output




Figure 39-179. Example of the Output Compare Mode when the Match Clears the Channel Output






Figure 39-180. Example of the Output Compare Mode when the Match Sets the Channel Output

It is possible to use the output compare mode with (ELSnB:ELSnA = 0:0). In this case, when the counter reaches the value in the CnV register, the CHnF bit is set and the channel (n) interrupt is generated (if CHnIE = 1), however the channel (n) output is not modified and controlled by FTM.

#### **Note**

It is expected that the output compare mode be used only with CNTIN = 0x0000.

# 39.4.6 Edge-Aligned PWM (EPWM) Mode

The edge-aligned mode is selected when (QUADEN = 0), (DECAPEN = 0), (COMBINE = 0), (CPWMS = 0), and (MSnB = 1).

The EPWM period is determined by (MOD - CNTIN + 0x0001) and the pulse width  $(duty\ cycle)$  is determined by (CnV - CNTIN).

The CHnF bit is set and the channel (n) interrupt is generated (if CHnIE = 1) at the channel (n) match (FTM counter = CnV), that is, at the end of the pulse width.

This type of PWM signal is called edge-aligned because the leading edges of all PWM signals are aligned with the beginning of the period, which is the same for all channels within an FTM.




Figure 39-181. EPWM Period and Pulse Width with ELSnB:ELSnA = 1:0

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



If (ELSnB:ELSnA = 0:0) when the counter reaches the value in the CnV register, the CHnF bit is set and the channel (n) interrupt is generated (if CHnIE = 1), however the channel (n) output is not controlled by FTM.

If (ELSnB:ELSnA = 1:0), then the channel (n) output is forced high at the counter overflow (when the CNTIN register value is are loaded into the FTM counter), and it is forced low at the channel (n) match (FTM counter = CnV) (see the following figure).




Figure 39-182. EPWM Signal with ELSnB:ELSnA = 1:0

If (ELSnB:ELSnA = X:1), then the channel (n) output is forced low at the counter overflow (when the CNTIN register value is loaded into the FTM counter), and it is forced high at the channel (n) match (FTM counter = CnV) (see the following figure).




Figure 39-183. EPWM Signal with ELSnB:ELSnA = X:1

If (CnV = 0x0000), then the channel (n) output is a 0% duty cycle EPWM signal and CHnF bit is not set even when there is the channel (n) match. If (CnV > MOD), then the channel (n) output is a 100% duty cycle EPWM signal and CHnF bit is not set even when there is the channel (n) match. Therefore, MOD must be less than 0xFFFF in order to get a 100% duty cycle EPWM signal.

#### Note

It is expected that the EPWM mode be used only with CNTIN = 0x0000.



## 39.4.7 Center-Aligned PWM (CPWM) Mode

The center-aligned mode is selected when (QUADEN = 0), (DECAPEN = 0), (COMBINE = 0), and (CPWMS = 1).

The CPWM pulse width (duty cycle) is determined by  $2 \times (CnV - CNTIN)$  and the period is determined by  $2 \times (MOD - CNTIN)$ (see the following figure). MOD must be kept in the range of 0x0001 to 0x7FFF because values outside this range can produce ambiguous results.

In the CPWM mode, the FTM counter counts up until it reaches MOD and then counts down until it reaches CNTIN.

The CHnF bit is set and channel (n) interrupt is generated (if CHnIE = 1) at the channel (n) match (FTM counter = CnV) when the FTM counting is down (at the begin of the pulse width) and when the FTM counting is up (at the end of the pulse width).

This type of PWM signal is called center-aligned because the pulse width centers for all channels are aligned with the value of CNTIN.

The other channel modes are not compatible with the up-down counter (CPWMS = 1). Therefore, all FTM channels must be used in CPWM mode when (CPWMS = 1).




Figure 39-184. CPWM Period and Pulse Width with ELSnB:ELSnA = 1:0

If (ELSnB:ELSnA = 0:0) when the FTM counter reaches the value in the CnV register, the CHnF bit is set and the channel (n) interrupt is generated (if CHnIE = 1), however the channel (n) output is not controlled by FTM.

If (ELSnB:ELSnA = 1:0), then the channel (n) output is forced high at the channel (n) match (FTM counter = CnV) when counting down, and it is forced low at the channel (n) match when counting up (see the following figure).






Figure 39-185. CPWM Signal with ELSnB:ELSnA = 1:0

If (ELSnB:ELSnA = X:1), then the channel (n) output is forced low at the channel (n) match (FTM counter = CnV) when counting down, and it is forced high at the channel (n) match when counting up (see the following figure).




Figure 39-186. CPWM Signal with ELSnB:ELSnA = X:1

If (CnV = 0x0000) or (CnV) is a negative value, that is, CnV[15] = 1) then the channel (n) output is a 0% duty cycle CPWM signal and CHnF bit is not set even when there is the channel (n) match.

If (CnV is a positive value, that is, CnV[15] = 0), (CnV  $\geq$  MOD), and (MOD  $\neq$  0x0000), then the channel (n) output is a 100% duty cycle CPWM signal and CHnF bit is not set even when there is the channel (n) match. This implies that the usable range of periods set by MOD is 0x0001 through 0x7FFE (0x7FFF if you do not need to generate a 100% duty cycle CPWM signal). This is not a significant limitation because the resulting period is much longer than required for normal applications.

The CPWM mode must not be used when the FTM counter is a free running counter.

#### Note

It is expected that the CPWM mode be used only with CNTIN = 0x0000.



#### 39.4.8 Combine Mode

The combine mode is selected when (FTMEN = 1), (QUADEN = 0), (DECAPEN = 0), (COMBINE = 1), and (CPWMS = 0).

In combine mode, the channel (n) (an even channel) and channel (n+1) (the adjacent odd channel) are combined to generate a PWM signal in the channel (n) output.

In the combine mode, the PWM period is determined by (MOD - CNTIN + 0x0001) and the PWM pulse width (duty cycle) is determined by (|C(n+1)V - C(n)V|).

The CHnF bit is set and the channel (n) interrupt is generated (if CHnIE = 1) at the channel (n) match (FTM counter = C(n)V). The CH(n+1)F bit is set and the channel (n +1) interrupt is generated (if CH(n+1)IE = 1) at the channel (n+1) match (FTM counter = C(n+1)V).

If (ELSnB:ELSnA = 1:0), then the channel (n) output is forced low at the beginning of the period (FTM counter = CNTIN) and at the channel (n+1) match (FTM counter = C(n + 1)V). It is forced high at the channel (n) match (FTM counter = C(n)V)(see the following figure).

If (ELSnB:ELSnA = X:1), then the channel (n) output is forced high at the beginning of the period (FTM counter = CNTIN) and at the channel (n+1) match (FTM counter = C(n+1)V). It is forced low at the channel (n) match (FTM counter = C(n)V)(see the following figure).

In combine mode, the ELS(n+1)B and ELS(n+1)A bits are not used in the generation of the channels (n) and (n+1) output. However, if (ELSnB:ELSnA = 0:0) then the channel (n) output is not controlled by FTM, and if (ELS(n+1)B:ELS(n+1)A = 0:0) then the channel (n+1) output is not controlled by FTM.




Figure 39-187. Combine Mode

The following figures illustrate the PWM signals generation using combine mode.






Figure 39-188. Channel (n) Output If (CNTIN < C(n)V < MOD) and (CNTIN < C(n+1)V < MOD) and (C(n)V < C(n+1)V)




Figure 39-189. Channel (n) Output If (CNTIN < C(n)V < MOD) and (C(n+1)V = MOD)




Figure 39-190. Channel (n) Output If (C(n)V = CNTIN) and (CNTIN < C(n+1)V < MOD)

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011






Figure 39-191. Channel (n) Output If (CNTIN < C(n)V < MOD) and (C(n)V is Almost Equal to CNTIN) and (C(n+1)V = MOD)




Figure 39-192. Channel (n) Output If (C(n)V = CNTIN) and (CNTIN < C(n+1)V < MOD) and (C(n+1)V) is Almost Equal to MOD)






Figure 39-193. Channel (n) Output If C(n)V and C(n+1)V Are Not Between CNTIN and




Figure 39-194. Channel (n) Output If (CNTIN < C(n)V < MOD) and (CNTIN < C(n+1)V < MOD) and (C(n)V = C(n+1)V)






Figure 39-195. Channel (n) Output If (C(n)V = C(n+1)V = CNTIN)




Figure 39-196. Channel (n) Output If (C(n)V = C(n+1)V = MOD)




Figure 39-197. Channel (n) Output If (CNTIN < C(n)V < MOD) and (CNTIN < C(n+1)V < MOD) and (C(n)V > C(n+1)V)

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011






Figure 39-198. Channel (n) Output If (C(n)V < CNTIN) and (CNTIN < C(n+1)V < MOD)




Figure 39-199. Channel (n) Output If (C(n+1)V < CNTIN) and (CNTIN < C(n)V < MOD)






Figure 39-200. Channel (n) Output If (C(n)V > MOD) and (CNTIN < C(n+1)V < MOD)




Figure 39-201. Channel (n) Output If (C(n+1)V > MOD) and (CNTIN < C(n)V < MOD)






Figure 39-202. Channel (n) Output If (C(n+1)V > MOD) and (CNTIN < C(n)V = MOD)

### 39.4.8.1 Asymmetrical PWM

In combine mode, the control of the PWM signal first edge (when the channel (n) match occurs, that is, FTM counter = C(n)V) is independent of the control of the PWM signal second edge (when the channel (n+1) match occurs, that is, FTM counter = C(n+1)V). So, combine mode allows the generation of asymmetrical PWM signals.

### 39.4.9 Complementary Mode

The complementary mode is selected when (FTMEN = 1), (QUADEN = 0), (DECAPEN = 0), (COMBINE = 1), (CPWMS = 0), and (COMP = 1).

In complementary mode the channel (n+1) output is the inverse of the channel (n) output.

If (FTMEN = 1), (QUADEN = 0), (DECAPEN = 0), (COMBINE = 1), (CPWMS = 0), and (COMP = 0), then the channel (n+1) output is the same as the channel (n) output.






Figure 39-203. Channel (n+1) Output in Complementary Mode with (ELSnB:ELSnA = 1:0)




Figure 39-204. Channel (n+1) Output in Complementary Mode with (ELSnB:ELSnA = X:1)

# 39.4.10 Registers Updated from Write Buffers

### 39.4.10.1 CNTIN Register Update

If (CLKS[1:0] = 0:0) then CNTIN register is updated when CNTIN register is written (independent of FTMEN bit).

If (FTMEN = 0) or (CNTINC = 0) then CNTIN register is updated at the next system clock after CNTIN was written.

If (FTMEN = 1), (SYNCMODE = 1) and (CNTINC = 1) then CNTIN register is updated by the CNTIN register synchronization (CNTIN Register Synchronization).

### 39.4.10.2 MOD Register Update

If (CLKS[1:0] = 0:0) then MOD register is updated when MOD register is written (independent of FTMEN bit).



If  $(CLKS[1:0] \neq 0:0$  and FTMEN = 0), then MOD register is updated according to the CPWMS bit, that is:

- If the selected mode is not CPWM then MOD register is updated after MOD register was written and the FTM counter changes from MOD to CNTIN. If the FTM counter is at free-running counter mode then this update occurs when the FTM counter changes from 0xFFFF to 0x0000.
- If the selected mode is CPWM then MOD register is updated after MOD register was written and the FTM counter changes from MOD to (MOD 0x0001).

If  $(CLKS[1:0] \neq 0:0$  and FTMEN = 1) then MOD register is updated by the MOD register synchronization (MOD Register Synchronization).

### 39.4.10.3 CnV Register Update

If (CLKS[1:0] = 0:0) then CnV register is updated when CnV register is written (independent of FTMEN bit).

If  $(CLKS[1:0] \neq 0:0$  and FTMEN = 0), then CnV register is updated according to the selected mode, that is:

- If the selected mode is output compare then CnV register is updated on the next FTM counter change (end of the prescaler counting) after CnV register was written.
- If the selected mode is EPWM then CnV register is updated after CnV register was written and the FTM counter changes from MOD to CNTIN. If the FTM counter is at free-running counter mode then this update occurs when the FTM counter changes from 0xFFFF to 0x0000.
- If the selected mode is CPWM then CnV register is updated after CnV register was written and the FTM counter changes from MOD to (MOD 0x0001).

If  $(CLKS[1:0] \neq 0:0$  and FTMEN = 1) then CnV register is updated according to the selected mode, that is:.



- If the selected mode is output compare then CnV register is updated according to the SYNCEN bit. If (SYNCEN = 0) then CnV register is updated after CnV register was written at the next change of the FTM counter (end of the prescaler counting). If (SYNCEN = 1) then CnV register is updated by the CnV register synchronization (C(n)V and C(n+1)V Register Synchronization).
- If the selected mode is not output compare and (SYNCEN = 1) then CnV register is updated by the CnV register synchronization (C(n)V and C(n+1)V Register Synchronization).

## 39.4.11 PWM Synchronization

The PWM synchronization provides an opportunity to update the MOD, CNTIN, CnV, OUTMASK, INVCTRL and SWOCTRL registers with their buffered value and force the FTM counter to the CNTIN register value.

#### Note

- It is expected that the PWM synchronization be used only in combine mode.
- The legacy PWM synchronization (SYNCMODE = 0) is a subset of the enhanced PWM synchronization (SYNCMODE = 1). Thus, it is expected that only the enhanced PWM synchronization be used.


### 39.4.11.1 Hardware Trigger

Three hardware trigger signal inputs of the FTM module are enabled when TRIGn = 1 (where n = 0, 1 or 2 corresponding to each one of the input signals, respectively). The hardware trigger input n is synchronized by the system clock. The PWM synchronization with hardware trigger is initiated when a rising edge is detected at the enabled hardware trigger inputs.

If (HWTRIGMODE = 0) then the TRIGn bit is cleared when 0 is written to it or when the trigger n event is detected.

In this case if two or more hardware triggers are enabled (for example, TRIG0 and TRIG1 = 1) and only trigger 1 event occurs then only TRIG1 bit is cleared. If a trigger n event occurs together with a write setting TRIGn bit then the synchronization is initiated, but TRIGn bit remains set due to the write operation.





Note
All hardware trigger inputs have the same behavior.

Figure 39-205. Hardware Trigger Event with HWTRIGMODE = 0

If HWTRIGMODE = 1 then the TRIGn bit is only cleared when 0 is written to it.

#### NOTE

It is expected that the HWTRIGMODE bit be 1 only with enhanced PWM synchronization (SYNCMODE = 1).

### 39.4.11.2 Software Trigger

A software trigger event occurs when 1 is written to the SYNC[SWSYNC] bit. The SWSYNC bit is cleared when 0 is written to it or when the PWM synchronization (initiated by the software event) is completed.

If a new software trigger event occurs (write 1 to SWSYNC bit) together with the end of the previous synchronization (also initiated by the software trigger event) then this new synchronization is started and SWSYNC bit remains equal to 1.

If SYNCMODE = 0 then the SWSYNC bit is also cleared by FTM according to PWMSYNC and REINIT bits. In this case if (PWMSYNC = 1) or (PWMSYNC = 0 and REINIT = 0) then SWSYNC bit is cleared at the next selected loading point (Boundary Cycle and Loading Points) after that the software trigger event occurred (see the following figure). If (PWMSYNC = 0) and (REINIT = 1) then SWSYNC bit is cleared when the software trigger event occurs.

If SYNCMODE = 1 then the SWSYNC bit is also cleared by FTM according to the SWRSTCNT bit. If SWRSTCNT = 0 then SWSYNC bit is cleared at the next selected loading point after that the software trigger event occurred (see the following figure). If SWRSTCNT = 1 then SWSYNC bit is cleared when the software trigger event occurs.






Figure 39-206. Software Trigger Event

### 39.4.11.3 Boundary Cycle and Loading Points

The boundary cycle definition is important for the loading points for the registers MOD, CNTIN and C(n)V.

In up counting mode (Up Counting) the boundary cycle is defined as when the counter wraps to its initial value (CNTIN). If in up-down counting mode (Up-Down Counting) then the boundary cycle is defined as when the counter turns from down to up counting and when from up to down counting.

The following figure shows the boundary cycles and the loading points. In the up counting mode, the loading points are enabled if one of CNTMIN or CTMAX bits are 1. In the up-down counting mode, the loading points are selected by CNTMIN and CNTMAX bits, as indicated in the figure. These loading points are safe places for register updates thus allowing a smooth transitions in PWM waveform generation.

For both counting modes if neither CNTMIN nor CNTMAX are 1 then the boundary cycles are not used as loading points for registers updates. See the register synchronization descriptions in the following sections for details.






Figure 39-207. Boundary Cycles and Loading Points

### 39.4.11.4 MOD Register Synchronization

The MOD register synchronization updates the MOD register with its buffer value. This synchronization is enabled if (FTMEN = 1).

The MOD register synchronization can be done by either the enhanced PWM synchronization (SYNCMODE = 1) or the legacy PWM synchronization (SYNCMODE = 0). However, it is expected that the MOD register be synchronized only by the enhanced PWM synchronization.

In the case of enhanced PWM synchronization, the MOD register synchronization depends on SWWRBUF, SWRSTCNT, HWWRBUF and HWRSTCNT bits according to this flowchart:






Figure 39-208. MOD Register Synchronization Flowchart

In the case of legacy PWM synchronization, the MOD register synchronization depends on PWMSYNC and REINIT bits according to the following description.

If (SYNCMODE = 0), (PWMSYNC = 0) and (REINIT = 0) then this synchronization is made on the next selected loading point after an enabled trigger event takes place. If the trigger event was a software trigger then the SWSYNC bit is cleared on the next selected



loading point. If the trigger event was a hardware trigger then the trigger enable bit (TRIGn) is cleared according to Hardware Trigger. Examples with software and hardware triggers follow.




Figure 39-209. MOD Synchronization with (SYNCMODE = 0), (PWMSYNC = 0), (REINIT = 0), and (Software Trigger Was Used)




Figure 39-210. MOD Synchronization with (SYNCMODE = 0), (HWTRIGMODE = 0), (PWMSYNC = 0), (REINIT = 0), and (a Hardware Trigger Was Used)

If (SYNCMODE = 0), (PWMSYNC = 0) and (REINIT = 1) then this synchronization is made on the next enabled trigger event. If the trigger event was a software trigger then the SWSYNC bit is cleared according to the following example. If the trigger event was a hardware trigger then the TRIGn bit is cleared according to Hardware Trigger. Examples with software and hardware triggers follow.






Figure 39-211. MOD Synchronization with (SYNCMODE = 0), (PWMSYNC = 0), (REINIT = 1), and (Software Trigger Was Used)




Figure 39-212. MOD Synchronization with (SYNCMODE = 0), (HWTRIGMODE = 0), (PWMSYNC = 0), (REINIT = 1), and (a Hardware Trigger Was Used)

If (SYNCMODE = 0) and (PWMSYNC = 1) then this synchronization is made on the next selected loading point after the software trigger event takes place. The SWSYNC bit is cleared on the next selected loading point:




Figure 39-213. MOD Synchronization with (SYNCMODE = 0) and (PWMSYNC = 1)



### 39.4.11.5 CNTIN Register Synchronization

The CNTIN register synchronization updates the CNTIN register with its buffer value.

This synchronization is enabled if (FTMEN = 1), (SYNCMODE = 1) and (CNTINC = 1). The CNTIN register synchronization can be done only by the enhanced PWM synchronization (SYNCMODE = 1). The synchronization mechanism is the same as the MOD register synchronization done by the enhanced PWM synchronization (MOD Register Synchronization).

### 39.4.11.6 C(n)V and C(n+1)V Register Synchronization

The C(n)V and C(n+1)V registers synchronization updates the C(n)V and C(n+1)V registers with their buffer values.

This synchronization is enabled if (FTMEN = 1) and (SYNCEN = 1). The synchronization mechanism is the same as the MOD register synchronization (MOD Register Synchronization). However, it is expected that the C(n)V and C(n+1)V registers be synchronized only by the enhanced PWM synchronization (SYNCMODE = 1).

### 39.4.11.7 OUTMASK Register Synchronization

The OUTMASK register synchronization updates the OUTMASK register with its buffer value.

The OUTMASK register can be updated at each rising edge of system clock (SYNCHOM = 0), by the enhanced PWM synchronization (SYNCHOM = 1 and SYNCMODE = 1) or by the legacy PWM synchronization (SYNCHOM = 1 and SYNCMODE = 0). However, it is expected that the OUTMASK register be synchronized only by the enhanced PWM synchronization.

In the case of enhanced PWM synchronization, the OUTMASK register synchronization depends on SWOM and HWOM bits. See the following flowchart:






Figure 39-214. OUTMASK Register Synchronization Flowchart

In the case of legacy PWM synchronization, the OUTMASK register synchronization depends on PWMSYNC bit according to the following description.



If (SYNCMODE = 0), (SYNCHOM = 1) and (PWMSYNC = 0) then this synchronization is done on the next enabled trigger event. If the trigger event was a software trigger then the SWSYNC bit is cleared on the next selected loading point. If the trigger event was a hardware trigger then the TRIGn bit is cleared according to Hardware Trigger. Examples with software and hardware triggers follow.




Figure 39-215. OUTMASK Synchronization with (SYNCMODE = 0), (SYNCHOM = 1), (PWMSYNC = 0) and (Software Trigger Was Used)




Figure 39-216. OUTMASK Synchronization with (SYNCMODE = 0), (HWTRIGMODE = 0), (SYNCHOM = 1), (PWMSYNC = 0), and (a Hardware Trigger Was Used)

If (SYNCMODE = 0), (SYNCHOM = 1) and (PWMSYNC = 1) then this synchronization is made on the next enabled hardware trigger. The TRIGn bit is cleared according to Hardware Trigger. An example with a hardware trigger follows.






Figure 39-217. OUTMASK Synchronization with (SYNCMODE = 0), (HWTRIGMODE = 0), (SYNCHOM = 1), (PWMSYNC = 1), and (a Hardware Trigger Was Used)

### 39.4.11.8 INVCTRL Register Synchronization

The INVCTRL register synchronization updates the INVCTRL register with its buffer value.

The INVCTRL register can be updated at each rising edge of system clock (INVC = 0) or by the enhanced PWM synchronization (INVC = 1 and SYNCMODE = 1) according to the following flowchart.

In the case of enhanced PWM synchronization, the INVCTRL register synchronization depends on SWINVC and HWINVC bits.






Figure 39-218. INVCTRL Register Synchronization Flowchart

### 39.4.11.9 SWOCTRL Register Synchronization

The SWOCTRL register synchronization updates the SWOCTRL register with its buffer value.



The SWOCTRL register can be updated at each rising edge of system clock (SWOC = 0) or by the enhanced PWM synchronization (SWOC = 1 and SYNCMODE = 1) according to the following flowchart.

In the case of enhanced PWM synchronization, the SWOCTRL register synchronization depends on SWSOC and HWSOC bits.




Figure 39-219. SWOCTRL Register Synchronization Flowchart

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

### 39.4.11.10 FTM Counter Synchronization

The FTM counter synchronization is a mechanism that allows the FTM to re-start the PWM generation at a certain point in the PWM period. The channels outputs are forced to their initial value (except for channels in output compare mode) and the FTM counter is forced to its initial counting value defined by CNTIN register.

The following figure shows the FTM counter synchronization. Note that after the synchronization event had occurred the channel (n) is set to its initial value and the channel (n+1) is not set to its initial value due to a specific timing of this figure in which the deadtime insertion prevents this channel output from transitioning to 1. If no deadtime insertion is selected then the channel (n+1) transitions to logical value 1 immediately after the synchronization event had occurred.




Figure 39-220. FTM Counter Synchronization

The FTM counter synchronization can be done by either the enhanced PWM synchronization (SYNCMODE = 1) or the legacy PWM synchronization (SYNCMODE = 0). However, it is expected that the FTM counter be synchronized only by the enhanced PWM synchronization.

In the case of enhanced PWM synchronization, the FTM counter synchronization depends on SWRSTCNT and HWRSTCNT bits according to the following flowchart.







Figure 39-221. FTM Counter Synchronization Flowchart

In the case of legacy PWM synchronization, the FTM counter synchronization depends on REINIT and PWMSYNC bits according to the following description.


If (SYNCMODE = 0), (REINIT = 1) and (PWMSYNC = 0) then this synchronization is made on the next enabled trigger event. If the trigger event was a software trigger then the SWSYNC bit is cleared according to the following example. If the trigger event was a hardware trigger then the TRIGn bit is cleared according to Hardware Trigger. Examples with software and hardware triggers follow.





FTM counter is updated with the CNTIN register value and channel outputs are forced to their initial value


Figure 39-222. FTM Counter Synchronization with (SYNCMODE = 0), (REINIT = 1), (PWMSYNC = 0), and (Software Trigger Was Used)



FTM counter is updated with the CNTIN register value and channel outputs are forced to their initial value

Figure 39-223. FTM Counter Synchronization with (SYNCMODE = 0), (HWTRIGMODE = 0), (REINIT = 1), (PWMSYNC = 0), and (a Hardware Trigger Was Used)

If (SYNCMODE = 0), (REINIT = 1) and (PWMSYNC = 1) then this synchronization is made on the next enabled hardware trigger. The TRIGn bit is cleared according to Hardware Trigger.



FTM counter is updated with the CNTIN register value and channel outputs are forced to their initial value


Figure 39-224. FTM Counter Synchronization with (SYNCMODE = 0), (HWTRIGMODE = 0), (REINIT = 1), (PWMSYNC = 1), and (a Hardware Trigger Was Used)



### **39.4.12 Inverting**

The invert functionality swaps the signals between channel (n) and channel (n+1) outputs. The inverting operation is selected when (FTMEN = 1), (QUADEN = 0), (DECAPEN = 0), (COMBINE = 1), (COMP = 1), (CPWMS = 0), and (INVm = 1), where m represents a channel pair. The INVm bit in INVCTRL register is updated with its buffer value according to INVCTRL Register Synchronization

In high-true (ELSnB:ELSnA = 1:0) combine mode, the channel (n) output is forced low at the beginning of the period (FTM counter = CNTIN), forced high at the channel (n) match and forced low at the channel (n+1) match. If the inverting is selected, the channel (n) output behavior is changed to force high at the beginning of the PWM period, force low at the channel (n) match and force high at the channel (n+1) match. See the following figure.




INV(m) bit selects the inverting to the pair channels (n) and (n+1).

Figure 39-225. Channels (n) and (n+1) Outputs After the Inverting in High-True (ELSnB:ELSnA = 1:0) Combine Mode

Note that the ELSnB:ELSnA bits value should be consider since that they define the active state of the channels outputs. In low-true (ELSnB:ELSnA = X:1) combine mode, the channel (n) output is forced high at the beginning of the period, forced low at the channel (n) match and forced high at the channel (n+1) match. In the case the inverting is selected the channels (n) and (n+1) present waveforms as shown in the following figure.







NOTE

INV(m) bit selects the inverting to the pair channels (n) and (n+1).

Figure 39-226. Channels (n) and (n+1) Outputs After the Inverting in Low-True (ELSnB:ELSnA = X:1) Combine Mode

#### **Note**

It is expected that the inverting feature be used only in combine mode.

### 39.4.13 Software Output Control


The software output control forces the channel output according to software defined values at a specific time in the PWM generation.

The software output control is selected when (FTMEN = 1), (QUADEN = 0), (DECAPEN = 0), (COMBINE = 1), (CPWMS = 0), and (CHnOC = 1). The CHnOC bit enables the software output control for a specific channel output and the CHnOCV selects the value that is forced to this channel output.

Both CHnOC and CHnOCV bits in SWOCTRL register are buffered and updated with their buffer value according to SWOCTRL Register Synchronization.

The following figure shows the channels (n) and (n+1) outputs signals when the software output control is used. In this case the channels (n) and (n+1) are set to combine and complementary mode.





NOTE

CH(n)OCV = 1 and CH(n+1)OCV = 0.

Figure 39-227. Example of Software Output Control in Combine and Complementary Mode

Software output control forces the following values on channels (n) and (n+1) when the COMP bit is zero.

Table 39-242. Software Ouput Control Behavior when (COMP = 0)

CH(n)OC	CH(n+1)OC	CH(n)OCV	CH(n+1)OCV	Channel (n) Output	Channel (n+1) Output
0	0	Х	Х	is not modified by SWOC	is not modified by SWOC
1	1	0	0	is forced to zero	is forced to zero
1	1	0	1	is forced to zero	is forced to one
1	1	1	0	is forced to one	is forced to zero
1	1	1	1	is forced to one	is forced to one

Software output control forces the following values on channels (n) and (n+1) when the COMP bit is one.

Table 39-243. Software Ouput Control Behavior when (COMP = 1)

CH(n)OC	CH(n+1)OC	CH(n)OCV	CH(n+1)OCV	Channel (n) Output	Channel (n+1) Output
0	0	Х	X	is not modified by SWOC	is not modified by SWOC
1	1	0	0	is forced to zero	is forced to zero
1	1	0	1	is forced to zero	is forced to one
1	1	1	0	is forced to one	is forced to zero
1	1	1	1	is forced to one	is forced to zero



#### **Note**

- It is expected that the software output control feature be used only in combine mode.
- The CH(n)OC and CH(n+1)OC bits should be equal.
- The COMP bit should not be modified when software output control is enabled, that is, CH(n)OC = 1 and/or CH(n+1)OC = 1.
- Software output control has the same behavior with disabled or enabled FTM counter (see the CLKS bitfield description in the Status and Control register).

#### 39.4.14 Deadtime Insertion

The deadtime insertion is enabled when (DTEN = 1) and (DTVAL[5:0] is non-zero).

DEADTIME register defines the deadtime delay that can be used for all FTM channels. The DTPS[1:0] bits define the prescaler for the system clock and the DTVAL[5:0] bits define the deadtime modulo (number of the deadtime prescaler clocks).

The deadtime delay insertion ensures that no two complementary signals (channels (n) and (n+1)) drive the active state at the same time.

If POL(n) = 0, POL(n+1) = 0, and the deadtime is enabled, then when the channel (n) match (FTM counter = C(n)V) occurs, the channel (n) output remains at the low value until the end of the deadtime delay when the channel (n) output is set. Similarly, when the channel (n+1) match (FTM counter = C(n+1)V) occurs, the channel (n+1) output remains at the low value until the end of the deadtime delay when the channel (n+1) output is set. See the following figures.

If POL(n) = 1, POL(n+1) = 1, and the deadtime is enabled, then when the channel (n) match (FTM counter = C(n)V) occurs, the channel (n) output remains at the high value until the end of the deadtime delay when the channel (n) output is cleared. Similarly, when the channel (n+1) match (FTM counter = C(n+1)V) occurs, the channel (n+1) output remains at the high value until the end of the deadtime delay when the channel (n+1) output is cleared.






Figure 39-228. Deadtime Insertion with ELSnB:ELSnA = 1:0, POL(n) = 0, and POL(n+1) = 0




Figure 39-229. Deadtime Insertion with ELSnB:ELSnA = X:1, POL(n) = 0, and POL(n+1) = 0

#### NOTE

It is expected that the deadtime feature be used only in combine and complementary modes.

## 39.4.14.1 Deadtime Insertion Corner Cases

If (PS[2:0] is cleared), (DTPS[1:0] = 0:0 or DTPS[1:0] = 0:1):



- and the deadtime delay is greater than or equal to the channel (n) duty cycle ((C(n + 1)V C(n)V) × system clock), then the channel (n) output is always the inactive value (POL(n) bit value).
- and the deadtime delay is greater than or equal to the channel (n+1) duty cycle  $((MOD CNTIN + 1 (C(n+1)V C(n)V)) \times system clock)$ , then the channel (n+1) output is always the inactive value (POL(n+1)) bit value.

Although, in most cases the deadtime delay is not comparable to channels (n) and (n+1) duty cycle, the following figures show examples where the deadtime delay is comparable to the duty cycle.




Figure 39-230. Example of the Deadtime Insertion (ELSnB:ELSnA = 1:0, POL(n) = 0, and POL(n+1) = 0) when the Deadtime Delay Is Comparable To Channel (n+1) Duty Cycle




Figure 39-231. Example of the Deadtime Insertion (ELSnB:ELSnA = 1:0, POL(n) = 0, and POL(n+1) = 0) when the Deadtime Delay Is Comparable To Channels (n) and (n+1) Duty Cycle



## 39.4.15 Output Mask

The output mask can be used to force channels output to their inactive state through software (for example: to control a BLDC motor).

Any write to the OUTMASK register updates its write buffer. The OUTMASK register is updated with its buffer value by PWM synchronization (OUTMASK Register Synchronization).

If CHnOM = 1, then the channel (n) output is forced to its inactive state (POLn bit value). If CHnOM = 0, then the channel (n) output is unaffected by the output mask (see the following figure).




Figure 39-232. Output Mask with POLn = 0

The following table shows the output mask result before the polarity control.

Table 39-244. Output Mask Result for Channel (n) (Before the Polarity Control)

CHnOM	Output Mask Input	Output Mask Result
0	inactive state	inactive state
	active state	active state
1	inactive state	inactive state
	active state	



## **Note**

It is expected the output mask feature be used only in combine mode.

## 39.4.16 Fault Control

The fault control is enabled if (FTMEN = 1) and (FAULTM[1:0]  $\neq$  0:0).

FTM can have up to four fault inputs. FAULTnEN bit (where n = 0, 1, 2, 3) enables the fault input n and FFLTRnEN bit enables the fault input n filter. FFVAL[3:0] bits select the value of the enabled filter in each enabled fault input.


First each fault input signal is synchronized by the system clock (see the synchronizer block in the following figure). Following synchronization, the fault input n signal enters the filter block. When there is a state change in the fault input n signal, the 5-bit counter is reset and starts counting up. As long as the new state is stable on the fault input n, the counter continues to increment. If the 5-bit counter overflows (the counter exceeds the value of the FFVAL[3:0] bits), the new fault input n value is validated. It is then transmitted as a pulse edge to the edge detector.

If the opposite edge appears on the fault input n signal before validation (counter overflow), the counter is reset. At the next input transition, the counter starts counting again. Any pulse that is shorter than the minimum value selected by FFVAL[3:0] bits (x system clock) is regarded as a glitch and is not passed on to the edge detector.

The fault input n filter is disabled when the FFVAL[3:0] bits are zero or when FAULTnEN = 0. In this case the fault input n signal is delayed 2 rising edges of the system clock and the FAULTFn bit is set on 3th rising edge of the system clock after a rising edge occurs on the fault input n.

If FFVAL[3:0] ≠ 0000 and FAULTnEN = 1, then the fault input n signal is delayed (3 + FFVAL[3:0]) rising edges of the system clock, that is, the FAULTFn bit is set (4 + FFVAL[3:0]) rising edges of the system clock after a rising edge occurs on the fault input n.





\* where n = 3, 2, 1, 0

Figure 39-233. Fault Input n Control Block Diagram

If the fault control and fault input n are enabled and a rising edge at the fault input n signal is detected, then the FAULTFn bit is set. The FAULTF bit is the logic OR of FAULTFn[3:0] bits (see the following figure).




Figure 39-234. FAULTF and FAULTIN Bits and Fault Interrupt

If the fault control is enabled (FAULTM[1:0]  $\neq$  0:0), a fault condition has occurred (rising edge at the logic OR of the enabled fault inputs) and (FAULTEN = 1), then channels (n) and (n+1) output are forced to their safe value (the channel (n) output is forced to the value of POL(n) and the channel (n+1) is forced to the value of POL(n+1)).

The fault interrupt is generated when (FAULTF = 1) and (FAULTIE = 1). This interrupt request remains set until:

- Software clears the FAULTF bit (by reading FAULTF bit as 1 and writing 0 to it)
- Software clears the FAULTIE bit
- A reset occurs

#### **Note**

It is expected that the fault control be used only in combine mode.

## 39.4.16.1 Automatic Fault Clearing

If the automatic fault clearing is selected (FAULTM[1:0] = 1:1), then the channels output disabled by fault control is again enabled when the fault input signal (FAULTIN) returns to zero and a new PWM cycle begins (see the following figure).





Figure 39-235. Fault Control with Automatic Fault Clearing

## 39.4.16.2 Manual Fault Clearing

If the manual fault clearing is selected (FAULTM[1:0] = 0:1 or 1:0), then the channels output disabled by fault control is again enabled when the FAULTF bit is cleared and a new PWM cycle begins (see the following figure).





The channel (n) output is after the fault control with manual fault clearing and POLn = 0.

Figure 39-236. Fault Control with Manual Fault Clearing

## 39.4.16.3 Fault Inputs Polarity Control

The FLTjPOL bit selects the fault input j polarity (where j = 0, 1, 2, 3).

- If FLTjPOL = 0, the fault j input polarity is high, so the logical one at the fault input j indicates a fault.
- If FLTjPOL = 1, the fault j input polarity is low, so the logical zero at the fault input j indicates a fault.

## 39.4.17 Polarity Control

The POLn bit selects the channel (n) output polarity.

- If POLn = 0, the channel (n) output polarity is high, so the logical one is the active state and the logical zero is the inactive state.
- If POLn = 1, the channel (n) output polarity is low, so the logical zero is the active state and the logical one is the inactive state.

## **Note**

It is expected that the polarity control be used only in combine mode.

## 39.4.18 Initialization

The initialization forces the CHnOI bit value to the channel (n) output when a one is written to the INIT bit.

The initialization depends on COMP and DTEN bits. The following table shows the values that channels (n) and (n+1) are forced by initialization when the COMP and DTEN bits are zero.

Table 39-245. Initialization Behavior when (COMP = 0 and DTEN = 0)

CH(n)OI	CH(n+1)OI	Channel (n) Output	Channel (n+1) Output
0	0	is forced to zero	is forced to zero
0	1	is forced to zero	is forced to one
1	0	is forced to one	is forced to zero
1	1	is forced to one	is forced to one

The following table shows the values that channels (n) and (n+1) are forced by initialization when (COMP = 1) or (DTEN = 1).

Table 39-246. Initialization Behavior when (COMP = 1 or DTEN = 1)

CH(n)OI	CH(n+1)OI	Channel (n) Output	Channel (n+1) Output
0	Χ	is forced to zero	is forced to one
1	X	is forced to one	is forced to zero

#### **Note**


It is expected that the initialization feature be used only in combine mode and with disabled FTM counter (see the description of the CLKS field in the Status and Control register).

## 39.4.19 Features Priority

The following figure shows the priority of the features used at the generation of channels (n) and (n+1) outputs signals.



pair channels (m) - channels (n) and (n+1)



NOTE

The channels (n) and (n+1) are in output compare, EPWM, CPWM or combine modes.

Figure 39-237. Priority of the Features Used at the Generation of Channels (n) and (n+1) Outputs Signals

#### **Note**

It is expected that the initialization feature (Initialization) is not used with inverting (Inverting) and software output control (Software Output Control) features.


## 39.4.20 Channel Trigger Output

If CHjTRIG = 1 (where j = 0, 1, 2, 3, 4, or 5), then the FTM generates a trigger when the channel (j) match occurs (FTM counter = C(j)V).

The channel trigger output provides a trigger signal that is used for on-chip modules.



The FTM is able to generate multiple triggers in one PWM period. Since each trigger is generated for a specific channel, several channels are required to implement this functionality. This behavior is described in the following figure.



#### NOTE

```
(a) CH0TRIG = 0, CH1TRIG = 0, CH2TRIG = 0, CH3TRIG = 0, CH4TRIG = 0, CH5TRIG = 0 (b) CH0TRIG = 1, CH1TRIG = 0, CH2TRIG = 0, CH3TRIG = 0, CH4TRIG = 0, CH5TRIG = 0 (c) CH0TRIG = 0, CH1TRIG = 0, CH2TRIG = 0, CH3TRIG = 1, CH4TRIG = 1, CH5TRIG = 1 (d) CH0TRIG = 1, CH1TRIG = 1, CH2TRIG = 1, CH3TRIG = 1, CH4TRIG = 1, CH5TRIG = 1
```

Figure 39-238. Channel Match Trigger

## **Note**

It is expected that the channel match trigger be used only in combine mode.

## 39.4.21 Initialization Trigger

If INITTRIGEN = 1, then the FTM generates a trigger when the FTM counter is updated with the CNTIN register value in the following cases.

• The FTM counter is automatically updated with the CNTIN register value by the selected counting mode.



- When there is a write to CNT register
- When there is the FTM counter synchronization (FTM Counter Synchronization)
- If (CNT = CNTIN), (CLKS[1:0] = 0:0), and a value different from zero is written to CLKS[1:0] bits

The following figures show the cases.




Figure 39-239. Initialization Trigger Is Generated When the FTM Counting Achieves the CNTIN Register Value




Figure 39-240. Initialization Trigger Is Generated When There Is a Write to CNT Register




Figure 39-241. Initialization Trigger Is Generated When There Is the FTM Counter Synchronization



CNTIN = 0x0000 MOD = 0x000FCPWMS = 0




Figure 39-242. Initialization Trigger Is Generated If (CNT = CNTIN), (CLKS[1:0] = 0:0), and a Value Different From Zero Is Written to CLKS[1:0] Bits

The initialization trigger output provides a trigger signal that is used for on-chip modules.

#### **Note**

It is expected that the initialization trigger be used only in combine mode.

## 39.4.22 Capture Test Mode


The capture test mode allows to test the CnV registers, the FTM counter and the interconnection logic between the FTM counter and CnV registers.

In this test mode, all channels must be configured for input capture mode (Input Capture Mode) and FTM counter must be configured to the up counting (Up Counting).

When the capture test mode is enabled (CAPTEST = 1), the FTM counter is frozen and any write to CNT register updates directly the FTM counter (see the following figure). After it was written, all CnV registers are updated with the written value to CNT register and CHnF bits are set. Therefore, the FTM counter is updated with its next value according to its configuration (its next value depends on CNTIN, MOD, and the written value to FTM counter).

The next reads of CnV registers return the written value to the FTM counter and the next reads of CNT register return FTM counter next value.





#### NOTE

- FTM counter configuration: (FTMEN = 1), (QUADEN = 0), (CAPTEST = 1), (CPWMS = 0), (CNTIN = 0x0000), and (MOD = 0xFFFF)
- FTM channel n configuration: input capture mode (DECAPEN = 0), (COMBINE = 0), and (MSnB:MSnA = 0:0)

Figure 39-243. Capture Test Mode

## 39.4.23 DMA

The channel generates a DMA transfer request according to DMA and CHnIE bits (see the following table).

**DMA CHnIE Channel DMA Transfer Request Channel Interrupt** 0 The channel DMA transfer request is not The channel interrupt is not generated. generated. The channel DMA transfer request is not The channel interrupt is generated if (CHnF = 1). 0 1 generated. 1 The channel DMA transfer request is not The channel interrupt is not generated. generated. The channel DMA transfer request is generated The channel interrupt is not generated. 1 1 if (CHnF = 1).

Table 39-247. Channel DMA Transfer Request

If DMA = 1, the CHnF bit is cleared either by channel DMA transfer done or reading CnSC while CHnF is set and then writing a zero to CHnF bit according to CHnIE bit (see the following table).



#### Table 39-248. Clear CHnF Bit when DMA = 1

CHnIE	How CHnF Bit Can Be Cleared		
0	CHnF bit is cleared either when the channel DMA transfer is done or by reading CnSC while CHnF is set and then writing a 0 to CHnF bit.		
1 CHnF bit is cleared when the channel DMA transfer is done.			

## 39.4.24 Dual Edge Capture Mode

The dual edge capture mode is selected if FTMEN = 1 and DECAPEN = 1. This mode allows to measure a pulse width or period of the signal on the input of channel (n) of a channel pair. The channel (n) filter can be active in this mode when n is 0 or 2.




Figure 39-244. Dual Edge Capture Mode Block Diagram

The MS(n)A bit defines if the dual edge capture mode is one-shot or continuous.

The ELS(n)B:ELS(n)A bits select the edge that is captured by channel (n), and ELS(n+1)B:ELS(n+1)A bits select the edge that is captured by channel (n+1). If both ELS(n)B:ELS(n)A and ELS(n+1)B:ELS(n+1)A bits select the same edge, then it is the period measurement. If these bits select different edges, then it is a pulse width measurement.

In the dual edge capture mode, only channel (n) input is used and channel (n+1) input is ignored.

If the selected edge by channel (n) bits is detected at channel (n) input, then CH(n)F bit is set and the channel (n) interrupt is generated (if CH(n)IE = 1). If the selected edge by channel (n+1) bits is detected at channel (n) input and (CH(n)F = 1), then CH(n+1)F bit is set and the channel (n+1) interrupt is generated (if CH(n+1)IE = 1).



The C(n)V register stores the value of FTM counter when the selected edge by channel (n) is detected at channel (n) input. The C(n+1)V register stores the value of FTM counter when the selected edge by channel (n+1) is detected at channel (n) input.

In this mode, the pair channels coherency mechanism ensures coherent data when the C(n)V and C(n+1)V registers are read. The only requirement is that C(n)V must be read before C(n+1)V.

## **Note**

- The CH(n)F, CH(n)IE, MS(n)A, ELS(n)B, and ELS(n)A bits are channel (n) bits.
- The CH(n+1)F, CH(n+1)IE, MS(n+1)A, ELS(n+1)B, and ELS(n+1)A bits are channel (n+1) bits.
- It is expected that the dual edge capture mode be used with ELS(n)B:ELS(n)A = 0:1 or 1:0, ELS(n+1)B:ELS(n+1)A = 0:1 or 1:0 and the FTM counter in free running counter mode (Free Running Counter).

## 39.4.24.1 One-Shot Capture Mode

The one-shot capture mode is selected when (FTMEN = 1), (DECAPEN = 1), and (MS(n)A = 0). In this capture mode, only one pair of edges at the channel (n) input is captured. The ELS(n)B:ELS(n)A bits select the first edge to be captured, and ELS(n+1)B:ELS(n+1)A bits select the second edge to be captured.

The edge captures are enabled while DECAP bit is set. For each new measurement in one-shot capture mode, first the CH(n)F and CH(n+1) bits must be cleared, and then the DECAP bit must be set.

In this mode, the DECAP bit is automatically cleared by FTM when the edge selected by channel (n+1) is captured. Therefore, while DECAP bit is set, the one-shot capture is in process. When this bit is cleared, both edges were captured and the captured values are ready for reading in the C(n)V and C(n+1)V registers.

Similarly, when the CH(n+1)F bit is set, both edges were captured and the captured values are ready for reading in the C(n)V and C(n+1)V registers.



## 39.4.24.2 Continuous Capture Mode

The continuous capture mode is selected when (FTMEN = 1), (DECAPEN = 1), and (MS(n)A = 1). In this capture mode, the edges at the channel (n) input are captured continuously. The ELS(n)B:ELS(n)A bits select the initial edge to be captured, and ELS(n+1)B:ELS(n+1)A bits select the final edge to be captured.

The edge captures are enabled while DECAP bit is set. For the initial use, first the CH(n)F and CH(n+1)F bits must be cleared, and then DECAP bit must be set to start the continuous measurements.

When the CH(n+1)F bit is set, both edges were captured and the captured values are ready for reading in the C(n)V and C(n+1)V registers. The latest captured values are always available in these registers even after the DECAP bit is cleared.

In this mode, it is possible to clear only the CH(n+1)F bit. Therefore, when the CH(n+1)F bit is set again, the latest captured values are available in C(n)V and C(n+1)V registers.

For a new sequence of the measurements in the dual edge capture – continuous mode, it is recommended to clear the CH(n)F and CH(n+1)F bits to start new measurements.


## 39.4.24.3 Pulse Width Measurement

If the channel (n) is configured to capture rising edges (ELS(n)B:ELS(n)A = 0:1) and the channel (n+1) to capture falling edges (ELS(n+1)B:ELS(n+1)A = 1:0), then the positive polarity pulse width is measured. If the channel (n) is configured to capture falling edges (ELS(n)B:ELS(n)A = 1:0) and the channel (n+1) to capture rising edges (ELS(n+1)B:ELS(n+1)A = 0:1), then the negative polarity pulse width is measured.

The pulse width measurement can be made in one-shot capture mode (One-Shot Capture Mode) or continuous capture mode (Continuous Capture Mode).

The following figure shows an example of the dual edge capture – one-shot mode used to measure the positive polarity pulse width. The DECAPEN bit selects the dual edge capture mode, so it keeps set in all operation mode. The DECAP bit is set to enable the measurement of next positive polarity pulse width. The CH(n)F bit is set when the first edge of this pulse is detected, that is, the edge selected by ELS(n)B:ELS(n)A bits. The CH(n+1)F bit is set and DECAP bit is cleared when the second edge of this pulse is detected, that is, the edge selected by ELS(n+1)B:ELS(n+1)A bits. Both DECAP and CH(n+1)F bits indicate when two edges of the pulse were captured and the C(n)V and C(n+1)V registers are ready for reading.






#### Note

- The commands set DECAPEN, set DECAP, clear CH(n)F, and clear CH(n+1)F are made by the user.
- Problem 1: channel (n) input = 1, set DECAP, not clear CH(n)F, and clear CH(n+1)F.
- Problem 2: channel (n) input = 1, set DECAP, not clear CH(n)F, and not clear CH(n+1)F.

Figure 39-245. Dual Edge Capture – One-Shot Mode for Positive Polarity Pulse Width Measurement

The following figure shows an example of the dual edge capture – continuous mode used to measure the positive polarity pulse width. The DECAPEN bit selects the dual edge capture mode, so it keeps set in all operation mode. While the DECAP bit is set the configured measurements are made. The CH(n)F bit is set when the first edge of the positive polarity pulse is detected, that is, the edge selected by ELS(n)B:ELS(n)A bits. The CH(n+1)F bit is set when the second edge of this pulse is detected, that is, the edge selected by ELS(n+1)B:ELS(n+1)A bits. The CH(n+1)F bit indicates when two edges of the pulse were captured and the C(n)V and C(n+1)V registers are ready for reading.





Note

Figure 39-246. Dual Edge Capture – Continuous Mode for Positive Polarity Pulse Width Measurement

## 39.4.24.4 Period Measurement


If the channels (n) and (n+1) are configured to capture consecutive edges of the same polarity, then the period of the channel (n) input signal is measured. If both channels (n) and (n+1) are configured to capture rising edges (ELS(n)B:ELS(n)A = 0:1 and ELS(n +1)B:ELS(n+1)A = 0:1), then the period between two consecutive rising edges is measured. If both channels (n) and (n+1) are configured to capture falling edges (ELS(n)B:ELS(n)A = 1:0 and ELS(n+1)B:ELS(n+1)A = 1:0), then the period between two consecutive falling edges is measured.

The period measurement can be made in one-shot capture mode (One-Shot Capture Mode) or continuous capture mode (Continuous Capture Mode).

<sup>-</sup> The commands set DECAPEN, set DECAP, clear CH(n)F, and clear CH(n+1)F are made by the user.



The following figure shows an example of the dual edge capture – one-shot mode used to measure the period between two consecutive rising edges. The DECAPEN bit selects the dual edge capture mode, so it keeps set in all operation mode. The DECAP bit is set to enable the measurement of next period. The CH(n)F bit is set when the first rising edge is detected, that is, the edge selected by ELS(n)B:ELS(n)A bits. The CH(n+1)F bit is set and DECAP bit is cleared when the second rising edge is detected, that is, the edge selected by ELS(n+1)B:ELS(n+1)A bits. Both DECAP and CH(n+1)F bits indicate when two selected edges were captured and the C(n)V and C(n+1)V registers are ready for reading.



#### Note


- The commands set DECAPEN, set DECAP, clear CH(n)F, and clear CH(n+1)F are made by the user.
- Problem 1: channel (n) input = 0, set DECAP, not clear CH(n)F, and not clear CH(n+1)F.
- Problem 2: channel (n) input = 1, set DECAP, not clear CH(n)F, and clear CH(n+1)F.
- Problem 3: channel (n) input = 1, set DECAP, not clear CH(n)F, and not clear CH(n+1)F.

Figure 39-247. Dual Edge Capture – One-Shot Mode to Measure of the Period Between Two Consecutive Rising Edges

The following figure shows an example of the dual edge capture – continuous mode used to measure the period between two consecutive rising edges. The DECAPEN bit selects the dual edge capture mode, so it keeps set in all operation mode. While the DECAP bit is set the configured measurements are made. The CH(n)F bit is set when the first rising



edge is detected, that is, the edge selected by ELS(n)B:ELS(n)A bits. The CH(n+1)F bit is set when the second rising edge is detected, that is, the edge selected by ELS(n+1)B:ELS(n+1)A bits. The CH(n+1)F bit indicates when two edges of the period were captured and the C(n)V and C(n+1)V registers are ready for reading.



Note

Figure 39-248. Dual Edge Capture – Continuous Mode to Measure of the Period Between
Two Consecutive Rising Edges

## 39.4.24.5 Read Coherency Mechanism

The dual edge capture mode implements a read coherency mechanism between the FTM counter value captured in C(n)V and C(n+1)V registers. The read coherency mechanism is illustrated in the following figure. In this example, the channels (n) and (n+1) are in dual edge capture – continuous mode for positive polarity pulse width measurement. Thus, the channel (n) is configured to capture the FTM counter value when there is a rising edge at channel (n) input signal, and channel (n+1) to capture the FTM counter value when there is a falling edge at channel (n) input signal.

<sup>-</sup> The commands set DECAPEN, set DECAP, clear CH(n)F, and clear CH(n+1)F are made by the user.



When a rising edge occurs in the channel (n) input signal, the FTM counter value is captured into channel (n) capture buffer. The channel (n) capture buffer value is transferred to C(n)V register when a falling edge occurs in the channel (n) input signal. C(n)V register has the FTM counter value when the previous rising edge occurred, and the channel (n) capture buffer has the FTM counter value when the last rising edge occurred.

When a falling edge occurs in the channel (n) input signal, the FTM counter value is captured into channel (n+1) capture buffer. The channel (n+1) capture buffer value is transferred to C(n+1)V register when the C(n)V register is read.

In the following figure, the read of C(n)V returns the FTM counter value when the event 1 occurred and the read of C(n+1)V returns the FTM counter value when the event 2 occurred.

C(n)V register must be read prior to C(n+1)V register in dual edge capture one-shot and continuous modes for the read coherency mechanism works properly.




Figure 39-249. Dual Edge Capture Mode Read Coherency Mechanism

## 39.4.25 Quadrature Decoder Mode

The quadrature decoder mode is selected if (FTMEN = 1) and (QUADEN = 1). The quadrature decoder mode uses the input signals phase A and B to control the FTM counter increment and decrement. The following figure shows the quadrature decoder block diagram.

Each one of input signals phase A and B has a filter that is equivalent to the filter used in the channels input (Filter for Input Capture Mode). The phase A input filter is enabled by PHAFLTREN bit and this filter's value is defined by CH0FVAL[3:0] bits



(CH(n)FVAL[3:0] bits in FILTER0 register). The phase B input filter is enabled by PHBFLTREN bit and this filter's value is defined by CH1FVAL[3:0] bits (CH(n +1)FVAL[3:0] bits in FILTER0 register).

Except for CH0FVAL[3:0] and CH1FVAL[3:0] bits, no channel logic is used in quadrature decoder mode.




Figure 39-250. Quadrature Decoder Block Diagram

#### Note

It is important to notice that the FTM counter is clocked by the phase A and B input signals when quadrature decoder mode is selected. Therefore it is expected that the quadrature decoder be used only with the FTM channels in input capture or output compare modes.

The PHAPOL bit selects the polarity of the phase A input, and the PHBPOL bit selects the polarity of the phase B input.

The QUADMODE selects the encoding mode used in the quadrature decoder mode. If QUADMODE = 1, then the count and direction encoding mode (see the following figure) is enabled. In this mode, the phase B input value indicates the counting direction (FTM counter increment or decrement), and the phase A input defines the counting rate (FTM counter is updated when there is a rising edge at phase A input signal).






Figure 39-251. Quadrature Decoder – Count and Direction Encoding Mode

If QUADMODE = 0, then the phase A and phase B encoding mode (see the following figure) is enabled. In this mode, the relationship between phase A and B signals indicates the counting direction, and phase A and B signals define the counting rate (FTM counter is updated when there is an edge either at the phase A or phase B signals).

If PHAPOL = 0 and PHBPOL = 0, then the FTM counter increment happens when:

- there is a rising edge at phase A signal and phase B signal is at logic zero;
- there is a rising edge at phase B signal and phase A signal is at logic one;
- there is a falling edge at phase B signal and phase A signal is at logic zero;
- there is a falling edge at phase A signal and phase B signal is at logic one;

and the FTM counter decrement happens when:

- there is a falling edge at phase A signal and phase B signal is at logic zero;
- there is a falling edge at phase B signal and phase A signal is at logic one;
- there is a rising edge at phase B signal and phase A signal is at logic zero;
- there is a rising edge at phase A signal and phase B signal is at logic one.




Figure 39-252. Quadrature Decoder – Phase A and Phase B Encoding Mode

The following figure shows the FTM counter overflow in up counting. In this case, when the FTM counter changes from MOD to CNTIN, TOF and TOFDIR bits are set. TOF bit indicates the FTM counter overflow occurred. TOFDIR indicates the counting was up when the FTM counter overflow occurred.




Figure 39-253. FTM Counter Overflow in Up Counting for Quadrature Decoder Mode

The following figure shows the FTM counter overflow in down counting. In this case, when the FTM counter changes from CNTIN to MOD, TOF bit is set and TOFDIR bit is cleared. TOF bit indicates the FTM counter overflow occurred. TOFDIR indicates the counting was down when the FTM counter overflow occurred.






Figure 39-254. FTM Counter Overflow in Down Counting for Quadrature Decoder Mode

## 39.4.25.1 Quadrature Decoder Boundary Conditions

The following figures are examples of motor jittering which causes the FTM counter transitions as indicated by these figures. It is expected to observe these behaviors in motor position control applications.




Figure 39-255. Motor Position Jittering in a Mid Count Value



The following figure shows motor jittering produced by the phase B and A pulses respectively. The first highlighted transition causes a jitter on the FTM counter value near the maximum count value (MOD). The second indicated transition occurs on phase A and causes the FTM counter transition between the maximum and minimum count values which are defined by MOD and CNTIN registers.




Figure 39-256. Motor Position Jittering Near Maximum and Minimum Count Value

The appropriate settings of the phase A and phase B input filters are important to avoid glitches that may cause oscillation on the FTM counter value. The preceding figures show examples of oscillations that can be caused by poor input filter setup. Thus, it is important to guarantee a minimum pulse width to avoid these oscillations.

## 39.4.26 BDM Mode

When the chip is in BDM mode, the BDMODE[1:0] bits select the behavior of the FTM counter, the CH(n)F bit, the channels output, and the writes to the MOD, CNTIN, and C(n)V registers according to the following table.

BDMMODE	FTM Counter	CH(n)F Bit	FTM Channels Output	Writes to MOD, CNTIN, and C(n)V Registers
00	Stopped	can be set	Functional mode	Writes to these registers bypass the registers buffers
01	Stopped	is not set	The channels outputs are forced to their safe value according to POLn bit	Writes to these registers bypass the registers buffers

Table 39-249. FTM Behavior When the Chip Is in BDM Mode

Table continues on the next page...



## Table 39-249. FTM Behavior When the Chip Is in BDM Mode (continued)

BDMMODE	FTM Counter	CH(n)F Bit	FTM Channels Output	Writes to MOD, CNTIN, and C(n)V Registers
10	Stopped	is not set	The channels outputs are frozen when the chip enters in BDM mode	Writes to these registers bypass the registers buffers
11	Functional mode	can be set	Functional mode	Functional mode

Note that if BDMMODE[1:0] = 2'b00 then the channels outputs remain at the value when the chip enters in BDM mode, since the FTM counter is stopped. However, the following situations modify the channels outputs in this BDM mode.

- Write any value to CNT register (Counter Reset). In this case, the FTM counter is updated with the CNTIN register value and the channels outputs are updated to the initial value except for those channels set to output compare mode.
- FTM counter is reset by PWM synchronization mode (FTM Counter Synchronization). In this case, the FTM counter is updated with the CNTIN register value and the channels outputs are updated to the initial value except for channels in output compare mode.
- In the channels outputs initialization (Initialization), the channel (n) output is forced to the CH(n)OI bit value when the value 1 is written to INIT bit.

#### Note

It is expected that the BDMMODE[1:0] = 2'b00 is not used with the fault control (Fault Control). Even if the fault control is enabled and a fault condition exists, the channels outputs values are as defined above.

## 39.4.27 Intermediate Load


The PWMLOAD register allows software to update the MOD, CNTIN, and C(n)V registers with the content of the register buffer at a defined load point. In this case it is not required to use the PWM synchronization control.

A possible loading point is when the FTM counter wraps from MOD value to CNTIN value. This loading point is always enabled. Another possible loading point is at the channel (j) match (FTM counter = C(j)V). This loading point is enabled when CHjSEL = 1. The following figure shows some examples of enabled loading points.



After enabling the loading points, the LDOK bit needs to be set for the load to occur. In this case the load occurs at the next enabled loading point according to the following conditions:

- If a new value was written to the MOD register, then the MOD register is updated with its write buffer value.
- If a new value was written to the CNTIN register and CNTINC = 1, then the CNTIN register is updated with its write buffer value.
- If a new value was written to the C(n)V register and SYNCENm = 1 where m indicates the pair channels (n) and (n+1), then the C(n)V register is updated with its write buffer value.
- If a new value was written to the C(n+1)V register and SYNCENm = 1 where m indicates the pair channels (n) and (n+1), then the C(n+1)V register is updates with its write buffer value.



#### NOTE

```
(a) LDOK = 0, CH0SEL = 0, CH1SEL = 0, CH2SEL = 0, CH3SEL = 0, CH4SEL = 0, CH5SEL = 0, CH6SEL = 0, CH7SEL = 0
(b) LDOK = 1, CH0SEL = 0, CH1SEL = 0, CH2SEL = 0, CH3SEL = 0, CH4SEL = 0, CH5SEL = 0, CH6SEL = 0, CH7SEL = 0
(c) LDOK = 0, CH0SEL = 0, CH1SEL = 0, CH2SEL = 0, CH3SEL = 1, CH4SEL = 0, CH5SEL = 0, CH6SEL = 0, CH7SEL = 0
(d) LDOK = 1, CH0SEL = 0, CH1SEL = 0, CH2SEL = 0, CH3SEL = 0, CH4SEL = 0, CH5SEL = 0, CH6SEL = 1, CH7SEL = 0
(e) LDOK = 1, CH0SEL = 1, CH1SEL = 0, CH2SEL = 1, CH3SEL = 0, CH4SEL = 1, CH5SEL = 0, CH6SEL = 1, CH7SEL = 0
(f) LDOK = 1, CH0SEL = 1, CH1SEL = 1, CH2SEL = 1, CH3SEL = 1, CH5SEL = 1, CH6SEL = 1, CH7SEL = 1
```

Figure 39-257. Loading Points for Intermediate Load



## **NOTE**

- If ELSjB and ELSjA bits are different from zero, then the channel (j) output signal is generated according to the configured output mode. If ELSjB and ELSjA bits are zero, then the generated signal is not available on channel (j) output.
- If CHjIE = 1, then the channel (j) interrupt is generated when the channel (j) match occurs.
- At the intermediate load neither the channels outputs nor the FTM counter are changed. Software must set the intermediate load at a safe point in time.
- It is expected that the intermediate load feature be used only in combine mode.

## 39.4.28 Global Time Base (GTB)

The global time base (GTB) is a FTM function that allows the synchronization of multiple FTM modules on a chip. The following figure shows an example of the GTB feature used to synchronize two FTM modules. In this case, the FTM A and B channels can behave as if just one FTM module was used, that is, a global time base.




Figure 39-258. Global Time Base (GTB) Block Diagram

The GTB functionality is implemented by the GTBEEN and GTBEOUT bits in the CONF register, the internal input signal *gtb\_in* and the internal output signal *gtb\_out*. The GTBEEN bit enables gtb\_in to control the FTM counter enable signal:

- If GTBEEN = 0, each one of FTM modules works independently according to their configured mode.
- If GTBEEN = 1, the FTM counter update is enabled only when gtb\_in is 1.



#### neset Overview

In the configuration described in the preceding figure, FTM modules A and B have their FTM counters enabled if at least one of the gtb\_out signals from one of the FTM modules is 1. There are several possible configurations for the interconnection of the gtb\_in and gtb\_out signals (represented by the example glue logic shown in the figure). Note that these configurations are chip-dependent and implemented outside of the FTM modules. See the Chip Configuration details for the chip's specific implementation.

#### NOTE

- In order to use the internal GTB signals to synchronize the FTM counter of different FTM modules, the configuration of each FTM module should guarantee that its FTM counter starts counting as soon as the gtb\_in signal is 1.
- The GTB feature does not provide continuous synchronization of FTM counters, meaning that the FTM counters may lose synchronization during FTM operation. The GTB feature only allows the FTM counters to *start* their operation synchronously.

## 39.4.28.1 Enabling the global time base (GTB)

To enable the GTB feature, follow these steps for each participating FTM module:

- 1. Stop the FTM counter: Write 00b to SC[CLKS].
- 2. Program the FTM module to the intended configuration. (The operation mode needs to be consistent across all participating modules.)
- 3. Write 1 to CONF[GTBEEN] and write 0 to CONF[GTBEOUT] at the same time.
- 4. Select the intended FTM counter clock source in SC[CLKS]. (The clock source needs to be consistent across all participating modules.)
- 5. Reset the FTM counter: Write any value to the CNT register.

To initiate the GTB feature, follow these steps for the FTM module used as the time base:

- 1. Write 1 to CONF[GTBEOUT].
- 2. If needed, configure the GTB glue logic connecting the FTM modules within the chip. Some chips do not require configuration of glue logic. See the Chip Configuration details for the chip's specific implementation.

## 39.5 Reset Overview

The FTM is reset whenever any chip reset occurs.



When the FTM exits from reset:

- the FTM counter and the prescaler counter are zero and are stopped (CLKS[1:0] = 00b);
- the timer overflow interrupt is zero (Timer Overflow Interrupt);
- the channels interrupts are zero (Channel (n) Interrupt);
- the fault interrupt is zero (Fault Interrupt);
- the channels are in input capture mode (Input Capture Mode);
- the channels outputs are zero;
- the channels pins are not controlled by FTM (ELS(n)B:ELS(n)A = 0:0) ().

The following figure shows the FTM behavior after the reset. At the reset (item 1), the FTM counter is disabled (see the description of the CLKS field in the Status and Control register), its value is updated to zero and the pins are not controlled by FTM ().

After the reset, the FTM should be configurated (item 2). It is necessary to define the FTM counter mode, the FTM counting limits (MOD and CNTIN registers value), the channels mode and CnV registers value according to the channels mode.

Thus, it is recommended to write any value to CNT register (item 3). This write updates the FTM counter with the CNTIN register value and the channels output with its initial value (except for channels in output compare mode) (Counter Reset).

The next step is to select the FTM counter clock by the CLKS[1:0] bits (item 4). It is important to highlight that the pins are only controlled by FTM when CLKS[1:0] bits are different from zero ().




Figure 39-259. FTM Behavior After Reset When the Channel (n) Is in Combine Mode



#### rıvı Interrupts

The following figure shows an example when the channel (n) is in output compare mode and the channel (n) output is toggled when there is a match. In the output compare mode, the channel output is not updated to its initial value when there is a write to CNT register (item 3). In this case, it is recommended to use the software output control (Software Output Control) or the initialization (Initialization) to update the channel output to the selected value (item 4).




Figure 39-260. FTM Behavior After Reset When the Channel (n) Is in Output Compare Mode

## 39.6 FTM Interrupts

This section describes FTM interrupts.

## 39.6.1 Timer Overflow Interrupt

The timer overflow interrupt is generated when (TOIE = 1) and (TOF = 1).

## 39.6.2 Channel (n) Interrupt

The channel (n) interrupt is generated when (CHnIE = 1) and (CHnF = 1).



# 39.6.3 Fault Interrupt

The fault interrupt is generated when (FAULTIE = 1) and (FAULTF = 1).



rıwı Interrupts



# **Chapter 40 Periodic Interrupt Timer (PIT)**

## 40.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The PIT timer module is an array of timers that can be used to raise interrupts and trigger DMA channels.

# 40.1.1 Block Diagram

The following figure shows the PIT block diagram.



#### orginal Description




Figure 40-1. Block diagram of the PIT

#### NOTE

Refer to the Chip Configuration information for the number of PIT channels used in this MCU.

## 40.1.2 Features

The main features of this block are:

- Timers can generate DMA trigger pulses
- Timers can generate interrupts
- All interrupts are maskable
- Independent timeout periods for each timer

## 40.2 Signal Description

The PIT module has no external pins.



# 40.3 Memory Map/Register Description

This section provides a detailed description of all registers accessible in the PIT module.

#### **NOTE**

Reserved registers will read as 0, writes will have no effect.

#### **NOTE**

Refer to the Chip Configuration information for the number of PIT channels used in this MCU.

#### PIT memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_7000	PIT Module Control Register (PIT_MCR)	32	R/W	0000_0002h	40.3.1/ 1010
4003_7100	Timer Load Value Register (PIT_LDVAL0)	32	R/W	0000_0000h	40.3.2/ 1011
4003_7104	Current Timer Value Register (PIT_CVAL0)	32	R/W	0000_0000h	40.3.3/ 1011
4003_7108	Timer Control Register (PIT_TCTRL0)	32	R/W	0000_0000h	40.3.4/ 1012
4003_710C	Timer Flag Register (PIT_TFLG0)	32	R/W	0000_0000h	40.3.5/ 1012
4003_7110	Timer Load Value Register (PIT_LDVAL1)	32	R/W	0000_0000h	40.3.2/ 1011
4003_7114	Current Timer Value Register (PIT_CVAL1)	32	R/W	0000_0000h	40.3.3/ 1011
4003_7118	Timer Control Register (PIT_TCTRL1)	32	R/W	0000_0000h	40.3.4/ 1012
4003_711C	Timer Flag Register (PIT_TFLG1)	32	R/W	0000_0000h	40.3.5/ 1012
4003_7120	Timer Load Value Register (PIT_LDVAL2)	32	R/W	0000_0000h	40.3.2/ 1011
4003_7124	Current Timer Value Register (PIT_CVAL2)	32	R/W	0000_0000h	40.3.3/ 1011
4003_7128	Timer Control Register (PIT_TCTRL2)	32	R/W	0000_0000h	40.3.4/ 1012
4003_712C	Timer Flag Register (PIT_TFLG2)	32	R/W	0000_0000h	40.3.5/ 1012




## PIT memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_7130	Timer Load Value Register (PIT_LDVAL3)	32	R/W	0000_0000h	40.3.2/ 1011
4003_7134	Current Timer Value Register (PIT_CVAL3)	32	R/W	0000_0000h	40.3.3/ 1011
4003_7138	Timer Control Register (PIT_TCTRL3)	32	R/W	0000_0000h	40.3.4/ 1012
4003_713C	Timer Flag Register (PIT_TFLG3)	32	R/W	0000_0000h	40.3.5/ 1012

## 40.3.1 PIT Module Control Register (PIT\_MCR)

This register controls whether the timer clocks should be enabled and whether the timers should run in debug mode.






#### PIT\_MCR field descriptions

Field	Description
31–2 Reserved	This read-only field is reserved and always has the value zero.
1 MDIS	Module Disable  This is used to disable the module clock. This bit must be enabled before any other setup is done.  Clock for PIT Timers is enabled.  Clock for PIT Timers is disabled.
0 FRZ	Freeze  Allows the timers to be stopped when the device enters debug mode.  0 Timers continue to run in debug mode.  1 Timers are stopped in debug mode.



## 40.3.2 Timer Load Value Register (PIT\_LDVALn)

These registers select the timeout period for the timer interrupts.



#### PIT\_LDVALn field descriptions

Field	Description
31–0 TSV	Timer Start Value Bits  These bits set the timer start value. The timer will count down until it reaches 0, then it will generate an interrupt and load this register value again. Writing a new value to this register will not restart the timer, instead the value will be loaded once the timer expires. To abort the current cycle and start a timer period
	with the new value, the timer must be disabled and enabled again.

## 40.3.3 Current Timer Value Register (PIT\_CVALn)

These registers indicate the current timer position.

#### PIT\_CVALn field descriptions

Field	Description
31–0 TVL	Current Timer Value  If the timer is enabled, these bits represent the current timer value. If the timer is disabled, do not use this field as its value is unreliable.
	<b>NOTE:</b> The timer uses a downcounter. The timer values are frozen in debug mode if the MCR[FRZ] bit is set.


#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## 40.3.4 Timer Control Register (PIT\_TCTRLn)

These register contain the control bits for each timer.

Addresses: PIT\_TCTRL0 is 4003\_7000h base + 108h offset = 4003\_7108h PIT\_TCTRL1 is 4003\_7000h base + 118h offset = 4003\_7118h PIT\_TCTRL2 is 4003\_7000h base + 128h offset = 4003\_7128h PIT\_TCTRL3 is 4003\_7000h base + 138h offset = 4003\_7138h



#### PIT\_TCTRLn field descriptions


Field	Description
31–2 Reserved	This read-only field is reserved and always has the value zero.
1 TIE	Timer Interrupt Enable Bit.  When an interrupt is pending (TIF set), enabling the interrupt will immediately cause an interrupt event. To avoid this, the associated TIF flag must be cleared first.  O Interrupt requests from Timer n are disabled.  1 Interrupt will be requested whenever TIF is set.
0 TEN	Timer Enable Bit.  This bit enables or disables the timer.  Timer n is disabled.  Timer n is active.

## 40.3.5 Timer Flag Register (PIT\_TFLGn)

These registers hold the PIT interrupt flags.

Addresses: PIT\_TFLG0 is 4003\_7000h base + 10Ch offset = 4003\_710Ch
PIT\_TFLG1 is 4003\_7000h base + 11Ch offset = 4003\_711Ch
PIT\_TFLG2 is 4003\_7000h base + 12Ch offset = 4003\_712Ch

PIT\_TFLG3 is 4003\_7000h base + 13Ch offset = 4003\_713Ch





#### PIT\_TFLGn field descriptions

Field	Description
31–1 Reserved	This read-only field is reserved and always has the value zero.
0 TIF	Timer Interrupt Flag.  TIF is set to 1 at the end of the timer period. This flag can be cleared only by writing it with 1. Writing 0 has no effect. If enabled (TIE = 1), TIF causes an interrupt request.  0 Time-out has not yet occurred.
	1 Time-out has occurred.

# 40.4 Functional Description

This section provides the functional description of the module.

#### 40.4.1 General

This section gives detailed information on the internal operation of the module. Each timer can be used to generate trigger pulses as well as to generate interrupts. Each interrupt is available on a separate interrupt line.

#### 40.4.1.1 Timers

The timers generate triggers at periodic intervals, when enabled. They load their start values, as specified in their LDVAL registers, then count down until they reach 0. Then they load their respective start value again. Each time a timer reaches 0, it will generate a trigger pulse and set the interrupt flag.

All interrupts can be enabled or masked (by setting the TIE bits in the TCTRL registers). A new interrupt can be generated only after the previous one is cleared.

If desired, the current counter value of the timer can be read via the CVAL registers.

The counter period can be restarted, by first disabling, then enabling the timer with the TEN bit (see the following figure).



#### runctional Description




Figure 40-23. Stopping and Starting a Timer

The counter period of a running timer can be modified, by first disabling the timer, setting a new load value and then enabling the timer again (see the following figure).




Figure 40-24. Modifying Running Timer Period

It is also possible to change the counter period without restarting the timer by writing the LDVAL register with the new load value. This value will then be loaded after the next trigger event (see the following figure).




Figure 40-25. Dynamically Setting a New Load Value

## 40.4.1.2 Debug Mode

In debug mode, the timers will be frozen based on FRZ bit in PIT module control register. This is intended to aid software development, allowing the developer to halt the processor, investigate the current state of the system (for example, the timer values) and then continue the operation.



## 40.4.2 Interrupts

All of the timers support interrupt generation. Refer to the MCU specification for related vector addresses and priorities.

Timer interrupts can be enabled by setting the TIE bits. The timer interrupt flags (TIF) are set to 1 when a timeout occurs on the associated timer, and are cleared to 0 by writing a 1 to that TIF bit.

## 40.5 Initialization and Application Information

In the example configuration:

- The PIT clock has a frequency of 50 MHz.
- Timer 1 creates an interrupt every 5.12 ms.
- Timer 3 creates a trigger event every 30 ms.

First the PIT module must be activated by writing a 0 to the MDIS bit in the MCR.

The 50 MHz clock frequency equates to a clock period of 20 ns. Timer 1 needs to trigger every 5.12 ms/20 ns = 256000 cycles and timer 3 every 30 ms/20 ns = 1500000 cycles. The value for the LDVAL register trigger is calculated as:

LDVAL trigger = (period / clock period) -1

This means LDVAL1 should be written with 0x0003E7FF, and LDVAL3 should be written with 0x0016E35F.

The interrupt for Timer 1 is enabled by setting TIE in the TCTRL1 register. The timer is started by writing 1 to bit TEN in the TCTRL1 register.

Timer 3 shall be used only for triggering. Therefore Timer 3 is started by writing a 1 to bit TEN in the TCTRL3 register, bit TIE stays at 0.

The following example code matches the described setup:

```
// turn on PIT
PIT_MCR = 0x00;

// Timer 1
PIT_LDVAL1 = 0x0003E7FF; // setup timer 1 for 256000 cycles
PIT_TCTRL1 = TIE; // enable Timer 1 interrupts
PIT_TCTRL1 |= TEN; // start Timer 1

// Timer 3
```



#### **ımualization and Application Information**

PIT\_LDVAL3 = 0x0016E35F; // setup timer 3for 1500000 cycles PIT\_TCTRL3 |= TEN; // start Timer 3



# Chapter 41 Low power timer (LPTMR)

#### 41.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The low power timer (LPTMR) can be configured to operate as a time counter (with optional prescaler) or as a pulse counter (with optional glitch filter) across all power modes, including the low leakage modes. It can also continue operating through most system reset events, allowing it to be used as a time of day counter.

#### 41.1.1 Features

The LPTMR module's features include:

- 16-bit time counter or pulse counter with compare
  - Optional interrupt can generate asynchronous wakeup from any low power mode
  - Hardware trigger output
  - Counter supports free-running mode or reset on compare
- Configurable clock source for prescaler/glitch filter
- Configurable input source for pulse counter
  - Rising edge or falling edge

## 41.1.2 Modes of operation

#### 41.1.2.1 Run mode

In run mode, the LPTMR operates normally.



#### 41.1.2.2 Wait mode

In wait mode, the LPTMR continues to operate normally and may be configured to exit the low power mode by generating an interrupt request.

## 41.1.2.3 Stop mode

In stop mode, the LPTMR continues to operate normally and may be configured to exit the low power mode by generating an interrupt request.

## 41.1.2.4 Low leakage modes

In low leakage modes, the LPTMR continues to operate normally and may be configured to exit the low power mode by generating an interrupt request.

## **41.1.2.5 Debug modes**

During debug mode, the LPTMR continues to operate normally.

# 41.2 LPTMR signal descriptions

Table 41-1. LPTMR signal descriptions

Signal	Description	I/O
LPTMR_ALTn	Pulse counter input pin	I



# 41.2.1 Detailed signal descriptions

Table 41-2. LPTMR interface-detailed signal descriptions

Signal	I/O	Description		
LPTMR_ALT <i>n</i>	I	Pulse counter input.  The LPTMR can select one of the input pins to be used in pulse counter mode.		
		State meaning	Assertion-If configured for pulse counter mode with active high input then assertion causes the LPTMR counter register to increment.	
			Negation-If configured for pulse counter mode with active low input then negation cause the LPTMR counter register to increment.	
		Timing	Assertion or negation may occur at any time; input may assert asynchronously to the bus clock.	

# 41.3 Memory map and register definition

#### **NOTE**

The LPTMR registers are reset only on a POR or LVD event. See LPTMR power and reset for more details.


#### **LPTMR** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_0000	Low Power Timer Control Status Register (LPTMR0_CSR)	32	R/W	0000_0000h	41.3.1/ 1020
4004_0004	Low Power Timer Prescale Register (LPTMR0_PSR)	32	R/W	0000_0000h	41.3.2/ 1021
4004_0008	Low Power Timer Compare Register (LPTMR0_CMR)	32	R/W	0000_0000h	41.3.3/ 1023
4004_000C	Low Power Timer Counter Register (LPTMR0_CNR)	32	R	0000_0000h	41.3.4/ 1023



## 41.3.1 Low Power Timer Control Status Register (LPTMRx\_CSR)

Addresses: LPTMR0\_CSR is 4004\_0000h base + 0h offset = 4004\_0000h



#### LPTMRx\_CSR field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 TCF	Timer Compare Flag  The timer compare flag is set when the LPTMR is enabled and the LPTMR Counter Register equals the LPTMR Compare Register and increments. This Timer Compare Flag is cleared when the LPTMR is disabled or a logic one is written to the Timer Compare Flag.  0 LPTMR Counter Register has not equaled the LPTMR Compare Register and incremented
	LPTMR Counter Register has equaled the LPTMR Compare Register and incremented
6 TIE	Timer Interrupt Enable  When the Timer Interrupt Enable is set, the LPTMR Interrupt is generated whenever the Timer Compare Flag is also set.
	0 Timer Interrupt Disabled.
	1 Timer Interrupt Enabled.
5–4 TPS	Timer Pin Select  The Timer Pin Select configures the input source to be used in Pulse Counter mode. The Timer Pin Select should only be altered when the LPTMR is disabled. The input connections vary by device. See the Chip Configuration details for information on the connections to these inputs.
	00 Pulse counter input 0 is selected.
	01 Pulse counter input 1 is selected.
	<ul><li>10 Pulse counter input 2 is selected.</li><li>11 Pulse counter input 3 is selected.</li></ul>
3 TPP	Timer Pin Polarity




## **LPTMRx\_CSR** field descriptions (continued)

Field	Description
	The Timer Pin Polarity configures the polarity of the input source in Pulse Counter mode. The Timer Pin Polarity should only be changed when the LPTMR is disabled.
	O Pulse Counter input source is active high, and LPTMR Counter Register will increment on the rising edge.
	1 Pulse Counter input source is active low, and LPTMR Counter Register will increment on the falling edge.
2 TFC	Timer Free Running Counter
	When clear the Timer Free Running Counter configures the LPTMR Counter Register to reset whenever the Timer Compare Flag is set. When set, the Timer Free Running Counter configures the LPTMR Counter Register to reset on overflow. The Timer Free Running Counter should only be altered when the LPTMR is disabled.
	<ul><li>0 LPTMR Counter Register is reset whenever the Timer Compare Flag is set.</li><li>1 LPTMR Counter Register is reset on overflow.</li></ul>
1	Timer Mode Select
TMS	The Timer Mode Select configures the mode of the LPTMR. The Timer Mode Select should only be altered when the LPTMR is disabled.
	0 Time Counter mode.
	1 Pulse Counter mode.
0 TEN	Timer Enable
	When the Timer Enable bit is clear, it resets the LPTMR internal logic (including the LPTMR Counter Register and Timer Compare Flag). When the Timer Enable bit is set, the LPTMR is enabled. When writing 1 to this bit, bits LPTMR_CSR[5:1] should not be altered.
	<ul><li>0 LPTMR is disabled and internal logic is reset.</li><li>1 LPTMR is enabled.</li></ul>

## 41.3.2 Low Power Timer Prescale Register (LPTMRx\_PSR)

Addresses: LPTMR0\_PSR is 4004\_0000h base + 4h offset = 4004\_0004h



#### LPTMRx\_PSR field descriptions

Field	Description
31–7 Reserved	This read-only field is reserved and always has the value zero.



#### memory map and register definition

## LPTMRx\_PSR field descriptions (continued)

Field	Description		
6–3 PRESCALE	Prescale Value		
1112001122	The Prescaler Value register field configures the size of the Prescaler (in Time Counter mode) or width of the Glitch Filter (in Pulse Counter mode). The Prescale Value should only be altered when the LPTMR is disabled.		
	O000 Prescaler divides the prescaler clock by 2; Glitch Filter does not support this configuration.  O001 Prescaler divides the prescaler clock by 4; Glitch Filter recognizes change on input pin after 2		
	rising clock edges.  On Prescaler divides the prescaler clock by 8; Glitch Filter recognizes change on input pin after 4 rising clock edges.		
	0011 Prescaler divides the prescaler clock by 16; Glitch Filter recognizes change on input pin after 8 rising clock edges.		
	0100 Prescaler divides the prescaler clock by 32; Glitch Filter recognizes change on input pin after 16 rising clock edges.		
	O101 Prescaler divides the prescaler clock by 64; Glitch Filter recognizes change on input pin after 32 rising clock edges.		
	O110 Prescaler divides the prescaler clock by 128; Glitch Filter recognizes change on input pin after 64 rising clock edges.		
	O111 Prescaler divides the prescaler clock by 256; Glitch Filter recognizes change on input pin after 128 rising clock edges.		
	1000 Prescaler divides the prescaler clock by 512; Glitch Filter recognizes change on input pin after 256 rising clock edges.		
	1001 Prescaler divides the prescaler clock by 1024; Glitch Filter recognizes change on input pin after 512 rising clock edges.		
	1010 Prescaler divides the prescaler clock by 2048; Glitch Filter recognizes change on input pin after 1024 rising clock edges.		
	1011 Prescaler divides the prescaler clock by 4096; Glitch Filter recognizes change on input pin after 2048 rising clock edges.		
	1100 Prescaler divides the prescaler clock by 8192; Glitch Filter recognizes change on input pin after 4096 rising clock edges.		
	1101 Prescaler divides the prescaler clock by 16384; Glitch Filter recognizes change on input pin after 8192 rising clock edges.		
	1110 Prescaler divides the prescaler clock by 32768; Glitch Filter recognizes change on input pin after 16384 rising clock edges.		
	Prescaler divides the prescaler clock by 65536; Glitch Filter recognizes change on input pin after 32768 rising clock edges.		
2 PBYP	Prescaler Bypass		
	When the Prescaler Bypass is set the selected prescaler clock (in Time Counter mode) or selected input source (in Pulse Counter mode) directly clocks the LPTMR Counter Register. When the Prescaler Bypass is clear, the LPTMR Counter Register is clocked by the output of the prescaler/glitch filter. The Prescaler Bypass should only be altered when the LPTMR is disabled.		
	<ul><li>0 Prescaler/Glitch Filter is enabled.</li><li>1 Prescaler/Glitch Filter is bypassed.</li></ul>		
1–0	Prescaler Clock Select		
PCS	The Prescaler Clock Select selects the clock to be used by the LPTMR prescaler/glitch filter. The Prescaler Clock Select should only be altered when the LPTMR is disabled. The clock connections vary by device. See the Chip Configuration details for information on the connections to these inputs.		




#### LPTMRx\_PSR field descriptions (continued)

Field		Description
	00	Prescaler/glitch filter clock 0 selected
	01	Prescaler/glitch filter clock 1 selected
	10	Prescaler/glitch filter clock 2 selected
	11	Prescaler/glitch filter clock 3 selected

## 41.3.3 Low Power Timer Compare Register (LPTMRx\_CMR)

Addresses: LPTMR0\_CMR is 4004\_0000h base + 8h offset = 4004\_0008h




#### LPTMRx\_CMR field descriptions

Field	Description	
31–16 Reserved	This read-only field is reserved and always has the value zero.	
15–0 COMPARE	Compare Value  When the LPTMR is enabled and the LPTMR Counter Register equals the value in the LPTMR Compare Register and increments, the Timer Compare Flag is set and the Hardware Trigger asserts until the next time the LPTMR Counter Register increments. If the LPTMR Compare Register is zero, the Hardware Trigger will remain asserted until the LPTMR is disabled. If the LPTMR is enabled, the LPTMR Compare Register should only be altered when the Timer Compare Flag is set.	

## 41.3.4 Low Power Timer Counter Register (LPTMRx\_CNR)

Addresses: LPTMR0\_CNR is 4004\_0000h base + Ch offset = 4004\_000Ch



#### LPTMRx\_CNR field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.



#### **runctional** description

#### LPTMRx\_CNR field descriptions (continued)

Field	Description	
15–0 COUNTER	Counter Value	
333111211	The LPTMR Counter Register returns the current value of the LPTMR Counter.	

## 41.4 Functional description

## 41.4.1 LPTMR power and reset

The LPTMR remains powered in all power modes, including low leakage modes. If the LPTMR is not required to remain operating during a low power mode, then it should be disabled before entering the mode.

The LPTMR is reset only on global POR or LVD. When configuring the LPTMR registers, the control status register should be initially written with the timer disabled, before configuring the LPTMR prescale register and compare register. The timer enable should then be set as the last step in the initialization. This ensures the LPTMR is configured correctly and the LPTMR counter is reset to zero following a warm reset.

## 41.4.2 LPTMR clocking

The LPTMR prescaler/glitch filter can be clocked by one of four clocks. The clock source should be enabled before the LPTMR is enabled.

#### NOTE

The clock source selected may need to be configured to remain enabled in low power modes, otherwise the LPTMR will not operate during low power modes.

In pulse counter mode with the prescaler/glitch filter bypassed, the selected input source directly clocks the LPTMR counter register and no other clock source is required. To minimize power in this case, configure the prescaler clock source for a clock that is not toggling.

#### NOTE

The clock source or pulse input source selected for the LPTMR should not exceed the frequency  $f_{LPTMR}$  defined in the device datasheet.



## 41.4.3 LPTMR prescaler/glitch filter

The LPTMR prescaler and glitch filter share the same logic which operates as a prescaler in time counter mode and as a glitch filter in pulse counter mode.

The prescaler/glitch filter configuration must not be altered when the LPTMR is enabled.

#### 41.4.3.1 Prescaler enabled

In time counter mode when the prescaler is enabled, the output of the prescaler directly clocks the LPTMR counter register. When the LPTMR is enabled, the LPTMR counter register will increment every  $2^2$  to  $2^{16}$  prescaler clock cycles. After the LPTMR is enabled, the first increment of the LPTMR counter register will take an additional one or two prescaler clock cycles due to synchronization logic.

## 41.4.3.2 Prescaler bypassed

In time counter mode when the prescaler is bypassed, the selected prescaler clock increments the LPTMR counter register on every clock cycle. When the LPTMR is enabled, the first increment will take an additional one or two prescaler clock cycles due to synchronization logic.

#### 41.4.3.3 Glitch filter

In pulse counter mode when the glitch filter is enabled, the output of the glitch filter directly clocks the LPTMR counter register. When the LPTMR is first enabled, the output of the glitch filter is asserted (logic one for active high and logic zero for active low). If the selected input source remains negated for at least  $2^1$  to  $2^{15}$  consecutive prescaler clock rising edges, then the glitch filter output will also negate. If the selected input source remains asserted for at least  $2^1$  to  $2^{15}$  consecutive prescaler clock rising edges, then the glitch filter output will also assert. Note that the input is only sampled on the rising clock edge.

The LPTMR counter register will increment each time the glitch filter output asserts. In pulse counter mode, the maximum rate at which the LPTMR counter register can increment is once every  $2^2$  to  $2^{16}$  prescaler clock edges. When first enabled, the glitch filter will wait an additional one or two prescaler clock edges due to synchronization logic.

## 41.4.3.4 Glitch filter bypassed

In pulse counter mode when the glitch filter is bypassed, the selected input source increments the LPTMR counter register every time it asserts. Before the LPTMR is first enabled, the selected input source is forced to asserted. This is to prevent the LPTMR counter register from incrementing if the selected input source is already asserted when the LPTMR is first enabled.

## 41.4.4 LPTMR compare

When the LPTMR counter register equals the value of the LPTMR compare register and increments, the following events occur:

- Timer compare flag is set
- LPTMR interrupt is generated if Timer Interrupt Enable is also set
- LPTMR hardware trigger is generated
- LPTMR counter register is reset if the free running counter bit is clear

When the LPTMR is enabled, the LPTMR compare register can only be altered when the timer compare flag is set. When updating the LPTMR compare register, the LPTMR compare register must be written and the timer compare flag must be cleared before the LPTMR counter has incremented past the new LPTMR compare value.

## 41.4.5 LPTMR counter

The LPTMR counter register increments by one on every:

- prescaler clock (time counter mode with prescaler bypassed)
- prescaler output (time counter mode with prescaler enabled)
- input source assertion (pulse counter mode with glitch filter bypassed)
- glitch filter output (pulse counter mode with glitch filter enabled).

The LPTMR counter register is reset when the LPTMR is disabled or if the counter register overflows. If the CSR[TFC] control bit is set then the LPTMR counter register is also reset whenever the CSR[TCF] status flag is set.

The LPTMR counter register continues incrementing when the core is halted in debug mode.



The LPTMR counter register cannot be initialized, but can be read at any time. Reading the LPTMR counter register at the same time as it is incrementing may return invalid data due to synchronization of the read data bus. If it is necessary for software to read the LPTMR counter register, it is recommended that two read accesses are performed and software verifies that the same data was returned for both reads.

## 41.4.6 LPTMR hardware trigger

The LPTMR hardware trigger asserts at the same time the timer compare flag is set and can be used to trigger hardware events in other peripherals without software intervention. The hardware trigger is always enabled.

When the LPTMR compare register is set to zero with the free running counter bit clear, the LPTMR hardware trigger will assert on the first compare and does not negate. When the LPTMR compare register is set to a non-zero value (or if the free running counter bit is set) the LPTMR hardware trigger will assert on each compare and negate on the following increment of the LPTMR counter register.

## 41.4.7 LPTMR interrupt

The LPTMR interrupt is generated whenever the CSR[TIE] and CSR[TCF] are set. The CSR[TCF] is cleared by disabling the LPTMR or by writing a logic one to it.

The CSR[TIE] can be altered and the CSR[TCF] can be cleared while the LPTMR is enabled.

The LPTMR interrupt is generated asynchronously to the system clock and can be used to generate a wakeup from any low power mode, including the low leakage modes (provided the LPTMR is enabled as a wakeup source).



runctional description



# **Chapter 42 Carrier Modulator Transmitter (CMT)**

#### 42.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The carrier modulator transmitter (CMT) module provides means to generate the protocol timing and carrier signals for a wide variety of encoding schemes. The CMT incorporates hardware to off-load the critical and/or lengthy timing requirements associated with signal generation from the CPU, releasing much of its bandwidth to handle other tasks such as code data generation, data decompression, or keyboard scanning. The CMT does not include dedicated hardware configurations for specific protocols but is intended to be sufficiently programmable in its function to handle the timing requirements of most protocols with minimal CPU intervention. When the modulator is disabled, certain CMT registers can be used to change the state of the infrared output (CMT\_IRO) signal directly. This feature allows for the generation of future protocol timing signals not readily producible by the current architecture.

## 42.2 Features

The features of this module include:

- Four modes of operation
  - Time; with independent control of high and low times
  - Baseband
  - Frequency shift key (FSK)
  - Direct software control of CMT\_IRO signal



#### **DIOCK Diagram**

- Extended space operation in time, baseband, and FSK modes
- Selectable input clock divider
- Interrupt on end of cycle
  - Ability to disable CMT\_IRO signal and use as timer interrupt

# 42.3 Block Diagram

The following figure is the CMT block diagram.




Figure 42-1. CMT Module Block Diagram



## 42.4 Modes of Operation

The CMT module operates in the following modes.

- Time—When operating in time mode, the user independently defines the high and low times of the carrier signal to determine both period and duty cycle.
- Baseband—When MSC[BASE] bit is set, the carrier output  $(f_{cg})$  to the modulator is held high continuously to allow for the generation of baseband protocols.
- Frequency shift key (FSK)—This mode allows the carrier generator to alternate between two sets of high and low times. When operating in FSK mode, the generator will toggle between the two sets when instructed by the modulator, allowing the user to dynamically switch between two carrier frequencies without CPU intervention.

The following table summarizes the CMT's modes.

MSC[MCGEN]1 MSC[BASE]2 MSC[FSK]2 MSC[EXSPC] Mode Comment fca controlled by primary high and low registers. Time 0 0 0 f<sub>cq</sub> transmitted to CMT\_IRO signal when modulator gate is open. f<sub>cq</sub> is always high. CMT\_IRO signal Baseband 1 Х 0 1 high when modulator gate is open. f<sub>ca</sub> control alternates between primary high/low registers and secondary high/low registers. **FSK** 1 0 1 0 f<sub>cq</sub> transmitted to CMT\_IRO signal when modulator gate is open. Setting MSC[EXSPC] bit causes subsequent modulator cycles to be Extended 1 Χ Χ 1 spaces (modulator out not asserted) Space

**Table 42-1. CMT Modes of Operation** 

Χ

Χ

Х

0

**IRO Latch** 

for the duration of the modulator period (mark and space times).

OC[IROL] bit controls state of

CMT\_IRO signal.

<sup>1.</sup> To prevent spurious operation, initialize all data and control registers before beginning a transmission (MSC[MCGEN]=1).

<sup>2.</sup> These bits are not double buffered and should not be changed during a transmission (while MSC[MCGEN]=1).



#### NOTE

The assignment of module modes to core modes is chipspecific. For module-to-core mode assignments, see the chapter that describes how modules are configured.

## 42.4.1 Wait Mode Operation

During wait mode, the CMT if enabled, will continue to operate normally. However, there is no change in operating modes of CMT while in wait mode, because the CPU is not operating.

## 42.4.2 Stop Mode Operation

This section describes the CMT stop mode operations.

## 42.4.2.1 Normal Stop Mode Operation

During Normal Stop mode, clocks to the CMT module are halted. No registers are affected.

Because the clocks are halted, the CMT will resume upon exit from Normal Stop. Software should ensure that the Normal Stop mode is not entered while the modulator is still in operation to prevent the CMT\_IRO signal from being asserted while in Normal Stop mode. This may require a time-out period from the time that MSC[MCGEN] bit is cleared to allow the last modulator cycle to complete.

## 42.4.2.2 Low Power Stop Mode Operation

During Low Power Stop mode, the CMT module is completely powered off internally and the CMT\_IRO signal state at the time that Low Power Stop mode is entered is latched and held. To prevent the CMT\_IRO signal from being asserted while in Low Power Stop mode, software should assure that the signal is not active when entering Low Power Stop mode. Upon wake-up from Low Power Stop mode, the CMT module will be in the reset state.



## 42.5 CMT External Signal Descriptions

This table shows the description of the external signal.

Table 42-2. CMT Signal Descriptions

Signal	Description	I/O
CMT_IRO	Infrared Output	0

## 42.5.1 CMT\_IRO — Infrared Output

This output signal is driven by the modulator output when MSC[MCGEN] is set and OC[IROPEN] is set. The CMT\_IRO signal starts a valid transmission with a delay, after MSC[MCGEN] bit be asserted to high, that can be calculated based on two register bits. The following table shows how to calculate this delay.

If MSC[MCGEN] bit is cleared and OC[IROPEN] bit is set, the signal is driven by OC[IROL] bit. This enables user software to directly control the state of the CMT\_IRO signal by writing to OC[IROL] bit. If OC[IROPEN] bit is cleared, the signal is disabled and is not driven by the CMT module. Therefore, CMT can be configured as a modulo timer for generating periodic interrupts without causing signal activity.

Table 42-3. CMT\_IRO signal delay calculation

Condition	Delay (bus clock cycles)
MSC[CMTDIV] = 0	PPS[PPSDIV] + 2
MSC[CMTDIV] > 0	(PPS{PPSDIV] × 2) + 3

## 42.6 Memory Map/Register Definition

The following registers control and monitor CMT operation.

The address of a register is the sum of a base address and an address offset. The base address is defined at the chip level. The address offset is defined at the module level.




## **CMT** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_2000	CMT Carrier Generator High Data Register 1 (CMT_CGH1)	8	R/W	Undefined	42.6.1/ 1034
4006_2001	CMT Carrier Generator Low Data Register 1 (CMT_CGL1)	8	R/W	Undefined	42.6.2/ 1035
4006_2002	CMT Carrier Generator High Data Register 2 (CMT_CGH2)	8	R/W	Undefined	42.6.3/ 1036
4006_2003	CMT Carrier Generator Low Data Register 2 (CMT_CGL2)	8	R/W	Undefined	42.6.4/ 1036
4006_2004	CMT Output Control Register (CMT_OC)	8	R/W	00h	42.6.5/ 1037
4006_2005	CMT Modulator Status and Control Register (CMT_MSC)	8	R/W	00h	42.6.6/ 1038
4006_2006	CMT Modulator Data Register Mark High (CMT_CMD1)	8	R/W	Undefined	42.6.7/ 1039
4006_2007	CMT Modulator Data Register Mark Low (CMT_CMD2)	8	R/W	Undefined	42.6.8/ 1040
4006_2008	CMT Modulator Data Register Space High (CMT_CMD3)	8	R/W	Undefined	42.6.9/ 1040
4006_2009	CMT Modulator Data Register Space Low (CMT_CMD4)	8	R/W	Undefined	42.6.10/ 1041
4006_200A	CMT Primary Prescaler Register (CMT_PPS)	8	R/W	00h	42.6.11/ 1041
4006_200B	CMT Direct Memory Access (CMT_DMA)	8	R/W	00h	42.6.12/ 1042

# **CMT Carrier Generator High Data Register 1 (CMT\_CGH1)**

This data register contain the primary high value for generating the carrier output.

Address: CMT\_CGH1 is 4006\_2000h base + 0h offset = 4006\_2000h



<sup>\*</sup> Notes:

x = Undefined at reset.




## **CMT\_CGH1** field descriptions

Field	Description
7–0 PH	Primary Carrier High Time Data Value  When selected, these bits contain the number of input clocks required to generate the carrier high time period. When operating in Time mode, this register is always selected. When operating in FSK mode, this register and the secondary register pair are alternately selected under control of the modulator. The primary carrier high time value is undefined out of reset. These bits must be written to non-zero values
	before the carrier generator is enabled to avoid spurious results.

## 42.6.2 CMT Carrier Generator Low Data Register 1 (CMT\_CGL1)

This data register contain the primary low value for generating the carrier output.

Address: CMT\_CGL1 is 4006\_2000h base + 1h offset = 4006\_2001h



<sup>\*</sup> Notes:

#### **CMT\_CGL1** field descriptions

Field	Description	
7–0 PL	Primary Carrier Low Time Data Value  When selected, these bits contain the number of input clocks required to generate the carrier low time period. When operating in Time mode, this register is always selected. When operating in FSK mode, this register and the secondary register pair are alternately selected under control of the modulator. The primary carrier low time value is undefined out of reset. These bits must be written to non-zero values before the carrier generator is enabled to avoid spurious results.	


<sup>•</sup> x = Undefined at reset.



## 42.6.3 CMT Carrier Generator High Data Register 2 (CMT\_CGH2)

This data register contain the secondary high value for generating the carrier output.

Address: CMT\_CGH2 is 4006\_2000h base + 2h offset = 4006\_2002h



<sup>\*</sup> Notes:


#### **CMT\_CGH2** field descriptions

Field	Description
7–0 SH	Secondary Carrier High Time Data Value  When selected, these bits contain the number of input clocks required to generate the carrier high time period. When operating in Time mode, this register is never selected. When operating in FSK mode, this register and the primary register pair are alternately selected under control of the modulator. The secondary carrier high time value is undefined out of reset. These bits must be written to nonzero values
	before the carrier generator is enabled when operating in FSK mode.

## 42.6.4 CMT Carrier Generator Low Data Register 2 (CMT\_CGL2)

This data register contain the secondary low value for generating the carrier output.

Address: CMT\_CGL2 is 4006\_2000h base + 3h offset = 4006\_2003h



<sup>\*</sup> Notes:

#### **CMT\_CGL2** field descriptions

Field	Description
7–0 SL	Secondary Carrier Low Time Data Value  When selected, these bits contain the number of input clocks required to generate the carrier low time period. When operating in Time mode, this register is never selected. When operating in FSK mode, this register and the primary register pair are alternately selected under control of the modulator. The
	secondary carrier low time value is undefined out of reset. These bits must be written to nonzero values before the carrier generator is enabled when operating in FSK mode.

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

<sup>•</sup> x = Undefined at reset.


x = Undefined at reset.



## 42.6.5 CMT Output Control Register (CMT\_OC)

This register is used to control the IRO signal of the CMT module.

Address: CMT\_OC is 4006\_2000h base + 4h offset = 4006\_2004h



#### **CMT\_OC** field descriptions


Field	Description
7	IRO Latch Control
IROL	Reading IROL reads the state of the IRO latch. Writing to IROL changes the state of the CMT_IRO signal when MSC[MCGEN] bit is cleared and the IROPEN bit is set.
6	CMT Output Polarity
CMTPOL	The CMTPOL bit controls the polarity of the CMT_IRO signal of the CMT.
	0 CMT_IRO signal is active low
	1 CMT_IRO signal is active high
5	IRO Pin Enable
IROPEN	The IROPEN bit is used to enable and disable the CMT_IRO signal. When CMT_IRO signal is enabled, it is an output that drives out either the CMT transmitter output or the state of the IROL bit depending on whether MSC[MCGEN] bit is set or not. Also, the state of the output is either inverted or not depending on the state of the CMTPOL bit. When CMT_IRO signal is disabled, it is in a high impedance state so as not to draw any current. This signal is disabled during reset.
	0 CMT_IRO signal disabled
	1 CMT_IRO signal enabled as output
4–0 Reserved	This read-only field is reserved and always has the value zero.



## 42.6.6 CMT Modulator Status and Control Register (CMT\_MSC)

The MSC register contains the modulator and carrier generator enable (MCGEN), end of cycle interrupt enable (EOCIE), FSK mode select (FSK), baseband enable (BASE), extended space (EXSPC), prescaler (CMTDIV) bits, and the end of cycle (EOCF) status bit.

Address: CMT\_MSC is 4006\_2000h base + 5h offset = 4006\_2005h



#### **CMT\_MSC** field descriptions

Field	Description
7 EOCF	End Of Cycle Status Flag
	<ul> <li>The EOCF bit is set when:</li> <li>The modulator is not currently active and the MCGEN bit is set to begin the initial CMT transmission.</li> <li>At the end of each modulation cycle while the MCGEN bit is set. This is recognized when a match occurs between the contents of the space period register and the down counter. At this time, the counter is initialized with the (possibly new) contents of the mark period buffer, CMT_CMD1 and CMT_CMD2, and the space period register is loaded with the (possibly new) contents of the space period buffer, CMT_CMD3 and CMT_CMD4.</li> </ul>
	This flag is cleared by a read of the MSC register followed by an access of CMD2 or CMD4 or by the DMA transfer.
	0 No end of modulation cycle occurrence since flag last cleared
	1 End of modulator cycle has occurred
6–5	CMT Clock Divide Prescaler
CMTDIV	The Secondary Prescaler causes the CMT to be clocked at the IF signal frequency, or the IF frequency divided by 2 ,4, or 8. Since these bits are not double buffered, they should not be changed during a transmission.
	00 IF ÷ 1 01 IF ÷ 2 10 IF ÷ 4 11 IF ÷ 8
4	Extended Space Enable
EXSPC	The EXSPC bit enables extended space operation.
	0 Extended space disabled
	1 Extended space enabled




## **CMT\_MSC** field descriptions (continued)

Field	Description
3 BASE	Baseband Enable
	When set, the BASE bit disables the carrier generator and forces the carrier output high for generation of baseband protocols. When BASE is cleared, the carrier generator is enabled and the carrier output toggles at the frequency determined by values stored in the carrier data registers. This bit is cleared by reset. This bit is not double buffered and should not be written to during a transmission.
	0 Baseband mode disabled
	1 Baseband mode enabled
2	FSK Mode Select
FSK	The FSK bit enables FSK operation.
	0 CMT operates in Time or Baseband mode
	1 CMT operates in FSK mode
1 EOCIE	End of Cycle Interrupt Enable
EOGIE	A CPU interrupt will be requested when EOCF is set if EOCIE is high.
	0 CPU interrupt disabled
	1 CPU interrupt enabled
0 MCGEN	Modulator and Carrier Generator Enable
MCGEN	Setting MCGEN will initialize the carrier generator and modulator and will enable all clocks. Once enabled, the carrier generator and modulator will function continuously. When MCGEN is cleared, the current modulator cycle will be allowed to expire before all carrier and modulator clocks are disabled (to save power) and the modulator output is forced low. To prevent spurious operation, the user should initialize all data and control registers before enabling the system.
	0 Modulator and carrier generator disabled
	1 Modulator and carrier generator enabled

# 42.6.7 CMT Modulator Data Register Mark High (CMT\_CMD1)

The contents of this register are transferred to the modulator down counter upon the completion of a modulation period.

Address: CMT\_CMD1 is 4006\_2000h base + 6h offset = 4006\_2006h



<sup>\*</sup> Notes:

x = Undefined at reset.



#### wemory Map/Register Definition


#### **CMT\_CMD1** field descriptions

Field	Description
7–0 MB[15:8]	These bits control the upper mark periods of the modulator for all modes.

## 42.6.8 CMT Modulator Data Register Mark Low (CMT\_CMD2)

The contents of this register are transferred to the modulator down counter upon the completion of a modulation period.

Address: CMT\_CMD2 is 4006\_2000h base + 7h offset = 4006\_2007h



<sup>\*</sup> Notes:


#### CMT\_CMD2 field descriptions

Field	Description
7–0 MB[7:0]	These bits control the lower mark periods of the modulator for all modes.

## 42.6.9 CMT Modulator Data Register Space High (CMT\_CMD3)

The contents of this register are transferred to the space period register upon the completion of a modulation period.

Address: CMT\_CMD3 is 4006\_2000h base + 8h offset = 4006\_2008h



<sup>\*</sup> Notes:

x = Undefined at reset.

<sup>•</sup> x = Undefined at reset.




#### **CMT\_CMD3** field descriptions

Field	Description
7–0 SB[15:8]	These bits control the upper space periods of the modulator for all modes.

## 42.6.10 CMT Modulator Data Register Space Low (CMT\_CMD4)

The contents of this register are transferred to the space period register upon the completion of a modulation period.

Address: CMT\_CMD4 is 4006\_2000h base + 9h offset = 4006\_2009h



<sup>\*</sup> Notes:


#### **CMT\_CMD4** field descriptions

Field	Description
7–0 SB[7:0]	These bits control the lower space periods of the modulator for all modes.

## 42.6.11 CMT Primary Prescaler Register (CMT PPS)

This register is used to set the primary prescaler bits (PPSDIV).

Address: CMT\_PPS is 4006\_2000h base + Ah offset = 4006\_200Ah



### **CMT\_PPS** field descriptions

Field	Description
7–4 Reserved	This read-only field is reserved and always has the value zero.
3–0 PPSDIV	Primary Prescaler Divider

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

<sup>•</sup> x = Undefined at reset.



#### wemory Map/Register Definition


### **CMT\_PPS** field descriptions (continued)

Field	Description
	The primary prescaler divides the CMT clock to generate the Intermediate Frequency clock enable to the secondary prescaler.
	0000 Bus Clock ÷ 1
	0001 Bus Clock ÷ 2
	0010 Bus Clock ÷ 3
	0011 Bus Clock ÷ 4
	0100 Bus Clock ÷ 5
	0101 Bus Clock ÷ 6
	0110 Bus Clock ÷ 7
	0111 Bus Clock ÷ 8
	1000 Bus Clock ÷ 9
	1001 Bus Clock ÷ 10
	1010 Bus Clock ÷ 11
	1011 Bus Clock ÷ 12
	1100 Bus Clock ÷ 13
	1101 Bus Clock ÷ 14
	1110 Bus Clock ÷ 15
	1111 Bus Clock ÷ 16

## 42.6.12 CMT Direct Memory Access (CMT\_DMA)

This register is used to enable/disable direct memory access (DMA).

Address: CMT\_DMA is 4006\_2000h base + Bh offset = 4006\_200Bh



#### **CMT\_DMA** field descriptions

Field	Description
7–1 Reserved	This read-only field is reserved and always has the value zero.
0 DMA	DMA Enable  This bit enables the DMA protocol.



#### CMT\_DMA field descriptions (continued)

Field	Description
	0 DMA transfer request and done are disabled
	DMA transfer request and done are enabled

## 42.7 Functional Description

The CMT module consists primarily of clock divider, carrier generator and modulator.

#### 42.7.1 Clock Divider

The CMT was originally designed to be based on 8 MHz bus clock that could be divided by 1, 2, 4 or 8 times accordingly with the specification. To be compatible with higher bus frequency, the Primary Prescaler (PPS) was developed to receive a higher frequency and generate a clock enable signal called Intermediate Frequency (IF). This IF should be approximately equal to 8 MHz and will work as a clock enable to the Secondary Prescaler. The following figure shows the clock divider block diagram.




Figure 42-14. Clock Divider Block Diagram

For compatibility with previous versions of CMT, when bus clock = 8 MHz, the PPS should be configured to zero. The PPS counter is selected according to the bus clock to generate an intermediate frequency approximately equal to 8 MHz.

## 42.7.2 Carrier Generator

The carrier generator resolution is 125 ns when operating with an 8 MHz intermediate frequency signal and the Secondary Prescaler is set to divide by 1 (MSC[CMTDIV] = 00). The carrier generator can generate signals with periods between 250 ns (4 MHz) and 127.5 µs (7.84 kHz) in steps of 125 ns. The following table shows the relationship between the clock divide bits and the carrier generator resolution, minimum carrier generator period, and minimum modulator period.



**runctional Description** 

Table 42-17. Clock Divider

Bus Clock (MHz)	MSC[CMTDIV]	Carrier Generator Resolution (µs)	Min. Carrier Generator Period (μs)	Min. Modulator Period (μs)
8	00	0.125	0.25	1.0
8	01	0.25	0.5	2.0
8	10	0.5	1.0	4.0
8	11	1.0	2.0	8.0

The possible duty cycle options depend upon the number of counts required to complete the carrier period. For example, 1.6 MHz signal has a period of 625 ns and will therefore require 5 x 125 ns counts to generate. These counts may be split between high and low times, so the duty cycles available will be 20% (one high, four low), 40% (two high, three low), 60% (three high, two low) and 80% (four high, one low).

For lower frequency signals with larger periods, higher resolution (as a percentage of the total period) duty cycles are possible.

The carrier signal is generated by counting a register-selected number of input clocks (125 ns for an 8 MHz bus) for both the carrier high time and the carrier low time. The period is determined by the total number of clocks counted. The duty cycle is determined by the ratio of high time clocks to total clocks counted. The high and low time values are user programmable and are held in two registers.

An alternate set of high/low count values is held in another set of registers to allow the generation of dual frequency FSK (frequency shift keying) protocols without CPU intervention.

#### Note

Only non-zero data values are allowed. The carrier generator will not work if any of the count values are equal to zero.

MSC[MCGEN] bit must be set and MSC[BASE] bit must be cleared to enable carrier generator clocks. When MSC[BASE] bit is set, the carrier output to the modulator is held high continuously. Following figure represents the block diagram of the clock generator.






Figure 42-15. Carrier Generator Block Diagram

The high/low time counter is an 8-bit up counter. After each increment, the contents of the counter are compared with the appropriate high or low count value register. When the compare value is reached, the counter is reset to a value of 0x01, and the compare is redirected to the other count value register.

Assuming that the high time count compare register is currently active, a valid compare will cause the carrier output to be driven low. The counter will continue to increment (starting at reset value of 0x01). When the value stored in the selected low count value register is reached, the counter will again be reset and the carrier output will be driven high.

The cycle repeats, automatically generating a periodic signal which is directed to the modulator. The lowest frequency (maximum period) and highest frequency (minimum period) which can be generated are defined as:

$$f_{\text{max}} = f_{\text{CMTCLK}} \div (2 \text{ x } 1) \text{ Hz}$$

$$f_{min} = f_{CMTCLK} \div (2 \times (2^8 - 1)) Hz$$

In the general case, the carrier generator output frequency is:

$$f_{cg} = f_{CMTCLK} \div (Highcount + Lowcount) Hz$$

Where: 0 < Highcount < 256 and

0 < Lowcount < 256



#### **runctional Description**

The duty cycle of the carrier signal is controlled by varying the ratio of high time to low + high time. As the input clock period is fixed, the duty cycle resolution will be proportional to the number of counts required to generate the desired carrier period.

$$DutyCycle = \frac{Highcount}{Highcount+Lowcount}$$

## 42.7.3 Modulator

The modulator block controls the state of the infrared out signal (IRO). The modulator output is gated on to the IRO signal when the modulator/carrier generator is enabled. When the modulator/carrier generator is disabled, the IRO signal is controlled by the state of the IRO latch. OC[CMTPOL] enables the IRO signal to be active high or active low.

In CMT modes, the modulator functions as given below:

- In Time mode, the modulator can gate the carrier onto the modulator output.
- In Baseband mode, the modulator can control the logic level of the modulator output.
- In FSK mode, the modulator can count carrier periods and instruct the carrier generator to alternate between two carrier frequencies whenever a modulation period (mark + space counts) expires.

The modulator provides a simple method to control protocol timing. The modulator has a minimum resolution of 1.0  $\mu$ s with an 8 MHz . It can count bus clocks (to provide real-time control) or it can count carrier clocks (for self-clocked protocols).

The modulator includes a 17-bit down counter with underflow detection. The counter is loaded from the 16-bit modulation mark period buffer registers, CMD1 and CMD2. The most significant bit is loaded with a logic zero and serves as a sign bit. When the counter holds a positive value, the modulator gate is open and the carrier signal is driven to the transmitter block.

When the counter underflows, the modulator gate is closed and a 16-bit comparator is enabled which compares the logical complement of the value of the down counter with the contents of the modulation space period register which has been loaded from the registers, CMD3 and CMD4.

When a match is obtained, the cycle repeats by opening the modulator gate, reloading the counter with the contents of CMD1 and CMD2, and reloading the modulation space period register with the contents of CMD3 and CMD4.



The activation of modulation space period is done when the carrier signal is low to prohibit cutting off the high pulse of a carrier signal. If the carrier signal is high, the modulator extends the mark period until the carrier signal become low. To de-assert the space period and assert the mark period, the carrier signal must have gone low to assure that a space period is not erroneously shortened.

Should the contents of the modulation space period register be all zeroes, the match will be immediate and no space period will be generated (for instance, for FSK protocols that require successive bursts of different frequencies).

MSC[MCGEN] must be set to enable the modulator timer.




Figure 42-16. Modulator Block Diagram

# 42.7.3.1 Time Mode

When the modulator operates in time mode (MSC[MCGEN] bit is set, MSC[BASE] and MSC[FSK] bits are cleared), the modulation mark period consists of an integer number of CMTCLK  $\div$  8 clock periods. The modulation space period consists of zero or an integer number of CMTCLK  $\div$  8 clock periods. With an 8 MHz IF and MSC[CMTDIV] = 00, the modulator resolution is 1  $\mu$ s and has a maximum mark and space period of about 65.535 ms each . See the following figure for an example of the time mode and baseband mode outputs.

The mark and space time equations for time and baseband mode are:



#### **runctional Description**

$$t_{\text{mark}} = (\text{CMD1:CMD2} + 1) \div (f_{\text{CMTCLK}} \div 8)$$

$$t_{\text{space}} = \text{CMD3:CMD4} \div (f_{\text{CMTCLK}} \div 8)$$

where CMD1:CMD2 and CMD3:CMD4 are the decimal values of the concatenated registers.




Figure 42-17. Example: CMT Output in Time and Baseband Modes with OC[CMTPOL]=0

#### 42.7.3.2 Baseband Mode

Baseband mode (MSC[MCGEN] and MSC[BASE] bits are set) is a derivative of time mode, where the mark and space period is based on (CMTCLK  $\div$  8) counts. The mark and space calculations are the same as in time mode. In this mode, the modulator output will be at a logic 1 for the duration of the mark period and at a logic 0 for the duration of a space period. See Figure 42-17 for an example of the output for both baseband and time modes. In the example, the carrier out frequency ( $f_{cg}$ ) is generated with a high count of 0x01 and a low count of 0x02 that results in a divide of 3 of CMTCLK with a 33% duty cycle. The modulator down counter was loaded with the value 0x0003 and the space period register with 0x0002.



#### **Note**

The waveforms in Figure 42-17 and Figure 42-18 are for the purpose of conceptual illustration and are not meant to represent precise timing relationships between the signals shown.

#### 42.7.3.3 FSK Mode

When the modulator operates in FSK mode (MSC[MCGEN] and MSC[FSK] bits are set, and MSC[BASE] bit is cleared), the modulation mark and space periods consist of an integer number of carrier clocks (space period can be zero). When the mark period expires, the space period is transparently started (as in time mode). The carrier generator toggles between primary and secondary data register values whenever the modulator space period expires.

The space period provides an interpulse gap (no carrier). If CMD3:CMD4 = 0x0000, then the modulator and carrier generator will switch between carrier frequencies without a gap or any carrier glitches (zero space).

Using timing data for carrier burst and interpulse gap length calculated by the CPU, FSK mode can automatically generate a phase-coherent, dual-frequency FSK signal with programmable burst and interburst gaps.

The mark and space time equations for FSK mode are:

$$t_{\text{mark}} = (\text{CMD1:CMD2} + 1) \div f_{\text{cg}}$$

$$t_{\text{space}} = \text{CMD3:CMD4} \div f_{\text{cg}}$$

Where  $f_{cg}$  is the frequency output from the carrier generator. The example in figure below shows what the IRO signal looks like in FSK mode with the following values: CMD1:CMD2 = 0x0003, CMD3:CMD4 = 0x0002, primary carrier high count = 0x01, primary carrier low count = 0x02, secondary carrier high count = 0x03, and secondary carrier low count = 0x01.



#### runctional Description




Figure 42-18. Example: CMT Output in FSK Mode

# 42.7.4 Extended Space Operation

In either time, baseband or FSK mode, the space period can be made longer than the maximum possible value of the space period register. Setting MSC[EXSPC] bit will force the modulator to treat the next modulation period (beginning with the next load of the counter and space period register) as a space period equal in length to the mark and space counts combined. Subsequent modulation periods will consist entirely of these extended space periods with no mark periods. Clearing MSC[EXSPC] will return the modulator to standard operation at the beginning of the next modulation period.

# 42.7.4.1 EXSPC Operation in Time Mode

To calculate the length of an extended space in time or baseband mode, add the mark and space times and multiply by the number of modulation periods when MSC[EXSPC] is set.

 $t_{exspace} = (t_{mark} + t_{space}) x$ (number of modulation periods)

For an example of extended space operation, see the following figure.

#### **Note**

The extended space enable feature can be used to emulate a zero mark event.






Figure 42-19. Extended Space Operation

## 42.7.4.2 EXSPC Operation in FSK Mode

In FSK mode, the modulator continues to count carrier out clocks, alternating between the primary and secondary registers at the end of each modulation period.

To calculate the length of an extended space in FSK mode, one needs to know whether MSC[EXSPC] bit was set on a primary or secondary modulation period, as well as the total number of both primary and secondary modulation periods completed while MSC[EXSPC] bit is high. A status bit for the current modulation is not accessible to the CPU. If necessary, software should maintain tracking of the current modulation cycle (primary or secondary). The extended space period ends at the completion of the space period time of the modulation period during which MSC[EXSPC] bit is cleared.

If MSC[EXSPC] bit was set during a primary modulation cycle, use the equation:

$$t_{\text{exspace}} = (t_{\text{space}})_p + (t_{\text{mark}} + t_{\text{space}})_s + (t_{\text{mark}} + t_{\text{space}})_p + \dots$$

Where the subscripts p and s refer to mark and space times for the primary and secondary modulation cycles.

If MSC[EXSPC] bit was set during a secondary modulation cycle, use the equation:

$$t_{\text{exspace}} = (t_{\text{space}})_{\text{s}} + (t_{\text{mark}} + t_{\text{space}})_{\text{p}} + (t_{\text{mark}} + t_{\text{space}})_{\text{s}} + \dots$$

# 42.8 CMT Interrupts and DMA

The CMT generates an Interrupt request or a DMA transfer request according to MSC[EOCIE], MSC[EOCF], DMA[DMA] bits.

Table 42-18. DMA Transfer Request x CMT Interrupt Request

MSC[EOCF] DMA[DMA] MSC[EOCIE] DMA transfer request CMT interrupt Request

MSC[EOCF]	DMA[DMA]	MSC[EOCIE]	DMA transfer request	CMT interrupt request
0	X	X	0	0
1	Х	0	0	0
1	0	1	0	1
1	1	1	1	0



### MSC[EOCF] is set when:

- The modulator is not currently active and MSC[MCGEN] bit is set to begin the initial CMT transmission
- At the end of each modulation cycle (when the counter is reloaded from CMD1:CMD2) while MSC[MCGEN] bit is set

In the case where MSC[MCGEN] bit is cleared and then set before the end of the modulation cycle, MSC[EOCF] bit will not be set when MSC[MCGEN] is set, but will become set at the end of the current modulation cycle.

When MSC[MCGEN] becomes disabled, the CMT module does not set the EOC flag at the end of the last modulation cycle.

If MSC[EOCIE] bit is high when MSC[EOCF] bit is set, the CMT module will generate an interrupt request or a DMA transfer request.

MSC[EOCF] bit must be cleared to prevent from being generated another event (interrupt or DMA request) after exiting the service routine. See following table.

 DMA[DM A]
 MSC[EOCIE]
 Description

 0
 X
 MSC[EOCF] bit is cleared by reading the CMT modulator status and control register MSC followed by an access of CMD2 or CMD4.

 1
 X
 MSC[EOCF] bit is cleared by the CMT DMA transfer done.

Table 42-19. How to clear MSC[EOCF] bit

The EOC interrupt is coincident with loading the down-counter with the contents of CMD1:CMD2 and loading the space period register with the contents of CMD3:CMD4. The EOC interrupt provides a means for the user to reload new mark/space values into the modulator data registers. Modulator data register updates will take effect at the end of the current modulation cycle. Note that the down-counter and space period register are updated at the end of every modulation cycle, irrespective of interrupt handling and the state of the EOCF flag.



# Chapter 43 Real Time Clock (RTC)

## 43.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

### 43.1.1 Features

The RTC module features include:

- Independent power supply, POR and 32 kHz crystal oscillator
- 32-bit seconds counter with roll-over protection and 32-bit alarm
- 16-bit prescaler with compensation that can correct errors between 0.12 ppm and 3906 ppm
- Register write protection
  - Lock register requires VBAT POR or software reset to enable write access
  - Access control registers require system reset to enable read and/or write access
- 1 Hz square wave output

# 43.1.2 Modes of operation

The RTC operates in one of two modes of operation, chip power-up and chip power-down.



#### negister definition

During chip power-down, RTC is powered from the backup power supply (VBAT) and is electrically isolated from the rest of the chip but continues to increment the time counter (if enabled) and retain the state of the RTC registers. The RTC registers are not accessible.

During chip power-up, RTC remains powered from the backup power supply (VBAT). All RTC registers are accessible by software and all functions are operational. If enabled, the 32.768 kHz clock can be supplied to the rest of the chip.

# 43.1.3 RTC signal descriptions

Table 43-1. RTC signal descriptions

Signal	Description	I/O
EXTAL32	32.768 kHz oscillator input	I
XTAL32	32.768 kHz oscillator output	0
RTC_CLKOUT	1Hz square-wave output	0
RTC_WAKEUP	Wakeup for external device	0

## 43.1.3.1 RTC clock output

The clock to the seconds counter is available on the RTC\_CLKOUT signal. It is a 1Hz square wave output.

# 43.1.3.2 RTC wakeup pin

The RTC wakeup pin is an open drain, active low, output that allows the RTC to wakeup the chip via an external component. The wakeup pin asserts when the wakeup pin enable is set, the RTC interrupt is asserted and the chip is powered down. The wakeup pin does not assert from the RTC seconds interrupt.

The wakeup pin is optional and may not be implemented on all devices.

# 43.2 Register definition

All registers must be accessed using 32-bit writes and all register accesses incur three wait states.



Write accesses to any register by non-supervisor mode software, when the supervisor access bit in the control register is clear, will terminate with a bus error.

Read accesses by non-supervisor mode software complete as normal.

Writing to a register protected by the write access register or lock register does not generate a bus error, but the write will not complete.


Reading a register protected by the read access register does not generate a bus error, but the register will read zero.

#### RTC memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4003_D000	RTC Time Seconds Register (RTC_TSR)	32	R/W	0000_0000h	43.2.1/ 1055
4003_D004	RTC Time Prescaler Register (RTC_TPR)	32	R/W	0000_0000h	43.2.2/ 1056
4003_D008	RTC Time Alarm Register (RTC_TAR)	32	R/W	0000_0000h	43.2.3/ 1056
4003_D00C	RTC Time Compensation Register (RTC_TCR)	32	R/W	0000_0000h	43.2.4/ 1057
4003_D010	RTC Control Register (RTC_CR)	32	R/W	0000_0000h	43.2.5/ 1058
4003_D014	RTC Status Register (RTC_SR)	32	R/W	0000_0001h	43.2.6/ 1060
4003_D018	RTC Lock Register (RTC_LR)	32	R/W	0000_00FFh	43.2.7/ 1061
4003_D01C	RTC Interrupt Enable Register (RTC_IER)	32	R/W	0000_0007h	43.2.8/ 1062
4003_D800	RTC Write Access Register (RTC_WAR)	32	R/W	0000_00FFh	43.2.9/ 1063
4003_D804	RTC Read Access Register (RTC_RAR)	32	R/W	0000_00FFh	43.2.10/ 1064

# 43.2.1 RTC Time Seconds Register (RTC\_TSR)

Address: RTC\_TSR is 4003\_D000h base + 0h offset = 4003\_D000h



#### negister definition

## RTC\_TSR field descriptions

Field	Description
31–0 TSR	Time Seconds Register
	When the time counter is enabled, the TSR is read only and increments once a second provided SR[TOF] or SR[TIF] are not set. The time counter will read as zero when SR[TOF] or SR[TIF] are set. When the time counter is disabled, the TSR can be read or written. Writing to the TSR when the time counter is disabled will clear the SR[TOF] and/or the SR[TIF]. Writing to the TSR register with zero is supported, but not recommended since TSR will read as zero when SR[TIF] or SR[TOF] are set (indicating the time is invalid).

# 43.2.2 RTC Time Prescaler Register (RTC\_TPR)

Address: RTC\_TPR is 4003\_D000h base + 4h offset = 4003\_D004h




#### RTC\_TPR field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 TPR	Time Prescaler Register  When the time counter is enabled, the TPR is read only and increments every 32.768 kHz clock cycle.  The time counter will read as zero when SR[TOF] or SR[TIF] are set. When the time counter is disabled, the TPR can be read or written. The TSR[TSR] increments when bit 14 of the TPR transitions from a logic one to a logic zero.

# 43.2.3 RTC Time Alarm Register (RTC\_TAR)

Address: RTC\_TAR is 4003\_D000h base + 8h offset = 4003\_D008h



#### RTC\_TAR field descriptions

Fie	eld	Description
31- TA		Time Alarm Register




## RTC\_TAR field descriptions (continued)

Field	Description
	When the time counter is enabled, the SR[TAF] is set whenever the TAR[TAR] equals the TSR[TSR] and the TSR[TSR] increments. Writing to the TAR clears the SR[TAF].

# 43.2.4 RTC Time Compensation Register (RTC\_TCR)

Address: RTC\_TCR is 4003\_D000h base + Ch offset = 4003\_D00Ch




### RTC\_TCR field descriptions

Field	Description
31–24 CIC	Compensation Interval Counter  Current value of the compensation interval counter. If the compensation interval counter equals zero then it is loaded with the contents of the CIR. If the CIC does not equal zero then it is decremented once a second.
23–16 TCV	Time Compensation Value  Current value used by the compensation logic for the present second interval. Updated once a second if the CIC equals 0 with the contents of the TCR field. If the CIC does not equal zero then it is loaded with zero (compensation is not enabled for that second increment).
15–8 CIR	Compensation Interval Register  Configures the compensation interval in seconds from 1 to 256 to control how frequently the TCR should adjust the number of 32.768 kHz cycles in each second. The value written should be one less than the number of seconds (for example, write zero to configure for a compensation interval of one second). This register is double buffered and writes do not take affect until the end of the current compensation interval.
7–0 TCR	Time Compensation Register  Configures the number of 32.768 kHz clock cycles in each second. This register is double buffered and writes do not take affect until the end of the current compensation interval.  80h Time prescaler register overflows every 32896 clock cycles  FFh Time prescaler register overflows every 32769 clock cycles.  00h Time prescaler register overflows every 32768 clock cycles.  11h Time prescaler register overflows every 32767 clock cycles  75h Time prescaler register overflows every 32641 clock cycles.



# 43.2.5 RTC Control Register (RTC\_CR)

Address: RTC\_CR is 4003\_D000h base + 10h offset = 4003\_D010h



## RTC\_CR field descriptions

Field	Description
31–15 Reserved	This read-only field is reserved and always has the value zero.
14 Reserved	This field is reserved. It must always be written to 0.
13 SC2P	Oscillator 2pF load configure  0 Disable the load. 1 Enable the additional load.
12 SC4P	Oscillator 4pF load configure  0 Disable the load. 1 Enable the additional load.
11 SC8P	Oscillator 8pF load configure  0 Disable the load. 1 Enable the additional load.
10 SC16P	Oscillator 16pF load configure  0 Disable the load. 1 Enable the additional load.

Table continues on the next page...




# RTC\_CR field descriptions (continued)

Field	Description
9 CLKO	Clock Output  The 32kHz clock is output to other peripherals  The 32kHz clock is not output to other peripherals
8 OSCE	Oscillator Enable  0 32.768 kHz oscillator is disabled.  1 32.768 kHz oscillator is enabled. After setting this bit, wait the oscillator startup time before enabling the time counter to allow the 32.768 kHz clock time to stabilize.
7–4 Reserved	This read-only field is reserved and always has the value zero.
3 UM	Update Mode  Allows the SR[TCE] to be written even when the Status Register is locked. When set, the SR[TCE] can always be written if the SR[TIF] or SR[TOF] are set or if the SR[TCE] is clear.  O Registers cannot be written when locked.  Registers can be written when locked under limited conditions.
2 SUP	Supervisor Access  O Non-supervisor mode write accesses are not supported and generate a bus error.  Non-supervisor mode write accesses are supported.
1 WPE	Wakeup Pin Enable  The wakeup pin is optional and not available on all devices.  0 Wakeup pin is disabled.  1 Wakeup pin is enabled and wakeup pin asserts if the RTC interrupt asserts and the chip is powered down.
0 SWR	Software Reset  O No effect  Resets all RTC registers except for the SWR bit and the RTC_WAR and RTC_RAR registers. The SWR bit is cleared after VBAT POR and by software explicitly clearing it.



# RTC Status Register (RTC\_SR)

Address: RTC\_SR is 4003\_D000h base + 14h offset = 4003\_D014h




## RTC\_SR field descriptions

Field	Description
31–5 Reserved	This read-only field is reserved and always has the value zero.
4 TCE	Time Counter Enable
	When time counter is disabled the TSR register and TPR register are writeable, but do not increment. When time counter is enabled the TSR register and TPR register are not writeable, but increment.
	Time counter is disabled.  Time counter is enabled.
3 Reserved	This read-only field is reserved and always has the value zero.
2 TAF	Time Alarm Flag
	Time alarm flag is set when the TAR[TAR] equals the TSR[TSR] and the TSR[TSR] increments. This bit is cleared by writing the TAR register.
	0 Time alarm has not occurred.
	1 Time alarm has occurred.
1 TOF	Time Overflow Flag
	Time overflow flag is set when the time counter is enabled and overflows. The TSR and TPR do not increment and read as zero when this bit is set. This bit is cleared by writing the TSR register when the time counter is disabled.
	0 Time overflow has not occurred.
	1 Time overflow has occurred and time counter is read as zero.
0 TIF	Time Invalid Flag
111	The time invalid flag is set on VBAT POR or software reset. The TSR and TPR do not increment and read as zero when this bit is set. This bit is cleared by writing the TSR register when the time counter is disabled.
	<ul><li>0 Time is valid.</li><li>1 Time is invalid and time counter is read as zero.</li></ul>



# 43.2.7 RTC Lock Register (RTC\_LR)

Address: RTC\_LR is 4003\_D000h base + 18h offset = 4003\_D018h




## RTC\_LR field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 Reserved	This read-only field is reserved and always has the value one.
6 LRL	Lock Register Lock  Once cleared, this bit can only be set by VBAT POR or software reset.  0 Lock register is locked and writes are ignored.  1 Lock register is not locked and writes complete as normal.
5 SRL	Status Register Lock  Once cleared, this bit can only be set by VBAT POR or software reset.  O Status register is locked and writes are ignored.  Status register is not locked and writes complete as normal.
4 CRL	Control Register Lock Once cleared, this bit can only be set by VBAT POR.  0 Control register is locked and writes are ignored. 1 Control register is not locked and writes complete as normal.
3 TCL	Time Compensation Lock  Once cleared, this bit can only be set by VBAT POR or software reset.  O Time compensation register is locked and writes are ignored.  Time compensation register is not locked and writes complete as normal.
2–0 Reserved	This read-only field is reserved and always has the value one.

# 43.2.8 RTC Interrupt Enable Register (RTC\_IER)

Address: RTC\_IER is 4003\_D000h base + 1Ch offset = 4003\_D01Ch




## RTC\_IER field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7–5 Reserved	This field is reserved.
4 Reserved	This field is reserved.
3 Reserved	This field is reserved.
2 TAIE	Time Alarm Interrupt Enable  O Time alarm flag does not generate an interrupt.  1 Time alarm flag does generate an interrupt.
1 TOIE	Time Overflow Interrupt Enable  O Time overflow flag does not generate an interrupt.  Time overflow flag does generate an interrupt.
0 TIIE	Time Invalid Interrupt Enable  O Time invalid flag does not generate an interrupt.  1 Time invalid flag does generate an interrupt.



# 43.2.9 RTC Write Access Register (RTC\_WAR)

Address: RTC\_WAR is 4003\_D000h base + 800h offset = 4003\_D800h



## RTC\_WAR field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 IERW	Interrupt Enable Register Write
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Writes to the interupt enable register are ignored.
	1 Writes to the interrupt enable register complete as normal.
6 LRW	Lock Register Write
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Writes to the lock register are ignored.
	1 Writes to the lock register complete as normal.
5 SRW	Status Register Write
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Writes to the status register are ignored.
	1 Writes to the status register complete as normal.
4 CRW	Control Register Write
Criv	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Writes to the control register are ignored.
	1 Writes to the control register complete as normal.
3 TCRW	Time Compensation Register Write
TOTIV	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Writes to the time compensation register are ignored.
	1 Writes to the time compensation register complete as normal.
2 TARW	Time Alarm Register Write
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Writes to the time alarm register are ignored.
	1 Writes to the time alarm register complete as normal.

Table continues on the next page...





#### negister definition

# RTC\_WAR field descriptions (continued)

Field	Description	
1 TPRW	Time Prescaler Register Write	
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.	
	0 Writes to the time prescaler register are ignored.	
	1 Writes to the time prescaler register complete as normal.	
0 TSRW	Time Seconds Register Write	
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.	
	0 Writes to the time seconds register are ignored.	
	1 Writes to the time seconds register complete as normal.	

# 43.2.10 RTC Read Access Register (RTC\_RAR)





#### RTC\_RAR field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.
7 IERR	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Reads to the interrupt enable register are ignored.
	1 Reads to the interrupt enable register complete as normal.
6 LRR	Lock Register Read
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Reads to the lock register are ignored.
	1 Reads to the lock register complete as normal.
5 SRR	Status Register Read
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Reads to the status register are ignored.
	1 Reads to the status register complete as normal.

Table continues on the next page...



## RTC\_RAR field descriptions (continued)

Field	Description
4 CRR	Control Register Read
01111	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Reads to the control register are ignored.
	1 Reads to the control register complete as normal.
3 TCRR	Time Compensation Register Read
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset
	0 Reads to the time compensation register are ignored.
	1 Reads to the time compensation register complete as normal.
2 TARR	Time Alarm Register Read
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Reads to the time alarm register are ignored.
	1 Reads to the time alarm register complete as normal.
1 TPRR	Time Prescaler Register Read
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Reads to the time prescaler register are ignored.
	1 Reads to the time prescaler register complete as normal.
0 TSRR	Time Seconds Register Read
	Once cleared, this bit is only set by system reset. It is not affected by VBAT POR or software reset.
	0 Reads to the time seconds register are ignored.
	1 Reads to the time seconds register complete as normal.

# 43.3 Functional description

# 43.3.1 Power, clocking and reset

The RTC is an always powered block that is powered by the battery power supply (VBAT). The battery power supply ensures that the RTC registers retain their state during chip power-down and that the RTC time counter remains operational.

The time counter within the RTC is clocked by a 32.768 kHz clock and can supply this clock to other peripherals. The 32.768 kHz clock can only be sourced from an external crystal using the oscillator that is part of the RTC module.



#### runctional description

The RTC includes its own analog POR block, which generates a power-on-reset signal whenever the RTC module is powered up and initializes all RTC registers to their default state. A software reset bit can also initialize all RTC registers. The RTC also monitors the chip power supply and electrically isolates itself when the rest of the chip is powered down.

Any attempt to access an RTC register (except the access control registers) when VBAT is powered down, when the RTC is electrically isolated, or when VBAT POR is asserted, will result in a bus error.

#### 43.3.1.1 Oscillator control

The 32.768 kHz crystal oscillator is disabled at VBAT POR and must be enabled by software. After enabling the cystal oscillator, wait the oscillator startup time before setting the SR[TCE] bit or using the oscillator clock external to the RTC.

The crystal oscillator includes tunable capacitors that can be configured by software. Do not change the capacitance unless the oscillator is disabled.

#### 43.3.1.2 Software reset

Writing one to the CR[SWR] forces the equivalent of a VBAT POR to the rest of the RTC module. The CR[SWR] is not affected by the software reset and must be cleared by software. The access control registers are not affected by either VBAT POR or the software reset; they are reset by the chip reset.

## 43.3.1.3 Supervisor access

When the supervisor access control bit is clear, only supervisor mode software can write to the RTC registers, non-supervisor mode software will generate a bus error. Both supervisor and non-supervisor mode software can always read the RTC registers.

## 43.3.2 Time counter

The time counter consists of a 32-bit seconds counter that increments once every second and a 16-bit prescaler register that increments once every 32.768 kHz clock cycle.



The time seconds register and time prescaler register can only be written when the SR[TCE] bit is clear. Always write to the prescaler register before writing to the seconds register, since the seconds register increments on the falling edge of bit 14 of the prescaler register.

The time prescaler register increments provided the SR[TCE] bit is set, the SR[TIF] is clear, the SR[TOF] is clear and the 32.768 kHz clock source is present. After enabling the oscillator, wait the oscillator startup time before setting the SR[TCE] bit to allow time for the oscillator clock output to stabilize.

If the time seconds register overflows then the SR[TOF] will set and the time prescaler register will stop incrementing. Clear the SR[TOF] by initializing the time seconds register. The time seconds register and time prescaler register read as zero whenever the SR[TOF] is set.

The SR[TIF] is set on VBAT POR and software reset and is cleared by initializing the time seconds register. The time seconds register and time prescaler register read as zero whenever the SR[TIF] is set.

# 43.3.3 Compensation

The compensation logic provides an accurate and wide compensation range and can correct errors as high as 3906 ppm and as low as 0.12 ppm. Note that the compensation factor must be calculated externally to the RTC and supplied by software to the compensation register. The RTC itself does not calculate the amount of compensation that is required, although the 1 Hz clock is output to an external pin in support of external calibration logic.

Crystal compensation can be supported by using firmware and crystal characteristics to determine the compensation amount. Temperature compensation can be supported by firmware that periodically measures the external temperature (via ADC) and updates the compensation register based on a look-up table that specifies the change in crystal frequency over temperature.

The compensation logic alters the number of 32.768 kHz clock cycles it takes for the prescaler register to overflow and increment the time seconds counter. The time compensation value is used to adjust the number of clock cycles between -127 and +128. Cycles are added or subtracted from the prescaler register when the prescaler register equals 0x3FFF and then increments. The compensation interval is used to adjust the frequency at which the time compensation value is used (from once a second to once every 256 seconds).



#### runctional description

Updates to the time compensation register will not take effect until the next time the time seconds register increments and provided the previous compensation interval has expired. When the compensation interval is set to other than once a second then the compensation is applied in the first second interval and the remaining second intervals receive no compensation.

Compensation is disabled by configuring the time compensation register to zero.

### 43.3.4 Time alarm

The time alarm register, SR[TAF] and IER[TAIE] allow the RTC to generate an interrupt at a predefined time. The 32-bit time alarm register is compared with the 32-bit time seconds register each time it increments. The SR[TAF] will set when the time alarm register equals the time seconds register and the time seconds register increments.

The time alarm flag is cleared by writing the time alarm register. This will usually be the next alarm value, although writing a value that is less than the time seconds register (such as zero) will prevent the time alarm flag from setting again. The time alarm flag cannot otherwise be disabled, although the interrupt it generates is enabled or disabled by IER[TAIE].

# 43.3.5 Update mode

The update mode bit (CR[UM]) in the control register configures software write access to the time counter enable (SR[TCE]) bit. When CR[UM] is clear, SR[TCE] can only be written when the LR[SRL] bit is set. When CR[UM] is set, the SR[TCE] can also be written when SR[TCE] is clear or when SR[TIF] or SR[TOF] are set. This allows the time seconds and prescaler registers to be initialized whenever time is invalidated, while preventing the time seconds and prescaler registers from being changed on the fly. When LR[SRL] is set, the CR[UM] bit has no effect on SR[TCE].

# 43.3.6 Register lock

The lock register can be used to block write accesses to certain registers until the next VBAT POR or software reset. Locking the control register will disable the software reset. Locking the lock register will block future updates to the lock register.

Write accesses to a locked register are ignored and do not generate a bus error.



### 43.3.7 Access control

The read access and write access registers are implemented in the chip power domain and reset on the chip reset (they are not affected by the VBAT POR or the software reset). They are used to block read or write accesses to each register until the next chip system reset. When accesses are blocked the bus access is not seen in the VBAT power supply and does not generate a bus error.

# 43.3.8 Interrupt

The RTC Interrupt is asserted whenever a status flag and the corresponding interrupt enable bit are both set. It is always asserted on VBAT POR, software reset and when the VBAT power supply is powered down. The RTC interrupt is enabled at the chip level by enabling the chip-specific RTC clock gate control bit. The RTC Interrupt can be used to wakeup the chip from any low power mode.

The optional RTC seconds interrupt is an edge-sensitive interrupt with a dedicated interrupt vector that is generated once a second and requires no software overhead (there is no corresponding status flag to clear). It is enabled in the RTC by the time seconds interrupt enable bit and enabled at the chip level by setting the chip-specific RTC clock gate control bit. The RTC seconds interrupt does not cause the RTC wakeup pin to assert. This interrupt is optional and may not be implemented on all devices.



runctional description



# **Chapter 44 Universal Serial Bus OTG Controller (USBOTG)**

## 44.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

This section describes the USB. The OTG implementation in this module provides limited host functionality as well as device solutions for implementing a USB 2.0 full-speed/low-speed compliant peripheral. The OTG implementation supports the On-The-Go (OTG) addendum to the USB 2.0 Specification. Only one protocol can be active at any time. A negotiation protocol must be used to switch to a USB host functionality from a USB device. This is known as the Master Negotiation Protocol (MNP).

## 44.1.1 USB

The USB is a cable bus that supports data exchange between a host computer and a wide range of simultaneously accessible peripherals. The attached peripherals share USB bandwidth through a host-scheduled, token-based protocol. The bus allows peripherals to be attached, configured, used, and detached while the host and other peripherals are in operation.

USB software provides a uniform view of the system for all application software, hiding implementation details making application software more portable. It manages the dynamic attach and detach of peripherals.

There is only one host in any USB system. The USB interface to the host computer system is referred to as the Host Controller.

There may be multiple USB devices in any system such as joysticks, speakers, printers, etc. USB devices present a standard USB interface in terms of comprehension, response, and standard capability.



#### muroduction

The host initiates transactions to specific peripherals, while the device responds to control transactions. The device sends and receives data to and from the host using a standard USB data format. USB 2.0 full-speed /low-speed peripherals operate at 12Mb/s or 1.5 Mb/s.

For additional information, refer to the USB 2.0 specification.




Figure 44-1. Example USB 2.0 System Configuration

## 44.1.2 USB On-The-Go

USB (Universal Serial Bus) is a popular standard for connecting peripherals and portable consumer electronic devices such as digital cameras and hand-held computers to host PCs. The On-The-Go (OTG) Supplement to the USB Specification extends USB to peer-to-peer application. Using USB OTG technology consumer electronics, peripherals and portable devices can connect to each other (for example, a digital camera can connect directly to a printer, or a keyboard can connect to a Personal Digital Assistant) to exchange data.

With the USB On-The-Go product, you can develop a fully USB-compliant peripheral device that can also assume the role of a USB host. Software determines the role of the device based on hardware signals, and then initializes the device in the appropriate mode of operation (host or peripheral) based on how it is connected. After connecting the devices can negotiate using the OTG protocols to assume the role of host or peripheral based on the task to be accomplished.

For additional information, refer to the *On-The-Go Supplement to the USB 2.0 Specification*.






Figure 44-2. Example USB 2.0 On-The-Go Configurations

## 44.1.3 USB-FS Features

- USB 1.1 and 2.0 compliant full-speed device controller
- 16-Bidirectional end points
- DMA or FIFO data stream interfaces
- Low-power consumption
- On-The-Go protocol logic

# 44.2 Functional Description

The USB-FS 2.0 full-speed/low-speed module communicates with the processor core through status registers, control registers, and data structures in memory.



**Programmers Interface** 

### 44.2.1 Data Structures

The function of the device operation is to transfer a request in the memory image to and from the Universal Serial Bus. To efficiently manage USB endpoint communications the USB-FS implements a Buffer Descriptor Table (BDT) in system memory. See Figure 44-3.

# 44.3 Programmers Interface

This section discusses the major components of the programming model for the USB module.

# 44.3.1 Buffer Descriptor Table

To efficiently manage USB endpoint communications the USB-FS implements a Buffer Descriptor Table (BDT) in system memory. The BDT resides on a 512 byte boundary in system memory and is pointed to by the BDT Page Registers. Every endpoint direction requires two eight-byte Buffer Descriptor entries. Therefore, a system with 16 fully bidirectional endpoints would require 512 bytes of system memory to implement the BDT. The two Buffer Descriptor (BD) entries allows for an EVEN BD and ODD BD entry for each endpoint direction. This allows the microprocessor to process one BD while the USB-FS is processing the other BD. Double buffering BDs in this way allows the USB-FS to easily transfer data at the maximum throughput provided by USB.

The software API intelligently manages buffers for the USB-FS by updating the BDT when needed. This allows the USB-FS to efficiently manage data transmission and reception, while the microprocessor performs communication overhead processing and other function dependent applications. Because the buffers are shared between the microprocessor and the USB-FS a simple semaphore mechanism is used to distinguish who is allowed to update the BDT and buffers in system memory. A semaphore bit, the OWN bit, is cleared to 0 when the BD entry is owned by the microprocessor. The microprocessor is allowed read and write access to the BD entry and the buffer in system memory when the OWN bit is 0. When the OWN bit is set to 1, the BD entry and the buffer in system memory are owned by the USB-FS. The USB-FS now has full read and write access and the microprocessor should not modify the BD or its corresponding data buffer. The BD also contains indirect address pointers to where the actual buffer resides in system memory. This indirect address mechanism is shown in the following diagram.






Figure 44-3. Buffer Descriptor Table

# 44.3.2 Rx vs. Tx as a USB Target Device or USB Host

The USB-FS core uses software control to switch between two modes of operation:

- USB target device
- USB hosts

In either mode, USB host or USB target device, the same data paths and buffer descriptors are used for the transmission and reception of data. For this reason, a USB-FS core centric nomenclature is used to describe the direction of the data transfer between the USB-FS core and the USB:

#### Rx (or receive)

describes transfers that move data from the USB to memory.

#### Tx (or transmit)

describes transfers that move data from memory to the USB.

The following table shows how the data direction corresponds to the USB token type in host and target device applications.

Table 44-1. Data Direction for USB Host or USB Target

	Rx	Тх
Device	OUT or Setup	IN

Table continues on the next page...



**Frogrammers Interface** 

Table 44-1. Data Direction for USB Host or USB Target (continued)

	Rx	Tx
Host	IN	Out or Setup

# 44.3.3 Addressing Buffer Descriptor Table Entries

An understanding of the addressing mechanism of the Buffer Descriptor Table is useful when accessing endpoint data via the USB-FS or microprocessor. Some points of interest are:

- The Buffer Descriptor Table occupies up to 512 bytes of system memory.
- 16 bidirectional endpoints can be supported with a full BDT of 512 bytes.
- 16 bytes are needed for each USB endpoint direction.
- Applications with less than 16 endpoints require less RAM to implement the BDT.
- The BDT Page Registers point to the starting location of the BDT.
- The BDT must be located on a 512-byte boundary in system memory.
- All enabled TX and RX endpoint BD entries are indexed into the BDT to allow easy access via the USB-FS or MCU core.

When a USB token on an enabled endpoint is received, the USB-FS uses its integrated DMA controller to interrogate the BDT. The USB-FS reads the corresponding endpoint BD entry to determine if it owns the BD and corresponding buffer in system memory.

To compute the entry point in to the BDT, the BDT\_PAGE registers is concatenated with the current endpoint and the TX and ODD fields to form a 32-bit address. This address mechanism is shown in the following diagrams:

Table 44-2. BDT Address Calculation Fields

Field	Description
BDT_PAGE	BDT_PAGE registers in the Control Register Block
END_POINT	END POINT field from the USB TOKEN
TX	1 for an TX transmit transfers and 0 for an RX receive transfers
ODD	This bit is maintained within the USB-FS SIE. It corresponds to the buffer currently in use. The buffers are used in a ping-pong fashion.

# 44.3.4 Buffer Descriptor Formats

The Buffer Descriptors (BD) provide endpoint buffer control information for the USB-FS and microprocessor. The Buffer Descriptors have different meaning based on whether it is the USB-FS or microprocessor reading the BD in memory.



The USB-FS Controller uses the data stored in the BDs to determine:

- Who owns the buffer in system memory
- Data0 or Data1 PID
- Release Own upon packet completion
- No address increment (FIFO Mode)
- Data toggle synchronization enable
- How much data is to be transmitted or received
- Where the buffer resides in system memory

While the microprocessor uses the data stored in the BDs to determine:

- Who owns the buffer in system memory
- Data0 or Data1 PID
- The received TOKEN PID
- How much data was transmitted or received
- Where the buffer resides in system memory

The format for the BD is shown in the following figure.

**Table 44-3. Buffer Descriptor Byte Format** 

31:26	25:16	15:8	7	6	5	4	3	2	1	0
RSVD	ВС	RSVD	OWN	DATA0/1	KEEP/	NINC/	DTS/	BDT_STALL/	0	٥
NOVD	(10 bits)	N3VD	OVVIN	DATAU/T	TOK_PID[3]	TOK_PID[2]	TOK_PID[1]	TOK_PID[0]	0	
	Buffer Address (32-Bits)									

Table 44-4. Buffer Descriptor Byte Fields

Field	Description
31 –26	Reserved
RSVD	
25 –16	The Byte Count bits represent the 10-bit Byte Count. The USB-FS SIE changes this field upon the
BC[9:0]	completion of a RX transfer with the byte count of the data received.
15 –8	Reserved
RSVD	

Table continues on the next page...



#### **Programmers Interface**

# Table 44-4. Buffer Descriptor Byte Fields (continued)

Field	Description
7 OWN	The OWN bit determines whether the microprocessor or the USB-FS currently owns the buffer. Except when KEEP=1, the SIE writes a 0 to this bit when it has completed a token. This byte of the BD should always be the last byte the microprocessor updates when it initializes a BD.
	<ul> <li>The microprocessor has exclusive access to the BD. The USB-FS ignores all other fields in the BD.</li> <li>1</li> </ul>
	USB-FS has exclusive access to the BD. After the BD has been assigned to the USB-FS, the microprocessor should not change it in any way.
6 DATA0/1	This bit defines if a DATA0 field (DATA0/1=0) or a DATA1 (DATA0/1=1) field was transmitted or received. It is unchanged by the USB-FS.
5 KEEP/ TOK_PID[3]	Typically this bit is set (that is, 1) with ISO endpoints feeding a FIFO. The microprocessor is not informed that a token has been processed, the data is simply transferred to or from the FIFO. If KEEP is set, normally the NINC bit is also set to prevent address increment.  0
	Bit 3 of the current token PID is written back in to the BD by the USB-FS. Allows the USB-FS to release the BD when a token has been processed.  1 This bit is unchanged by the USB-FS. If the OWN bit also is set, the BD remains owned by the USB-FS forever.
4 NINC/ TOK_PID[2]	The No Increment (NINC) bit disables the DMA engine address increment. This forces the DMA engine to read or write from the same address. This is useful for endpoints when data needs to be read from or written to a single location such as a FIFO. Typically this bit is set with the KEEP bit for ISO endpoints that are interfacing to a FIFO.  0
	the USB-FS writes bit 2 of the current token PID to the BD.  1 This bit is unchanged by the USB-FS.
3 DTS/ TOK_PID[1]	Setting this bit enables the USB-FS to perform Data Toggle Synchronization.  • If KEEP=0, bit 1 of the current token PID is written back to the BD.  • If KEEP=1, this bit is unchanged by the USB-FS.
	Data Toggle Synchronization is disabled.  1
	Enables the USB-FS to perform Data Toggle Synchronization.

Table continues on the next page...



## Table 44-4. Buffer Descriptor Byte Fields (continued)

Field	Description
2 BDT_STALL TOK_PID[0]	Setting this bit causes the USB-FS to issue a STALL handshake if a token is received by the SIE that would use the BDT in this location. The BDT is not consumed by the SIE (the owns bit remains set and the rest of the BDT is unchanged) when a BDT-STALL bit is set.  • If KEEP=0, bit 0 of the current token PID is written back to the BD.  • If KEEP=1, this bit is unchanged by the USB-FS.   O  No stall issued.  1  The BDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the rest of the DDT is not consumed by the SIE (the OWN bit remains set and the size of the DDT is not consumed by the SIE (the OWN bit remains set and the SIE (the OWN bit
TOK_PID[n]	BDT is unchanged).  Bits [5:2] can also represent the current token PID. The current token PID is written back in to the BD by the USB-FS when a transfer completes. The values written back are the token PID values from the USB specification:  • 0x1 for an OUT token.  • 0x9 for an IN token.
	<ul> <li>0xd for a SETUP token.</li> <li>In host mode, this field is used to report the last returned PID or a transfer status indication. The possible values returned are:</li> <li>0x3 DATA0</li> </ul>
	<ul> <li>0xb DATA1</li> <li>0x2 ACK</li> <li>0xe STALL</li> <li>0xa NAK</li> <li>0x0 Bus Timeout</li> <li>0xf Data Error</li> </ul>
1–0	Reserved, should read as zeroes.
Reserved	
ADDR[31:0]	The Address bits represent the 32 -bit buffer address in system memory. These bits are unchanged by the USB-FS.

## 44.3.5 USB Transaction

When the USB-FS transmits or receives data, it computes the BDT address using the address generation shown in "Addressing Buffer Descriptor Entries" table.

If OWN =1, the following process occurs:

- 1. The USB-FS reads the BDT.
- 2. The SIE transfers the data via the DMA to or from the buffer pointed to by the ADDR field of the BD.
- 3. When the TOKEN is complete, the USB-FS updates the BDT and, if KEEP=0, changes the OWN bit to 0.
- 4. The STAT register is updated and the TOK\_DNE interrupt is set.



#### **Frogrammers Interface**

- 5. When the microprocessor processes the TOK\_DNE interrupt, it reads from the status register all the information needed to process the endpoint.
- 6. At this point, the microprocessor allocates a new BD so additional USB data can be transmitted or received for that endpoint, and then processes the last BD.

The following figure shows a timeline of how a typical USB token is processed after the BDT is read and OWN=1.




Figure 44-4. USB Token Transaction

The USB has two sources for the DMA overrun error:

#### **Memory Latency**

The memory latency on the BVCI initiator interface may be too high and cause the receive FIFO to overflow. This is predominantly a hardware performance issue, usually caused by transient memory access issues.

#### **Oversized Packets**

The packet received may be larger than the negotiated *MaxPacket* size. Typically, this is caused by a software bug. For DMA overrun errors due to oversized data packets, the USB specification is ambiguous. It assumes correct software drivers on both sides. NAKing the packet can result in retransmission of the already oversized packet data. Therefore, in response to oversized packets, the USB core continues ACKing the packet for non-isochronous transfers.

Table 44-5. USB Responses to DMA Overrun Errors

Errors due to Memory Latency	Errors due to Oversized Packets
Non-Acknowledgment (NAK) or Bus Timeout (BTO) — See bit 4 in "Error Interrupt Status Register (ERR_STAT)" as appropriate for the class of transaction.	Continues acknowledging (ACKing) the packet for non-isochronous transfers.

Table continues on the next page...



# Table 44-5. USB Responses to DMA Overrun Errors (continued)

Errors due to Memory Latency	Errors due to Oversized Packets
_	The data written to memory is clipped to the MaxPacket size so as not to corrupt system memory.
The DMA_ERR bit is set in the ERR_STAT register for host and device modes of operation. Depending on the values of the INT_ENB and ERR_ENB register, the core may assert an interrupt to notify the processor of the DMA error.	Asserts the DMA_ERR bit of the ERR_STAT register (which could trigger an interrupt) and a TOK_DNE interrupt fires. (Note: The TOK_PID field of the BDT is not 1111 because the DMA_ERR is not due to latency).
<ul> <li>For host mode, the TOK_DNE interrupt fires and the TOK_PID field of the BDT is 1111 to indicate the DMA latency error. Host mode software can decide to retry or move to next scheduled item.</li> <li>In device mode, the BDT is not written back nor is the TOK_DNE interrupt triggered because it is assumed that a second attempt is queued and will succeed in the future.</li> </ul>	The packet length field written back to the BDT is the MaxPacket value that represents the length of the clipped data actually written to memory.

From here, the software can decide an appropriate course of action for future transactions such as stalling the endpoint, canceling the transfer, disabling the endpoint, etc.

# 44.4 Memory Map/Register Definitions

This section provides the memory map and detailed descriptions of all USB interface registers.

# **USB** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4007_2000	Peripheral ID Register (USB0_PERID)	8	R	04h	44.4.1/ 1083
4007_2004	Peripheral ID Complement Register (USB0_IDCOMP)	8	R	FBh	44.4.2/ 1084
4007_2008	Peripheral Revision Register (USB0_REV)	8	R	33h	44.4.3/ 1084
4007_200C	Peripheral Additional Info Register (USB0_ADDINFO)	8	R	01h	44.4.4/ 1085
4007_2010	OTG Interrupt Status Register (USB0_OTGISTAT)	8	R/W	00h	44.4.5/ 1085
4007_2014	OTG Interrupt Control Register (USB0_OTGICR)	8	R/W	00h	44.4.6/ 1086
4007_2018	OTG Status Register (USB0_OTGSTAT)	8	R/W	00h	44.4.7/ 1087



#### wemory Map/Register Definitions

# **USB** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4007_201C	OTG Control Register (USB0_OTGCTL)	8	R/W	00h	44.4.8/ 1088
4007_2080	Interrupt Status Register (USB0_ISTAT)	8	R/W	00h	44.4.9/ 1089
4007_2084	Interrupt Enable Register (USB0_INTEN)	8	R/W	00h	44.4.10/ 1090
4007_2088	Error Interrupt Status Register (USB0_ERRSTAT)	8	R/W	00h	44.4.11/ 1091
4007_208C	Error Interrupt Enable Register (USB0_ERREN)	8	R/W	00h	44.4.12/ 1092
4007_2090	Status Register (USB0_STAT)	8	R	00h	44.4.13/ 1094
4007_2094	Control Register (USB0_CTL)	8	R/W	00h	44.4.14/ 1095
4007_2098	Address Register (USB0_ADDR)	8	R/W	00h	44.4.15/ 1096
4007_209C	BDT Page Register 1 (USB0_BDTPAGE1)	8	R/W	00h	44.4.16/ 1097
4007_20A0	Frame Number Register Low (USB0_FRMNUML)	8	R/W	00h	44.4.17/ 1097
4007_20A4	Frame Number Register High (USB0_FRMNUMH)	8	R/W	00h	44.4.18/ 1098
4007_20A8	Token Register (USB0_TOKEN)	8	R/W	00h	44.4.19/ 1098
4007_20AC	SOF Threshold Register (USB0_SOFTHLD)	8	R/W	00h	44.4.20/ 1099
4007_20B0	BDT Page Register 2 (USB0_BDTPAGE2)	8	R/W	00h	44.4.21/ 1100
4007_20B4	BDT Page Register 3 (USB0_BDTPAGE3)	8	R/W	00h	44.4.22/ 1100
4007_20C0	Endpoint Control Register (USB0_ENDPT0)	8	R/W	00h	44.4.23/ 1100
4007_20C4	Endpoint Control Register (USB0_ENDPT1)	8	R/W	00h	44.4.23/ 1100
4007_20C8	Endpoint Control Register (USB0_ENDPT2)	8	R/W	00h	44.4.23/ 1100
4007_20CC	Endpoint Control Register (USB0_ENDPT3)	8	R/W	00h	44.4.23/ 1100
4007_20D0	Endpoint Control Register (USB0_ENDPT4)	8	R/W	00h	44.4.23/ 1100



# **USB** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4007_20D4	Endpoint Control Register (USB0_ENDPT5)	8	R/W	00h	44.4.23/ 1100
4007_20D8	Endpoint Control Register (USB0_ENDPT6)	8	R/W	00h	44.4.23/ 1100
4007_20DC	Endpoint Control Register (USB0_ENDPT7)	8	R/W	00h	44.4.23/ 1100
4007_20E0	Endpoint Control Register (USB0_ENDPT8)	8	R/W	00h	44.4.23/ 1100
4007_20E4	Endpoint Control Register (USB0_ENDPT9)	8	R/W	00h	44.4.23/ 1100
4007_20E8	Endpoint Control Register (USB0_ENDPT10)	8	R/W	00h	44.4.23/ 1100
4007_20EC	Endpoint Control Register (USB0_ENDPT11)	8	R/W	00h	44.4.23/ 1100
4007_20F0	Endpoint Control Register (USB0_ENDPT12)	8	R/W	00h	44.4.23/ 1100
4007_20F4	Endpoint Control Register (USB0_ENDPT13)	8	R/W	00h	44.4.23/ 1100
4007_20F8	Endpoint Control Register (USB0_ENDPT14)	8	R/W	00h	44.4.23/ 1100
4007_20FC	Endpoint Control Register (USB0_ENDPT15)	8	R/W	00h	44.4.23/ 1100
4007_2100	USB Control Register (USB0_USBCTRL)	8	R/W	C0h	44.4.24/ 1102
4007_2104	USB OTG Observe Register (USB0_OBSERVE)	8	R	50h	44.4.25/ 1102
4007_2108	USB OTG Control Register (USB0_CONTROL)	8	R/W	00h	44.4.26/ 1103
4007_210C	USB Transceiver Control Register 0 (USB0_USBTRC0)	8	R/W	00h	44.4.27/ 1104

# 44.4.1 Peripheral ID Register (USBx\_PERID)

The Peripheral ID Register reads back the value of 0x04. This value is defined for the USB Peripheral.

Addresses: USB0\_PERID is 4007\_2000h base + 0h offset = 4007\_2000h



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

#### wemory Map/Register Definitions

# **USBx\_PERID** field descriptions

Field	Description
7–6 Reserved	This read-only field is reserved and always has the value zero.
5–0 ID	Peripheral identification bits  These bits always read 0x04 (00_0100)

# 44.4.2 Peripheral ID Complement Register (USBx\_IDCOMP)

The Peripheral ID Complement Register reads back the complement of the Peripheral ID Register. For the USB Peripheral, this is the value 0xFB.

Addresses: USB0\_IDCOMP is 4007\_2000h base + 4h offset = 4007\_2004h




#### **USBx\_IDCOMP** field descriptions

Field	Description
7–6 Reserved	This read-only field is reserved and always has the value one. These bits always read ones
5–0 NID	Ones complement of peripheral identification bits.

# 44.4.3 Peripheral Revision Register (USBx\_REV)

This register contains the revision number of the USB Module.

Addresses: USB0\_REV is 4007\_2000h base + 8h offset = 4007\_2008h



#### **USBx\_REV** field descriptions


Field	Description
7–0 REV	Revision
	Indicate the revision number of the USB Core.



# 44.4.4 Peripheral Additional Info Register (USBx\_ADDINFO)

The Peripheral Additional info Register reads back the value of the fixed Interrupt Request Level (IRQNUM) along with the Host Enable bit. If set to 1, the Host Enable bit indicates the USB peripheral is operating in host mode.

Addresses: USB0\_ADDINFO is 4007\_2000h base + Ch offset = 4007\_200Ch




# USBx\_ADDINFO field descriptions

Field	Description
7–3 IRQNUM	Assigned Interrupt Request Number
2–1 Reserved	This read-only field is reserved and always has the value zero.
0 IEHOST	This bit is set if host mode is enabled.

# 44.4.5 OTG Interrupt Status Register (USBx\_OTGISTAT)

The OTG Interrupt Status Register records changes of the ID sense and VBUS signals. Software can read this register to determine which event has caused an interrupt. Only bits that have changed since the last software read are set. Writing a one to a bit clears the associated interrupt.

Addresses: USB0\_OTGISTAT is 4007\_2000h base + 10h offset = 4007\_2010h



#### **USBx\_OTGISTAT** field descriptions

Field	Description
7 IDCHG	This bit is set when a change in the ID Signal from the USB connector is sensed.
6 ONEMSEC	This bit is set when the 1 millisecond timer expires. This bit stays asserted until cleared by software. The interrupt must be serviced every millisecond to avoid losing 1msec counts.



#### wemory Map/Register Definitions


# **USBx\_OTGISTAT** field descriptions (continued)

Field	Description
5 LINE_STATE_ CHG	This bit is set when the USB line state changes. The interrupt associated with this bit can be used to detect Reset, Resume, Connect, and Data Line Pulse signals.
4 Reserved	This read-only field is reserved and always has the value zero.
3 SESSVLDCHG	This bit is set when a change in VBUS is detected indicating a session valid or a session no longer valid.
2 B_SESS_CHG	This bit is set when a change in VBUS is detected on a B device.
1 Reserved	This read-only field is reserved and always has the value zero.
0 AVBUSCHG	This bit is set when a change in VBUS is detected on an A device.

# 44.4.6 OTG Interrupt Control Register (USBx\_OTGICR)

The OTG Interrupt Control Register enables the corresponding interrupt status bits defined in the OTG Interrupt Status Register.

Addresses: USB0\_OTGICR is 4007\_2000h base + 14h offset = 4007\_2014h



# USBx\_OTGICR field descriptions

Field	Description
7	ID interrupt enable
IDEN	
	0 The ID interrupt is disabled
	1 The ID interrupt is enabled
6 ONEMSECEN	1 millisecond interrupt enable
	0 The 1msec timer interrupt is disabled.
	1 The 1msec timer interrupt is enabled.
5	Line State change interrupt enable
LINESTATEEN	O The LINE OTAT OUG interment in disable d
	0 The LINE_STAT_CHG interrupt is disabled.
	1 The LINE_STAT_CHG interrupt is enabled
4	This read-only field is reserved and always has the value zero.
Reserved	



# **USBx\_OTGICR** field descriptions (continued)

Field	Description
3 SESSVLDEN	Session valid interrupt enable
OLOGVEDEN	0 The SESSVLDCHG interrupt is disabled.
	1 The SESSVLDCHG interrupt is enabled.
2 BSESSEN	B Session END interrupt enable
	0 The B_SESS_CHG interrupt is disabled
	1 The B_SESS_CHG interrupt is enabled
1 Reserved	This read-only field is reserved and always has the value zero.
0 AVBUSEN	A VBUS Valid interrupt enable
711200211	0 The AVBUSCHG interrupt is disabled
	1 The AVBUSCHG interrupt is enabled

# 44.4.7 OTG Status Register (USBx\_OTGSTAT)

The OTG Status Register displays the actual value from the external comparator outputs of the ID pin and VBUS.

Addresses: USB0\_OTGSTAT is 4007\_2000h base + 18h offset = 4007\_2018h



#### **USBx\_OTGSTAT** field descriptions

Field	Description
7	Indicates the current state of the ID pin on the USB connector
ID ID	<ul> <li>Indicates a Type A cable has been plugged into the USB connector</li> <li>Indicates no cable is attached or a Type B cable has been plugged into the USB connector</li> </ul>
6 ONEMSECEN	This bit is reserved for the 1msec count, but it is not useful to software.
5 LINESTATESTABLE	This bit indicates that the internal signals that control the LINE_STATE_CHG bit (bit 5) of the OTGISTAT register have been stable for at least 1 millisecond. First read the LINE_STATE_CHG bit, and then read this bit. If this bit reads as 1, then the value of LINE_STATE_CHG can be considered stable.



#### wemory Map/Register Definitions

# **USBx\_OTGSTAT** field descriptions (continued)

Field	Description
	0 The LINE_STAT_CHG bit is not yet stable.
	1 The LINE_STAT_CHG bit has been debounced and is stable.
4 Reserved	This read-only field is reserved and always has the value zero.
3 SESS_VLD	Session valid
000_100	0 The VBUS voltage is below the B session Valid threshold
	1 The VBUS voltage is above the B session Valid threshold.
2 BSESSEND	B Session END
	0 The VBUS voltage is above the B session End threshold.
	1 The VBUS voltage is below the B session End threshold.
1 Reserved	This read-only field is reserved and always has the value zero.
0	A VBUS Valid
AVBUSVLD	<ul><li>The VBUS voltage is below the A VBUS Valid threshold.</li><li>The VBUS voltage is above the A VBUS Valid threshold.</li></ul>

# 44.4.8 OTG Control Register (USBx\_OTGCTL)

The OTG Control Register controls the operation of VBUS and Data Line termination resistors.

Addresses: USB0\_OTGCTL is 4007\_2000h base + 1Ch offset = 4007\_201Ch



# **USBx\_OTGCTL** field descriptions

Field	Description				
7 DPHIGH	D+ Data Line pullup resistor enable				
	0 D+ pullup resistor is not enabled				
	1 D+ pullup resistor is enabled				
6 Reserved	This read-only field is reserved and always has the value zero.				
5 DPLOW	D+ Data Line pull-down resistor enable				
DFLOW	This bit should always be enabled together with bit 4 (DMLOW)				



#### **USBx\_OTGCTL** field descriptions (continued)

Field	Description
	D+ pulldown resistor is not enabled.     D+ pulldown resistor is enabled.
4 DMLOW	D- Data Line pull-down resistor enable  D- pulldown resistor is not enabled.  D- pulldown resistor is enabled.
3 Reserved	This read-only field is reserved and always has the value zero.
2 OTGEN	On-The-Go pullup/pulldown resistor enable  0 If USB_EN is set and HOST_MODE is clear in the Control Register (CTL), then the D+ Data Line pull-up resistors are enabled. If HOST_MODE is set the D+ and D- Data Line pull-down resistors are engaged.  1 The pull-up and pull-down controls in this register are used.
1–0 Reserved	This read-only field is reserved and always has the value zero.

# 44.4.9 Interrupt Status Register (USBx\_ISTAT)

The Interrupt Status Register contains bits for each of the interrupt sources within the USB Module. Each of these bits are qualified with their respective interrupt enable bits. All bits of this register are logically OR'd together along with the OTG Interrupt Status Register (OTGSTAT) to form a single interrupt source for the processor's interrupt controller. After an interrupt bit has been set it may only be cleared by writing a one to the respective interrupt bit. This register contains the value of 0x00 after a reset.

Addresses: USB0\_ISTAT is 4007\_2000h base + 80h offset = 4007\_2080h

Bit	7	6	5	4	3	2	1	0
Read	STALL	ATTACH	RESUME	SLEEP	TOKDNE	SOFTOK	ERROR	USBRST
Write	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c
Reset	0	0	0	0	0	0	0	0

#### **USBx\_ISTAT** field descriptions

Field	Description
7 STALL	Stall Interrupt In Target mode this bit is asserted when a STALL handshake is sent by the SIE.
	In Host mode this bit is set when the USB Module detects a STALL acknowledge during the handshake phase of a USB transaction. This interrupt can be use to determine is the last USB transaction was completed successfully or if it stalled.
6 ATTACH	Attach Interrupt



#### wemory Map/Register Definitions


# USBx\_ISTAT field descriptions (continued)

Field	Description
	This bit is set when the USB Module detects an attach of a USB device. This signal is only valid if HOSTMODEEN is true. This interrupt signifies that a peripheral is now present and must be configured.
5 RESUME	This bit is set depending upon the DP/DM signals, and can be used to signal remote wake-up signaling on the USB bus. When not in suspend mode this interrupt should be disabled.
4 SLEEP	This bit is set when the USB Module detects a constant idle on the USB bus for 3 milliseconds. The sleep timer is reset by activity on the USB bus.
3 TOKDNE	This bit is set when the current token being processed has completed. The processor should immediately read the STAT register to determine the EndPoint and BD used for this token. Clearing this bit (by writing a one) causes the STAT register to be cleared or the STAT holding register to be loaded into the STAT register.
2 SOFTOK	This bit is set when the USB Module receives a Start Of Frame (SOF) token.  In Host mode this bit is set when the SOF threshold is reached, so that software can prepare for the next SOF.
1 ERROR	This bit is set when any of the error conditions within the ERRSTAT register occur. The processor must then read the ERRSTAT register to determine the source of the error.
0 USBRST	This bit is set when the USB Module has decoded a valid USB reset. This informs the Microprocessor that it should write 0x00 into the address register and enable endpoint 0. USBRST is set after a USB reset has been detected for 2.5 microseconds. It is not asserted again until the USB reset condition has been removed and then reasserted.

# 44.4.10 Interrupt Enable Register (USBx\_INTEN)

The Interrupt Enable Register contains enable bits for each of the interrupt sources within the USB Module. Setting any of these bits enables the respective interrupt source in the ISTAT register. This register contains the value of 0x00 after a reset.

Addresses: USB0\_INTEN is 4007\_2000h base + 84h offset = 4007\_2084h



#### **USBx\_INTEN** field descriptions

Field	Description
7 STALLEN	STALL Interrupt Enable
	<ul><li>The STALL interrupt is not enabled.</li><li>The STALL interrupt is enabled.</li></ul>
6 ATTACHEN	ATTACH Interrupt Enable
	<ul><li>The ATTACH interrupt is not enabled.</li><li>The ATTACH interrupt is enabled.</li></ul>

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### **USBx\_INTEN** field descriptions (continued)

Field	Description
5 RESUMEEN	RESUME Interrupt Enable
	0 The RESUME interrupt is not enabled.
	1 The RESUME interrupt is enabled.
4 SLEEPEN	SLEEP Interrupt Enable
	0 The SLEEP interrupt is not enabled.
	1 The SLEEP interrupt is enabled.
3 TOKDNEEN	TOKDNE Interrupt Enable
	0 The TOKDNE interrupt is not enabled.
	1 The TOKDNE interrupt is enabled.
2 SOFTOKEN	SOFTOK Interrupt Enable
	0 The SOFTOK interrupt is not enabled.
	1 The SOFTOK interrupt is enabled.
1 ERROREN	ERROR Interrupt Enable
	0 The ERROR interrupt is not enabled.
	1 The ERROR interrupt is enabled.
0 USBRSTEN	USBRST Interrupt Enable
	0 The USBRST interrupt is not enabled.
	1 The USBRST interrupt is enabled.

# 44.4.11 Error Interrupt Status Register (USBx\_ERRSTAT)

The Error Interrupt Status Register contains enable bits for each of the error sources within the USB Module. Each of these bits are qualified with their respective error enable bits. All bits of this Register are logically OR'd together and the result placed in the ERROR bit of the ISTAT register. After an interrupt bit has been set it may only be cleared by writing a one to the respective interrupt bit. Each bit is set as soon as the error conditions is detected. Therefore, the interrupt does not typically correspond with the end of a token being processed. This register contains the value of 0x00 after a reset.

Addresses: USB0\_ERRSTAT is 4007\_2000h base + 88h offset = 4007\_2088h

Bit	7	6	5	4	3	2	1	0	_
Read	BTSERR	0	DMAERR	BTOERR	DFN8	CRC16	CRC5EOF	PIDERR	
Write	w1c		w1c	w1c	w1c	w1c	w1c	w1c	
Reset	0	0	0	0	0	0	0	0	-

#### wemory Map/Register Definitions


#### **USBx\_ERRSTAT** field descriptions

Field	Description
7 BTSERR	This bit is set when a bit stuff error is detected. If set, the corresponding packet is rejected due to the error.
6 Reserved	This read-only field is reserved and always has the value zero.
5 DMAERR	This bit is set if the USB Module has requested a DMA access to read a new BDT but has not been given the bus before it needs to receive or transmit data. If processing a TX transfer this would cause a transmit data underflow condition. If processing a RX transfer this would cause a receive data overflow condition. This interrupt is useful when developing device arbitration hardware for the microprocessor and the USB Module to minimize bus request and bus grant latency. This bit is also set if a data packet to or from the host is larger than the buffer size allocated in the BDT. In this case the data packet is truncated as it is put into buffer memory.
4 BTOERR	This bit is set when a bus turnaround timeout error occurs. The USB Module contains a bus turnaround timer that keeps track of the amount of time elapsed between the token and data phases of a SETUP or OUT TOKEN or the data and handshake phases of a IN TOKEN. If more than 16 bit times are counted from the previous EOP before a transition from IDLE, a bus turnaround timeout error occurs.
3 DFN8	This bit is set if the data field received was not 8 bits in length. USB Specification 1.0 requires that data fields be an integral number of bytes. If the data field was not an integral number of bytes, this bit is set.
2 CRC16	This bit is set when a data packet is rejected due to a CRC16 error.
1 CRC5EOF	This error interrupt has two functions. When the USB Module is operating in peripheral mode (HOSTMODEEN=0), this interrupt detects CRC5 errors in the token packets generated by the host. If set the token packet was rejected due to a CRC5 error.
	When the USB Module is operating in host mode (HOSTMODEEN=1), this interrupt detects End Of Frame (EOF) error conditions. This occurs when the USB Module is transmitting or receiving data and the SOF counter reaches zero. This interrupt is useful when developing USB packet scheduling software to ensure that no USB transactions cross the start of the next frame.
0 PIDERR	This bit is set when the PID check field fails.

# 44.4.12 Error Interrupt Enable Register (USBx\_ERREN)

The Error Interrupt Enable Register contains enable bits for each of the error interrupt sources within the USB Module. Setting any of these bits enables the respective interrupt source in the ERRSTAT register. Each bit is set as soon as the error conditions is detected. Therefore, the interrupt does not typically correspond with the end of a token being processed. This register contains the value of 0x00 after a reset.

Addresses: USB0\_ERREN is 4007\_2000h base + 8Ch offset = 4007\_208Ch





# **USBx\_ERREN** field descriptions


Field	Description
7	BTSERR Interrupt Enable
BTSERREN	0 The BTSERR interrupt is not enabled.
	1 The BTSERR interrupt is enabled.
6 Reserved	This read-only field is reserved and always has the value zero.
5	DMAERR Interrupt Enable
DMAERREN	0 The DMAERR interrupt is not enabled.
	1 The DMAERR interrupt is enabled.
4 BTOERREN	BTOERR Interrupt Enable
	0 The BTOERR interrupt is not enabled.
	1 The BTOERR interrupt is enabled.
3 DFN8EN	DFN8 Interrupt Enable
	0 The DFN8 interrupt is not enabled.
	1 The DFN8 interrupt is enabled.
2 CRC16EN	CRC16 Interrupt Enable
ONOTOLIN	0 The CRC16 interrupt is not enabled.
	1 The CRC16 interrupt is enabled.
1 CRC5EOFEN	CRC5/EOF Interrupt Enable
	0 The CRC5/EOF interrupt is not enabled.
	1 The CRC5/EOF interrupt is enabled.
0 PIDERREN	PIDERR Interrupt Enable
	0 The PIDERR interrupt is not enabled.
	1 The PIDERR interrupt is enabled.



# 44.4.13 Status Register (USBx\_STAT)

The Status Register reports the transaction status within the USB Module. When the processor's interrupt controller has received a TOKDNE interrupt the Status Register should be read to determine the status of the previous endpoint communication. The data in the status register is valid when the TOKDNE interrupt bit is asserted. The STAT register is actually a read window into a status FIFO maintained by the USB Module. When the USB Module uses a BD, it updates the Status Register. If another USB transaction is performed before the TOKDNE interrupt is serviced, the USB Module stores the status of the next transaction in the STAT FIFO. Thus the STAT register is actually a four byte FIFO that allows the processor core to process one transaction while the SIE is processing the next transaction. Clearing the TOKDNE bit in the ISTAT register causes the SIE to update the STAT register with the contents of the next STAT value. If the data in the STAT holding register is valid, the SIE immediately reasserts to TOKDNE interrupt.

Addresses: USB0\_STAT is 4007\_2000h base + 90h offset = 4007\_2090h



#### **USBx STAT field descriptions**


Field	Description
7–4 ENDP	This four-bit field encodes the endpoint address that received or transmitted the previous token. This allows the processor core to determine which BDT entry was updated by the last USB transaction.
3 TX	Transmit Indicator  0 The most recent transaction was a Receive operation.  1 The most recent transaction was a Transmit operation.
2 ODD	this bit is set if the last Buffer Descriptor updated was in the odd bank of the BDT.
1–0 Reserved	This read-only field is reserved and always has the value zero.



# 44.4.14 Control Register (USBx\_CTL)

The Control Register provides various control and configuration information for the USB Module.

Addresses: USB0\_CTL is 4007\_2000h base + 94h offset = 4007\_2094h



# **USBx\_CTL** field descriptions

Field	Description
7 JSTATE	Live USB differential receiver JSTATE signal  The polarity of this signal is affected by the current state of LSEN.
6 SE0	Live USB Single Ended Zero signal
5 TXSUSPENDTOKENBUSY	When the USB Module is in Host mode TOKEN_BUSY is set when the USB Module is busy executing a USB token and no more token commands should be written to the Token Register. Software should check this bit before writing any tokens to the Token Register to ensure that token commands are not lost. In Target mode TXD_SUSPEND is set when the SIE has disabled packet transmission and reception. Clearing this bit allows the SIE to continue token processing. This bit is set by the SIE when a Setup Token is received allowing software to dequeue any pending packet transactions in the BDT before resuming token processing.
4 RESET	Setting this bit enables the USB Module to generate USB reset signaling. This allows the USB Module to reset USB peripherals. This control signal is only valid in Host mode (HOSTMODEEN=1). Software must set RESET to 1 for the required amount of time and then clear it to 0 to end reset signaling. For more information on RESET signaling see Section 7.1.4.3 of the USB specification version 1.0.
3 HOSTMODEEN	When set to 1, this bit enables the USB Module to operate in Host mode. In host mode, the USB module performs USB transactions under the programmed control of the host processor.
2 RESUME	When set to 1 this bit enables the USB Module to execute resume signaling. This allows the USB Module to perform remote wake-up. Software must set RESUME to 1 for the required amount of time and then clear it to 0. If the HOSTMODEEN bit is set, the USB module appends a Low Speed End of Packet to the Resume signaling when the RESUME bit is cleared. For more information on RESUME signaling see Section 7.1.4.5 of the USB specification version 1.0.
1 ODDRST	Setting this bit to 1 resets all the BDT ODD ping/pong bits to 0, which then specifies the EVEN BDT bank.



#### wemory Map/Register Definitions


#### **USBx\_CTL** field descriptions (continued)

Field	Description
0 USBENSOFEN	USB Enable  Setting this bit causes the SIE to reset all of its ODD bits to the BDTs. Therefore, setting this bit
	resets much of the logic in the SIE. When host mode is enabled, clearing this bit causes the SIE to stop sending SOF tokens.
	<ul><li>0 The USB Module is disabled.</li><li>1 The USB Module is enabled.</li></ul>

# 44.4.15 Address Register (USBx\_ADDR)

The Address Register holds the unique USB address that the USB Module decodes when in Peripheral mode (HOSTMODEEN=0). When operating in Host mode (HOSTMODEEN=1) the USB Module transmits this address with a TOKEN packet. This enables the USB Module to uniquely address an USB peripheral. In either mode, the USB\_EN bit within the control register must be set. The Address Register is reset to 0x00 after the reset input becomes active or the USB Module decodes a USB reset signal. This action initializes the Address Register to decode address 0x00 as required by the USB specification.

Addresses: USB0\_ADDR is 4007\_2000h base + 98h offset = 4007\_2098h



#### **USBx ADDR field descriptions**


Field	Description
7 LSEN	Low Speed Enable bit
	This bit informs the USB Module that the next token command written to the token register must be performed at low speed. This enables the USB Module to perform the necessary preamble required for low-speed data transmissions.
6–0 ADDR	USB address
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	This 7-bit value defines the USB address that the USB Module decodes in peripheral mode, or transmit when in host mode.



# 44.4.16 BDT Page Register 1 (USBx\_BDTPAGE1)

The Buffer Descriptor Table Page Register 1 provides address bits 15 through 9 of the base address where the current Buffer Descriptor Table (BDT) resides in system memory. The 32-bit BDT Base Address is always aligned on 512-byte boundaries, so bits 8 through 0 of the base address are always taken as zero.

Addresses: USB0\_BDTPAGE1 is 4007\_2000h base + 9Ch offset = 4007\_209Ch




#### **USBx\_BDTPAGE1** field descriptions

Field	Description
7–1 BDTBA	This field provides address bits 15 through 9 of the BDT base address.
0 Reserved	This read-only field is reserved and always has the value zero.

# 44.4.17 Frame Number Register Low (USBx\_FRMNUML)

The Frame Number Register (Low and High) contains an 11-bit value used to compute the address where the current Buffer Descriptor Table (BDT) resides in system memory.

Addresses: USB0\_FRMNUML is 4007\_2000h base + A0h offset = 4007\_20A0h




#### **USBx\_FRMNUML** field descriptions


Fie	eld	Description
7- FRM		This 8-bit field and the 3-bit field in the Frame Number Register High are used to compute the address where the current Buffer Descriptor Table (BDT) resides in system memory.



# 44.4.18 Frame Number Register High (USBx\_FRMNUMH)

The Frame Number Register (Low and High) contains an 11-bit value used to compute the address where the current Buffer Descriptor Table (BDT) resides in system memory.






#### **USBx FRMNUMH field descriptions**

Field	Description
7–3 Reserved	This read-only field is reserved and always has the value zero.
2-0 FRM[10:8]	This 3-bit field and the 8-bit field in the Frame Number Register Low are used to compute the address where the current Buffer Descriptor Table (BDT) resides in system memory.

# 44.4.19 Token Register (USBx\_TOKEN)

The Token Register is used to perform USB transactions when in host mode (HOSTMODEEN=1). When the processor core wishes to execute a USB transaction to a peripheral, it writes the TOKEN type and endpoint to this register. After this register has been written, the USB module begins the specified USB transaction to the address contained in the address register. The processor core should always check that the TOKEN\_BUSY bit in the control register is not set before performing a write to the Token Register. This ensures token commands are not overwritten before they can be executed. The address register and endpoint control register 0 are also used when performing a token command and therefore must also be written before the Token Register. The address register is used to correctly select the USB peripheral address transmitted by the token command. The endpoint control register determines the handshake and retry policies used during the transfer.

Addresses: USB0\_TOKEN is 4007\_2000h base + A8h offset = 4007\_20A8h






#### **USBx\_TOKEN** field descriptions

Field	Description
7–4 TOKENPID	This 4-bit field contains the token type executed by the USB Module.
	0001 OUT Token. USB Module performs an OUT (TX) transaction.
	1001 IN Token. USB Module performs an In (RX) transaction.
	1101 SETUP Token. USB Module performs a SETUP (TX) transaction
3–0 TOKENENDPT	This 4 bit field holds the Endpoint address for the token command. The four bit value written must be a valid endpoint.

# 44.4.20 SOF Threshold Register (USBx\_SOFTHLD)

The SOF Threshold Register is used only in Hosts mode (HOSTMODEEN=1). When in Host mode, the 14-bit SOF counter counts the interval between SOF frames. The SOF must be transmitted every 1msec so the SOF counter is loaded with a value of 12000. When the SOF counter reaches zero, a Start Of Frame (SOF) token is transmitted. The SOF threshold register is used to program the number of USB byte times before the SOF to stop initiating token packet transactions. This register must be set to a value that ensures that other packets are not actively being transmitted when the SOF time counts to zero. When the SOF counter reaches the threshold value, no more tokens are transmitted until after the SOF ha been transmitted. The value programmed into the threshold register must reserve enough time to ensure the worst case transaction completes. In general the worst case transaction is a IN token followed by a data packet from the target followed by the response from the host. The actual time required is a function of the maximum packet size on the bus. Typical values for the SOF threshold are: 64-byte packets=74; 32-byte packets=42; 16-byte packets=26; 8-byte packets=18.

Addresses: USB0\_SOFTHLD is 4007\_2000h base + ACh offset = 4007\_20ACh



#### **USBx SOFTHLD field descriptions**


Field	Description
7–0 CNT	This 8-bit field represents the SOF count threshold in byte times.



# 44.4.21 BDT Page Register 2 (USBx\_BDTPAGE2)

The Buffer Descriptor Table Page Register 2 contains an 8-bit value used to compute the address where the current Buffer Descriptor Table (BDT) resides in system memory.

Addresses: USB0\_BDTPAGE2 is 4007\_2000h base + B0h offset = 4007\_20B0h




#### **USBx BDTPAGE2 field descriptions**

Field	Description
7–0 BDTBA	This 8 bit field provides address bits 23 through 16 of the BDT base address, which defines where the Buffer Descriptor Table resides in system memory.

# 44.4.22 BDT Page Register 3 (USBx\_BDTPAGE3)

The Buffer Descriptor Table Page Register 3 contains an 8-bit value used to compute the address where the current Buffer Descriptor Table (BDT) resides in system memory.

Addresses: USB0\_BDTPAGE3 is 4007\_2000h base + B4h offset = 4007\_20B4h



#### USBx\_BDTPAGE3 field descriptions

Field	Description
	This 8 bit field provides address bits 31 through 24 of the BDT base address, which defines where the Buffer Descriptor Table resides in system memory.


# 44.4.23 Endpoint Control Register (USBx\_ENDPTn)

The Endpoint Control Registers contain the endpoint control bits for each of the 16 endpoints available within the USB Module for a decoded address. The format for these registers is shown in the following figure. Endpoint 0 (ENDPT0) is associated with control pipe 0, which is required for all USB functions. Therefore, after a USBRST interrupt occurs the processor core should set the ENDPT0 register to contain 0x0D.



In Host mode ENDPT0 is used to determine the handshake, retry and low speed characteristics of the host transfer. For Host mode control, bulk and interrupt transfers the EPHSHK bit should be set to 1. For Isochronous transfers it should be set to 0. Common values to use for ENDPT0 in host mode are 0x4D for Control, Bulk, and Interrupt transfers, and 0x4C for Isochronous transfers.

Addresses:  $4007_{2000h}$  base + C0h offset +  $(4d \times n)$ , where n = 0d to 15d




# USBx\_ENDPTn field descriptions

Field	Description
7 HOSTWOHUB	This is a Host mode only bit and is only present in the control register for endpoint 0 (ENDPT0). When set this bit allows the host to communicate to a directly connected low speed device. When cleared, the host produces the PRE_PID then switch to low speed signaling when sending a token to a low speed device as required to communicate with a low speed device through a hub.
6 RETRYDIS	This is a Host mode only bit and is only present in the control register for endpoint 0 (ENDPT0). When set this bit causes the host to not retry NAK'ed (Negative Acknowledgement) transactions. When a transaction is NAKed, the BDT PID field is updated with the NAK PID, and the TOKEN_DNE interrupt is set. When this bit is cleared NAKed transactions is retried in hardware. This bit must be set when the host is attempting to poll an interrupt endpoint.
5 Reserved	This read-only field is reserved and always has the value zero.
4 EPCTLDIS	This bit, when set, disables control (SETUP) transfers. When cleared, control transfers are enabled. This applies if and only if the EPRXEN and EPTXEN bits are also set.
3 EPRXEN	This bit, when set, enables the endpoint for RX transfers.
2 EPTXEN	This bit, when set, enables the endpoint for TX transfers.
1 EPSTALL	When set this bit indicates that the endpoint is called. This bit has priority over all other control bits in the EndPoint Enable Register, but it is only valid if EPTXEN=1 or EPRXEN=1. Any access to this endpoint causes the USB Module to return a STALL handshake. After an endpoint is stalled it requires intervention from the Host Controller.
0 EPHSHK	When set this bet enables an endpoint to perform handshaking during a transaction to this endpoint. This bit is generally set unless the endpoint is Isochronous.



# 44.4.24 USB Control Register (USBx\_USBCTRL)

Addresses: USB0\_USBCTRL is 4007\_2000h base + 100h offset = 4007\_2100h




#### USBx\_USBCTRL field descriptions

Field	Description	
7 SUSP	Places the USB transceiver into the suspend state.	
	0 USB transceiver is not in suspend state.	
	1 USB transceiver is in suspend state.	
6 PDE	Enables the weak pulldowns on the USB transceiver.	
	0 Weak pulldowns are disabled on D+ and D-	
	1 Weak pulldowns are enabled on D+ and D	
5–0 Reserved	This read-only field is reserved and always has the value zero.	

# 44.4.25 USB OTG Observe Register (USBx\_OBSERVE)

Provides visibility on the state of the pull-ups and pull-downs at the transceiver. Useful when interfacing to an external OTG control module via a serial interface.

Addresses: USB0\_OBSERVE is 4007\_2000h base + 104h offset = 4007\_2104h



# USBx\_OBSERVE field descriptions

Field	Description	
7 DPPU	Provides observability of the D+ Pull Up signal output from the USB OTG module.	
	0 D+ pullup disabled.	
	1 D+ pullup enabled.	
6 DPPD	Provides observability of the D+ Pull Down signal output from the USB OTG module.	
	0 D+ pulldown disabled.	
	1 D+ pulldown enabled.	




# **USBx\_OBSERVE** field descriptions (continued)

Field	Description	
5 Reserved	This read-only field is reserved and always has the value zero.	
4 DMPD	Provides observability of the D- Pull Down signal output from the USB OTG module.  0 D- pulldown disabled.  1 D- pulldown enabled.	
3–1 Reserved	This read-only field is reserved and always has the value zero.	
0 Reserved	This read-only field is reserved and always has the value zero.	

# 44.4.26 USB OTG Control Register (USBx\_CONTROL)

Addresses: USB0\_CONTROL is 4007\_2000h base + 108h offset = 4007\_2108h




# **USBx\_CONTROL** field descriptions

Field	Description	
7–5 Reserved	This read-only field is reserved and always has the value zero.	
4 DPPULLUPNONOTG	Provides control of the DP PULLUP in the USB OTG module, if USB is configured in non-OTG device mode.	
	0 DP Pull up in non-OTG device mode is not enabled.	
	1 DP Pull up in non-OTG device mode is enabled.	
3–0 Reserved	This read-only field is reserved and always has the value zero.	



# 44.4.27 USB Transceiver Control Register 0 (USBx\_USBTRC0)

Addresses: USB0\_USBTRC0 is 4007\_2000h base + 10Ch offset = 4007\_210Ch



# USBx\_USBTRC0 field descriptions

Field	Description	
7 USBRESET	USB reset  Generates a hard reset to the USB_OTG module. After this bit is set and the reset occurs, this bit is automatically cleared.	
	NOTE: It is always read as zero.	
	0 Normal USB module operation.	
	1 Returns the USB module to its reset state.	
6 Reserved	This field is reserved.	
	NOTE: Software must set this bit to 1b.	
5 USBRESMEN	Asynchronous Resume Interrupt Enable	
	This bit, when set, allows the USB module to send an asynchronous wakeup event to the MCU upon detection of resume signaling on the USB bus. The MCU then re-enables clocks to the USB module. It is used for low-power suspend mode when USB module clocks are stopped or the USB transceiver is in Suspend mode. Async wakeup only works in device mode.	
	0 USB asynchronous wakeup from suspend mode disabled.	
	1 USB asynchronous wakeup from suspend mode enabled. The asynchronous resume interrupt differs from the synchronous resume interrupt in that it asynchronously detects K-state using the unfiltered state of the D+ and D- pins. This interupt should only be enabled when the Transceiver is suspended.	
4–2 Reserved	This read-only field is reserved and always has the value zero.	
1 SYNC_DET	Synchronous USB Interrupt Detect	
OTNO_BET	0 Synchronous interrupt has not been detected.	
	1 Synchronous interrupt has been detected.	
0 USB_RESUME	USB Asynchronous Interrupt	
INT	0 No interrupt was generated.	
	1 Interrupt was generated because of the USB asynchronous interrupt.	



# 44.5 OTG and Host Mode Operation

The Host Mode logic allows devices such as digital cameras and palmtop computers to function as a USB Host Controller. The OTG logic adds an interface to allow the OTG Host Negotiation and Session Request Protocols (HNP and SRP) to be implemented in software. Host Mode allows a peripheral such as a digital camera to be connected directly to a USB compliant printer. Digital photos can then be easily printed without having to upload them to a PC. In the palmtop computer application, a USB compliant keyboard/ mouse can be connected to the palmtop computer with the obvious advantages of easier interaction.

Host mode is intended for use in handheld-portable devices to allow easy connection to simple HID class devices such as printers and keyboards. It is NOT intended to perform the functions of a full OHCI or UHCI compatible host controller found on PC motherboards. The USB-FS is not supported by Windows 98 as a USB host controller. Host mode allows bulk, Isochronous, interrupt and control transfers. Bulk data transfers are performed at nearly the full USB bus bandwidth. Support is provided for ISO transfers, but the number of ISO streams that can be practically supported is affected by the interrupt latency of the processor servicing the token during interrupts from the SIE. Custom drivers must be written to support Host mode operation.

Setting the HOST\_MODE\_EN bit in the CTL register enables host Mode. The USB-FS core can only operate as a peripheral device or in Host Mode. It cannot operate in both modes simultaneously. When HOST\_MODE is enabled, only endpoint zero is used. All other endpoints should be disabled by software.

# 44.6 Host Mode Operation Examples

The following sections illustrate the steps required to perform USB host functions using the USB-FS core. While it is useful to understand the interaction of the hardware and the software at a detailed level, an understanding of the interactions at this level is not required to write host applications using the API software.

To enable host mode and discover a connected device:

1. Enable Host Mode (CTL[HOST\_MODE\_EN]=1). The pull-down resistors are enabled, and pull-up disabled. Start of Frame (SOF) generation begins. SOF counter loaded with 12,000. Disable SOF packet generation to eliminate noise on the USB by writing the USB enable bit to 0 (CTL[USB\_EN]=0).



#### **musi Mode Operation Examples**

- 2. Enable the ATTACH interrupt (INT\_ENB[ATTACH]=1).
- 3. Wait for ATTACH interrupt (INT\_STAT[ATTACH]). Signaled by USB Target pull-up resistor changing the state of DPLUS or DMINUS from 0 to 1 (SE0 to J or K state).
- 4. Check the state of the JSTATE and SE0 bits in the control register. If the connecting device is low speed (JSTATE bit is 0), set the low-speed bit in the address registers (ADDR[LS\_EN]=1) and the host without hub bit in endpoint 0 register control (EP\_CTL0[HOST\_WO\_HUB]=1).
- 5. Enable RESET (CTL[RESET]=1) for 10 ms.
- 6. Enable SOF packet to keep the connected device from going to suspend (CTL[USB\_EN=1]).
- 7. Start enumeration by sending a sequence of device framework commands, device frame work packets to the default control pipe of the connected device. Refer to the *Universal Serial Bus Revision 2.0 specification*, "Chapter 9 USB Device Framework" (http://www.usb.org/developers/docs).

#### To complete a control transaction to a connected device:

- 1. Complete all steps discover a connected device
- 2. Set up the endpoint control register for bidirectional control transfers EP\_CTL0[4:0] = 0x0d.
- 3. Place a copy of the device framework setup command in a memory buffer. Refer to the *Universal Serial Bus Revision 2.0 specification*, "Chapter 9 USB Device Framework" (http://www.usb.org/developers/docs).
- 4. Initialize current (even or odd) TX EP0 BDT to transfer the 8 bytes of command data for a device framework command (for example, a GET DEVICE DESCRIPTOR).
  - Set the BDT command word to 0x00080080 –Byte count to 8, own bit to 1.
  - Set the BDT buffer address field to the start address of the 8 byte command buffer.
- 5. Set the USB device address of the target device in the address register (ADDR[6:0]). After the USB bus reset, the device USB address is zero. It is set to some other value (usually 1) by the Set Address device framework command.
- 6. Write the token register with a SETUP to Endpoint 0 the target device default control pipe (TOKEN=0xD0). This initiates a setup token on the bus followed by a data packet. The device handshake is returned in the BDT PID field after the packets



- complete. When the BDT is written a token done (INT\_STAT[TOK\_DNE]) interrupt is asserted. This completes the setup phase of the setup transaction. Refer to the *Universal Serial Bus Revision 2.0 specification*, "Chapter 9 USB Device Framework" (http://www.usb.org/developers/docs).
- 7. To initiate the data phase of the setup transaction (for example, get the data for the GET DEVICE descriptor command) set up a buffer in memory for the data to be transferred.
- 8. Initialize the current (even or odd) TX EP0 BDT to transfer the data.
  - Set the BDT command word to 0x004000C0 –Byte count to the length of the data buffer in this case 64, own bit to 1, Data toggle to Data1.
  - Set the BDT buffer address field to the start address of the data buffer
- 9. Write the token register with a IN or OUT token to Endpoint 0 the target device default control pipe, an IN token for a GET DEVICE DESCRIPTOR command (TOKEN=0x90). This initiates an IN token on the bus followed by a data packet from the device to the host. When the data packet completes the BDT is written and a token done (INT\_STAT[TOK\_DNE]) interrupt is asserted. For control transfers with a single packet data phase this completes the data phase of the setup transaction. Refer to the *Universal Serial Bus Revision 2.0 specification*, "Chapter 9 USB Device Framework" (http://www.usb.org/developers/docs).
- 10. To initiate the Status phase of the setup transaction set up a buffer in memory to receive or send the zero length status phase data packet.
- 11. Initialize the current (even or odd) TX EP0 BDT to transfer the status data.
  - Set the BDT command word to 0x00000080 –Byte count to the length of the data buffer in this case 0, own bit to 1, Data toggle to Data0.
  - Set the BDT buffer address field to the start address of the data buffer
- 12. Write the token register with a IN or OUT token to Endpoint 0 the target device default control pipe, an OUT token for a GET DEVICE DESCRIPTOR command (TOKEN=0x10). This initiates an OUT token on the bus followed by a zero length data packet from the host to the device. When the data packet completes the BDT is written with the handshake form the device and a token done (INT\_STAT[TOK\_DNE]) interrupt is asserted. This completes the data phase of the setup transaction. Refer to the *Universal Serial Bus Revision 2.0 specification*, "Chapter 9 USB Device Framework" (http://www.usb.org/developers/docs).

To send a Full speed bulk data transfer to a target device:



#### Un- i he-Go Operation

- 1. Complete all steps discover a connected device and to configure a connected device. Write the ADDR register with the address of the target device. Typically, there is only one other device on the USB bus in host mode so it is expected that the address is 0x01 and should remain constant.
- 2. Write the ENDPT0 to 0x1D register to enable transmit and receive transfers with handshaking enabled.
- 3. Setup the Even TX EP0 BDT to transfer up to 64 bytes.
- 4. Set the USB device address of the target device in the address register (ADDR[6:0]).
- 5. Write the TOKEN register with an OUT token to the desired endpoint. The write to this register triggers the USB-FS transmit state machines to begin transmitting the TOKEN and the data.
- 6. Setup the Odd TX EP0 BDT to transfer up to 64 bytes.
- 7. Write the TOKEN register with an OUT token as in step 4. Two Tokens can be queued at a time to allow the packets to be double buffered to achieve maximum throughput.
- 8. Wait for the TOK\_DNE interrupt. This indicates one of the BDTs has been released back to the microprocessor and that the transfer has completed. If the target device asserts NAKs, the USB-FS continues to retry the transfer indefinitely without processor intervention unless the RETRY\_DIS retry disable bit is set in the EPO control register. If the retry disable bit is set, the handshake (ACK, NAK, STALL, or ERROR (0xf)) is returned in the BDT PID field. If a stall interrupt occurs, the pending packet must be dequeued and the error condition in the target device cleared. If a RESET interrupt occurs (SEO for more than 2.5us), the target has detached.
- 9. After the TOK\_DNE interrupt occurs, the BDTs can be examined and the next data packet queued by returning to step 2.

# 44.7 On-The-Go Operation

The USB-OTG core provides sensors and controls to enable On-The-Go (OTG) operation. These sensors are used by the OTG API software to implement the Host Negotiation Protocol (HNP) and Session Request Protocol (SRP). API calls are provided to give access the OTG protocol control signals, and include the OTG capabilities in the device application. The following state machines show the OTG operations involved with HNP and SRP protocols from either end of the USB cable.



# 44.7.1 OTG Dual Role A Device Operation

A device is considered the A device because of the type of cable attached. If the USB Type A connector or the USB Type Mini A connector is plugged into the device, he is considered the A device.

A dual role A device operates as the following flow diagram and state description table illustrates.




Figure 44-91. Dual Role A Device Flow Diagram

Table 44-94. State Descriptions for the Dual Role A Device Flow

State	Action	Response
A_IDLE	If ID Interrupt.	Go to B_IDLE
	The cable has been un-plugged or a Type B cable has been attached. The device now acts as a Type B device.	
	If the A application wants to use the bus or if the B device is doing	Go to A_WAIT_VRISE
	an SRP as indicated by an A_SESS_VLD Interrupt or Attach or Port Status Change Interrupt check data line for 5 –10 msec pulsing.	Turn on DRV_VBUS
A_WAIT_VRISE	If ID Interrupt or if A_VBUS_VLD is false after 100 msec	Go to A_WAIT_VFALL
	The cable has been changed or the A device cannot support the current required from the B device.	Turn off DRV_VBUS
	If A_VBUS_VLD interrupt	Go to A_WAIT_BCON



Un- i he-Go Operation

# Table 44-94. State Descriptions for the Dual Role A Device Flow (continued)

State	Action	Response
A_WAIT_BCON	After 200 msec without Attach or ID Interrupt. (This could wait	Go to A_WAIT_FALL
	forever if desired.)	Turn off DRV_VBUS
	A_VBUS_VLD Interrupt and B device attaches	Go to A_HOST
		Turn on Host Mode
A_HOST	Enumerate Device determine OTG Support.	
	If A_VBUS_VLD/ Interrupt or A device is done and doesn't think he	Go to A_WAIT_VFALL
	wants to do something soon or the B device disconnects	Turn off Host Mode
		Turn off DRV_VBUS
	If the A device is finished with session or if the A device wants to allow the B device to take bus.	Go to A_SUSPEND
	ID Interrupt or the B device disconnects	Go to A_WAIT_BCON
A_SUSPEND	If ID Interrupt, or if 150 msec B disconnect timeout (This timeout	Go to A_WAIT_VFALL
	value could be longer) or if A_VBUS_VLD\ Interrupt	Turn off DRV_VBUS
	If HNP enabled, and B disconnects in 150 msec then B device is	Go to A_PERIPHERAL
	becoming the host.	Turn off Host Mode
	If A wants to start another session	Go to A_HOST
A_PERIPHERAL	If ID Interrupt or if A_VBUS_VLD interrupt	Go to A_WAIT_VFALL
		Turn off DRV_VBUS.
	If 3 –200 msec of Bus Idle	Go to A_WAIT_BCON
		Turn on Host Mode
A_WAIT_VFALL	If ID Interrupt or (A_SESS_VLD/ & b_conn/)	Go to A_IDLE

# 44.7.2 OTG Dual Role B Device Operation

A device is considered a B device if it connected to the bus with a USB Type B cable or a USB Type Mini B cable.

A dual role B device operates as the following flow diagram and state description table illustrates.

#### **Chapter 44 Universal Serial Bus OTG Controller (USBOTG)**




Figure 44-92. Dual Role B Device Flow Diagram

# Table 44-95. State Descriptions for the Dual Role B Device Flow

State	Action	Response
B_IDLE	If ID\ Interrupt.	Go to A_IDLE
	A Type A cable has been plugged in and the device should now respond as a Type A device.	
	If B_SESS_VLD Interrupt.	Go to B_PERIPHERAL
	The A device has turned on VBUS and begins a session.	Turn on DP_HIGH
	If B application wants the bus and Bus is Idle for 2 ms and the	Go to B_SRP_INIT
	B_SESS_END bit is set, the B device can perform an SRP.	Pulse CHRG_VBUS Pulse DP_HIGH 5-10 ms
B_SRP_INIT	If ID\ Interrupt or SRP Done (SRP must be done in less than 100 Go to B_IDLE msecs.)	
B_PERIPHERAL	If HNP enabled and the bus is suspended and B wants the bus, the	Go to B_WAIT_ACON
	B device can become the host.	Turn off DP_HIGH
B_WAIT_ACON	If A connects, an attach interrupt is received	Go to B_HOST
		Turn on Host Mode
	If ID\ Interrupt or B_SESS_VLD/ Interrupt	Go to B_IDLE
	If the cable changes or if VBUS goes away, the host doesn't support us.	
	Go to B_IDLE	
	If 3.125 ms expires or if a Resume occurs	Go to B_PERIPHERAL
B_HOST	If ID\ Interrupt or B_SESS_VLD\ Interrupt	Go to B_IDLE
	If the cable changes or if VBUS goes away, the host doesn't support us.	
	If B application is done or A disconnects	Go to B_PERIPHERAL



Un-The-Go Operation



# **Chapter 45 USB Device Charger Detection Module (USBDCD)**

# 45.1 Preface

#### 45.1.1 References

The following publications are referenced in this document. For updates to these specifications, see http://www.usb.org.

- USB Battery Charging Specification Revision 1.1, USB Implementers Forum
- Universal Serial Bus Specification Revision 2.0, USB Implementers Forum

# 45.1.2 Acronyms and Abbreviations

The following table contains acronyms and abbreviations used in this document.

Table 45-1. Acronyms and Abbreviated Terms

Term	Meaning	
FS	Full Speed (12 Mbps)	
HS	High Speed (480 Mbps)	
I <sub>DEV_DCHG</sub>	Current drawn when the USB device is connected to a dedicated charging port	
I <sub>DEV_HCHG_LFS</sub>	Current drawn when the USB device is connected to an FS charging host port	
I <sub>DM_SINK</sub>	Current sink for the D- line	
I <sub>DP_SRC</sub>	Current source for the D+ line	
I <sub>SUSP</sub>	Current drawn when the USB device is suspended	
LDO	Low dropout	
LS	Low Speed (1.5 Mbps)	
N/A	Not applicable	



muroduction

Table 45-1. Acronyms and Abbreviated Terms (continued)

Term	Meaning	
OTG	On-The-Go	
R <sub>DM_DWN</sub>	O- pulldown resistance for data pin contact detect	
V <sub>DAT_REF</sub>	Data detect reference voltage for the voltage comparator	
V <sub>DP_SRC</sub>	Voltage source for the D+ line	
$V_{LGC}$	Threshold voltage for logic high	

# 45.1.3 Glossary

The following table shows a glossary of terms used in this document.

Table 45-2. Glossary of Terms

Term	Definition	
Transceiver	Module that implements the physical layer of the USB standard (FS or LS only)	
PHY	Module that implements the physical layer of the USB standard (HS capable)	
Attached	Device is physically plugged into USB port but has not enabled either D+ or D- pullup resistor	
Connected	Device is physically plugged into USB port and has enabled either D+ or D- pullup resistor	
Suspended	After 3 ms of no bus activity the USB device enters suspend mode.	
Component	The hardware and software that make up a subsystem.	

# 45.2 Introduction

#### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The USBDCD module works with the USB transceiver to detect if the USB device is attached to a charging port (either a dedicated charging port or a charging host). System software coordinates the detection activities of the module and controls an off-chip integrated circuit that performs the battery charging.

# 45.2.1 Block Diagram

The following figure is a high level block diagram of the module.






Figure 45-1. Block Diagram

The USBDCD module consists of 2 main blocks:

- A digital block provides the programming interface (memory-mapped registers) and includes the timer unit and the analog control unit.
- An analog block provides the circuitry for the physical detection of the charger, including the voltage source, current source, current sink, and voltage comparator circuitry.

# 45.2.2 Features

The USBDCD module offers the following features:

- Compliant with the latest industry standard specification: *USB Battery Charging Specification*, *Revision 1.1*
- Programmable timing parameters default to values required by the industry standards:
  - Having standard default values allows for minimal configuration: Set the clock frequency before enabling the module.
  - Programmability allows for flexibility to meet future udpates to the standards.

# 45.2.3 Modes of Operation

The USBDCD module operating modes are shown in the following table.



#### woule Signal Description

Table 45-3. Module Modes and Their Conditions

Module Mode	Description	Conditions When Used
Enabled	The module performs the charger detection sequence.	System software should enable the module only when all of the following conditions are true:
		The system uses a rechargeable battery.
		The device is being used in an FS USB device application.
		The device has detected that it is attached to the USB cable.
Disabled	The module is not active and is held in a low power state.	System software should disable the module when either of the following conditions is true:
		The charger detect sequence is complete.
		The conditions for being enabled are not met.
Powered Off	The digital supply voltage dvdd is removed.	Low system performance requirements allow putting the device into a very low-power stop mode.
	Optionally, the analog supply voltage avdd33 also may be reduced to as low as 1.7v without causing excess leakage.	

Operating mode transitions are shown in the following table.

Table 45-4. Entering and Exiting Module Modes

Module Mode	Entering	Exiting	Mode after Exiting
Enabled	Set the CONTROL[START] bit.	Set the CONTROL[SR] bit.1	Disabled
Disabled	Take either of the following actions:  Set the CONTROL[SR] bit.  Reset the module. (The module is disabled out of reset by default.)	Set the CONTROL[START] bit.	Enabled
Powered Off	Perform the following actions:  1. Put the device into very low-power stop mode.  2. Adjust the supply voltages.	Perform the following actions:  1. Restore the supply voltages.  2. Take the device out of very low-power stop mode.	Disabled

<sup>1.</sup> The effect of setting the SR bit is immediate; that is, the module is disabled even if the sequence has not completed.

# 45.3 Module Signal Description

This section describes the module signals.



## 45.3.1 USB Signal Descriptions

The following table shows a summary of module signals that interface with the device's pins.

Table 45-5. USB Signal Descriptions

Signal	Description	I/O
usb_dm	USB D- analog data signal. The analog block interfaces directly to the D-signal on the USB bus.	I/O
usb_dp	USB D+ analog data signal. The analog block interfaces directly to the D+ signal on the USB bus.	I/O
avdd33 <sup>1</sup>	3.3v regulated analog supply	I
avss	Analog ground	I
dvss	Digital ground	I
dvdd	1.2 V digital supply	I

<sup>1.</sup> Voltage must be 3.3v +/- 10% for full functionality of the module. That is, the charger detection function does not work when this voltage is below 3.0v, and the CONTROL[START] bit should not be set.

#### **NOTE**

The transceiver module also interfaces to usb\_dm and usb\_dp. Both modules and the USB host/hub use these signal as bidirectional, tri-state signals.

Information about the signal integrity aspects of the lines including shielding, isolated return paths, input or output impedance, packaging, suggested external components, ESD, and other protections can be found in the USB 2.0 specification and in Application Information.

## 45.4 Memory Map/Register Definition

This section describes the memory map and registers for the USBDCD module.

#### **USBDCD** memory map

Absolute address (hex)	Register name		Access	Reset value	Section/ page
4003_5000	USBDCD_CONTROL	32	R/W	0001_0000h	45.4.1/ 1118
4003_5004	Clock Register (USBDCD_CLOCK)	32	R/W	0000_00C1h	45.4.2/ 1119

Table continues on the next page...




#### **USBDCD** memory map (continued)

Absolute address (hex)	Register name		Access	Reset value	Section/ page
4003_5008	Status Register (USBDCD_STATUS)	32	R	0000_0000h	45.4.3/ 1120
4003_5010	TIMER0 Register (USBDCD_TIMER0)	32	R/W	0010_0000h	45.4.4/ 1122
4003_5014	USBDCD_TIMER1	32	R/W	000A_0028h	45.4.5/ 1123
4003_5018	USBDCD_TIMER2	32	R/W	0028_0001h	45.4.6/ 1123

## 45.4.1 Control Register (USBDCD\_CONTROL)

Contains the control and interrupt bit fields.

Address: USBDCD\_CONTROL is 4003\_5000h base + 0h offset = 4003\_5000h



## **USBDCD\_CONTROL** field descriptions

Field	Description	
31–26 Reserved	This read-only field is reserved and always has the value zero.	
25 SR	Software Reset  Determines whether a software reset is performed.  0 Do not perform a software reset.  1 Perform a software reset.	
24 START	Start Change Detection Sequence	

Table continues on the next page...




#### **USBDCD\_CONTROL** field descriptions (continued)

Field	Description		
Field	Description		
	Determines whether the charger detection sequence is initiated.		
	0b0 Do not start the sequence. Writes of this value have no effect.		
	0b1 Initiate the charger detection sequence. If the sequence is already running, writes of this value have no effect.		
23–17 Reserved	This read-only field is reserved and always has the value zero.		
16 IE	Interrupt Enable		
10	Enables/disables interrupts to the system.		
	0b0 Disable interrupts to the system.		
	0b1 Enable interrupts to the system.		
15–9 Reserved	This field is reserved.		
8 IF	Interrupt Flag		
IF IF	Determines whether an interrupt is pending		
	0b0 No interrupt is pending.		
	0b1 An interrupt is pending.		
7–1 Reserved	This read-only field is reserved and always has the value zero.		
0 IACK	Interrupt Acknowledge		
IAON	Determines whether the interrupt is cleared.		
	0b0 Do not clear the interrupt.		
	0b1 Clear the IF bit (interrupt flag).		

## 45.4.2 Clock Register (USBDCD\_CLOCK)

Address: USBDCD\_CLOCK is 4003\_5000h base + 4h offset = 4003\_5004h



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory Map/Register Definition


## **USBDCD\_CLOCK** field descriptions

Field	Description	
31–12 Reserved	This read-only field is reserved and always has the value zero.	
11–2 CLOCK_SPEED	Numerical Value of Clock Speed in Binary  The unit of measure is programmed in CLOCK_UNIT. The valid range is from 1 to 1023 when clock unit is MHz and 4 to 1023 when clock unit is KHz. Examples with CLOCK_UNIT = 1:  • For 48 MHz: 0b00_0011_0000 (48) (Default)  • For 24 MHz: 0b00_0001_1000 (24)  Examples with CLOCK_UNIT = 0:  • For 100 kHz: 0b00_0110_0100 (100)  • For 500 kHz: 0b01_1111_0100 (500)	
1 Reserved	This read-only field is reserved and always has the value zero.	
0 CLOCK_UNIT	Unit of measurement encoding for Clock Speed  Specifies the unit of measure for the clock speed.  Ob0 kHz Speed (between 1 kHz and 1023 kHz)  Ob1 MHz Speed (between 1 MHz and 1023 MHz)	

## 45.4.3 Status Register (USBDCD\_STATUS)

The status register provides the current state of the module for system software monitoring.

Address: USBDCD\_STATUS is 4003\_5000h base + 8h offset = 4003\_5008h








#### **USBDCD\_STATUS** field descriptions


Field	Description		
31–23 Reserved	This read-only field is reserved and always has the value zero.		
22 ACTIVE	Active Status Indicator		
NOTIVE	Indicates whether the sequence is running.		
	0b0 The sequence is not running.		
	0b1 The sequence is running.		
21 TO	Timeout Flag		
10	Indicates whether the detection sequence has passed the timeout threshhold.		
	0b0 The detection sequence has not been running for over 1 s.		
	0b1 It has been over 1 s since the data pin contact was detected and debounced.{		
20 ERR	Error Flag		
	Indicates whether there is an error in the detection sequence.		
	0b0 No sequence errors.		
	0b1 Error in the detection sequence. See the SEQ_STAT field to determine the phase in which the error occurred.		
19–18 SEQ_STAT	Charger Detection Sequence Status		
_	Indicates the status of the charger detection sequence.		
	Ob00 The module is either not enabled, or the module is enabled but the data pins have not yet been detected.		
	0b01 Data pin contact detection is complete.		
	0b10 Charger detection is complete.		
	0b11 Charger type detection is complete.		
17–16 SEQ_RES	Charger Detection Sequence Results  Reports how charger detection is attached.		
	neports now charger detection is attached.		
	0b00 No results to report.		
	0b01 Attached to a standard host. Must comply with USB Spec 2.0 by drawing only 2.5mA (max) until connected.		
	0b10 Attached to a charging port. The exact meaning depends on bit 18: 0: Attached to either a charging host or a dedicated charger (The charger type detection has not completed.) 1: Attached to a charging host (The charger type detection has completed.)		
	0b11 Attached to a dedicated charger.		
15–0 Reserved	This field is reserved.		
	NOTE: Bits do not always read as 0.		



## 45.4.4 TIMER0 Register (USBDCD\_TIMER0)

TIMER0 has an TSEQ\_INIT field that represents the system latency (in ms) measured from the time VBUS goes active to the time system software initiates the charger detection sequence in the USBDCD module. When software sets the CONTROL[START] bit, the Unit Connection Timer (TUNITCON) is initialized with the value of TSEQ\_INIT. Valid values are 0-1023, however the USB Battery Charging Specification requires the entire sequence, including TSEQ\_INIT, to be completed in 1s or less.






#### **USBDCD\_TIMER0** field descriptions

Field	Description
31–26 Reserved	This read-only field is reserved and always has the value zero.
25–16 TSEQ_INIT	Sequence Initiation Time  TSEQ_INIT represents the system latency (in ms) measured from the time VBUS goes active to the time system software initiates the charger detection sequence in the USBDCD module. When software sets the CONTROL[START] bit, the Unit Connection Timer (TUNITCON) is initialized with the value of TSEQ_INIT. Valid values are 0-1023, but the USB Battery Charging Specification requires the entire sequence, including TSEQ_INIT, to be completed in 1s or less.
15–12 Reserved	This read-only field is reserved and always has the value zero.
11-0 TUNITCON	Unit Connection Timer Elapse (in ms)  Displays the current elapsed time since software set the CONTROL[START] bit plus the value of TSEQ_INIT. The timer is initially loaded with the value of TSEQ_INIT before starting to count.  This timer enables compliance with the maximum time allowed to connect (TUNIT_CON) under the USB Battery Charging Specification, v1.1.If the timer reaches the TUNIT_CON one second limit, the module triggers an interrupt and sets the error flag STATUS[ERR].  The timer continues counting throughout the charger detection sequence, even when control has been passed to software. As long as the module is active, the timer continues to count until it reaches the maximum value of 0xFFF (4095 ms). The timer does not rollover to zero. A software reset clears the timer.



## 45.4.5 USBDCD\_TIMER1

Address: USBDCD\_TIMER1 is 4003\_5000h base + 14h offset = 4003\_5014h




#### **USBDCD\_TIMER1** field descriptions

Field	Description	
31–26 Reserved	This read-only field is reserved and always has the value zero.	
25–16 TDCD_DBNC	Time Period to Debounce D+ Signal  Sets the amount of time (in ms) to debounce the D+ signal during the data pin contact detection phase (while IDP_SRC and RDM_DWN are enabled). Valid values are 1-1023, but the USB Battery Charging Specification requires a minimum value of 10 ms.	
15–10 Reserved	This read-only field is reserved and always has the value zero.	
9-0 TVDPSRC_ON	Time Period Comparator Enabled  Sets the amount of time (in ms) that VDP_SRC, IDM_SINK, and the D-/VDAT_REF comparator are enabled and connected to the D+/D- lines during the charging port detection phase of the sequence. Valid values are 1-1023, but the USB Battery Charging Specification requires a minimum value of 40 ms.	

## 45.4.6 USBDCD TIMER2

TIMER2 contains timing parameters. Note that register values can be written that are not compliant with the USB Battery Charging Specification v1.1, so care should be taken when overwriting the default values.

Address: USBDCD\_TIMER2 is 4003\_5000h base + 18h offset = 4003\_5018h



#### **USBDCD\_TIMER2** field descriptions

Field	Description
31–26 Reserved	This read-only field is reserved and always has the value zero.

Table continues on the next page...

runctional Description

#### **USBDCD\_TIMER2** field descriptions (continued)

Field	Description	
25–16 TVDPSRC_CON	Time Period Before Enabling D+ Pullup  Sets the amount of time (in ms) that the module waits after charging port detection before system software should enable the D+ pullup to connect to the USB host. Valid values are 1-1023, but the USB Battery Charging Specification requires a minimum value of 40 ms.	
15–4 Reserved	This read-only field is reserved and always has the value zero.	
3-0 CHECK_DM	Time Before Check of D- Line  Sets the amount of time (in ms) that the module waits after the device connects to the USB bus (software enables the D+ pullup) until checking the state of the D- line to determine the type of charging port. Valid values are 1-15ms.	

## 45.5 Functional Description

The sequence of detecting the presence of and type of charging port involves several hardware components, coordinated by system software. This collection of interacting hardware and software is called the USB Battery Charging Subsystem. The following figure shows the USBDCD module as a component of the subsystem. The following table describes the components.




Figure 45-8. The USB Battery Charging Subsystem



#### Table 45-13. USB Battery Charger Subsystem Components

Component	Description		
Battery Charger IC	The external battery charger IC regulates the charge rate to the rechargable battery. System software is responsible for communicating the appropriate charge rates.		
Charger Maximum Currer		Maximum Current Drawn <sup>1</sup>	
	Standard host port	up to 500 mA	
	Charging host port	up to 1500 mA	
	Dedicated charging port	up to 1800 mA	
	If the USB host has suspended the USB device, system software must configure the system to limit the current drawn from the USB bus to 2.5 mA or less.		
Comm Module	A communications module on the device can be used to control the charge rate of the battery charger IC.		
System software	Coordinates the detection activities	s of the subsystem.	
USB Controller	The D+ pullup enable control signal plays a role during the charger type detection phase. System software must issue a command to the USB controller to assert this signal. Once pullup is enabled, the device is considered to be connected to the USB bus. The host the attempts to enumerate it.		
Note that the USB controller must be used only for USB <i>device</i> applications used used only for USB <i>device</i> applications the USBDCD module must be used only for USB <i>device</i> applications.			
USB Transceiver	The USB transceiver contains the pullup resistor for the USB D+ signal and the pulldow resistors for the USB D+ and D- signals. The D+ pullup and the D- pulldown are both us during the charger detection sequence. The USB transceiver also outputs the digital state the D+ and D- signals from the USB bus.		
	The pullup and pulldown enable signals are controlled by other modules during the charger detection sequence: The D+ pullup enable is physically output from the USB controller but is under software control. The USBDCD module controls the D- pulldown enable.		
USBDCD Module	Detects if the device has been plugged into either a standard host port, a charging host port, or a dedicated charger.		
VBUS_detect	VBUS_detect  This interrupt pin connected to the USB VBUS signal detects when the device has been plugged into or unplugged from the USB bus. If the system requires waking up from a loop power mode upon being plugged into the USB port, this interrupt should also be a low power wake up source. If this pin multiplexes other functions, such as GPIO, the pin should be configured as an interrupt whenever the USB plug or unplug event is required to be determined.		

<sup>1.</sup> If the USB host has suspended the USB device, system software must configure the system to limit the current drawn from the USB bus to 2.5 mA or less.

## 45.5.1 The Charger Detection Sequence

The following figure illustrates the charger detection sequence in a simplified timing diagram based on the USB Battery Charging Specification v1.1.

runctional Description




Figure 45-9. Full Speed Charger Detection Timing

The following table provides an overview description of the charger detection sequence shown in the preceding figure.



Table 45-14. Overview of the Charger Detection Sequence

	Phase	Overview Description	Full Description
1	Initial Conditions	Initial system conditions that need to be met before initiating the detection sequence	Initial System Conditions
2	VBUS Detection	System software detects contact of the VBUS signal with the system interrupt pin VBUS_detect.	VBUS Contact Detection
3	Data Pin Contact Detection	The USBDCD module detects that the USB data pins D+ and D- have made contact with the USB port.	Data Pin Contact Detection
4	Charging Port Detection	The USBDCD module detects if the port is a standard host or either type of charging port (charging host or dedicated charger).	Charging Port Detection
5	Charger Type Detection	If attached to a charging port, detect which type.	Charger Type Detection
6	Sequence Timeout	The USBDCD module did not finish the detection sequence within the timeout interval. The sequence will continue until halted by software.	Charger Detection Sequence Timeout

Timing parameter values used in this module are listed in the following table.

Table 45-15. Timing Parameters for the Charger Detection Sequence

Parameter	USB Battery Charging Spec	Module Default	Module Programmable Range
T <sub>DCD_DBNC</sub> 1	10 ms min (no max)	10 ms	0 - 1023 ms
T <sub>VDPSRC_ON</sub> 1	40 ms min (no max)	40 ms	0 - 1023 ms
T <sub>VDPSRC_CON</sub> 1	40 ms min (no max)	40 ms	0 - 1023 ms
CHECK_DM	N/A	1 ms	0 - 15 ms
T <sub>SEQ_INIT</sub>	N/A	16 ms	0 - 1023 ms
T <sub>UNIT_CON</sub> 1	1 s	N/A	N/A
T <sub>VDMSRC_EN</sub> 1	1 - 20 ms	From the USB host	N/A
T <sub>VDMSRC_DIS</sub> 1	0 - 20 ms	From the USB host	N/A
T <sub>CON_IDPSINK_DIS</sub>	0 - 20 ms	From the USB host	N/A

<sup>1.</sup> This parameter is defined by the USB Battery Charging Specification, v1.1.

## 45.5.1.1 Initial System Conditions

Before starting the USBDCD module's charger detection sequence, the system must be:

- using a rechargable battery,
- for a FS USB device application (cannot be HS, LS, host, or OTG),
- powered-up and in run mode,



#### **runctional Description**

- recently plugged into a USB port, and
- drawing no more than 2.5 mA total system current from the USB bus.

There are many allowable precursors to this set of initial conditions. For example, the device could have been powered down and subsequently powered up upon being plugged into the USB bus. Alternatively, the device could have been in a low power state that was exited due to the plugin event. Or, the device could have been operating in normal run mode, powered by a separate supply or non-rechargable battery.

#### 45.5.1.2 VBUS Contact Detection

Once the device is plugged into a USB port, the VBUS\_detect system interrupt is triggered. System software should do the following to initialize the module and start the charger detection sequence:

- 1. Restore power if the module is powered-off.
- 2. Set the CONTROL[SR] bit to initiate a software reset.
- 3. Configure the USBDCD module: Program the CLOCK register and the timing parameters as needed.
- 4. Set the CONTROL[IE] bit to enable interrupts (by default), or clear the bit if using a software polling method.
- 5. Set the CONTROL[START] bit to start the charger detection sequence.

#### 45.5.1.3 Data Pin Contact Detection

Because the detection sequence depends upon the state of the USB D+, the module must ensure that the data pins have made contact. USB plugs and receptables are designed such that when the plug is inserted into the receptable, the power pins make contact before the data pins make contact. See the following figure.






Figure 45-10. Relative Pin Positions in USB Plugs and Receptacles

As a result, when a portable USB device is attached to an upstream port, the portable USB device detects VBUS before the data pins have made contact. The time between power pins and data pins making contact depends on how fast the plug is inserted into the receptable. Delays of several hundred milliseconds are possible.

#### 45.5.1.3.1 Debouncing the Data Pin Contact

When system software has initiated the charger detection sequence, as described in Initial System Conditions the USBDCD module turns on the  $I_{DP\_SRC}$  current source and enables the  $R_{DM\_DWN}$  pulldown resistor. If the data pins have not made contact, the D+ line remains high. Once the data pins make contact, the D+ line goes low and debouncing begins.

Once the D+ line goes low, the module continuously samples the D+ line over the duration of the  $T_{DCD\_DBNC}$  debounce time interval.  $T_{DCD\_DBNC}$  defaults to 10 ms but can be programmed in the TIMER0[TDCD\_DBNC] field. See the description of the TIMER0 Register for register information.

When it has remained low for the entire interval, the debouncing is complete. However, if the D+ line returns high during the debounce interval, the module waits until the D+ line goes low again to restart the debouncing. This cycle repeats until either:

- the data pin contact has been successfully debounced (see Success in Detecting Data Pin Contact (Phase Completion)), or
- a timeout occurs (see Charger Detection Sequence Timeout).

#### 45.5.1.3.2 Success in Detecting Data Pin Contact (Phase Completion)

After successfully debouncing the D+ state, the module does the following:



#### **runctional Description**

- updates the STATUS register to reflect phase completion (See Table 45-18 for field values.)
- directly proceeds to the next step in the sequence: detection of a charging port See Charging Port Detection.

#### 45.5.1.4 Charging Port Detection

Once it is known that the data pins have made contact, the module waits for a fixed delay of 1 ms, and then attempts to detect if it has been plugged into a charging port. The module connects the following analog units to the USB D+ or D- lines during this phase (when the usbdcd\_en and usbdcd\_chg\_det\_en signals are asserted high):

- The voltage source V<sub>DP SRC</sub> connects to the D+ line
- The current sink I<sub>DM</sub> SINK connects to the D- line
- The voltage comparator connects to the USB D- line, comparing it to the voltage  $V_{DAT\_REF}$  .

After a time of  $T_{VDPSRC\_ON}$ , the module samples the D- line. The  $T_{VDPSRC\_ON}$  parameter is programmable and defaults to 40 ms. After sampling the D- line, the module disconnects the voltage source, current sink, and comparator.

The next steps in the sequence depend on the voltage on the D- line as determined by the voltage comparator. See the following table.

 If the voltage on D- is...
 Then...
 See...

 Below VDAT\_REF
 The port is a standard host that does not support the USB Battery Charging Specification v1.1.
 Standard Host Port

 Above VDAT\_REF but below VLGC
 The port is a charging port.
 Charging Port

 Above VLGC
 This is an error condition..
 Error in Charging Port Detection

Table 45-16. Sampling D- in the Charging Port Detection Phase

#### 45.5.1.4.1 Standard Host Port

As part of the charger detection handshake with a standard USB host, the module does the following (without waiting for the  $T_{VDPSRC\ CON}$  interval to elapse):

• Updates the STATUS register to reflect that a standard host has been detected with SEQ\_RES = 01. (See Table 45-18 for field values.)



- Sets the CONTROL[IF] bit.
- Generates an interrupt if enabled (the CONTROL[IE] bit is set).

At this point, control has been passed to system software via the interrupt. The rest of the sequence (detecting the type of charging port) is not applicable, so software should:

- 1. Read the STATUS register.
- 2. Set the CONTROL[IACK] bit to acknowledge the interrupt.
- 3. Set the CONTROL[SR] bit to issue a software reset to the module.
- 4. Disable the module.
- 5. Communicate the appropriate charge rate to the external battery charger IC; see Table 45-13.

#### 45.5.1.4.2 Charging Port

As part of the charger detection handshake with any type of USB host, the module waits until the T<sub>VDPSRC</sub> CON interval has elapsed before doing the following:

- Updates the STATUS register to reflect that a charging port has been detected with SEQ\_RES = 10. (See Table 45-18 for field values.)
- Sets the CONTROL[IF] bit.
- Generates an interrupt if enabled (the CONTROL[IE] bit is set).

At this point, control has passed to system software via the interrupt. Software should:

- 1. Read the STATUS register.
- 2. Set the CONTROL[IACK] bit to acknowledge the interrupt.
- 3. Issue a command to the USB controller to pullup the USB D+ line.
- 4. Wait for the module to complete the final phase of the sequence. See Charger Type Detection.

#### 45.5.1.4.3 Error in Charging Port Detection

For this error condition, the module does the following:



#### **runctional Description**

- Updates the STATUS register to reflect the error with SEQ\_RES = 00. (See Table 45-18 for field values.)
- Sets the CONTROL[IF] bit.
- Generates an interrupt if enabled (the CONTROL[IE] bit is set).

Note that in this case the module does not wait for the T<sub>VDPSRC</sub> CON interval to elapse.

At this point, control has been passed to system software via the interrupt. The rest of the sequence (detecting the type of charging port) is not applicable, so software should:

- 1. Read the STATUS register.
- 2. Set the CONTROL[IACK] bit to acknowledge the interrupt.
- 3. Set the CONTROL[SR] bit to issue a software reset to the module.
- 4. Disable the module.

## 45.5.1.5 Charger Type Detection

After software enables the D+ pullup resistor, the module is notified automatically (via internal signaling; the module waits until the ipp\_pue\_pullup\_dp input goes high) to start the CHECK\_DM timer counting down the time interval programmed into the TIMER2[CHECK\_DM] field.

Once the CHECK\_DM time has elapsed, the module samples the USB D- line to determine the type of charger. See the following table.

Table 45-17. Sampling D- in the Charger Type Detection Phase

If the voltage on D- is	Then	See
High	The port is a dedicated charging port.1	Dedicated Charging Port
Low	The port is a charging host port.2	Charging Host Port

- 1. In a dedicated charger, the D+ and D- lines are shorted together through a small resistor.
- 2. In a charging host port, the D+ and D- lines are not shorted.

#### 45.5.1.5.1 Dedicated Charging Port

For a dedicated charger, the module does the following:



- Updates the STATUS register to reflect that a dedicated charger has been detected with SEQ\_RES = 11. (See Table 45-18 for field values.)
- Sets the CONTROL[IF] bit.
- Generates an interrupt if enabled (the CONTROL[IE] bit is set).

At this point, control has been passed to system software via the interrupt. Software should:

- 1. Read the STATUS register.
- 2. Disable the USB controller to prevent transitions on the USB D+ or D- lines from causing spurious interrupt or wake-up events to the system.
- 3. Set the CONTROL[IACK] bit to acknowledge the interrupt.
- 4. Set the CONTROL[SR] bit to issue a software reset to the module.
- 5. Disable the module.
- 6. Communicate the appropriate charge rate to the external battery charger IC; see Table 45-13.

#### 45.5.1.5.2 Charging Host Port

For a charging host port, the module does the following:

- Updates the STATUS register to reflect that a charging host port has been detected with SEQ\_RES = 10. (See Table 45-18 for field values.)
- Sets the CONTROL[IF] bit.
- Generates an interrupt if enabled (the CONTROL[IE] bit is set).

At this point, control has been passed to system software via the interrupt. Software should:

- 1. Read the STATUS register.
- 2. Set the CONTROL[IACK] bit to acknowledge the interrupt.
- 3. Set the CONTROL[SR] bit to issue a software reset to the module.
- 4. Disable the module.
- 5. Communicate the appropriate charge rate to the external battery charger IC; see Table 45-13.

## 45.5.1.6 Charger Detection Sequence Timeout

The maximum time to connect allowed under the *USB Battery Charging Specification*, v1.1 is one second. If the Unit Connection Timer reaches the one second limit and the sequence is still running (indicated by the STATUS[ACTIVE] bit still being set), the module does the following:

- Updates the STATUS register to reflect that a timeout error has occured. (See Table 45-18 for field values.)
- Sets the CONTROL[IF] bit.
- Generates an interrupt if enabled (the CONTROL[IE] bit is set).
- The detection sequence continues until explicitly halted by software setting the CONTROL[SR] bit.
- The Unit Connection Timer continues counting. See the description of the TIMER0 Register.

At this point, control has been passed to system software via the interrupt, which has two options: ignore the interrupt and allow more time for the sequence to complete, or halt the sequence. To halt the sequence, software should:

- 1. Read the STATUS register.
- 2. Set the CONTROL[IACK] bit to acknowledge the interrupt.
- 3. Set the CONTROL[SR] bit to issue a software reset to the module.
- 4. Disable the module.

This timeout function is also useful in case software does not realize that the user unplugged the USB device from the USB port during the charger detection sequence. If the interrupt occurs but the  $V_{BUS\_DETECT}$  input is low, software can disable and reset the module.

System software might allow the sequence to run past the timeout interrupt under these conditions:

- 1. the USB Battery Charging Spec is amended to allow more time. In this case, software should poll the T<sub>UNITCON</sub> register field (see the description of the TIMER0 Register) periodically to track elapsed time after 1s; or
- 2. for debug purposes.



Note that the  $T_{UNITCON}$  register field will stop incrementing when it reaches its maximum value so it will not rollover to zero and start counting up again.

## 45.5.2 Interrupts and Events

The USBDCD module has an interrupt to alert system software of certain events, which are listed in the following table. All events except the Phase Complete event for the Data Pin Detection phase can trigger an interrupt.

Table 45-18. Events Triggering an Interrupt by Sequence Phase

Sequence Phase	Event	Event Description	STATUS Fields <sup>1</sup>	Phase Description	
Data Pin	Phase	The module has detected data pin contact.	ERR = 0	VBUS Contact	
Detection	Complete	No interrupt occurs: CONTROL[IF] = 0.	SEQ_STAT = 01	Detection	
			SEQ_RES = 00		
			TO = 0		
Charging Port	Phase	The module has completed the process of	ERR = 0	Charging Port	
Detection	Complete	identifying if the USB port is a charging port or not.	SEQ_STAT = 10	Detection	
		Tiot.	SEQ_RES = 01 or 10		
			TO = 0		
	Error	The module cannot identify the type of port because the D- line is above the USB's VLGC threshold.	ERR = 1	Error in Charging	
			SEQ_STAT = 10	Port Detection	
			SEQ_RES = 00		
			TO = 0		
Charger Type	Phase	The module has completed the process of	ERR = 0	Charger Type	
Detection	Complete	identifying the charger type detection.	SEQ_STAT = 11	Detection	
		Note: The ERR flag always reads as zero because no known error conditions	SEQ_RES = 11 or 10		
		are checked during this phase.	TO = 0		
Sequence	Error	The timeout interval from the time the USB	ERR = 1	Charger	
Timeout		device attaches to a USB port until it connects has elapsed	SEQ_STAT = last value <sup>2</sup>	Detection Sequence	
		The stapes of	SEQ_RES = last value <sup>2</sup>	Timeout.	
			TO = 1		

<sup>1.</sup> See the description of the Status Register for register information.

#### 45.5.2.1 Interrupt Handling

Software can read which event caused the interrupt from the STATUS register during the interrupt service routine.

<sup>2.</sup> The SEQ\_STAT and SEQ\_RES fields retain the values held at the time of the timeout error.



#### runctional Description

An interrupt is generated only if the CONTROL[IE] bit is set. The CONTROL[IF] bit is always set under interrupt conditions, even if the IE bit is cleared. In this case, software can poll the IF flag to determine if an interrupt condition is pending.

Writes to the IF bit are ignored. To reset the IF bit, set the CONTROL[IACK] bit to acknowledge the interrupt. Writing to the IACK bit while the IF bit is cleared has no effect.

#### 45.5.3 Resets

There are two ways to reset various register contents in this module: hardware resets and a software reset.

#### 45.5.3.1 Hardware Resets

Hardware resets originate at the system or device level and propagate down to the individual module level. They include power-on reset, low-voltage reset, and all other hardware reset sources.

Hardware resets cause the register contents to be restored to their default state as listed in the register descriptions.

#### 45.5.3.2 Software Reset

A software reset re-initializes the module's status information but leaves configuration information unchanged. The software reset allows software to prepare the module without needing to reprogram the same configuration each time the USB device is plugged into a USB port.

Setting the CONTROL[SR] bit initiates a software reset. The following table shows what register fields are reset to their default values by a software reset.

Table 45-19. Software Reset and Register Fields Affected

Register	Fields Affected	Fields Not Affected
CONTROL <sup>1</sup>	[IF]	[IE, START]
STATUS	All	None
CLOCK	None	All
TIMERn	TUNITCON	All other

1. The CONTROL[SR, IACK] bits are self-clearing.



A software reset also returns all internal logic, timers, and counters to their reset states. State Machines return to IDLE. If the module is already active (STATUS[ACTIVE] = 1), a software reset stops the sequence.

#### **Note**

Software should always initiate a software reset before starting the sequence (setting the CONTROL[START] bit) to ensure the module is in a known state.

#### 45.6 Initialization Information

This module has been designed for minimal configuration while retaining significant programmability. The CLOCK register needs to be initialized to the actual system clock frequency (unless the default value already matches the system requirements).

The other registers generally do not need to be modified because they default to values that comply with the USB Battery Charging Specification v1.1. However, several timing parameters can be changed for a great deal of flexibility if a particular system requires it.

All module configuration must occur *before* initiating the charger detection sequence. Configuration changes made *after* setting the CONTROL[START] bit result in undefined behavior.

## 45.7 Application Information

This section provides application information.

## 45.7.1 External Pullups

Any external pullups applied to the USB D+ or D- data lines must be capable of being disabled to prevent incorrect pullup values or incorrect operation of the USB subsystem.

## 45.7.2 Dead or Weak Battery

According to the USB Battery Charging Specification v1.1, a USB device with a dead, weak, or missing battery that is attached to a charging port can remain attached indefinitely drawing up to 1.5A until the battery is charged to the point that the USB device can connect.



#### Application Information

The USBDCD module is compatible with systems that do not check the strength of the battery. Therefore, this module assumes that the battery is good, so the USB device must immediately connect to the USB bus by pulling the D+ line high after the USBDCD module has determined that the device is attached to a charging port. The module is also compatible with systems that do check the strength of the battery. In these systems, if it is known that the battery is weak or dead, software can delay connecting to the USB while charging at 1.5A. Once the battery is charged to the good battery threshold, software can then connect to the USB host by pulling the D+ line high.

## 45.7.3 Handling Unplug Events

If the device is unplugged from the USB bus during the charger detection sequence, the contents of the STATUS register should be ignored and the USBDCD module should get a Sotware Reset, as described in Software Reset.



## Chapter 46 USB Voltage Regulator

#### 46.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The USB Voltage Regulator module is a LDO linear voltage regulator to provide 3.3V power from an input power supply varying from 2.7 V to 5.5 V. It consists of one 3.3 V power channel. When the input power supply is below 3.6 V, the regulator goes to pass-through mode. The following figure shows the ideal relation between the regulator output and input power supply.




Figure 46-1. Ideal Relation Between the Regulator Output and Input Power Supply



muroduction

#### 46.1.1 Overview

A simplified block diagram for the USB Voltage Regulator module is shown below.




Figure 46-2. USB Voltage Regulator Block Diagram

This module uses 2 regulators in parallel. In run mode, the RUN regulator with the bandgap voltage reference is enabled and can provide up to 120 mA load current. In run mode, the STANDBY regulator and the low power reference are also enabled, but a switch disconnects its output from the external pin. In STANDBY mode, the RUN regulator is disabled and the STANDBY regulator output is connected to the external pin supplying up to 3 mA load current.

Internal power mode signals control whether the module is in RUN or STANDBY mode.

## 46.1.2 Features

- Low drop-out linear voltage regulator with one power channel (3.3V).
- Low drop-out voltage: 300 mV.
- Output current: 120 mA.
- Three different power modes: RUN, STANDBY and SHUTDOWN.
- Low quiescent current in RUN mode.
  - Typical value is around 120 uA (one thousand times smaller than the maximum load current).
- Very low quiescent current in STANDBY mode.
  - Typical value is around 1 uA.



- Automatic current limiting if the load current is greater than 290 mA.
- Automatic power-up once some voltage is applied to the regulator input.
- Pass-through mode for regulator input voltages less than 3.6 V
- Small output capacitor: 2.2 uF
- Stable with aluminum, tantalum or ceramic capacitors.

## 46.1.3 Modes of Operation

The regulator has these power modes:

- RUN—The regulating loop of the RUN regulator and the STANDBY regulator are active, but the switch connecting the STANDBY regulator output to the external pin is open.
- STANDBY—The regulating loop of the RUN regulator is disabled and the standby regulator is active. The switch connecting the STANDBY regulator output to the external pin is closed.
- SHUTDOWN—The module is disabled.

The regulator is enabled by default. This means that once the power supply is provided, the module power-up sequence to RUN mode starts.

## 46.2 USB Voltage Regulator Module Signal Descriptions

The following table shows the external signals for the regulator.

Table 46-1. USB Voltage Regulator Module Signal Descriptions

Signal	Description	I/O
reg33_in	Unregulated power supply	I
reg33_out	Regulator output voltage	0



Voltage Regulator Module Signal Descriptions



# Chapter 47 SPI (DSPI)

#### 47.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The serial peripheral interface module provides a synchronous serial bus for communication between an MCU and an external peripheral device.

## 47.1.1 Block Diagram

The block diagram of this module is as follows:



#### muroduction




Figure 47-1. DSPI Block Diagram

#### 47.1.2 Features

The DSPI supports these SPI features:

- Full-duplex, Four-wire synchronous transfers
- Master and slave modes
  - Data streaming operation in slave mode with continuous slave selection
- Buffered transmit operation using the TX FIFO with depth of 4 entries
- Buffered receive operation using the RX FIFO with depth of 4 entries
- TX and RX FIFOs can be disabled individually for low-latency updates to SPI queues
- Visibility into TX and RX FIFOs for ease of debugging
- Programmable transfer attributes on a per-frame basis:



- 2 transfer attribute registers
- Serial clock with programmable polarity and phase
- Various programmable delays
- Programmable serial frame size of 4 to 16 bits, expandable by software control
  - SPI frames longer than 16 bits can be supported using the continuous selection format.
- Continuously held chip select capability
- 6 Peripheral Chip Selects, expandable to 64 with external demultiplexer
- Deglitching support for up to 32 Peripheral Chip Select with external demultiplexer
- DMA support for adding entries to TX FIFO and removing entries from RX FIFO:
  - TX FIFO is not full (TFFF)
  - RX FIFO is not empty (RFDF)
- Interrupt conditions:
  - End of queue reached (EOQF)
  - TX FIFO is not full (TFFF)
  - Transfer of current frame complete (TCF)
  - Attempt to transmit with an empty Transmit FIFO (TFUF)
  - RX FIFO is not empty (RFDF)
  - Frame received while Receive FIFO is full (RFOF)
- Global interrupt request line
- Modified SPI transfer formats for communication with slower peripheral devices
- Power-saving architectural features
  - Support for stop mode
  - Support for doze mode

## 47.1.3 DSPI Configurations

The DSPI module always operates in SPI configuration.



## 47.1.3.1 SPI Configuration

The SPI configuration allows the DSPI to send and receive serial data. This configuration allows the DSPI to operate as a basic SPI block with internal FIFOs supporting external queues operation. Transmit data and received data reside in separate FIFOs. The host CPU or a DMA controller read the received data from the receive FIFO and write transmit data to the transmit FIFO.

For queued operations the SPI queues can reside in system RAM, external to the DSPI. Data transfers between the queues and the DSPI FIFOs are accomplished by a DMA controller or host CPU. The following figure shows a system example with DMA, DSPI and external queues in system RAM.




Figure 47-2. DSPI with Queues and DMA

## 47.1.4 Modes of Operation

The DSPI supports the following modes of operation that can be divided into two categories;

- Module-specific modes:
  - Master mode
  - Slave mode
  - Module disable mode
- MCU-specific modes:



- External stop mode
- Debug mode

The DSPI enters module-specific modes when the host writes a DSPI register. The MCU-specific modes are controlled by signals, external to the DSPI. The MCU-specific modes are modes that an MCU may enter in parallel to the DSPI block-specific modes.

#### 47.1.4.1 Master Mode

Master mode allows the DSPI to initiate and control serial communication. In this mode, the SCK signal and the PCS[x] signals are controlled by the DSPI and configured as outputs.

#### 47.1.4.2 Slave Mode

Slave mode allows the DSPI to communicate with SPI bus masters. In this mode, the DSPI responds to externally controlled serial transfers. The SCK signal and the PCS[0]/SS signals are configured as inputs and driven by a SPI bus master.

#### 47.1.4.3 Module Disable Mode

The module disable mode can be used for MCU power management. The clock to the non-memory mapped logic in the DSPI can be stopped while in the module disable mode.

#### 47.1.4.4 External Stop Mode

External stop mode is used for MCU power management. The DSPI supports the Peripheral Bus stop mode mechanism. When a request is made to enter external stop mode, the DSPI block acknowledges the request and completes the transfer in progress. When the DSPI reaches the frame boundary it signals that the system clock to the DSPI module may be shut off.



שברו Signal Descriptions

## 47.1.4.5 Debug Mode

Debug mode is used for system development and debugging. The MCR[FRZ] bit controls DSPI behavior in the debug mode. If the bit is set, the DSPI stops all serial transfers, when the MCU is in debug mode. If the bit is cleared, the MCU debug mode has no effect on the DSPI.

## 47.2 DSPI Signal Descriptions

This section provides the DSPI signals description.

The following table lists the signals that may connect off chip depending on device implementation.

Signal	Description	I/O
PCS0/SS	Master mode: Peripheral Chip Select 0 output	I/O
	Slave mode: Slave Select input	
PCS[3:1]	Master mode: Peripheral Chip Select 1 - 3	0
	Slave mode: Unused	
PCS4	Master mode: Peripheral Chip Select 4	0
	Slave mode: Unused	
PCS5/ PCSS	Master mode: Peripheral Chip Select 5 /	0
	Peripheral Chip Select Strobe	
	Slave mode: Unused	
SIN	Serial Data In	I
SOUT	Serial Data Out	0
SCK	Master mode: Serial Clock (output)	I/O
	Slave mode: Serial Clock (input)	

Table 47-1. DSPI Signal Descriptions

## 47.2.1 PCS0/SS — Peripheral Chip Select/Slave Select

In master mode, the PCS0 signal is a Peripheral Chip Select output that selects which slave device the current transmission is intended for.

In slave mode, the active low  $\overline{SS}$  signal is a Slave Select input signal that allows a SPI master to select the DSPI as the target for transmission.



## 47.2.2 PCS1 - PCS3 — Peripheral Chip Selects 1 - 3

PCS1 - PCS3 are Peripheral Chip Select output signals in master mode.

In slave mode, these signals are unused.

## 47.2.3 PCS4 — Peripheral Chip Select 4

In master mode, PCS4 is a Peripheral Chip Select output signal.

In slave mode, this signal is unused.

## 47.2.4 PCS5/PCSS — Peripheral Chip Select 5/Peripheral Chip Select Strobe

PCS5 is a Peripheral Chip Select output signal. When the DSPI is in master mode and the MCR[PCSSE] bit is cleared, this signal selects which slave device the current transfer is intended for.

When the DSPI is in master mode and the MCR[PCSSE] bit is set, the PCSS signal acts as a strobe to an external peripheral chip select demultiplexer, which decodes the PCSO - PCS4 signals, preventing glitches on the demultiplexer outputs.

This signal is not used in slave mode.

## 47.2.5 SIN — Serial Input

SIN is a serial data input signal.

#### 47.2.6 SOUT — Serial Output

SOUT is a serial data output signal.

## 47.2.7 SCK — Serial Clock

SCK is a serial communication clock signal. In master mode, the DSPI generates the SCK. In slave mode, SCK is an input from an external bus master.



## 47.3 Memory Map/Register Definition

Register accesses to memory addresses that are reserved or undefined result in a transfer error. Write access to the POPR register also results in a transfer error.

#### **SPI** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4002_C000	DSPI Module Configuration Register (SPI0_MCR)	32	R/W	0000_4001h	47.3.1/ 1153
4002_C008	DSPI Transfer Count Register (SPI0_TCR)	32	R/W	0000_0000h	47.3.2/ 1156
4002_C00C	DSPI Clock and Transfer Attributes Register (In Master Mode) (SPI0_CTAR0)	32	R/W	7800_0000h	47.3.3/ 1156
4002_C00C	DSPI Clock and Transfer Attributes Register (In Slave Mode) (SPI0_CTAR0_SLAVE)	32	R/W	7800_0000h	47.3.4/ 1161
4002_C010	DSPI Clock and Transfer Attributes Register (In Master Mode) (SPI0_CTAR1)	32	R/W	7800_0000h	47.3.3/ 1156
4002_C02C	DSPI Status Register (SPI0_SR)	32	R/W	See section	47.3.5/ 1162
4002_C030	DSPI DMA/Interrupt Request Select and Enable Register (SPI0_RSER)	32	R/W	0000_0000h	47.3.6/ 1165
4002_C034	DSPI PUSH TX FIFO Register In Master Mode (SPI0_PUSHR)	32	R/W	0000_0000h	47.3.7/ 1167
4002_C034	DSPI PUSH TX FIFO Register In Slave Mode (SPI0_PUSHR_SLAVE)	32	R/W	0000_0000h	47.3.8/ 1169
4002_C038	DSPI POP RX FIFO Register (SPI0_POPR)	32	R	0000_0000h	47.3.9/ 1169
4002_C03C	DSPI Transmit FIFO Registers (SPI0_TXFR0)	32	R	0000_0000h	47.3.10/ 1170
4002_C040	DSPI Transmit FIFO Registers (SPI0_TXFR1)	32	R	0000_0000h	47.3.10/ 1170
4002_C044	DSPI Transmit FIFO Registers (SPI0_TXFR2)	32	R	0000_0000h	47.3.10/ 1170
4002_C048	DSPI Transmit FIFO Registers (SPI0_TXFR3)	32	R	0000_0000h	47.3.10/ 1170
4002_C07C	DSPI Receive FIFO Registers (SPI0_RXFR0)	32	R	0000_0000h	47.3.11/ 1170
4002_C080	DSPI Receive FIFO Registers (SPI0_RXFR1)	32	R	0000_0000h	47.3.11/ 1170

Table continues on the next page...



## SPI memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4002_C084	DSPI Receive FIFO Registers (SPI0_RXFR2)	32	R	0000_0000h	47.3.11/ 1170
4002_C088	DSPI Receive FIFO Registers (SPI0_RXFR3)	32	R	0000_0000h	47.3.11/ 1170
4002_D000	DSPI Module Configuration Register (SPI1_MCR)	32	R/W	0000_4001h	47.3.1/ 1153
4002_D008	DSPI Transfer Count Register (SPI1_TCR)	32	R/W	0000_0000h	47.3.2/ 1156
4002_D00C	DSPI Clock and Transfer Attributes Register (In Master Mode) (SPI1_CTAR0)	32	R/W	7800_0000h	47.3.3/ 1156
4002_D00C	DSPI Clock and Transfer Attributes Register (In Slave Mode) (SPI1_CTAR0_SLAVE)	32	R/W	7800_0000h	47.3.4/ 1161
4002_D010	DSPI Clock and Transfer Attributes Register (In Master Mode) (SPI1_CTAR1)	32	R/W	7800_0000h	47.3.3/ 1156
4002_D02C	DSPI Status Register (SPI1_SR)	32	R/W	See section	47.3.5/ 1162
4002_D030	DSPI DMA/Interrupt Request Select and Enable Register (SPI1_RSER)	32	R/W	0000_0000h	47.3.6/ 1165
4002_D034	DSPI PUSH TX FIFO Register In Master Mode (SPI1_PUSHR)	32	R/W	0000_0000h	47.3.7/ 1167
4002_D034	DSPI PUSH TX FIFO Register In Slave Mode (SPI1_PUSHR_SLAVE)	32	R/W	0000_0000h	47.3.8/ 1169
4002_D038	DSPI POP RX FIFO Register (SPI1_POPR)	32	R	0000_0000h	47.3.9/ 1169
4002_D03C	DSPI Transmit FIFO Registers (SPI1_TXFR0)	32	R	0000_0000h	47.3.10/ 1170
4002_D040	DSPI Transmit FIFO Registers (SPI1_TXFR1)	32	R	0000_0000h	47.3.10/ 1170
4002_D044	DSPI Transmit FIFO Registers (SPI1_TXFR2)	32	R	0000_0000h	47.3.10/ 1170
4002_D048	DSPI Transmit FIFO Registers (SPI1_TXFR3)	32	R	0000_0000h	47.3.10/ 1170
4002_D07C	DSPI Receive FIFO Registers (SPI1_RXFR0)	32	R	0000_0000h	47.3.11/ 1170
4002_D080	DSPI Receive FIFO Registers (SPI1_RXFR1)	32	R	0000_0000h	47.3.11/ 1170
4002_D084	DSPI Receive FIFO Registers (SPI1_RXFR2)	32	R	0000_0000h	47.3.11/ 1170
4002_D088	DSPI Receive FIFO Registers (SPI1_RXFR3)	32	R	0000_0000h	47.3.11/ 1170



#### wemory Map/Register Definition

## SPI memory map (continued)


Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400A_C000	DSPI Module Configuration Register (SPI2_MCR)	32	R/W	0000_4001h	47.3.1/ 1153
400A_C008	DSPI Transfer Count Register (SPI2_TCR)	32	R/W	0000_0000h	47.3.2/ 1156
400A_C00C	DSPI Clock and Transfer Attributes Register (In Master Mode) (SPI2_CTAR0)	32	R/W	7800_0000h	47.3.3/ 1156
400A_C00C	DSPI Clock and Transfer Attributes Register (In Slave Mode) (SPI2_CTAR0_SLAVE)	32	R/W	7800_0000h	47.3.4/ 1161
400A_C010	DSPI Clock and Transfer Attributes Register (In Master Mode) (SPI2_CTAR1)	32	R/W	7800_0000h	47.3.3/ 1156
400A_C02C	DSPI Status Register (SPI2_SR)	32	R/W	See section	47.3.5/ 1162
400A_C030	DSPI DMA/Interrupt Request Select and Enable Register (SPI2_RSER)	32	R/W	0000_0000h	47.3.6/ 1165
400A_C034	DSPI PUSH TX FIFO Register In Master Mode (SPI2_PUSHR)	32	R/W	0000_0000h	47.3.7/ 1167
400A_C034	DSPI PUSH TX FIFO Register In Slave Mode (SPI2_PUSHR_SLAVE)	32	R/W	0000_0000h	47.3.8/ 1169
400A_C038	DSPI POP RX FIFO Register (SPI2_POPR)	32	R	0000_0000h	47.3.9/ 1169
400A_C03C	DSPI Transmit FIFO Registers (SPI2_TXFR0)	32	R	0000_0000h	47.3.10/ 1170
400A_C040	DSPI Transmit FIFO Registers (SPI2_TXFR1)	32	R	0000_0000h	47.3.10/ 1170
400A_C044	DSPI Transmit FIFO Registers (SPI2_TXFR2)	32	R	0000_0000h	47.3.10/ 1170
400A_C048	DSPI Transmit FIFO Registers (SPI2_TXFR3)	32	R	0000_0000h	47.3.10/ 1170
400A_C07C	DSPI Receive FIFO Registers (SPI2_RXFR0)	32	R	0000_0000h	47.3.11/ 1170
400A_C080	DSPI Receive FIFO Registers (SPI2_RXFR1)	32	R	0000_0000h	47.3.11/ 1170
400A_C084	DSPI Receive FIFO Registers (SPI2_RXFR2)	32	R	0000_0000h	47.3.11/ 1170
400A_C088	DSPI Receive FIFO Registers (SPI2_RXFR3)	32	R	0000_0000h	47.3.11/ 1170



## 47.3.1 DSPI Module Configuration Register (SPIx\_MCR)

Contains bits to configure various attributes associated with DSPI operations. The HALT and MDIS bits can be changed at any time, but they only take effect on the next frame boundary. Only the HALT and MDIS bits in the MCR can be changed, while the DSPI is in the Running state.

Addresses: SPI0\_MCR is 4002\_C000h base + 0h offset = 4002\_C000h SPI1\_MCR is 4002\_D000h base + 0h offset = 4002\_D000h SPI2\_MCR is 400A\_C000h base + 0h offset = 400A\_C000h



#### SPIx\_MCR field descriptions

Field	Description
31 MSTR	Master/Slave Mode Select
	Configures the DSPI for either master mode or slave mode.
	0 DSPI is in slave mode.
	1 DSPI is in master mode.
30 CONT_SCKE	Continuous SCK Enable
00111_00112	Enables the Serial Communication Clock (SCK) to run continuously.
	0 Continuous SCK disabled.
	1 Continuous SCK enabled.
29–28 DCONF	DSPI Configuration
	Selects among the different configurations of the DSPI.
	00 SPI
	01 Reserved
	10 Reserved
	11 Reserved



#### wemory Map/Register Definition

# SPIx\_MCR field descriptions (continued)

Field	Description
27 FRZ	Freeze
	Enables the DSPI transfers to be stopped on the next frame boundary when the device enters Debug mode.
	<ul><li>Do not halt serial transfers in debug mode.</li><li>Halt serial transfers in debug mode.</li></ul>
26 MTFE	Modified Timing Format Enable
	Enables a modified transfer format to be used.  O Modified SPI transfer format disabled.
	Modified SPI transfer format enabled.
25 PCSSE	Peripheral Chip Select Strobe Enable
	Enables the PCS[5]/ PCSS to operate as a PCS Strobe output signal.
	<ul> <li>PCS[5]/PCSS is used as the Peripheral Chip Select[5] signal.</li> <li>PCS[5]/PCSS is used as an active-low PCS Strobe signal.</li> </ul>
24 ROOE	Receive FIFO Overflow Overwrite Enable
HOOL	In the RX FIFO overflow condition, configures the DSPI to ignore the incoming serial data or overwrite existing data. If the RX FIFO is full and new data is received, the data from the transfer, generating the overflow, is ignored or shifted into the shift register.
	0 Incoming data is ignored.
23–22	Incoming data is shifted into the shift register.  This read-only field is reserved and always has the value zero.
Reserved 21–16	Peripheral Chip Select x Inactive State
PCSIS[5:0]	Determines the inactive state of PCSx.
	<ul> <li>The inactive state of PCSx is low.</li> <li>The inactive state of PCSx is high.</li> </ul>
15	Doze Enable
DOZE	Provides support for an externally controlled Doze mode power-saving mechanism.
	<ul><li>0 Doze mode has no effect on DSPI.</li><li>1 Doze mode disables DSPI.</li></ul>
14 MDIS	Module Disable
2.0	Allows the clock to be stopped to the non-memory mapped logic in the DSPI effectively putting the DSPI in a software controlled power-saving state. The reset value of the MDIS bit is parameterized, with a default reset value of "0".
	Enable DSPI clocks.     Allow external logic to disable DSPI clocks.
L	




# SPIx\_MCR field descriptions (continued)


Field	Description
13 DIS_TXF	Disable Transmit FIFO  When the TX FIFO is disabled, the transmit part of the DSPI operates as a simplified double-buffered SPI. This bit can only be written when the MDIS bit is cleared.
	<ul><li>0 Tx FIFO is enabled.</li><li>1 Tx FIFO is disabled.</li></ul>
12 DIS_RXF	Disable Receive FIFO  When the RX FIFO is disabled, the receive part of the DSPI operates as a simplified double-buffered SPI.
	This bit can only be written when the MDIS bit is cleared.  O Rx FIFO is enabled.
	1 Rx FIFO is disabled.
11 CLR_TXF	Clear TX FIFO  Flushes the TX FIFO. Writing a 1 to CLR_TXF clears the TX FIFO Counter. The CLR_TXF bit is always
	read as zero.
	0 Do not clear the Tx FIFO counter.
	1 Clear the Tx FIFO counter.
10 CLR_RXF	Flushes the RX FIFO. Writing a 1 to CLR_RXF clears the RX Counter. The CLR_RXF bit is always read as zero.
	0 Do not clear the Rx FIFO counter.
	1 Clear the Rx FIFO counter.
9–8 SMPL_PT	Sample Point
	Controls when the DSPI master samples SIN in Modified Transfer Format. This field is valid only when CPHA bit in CTAR register is 0.
	00 0 system clocks between SCK edge and SIN sample
	01 1 system clock between SCK edge and SIN sample
	<ul><li>10 2 system clocks between SCK edge and SIN sample</li><li>11 Reserved</li></ul>
7–2 Reserved	This read-only field is reserved and always has the value zero.
1 Reserved	This read-only field is reserved and always has the value zero.
0 HALT	Halt
	Starts and stops DSPI transfers.
	0 Start transfers.
	1 Stop transfers.



## 47.3.2 DSPI Transfer Count Register (SPIx\_TCR)

TCR contains a counter that indicates the number of SPI transfers made. The transfer counter is intended to assist in queue management. Do not write the TCR when the DSPI is in the Running state.





#### SPIx\_TCR field descriptions

Field	Description
31–16 SPI_TCNT	SPI Transfer Counter  Counts the number of SPI transfers the DSPI makes. The SPI_TCNT field increments every time the last bit of a SPI frame is transmitted. A value written to SPI_TCNT presets the counter to that value. SPI_TCNT is reset to zero at the beginning of the frame when the CTCNT field is set in the executing SPI command. The Transfer Counter wraps around; incrementing the counter past 65535 resets the counter to zero.
15–0 Reserved	This read-only field is reserved and always has the value zero.

# 47.3.3 DSPI Clock and Transfer Attributes Register (In Master Mode) (SPIx\_CTARn)

CTAR registers are used to define different transfer attributes. The number of CTAR registers is parameterized in the RTL and can be from two to eight registers. Do not write to the CTAR registers while the DSPI is in the Running state.

In master mode, the CTAR registers define combinations of transfer attributes such as frame size, clock phase and polarity, data bit ordering, baud rate, and various delays. In slave mode, a subset of the bitfields in CTARO are used to set the slave transfer attributes.

When the DSPI is configured as an SPI master, the CTAS field in the command portion of the TX FIFO entry selects which of the CTAR register is used. When the DSPI is configured as an SPI bus slave, the CTAR0 register is used.



Addresses: SPI0\_CTAR0 is 4002\_C000h base + Ch offset = 4002\_C00Ch


SPI0\_CTAR1 is 4002\_C000h base + 10h offset = 4002\_C010h

SPI1\_CTAR0 is 4002\_D000h base + Ch offset = 4002\_D00Ch

SPI1\_CTAR1 is 4002\_D000h base + 10h offset = 4002\_D010h

SPI2\_CTAR0 is 400A\_C000h base + Ch offset = 400A\_C00Ch

SPI2\_CTAR1 is 400A\_C000h base + 10h offset = 400A\_C010h



## SPIx\_CTARn field descriptions

Field	Description			
31 DBR	master mode. It effectivel division ratios for the Seri Serial Communications C	nd rate of the Serial Communic y halves the Baud Rate division ial Communications Clock (SC Block (SCK) depends on the va following table. See the BR fie	on ratio, supporting fas CK). When the DBR bit alue in the Baud Rate	ster frequencies, and ode t is set, the duty cycle of Prescaler and the Clock
		Table 47-32. DSP	I SCK Duty Cyc	ele
	DBR	СРНА	PBR	SCK Duty Cycle
	0	any	any	50/50
	1	0	00	50/50
	1	0	01	33/66
	1	0	01 10	33/66 40/60
	1 1 1			
	1 1 1	0	10	40/60
	1 1 1 1	0	10	40/60 43/57
	1 1 1 1 1	0 0 1	10 11 00	40/60 43/57 50/50

Table continues on the next page...

The baud rate is doubled with the duty cycle depending on the Baud Rate Prescaler.



#### wemory Map/Register Definition

# SPIx\_CTARn field descriptions (continued)

Field	Description
30–27	Frame Size
FMSZ	The number of bits transferred per frame is equal to the FMSZ field value plus 1. The minimum valid FMSZ field value is 3.
26 CPOL	Clock Polarity
OI OL	Selects the inactive state of the Serial Communications Clock (SCK). This bit is used in both master and slave mode. For successful communication between serial devices, the devices must have identical clock polarities. When the Continuous Selection Format is selected, switching between clock polarities without stopping the DSPI can cause errors in the transfer due to the peripheral device interpreting the switch of clock polarity as a valid clock edge.
	0 The inactive state value of SCK is low.
	1 The inactive state value of SCK is high.
25	Clock Phase
СРНА	Selects which edge of SCK causes data to change and which edge causes data to be captured. This bit is used in both master and slave mode. For successful communication between serial devices, the devices must have identical clock phase settings. In Continuous SCK mode, the bit value is ignored and the transfers are done as if the CPHA bit is set to 1.
	0 Data is captured on the leading edge of SCK and changed on the following edge.
	1 Data is changed on the leading edge of SCK and captured on the following edge.
24 LSBFE	LBS First  Specifies whether the LSB or MSB of the frame is transferred first.
	Data is transferred MSB first.     Data is transferred LSB first.
23–22	
PCSSCK	PCS to SCK Delay Prescaler  Selects the prescaler value for the delay between assertion of PCS and the first edge of the SCK. See the CSSCK field description for information on how to compute the PCS to SCK Delay. Refer PCS to SCK Delay (t <sub>CSC</sub> ) for more details.
	00 PCS to SCK Prescaler value is 1.
	01 PCS to SCK Prescaler value is 3.
	10 PCS to SCK Prescaler value is 5.
	11 PCS to SCK Prescaler value is 7.
21–20 PASC	After SCK Delay Prescaler
1 7.00	Selects the prescaler value for the delay between the last edge of SCK and the negation of PCS. See the ASC field description for information on how to compute the After SCK Delay.Refer After SCK Delay (t <sub>ASC</sub> ) for more details.
	00 Delay after Transfer Prescaler value is 1.
	01 Delay after Transfer Prescaler value is 3.
	10 Delay after Transfer Prescaler value is 5.
	11 Delay after Transfer Prescaler value is 7.
19–18 PDT	Delay after Transfer Prescaler



# SPIx\_CTARn field descriptions (continued)

Field	Description		
	Selects the prescaler value for the delay between the negation of the PCS signal at the end of a frame and the assertion of PCS at the beginning of the next frame. The PDT field is only used in master mode. See the DT field description for details on how to compute the Delay after Transfer. Refer Delay after Transfer (t <sub>DT</sub> ) for more details.		
	00 Delay after Transfer Prescaler value is 1.		
	01 Delay after Transfer Prescaler value is 3.		
	10 Delay after Transfer Prescaler value is 5.		
17–16	11 Delay after Transfer Prescaler value is 7.  Baud Rate Prescaler		
PBR	Selects the prescaler value for the baud rate. This field is used only in master mode. The baud rate is th frequency of the SCK. The system clock is divided by the prescaler value before the baud rate selection takes place. See the BR field description for details on how to compute the baud rate.  00 Baud Rate Prescaler value is 2.		
	01 Baud Rate Prescaler value is 3.		
	10 Baud Rate Prescaler value is 5.  11 Baud Rate Prescaler value is 7.		
CSSCK	Selects the scaler value for the PCS to SCK delay. Th SCK Delay is the delay between the assertion of PCS		
OGGOIX		and the first edge of the SCK. The delay is a laccording to the following equation:	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values.	and the first edge of the SCK. The delay is a laccording to the following equation:	
OGGOIX	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values. <b>Table 47-33. Dela</b>	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values.  Table 47-33. Dela  Field Value	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed t <sub>CSC</sub> = (1/f <sub>SYS</sub> ) x PCSSCK x CSSCK  The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8  16	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010  0011  0100	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8  16  32	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed t <sub>CSC</sub> = (1/f <sub>SYS</sub> ) x PCSSCK x CSSCK  The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010  0010  0100  0101	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8  16  32  64	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed t <sub>CSC</sub> = (1/f <sub>SYS</sub> ) x PCSSCK x CSSCK  The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010  0110  0100  0101	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8  16  32  64  128	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed $t_{CSC} = (1/f_{SYS}) \times PCSSCK \times CSSCK$ The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010  0110  0110  0111	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8  16  32  64  128  256	
COCOIN	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed t <sub>CSC</sub> = (1/f <sub>SYS</sub> ) x PCSSCK x CSSCK  The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010  0010  0110  0110  0111  1000	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8  16  32  64  128  256  512	
	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed t <sub>CSC</sub> = (1/f <sub>SYS</sub> ) x PCSSCK x CSSCK  The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010  0010  0110  0110  0111  1000  1001	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2  4  8  16  32  64  128  256  512  1024	
	SCK Delay is the delay between the assertion of PCS multiple of the system clock period, and it is computed t <sub>CSC</sub> = (1/f <sub>SYS</sub> ) x PCSSCK x CSSCK  The following table lists the delay scaler values.  Table 47-33. Dela  Field Value  0000  0001  0010  0011  0100  0111  1000  1001  1001	and the first edge of the SCK. The delay is a laccording to the following equation:  y Scaler Encoding  Delay Scaler Value  2 4 8 16 32 64 128 256 512 1024 2048	



#### wemory Map/Register Definition

# SPIx\_CTARn field descriptions (continued)

Field	Description			
	Table 47-33. Delay Sca	ler Encoding (continued)		
	Field Value	Delay Scaler Value		
	1110	32768		
	1111	65536		
	Refer PCS to SCK Delay (t <sub>CSC</sub> ) for more details.			
11–8	After SCK Delay Scaler			
Selects the scaler value for the After SCK Delay. This field is used only in master mode. Delay is the delay between the last edge of SCK and the negation of PCS. The delay is a system clock period, and it is computed according to the following equation:		the negation of PCS. The delay is a multiple of the		
	$t_{ASC} = (1/f_{SYS}) \times PASC \times ASC$			
	See Delay Scaler Encoding table in CTARn[CSSCK] bit field description for scaler values. Refer After SCK Delay (t <sub>ASC</sub> ) for more details.			
7–4	Delay After Transfer Scaler			
Selects the Delay after Transfer Scaler. This field is used only in master mode. The De the time between the negation of the PCS signal at the end of a frame and the assertio beginning of the next frame.				
	In the Continuous Serial Communications Clock operation, the DT value is fixed to one SCK clock period, The Delay after Transfer is a multiple of the system clock period, and it is computed according to the following equation:			
	$t_{DT} = (1/f_{SYS}) \times PDT \times DT$			
	See Delay Scaler Encoding table in CTARn[CSSCK]	bit field description for scaler values.		
3–0	Baud Rate Scaler			
Selects the scaler value for the baud rate. This field is used only in master mode. The clock is divided by the Baud Rate Scaler to generate the frequency of the SCK. The computed according to the following equation:				
	SCK baud rate = (f <sub>SYS</sub> /PBR) x [(1+DBR)/BR]			
	The following table lists the baud rate scaler values.			
	Table 47-34. DSPI Baud Rate Scaler			
	CTARn[BR]	Baud Rate Scaler Value		
	0000	2		
	0001	4		
	0010	6		
	0011	8		
	0100	16		
	0101	32		
	0110	64		
	11			




## SPIx\_CTARn field descriptions (continued)

Field	Des	cription
	Table 47-34. DSPI Ba	ud Rate Scaler (continued)
	CTARn[BR]	Baud Rate Scaler Value
	1000	256
	1001	512
	1010	1024
	1011	2048
	1100	4096
	1101	8192
	1110	16384
	1111	32768

# 47.3.4 DSPI Clock and Transfer Attributes Register (In Slave Mode) (SPIx\_CTAR\_SLAVE)

When the DSPI is configured as an SPI bus slave, the CTAR0 register is used.

Addresses: SPI0\_CTAR0\_SLAVE is 4002\_C000h base + Ch offset = 4002\_C00Ch SPI1\_CTAR0\_SLAVE is 4002\_D000h base + Ch offset = 4002\_D00Ch SPI2\_CTAR0\_SLAVE is 400A\_C000h base + Ch offset = 400A\_C00Ch



## SPIx\_CTARn\_SLAVE field descriptions

Field	Description
31–27 FMSZ	Frame Size  The number of bits transferred per frame is equal to the FMSZ field value plus 1. The minimum valid FMSZ field value is 3.
26 CPOL	Clock Polarity  Selects the inactive state of the Serial Communications Clock (SCK).  The inactive state value of SCK is low.  The inactive state value of SCK is high.
25 CPHA	Clock Phase



#### wemory Map/Register Definition


#### SPIx\_CTARn\_SLAVE field descriptions (continued)

Field	Description	
	Selects which edge of SCK causes data to change and which edge causes data to be captured. This bit is used in both master and slave mode. For successful communication between serial devices, the devices must have identical clock phase settings. In Continuous SCK mode, the bit value is ignored and the transfers are done as the CPHA bit is set to 1.  O Data is captured on the leading edge of SCK and changed on the following edge.  Data is changed on the leading edge of SCK and captured on the following edge.	
24–23 Reserved	This read-only field is reserved and always has the value zero.	
22–0 Reserved	This read-only field is reserved and always has the value zero.	

## 47.3.5 DSPI Status Register (SPIx\_SR)

SR contains status and flag bits. The bits reflect the status of the DSPI and indicate the occurrence of events that can generate interrupt or DMA requests. Software can clear flag bits in the SR by writing a 1 to them. Writing a 0 to a flag bit has no effect. This register may not be writable in module disable mode due to the use of power saving mechanisms.

Addresses: SPI0\_SR is 4002\_C000h base + 2Ch offset = 4002\_C02Ch SPI1\_SR is 4002\_D000h base + 2Ch offset = 4002\_D02Ch SPI2\_SR is 400A\_C000h base + 2Ch offset = 400A\_C02Ch



<sup>\*</sup> Notes:

• TFFF bitfield: Depends on MCR[MDIS] bit. See bit description for more details.



# SPIx\_SR field descriptions

Field	Description
31	Transfer Complete Flag
TCF	Indicates that all bits in a frame have been shifted out. TCF remains set until it is cleared by writing a 1 to it.
	<ul><li>0 Transfer not complete.</li><li>1 Transfer complete.</li></ul>
30	TX and RX Status
TXRXS	Reflects the run status of the DSPI.
	0 Transmit and receive operations are disabled (DSPI is in stopped state).
	1 Transmit and receive operations are enabled (DSPI is in running state).
29 Reserved	This read-only field is reserved and always has the value zero.
28 EOQF	End of Queue Flag
20 4.	Indicates that the last entry in a queue has been transmitted when the DSPI is in master mode. The EOQF bit is set when the TX FIFO entry has the EOQ bit set in the command halfword and the end of the transfer is reached. The EOQF bit remains set until cleared by writing a 1 to it. When the EOQF bit is set, the TXRXS bit is automatically cleared.
	<ul><li>EOQ is not set in the executing command.</li><li>EOQ is set in the executing SPI command.</li></ul>
27 TFUF	Transmit FIFO Underflow Flag
	Indicates an underflow condition in the TX FIFO. The transmit underflow condition is detected only for DSPI blocks operating in slave mode and SPI configuration. TFUF is set when the TX FIFO of a DSPI operating in SPI slave mode is empty and an external SPI master initiates a transfer. The TFUF bit remains set until cleared by writing 1 to it.
	No Tx FIFO underflow.     Tx FIFO underflow has occurred.
26 Reserved	This read-only field is reserved and always has the value zero.
25 TFFF	Transmit FIFO Fill Flag
	Provides a method for the DSPI to request more entries to be added to the TX FIFO. The TFFF bit is set while the TX FIFO is not full. The TFFF bit can be cleared by writing 1 to it or by acknowledgement from the DMA controller to the TX FIFO full request. The Reset Value of this bit is 0 if MCR[MDIS] = 1. The Reset Value of this bit is 1 if MCR[MDIS] = 0.
	0 Tx FIFO is full. 1 Tx FIFO is not full.
24 Reserved	This read-only field is reserved and always has the value zero.
23 Reserved	This read-only field is reserved and always has the value zero.
22 Reserved	This read-only field is reserved and always has the value zero.



#### wemory Map/Register Definition

# SPIx\_SR field descriptions (continued)


Field	Description							
21 Reserved	This read-only field is reserved and always has the value zero.							
20 Reserved	This read-only field is reserved and always has the value zero.							
19 RFOF	Receive FIFO Overflow Flag  Indicates an overflow condition in the RX FIFO. The bit is set when the RX FIFO and shift register are full and a transfer is initiated. The bit remains set until it is cleared by writing a 1 to it.  O No Rx FIFO overflow.  Rx FIFO overflow has occurred.							
18 Reserved	This read-only field is reserved and always has the value zero.							
17 RFDF	Provides a method for the DSPI to request that entries be removed from the RX FIFO. The bit is set while the RX FIFO is not empty. The RFDF bit can be cleared by writing 1 to it or by acknowledgement from the DMA controller when the RX FIFO is empty.  O Rx FIFO is empty.  Rx FIFO is not empty.							
16 Reserved	This read-only field is reserved and always has the value zero.							
15–12 TXCTR	TX FIFO Counter  Indicates the number of valid entries in the TX FIFO. The TXCTR is incremented every time the PUSHR is written. The TXCTR is decremented every time a SPI command is executed and the SPI data is transferred to the shift register.							
11–8 TXNXTPTR	Transmit Next Pointer  Indicates which TX FIFO Entry is transmitted during the next transfer. The TXNXTPTR field is updated every time SPI data is transferred from the TX FIFO to the shift register.							
7–4 RXCTR	RX FIFO Counter  Indicates the number of entries in the RX FIFO. The RXCTR is decremented every time the POPR is read. The RXCTR is incremented every time data is transferred from the shift register to the RX FIFO.							
3–0 POPNXTPTR	Pop Next Pointer  Contains a pointer to the RX FIFO entry to be returned when the POPR is read. The POPNXTPTR is updated when the POPR is read.							



# 47.3.6 DSPI DMA/Interrupt Request Select and Enable Register (SPIx\_RSER)

RSER controls DMA and interrupt requests. Do not write to the RSER while the DSPI is in the Running state.

Addresses: SPI0\_RSER is 4002\_C000h base + 30h offset = 4002\_C030h SPI1\_RSER is 4002\_D000h base + 30h offset = 4002\_D030h SPI2\_RSER is 400A\_C000h base + 30h offset = 400A\_C030h



## SPIx\_RSER field descriptions

Field	Description							
31 TCF_RE	Transmission Complete Request Enable							
	Enables TCF flag in the SR to generate an interrupt request.							
	0 TCF interrupt requests are disabled.							
	1 TCF interrupt requests are enabled.							
30 Reserved	This read-only field is reserved and always has the value zero.							
29 Reserved	This read-only field is reserved and always has the value zero.							
28	DSPI Finished Request Enable							
EOQF_RE	Enables the EOQF flag in the SR to generate an interrupt request.							
	0 EOQF interrupt requests are disabled.							
	1 EOQF interrupt requests are enabled.							
27 TFUF_RE	Transmit FIFO Underflow Request Enable							
	Enables the TFUF flag in the SR to generate an interrupt request.							
	0 TFUF interrupt requests are disabled.							
	1 TFUF interrupt requests are enabled.							



#### wemory Map/Register Definition

# SPIx\_RSER field descriptions (continued)

Field	Description						
26 Reserved	This read-only field is reserved and always has the value zero.						
25 TFFF_RE	Transmit FIFO Fill Request Enable						
	Enables the TFFF flag in the SR to generate a request. The TFF_DIRS bit selects between generating an interrupt request or a DMA request.						
	<ul><li>0 TFFF interrupts or DMA requests are disabled.</li><li>1 TFFF interrupts or DMA requests are enabled.</li></ul>						
24 TFFF_DIRS	Transmit FIFO Fill DMA or Interrupt Request Select						
TTT _BIIIO	Selects between generating a DMA request or an interrupt request. When the TFFF flag bit in the SR is set and the TFFF_RE bit in the RSER register is set, this bit selects between generating an interrupt request or a DMA request.						
	TFFF flag generates interrupt requests.     TFFF flag generates DMA requests.						
23 Reserved	This read-only field is reserved and always has the value zero.						
22 Reserved	This read-only field is reserved and always has the value zero.						
21 Reserved	This read-only field is reserved and always has the value zero.						
20 Reserved	This read-only field is reserved and always has the value zero.						
19 RFOF_RE	Receive FIFO Overflow Request Enable						
	Enables the RFOF flag in the SR to generate an interrupt request.						
	0 RFOF interrupt requests are disabled.						
	1 RFOF interrupt requests are enabled.						
18 Reserved	This read-only field is reserved and always has the value zero.						
17 RFDF_RE	Receive FIFO Drain Request Enable						
THE DI _NE	Enables the RFDF flag in the SR to generate a request. The RFDF_DIRS bit selects between generating an interrupt request or a DMA request.						
	0 RFDF interrupt or DMA requests are disabled						
	1 RFDF interrupt or DMA requests are enabled						
16 RFDF_DIRS	Receive FIFO Drain DMA or Interrupt Request Select.						
21 _51110	Selects between generating a DMA request or an interrupt request. When the RFDF flag bit in the SR is set, and the RFDF_RE bit in the RSER is set, the RFDF_DIRS bit selects between generating an interrupt request or a DMA request.						
	0 Interrupt request. 1 DMA request.						




### SPIx\_RSER field descriptions (continued)

Field	Description
15–0 Reserved	This read-only field is reserved and always has the value zero.

## 47.3.7 DSPI PUSH TX FIFO Register In Master Mode (SPIx\_PUSHR)

PUSHR provides the means to write to the TX FIFO. Data written to this register is transferred to the TX FIFO. Eight- or sixteen-bit write accesses to the PUSHR transfer all 32 register bits to the TX FIFO. The register structure is different in master and slave modes. In master mode the register provides 16-bit command and 16-bit data to the TX FIFO. In slave mode all 32 register bits can be used as data, supporting up to 32-bit SPI frame operation.

Addresses: SPI0\_PUSHR is 4002\_C000h base + 34h offset = 4002\_C034h SPI1\_PUSHR is 4002\_D000h base + 34h offset = 4002\_D034h SPI2\_PUSHR is 400A\_C000h base + 34h offset = 400A\_C034h



### SPIx\_PUSHR field descriptions

Field	Description							
31 CONT	Continuous Peripheral Chip Select Enable							
33111	Selects a Continuous Selection Format. The bit is used in SPI master mode. The bit enables the selected PCS signals to remain asserted between transfers.							
	Return PCSn signals to their inactive state between transfers.      Keep BCSn signals accounted between transfers.							
	1 Keep PCSn signals asserted between transfers.							
30–28	Clock and Transfer Attributes Select.							
CTAS	Selects which CTAR register to use in master mode to specify the transfer attributes for the associated SPI frame. In SPI slave mode, CTAR0 is used. See the Chip Configuration chapter to determine how many CTAR registers this device has. You should not program a value in this field for a register that is not present.							
	000 CTAR0							
	001 CTAR1							
	010 Reserved							
	011 Reserved							
	100 Reserved							
	101 Reserved							



#### wemory Map/Register Definition


# SPIx\_PUSHR field descriptions (continued)

Field	Description					
	110 Reserved 111 Reserved					
27 EOQ	End Of Queue  Host software uses this bit to signal to the DSPI that the current SPI transfer is the last in a queue. At the end of the transfer, the EOQF bit in the SR is set.  O The SPI data is not the last data to transfer.  1 The SPI data is the last data to transfer.					
26 CTCNT	Clear Transfer Counter.  Clears the SPI_TCNT field in the TCR register. The SPI_TCNT field is cleared before the DSPI starts transmitting the current SPI frame.  0 Do not clear the TCR[SPI_TCNT] field.  1 Clear the TCR[SPI_TCNT] field.					
25–24 Reserved	This read-only field is reserved and always has the value zero.					
23–22 Reserved	This read-only field is reserved and always has the value zero.					
21–16 PCS[5:0]	Select which PCS signals are to be asserted for the transfer. Refer to the chip configuration chapter for the number of PCS signals used in this MCU.  Negate the PCS[x] signal.  Assert the PCS[x] signal.					
15–0 TXDATA	Transmit Data  Holds SPI data to be transferred according to the associated SPI command.					



# 47.3.8 DSPI PUSH TX FIFO Register In Slave Mode (SPIx\_PUSHR\_SLAVE)

PUSHR provides the means to write to the TX FIFO. Data written to this register is transferred to the TX FIFO. Eight- or sixteen-bit write accesses to the PUSHR transfer all 32 register bits to the TX FIFO. The register structure is different in master and slave modes. In master mode the register provides 16-bit command and 16-bit data to the TX FIFO. In slave mode all 32 register bits can be used as data, supporting up to 32-bit SPI frame operation.




## SPIx\_PUSHR\_SLAVE field descriptions

Field	Description
31–0 TXDATA	Transmit Data
	Holds SPI data to be transferred according to the associated SPI command.

## 47.3.9 DSPI POP RX FIFO Register (SPIx\_POPR)

POPR is used to read the RX FIFO. Eight- or sixteen-bit read accesses to the POPR have the same effect on the RX FIFO as 32-bit read accesses. A write to this register will generate a Transfer Error.



#### memory Map/Register Definition


#### SPIx\_POPR field descriptions

Field	Description					
31–0 RXDATA	Received Data					
	Contains the SPI data from the RX FIFO entry to which the Pop Next Data Pointer points.					

## 47.3.10 DSPI Transmit FIFO Registers (SPIx\_TXFRn)

TXFRn provide visibility into the TX FIFO for debugging purposes. Each register is an entry in the TX FIFO. The registers are read-only and cannot be modified. Reading the TXFRx registers does not alter the state of the TX FIFO.

Addresses: SPI0\_TXFR0 is 4002\_C000h base + 3Ch offset = 4002\_C03Ch




#### SPIx\_TXFRn field descriptions

Field	Description					
31–16 TXCMD_ TXDATA	In master mode the TXCMD field contains the command that sets the transfer attributes for the SPI data. In slave mode, the TXDATA contains 16 MSB bits of the SPI data to be shifted out.					
15–0 TXDATA	Transmit Data  Contains the SPI data to be shifted out.					

## 47.3.11 DSPI Receive FIFO Registers (SPIx\_RXFRn)

RXFRn provide visibility into the RX FIFO for debugging purposes. Each register is an entry in the RX FIFO. The RXFR registers are read-only. Reading the RXFRx registers does not alter the state of the RX FIFO.

Addresses: SPI0\_RXFR0 is 4002\_C000h base + 7Ch offset = 4002\_C07Ch





#### SPIx\_RXFRn field descriptions

Field	Description			
31–0 RXDATA	Receive Data			
	Contains the received SPI data.			

# 47.4 Functional Description

The Serial Peripheral Interface (DSPI) block supports full-duplex, synchronous serial communications between MCUs and peripheral devices. All communications are done with SPI-like protocol.

The DSPI has the following configurations:

• SPI Configuration in which the DSPI operates as a basic SPI or a queued SPI.

The DCONF field in the DSPI Module Configuration Register (MCR) determines the DSPI Configuration. See for the DSPI configuration values.

The CTARn registers hold clock and transfer attributes. The SPI configuration allows to select which CTAR to use on a frame by frame basis by setting a field in the SPI command. See DSPI Clock and Transfer Attributes Registers for information on the fields of the CTAR registers.

Typical master to slave connections are shown in the following figure. When a data transfer operation is performed, data is serially shifted a predetermined number of bit positions. Because the modules are linked, data is exchanged between the master and the slave. The data that was in the master shift register is now in the shift register of the slave, and vice versa. At the end of a transfer, the TCF bit in the SR is set to indicate a completed transfer.




Figure 47-91. SPI Serial Protocol Overview



#### **runctional Description**

Generally more than one slave device can be connected to the DSPI master. 6 Peripheral Chip Select (PCS) signals of the DSPI masters can be used to select which of the slaves to communicate with. Refer to the chip configuration chapter for the number of PCS signals used in this MCU.

The three DSPI configurations share transfer protocol and timing properties which are described independently of the configuration in Transfer Formats. The transfer rate and delay settings are described in DSPI Baud Rate and Clock Delay Generation.

## 47.4.1 Start and Stop of DSPI Transfers

The DSPI has two operating states: STOPPED and RUNNING. The states are independent of DSPI configuration. The default state of the DSPI is STOPPED. In the STOPPED state no serial transfers are initiated in master mode and no transfers are responded to in slave mode. The STOPPED state is also a safe state for writing the various configuration registers of the DSPI without causing undetermined results. In the RUNNING state serial transfers take place.

The TXRXS bit in the SR indicates what state the DSPI in. The bit is set if the module in RUNNING state.

The DSPI is started (DSPI transitions to RUNNING) when all of the following conditions are true:

- SR[EOQF] bit is clear
- MCU is not in the debug mode or the MCR[FRZ] bit is clear
- MCR[HALT] bit is clear

The DSPI stops (transitions from RUNNING to STOPPED) after the current frame when any one of the following conditions exist:

- SR[EOQF] bit is set
- MCU in the debug mode and the MCR[FRZ] bit is set
- MCR[HALT] bit is set

State transitions from RUNNING to STOPPED occur on the next frame boundary if a transfer is in progress, or immediately if no transfers are in progress.



## 47.4.2 Serial Peripheral Interface (SPI) Configuration

The SPI Configuration transfers data serially using a shift register and a selection of programmable transfer attributes. The DSPI is in SPI Configuration when the DCONF field in the MCR is 0b00. The SPI frames can be 32 bits long. The host CPU or a DMA controller transfers the SPI data from the external to DSPI RAM queues to a transmit FIFO (TX FIFO) buffer. The received data is stored in entries in the Receive FIFO (RX FIFO) buffer. The host CPU or the DMA controller transfers the received data from the RX FIFO to memory external to the DSPI. The FIFO buffers operation is described in Transmit First In First Out (TX FIFO) Buffering Mechanism, and Receive First In First Out (RX FIFO) Buffering Mechanism. The interrupt and DMA request conditions are described in Interrupts/DMA Requests.

The SPI Configuration supports two block-specific modes —master mode and slave mode. The FIFO operations are similar for both modes. The main difference is that in master mode the DSPI initiates and controls the transfer according to the fields in the SPI command field of the TX FIFO entry. In slave mode, the DSPI only responds to transfers initiated by a bus master external to the DSPI and the SPI command field space is used for 16 most significant bit of the transmit data.

#### 47.4.2.1 Master Mode

In SPI master mode the DSPI initiates the serial transfers by controlling the Serial Communications Clock (SCK) and the Peripheral Chip Select (PCS) signals. The SPI command field in the executing TX FIFO entry determines which CTAR registers will be used to set the transfer attributes and which PCS signals to assert. The command field also contains various bits that help with queue management and transfer protocol. See DSPI PUSH TX FIFO Register (PUSHR) for details on the SPI command fields. The data field in the executing TX FIFO entry is loaded into the shift register and shifted out on the Serial Out (SOUT) pin. In SPI master mode, each SPI frame to be transmitted has a command associated with it allowing for transfer attribute control on a frame by frame basis.

### 47.4.2.2 Slave Mode

In SPI slave mode the DSPI responds to transfers initiated by a SPI bus master. The DSPI does not initiate transfers. Certain transfer attributes such as clock polarity, clock phase and frame size must be set for successful communication with a SPI master. The SPI slave mode transfer attributes are set in the CTARO. The data is shifted out with MSB first. Shifting out of LSB is not supported in this mode.



## 47.4.2.3 FIFO Disable Operation

The FIFO disable mechanisms allow SPI transfers without using the TX FIFO or RX FIFO. The DSPI operates as a double-buffered simplified SPI when the FIFOs are disabled. The FIFOs are disabled separately; setting the MCR[DIS\_TXF] bit disables the TX FIFO, and setting the MCR[DIS\_RXF] bit disables the RX FIFO.

The FIFO Disable mechanisms are transparent to the user and to host software; Transmit data and commands are written to the PUSHR and received data is read from the POPR.

When the TX FIFO is disabled the TFFF, TFUF and TXCTR fields in SR behave as if there is a one-entry FIFO but the contents of the TXFR registers and TXNXTPTR are undefined. Likewise, when the RX FIFO is disabled, the RFDF, RFOF and RXCTR fields in the SR behave as if there is a one-entry FIFO, but the contents of the RXFR registers and POPNXTPTR are undefined.

## 47.4.2.4 Transmit First In First Out (TX FIFO) Buffering Mechanism

The TX FIFO functions as a buffer of SPI data and SPI commands for transmission. The TX FIFO holds 4 words, each consisting of a command field and a data field. The number of entries in the TX FIFO is device-specific. SPI commands and data are added to the TX FIFO by writing to the DSPI PUSH TX FIFO Register (PUSHR). TX FIFO entries can only be removed from the TX FIFO by being shifted out or by flushing the TX FIFO.

The TX FIFO Counter field (TXCTR) in the DSPI Status Register (SR) indicates the number of valid entries in the TX FIFO. The TXCTR is updated every time the DSPI \_PUSHR is written or SPI data is transferred into the shift register from the TX FIFO.

The TXNXTPTR field indicates which TX FIFO Entry will be transmitted during the next transfer. The TXNXTPTR contains the positive offset from TXFR0 in number of 32-bit registers. For example, TXNXTPTR equal to two means that the TXFR2 contains the SPI data and command for the next transfer. The TXNXTPTR field is incremented every time SPI data is transferred from the TX FIFO to the shift register. The maximum value of the field is equal to the maximum implemented TXFR register number and it rolls over after reaching the maximum.



### 47.4.2.4.1 Filling the TX FIFO

Host software or other intelligent blocks can add (push) entries to the TX FIFO by writing to the PUSHR. When the TX FIFO is not full, the TX FIFO Fill Flag (TFFF) in the SR is set. The TFFF bit is cleared when TX FIFO is full and the DMA controller indicates that a write to PUSHR is complete. Writing a '1' to the TFFF bit also clears it. The TFFF can generate a DMA request or an interrupt request. See Transmit FIFO Fill Interrupt or DMA Request for details.

The DSPI ignores attempts to push data to a full TX FIFO, the state of the TX FIFO does not change and no error condition is indicated.

## 47.4.2.4.2 Draining the TX FIFO

The TX FIFO entries are removed (drained) by shifting SPI data out through the shift register. Entries are transferred from the TX FIFO to the shift register and shifted out as long as there are valid entries in the TX FIFO. Every time an entry is transferred from the TX FIFO to the shift register, the TX FIFO Counter decrements by one. At the end of a transfer, the TCF bit in the SR is set to indicate the completion of a transfer. The TX FIFO is flushed by writing a '1' to the CLR\_TXF bit in MCR.

If an external bus master initiates a transfer with a DSPI slave while the slave's DSPI TX FIFO is empty, the Transmit FIFO Underflow Flag (TFUF) in the slave's SR is set. See Transmit FIFO Underflow Interrupt Request for details.

## 47.4.2.5 Receive First In First Out (RX FIFO) Buffering Mechanism

The RX FIFO functions as a buffer for data received on the SIN pin. The RX FIFO holds 4 received SPI data frames. The number of entries in the RX FIFO is device-specific. SPI data is added to the RX FIFO at the completion of a transfer when the received data in the shift register is transferred into the RX FIFO. SPI data are removed (popped) from the RX FIFO by reading the DSPI POP RX FIFO Register (POPR). RX FIFO entries can only be removed from the RX FIFO by reading the POPR or by flushing the RX FIFO.

The RX FIFO Counter field (RXCTR) in the DSPI Status Register (SR) indicates the number of valid entries in the RX FIFO. The RXCTR is updated every time the POPR is read or SPI data is copied from the shift register to the RX FIFO.

The POPNXTPTR field in the SR points to the RX FIFO entry that is returned when the POPR is read. The POPNXTPTR contains the positive offset from RXFR0 in number of 32-bit registers. For example, POPNXTPTR equal to two means that the RXFR2 contains the received SPI data that will be returned when POPR is read. The POPNXTPTR field is



#### **runctional Description**

incremented every time the POPR is read. The maximum value of the field is equal to the maximum implemented RXFR register number and it rolls over after reaching the maximum.

## 47.4.2.5.1 Filling the RX FIFO

The RX FIFO is filled with the received SPI data from the shift register. While the RX FIFO is not full, SPI frames from the shift register are transferred to the RX FIFO. Every time a SPI frame is transferred to the RX FIFO the RX FIFO Counter is incremented by one.

If the RX FIFO and shift register are full and a transfer is initiated, the RFOF bit in the SR is set indicating an overflow condition. Depending on the state of the ROOE bit in the MCR, the data from the transfer that generated the overflow is either ignored or shifted in to the shift register. If the ROOE bit is set, the incoming data is shifted in to the shift register. If the ROOE bit is cleared, the incoming data is ignored.

## 47.4.2.5.2 Draining the RX FIFO

Host CPU or a DMA can remove (pop) entries from the RX FIFO by reading the DSPI POP RX FIFO Register (POPR). A read of the POPR decrements the RX FIFO Counter by one. Attempts to pop data from an empty RX FIFO are ignored and the RX FIFO Counter remains unchanged. The data, read from the empty RX FIFO, is undetermined.

When the RX FIFO is not empty, the RX FIFO Drain Flag (RFDF) in the SR is set. The RFDF bit is cleared when the RX\_FIFO is empty and the DMA controller indicates that a read from POPR is complete or by writing a '1' to it.

## 47.4.3 DSPI Baud Rate and Clock Delay Generation

The SCK frequency and the delay values for serial transfer are generated by dividing the system clock frequency by a prescaler and a scaler with the option for doubling the baud rate. The following figure shows conceptually how the SCK signal is generated.




Figure 47-92. Communications Clock Prescalers and Scalers



#### 47.4.3.1 Baud Rate Generator

The Baud Rate is the frequency of the Serial Communication Clock (SCK). The system clock is divided by a prescaler (PBR) and scaler (BR) to produce SCK with the possibility of halving the scaler division. The DBR, PBR and BR fields in the CTAR registers select the frequency of SCK by the formula in the BR field description. The following table shows an example of how to compute the baud rate.

Table 47-106. Baud Rate Computation Example

f <sub>sys</sub>	PBR	Prescaler	BR	Scaler	DBR	Baud Rate
100 MHz	0b00	2	0b0000	2	0	25 Mb/s
20 MHz	0b00	2	0b0000	2	1	10 Mb/s

#### **NOTE**

The clock frequencies mentioned in the preceding table are given as an example. Refer to the clocking chapter for the frequency used to drive this module in the device.

## 47.4.3.2 PCS to SCK Delay (t<sub>CSC</sub>)

The PCS to SCK delay is the length of time from assertion of the PCS signal to the first SCK edge. See Figure 47-94 for an illustration of the PCS to SCK delay. The PCSSCK and CSSCK fields in the CTAR*x* registers select the PCS to SCK delay by the formula in the CSSCK field description. The following table shows an example of how to compute the PCS to SCK delay.

Table 47-107. PCS to SCK Delay Computation Example

f <sub>sys</sub>	PCSSCK	Prescaler	CSSCK	Scaler	PCS to SCK Delay
100 MHz	0b01	3	0b0100	32	0.96 µs

#### NOTE

The clock frequency mentioned in the preceding table is given as an example. Refer to the clocking chapter for the frequency used to drive this module in the device.



**runctional Description** 

## 47.4.3.3 After SCK Delay (t<sub>ASC</sub>)

The After SCK Delay is the length of time between the last edge of SCK and the negation of PCS. See Figure 47-94 and Figure 47-95 for illustrations of the After SCK delay. The PASC and ASC fields in the CTARx registers select the After SCK Delay by the formula in the ASC field description. The following table shows an example of how to compute the After SCK delay.

Table 47-108. After SCK Delay Computation Example

f <sub>sys</sub>	PASC	Prescaler	ASC	Scaler	After SCK Delay
100 MHz	0b01	3	0b0100	32	0.96 µs

#### NOTE

The clock frequency mentioned in the preceding table is given as an example. Refer to the clocking chapter for the frequency used to drive this module in the device.

## 47.4.3.4 Delay after Transfer (t<sub>DT</sub>)

The Delay after Transfer is the minimum time between negation of the PCS signal for a frame and the assertion of the PCS signal for the next frame. See Figure 47-94 for an illustration of the Delay after Transfer. The PDT and DT fields in the CTARx registers select the Delay after Transfer by the formula in the DT field description. The following table shows an example of how to compute the Delay after Transfer.

 Table 47-109.
 Delay after Transfer Computation Example

f <sub>sys</sub>	PDT	Prescaler	DT	Scaler	Delay after Transfer
100 MHz	0b01	3	0b1110	32768	0.98 ms

#### NOTE

The clock frequency mentioned in the preceding table is given as an example. Refer to the clocking chapter for the frequency used to drive this module in the device.

When in non-continuous clock mode the t<sub>DT</sub> delay is configured according to the equation specified in the CTAR[DT] bitfield description. When in continuous clock mode, the delay is fixed at 1 SCK period.



# 47.4.3.5 Peripheral Chip Select Strobe Enable (PCSS)

The PCSS signal provides a delay to allow the PCS signals to settle after a transition occurs thereby avoiding glitches. When the DSPI is in master mode and the PCSSE bit is set in the MCR,  $\overline{PCSS}$  provides a signal for an external demultiplexer to decode the PCS[0] - PCS[4] signals into as many as 128 glitch-free PCS signals. The following figure shows the timing of the  $\overline{PCSS}$  signal relative to PCS signals.




Figure 47-93. Peripheral Chip Select Strobe Timing

The delay between the assertion of the PCS signals and the assertion of  $\overline{PCSS}$  is selected by the PCSSCK field in the CTAR based on the following formula:

$$t_{\text{PCSSCK}} = \frac{1}{f_{\text{SYS}}} \times \text{PCSSCK}$$

At the end of the transfer the delay between  $\overline{PCSS}$  negation and PCS negation is selected by the PASC field in the CTAR based on the following formula:

$$t_{\text{PASC}} = \frac{1}{f_{\text{SYS}}} \times \text{PASC}$$

The following table shows an example of how to compute the  $t_{pcssck}$  delay.

Table 47-110. Peripheral Chip Select Strobe Assert Computation Example

f <sub>sys</sub>	PCSSCK	Prescaler	Delay before Transfer	
100 MHz	0b11	7	70.0 ns	

The following table shows an example of how to compute the  $t_{pasc}$  delay.

Table 47-111. Peripheral Chip Select Strobe Negate Computation Example

f <sub>sys</sub>	f <sub>sys</sub> PASC Pres		Delay after Transfer
100 MHz	0b11	7	70.0 ns

The PCSS signal is not supported when Continuous Serial Communication SCK mode are enabled.



#### **runctional Description**

#### NOTE

The clock frequency mentioned in the preceding tables is given as an example. Refer to the clocking chapter for the frequency used to drive this module in the device.

### 47.4.4 Transfer Formats

The SPI serial communication is controlled by the Serial Communications Clock (SCK) signal and the PCS signals. The SCK signal provided by the master device synchronizes shifting and sampling of the data on the SIN and SOUT pins. The PCS signals serve as enable signals for the slave devices.

In master mode, the CPOL and CPHA bits in the Clock and Transfer Attributes Registers (CTARn) select the polarity and phase of the serial clock, SCK.

- CPOL Selects the idle state polarity of the SCK
- CPHA Selects if the data on SOUT is valid before or on the first SCK edge

Even though the bus slave does not control the SCK signal, in slave mode these values must be identical to the master device settings to ensure proper transmission. In SPI slave mode, only CTAR0 is used.

The DSPI supports four different transfer formats:

- Classic SPI with CPHA=0
- Classic SPI with CPHA=1
- Modified Transfer format with CPHA = 0
- Modified Transfer format with CPHA = 1

A modified transfer format is supported to allow for high-speed communication with peripherals that require longer setup times. The DSPI can sample the incoming data later than halfway through the cycle to give the peripheral more setup time. The MTFE bit in the MCR selects between Classic SPI Format and Modified Transfer Format.

In the SPI Configurations, the DSPI provides the option of keeping the PCS signals asserted between frames. See Continuous Selection Format for details.



## 47.4.4.1 Classic SPI Transfer Format (CPHA = 0)

The transfer format shown in following figure is used to communicate with peripheral SPI slave devices where the first data bit is available on the first clock edge. In this format, the master and slave sample their SIN pins on the odd-numbered SCK edges and change the data on their SOUT pins on the even-numbered SCK edges.





Figure 47-94. DSPI Transfer Timing Diagram (MTFE=0, CPHA=0, FMSZ=8)


The master initiates the transfer by placing its first data bit on the SOUT pin and asserting the appropriate peripheral chip select signals to the slave device. The slave responds by placing its first data bit on its SOUT pin. After the tCSC delay elapses, the master outputs the first edge of SCK. The master and slave devices use this edge to sample the first input data bit on their serial data input signals. At the second edge of the SCK the master and slave devices place their second data bit on their serial data output signals. For the rest of the frame the master and the slave sample their SIN pins on the odd-numbered clock edges and changes the data on their SOUT pins on the even-numbered clock edges. After the last clock edge occurs a delay of  $t_{\rm ASC}$  is inserted before the master negates the PCS signals. A delay of  $t_{\rm DT}$  is inserted before a new frame transfer can be initiated by the master.



unctional Description

#### Classic SPI Transfer Format (CPHA = 1) 47.4.4.2

This transfer format shown in the following figure is used to communicate with peripheral SPI slave devices that require the first SCK edge before the first data bit becomes available on the slave SOUT pin. In this format the master and slave devices change the data on their SOUT pins on the odd-numbered SCK edges and sample the data on their SIN pins on the even-numbered SCK edges



t<sub>ASC -</sub> After SCK delay

tDT = Delay after Transfer (minimum CS negation time)

Figure 47-95. DSPI Transfer Timing Diagram (MTFE=0, CPHA=1, FMSZ=8)

The master initiates the transfer by asserting the PCS signal to the slave. After the  $t_{CSC}$ delay has elapsed, the master generates the first SCK edge and at the same time places valid data on the master SOUT pin. The slave responds to the first SCK edge by placing its first data bit on its slave SOUT pin.


At the second edge of the SCK the master and slave sample their SIN pins. For the rest of the frame the master and the slave change the data on their SOUT pins on the oddnumbered clock edges and sample their SIN pins on the even-numbered clock edges. After the last clock edge occurs a delay of t<sub>ASC</sub> is inserted before the master negates the PCS signal. A delay of t<sub>DT</sub> is inserted before a new frame transfer can be initiated by the master.



#### 47.4.4.3 Continuous Selection Format

Some peripherals must be deselected between every transfer. Other peripherals must remain selected between several sequential serial transfers. The Continuous Selection Format provides the flexibility to handle the following case. The Continuous Selection Format is enabled for the SPI Configuration by setting the CONT bit in the SPI command. The behavior of the PCS signals in the configurations is identical so only SPI Configuration will be described.

When the CONT bit = 0, the DSPI drives the asserted Chip Select signals to their idle states in between frames. The idle states of the Chip Select signals are selected by the PCSISn bits in the MCR. The following timing diagram is for two four-bit transfers with CPHA = 1 and CONT = 0.



t<sub>CSC</sub> = PCS to SCK dela

Figure 47-96. Example of Non-Continuous Format (CPHA=1, CONT=0)

When the CONT bit = 1, the PCS signal remains asserted for the duration of the two transfers. The Delay between Transfers ( $t_{\rm DT}$ ) is not inserted between the transfers. The following figure shows the timing diagram for two four-bit transfers with CPHA = 1 and CONT = 1.

 $<sup>^{</sup>t}$  ASC = After SCK delay  $^{t}$  DT = Delay after Transfer (minimum CS negation time)






Figure 47-97. Example of Continuous Transfer (CPHA=1, CONT=1)

When using DSPI with continuous selection follow these rules:

- All transmit commands must have the same PCSn bits programming.
- The CTARs, selected by transmit commands, must be programmed with the same transfer attributes. Only FMSZ field can be programmed differently in these CTARs.
- When transmitting multiple frames in this mode, the user software must ensure that the last frame has the PUSHR[CONT] bit de-asserted (in master mode) and the user software must provide sufficient frames in the TX\_FIFO to be sent out (in slave mode) and the master de-asserts the PCSn at end of transmission of last frame.
- The PUSHR[CONT] / DSICR0[DCONT] bits must be de-asserted before asserting MCR[HALT] bit (in master mode). This will make sure that the PCSn signals are de-asserted. Asserting MCR[HALT] bit during continuous transfer will cause the PCSn signals to remain asserted and hence Slave Device cannot transition from RUNNING to STOPPED state.

#### **NOTE**

User must fill the TXFIFO with the number of entries that will be concatenated together under one PCS assertion for both master and slave before the TXFIFO becomes empty.

When operating in slave mode, ensure that when the last-entry in the TXFIFO is completely transmitted (that is the corresponding TCF flag is asserted and TXFIFO is empty), the slave is deselected for any further serial communication; otherwise, an underflow error occurs.



## 47.4.5 Continuous Serial Communications Clock

The DSPI provides the option of generating a continuous SCK signal for slave peripherals that require a continuous clock.

Continuous SCK is enabled by setting the CONT\_SCKE bit in the MCR. Enabling this bit generates the Continuous Serial Communications Clock regardless of the MCR[HALT] bit status.. Continuous SCK is valid in all configurations.

Continuous SCK is only supported for CPHA=1. Clearing CPHA is ignored if the CONT\_SCKE bit is set. Continuous SCK is supported for Modified Transfer Format.

Clock and transfer attributes for the Continuous SCK mode are set according to the following rules:

- When the DSPI is in SPI configuration, CTAR0 is used initially. At the start of each SPI frame transfer, the CTAR specified by the CTAS for the frame is used.
- In all configurations, the currently selected CTAR remains in use until the start of a frame with a different CTAR specified, or the Continuous SCK mode is terminated.

It is recommended to keep the baud rate the same while using the Continuous SCK. Switching clock polarity between frames while using Continuous SCK can cause errors in the transfer. Continuous SCK operation is not guaranteed if the DSPI is put into the External Stop mode or Module Disable mode.

Enabling Continuous SCK disables the PCS to SCK delay and the Delay after Transfer (t<sub>DT</sub>) is fixed to one SCK cycle. The following figure is the timing diagram for Continuous SCK format with Continuous Selection disabled.

#### **NOTE**

When in Continuous SCK mode, for the SPI transfer CTAR0 should always be used, and the TXFIFO must be cleared using the MCR[CLR\_TXF] field before initiating transfer.

#### runctional Description




Figure 47-98. Continuous SCK Timing Diagram (CONT=0)

If the CONT bit in the TX FIFO entry is set, PCS remains asserted between the transfers. Under certain conditions, SCK can continue with PCS asserted, but with no data being shifted out of SOUT (SOUT pulled high). This can cause the slave to receive incorrect data. Those conditions include:

- Continuous SCK with CONT bit set, but no data in the transmit FIFO.
- Continuous SCK with CONT bit set and entering STOPPED state (refer to Start and Stop of DSPI Transfers).
- Continuous SCK with CONT bit set and entering Stop mode or Module Disable mode.

The following figure shows timing diagram for Continuous SCK format with Continuous Selection enabled.




Figure 47-99. Continuous SCK Timing Diagram (CONT=1)



## 47.4.6 Slave Mode Operation Constraints

Slave mode logic shift register is buffered. This allows data streaming operation, when the DSPI is permanently selected and data is shifted in with a constant rate.

The transmit data is transferred at second SCK clock edge of the each frame to the shift register if the  $\overline{SS}$  signal is asserted and any time when transmit data is ready and  $\overline{SS}$  signal is negated.

Received data is transferred to the receive buffer at last SCK edge of each frame, defined by frame size programmed to the CTAR0/1 register. Then the data from the buffer is transferred to the RXFIFO or DDR register.

If the  $\overline{SS}$  negates before that last SCK edge, the data from shift register is lost.

This buffering scheme allows to operate slave clock with higher frequency than the system frequency. The clocks relationship is defined by the following equation. *FrameSize* is the value of the CTAR0/1[FMSZ] field plus one.

$$f_{\text{SCK}} < f_{\text{SYS}} \times \text{FrameSize/3}$$

## 47.4.7 Interrupts/DMA Requests

The DSPI has several conditions that can only generate interrupt requests and two conditions that can generate interrupt or DMA requests. The following table lists these conditions.

Condition	Flag	Interrupt	DMA
End of Queue (EOQ)	EOQF	Yes	
TX FIFO Fill	TFFF	Yes	Yes
Transfer Complete	TCF	Yes	
TX FIFO Underflow	TFUF	Yes	
RX FIFO Drain	RFDF	Yes	Yes
RX FIFO Overflow	RFOF	Yes	

Table 47-112. Interrupt and DMA Request Conditions

Each condition has a flag bit in the DSPI Status Register (SR) and an Request Enable bit in the DSPI DMA/Interrupt Request Select and Enable Register (RSER). The TX FIFO Fill Flag (TFFF) and RX FIFO Drain Flag (RFDF) generate interrupt requests or DMA requests depending on the TFFF\_DIRS and RFDF\_DIRS bits in the RSER.

The DSPI module also provides a global interrupt request line, which is asserted when any of individual interrupt requests lines is asserted.



## 47.4.7.1 End of Queue Interrupt Request

The End of Queue Request indicates that the end of a transmit queue is reached. The End of Queue Request is generated when the EOQ bit in the executing SPI command is set and the EOQF\_RE bit in the RSER is set.

#### **NOTE**

This interrupt request is generated when the last bit of the SPI frame with EOQ bit set is transmitted.

## 47.4.7.2 Transmit FIFO Fill Interrupt or DMA Request

The Transmit FIFO Fill Request indicates that the TX FIFO is not full. The Transmit FIFO Fill Request is generated when the number of entries in the TX FIFO is less than the maximum number of possible entries, and the TFFF\_RE bit in the RSER is set. The TFFF\_DIRS bit in the RSER selects whether a DMA request or an interrupt request is generated.

#### NOTE

TFFF flag clears automatically when DMA is used to fill TXFIFO.

To clear TFFF when not using DMA, follow these steps for every PUSH performed using CPU to fill TXFIFO:

- 1. Wait until TFFF = 1
- 2. Write data to PUSHR using CPU.
- 3. Clear TFFF by writing a 1 to its location. If FIFO is not full, this flag will not clear.

## 47.4.7.3 Transfer Complete Interrupt Request

The Transfer Complete Request indicates the end of the transfer of a serial frame. The Transfer Complete Request is generated at the end of each frame transfer when the TCF\_RE bit is set in the RSER.



## 47.4.7.4 Transmit FIFO Underflow Interrupt Request

The Transmit FIFO Underflow Request indicates that an underflow condition in the TX FIFO has occurred. The transmit underflow condition is detected only for the DSPI, operating in slave mode and SPI configuration. The TFUF bit is set when the TX FIFO of a DSPI is empty, and a transfer is initiated from an external SPI master. If the TFUF bit is set while the TFUF\_RE bit in the RSER is set, an interrupt request is generated.

## 47.4.7.5 Receive FIFO Drain Interrupt or DMA Request

The Receive FIFO Drain Request indicates that the RX FIFO is not empty. The Receive FIFO Drain Request is generated when the number of entries in the RX FIFO is not zero, and the RFDF\_RE bit in the RSER is set. The RFDF\_DIRS bit in the RSER selects whether a DMA request or an interrupt request is generated.

## 47.4.7.6 Receive FIFO Overflow Interrupt Request

The Receive FIFO Overflow Request indicates that an overflow condition in the RX FIFO has occurred. A Receive FIFO Overflow request is generated when RX FIFO and shift register are full and a transfer is initiated. The RFOF\_RE bit in the RSER must be set for the interrupt request to be generated.

Depending on the state of the ROOE bit in the MCR, the data from the transfer that generated the overflow is either ignored or shifted in to the shift register. If the ROOE bit is set, the incoming data is shifted in to the shift register. If the ROOE bit is cleared, the incoming data is ignored.

## 47.4.8 Power Saving Features

The DSPI supports following power-saving strategies:

- External Stop mode
- Module Disable mode Clock gating of non-memory mapped logic

mualization/Application Information

## 47.4.8.1 Stop Mode (External Stop Mode)

The DSPI supports the stop mode protocol. When a request is made to enter external stop mode, the DSPI block acknowledges the request. If a serial transfer is in progress, the DSPI waits until it reaches the frame boundary before it is ready to have its clocks shut off. While the clocks are shut off, the DSPI memory-mapped logic is not accessible. The states of the interrupt and DMA request signals cannot be changed while in External Stop mode.

#### 47.4.8.2 Module Disable Mode

Module disable mode is a block-specific mode that the DSPI can enter to save power. Host CPU can initiate the module disable mode by setting the MDIS bit in the MCR. The module disable mode can also be initiated by hardware. A power management block can initiate the module disable mode by asserting the DOZE mode signal while the DOZE bit in the MCR is set.

When the MDIS bit is set or the DOZE mode signal is asserted while the DOZE bit is set, the DSPI negates Clock Enable signal at the next frame boundary. If implemented, the Clock Enable signal can stop the clock to the non-memory mapped logic. When Clock Enable is negated, the DSPI is in a dormant state, but the memory mapped registers are still accessible. Certain read or write operations have a different effect when the DSPI is in the module disable mode. Reading the RX FIFO Pop Register does not change the state of the RX FIFO. Likewise, writing to the TX FIFO Push Register does not change the state of the TX FIFO. Clearing either of the FIFOs has no effect in the module disable mode. Changes to the DIS\_TXF and DIS\_RXF fields of the MCR have no effect in the module disable mode. In the module disable mode, all status bits and register flags in the DSPI return the correct values when read, but writing to them has no effect. Writing to the TCR during module disable mode has no effect. Interrupt and DMA request signals cannot be cleared while in the module disable mode.

## 47.5 Initialization/Application Information

This section describes how to initialize the DSPI module.

## 47.5.1 How to Manage DSPI Queues

The queues are not part of the DSPI, but the DSPI includes features in support of queue management. Queues are primarily supported in SPI Configuration.



- 1. When DSPI executes last command word from a queue, the EOQ bit in the command word is set to indicate to the DSPI that this is the last entry in the queue.
- 2. At the end of the transfer, corresponding to the command word with EOQ set is sampled, the EOQ flag (EOQF) in the SR is set.
- 3. The setting of the EOQF flag disables serial transmission and reception of data, putting the DSPI in the STOPPED state. The TXRXS bit is cleared to indicate the STOPPED state.
- 4. The DMA can continue to fill TX FIFO until it is full or step 5 occurs.
- 5. Disable DSPI DMA transfers by disabling the DMA enable request for the DMA channel assigned to TX FIFO and RX FIFO. This is done by clearing the corresponding DMA enable request bits in the DMA Controller.
- 6. Ensure all received data in RX FIFO has been transferred to memory receive queue by reading the RXCNT in SR or by checking RFDF in the SR after each read operation of the POPR.
- 7. Modify DMA descriptor of TX and RX channels for new queues
- 8. Flush TX FIFO by writing a '1' to the CLR\_TXF bit in the MCR. Flush RX FIFO by writing a '1' to the CLR\_RXF bit in the MCR.
- 9. Clear transfer count either by setting CTCNT bit in the command word of the first entry in the new queue or via CPU writing directly to SPI\_TCNT field in the TCR.
- 10. Enable DMA channel by enabling the DMA enable request for the DMA channel assigned to the DSPI TX FIFO, and RX FIFO by setting the corresponding DMA set enable request bit.
- 11. Enable serial transmission and serial reception of data by clearing the EOQF bit.

## 47.5.2 Switching Master and Slave Mode

When changing modes in the DSPI, follow the steps below to guarantee proper operation.

- 1. Halt the DSPI by setting MCR[HALT].
- 2. Clear the transmit and receive FIFOs by writing a 1 to the CLR\_TXF and CLR\_RXF bits in MCR.
- 3. Set the appropriate mode in MCR[MSTR] and enable the DSPI by clearing MCR[HALT].



## 47.5.3 Baud Rate Settings

The following table shows the baud rate that is generated based on the combination of the baud rate prescaler PBR and the baud rate scaler BR in the CTAR registers. The values calculated assume a 100 MHz system frequency and the double baud rate DBR bit is clear.

#### NOTE

The clock frequency mentioned above is given as an example in this chapter. Refer to the clocking chapter for the frequency used to drive this module in the device.

		Baud Rate Divider Prescaler Values			
		2	3	5	7
	2	25.0M	16.7M	10.0M	7.14M
	4	12.5M	8.33M	5.00M	3.57M
	6	8.33M	5.56M	3.33M	2.38M
	8	6.25M	4.17M	2.50M	1.79M
	16	3.12M	2.08M	1.25M	893k
es	32	1.56M	1.04M	625k	446k
Valu	64	781k	521k	312k	223k
Baud Rate Scaler Values	128	391k	260k	156k	112k
Scs	256	195k	130k	78.1k	55.8k
Rate	512	97.7k	65.1k	39.1k	27.9k
and	1024	48.8k	32.6k	19.5k	14.0k
Ä	2048	24.4k	16.3k	9.77k	6.98k
	4096	12.2k	8.14k	4.88k	3.49k
	8192	6.10k	4.07k	2.44k	1.74k
	16384	3.05k	2.04k	1.22k	872
	32768	1.53k	1.02k	610	436

Table 47-113. Baud Rate Values (bps)

## 47.5.4 Delay Settings

The following table shows the values for the Delay after Transfer  $(t_{DT})$  and CS to SCK Delay  $(T_{CSC})$  that can be generated based on the prescaler values and the scaler values set in the CTAR registers. The values calculated assume a 100 MHz system frequency.



#### NOTE

The clock frequency mentioned above is given as an example in this chapter. Refer to the clocking chapter for the frequency used to drive this module in the device.

**Delay Prescaler Values** 5 1 3 140.0 ns 20.0 ns 60.0 ns 100.0 ns 4 40.0 ns 120.0 ns 280.0 ns 200.0 ns 8 80.0 ns 240.0 ns 400.0 ns 560.0 ns 160.0 ns 480.0 ns 800.0 ns 16  $1.1 \, \mu s$ 960.0 ns  $2.2 \, \mu s$ 32 320.0 ns  $1.6 \, \mu s$ 64 640.0 ns  $4.5 \, \mu s$  $1.9\,\mu s$  $3.2 \, \mu s$ **Delay Scaler Values** 128  $9.0 \, \mu s$  $1.3 \, \mu s$  $3.8 \, \mu s$  $6.4 \, \mu s$ 256  $2.6 \, \mu s$  $7.7 \, \mu s$  $12.8 \, \mu s$  $17.9 \, \mu s$ 512  $35.8 \, \mu s$  $5.1 \, \mu s$  $15.4 \, \mu s$  $25.6 \, \mu s$ 1024  $71.7 \, \mu s$  $10.2 \, \mu s$  $30.7 \, \mu s$  $51.2 \, \mu s$ 2048  $20.5 \, \mu s$  $61.4 \, \mu s$  $102.4 \, \mu s$  $143.4 \, \mu s$ 4096  $41.0 \, \mu s$  $122.9 \, \mu s$  $286.7 \, \mu s$  $204.8 \, \mu s$ 8192  $81.9 \, \mu s$  $245.8 \, \mu s$  $409.6 \, \mu s$ 573.4 µs 163.8 µs  $491.5 \, \mu s$ 16384  $819.2 \, \mu s$ 1.1 ms 32768 327.7 µs 983.0 µs 1.6 ms 2.3 ms 65536 655.4 µs 2.0 ms 3.3 ms 4.6 ms

Table 47-114. Delay Values

#### 47.5.5 Calculation of FIFO Pointer Addresses

Complete visibility of the TX and RX FIFO contents is available through the FIFO registers, and valid entries can be identified through a memory mapped pointer and a memory mapped counter for each FIFO. The pointer to the first-in entry in each FIFO is memory mapped. For the TX FIFO the first-in pointer is the Transmit Next Pointer (TXNXTPTR). For the RX FIFO the first-in pointer is the Pop Next Pointer (POPNXTPTR). The following figure illustrates the concept of first-in and last-in FIFO entries along with the FIFO Counter. The TX FIFO is chosen for the illustration, but the concepts carry over to the RX FIFO. See Transmit First In First Out (TX FIFO) Buffering Mechanism and Receive First In First Out (RX FIFO) Buffering Mechanism for details on the FIFO operation.



#### mualization/Application Information




Figure 47-100. TX FIFO Pointers and Counter

# 47.5.5.1 Address Calculation for the First-in Entry and Last-in Entry in the TX FIFO

The memory address of the first-in entry in the TX FIFO is computed by the following equation:

## First-in EntryAddress = TXFIFOBase + (4 × TXNXTPTR)

The memory address of the last-in entry in the TX FIFO is computed by the following equation:

 $Last-inEntryaddress = TXFIFOBase + 4 \times \big(TXCTR + TXNXTPTR - 1\big) mod \big(TXFIFOdepth\big)$ 

TX FIFO Base - Base address of TX FIFO

TXCTR - TX FIFO Counter

TXNXTPTR - Transmit Next Pointer

TX FIFO Depth - Transmit FIFO depth, implementation specific

# 47.5.5.2 Address Calculation for the First-in Entry and Last-in Entry in the RX FIFO

The memory address of the first-in entry in the RX FIFO is computed by the following equation:



# First-in EntryAddress = RX FIFOBase + (4 × POPNXTPTR)

The memory address of the last-in entry in the RX FIFO is computed by the following equation:

Last-inEntryaddress = RX FIFO Base + 4 × (RXCTR + POPNXTPTR - 1)mod(RXFIFOdepth)

RX FIFO Base - Base address of RX FIFO

RXCTR - RX FIFO counter

POPNXTPTR - Pop Next Pointer

RX FIFO Depth - Receive FIFO depth, implementation specific



**mualization/Application Information** 



# **Chapter 48 Inter-Integrated Circuit (I2C)**

## 48.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The inter-integrated circuit (I<sup>2</sup>C, I2C, or IIC) module provides a method of communication between a number of devices. The interface is designed to operate up to 100 kbit/s with maximum bus loading and timing. The device is capable of operating at higher baud rates, up to a maximum of clock/20, with reduced bus loading. The maximum communication length and the number of devices that can be connected are limited by a maximum bus capacitance of 400 pF. The I2C module also complies with the *System Management Bus (SMBus) Specification, version 2*.

## 48.1.1 Features

The I2C module has the following features:

- Compatible with *The I<sup>2</sup>C-Bus Specification*
- Multimaster operation
- Software programmable for one of 64 different serial clock frequencies
- Software-selectable acknowledge bit
- Interrupt-driven byte-by-byte data transfer
- Arbitration-lost interrupt with automatic mode switching from master to slave
- Calling address identification interrupt
- START and STOP signal generation and detection
- Repeated START signal generation and detection
- Acknowledge bit generation and detection
- Bus busy detection
- General call recognition



#### ınıroduction

- 10-bit address extension
- Support for System Management Bus (SMBus) Specification, version 2
- Programmable glitch input filter
- Low power mode wakeup on slave address match
- Range slave address support
- DMA support

## 48.1.2 Modes of Operation

The I2C module's operation in various low power modes is as follows:

- Run mode: This is the basic mode of operation. To conserve power in this mode, disable the module.
- Wait mode: The module continues to operate when the core is in wait mode and can provide a wakeup interrupt.
- Stop mode: The module is inactive in stop mode for reduced power consumption, except that address matching is enabled in stop mode. The STOP instruction does not affect the I2C module's register states. In any VLLSx mode, the register contents are reset.

## 48.1.3 Block Diagram

The following figure is a functional block diagram of the I2C module.






Figure 48-1. I2C Functional Block Diagram

## 48.2 I<sup>2</sup>C Signal Descriptions

The signal properties of I<sup>2</sup>C are shown in the following table.

Table 48-1. I<sup>2</sup>C Signal Descriptions

Signal	Description	I/O
SCL	Bidirectional serial clock line of the I <sup>2</sup> C system.	I/O
SDA	Bidirectional serial data line of the I <sup>2</sup> C system.	I/O

## 48.3 Memory Map and Register Descriptions

This section describes in detail all I2C registers accessible to the end user.



#### **Welliory Map and Register Descriptions**

## **I2C** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_6000	I2C Address Register 1 (I2C0_A1)	8	R/W	00h	48.3.1/ 1201
4006_6001	I2C Frequency Divider register (I2C0_F)	8	R/W	00h	48.3.2/ 1201
4006_6002	I2C Control Register 1 (I2C0_C1)	8	R/W	00h	48.3.3/ 1202
4006_6003	I2C Status Register (I2C0_S)	8	R/W	80h	48.3.4/ 1204
4006_6004	I2C Data I/O register (I2C0_D)	8	R/W	00h	48.3.5/ 1206
4006_6005	I2C Control Register 2 (I2C0_C2)	8	R/W	00h	48.3.6/ 1207
4006_6006	I2C Programmable Input Glitch Filter register (I2C0_FLT)	8	R/W	00h	48.3.7/ 1208
4006_6007	I2C Range Address register (I2C0_RA)	8	R/W	00h	48.3.8/ 1208
4006_6008	I2C SMBus Control and Status register (I2C0_SMB)	8	R/W	00h	48.3.9/ 1209
4006_6009	I2C Address Register 2 (I2C0_A2)	8	R/W	C2h	48.3.10/ 1210
4006_600A	I2C SCL Low Timeout Register High (I2C0_SLTH)	8	R/W	00h	48.3.11/ 1211
4006_600B	I2C SCL Low Timeout Register Low (I2C0_SLTL)	8	R/W	00h	48.3.12/ 1211
4006_7000	I2C Address Register 1 (I2C1_A1)	8	R/W	00h	48.3.1/ 1201
4006_7001	I2C Frequency Divider register (I2C1_F)	8	R/W	00h	48.3.2/ 1201
4006_7002	I2C Control Register 1 (I2C1_C1)	8	R/W	00h	48.3.3/ 1202
4006_7003	I2C Status Register (I2C1_S)	8	R/W	80h	48.3.4/ 1204
4006_7004	I2C Data I/O register (I2C1_D)	8	R/W	00h	48.3.5/ 1206
4006_7005	I2C Control Register 2 (I2C1_C2)	8	R/W	00h	48.3.6/ 1207
4006_7006	I2C Programmable Input Glitch Filter register (I2C1_FLT)	8	R/W	00h	48.3.7/ 1208
4006_7007	I2C Range Address register (I2C1_RA)	8	R/W	00h	48.3.8/ 1208




## I2C memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_7008	I2C SMBus Control and Status register (I2C1_SMB)	8	R/W	00h	48.3.9/ 1209
4006_7009	I2C Address Register 2 (I2C1_A2)	8	R/W	C2h	48.3.10/ 1210
4006_700A	I2C SCL Low Timeout Register High (I2C1_SLTH)	8	R/W	00h	48.3.11/ 1211
4006_700B	I2C SCL Low Timeout Register Low (I2C1_SLTL)	8	R/W	00h	48.3.12/ 1211

## 48.3.1 I2C Address Register 1 (I2Cx\_A1)

This register contains the slave address to be used by the I2C module.

Addresses: I2C0\_A1 is 4006\_6000h base + 0h offset = 4006\_6000h I2C1\_A1 is 4006\_7000h base + 0h offset = 4006\_7000h




#### I2Cx\_A1 field descriptions

Field	Description
7–1 AD[7:1]	Address  Contains the primary slave address used by the I2C module when it is addressed as a slave. This field is used in the 7-bit address scheme and the lower seven bits in the 10-bit address scheme.
0 Reserved	This read-only field is reserved and always has the value zero.

## 48.3.2 I2C Frequency Divider register (I2Cx\_F)

Addresses: I2C0\_F is 4006\_6000h base + 1h offset = 4006\_6001h I2C1\_F is 4006\_7000h base + 1h offset = 4006\_7001h






#### **INITIAL TOTAL MAD AND REGISTER DESCRIPTIONS**

## I2Cx\_F field descriptions

Field	Description
7–6 MULT	The MULT bits define the multiplier factor mul. This factor is used along with the SCL divider to generate the I2C baud rate.
	00 mul = 1
	01 mul = 2
	10 mul = 4
	11 Reserved
5–0	Clock rate
ICR	Prescales the bus clock for bit rate selection. This field and the MULT field determine the I2C baud rate, the SDA hold time, the SCL start hold time, and the SCL stop hold time. For a list of values corresponding to each ICR setting, see I2C Divider and Hold Values.
	The SCL divider multiplied by multiplier factor (mul) determines the I2C baud rate.
	I2C baud rate = bus speed (Hz)/(mul x SCL divider)
	The SDA hold time is the delay from the falling edge of SCL (I2C clock) to the changing of SDA (I2C data).
	SDA hold time = bus period (s) $\times$ mul $\times$ SDA hold value
	The SCL start hold time is the delay from the falling edge of SDA (I2C data) while SCL is high (start condition) to the falling edge of SCL (I2C clock).
	SCL start hold time = bus period (s) × mul × SCL start hold value
	The SCL stop hold time is the delay from the rising edge of SCL (I2C clock) to the rising edge of SDA (I2C data) while SCL is high (stop condition).
	SCL stop hold time = bus period (s) × mul × SCL stop hold value

## 48.3.3 I2C Control Register 1 (I2Cx\_C1)

Addresses: I2C0\_C1 is 4006\_6000h base + 2h offset = 4006\_6002h I2C1\_C1 is 4006\_7000h base + 2h offset = 4006\_7002h



#### I2Cx\_C1 field descriptions

Field	Description
	I2C enable
IICEN	Enables I2C module operation.



## I2Cx\_C1 field descriptions (continued)

Field	Description
	0 Disabled
	1 Enabled
6 IICIE	I2C interrupt enable
	Enables I2C interrupt requests.
	0 Disabled
	1 Enabled
5 MST	Master mode select
WIGT	When the MST bit is changed from a 0 to a 1, a START signal is generated on the bus and master mode is selected. When this bit changes from a 1 to a 0, a STOP signal is generated and the mode of operation changes from master to slave.
	<ul><li>0 Slave mode</li><li>1 Master mode</li></ul>
4 TX	Transmit mode select
	Selects the direction of master and slave transfers. In master mode this bit must be set according to the type of transfer required. Therefore, for address cycles, this bit is always set. When addressed as a slave this bit must be set by software according to the SRW bit in the status register.
	0 Receive
	1 Transmit
3 TXAK	Transmit acknowledge enable
IAAR	Specifies the value driven onto the SDA during data acknowledge cycles for both master and slave receivers. The value of the FACK bit affects NACK/ACK generation.
	O An acknowledge signal is sent to the bus on the following (if FACK is cleared) or current (if FACK is set) receiving byte.
	1 No acknowledge signal is sent to the bus on the following (if FACK is cleared) or current (if FACK is set) receiving data byte.
	NOTE: SCL is held low until TXAK is written.
2	Repeat START
RSTA	Writing a one to this bit generates a repeated START condition provided it is the current master. This bit will always be read as zero. Attempting a repeat at the wrong time results in loss of arbitration.
1 WUEN	Wakeup enable
VVOEIN	The I2C module can wake the MCU from low power mode with no peripheral bus running when slave address matching occurs.
	0 Normal operation. No interrupt generated when address matching in low power mode.
	1 Enables the wakeup function in low power mode.
0 DMAEN	DMA enable
DMAEN	The DMAEN bit enables or disables the DMA function.




#### wemory Map and Register Descriptions

## I2Cx\_C1 field descriptions (continued)

Field	Description			
	0 All DMA signalling disabled.			
	DMA transfer is enabled and the following conditions trigger the DMA request:			
	While FACK = 0, a data byte is received, either address or data is transmitted. (ACK/NACK automatic)      While FACK = 0, the first but a received to a the Address or data is transmitted.			
	While FACK = 0, the first byte received matches the A1 register or is general call address.			
	If any address matching occurs, IAAS and TCF are set. If the direction of transfer is known from master to slave, then it is not required to check the SRW. With this assumption, DMA can also be used in this case. In other cases, if the master reads data from the slave, then it is required to rewrite the C1 register operation. With this assumption, DMA cannot be used.			
	When FACK = 1, an address or a data byte is transmitted.			

## 48.3.4 I2C Status Register (I2Cx\_S)

Addresses: I2C0\_S is 4006\_6000h base + 3h offset = 4006\_6003h I2C1\_S is 4006\_7000h base + 3h offset = 4006\_7003h



#### I2Cx\_S field descriptions

Field	Description
7 TCF	Transfer complete flag
	This bit sets on the completion of a byte and acknowledge bit transfer. This bit is valid only during or immediately following a transfer to or from the I2C module. The TCF bit is cleared by reading the I2C data register in receive mode or by writing to the I2C data register in transmit mode.
	0 Transfer in progress
	1 Transfer complete
6 IAAS	Addressed as a slave
1,000	This bit is set by one of the following conditions:
	The calling address matches the programmed slave primary address in the A1 register or range address in the RA register (which must be set to a nonzero value).
	<ul> <li>GCAEN is set and a general call is received.</li> <li>SIICAEN is set and the calling address matches the second programmed slave address.</li> </ul>
	ALERTEN is set and an SMBus alert response address is received
	RMEN is set and an address is received that is within the range between the values of the A1 and RA registers.
	This bit sets before the ACK bit. The CPU must check the SRW bit and set TX/RX accordingly. Writing the C1 register with any value clears this bit.



## I2Cx\_S field descriptions (continued)

Field	Description
	0 Not addressed
	1 Addressed as a slave
5 BUSY	Bus busy
	Indicates the status of the bus regardless of slave or master mode. This bit is set when a START signal is detected and cleared when a STOP signal is detected.
	0 Bus is idle 1 Bus is busy
4 ARBL	Arbitration lost
	This bit is set by hardware when the arbitration procedure is lost. The ARBL bit must be cleared by software, by writing a one to it.
	<ul><li>0 Standard bus operation.</li><li>1 Loss of arbitration.</li></ul>
3 RAM	Range address match
	<ul> <li>This bit is set by any of the following conditions:</li> <li>Any nonzero calling address is received that matches the address in the RA register.</li> <li>The RMEN bit is set and the calling address is within the range of values of the A1 and RA registers.</li> </ul>
	Writing the C1 register with any value clears this bit.
	<ul><li>0 Not addressed</li><li>1 Addressed as a slave</li></ul>
2	Slave read/write
SRW	When addressed as a slave, SRW indicates the value of the R/W command bit of the calling address sent to the master.
	O Slave receive, master writing to slave  Clave transmit master reading from slave
1	Slave transmit, master reading from slave     Interrupt flag
IICIF	This bit sets when an interrupt is pending. This bit must be cleared by software or by writing a 1 to it in the interrupt routine. One of the following events can set this bit:
	<ul> <li>One byte transfer including ACK/NACK bit completes if FACK = 0</li> <li>One byte transfer excluding ACK/NACK bit completes if FACK = 1. An ACK or NACK is sent on the bus by writing 0 or 1 to TXAK after this bit is set in receive mode</li> <li>Match of slave address to calling address including primary slave address, range slave address, alert response address, second slave address, or general call address.</li> <li>Arbitration lost</li> <li>In SMBus mode, any timeouts except SCL and SDA high timeouts</li> </ul>
	<ul><li>0 No interrupt pending</li><li>1 Interrupt pending</li></ul>
0	<u> </u>
RXAK	Receive acknowledge




#### wemory Map and Register Descriptions

## I2Cx\_S field descriptions (continued)

Field	Description		
	O Acknowledge signal was received after the completion of one byte of data transmission on the bus		
	1 No acknowledge signal detected		

## 48.3.5 I2C Data I/O register (I2Cx\_D)

Addresses: I2C0\_D is 4006\_6000h base + 4h offset = 4006\_6004h I2C1\_D is 4006\_7000h base + 4h offset = 4006\_7004h




## I2Cx\_D field descriptions

Field	Description
7–0 DATA	Data
Britin	In master transmit mode, when data is written to this register, a data transfer is initiated. The most significant bit is sent first. In master receive mode, reading this register initiates receiving of the next byte of data.
	<b>NOTE:</b> When making the transition out of master receive mode, switch the I2C mode before reading the Data register to prevent an inadvertent initiation of a master receive data transfer.
	In slave mode, the same functions are available after an address match occurs.
	The C1[TX] bit must correctly reflect the desired direction of transfer in master and slave modes for the transmission to begin. For example, if the I2C module is configured for master transmit but a master receive is desired, reading the Data register does not initiate the receive.
	Reading the Data register returns the last byte received while the I2C module is configured in master receive or slave receive mode. The Data register does not reflect every byte that is transmitted on the I2C bus, and neither can software verify that a byte has been written to the Data register correctly by reading it back.
	In master transmit mode, the first byte of data written to the Data register following assertion of MST (start bit) or assertion of RSTA (repeated start bit) is used for the address transfer and must consist of the calling address (in bits 7-1) concatenated with the required R/W bit (in position bit 0).



## 48.3.6 I2C Control Register 2 (I2Cx\_C2)

Addresses: I2C0\_C2 is 4006\_6000h base + 5h offset = 4006\_6005h I2C1\_C2 is 4006\_7000h base + 5h offset = 4006\_7005h



#### I2Cx\_C2 field descriptions

Field	Description
7 GCAEN	General call address enable Enables general call address.
	0 Disabled 1 Enabled
6 ADEXT	Address extension  Controls the number of bits used for the slave address.  0 7-bit address scheme
	1 10-bit address scheme
5 HDRS	High drive select  Controls the drive capability of the I2C pads.
	0 Normal drive mode 1 High drive mode
4 SBRC	Slave baud rate control  Enables independent slave mode baud rate at max frequency. This forces clock stretching on SCL in very fast I2C modes.
	<ul> <li>The slave baud rate follows the master baud rate and clock stretching may occur</li> <li>Slave baud rate is independent of the master baud rate</li> </ul>
3 RMEN	Range address matching enable  This bit controls slave address matching for addresses between the values of the A1 and RA registers.  When this bit is set, a slave address match occurs for any address greater than the value of the A1 register and less than or equal to the value of the RA register.  O Range mode disabled. No address match occurs for an address within the range of values of the A1 and RA registers.  Range mode enabled. Address matching occurs when a slave receives an address within the range of values of the A1 and RA registers.
2–0 AD[10:8]	Slave address  Contains the upper three bits of the slave address in the 10-bit address scheme. This field is valid only when the ADEXT bit is set.

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## 48.3.7 I2C Programmable Input Glitch Filter register (I2Cx\_FLT)

Addresses: I2C0\_FLT is 4006\_6000h base + 6h offset = 4006\_6006h

I2C1\_FLT is 4006\_7000h base + 6h offset = 4006\_7006h




#### I2Cx\_FLT field descriptions

Field	Description								
7 Reserved	his read-only field is reserved and always has the value zero.								
6–5 Reserved	This read-only field is reserved and always has the value zero.								
4–0 FLT	I2C programmable filter factor  Controls the width of the glitch, in terms of bus clock cycles, that the filter must absorb. For any glitch whose size is less than or equal to this width setting, the filter does not allow the glitch to pass.  Oh No filter/bypass  O1-1Fh Filter glitches up to width of <i>n</i> bus clock cycles, where <i>n</i> =1-31d								

## 48.3.8 I2C Range Address register (I2Cx\_RA)

Addresses: I2C0\_RA is 4006\_6000h base + 7h offset = 4006\_6007h

I2C1\_RA is 4006\_7000h base + 7h offset = 4006\_7007h



#### I2Cx\_RA field descriptions

Field	Description
7–1 RAD	Range slave address
10.0	This field contains the slave address to be used by the I2C module. The field is used in the 7-bit address scheme. Any nonzero write enables this register. This register's use is similar to that of the A1 register, but in addition this register can be considered a maximum boundary in range matching mode.
0 Reserved	This read-only field is reserved and always has the value zero.



## 48.3.9 I2C SMBus Control and Status register (I2Cx\_SMB)


#### NOTE

When the SCL and SDA signals are held high for a length of time greater than the high timeout period, the SHTF1 flag sets. Before reaching this threshold, while the system is detecting how long these signals are being held high, a master assumes that the bus is free. However, the SHTF1 bit rises in the bus transmission process with the idle bus state.

#### NOTE

When the TCKSEL bit is set, there is no meaning to monitor the SHTF1 bit because the bus speed is too high to match the protocol of SMBus.

Addresses: I2C0\_SMB is 4006\_6000h base + 8h offset = 4006\_6008h I2C1\_SMB is 4006\_7000h base + 8h offset = 4006\_7008h



#### I2Cx\_SMB field descriptions

Field	Description								
7 FACK	Fast NACK/ACK enable								
	For SMBus packet error checking, the CPU must be able to issue an ACK or NACK according to the result of receiving data byte.								
	0 An ACK or NACK is sent on the following receiving data byte								
	<ul> <li>Writing 0 to TXAK after receiving a data byte generates an ACK. Writing 1 to TXAK after receiving a data byte generates a NACK.</li> </ul>								
6 ALERTEN	SMBus alert response address enable								
	Enables or disables SMBus alert response address matching.								
	<b>NOTE:</b> After the host responds to a device that used the alert response address, you must use software to put the device's address on the bus. The alert protocol is described in the SMBus specification.								
	0 SMBus alert response address matching is disabled								
	1 SMBus alert response address matching is enabled								
5 SIICAEN	Second I2C address enable								
3371214	Enables or disables SMBus device default address.								




#### wemory Map and Register Descriptions

## I2Cx\_SMB field descriptions (continued)

Field	Description						
	0 I2C address register 2 matching is disabled						
	1 I2C address register 2 matching is enabled						
4	Timeout counter clock select						
TCKSEL	Selects the clock source of the timeout counter.						
	0 Timeout counter counts at the frequency of the bus clock / 64						
	1 Timeout counter counts at the frequency of the bus clock						
3 SLTF	SCL low timeout flag						
	This bit is set when the SLT register (consisting of the SLTH and SLTL registers) is loaded with a non-zero value (LoValue) and an SCL low timeout occurs. Software clears this bit by writing a logic 1 to it.						
	NOTE: The low timeout function is disabled when the SLT register's value is zero.						
	0 No low timeout occurs						
	1 Low timeout occurs						
2 SHTF1	SCL high timeout flag 1						
	This read-only bit sets when SCL and SDA are held high more than clock $\times$ LoValue / 512, which indicates the bus is free. This bit is cleared automatically.						
	0 No SCL high and SDA high timeout occurs						
	1 SCL high and SDA high timeout occurs						
1 SHTF2	SCL high timeout flag 2						
	This bit sets when SCL is held high and SDA is held low more than clock $\times$ LoValue/512. Software clears this bit by writing a 1 to it.						
	0 No SCL high and SDA low timeout occurs						
	1 SCL high and SDA low timeout occurs						
0 SHTF2IE	SHTF2 interrupt enable						
	Enables SCL high and SDA low timeout interrupt.						
	0 SHTF2 interrupt is disabled						
	1 SHTF2 interrupt is enabled						

## 48.3.10 I2C Address Register 2 (I2Cx\_A2)

Addresses: I2C0\_A2 is 4006\_6000h base + 9h offset = 4006\_6009h I2C1\_A2 is 4006\_7000h base + 9h offset = 4006\_7009h



#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




#### I2Cx\_A2 field descriptions

Field	Description
7–1 SAD	SMBus address  Contains the slave address used by the SMBus. This field is used on the device default address or other related addresses.
0 Reserved	This read-only field is reserved and always has the value zero.

## 48.3.11 I2C SCL Low Timeout Register High (I2Cx\_SLTH)

Addresses: I2C0\_SLTH is 4006\_6000h base + Ah offset = 4006\_600Ah I2C1\_SLTH is 4006\_7000h base + Ah offset = 4006\_700Ah




#### I2Cx\_SLTH field descriptions

Field	Description
7–0 SSLT[15:8]	Most significant byte of SCL low timeout value that determines the timeout period of SCL low.

## 48.3.12 I2C SCL Low Timeout Register Low (I2Cx\_SLTL)

Addresses: I2C0\_SLTL is 4006\_6000h base + Bh offset = 4006\_600Bh I2C1\_SLTL is 4006\_7000h base + Bh offset = 4006\_700Bh



#### I2Cx\_SLTL field descriptions

Field	Description
7–0 SSLT[7:0]	Least significant byte of SCL low timeout value that determines the timeout period of SCL low.

## 48.4 Functional Description

This section provides a comprehensive functional description of the I2C module.

## 48.4.1 I2C Protocol

The I2C bus system uses a serial data line (SDA) and a serial clock line (SCL) for data transfers. All devices connected to it must have open drain or open collector outputs. A logic AND function is exercised on both lines with external pull-up resistors. The value of these resistors depends on the system.

Normally, a standard instance of communication is composed of four parts:

- 1. START signal
- 2. Slave address transmission
- 3. Data transfer
- 4. STOP signal

The STOP signal should not be confused with the CPU STOP instruction. The following figure illustrates I2C bus system communication.




Figure 48-38. I2C Bus Transmission Signals



## 48.4.1.1 START Signal

The bus is free when no master device is engaging the bus (both SCL and SDA are high). When the bus is free, a master may initiate communication by sending a START signal. A START signal is defined as a high-to-low transition of SDA while SCL is high. This signal denotes the beginning of a new data transfer (each data transfer might contain several bytes of data) and brings all slaves out of their idle states.

#### 48.4.1.2 Slave Address Transmission

Immediately after the START signal, the first byte of a data transfer is the slave address transmitted by the master. This address is a 7-bit calling address followed by an  $R/\overline{W}$  bit. The  $R/\overline{W}$  bit tells the slave the desired direction of data transfer.

- 1 = Read transfer: The slave transmits data to the master
- 0 =Write transfer: The master transmits data to the slave

Only the slave with a calling address that matches the one transmitted by the master responds by sending an acknowledge bit. The slave sends the acknowledge bit by pulling SDA low at the ninth clock.

No two slaves in the system can have the same address. If the I2C module is the master, it must not transmit an address that is equal to its own slave address. The I2C module cannot be master and slave at the same time. However, if arbitration is lost during an address cycle, the I2C module reverts to slave mode and operates correctly even if it is being addressed by another master.

#### 48.4.1.3 Data Transfers

When successful slave addressing is achieved, data transfer can proceed on a byte-by-byte basis in the direction specified by the  $R/\overline{W}$  bit sent by the calling master.

All transfers that follow an address cycle are referred to as data transfers, even if they carry subaddress information for the slave device.

Each data byte is 8 bits long. Data may be changed only while SCL is low. Data must be held stable while SCL is high. There is one clock pulse on SCL for each data bit, and the MSB is transferred first. Each data byte is followed by a ninth (acknowledge) bit, which is signaled from the receiving device by pulling SDA low at the ninth clock. In summary, one complete data transfer needs nine clock pulses.



#### runctional Description

If the slave receiver does not acknowledge the master in the ninth bit, the slave must leave SDA high. The master interprets the failed acknowledgement as an unsuccessful data transfer.

If the master receiver does not acknowledge the slave transmitter after a data byte transmission, the slave interprets it as an end to data transfer and releases the SDA line.

In the case of a failed acknowledgement by either the slave or master, the data transfer is aborted and the master does one of two things:

- Relinquishes the bus by generating a STOP signal.
- Commences a new call by generating a repeated START signal.

## 48.4.1.4 STOP Signal

The master can terminate the communication by generating a STOP signal to free the bus. A STOP signal is defined as a low-to-high transition of SDA while SCL is asserted.

The master can generate a STOP signal even if the slave has generated an acknowledgement, at which point the slave must release the bus.

## 48.4.1.5 Repeated START Signal

The master may generate a START signal followed by a calling command without generating a STOP signal first. This action is called a repeated START. The master uses a repeated START to communicate with another slave or with the same slave in a different mode (transmit/receive mode) without releasing the bus.

#### 48.4.1.6 Arbitration Procedure

The I2C bus is a true multimaster bus that allows more than one master to be connected on it.

If two or more masters try to control the bus at the same time, a clock synchronization procedure determines the bus clock. The bus clock's low period is equal to the longest clock low period, and the high period is equal to the shortest one among the masters.

The relative priority of the contending masters is determined by a data arbitration procedure. A bus master loses arbitration if it transmits logic level 1 while another master transmits logic level 0. The losing masters immediately switch to slave receive mode and



stop driving SDA output. In this case, the transition from master to slave mode does not generate a STOP condition. Meanwhile, hardware sets a status bit to indicate the loss of arbitration.

## 48.4.1.7 Clock Synchronization

Because wire AND logic is performed on SCL, a high-to-low transition on SCL affects all devices connected on the bus. The devices start counting their low period and, after a device's clock has gone low, that device holds SCL low until the clock reaches its high state. However, the change of low to high in this device clock might not change the state of SCL if another device clock is still within its low period. Therefore, the synchronized clock SCL is held low by the device with the longest low period. Devices with shorter low periods enter a high wait state during this time (see the following diagram). When all applicable devices have counted off their low period, the synchronized clock SCL is released and pulled high. Afterward there is no difference between the device clocks and the state of SCL, and all devices start counting their high periods. The first device to complete its high period pulls SCL low again.





Figure 48-39. I2C Clock Synchronization

## 48.4.1.8 Handshaking

The clock synchronization mechanism can be used as a handshake in data transfers. A slave device may hold SCL low after completing a single byte transfer (9 bits). In this case, it halts the bus clock and forces the master clock into wait states until the slave releases SCL.





#### **Clock Stretching** 48.4.1.9

The clock synchronization mechanism can be used by slaves to slow down the bit rate of a transfer. After the master drives SCL low, a slave can drive SCL low for the required period and then release it. If the slave's SCL low period is greater than the master's SCL low period, the resulting SCL bus signal's low period is stretched.

#### 48.4.1.10 I2C Divider and Hold Values

Table 48-41. I2C Divider and Hold Values

ICR (hex)	SCL Divider	SDA Hold Value	SCL Hold (Start)	SCL Hold (Stop)	ICR (hex)	SCL Divider	SDA Hold (clocks)	(Start)	SCL Hold (Stop)
(110%)			Value	Value	(110%)	(clocks)		Value	Value
00	20	7	6	11	20	160	17	78	81
01	22	7	7	12	21	192	17	94	97
02	24	8	8	13	22	224	33	110	113
03	26	8	9	14	23	256	33	126	129
04	28	9	10	15	24	288	49	142	145
05	30	9	11	16	25	320	49	158	161
06	34	10	13	18	26	384	65	190	193
07	40	10	16	21	27	480	65	238	241
08	28	7	10	15	28	320	33	158	161
09	32	7	12	17	29	384	33	190	193
0A	36	9	14	19	2A	448	65	222	225
0B	40	9	16	21	2B	512	65	254	257
0C	44	11	18	23	2C	576	97	286	289
0D	48	11	20	25	2D	640	97	318	321
0E	56	13	24	29	2E	768	129	382	385
0F	68	13	30	35	2F	960	129	478	481
10	48	9	18	25	30	640	65	318	321
11	56	9	22	29	31	768	65	382	385
12	64	13	26	33	32	896	129	446	449
13	72	13	30	37	33	1024	129	510	513
14	80	17	34	41	34	1152	193	574	577
15	88	17	38	45	35	1280	193	638	641
16	104	21	46	53	36	1536	257	766	769
17	128	21	58	65	37	1920	257	958	961
18	80	9	38	41	38	1280	129	638	641



Table 48-41.	12C Divider	and Hold	Values	(continued)
I able to-ti.	IZO DIVIGEI	and noid	values	(COIILIIIAEA <i>)</i>

ICR (hex)	SCL Divider	SDA Hold Value	SCL Hold (Start) Value	SCL Hold (Stop) Value	ICR (hex)	SCL Divider (clocks)	SDA Hold (clocks)	SCL Hold (Start) Value	SCL Hold (Stop) Value
19	96	9	46	49	39	1536	129	766	769
1A	112	17	54	57	3A	1792	257	894	897
1B	128	17	62	65	3B	2048	257	1022	1025
1C	144	25	70	73	3C	2304	385	1150	1153
1D	160	25	78	81	3D	2560	385	1278	1281
1E	192	33	94	97	3E	3072	513	1534	1537
1F	240	33	118	121	3F	3840	513	1918	1921

#### 48.4.2 10-bit Address

For 10-bit addressing, 0x11110 is used for the first 5 bits of the first address byte. Various combinations of read/write formats are possible within a transfer that includes 10-bit addressing.

#### 48.4.2.1 Master-Transmitter Addresses a Slave-Receiver

The transfer direction is not changed. When a 10-bit address follows a START condition, each slave compares the first seven bits of the first byte of the slave address (11110XX) with its own address and tests whether the eighth bit  $(R/\overline{W})$  direction bit) is 0. It is possible that more than one device finds a match and generates an acknowledge (A1). Each slave that finds a match compares the eight bits of the second byte of the slave address with its own address, but only one slave finds a match and generate an acknowledge (A2). The matching slave remains addressed by the master until it receives a STOP condition (P) or a repeated START condition (Sr) followed by a different slave address.

Table 48-42. Master-Transmitter Addresses Slave-Receiver with a 10-bit Address

+ AD9		S	Slave addres s first 7 bits 11110 + AD10 + AD9	R/W 0	A1	Slave addres s second byte AD[8:1]	A2	Data	А		Data	A/A	Р
-------	--	---	---	----------	----	---	----	------	---	--	------	-----	---



#### runctional Description

After the master-transmitter has sent the first byte of the 10-bit address, the slave-receiver sees an I2C interrupt. User software must ensure that for this interrupt, the contents of the Data register are ignored and not treated as valid data.

#### 48.4.2.2 Master-Receiver Addresses a Slave-Transmitter

The transfer direction is changed after the second  $R/\overline{W}$  bit. Up to and including acknowledge bit A2, the procedure is the same as that described for a master-transmitter addressing a slave-receiver. After the repeated START condition (Sr), a matching slave remembers that it was addressed before. This slave then checks whether the first seven bits of the first byte of the slave address following Sr are the same as they were after the START condition (S), and it tests whether the eighth  $(R/\overline{W})$  bit is 1. If there is a match, the slave considers that it has been addressed as a transmitter and generates acknowledge A3. The slave-transmitter remains addressed until it receives a STOP condition (P) or a repeated START condition (Sr) followed by a different slave address.

After a repeated START condition (Sr), all other slave devices also compare the first seven bits of the first byte of the slave address with their own addresses and test the eighth  $(R/\overline{W})$  bit. However, none of them are addressed because  $R/\overline{W} = 1$  (for 10-bit devices), or the 11110XX slave address (for 7-bit devices) does not match.

Table 48-43. Master-Receiver Addresses a Slave-Transmitter with a 10-bit Address

S	Slave address first 7 bits 11110 + AD10 + AD9	R/W 0	A1	Slave address second byte AD[8:1]	A2	Sr	Slave address first 7 bits 11110 + AD10 + AD9	R/W 1	А3	Data	Α		Data	Α	Р	
---	---	----------	----	---	----	----	---	----------	----	------	---	--	------	---	---	--

After the master-receiver has sent the first byte of the 10-bit address, the slave-transmitter sees an I2C interrupt. User software must ensure that for this interrupt, the contents of the Data register are ignored and not treated as valid data.

## 48.4.3 Address Matching

All received addresses can be requested in 7-bit or 10-bit address format. The Address Register 1, which contains the I2C primary slave address, always participates in the address matching process. If the GCAEN bit is set, general call participates the address matching process. If the ALERTEN bit is set, alert response participates the address matching process. If the SIICAEN bit is set, the Address Register 2 participates in the



address matching process. If the Range Address register is programmed to a nonzero value, the range address itself participates in the address matching process. If the RMEN bit is set, any address within the range of values of the Address Register 1 and the Range Address register participates in the address matching process. The Range Address register must be programmed to a value greater than the value of the Address Register 1.

When the I2C module responds to one of these addresses, it acts as a slave-receiver and the IAAS bit is set after the address cycle. Software must read the Data register after the first byte transfer to determine that the address is matched.

## 48.4.4 System Management Bus Specification

SMBus provides a control bus for system and power management related tasks. A system can use SMBus to pass messages to and from devices instead of tripping individual control lines. Removing the individual control lines reduces pin count. Accepting messages ensures future expandability. With the system management bus, a device can provide manufacturer information, tell the system what its model/part number is, save its state for a suspend event, report different types of errors, accept control parameters, and return its status.

#### 48.4.4.1 Timeouts

The  $T_{TIMEOUT,MIN}$  parameter allows a master or slave to conclude that a defective device is holding the clock low indefinitely or a master is intentionally trying to drive devices off the bus. It is highly recommended that a slave device release the bus (stop driving the bus and let SCL and SDA float high) when it detects any single clock held low longer than  $T_{TIMEOUT,MIN}$ . Devices that have detected this condition must reset their communication and be able to receive a new START condition within the timeframe of  $T_{TIMEOUT,MAX}$ .

SMBus defines a clock low timeout,  $T_{TIMEOUT}$ , of 35 ms, specifies  $T_{LOW:SEXT}$  as the cumulative clock low extend time for a slave device, and specifies  $T_{LOW:MEXT}$  as the cumulative clock low extend time for a master device.

## 48.4.4.1.1 SCL Low Timeout

If the SCL line is held low by a slave device on the bus, no further communication is possible. Furthermore, the master cannot force the SCL line high to correct the error condition. To solve this problem, the SMBus protocol specifies that devices participating in a transfer must detect any clock cycle held low longer than a timeout value condition. Devices that have detected the timeout condition must reset the communication. When



#### runctional Description

the I2C module is an active master, if it detects that SMBCLK low has exceeded the value of  $T_{TIMEOUT,MIN}$ , it must generate a stop condition within or after the current data byte in the transfer process. When the I2C module is a slave, if it detects the  $T_{TIMEOUT,MIN}$  condition, it resets its communication and is then able to receive a new START condition.

## 48.4.4.1.2 SCL High Timeout

When the I2C module has determined that the SMBCLK and SMBDAT signals have been high for at least T<sub>HIGH:MAX</sub>, it assumes that the bus is idle. A HIGH timeout can occur in two ways:

- 1. HIGH timeout detected after a STOP condition appears on the bus
- 2. HIGH timeout detected after a START condition, but before a STOP condition appears on the bus

Any master detecting either scenario can assume the bus is free when SHTF1 rises. A HIGH timeout occurs in scenario 2 if a master ever detects that both the BUSY bit is high and SHTF1 is high.

When the SMBDAT signal is low and the SMBCLK signal is high for a period of time, the other kind of timeout occurs. The time period must be defined in software. SHTF2 is used as the flag when the time limit is reached. This flag is also an interrupt resource, so it also triggers IICIF.

#### 48.4.4.1.3 CSMBCLK TIMEOUT MEXT and CSMBCLK TIMEOUT SEXT

The following figure illustrates the definition of the timeout intervals  $T_{LOW:SEXT}$  and  $T_{LOW:MEXT}$ . When in master mode, the I2C module must not cumulatively extend its clock cycles for a period greater than  $T_{LOW:MEXT}$  within a byte, where each byte is defined as START-to-ACK, ACK-to-ACK, or ACK-to-STOP. When CSMBCLK TIMEOUT MEXT occurs, SMBus MEXT rises and also triggers the SLTF.






Figure 48-40. Timeout measurement intervals

A master is allowed to abort the transaction in progress to any slave that violates the  $T_{LOW:SEXT}$  or  $T_{TIMEOUT,MIN}$  specifications. To abort the transaction, the master issues a STOP condition at the conclusion of the byte transfer in progress. When a slave, the I2C module must not cumulatively extend its clock cycles for a period greater than  $T_{LOW:SEXT}$  during any message from the initial START to the STOP. When CSMBCLK TIMEOUT SEXT occurs, SEXT rises and also triggers SLTF.

#### **NOTE**

CSMBCLK TIMEOUT SEXT and CSMBCLK TIMEOUT MEXT are optional functions that are implemented in the second step.

#### 48.4.4.2 FAST ACK and NACK

To improve reliability and communication robustness, implementation of packet error checking (PEC) by SMBus devices is optional for SMBus devices but required for devices participating in and only during the address resolution protocol (ARP) process. The PEC is a CRC-8 error checking byte, calculated on all the message bytes. The PEC is appended to the message by the device that supplied the last data byte. If the PEC is present but not correct, a NACK is issued by the receiver. Otherwise an ACK is issued. In order to calculate the CRC-8 by software, this module can hold the SCL line low after receiving the eighth SCL (8th bit) if this byte is a data byte. So software can determine whether an ACK or NACK should be sent to the bus by setting or clearing the TXAK bit if the FACK (fast ACK/NACK enable) bit is enabled.

SMBus requires a device always to acknowledge its own address, as a mechanism to detect the presence of a removable device (such as a battery or docking station) on the bus. In addition to indicating a slave device busy condition, SMBus uses the NACK mechanism to indicate the reception of an invalid command or invalid data. Because such a condition may occur on the last byte of the transfer, SMBus devices are required to



#### runctional Description

have the ability to generate the not acknowledge after the transfer of each byte and before the completion of the transaction. This requirement is important because SMBus does not provide any other resend signaling. This difference in the use of the NACK signaling has implications on the specific implementation of the SMBus port, especially in devices that handle critical system data such as the SMBus host and the SBS components.

#### **NOTE**

In the last byte of master receive slave transmit mode, the master must send a NACK to the bus, so FACK must be switched off before the last byte transmits.

#### 48.4.5 Resets

The I2C module is disabled after a reset. The I2C module cannot cause a core reset.

## 48.4.6 Interrupts

The I2C module generates an interrupt when any of the events in the following table occur, provided that the IICIE bit is set. The interrupt is driven by the IICIF bit (of the I2C Status Register) and masked with the IICIE bit (of the I2C Control Register 1). The IICIF bit must be cleared (by software) by writing 1 to it in the interrupt routine. The SMBus timeouts interrupt is driven by SLTF and masked with the IICIE bit. The SLTF bit must be cleared by software by writing 1 to it in the interrupt routine. You can determine the interrupt type by reading the Status Register.

#### **NOTE**

In master receive mode, the FACK bit must be set to zero before the last byte transfer.

Interrupt Source	Status	Flag	Local Enable
Complete 1-byte transfer	TCF	IICIF	IICIE
Match of received calling address	IAAS	IICIF	IICIE
Arbitration lost	ARBL	IICIF	IICIE
SMBus SCL low timeout interrupt flag	SLTF	IICIF	IICIE
SMBus SCL high SDA low timeout interrupt flag	SHTF2	IICIF	IICIE & SHTF2IE
Wakeup from stop interrupt	IAAS	IICIF	IICIE & WUEN



## 48.4.6.1 Byte Transfer Interrupt

The transfer complete flag (TCF) bit is set at the falling edge of the ninth clock to indicate the completion of a byte and acknowledgement transfer. When FACK is enabled, TCF is then set at the falling edge of 8th clock to indicate the completion of byte.

## 48.4.6.2 Address Detect Interrupt

When the calling address matches the programmed slave address (I2C Address Register) or when the GCAEN bit is set and a general call is received, the IAAS bit in the Status Register is set. The CPU is interrupted, provided the IICIE bit is set. The CPU must check the SRW bit and set its Tx mode accordingly.

## 48.4.6.3 Exit from Low-Power/Stop Modes

The slave receive input detect circuit and address matching feature are still active on low power modes (wait and stop). An asynchronous input matching slave address or general call address brings the CPU out of low power/stop mode if the interrupt is not masked. Therefore, TCF and IAAS both can trigger this interrupt.

## 48.4.6.4 Arbitration Lost Interrupt

The I2C is a true multimaster bus that allows more than one master to be connected on it. If two or more masters try to control the bus at the same time, the relative priority of the contending masters is determined by a data arbitration procedure. The I2C module asserts the arbitration-lost interrupt when it loses the data arbitration process and the ARBL bit in the Status Register is set.

Arbitration is lost in the following circumstances:

- 1. SDA is sampled as low when the master drives high during an address or data transmit cycle.
- 2. SDA is sampled as low when the master drives high during the acknowledge bit of a data receive cycle.
- 3. A START cycle is attempted when the bus is busy.
- 4. A repeated START cycle is requested in slave mode.
- 5. A STOP condition is detected when the master did not request it.



**runctional Description** 

The ARBL bit must be cleared (by software) by writing 1 to it.

## 48.4.6.5 Timeout Interrupt in SMBus

When the IICIE bit is set, the I2C module asserts a timeout interrupt (outputs SLTF and SHTF2) upon detection of any of the mentioned timeout conditions, with one exception. The SCL high and SDA high TIMEOUT mechanism must not be used to influence the timeout interrupt output, because this timeout indicates an idle condition on the bus. SHTF1 rises when it matches the SCL high and SDA high TIMEOUT and falls automatically just to indicate the bus status. The SHTF2's timeout period is the same as that of SHTF1, which is short compared to that of SLTF, so another control bit, SHTF2IE, is added to enable or disable it.

## 48.4.7 Programmable Input Glitch Filter

An I2C glitch filter has been added outside legacy I2C modules but within the I2C package. This filter can absorb glitches on the I2C clock and data lines for the I2C module. The width of the glitch to absorb can be specified in terms of the number of (half) bus clock cycles. A single Programmable Input Glitch Filter control register is provided. Effectively, any down-up-down or up-down-up transition on the data line that occurs within the number of clock cycles programmed in this register is ignored by the I2C module. The programmer must specify the size of the glitch (in terms of bus clock cycles) for the filter to absorb and not pass.




Figure 48-41. Programmable input glitch filter diagram

## 48.4.8 Address Matching Wakeup

When a primary, range, or general call address match occurs when the I2C module is in slave receive mode, the MCU wakes from low power mode with no peripheral bus running. After the address matching IAAS bit is set, an interrupt is sent at the end of address matching to wake the core. The IAAS bit must be cleared after the clock recovery.



### NOTE

After the system recovers and is in run mode, restart the I2C module if necessary. The SCL line is not held low until the I2C module resets after address matching. The main purpose of this feature is to wake the MCU from stop mode. Data sent on the bus that is the same as a target device address might also wake the target MCU.

# 48.4.9 DMA Support

If the DMAEN bit is cleared and the IICIE bit is set, an interrupt condition generates an interrupt request. If the DMAEN bit is set and the IICIE bit is set, an interrupt condition generates a DMA request instead. DMA requests are generated by the transfer complete flag (TCF).

If the DMAEN bit is set, the only arbitration lost is to another I2C module (error), and SCL low timeouts (error) generate CPU interrupts. All other events initiate a DMA transfer.

### **NOTE**

Before the last byte of master receive mode, TXAK must be set to send a NACK after the last byte's transfer. Therefore, the DMA must be disabled before the last byte's transfer.

### **NOTE**

In 10-bit address mode transmission, the addresses to send occupy 2-3 bytes. During this transfer period, the DMA must be disabled because the C1 register is written to send a repeat start or to change the transfer direction.

# 48.5 Initialization/Application Information

Module Initialization (Slave)

- 1. Write: Control Register 2
  - to enable or disable general call
  - to select 10-bit or 7-bit addressing mode
- 2. Write: Address Register 1 to set the slave address
- 3. Write: Control Register 1 to enable the I2C module and interrupts
- 4. Initialize RAM variables (IICEN = 1 and IICIE = 1) for transmit data
- 5. Initialize RAM variables used to achieve the routine shown in the following figure




#### mualization/Application Information

Module Initialization (Master)

- 1. Write: Frequency Divider register to set the I2C baud rate (example provided in this chapter)
- 2. Write: Control Register 1 to enable the I2C module and interrupts
- 3. Initialize RAM variables (IICEN = 1 and IICIE = 1) for transmit data
- 4. Initialize RAM variables used to achieve the routine shown in the following figure
- 5. Write: Control Register 1 to enable TX
- 6. Write: Control Register 1 to enable MST (master mode)
- 7. Write: Data register with the address of the target slave (the LSB of this byte determines whether the communication is master receive or transmit)

The routine shown in the following figure can handle both master and slave I2C operations. For slave operation, an incoming I2C message that contains the proper address begins I2C communication. For master operation, communication must be initiated by writing the Data register.






- 1. If general call is enabled, check to determine if the received address is a general call address (0x00). If the received address is a general call address, the general call must be handled by user software.
- 2. When 10-bit addressing addresses a slave, the slave sees an interrupt following the first byte of the extended address. Ensure that for this interrupt, the contents of the Data register are ignored and not treated as a valid data transfer.

Figure 48-42. Typical I2C Interrupt Routine



#### **ınınalization/Application Information**



#### Notes:

- 1. If general call or SIICAEN is enabled, check to determine if the received address is a general call address (0x00) or an SMBus device default address. In either case, they must be handled by user software.
- 2. In receive mode, one bit time delay may be needed before the first and second data reading.

Figure 48-43. Typical I2C SMBus Interrupt Routine



# Chapter 49 Universal Asynchronous Receiver/Transmitter (UART)

### 49.1 Introduction

### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The UART allows asynchronous serial communication with peripheral devices and CPUs.

### 49.1.1 Features

The UART includes these distinctive features:

- Full-duplex operation
- Standard mark/space non-return-to-zero (NRZ) format
- Selectable IrDA 1.4 return-to-zero-inverted (RZI) format with programmable pulse widths
- 13-bit baud rate selection with /32 fractional divide, based on module clock frequency
- Programmable 8-bit or 9-bit data format
- Separately enabled transmitter and receiver
- Programmable transmitter output polarity
- Programmable receive input polarity
- 13-bit break character option



#### muroduction

- 11-bit break character detection option
- Independent FIFO structure for transmit and receive
- Two receiver wakeup methods:
  - Idle line wakeup
  - Address mark wakeup
- Address match feature in receiver to reduce address mark wakeup ISR overhead
- Ability to select MSB or LSB to be first bit on wire
- Hardware flow control support for request to send (RTS) and clear to send (CTS) signals
- Support for ISO 7816 protocol for interfacing with SIM cards and smart cards
  - Support of T=0 and T=1 protocols
  - Automatic retransmission of NACK'd packets with programmable retry threshold
  - Support for 11 and 12 ETU transfers
  - Detection of initial packet and automated transfer parameter programming
  - Interrupt-driven operation with seven ISO-7816 specific interrupts
    - Wait time violated
    - Character wait time violated
    - Block wait time violated
    - Initial frame detected
    - Transmit error threshold exceeded
    - Receive error threshold exceeded
    - Guard time violated
- Interrupt-driven operation with 12 flags (not specific to ISO-7816 support):
  - Transmitter data buffer at or below watermark
  - Transmission complete
  - Receiver data buffer at or above watermark
  - Idle receiver input



- Receiver data buffer overrun
- Receiver data buffer underflow
- Transmit data buffer overflow
- Noise error
- Framing error
- Parity error
- Active edge on receive pin
- LIN break detect
- Receiver framing error detection
- Hardware parity generation and checking
- 1/16 bit-time noise detection
- DMA interface

# 49.1.2 Modes of operation

The UART functions the same in all the normal modes.

It has two low power modes: Wait and Stop modes.

# 49.1.2.1 Run mode

This is the normal mode of operation.

### 49.1.2.2 Wait mode

UART operation in wait mode depends on the state of the C1[UARTSWAI] bit.

- If the C1[UARTSWAI] bit is cleared, the UART operates normally when the CPU is in Wait mode.
- If the C1[UARTSWAI] bit is set, UART clock generation ceases and the UART module enters a power-conservation state when the CPU is in Wait mode.



### υΑπ Γ signal descriptions

The C1[UARTSWAI] bit does not initiate any power down or power up procedures for the smartcard (ISO-7816) interface.

Setting C1[UARTSWAI] does not affect the state of the C2[RE], or C2[TE].

If C1[UARTSWAI] is set, any transmission or reception in progress stops at Wait mode entry. The transmission or reception resumes when either an internal or external interrupt brings the CPU out of Wait mode. Exiting Wait mode by reset aborts any transmission or reception in progress and resets the UART.

# 49.1.2.3 Stop mode

The UART is inactive during stop mode for reduced power consumption. The STOP instruction does not affect the UART register states, but the UART module clock will be disabled. The UART operation resumes from where it left off after an external interrupt brings the CPU out of stop mode. Exiting stop mode by reset aborts any transmission or reception in progress and resets the UART. Entering or leaving stop mode does not initiate any power down or power up procedures for the smartcard (ISO-7816) interface.

# 49.2 UART signal descriptions

The UART signals are shown in the following table.

 Signal
 Description
 I/O

 CTS
 Clear to send
 I

 RTS
 Request to send
 O

 RXD
 Receive data
 I

 TXD
 Transmit data
 O

Table 49-1. UART signal descriptions

# 49.2.1 Detailed signal descriptions

The UART detailed signal descriptions are shown in the following table.



### Table 49-2. UART—Detailed signal descriptions

Signal	I/O		Description		
CTS	I	Clear to send. I	ndicates whether the UART can start to transmit data when flow control is enabled.		
		State meaning	tate meaning  Asserted—Data transmission can start.		
			Negated—Data transmission can not start.		
		Timing	Assertion—When transmitting device's RTS asserts.		
			Negation—When transmitting device's RTS deasserts.		
RTS	0		Request to send. When driven by the receiver, indicates whether the UART is ready to receive data. When driven by the transmitter, can enable an external transceiver during transmission.		
		State Meaning	Asserted—When driven by the receiver, ready to receive data. When driven by the transmitter, enable the external transmitter.		
			Negated—When driven by the receiver, not ready to receive data. When driven by the transmitter, disable the external transmitter.		
		Timing	Assertion—Can occur at any time; can assert asynchronously to the other input signals.		
			Negation—Can occur at any time; can deassert asynchronously to the other input signals.		
RXD	I		Receive data. Serial data input to receiver.		
		State meaning	Whether RXD is interpreted as a '1' or '0' depends on the bit encoding method along with other configuration settings.		
		Timing	Sampled at a frequency determined by the module clock divided by the baud rate.		
TXD	0		Transmit data. Serial data output from transmitter.		
		State meaning	Whether TXD is interpreted as a '1' or '0' depends on the bit encoding method along with other configuration settings.		
		Timing	Driven at the beginning or within a bit time according to the bit encoding method along with other configuration settings. Otherwise, transmissions are independent of reception timing.		

# 49.3 Memory map and registers

This section provides a detailed description of all memory and registers.

Accessing reserved addresses within the memory map will result in a transfer error. None of the contents of the implemented addresses will be modified as a result of that access.

Only byte accesses are supported.



# **UART** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_A000	UART Baud Rate Registers:High (UART0_BDH)	8	R/W	00h	49.3.1/ 1243
4006_A001	UART Baud Rate Registers: Low (UART0_BDL)	8	R/W	04h	49.3.2/ 1244
4006_A002	UART Control Register 1 (UART0_C1)	8	R/W	00h	49.3.3/ 1245
4006_A003	UART Control Register 2 (UART0_C2)	8	R/W	00h	49.3.4/ 1247
4006_A004	UART Status Register 1 (UART0_S1)	8	R	C0h	49.3.5/ 1249
4006_A005	UART Status Register 2 (UART0_S2)	8	R/W	00h	49.3.6/ 1252
4006_A006	UART Control Register 3 (UART0_C3)	8	R/W	00h	49.3.7/ 1254
4006_A007	UART Data Register (UART0_D)	8	R/W	00h	49.3.8/ 1255
4006_A008	UART Match Address Registers 1 (UART0_MA1)	8	R/W	00h	49.3.9/ 1257
4006_A009	UART Match Address Registers 2 (UART0_MA2)	8	R/W	00h	49.3.10/ 1257
4006_A00A	UART Control Register 4 (UART0_C4)	8	R/W	00h	49.3.11/ 1258
4006_A00B	UART Control Register 5 (UART0_C5)	8	R/W	00h	49.3.12/ 1259
4006_A00C	UART Extended Data Register (UART0_ED)	8	R	00h	49.3.13/ 1260
4006_A00D	UART Modem Register (UART0_MODEM)	8	R/W	00h	49.3.14/ 1261
4006_A00E	UART Infrared Register (UART0_IR)	8	R/W	00h	49.3.15/ 1262
4006_A010	UART FIFO Parameters (UART0_PFIFO)	8	R/W	See section	49.3.16/ 1263
4006_A011	UART FIFO Control Register (UART0_CFIFO)	8	R/W	00h	49.3.17/ 1265
4006_A012	UART FIFO Status Register (UART0_SFIFO)	8	R/W	C0h	49.3.18/ 1266
4006_A013	UART FIFO Transmit Watermark (UART0_TWFIFO)	8	R/W	00h	49.3.19/ 1267
4006_A014	UART FIFO Transmit Count (UART0_TCFIFO)	8	R	00h	49.3.20/ 1268





# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_A015	UART FIFO Receive Watermark (UART0_RWFIFO)	8	R/W	01h	49.3.21/ 1268
4006_A016	UART FIFO Receive Count (UART0_RCFIFO)	8	R	00h	49.3.22/ 1269
4006_A018	UART 7816 Control Register (UART0_C7816)	8	R/W	00h	49.3.23/ 1270
4006_A019	UART 7816 Interrupt Enable Register (UART0_IE7816)	8	R/W	00h	49.3.24/ 1271
4006_A01A	UART 7816 Interrupt Status Register (UART0_IS7816)	8	R/W	00h	49.3.25/ 1273
4006_A01B	UART 7816 Wait Parameter Register (UART0_WP7816T0)	8	R/W	0Ah	49.3.26/ 1275
4006_A01B	UART 7816 Wait Parameter Register (UART0_WP7816T1)	8	R/W	0Ah	49.3.27/ 1276
4006_A01C	UART 7816 Wait N Register (UART0_WN7816)	8	R/W	00h	49.3.28/ 1277
4006_A01D	UART 7816 Wait FD Register (UART0_WF7816)	8	R/W	01h	49.3.29/ 1277
4006_A01E	UART 7816 Error Threshold Register (UART0_ET7816)	8	R/W	00h	49.3.30/ 1278
4006_A01F	UART 7816 Transmit Length Register (UART0_TL7816)	8	R/W	00h	49.3.31/ 1279
4006_B000	UART Baud Rate Registers:High (UART1_BDH)	8	R/W	00h	49.3.1/ 1243
4006_B001	UART Baud Rate Registers: Low (UART1_BDL)	8	R/W	04h	49.3.2/ 1244
4006_B002	UART Control Register 1 (UART1_C1)	8	R/W	00h	49.3.3/ 1245
4006_B003	UART Control Register 2 (UART1_C2)	8	R/W	00h	49.3.4/ 1247
4006_B004	UART Status Register 1 (UART1_S1)	8	R	C0h	49.3.5/ 1249
4006_B005	UART Status Register 2 (UART1_S2)	8	R/W	00h	49.3.6/ 1252
4006_B006	UART Control Register 3 (UART1_C3)	8	R/W	00h	49.3.7/ 1254
4006_B007	UART Data Register (UART1_D)	8	R/W	00h	49.3.8/ 1255
4006_B008	UART Match Address Registers 1 (UART1_MA1)	8	R/W	00h	49.3.9/ 1257



# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_B009	UART Match Address Registers 2 (UART1_MA2)	8	R/W	00h	49.3.10/ 1257
4006_B00A	UART Control Register 4 (UART1_C4)	8	R/W	00h	49.3.11/ 1258
4006_B00B	UART Control Register 5 (UART1_C5)	8	R/W	00h	49.3.12/ 1259
4006_B00C	UART Extended Data Register (UART1_ED)	8	R	00h	49.3.13/ 1260
4006_B00D	UART Modem Register (UART1_MODEM)	8	R/W	00h	49.3.14/ 1261
4006_B00E	UART Infrared Register (UART1_IR)	8	R/W	00h	49.3.15/ 1262
4006_B010	UART FIFO Parameters (UART1_PFIFO)	8	R/W	See section	49.3.16/ 1263
4006_B011	UART FIFO Control Register (UART1_CFIFO)	8	R/W	00h	49.3.17/ 1265
4006_B012	UART FIFO Status Register (UART1_SFIFO)	8	R/W	C0h	49.3.18/ 1266
4006_B013	UART FIFO Transmit Watermark (UART1_TWFIFO)	8	R/W	00h	49.3.19/ 1267
4006_B014	UART FIFO Transmit Count (UART1_TCFIFO)	8	R	00h	49.3.20/ 1268
4006_B015	UART FIFO Receive Watermark (UART1_RWFIFO)	8	R/W	01h	49.3.21/ 1268
4006_B016	UART FIFO Receive Count (UART1_RCFIFO)	8	R	00h	49.3.22/ 1269
4006_B018	UART 7816 Control Register (UART1_C7816)	8	R/W	00h	49.3.23/ 1270
4006_B019	UART 7816 Interrupt Enable Register (UART1_IE7816)	8	R/W	00h	49.3.24/ 1271
4006_B01A	UART 7816 Interrupt Status Register (UART1_IS7816)	8	R/W	00h	49.3.25/ 1273
4006_B01B	UART 7816 Wait Parameter Register (UART1_WP7816T0)	8	R/W	0Ah	49.3.26/ 1275
4006_B01B	UART 7816 Wait Parameter Register (UART1_WP7816T1)	8	R/W	0Ah	49.3.27/ 1276
4006_B01C	UART 7816 Wait N Register (UART1_WN7816)	8	R/W	00h	49.3.28/ 1277
4006_B01D	UART 7816 Wait FD Register (UART1_WF7816)	8	R/W	01h	49.3.29/ 1277





# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_B01E	UART 7816 Error Threshold Register (UART1_ET7816)	8	R/W	00h	49.3.30/ 1278
4006_B01F	UART 7816 Transmit Length Register (UART1_TL7816)	8	R/W	00h	49.3.31/ 1279
4006_C000	UART Baud Rate Registers:High (UART2_BDH)	8	R/W	00h	49.3.1/ 1243
4006_C001	UART Baud Rate Registers: Low (UART2_BDL)	8	R/W	04h	49.3.2/ 1244
4006_C002	UART Control Register 1 (UART2_C1)	8	R/W	00h	49.3.3/ 1245
4006_C003	UART Control Register 2 (UART2_C2)	8	R/W	00h	49.3.4/ 1247
4006_C004	UART Status Register 1 (UART2_S1)	8	R	C0h	49.3.5/ 1249
4006_C005	UART Status Register 2 (UART2_S2)	8	R/W	00h	49.3.6/ 1252
4006_C006	UART Control Register 3 (UART2_C3)	8	R/W	00h	49.3.7/ 1254
4006_C007	UART Data Register (UART2_D)	8	R/W	00h	49.3.8/ 1255
4006_C008	UART Match Address Registers 1 (UART2_MA1)	8	R/W	00h	49.3.9/ 1257
4006_C009	UART Match Address Registers 2 (UART2_MA2)	8	R/W	00h	49.3.10/ 1257
4006_C00A	UART Control Register 4 (UART2_C4)	8	R/W	00h	49.3.11/ 1258
4006_C00B	UART Control Register 5 (UART2_C5)	8	R/W	00h	49.3.12/ 1259
4006_C00C	UART Extended Data Register (UART2_ED)	8	R	00h	49.3.13/ 1260
4006_C00D	UART Modem Register (UART2_MODEM)	8	R/W	00h	49.3.14/ 1261
4006_C00E	UART Infrared Register (UART2_IR)	8	R/W	00h	49.3.15/ 1262
4006_C010	UART FIFO Parameters (UART2_PFIFO)	8	R/W	See section	49.3.16/ 1263
4006_C011	UART FIFO Control Register (UART2_CFIFO)	8	R/W	00h	49.3.17/ 1265
4006_C012	UART FIFO Status Register (UART2_SFIFO)	8	R/W	C0h	49.3.18/ 1266



# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_C013	UART FIFO Transmit Watermark (UART2_TWFIFO)	8	R/W	00h	49.3.19/ 1267
4006_C014	UART FIFO Transmit Count (UART2_TCFIFO)	8	R	00h	49.3.20/ 1268
4006_C015	UART FIFO Receive Watermark (UART2_RWFIFO)	8	R/W	01h	49.3.21/ 1268
4006_C016	UART FIFO Receive Count (UART2_RCFIFO)	8	R	00h	49.3.22/ 1269
4006_C018	UART 7816 Control Register (UART2_C7816)	8	R/W	00h	49.3.23/ 1270
4006_C019	UART 7816 Interrupt Enable Register (UART2_IE7816)	8	R/W	00h	49.3.24/ 1271
4006_C01A	UART 7816 Interrupt Status Register (UART2_IS7816)	8	R/W	00h	49.3.25/ 1273
4006_C01B	UART 7816 Wait Parameter Register (UART2_WP7816T0)	8	R/W	0Ah	49.3.26/ 1275
4006_C01B	UART 7816 Wait Parameter Register (UART2_WP7816T1)	8	R/W	0Ah	49.3.27/ 1276
4006_C01C	UART 7816 Wait N Register (UART2_WN7816)	8	R/W	00h	49.3.28/ 1277
4006_C01D	UART 7816 Wait FD Register (UART2_WF7816)	8	R/W	01h	49.3.29/ 1277
4006_C01E	UART 7816 Error Threshold Register (UART2_ET7816)	8	R/W	00h	49.3.30/ 1278
4006_C01F	UART 7816 Transmit Length Register (UART2_TL7816)	8	R/W	00h	49.3.31/ 1279
4006_D000	UART Baud Rate Registers:High (UART3_BDH)	8	R/W	00h	49.3.1/ 1243
4006_D001	UART Baud Rate Registers: Low (UART3_BDL)	8	R/W	04h	49.3.2/ 1244
4006_D002	UART Control Register 1 (UART3_C1)	8	R/W	00h	49.3.3/ 1245
4006_D003	UART Control Register 2 (UART3_C2)	8	R/W	00h	49.3.4/ 1247
4006_D004	UART Status Register 1 (UART3_S1)	8	R	C0h	49.3.5/ 1249
4006_D005	UART Status Register 2 (UART3_S2)	8	R/W	00h	49.3.6/ 1252
4006_D006	UART Control Register 3 (UART3_C3)	8	R/W	00h	49.3.7/ 1254





# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_D007	UART Data Register (UART3_D)	8	R/W	00h	49.3.8/ 1255
4006_D008	UART Match Address Registers 1 (UART3_MA1)	8	R/W	00h	49.3.9/ 1257
4006_D009	UART Match Address Registers 2 (UART3_MA2)	8	R/W	00h	49.3.10/ 1257
4006_D00A	UART Control Register 4 (UART3_C4)	8	R/W	00h	49.3.11/ 1258
4006_D00B	UART Control Register 5 (UART3_C5)	8	R/W	00h	49.3.12/ 1259
4006_D00C	UART Extended Data Register (UART3_ED)	8	R	00h	49.3.13/ 1260
4006_D00D	UART Modem Register (UART3_MODEM)	8	R/W	00h	49.3.14/ 1261
4006_D00E	UART Infrared Register (UART3_IR)	8	R/W	00h	49.3.15/ 1262
4006_D010	UART FIFO Parameters (UART3_PFIFO)	8	R/W	See section	49.3.16/ 1263
4006_D011	UART FIFO Control Register (UART3_CFIFO)	8	R/W	00h	49.3.17/ 1265
4006_D012	UART FIFO Status Register (UART3_SFIFO)	8	R/W	C0h	49.3.18/ 1266
4006_D013	UART FIFO Transmit Watermark (UART3_TWFIFO)	8	R/W	00h	49.3.19/ 1267
4006_D014	UART FIFO Transmit Count (UART3_TCFIFO)	8	R	00h	49.3.20/ 1268
4006_D015	UART FIFO Receive Watermark (UART3_RWFIFO)	8	R/W	01h	49.3.21/ 1268
4006_D016	UART FIFO Receive Count (UART3_RCFIFO)	8	R	00h	49.3.22/ 1269
4006_D018	UART 7816 Control Register (UART3_C7816)	8	R/W	00h	49.3.23/ 1270
4006_D019	UART 7816 Interrupt Enable Register (UART3_IE7816)	8	R/W	00h	49.3.24/ 1271
4006_D01A	UART 7816 Interrupt Status Register (UART3_IS7816)	8	R/W	00h	49.3.25/ 1273
4006_D01B	UART 7816 Wait Parameter Register (UART3_WP7816T0)	8	R/W	0Ah	49.3.26/ 1275
4006_D01B	UART 7816 Wait Parameter Register (UART3_WP7816T1)	8	R/W	0Ah	49.3.27/ 1276



# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4006_D01C	UART 7816 Wait N Register (UART3_WN7816)	8	R/W	00h	49.3.28/ 1277
4006_D01D	UART 7816 Wait FD Register (UART3_WF7816)	8	R/W	01h	49.3.29/ 1277
4006_D01E	UART 7816 Error Threshold Register (UART3_ET7816)	8	R/W	00h	49.3.30/ 1278
4006_D01F	UART 7816 Transmit Length Register (UART3_TL7816)	8	R/W	00h	49.3.31/ 1279
400E_A000	UART Baud Rate Registers:High (UART4_BDH)	8	R/W	00h	49.3.1/ 1243
400E_A001	UART Baud Rate Registers: Low (UART4_BDL)	8	R/W	04h	49.3.2/ 1244
400E_A002	UART Control Register 1 (UART4_C1)	8	R/W	00h	49.3.3/ 1245
400E_A003	UART Control Register 2 (UART4_C2)	8	R/W	00h	49.3.4/ 1247
400E_A004	UART Status Register 1 (UART4_S1)	8	R	C0h	49.3.5/ 1249
400E_A005	UART Status Register 2 (UART4_S2)	8	R/W	00h	49.3.6/ 1252
400E_A006	UART Control Register 3 (UART4_C3)	8	R/W	00h	49.3.7/ 1254
400E_A007	UART Data Register (UART4_D)	8	R/W	00h	49.3.8/ 1255
400E_A008	UART Match Address Registers 1 (UART4_MA1)	8	R/W	00h	49.3.9/ 1257
400E_A009	UART Match Address Registers 2 (UART4_MA2)	8	R/W	00h	49.3.10/ 1257
400E_A00A	UART Control Register 4 (UART4_C4)	8	R/W	00h	49.3.11/ 1258
400E_A00B	UART Control Register 5 (UART4_C5)	8	R/W	00h	49.3.12/ 1259
400E_A00C	UART Extended Data Register (UART4_ED)	8	R	00h	49.3.13/ 1260
400E_A00D	UART Modem Register (UART4_MODEM)	8	R/W	00h	49.3.14/ 1261
400E_A00E	UART Infrared Register (UART4_IR)	8	R/W	00h	49.3.15/ 1262
400E_A010	UART FIFO Parameters (UART4_PFIFO)	8	R/W	See section	49.3.16/ 1263





# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400E_A011	UART FIFO Control Register (UART4_CFIFO)	8	R/W	00h	49.3.17/ 1265
400E_A012	UART FIFO Status Register (UART4_SFIFO)	8	R/W	C0h	49.3.18/ 1266
400E_A013	UART FIFO Transmit Watermark (UART4_TWFIFO)	8	R/W	00h	49.3.19/ 1267
400E_A014	UART FIFO Transmit Count (UART4_TCFIFO)	8	R	00h	49.3.20/ 1268
400E_A015	UART FIFO Receive Watermark (UART4_RWFIFO)	8	R/W	01h	49.3.21/ 1268
400E_A016	UART FIFO Receive Count (UART4_RCFIFO)	8	R	00h	49.3.22/ 1269
400E_A018	UART 7816 Control Register (UART4_C7816)	8	R/W	00h	49.3.23/ 1270
400E_A019	UART 7816 Interrupt Enable Register (UART4_IE7816)	8	R/W	00h	49.3.24/ 1271
400E_A01A	UART 7816 Interrupt Status Register (UART4_IS7816)	8	R/W	00h	49.3.25/ 1273
400E_A01B	UART 7816 Wait Parameter Register (UART4_WP7816T0)	8	R/W	0Ah	49.3.26/ 1275
400E_A01B	UART 7816 Wait Parameter Register (UART4_WP7816T1)	8	R/W	0Ah	49.3.27/ 1276
400E_A01C	UART 7816 Wait N Register (UART4_WN7816)	8	R/W	00h	49.3.28/ 1277
400E_A01D	UART 7816 Wait FD Register (UART4_WF7816)	8	R/W	01h	49.3.29/ 1277
400E_A01E	UART 7816 Error Threshold Register (UART4_ET7816)	8	R/W	00h	49.3.30/ 1278
400E_A01F	UART 7816 Transmit Length Register (UART4_TL7816)	8	R/W	00h	49.3.31/ 1279
400E_B000	UART Baud Rate Registers:High (UART5_BDH)	8	R/W	00h	49.3.1/ 1243
400E_B001	UART Baud Rate Registers: Low (UART5_BDL)	8	R/W	04h	49.3.2/ 1244
400E_B002	UART Control Register 1 (UART5_C1)	8	R/W	00h	49.3.3/ 1245
400E_B003	UART Control Register 2 (UART5_C2)	8	R/W	00h	49.3.4/ 1247
400E_B004	UART Status Register 1 (UART5_S1)	8	R	C0h	49.3.5/ 1249



# **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400E_B005	UART Status Register 2 (UART5_S2)	8	R/W	00h	49.3.6/ 1252
400E_B006	UART Control Register 3 (UART5_C3)	8	R/W	00h	49.3.7/ 1254
400E_B007	UART Data Register (UART5_D)	8	R/W	00h	49.3.8/ 1255
400E_B008	UART Match Address Registers 1 (UART5_MA1)	8	R/W	00h	49.3.9/ 1257
400E_B009	UART Match Address Registers 2 (UART5_MA2)	8	R/W	00h	49.3.10/ 1257
400E_B00A	UART Control Register 4 (UART5_C4)	8	R/W	00h	49.3.11/ 1258
400E_B00B	UART Control Register 5 (UART5_C5)	8	R/W	00h	49.3.12/ 1259
400E_B00C	UART Extended Data Register (UART5_ED)	8	R	00h	49.3.13/ 1260
400E_B00D	UART Modem Register (UART5_MODEM)	8	R/W	00h	49.3.14/ 1261
400E_B00E	UART Infrared Register (UART5_IR)	8	R/W	00h	49.3.15/ 1262
400E_B010	UART FIFO Parameters (UART5_PFIFO)	8	R/W	See section	49.3.16/ 1263
400E_B011	UART FIFO Control Register (UART5_CFIFO)	8	R/W	00h	49.3.17/ 1265
400E_B012	UART FIFO Status Register (UART5_SFIFO)	8	R/W	C0h	49.3.18/ 1266
400E_B013	UART FIFO Transmit Watermark (UART5_TWFIFO)	8	R/W	00h	49.3.19/ 1267
400E_B014	UART FIFO Transmit Count (UART5_TCFIFO)	8	R	00h	49.3.20/ 1268
400E_B015	UART FIFO Receive Watermark (UART5_RWFIFO)	8	R/W	01h	49.3.21/ 1268
400E_B016	UART FIFO Receive Count (UART5_RCFIFO)	8	R	00h	49.3.22/ 1269
400E_B018	UART 7816 Control Register (UART5_C7816)	8	R/W	00h	49.3.23/ 1270
400E_B019	UART 7816 Interrupt Enable Register (UART5_IE7816)	8	R/W	00h	49.3.24/ 1271
400E_B01A	UART 7816 Interrupt Status Register (UART5_IS7816)	8	R/W	00h	49.3.25/ 1273



### **UART** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400E_B01B	UART 7816 Wait Parameter Register (UART5_WP7816T0)	8	R/W	0Ah	49.3.26/ 1275
400E_B01B	UART 7816 Wait Parameter Register (UART5_WP7816T1)	8	R/W	0Ah	49.3.27/ 1276
400E_B01C	UART 7816 Wait N Register (UART5_WN7816)	8	R/W	00h	49.3.28/ 1277
400E_B01D	UART 7816 Wait FD Register (UART5_WF7816)	8	R/W	01h	49.3.29/ 1277
400E_B01E	UART 7816 Error Threshold Register (UART5_ET7816)	8	R/W	00h	49.3.30/ 1278
400E_B01F	UART 7816 Transmit Length Register (UART5_TL7816)	8	R/W	00h	49.3.31/ 1279

# 49.3.1 UART Baud Rate Registers: High (UARTx\_BDH)

This register, along with the BDL register, controls the prescale divisor for UART baud rate generation. To update the 13-bit baud rate setting (SBR[12:0]), first write to BDH to buffer the high half of the new value and then write to BDL. The working value in BDH does not change until BDL is written.

BDL is reset to a non-zero value, but after reset the baud rate generator remains disabled until the first time the receiver or transmitter is enabled (C2[RE] or C2[TE] bits are set).

Addresses: UART0\_BDH is 4006\_A000h base + 0h offset = 4006\_A000h

UART1\_BDH is 4006\_B000h base + 0h offset = 4006\_B000h

UART2\_BDH is 4006\_C000h base + 0h offset = 4006\_C000h

UART3\_BDH is 4006\_D000h base + 0h offset = 4006\_D000h

UART4\_BDH is 400E\_A000h base + 0h offset = 400E\_A000h

UART5\_BDH is 400E\_B000h base + 0h offset = 400E\_B000h

Bit 7 6 5 4 3 2 1 0

Read UBKDIE RXEDGIE SBR

### **UARTx\_BDH** field descriptions

Field	Description
7 LBKDIE	LIN Break Detect Interrupt Enable
	LBKDIE enables the LIN break detect flag, LBKDIF, to generate interrupt requests based on the state of LBKDDMAS.




### **UARTx\_BDH** field descriptions (continued)

Field	Description				
	LBKDIF interrupt requests disabled.				
	1 LBKDIF interrupt requests enabled.				
6 RXEDGIE	RxD Input Active Edge Interrupt Enable				
	RXEDGIE enables the Receive input active edge, RXEDGIF, to generate interrupt requests.				
	0 Hardware interrupts from RXEDGIF disabled (use polling).				
	1 RXEDGIF interrupt request enabled.				
5 Reserved	This read-only field is reserved and always has the value zero.				
4–0 SBR	UART Baud Rate Bits				
OBIT	The baud rate for the UART is determined by these 13 bits. See Baud rate generation for details.				
	<b>NOTE:</b> The baud rate generator is disabled until the C2[TE] bit or the C2[RE] bit is set for the first time after reset. The baud rate generator is disabled when SBR = 0.				
	NOTE: Writing to BDH has no effect without writing to BDL, since writing to BDH puts the data in a temporary location until BDL is written.				

## 49.3.2 UART Baud Rate Registers: Low (UARTx\_BDL)

This register, along with the BDH register, controls the prescale divisor for UART baud rate generation. To update the 13-bit baud rate setting (SBR[12:0]), first write to BDH to buffer the high half of the new value and then write to BDL. The working value in BDH does not change until BDL is written. BDL is reset to a non-zero value, but after reset the baud rate generator remains disabled until the first time the receiver or transmitter is enabled (C2[RE] or C2[TE] bits are set)





### **UARTx\_BDL** field descriptions

Field	Description					
7–0 SBR	UART Baud Rate Bits					
	The baud rate for the UART is determined by these 13 bits. See Baud rate generation for details					
	<b>NOTE:</b> The baud rate generator is disabled until the C2[TE] bit or the C2[RE] bit is set for the first time after reset. The baud rate generator is disabled when SBR = 0.					
	NOTE: Writing to BDH has no effect without writing to BDL, since writing to BDH puts the data in a temporary location until BDL is written.					
	NOTE: When the 1/32 narrow pulse width is selected for infrared (IrDA), the baud rate bits must be even, the least significant bit is 0. Refer to MODEM register.					

# 49.3.3 UART Control Register 1 (UARTx\_C1)

This read/write register controls various optional features of the UART system.

Addresses: UART0\_C1 is 4006\_A000h base + 2h offset = 4006\_A002h

UART1\_C1 is 4006\_B000h base + 2h offset = 4006\_B002h

UART2\_C1 is 4006\_C000h base + 2h offset = 4006\_C002h

UART3\_C1 is 4006\_D000h base + 2h offset = 4006\_D002h

UART4\_C1 is 400E\_A000h base + 2h offset = 400E\_A002h

UART5\_C1 is 400E\_B000h base + 2h offset = 400E\_B002h

Bit	7	6	5	4	3	2	1	0
Read								
Write	LOOPS	UARTSWAI	RSRC	М	WAKE	ILT	PE	PT
Reset	0	0	0	0	0	0	0	0

# **UARTx\_C1** field descriptions

Field	Description
7 LOOPS	Loop Mode Select
200.0	When LOOPS is set, the RxD pin is disconnected from the UART and the transmitter output is internally connected to the receiver input. The transmitter and the receiver must be enabled to use the loop function.
	0 Normal operation.
	1 Loop mode where transmitter output is internally connected to receiver input. The receiver input is determined by the RSRC bit.
6 UARTSWAI	UART Stops in Wait Mode
07111107711	0 UART clock continues to run in wait mode.
	1 UART clock freezes while CPU is in wait mode.
5 RSRC	Receiver Source Select
	This bit has no meaning or effect unless the LOOPS bit is set. When LOOPS is set, the RSRC bit determines the source for the receiver shift register input.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# **UARTx\_C1** field descriptions (continued)

Field	Description
	0 Selects internal loop back mode and receiver input is internally connected to transmitter output.
	1 Single-wire UART mode where the receiver input is connected to the transmit pin input signal.
4 M	9-bit or 8-bit Mode Select
	This bit must be set when 7816E is set/enabled.
	<ul> <li>Normal - start + 8 data bits (MSB/LSB first as determined by MSBF) + stop.</li> <li>Use - start + 9 data bits (MSB/LSB first as determined by MSBF) + stop.</li> </ul>
3 WAKE	Receiver Wakeup Method Select
	WAKE determines which condition wakes the UART: address mark in the most significant bit position of a received data character or an idle condition on the receive pin input signal.
	0 Idle-line wakeup.
	1 Address-mark wakeup.
2 ILT	Idle Line Type Select
	ILT determines when the receiver starts counting logic 1s as idle character bits. The counting begins either after a valid start bit or after the stop bit. If the count begins after the start bit, then a string of logic 1s preceding the stop bit can cause false recognition of an idle character. Beginning the count after the stop bit avoids false idle character recognition, but requires properly synchronized transmissions.
	<b>NOTE:</b> In the case where UART is programmed with ILT = 1, a logic of 1'b0 is automatically shifted after a received stop bit thus resetting the idle count.
	NOTE: In the case where UART is programmed for IDLE line wakeup (RWU = 1 and WAKE = 0), ILT has no effect on when the receiver starts counting logic 1s as idle character bits. In idle line wakeup an idle character is recognized at anytime the receiver sees 10, 11, or 12 1s depending on the M, PE, and C4[M10] bits.
	<ul> <li>0 Idle character bit count starts after start bit.</li> <li>1 Idle character bit count starts after stop bit.</li> </ul>
1	Parity Enable
PE	Enables the parity function. When parity is enabled, parity function inserts a parity bit in the bit position
	immediately preceding the stop bit. This bit must be set when 7816E is set/enabled.
	0 Parity function disabled.
	1 Parity function enabled.
0 PT	Parity Type
	PT determines whether the UART generates and checks for even parity or odd parity. With even parity, an even number of 1s clears the parity bit and an odd number of 1s sets the parity bit. With odd parity, an odd number of 1s clears the parity bit and an even number of 1s sets the parity bit. This bit must be cleared when 7816E is set/enabled.
	0 Even parity.
	1 Odd parity.



# 49.3.4 UART Control Register 2 (UARTx\_C2)

This register can be read or written at any time.

Addresses: UART0\_C2 is 4006\_A000h base + 3h offset = 4006\_A003h

UART1\_C2 is 4006\_B000h base + 3h offset = 4006\_B003h

UART2\_C2 is 4006\_C000h base + 3h offset = 4006\_C003h

UART3\_C2 is 4006\_D000h base + 3h offset = 4006\_D003h

UART4\_C2 is 400E\_A000h base + 3h offset = 400E\_A003h

UART5\_C2 is 400E\_B000h base + 3h offset = 400E\_B003h

Bit	7	6	5	4	3	2	1	0
Read	TIE	TCIE	RIE	ILIE	TE	RE	RWU	SBK
Write	116	TOIL	1111	ILIL	16	11.	11000	ODIC
Reset	0	0	0	0	0	0	0	0

### **UARTx\_C2** field descriptions

Field	Description
7 TIE	Transmitter Interrupt or DMA Transfer Enable.
1112	TIE enables the S1[TDRE] flag, to generate interrupt requests or DMA transfer requests, based on the state of C5[TDMAS].
	NOTE: If C2[TIE] and C5[TDMAS] are both set, then TCIE must be cleared, and D[D] must not be written outside of servicing of a DMA request.
	0 TDRE interrupt and DMA transfer requests disabled.
	1 TDRE interrupt or DMA transfer requests enabled.
6 TCIE	Transmission Complete Interrupt Enable
TOIL	TCIE enables the transmission complete flag, S1[TC], to generate interrupt requests.
	0 TC interrupt requests disabled.
	1 TC interrupt requests enabled.
5	Receiver Full Interrupt or DMA Transfer Enable
RIE	RIE enables the S1[RDRF] flag, to generate interrupt requests or DMA transfer requests, based on the state of C5[RDMAS].
	0 RDRF interrupt and DMA transfer requests disabled.
	1 RDRF interrupt or DMA transfer requests enabled
4 ILIE	Idle Line Interrupt Enable
ILIE	ILIE enables the idle line flag, S1[IDLE], to generate interrupt requests, based on the state of C5[ILDMAS].
	0 IDLE interrupt requests disabled.
	1 IDLE interrupt requests enabled.



# **UARTx\_C2** field descriptions (continued)

Field	Description
3 TE	Transmitter Enable  TE enables the UART transmitter. The TE bit can be used to queue an idle preamble by clearing and then setting the TE bit. When 7816E is set/enabled and C7816[TTYPE] = 1, this bit is automatically cleared after the requested block has been transmitted. This condition is detected when TL7816[TLEN] = 0 and
	four additional characters have been transmitted.  O Transmitter off.
	1 Transmitter on.
2 RE	Receiver Enable
	RE enables the UART receiver.
	<ul><li>0 Receiver off.</li><li>1 Receiver on.</li></ul>
1 RWU	Receiver Wakeup Control
	This bit can be set to place the UART receiver in a standby state. RWU automatically clears when an RWU event occurs (an IDLE event when C1[WAKE] is clear or an address match when C1[WAKE] is set). This bit must be cleared when 7816E is set.
	NOTE: RWU should only be set with C1[WAKE] = 0 (wakeup on idle) if the channel is currently not idle. This can be determined by the S2[RAF] flag. If set to wake up an IDLE event and the channel is already idle, it is possible that the UART will discard data since data must be received (or a LIN break detect) after an IDLE is detected before IDLE is allowed to reasserted.
	<ul> <li>Normal operation.</li> <li>RWU enables the wakeup function and inhibits further receiver interrupt requests. Normally, hardware wakes the receiver by automatically clearing RWU.</li> </ul>
0 SBK	Send Break
SDN	Toggling SBK sends one break character (10, 11, or 12 logic 0s, if S2[BRK13] is cleared; 13 or 14 logic 0s, if S2[BRK13] is set). See Transmitting break characters for the number of logic 0s for the different configurations. Toggling implies clearing the SBK bit before the break character has finished transmitting. As long as SBK is set, the transmitter continues to send complete break characters (10, 11, or 12 bits, or 13 or 14 bits). This bit must be cleared when 7816E is set.
	<ul><li>0 Normal transmitter operation.</li><li>1 Queue break character(s) to be sent.</li></ul>
	I Queue break character(s) to be sent.



# 49.3.5 UART Status Register 1 (UARTx\_S1)

The S1 register provides inputs to the MCU for generation of UART interrupts or DMA requests. This register can also be polled by the MCU to check the status of these bits. To clear a flag, the status register should be read followed by a read or write (depending on interrupt flag type) to the UART Data Register. Other instructions can be executed between the two steps as long as it does not compromise the handling of I/O, but the order of operations is important for flag clearing. When a flag is configured to trigger a DMA request, assertion of the associated DMA done signal from the DMA controller, clears the flag.

### **NOTE**

If the condition that results in the assertion of the flag, interrupt or DMA request is not resolved prior to clearing the flag, the flag (and interrupt/DMA request) will reassert. For example, if the DMA or interrupt service routine failed to write sufficient data to the transmit buffer to raise it above the watermark level, the flag will reassert and generate another interrupt or DMA request.

### NOTE

Reading an empty data register to clear one of these flags causes the FIFO pointers to get out of alignment. A receive FIFO flush reinitializes the pointers.

Addresses: UART0\_S1 is 4006\_A000h base + 4h offset = 4006\_A004h

UART1\_S1 is 4006\_B000h base + 4h offset = 4006\_B004h

UART2\_S1 is 4006\_C000h base + 4h offset = 4006\_C004h

UART3\_S1 is 4006\_D000h base + 4h offset = 4006\_D004h

UART4\_S1 is 400E\_A000h base + 4h offset = 400E\_A004h

UART5\_S1 is 400E\_B000h base + 4h offset = 400E\_B004h

Bit 7 6 5 4 3 2 1

Read TDRE TC RDRF IDLE OR NF FE

Bit	7	6	5	4	3	2	1	0
Read	TDRE	TC	RDRF	IDLE	OR	NF	FE	PF
Write								
Reset	1	1	0	0	0	0	0	0

### **UARTx\_S1** field descriptions

Field	Description
7 TDRE	Transmit Data Register Empty Flag
	TDRE will set when the number of datawords in the transmit buffer (D and C3[T8])is equal to or less than the number indicated by TWFIFO[TXWATER]. A character that is in the process of being transmitted is not included in the count. To clear TDRE, read S1 when TDRE is set and then write to the UART data



# **UARTx\_S1** field descriptions (continued)

Field	Description
	register (D). For more efficient interrupt servicing all data except the final value to be written to the buffer should written to D/C3[T8]. Then S1 can be read before writing the final data value, resulting in the clearing of the TRDE flag. This is more efficient since the TDRE will reassert until the watermark has been exceeded so attempting to clear the TDRE every write will be ineffective until sufficient data has been written.
	<ul> <li>The amount of data in the transmit buffer is greater than the value indicated by TWFIFO[TXWATER].</li> <li>The amount of data in the transmit buffer is less than or equal to the value indicated by TWFIFO[TXWATER] at some point in time since the flag has been cleared.</li> </ul>
6 TC	Transmit Complete Flag
10	TC is cleared when there is a transmission in progress or when a preamble or break character is loaded. TC is set when the transmit buffer is empty and no data, preamble, or break character is being transmitted. When TC is set, the transmit data output signal becomes idle (logic 1). When 7816E is set/enabled this bit is set after any NACK signal has been received but prior to any corresponding guard times expiring. TC is cleared by reading S1 with TC set and then doing one of the following:  • Writing to the UART data register (D) to transmit new data  • Queuing a preamble by clearing and then setting the C2[TE] bit.  • Queuing a break character by writing 1 to SBK in C2
	O Transmitter active (sending data, a preamble, or a break).  Transmitter idla (transmission activity complete).
5 RDRF	Transmitter idle (transmission activity complete).  Receive Data Register Full Flag
	RDRF is set when the number of datawords in the receive buffer is equal to or more than the number indicated by RWFIFO[RXWATER]. A dataword that is in the process of being received is not included in the count. RDRF is prevented from setting while S2[LBKDE] is set. Additionally, when S2[LBKDE] is set, datawords that are received will be stored in the receive buffer but will over-write each other. To clear RDRF, read S1 when RDRF is set and then read the UART data register (D). For more efficient interrupt and DMA operation all data except the final value is to be read from the buffer using D/C3[T8]/ED. The S1 should then be read and the final data value read, resulting in the clearing of the RDRF flag. Even if the RDRF flag is set, data will continue to be received until an overrun condition occurs.
	0 The number of datawords in the receive buffer is less than the number indicated by RXWATER.
	1 The number of datawords in the receive buffer is equal to or greater than the number indicated by RXWATER at some point in time since this flag was last cleared.
4 IDLE	Idle Line Flag
IDLE	IDLE is set when 10 consecutive logic 1s (if C1[M] = 0), 11 consecutive logic 1s (if C1[M] = 1 and C4[M10 = 0), or 12 consecutive logic 1s (if C1[M] = 1, C4[M10] = 1, and C1[PE] = 1) appear on the receiver input. After the IDLE flag is cleared, a frame must be received (although not necessarily stored in the data buffer, for example if C2[RWU] is set) or a LIN break character must set the S2[LBKDIF] flag before an idle condition can set the IDLE flag. To clear IDLE, read UART status S1 with IDLE set and then read D. Idle detection is not supported when 7816E is set/enabled and hence this flag is ignored.
	<b>NOTE:</b> When the receiver wakeup bit (RWU) is set and WAKE is cleared, an idle line condition sets the IDLE flag if RWUID is set, else the IDLE flag does not get set.
	<ul> <li>Receiver input is either active now or has never become active since the IDLE flag was last cleared.</li> <li>Receiver input has become idle or the flag has not been cleared since it last asserted.</li> </ul>
3 OR	Receiver Overrun Flag






# **UARTx\_S1** field descriptions (continued)

Field	Description
	OR is set when software fails to prevent the receive data register from overflowing with data. The OR bit is set immediately after the stop bit has been completely received for the dataword that overflows the buffer and all the other error flags (FE,NF and PF) are prevented from setting. The data in the shift register is lost, but the data already in the UART data registers is not affected. If the OR flag is set, no data will be stored in the data buffer even if sufficient room exists. Additionally, while the OR flag is set the RDRF flag, and IDLE flags will be blocked from asserting, i.e. transition from an inactive to an active state. To clear OR, read S1 when OR is set and then read UART data register (D). If LBKDE is enabled and a LIN Break is detected, the OR bit will assert if the S2[LBKDIF] flag is not cleared before the next data character is received. See Overrun (OR) flag implications for more details regarding the operation of the OR bit. In 7816 mode, it is possible to configure a NACK to be returned by programing the C7816[ONACK] bit.  O No overrun has occurred since the last time the flag was cleared.
0	1 Overrun has occurred or the overrun flag has not been cleared since the last overrun occured.
2 NF	NF is set when the UART detects noise on the receiver input. NF bit does not get set in the case of an overrun or while the LIN break detect feature is enabled (S2[LBKDE] = 1). When NF is set, it only indicates that a dataword has been received with noise since the last time it was cleared. There is no guarantee that the first dataword read from the receive buffer has noise or that there is only one dataword in the buffer that was received with noise unless the receive buffer has a depth of one. To clear NF, read S1 and then read the UART data register (D).
	<ul> <li>No noise detected since the last time this flag was cleared. If the receive buffer has a depth greater than 1 then there may be data in the receiver buffer that was received with noise.</li> <li>At least one dataword was received with noise detected since the last time the flag was cleared.</li> </ul>
1	Framing Error Flag
FE	FE is set when a logic 0 is accepted as the stop bit. FE bit does not set in the case of an overrun or while the LIN break detect feature is enabled (S2[LBKDE] = 1). FE inhibits further data reception until it is cleared. To clear FE, read S1 with FE set and then read the UART data register (D). The last data in the receive buffer represents the data that was received with the frame error enabled. However, framing errors are not supported when 7816E is set/enabled. However, if this flag is set, data will still not be received in 7816 mode.
	<ul><li>No framing error detected.</li><li>Framing error.</li></ul>
0 PF	Parity Error Flag  PF is set when PE is set, S2[LBKDE] is disabled, and the parity of the received data does not match its parity bit. The PF is not set in the case of an overrun condition. When the PF bit is set it only indicates that a dataword was received with parity error since the last time it was cleared. There is no guarantee that the first dataword read from the receive buffer has a parity error or that there is only one dataword in the buffer that was received with a parity error unless the receive buffer was a depth of one. To clear PF, read S1 and then read the UART data register (D). Within the receive buffer structure the received dataword is tagged if it was received with a parity error. That information is available by reading the ED register prior to reading the D register.  O No parity error has been detected since the last time this flag was cleared. If the receive buffer has a depth greater than 1 then there may be data in the receive buffer what was received with a parity error.  At least one dataword was received with a parity error since the last time this flag was cleared.



# 49.3.6 UART Status Register 2 (UARTx\_S2)

The S2 register provides inputs to the MCU for generation of UART interrupts or DMA requests. Also, this register can be polled by the MCU to check the status of these bits. This register can be read or written at any time, with the exception of the MSBF and RXINV bits which should only be changed by the user between transmit and receive packets.



### **UARTx\_S2** field descriptions

Field	Description			
7 LBKDIF	LIN Break Detect Interrupt Flag			
	LBKDIF is set when LBKDE is set and a LIN break character is detected, when 11 consecutive logic 0s (if C1[M] = 0) or 12 consecutive logic 0s (if C1[M] = 1) appear on the receiver input. LBKDIF is set right after receiving the last LIN break character bit. LBKDIF is cleared by writing a 1 to it.			
	0 No LIN break character has been detected.			
	1 LIN break character has been detected.			
6 RXEDGIF	RxD Pin Active Edge Interrupt Flag			
	RXEDGIF is set when an active edge (falling if RXINV = 0, rising if RXINV=1) on the RxD pin occurs.  RXEDGIF is cleared by writing a 1 to it. See RXEDGIF description for additional details.			
	<b>NOTE:</b> The active edge is only detected when in two wire mode and on receive data coming from the RxD pin.			
	0 No active edge on the receive pin has occurred.			
	1 An active edge on the receive pin has occurred.			
5 MSBF	Most Significant Bit First			
	Setting this bit reverses the order of the bits that are transmitted and received on the wire. This bit does not affect the polarity of the bits, the location of the parity bit or the location of the start or stop bits. This bit is automatically set or cleared when C7816[INIT] and C7816[ISO7816E] are enabled and an initial character is detected.			





# **UARTx\_S2** field descriptions (continued)

Field	Description
	0 LSB (bit0) is the first bit that is transmitted following the start bit. Further, the first bit received after the start bit is identified as bit0.
	1 MSB (bit8, bit7 or bit6) is the first bit that is transmitted following the start bit depending on the setting of C1[M] and C1[PE]. Further, the first bit received after the start bit is identified as bit8, bit7 or bit6 depending on the setting of C1[M] and C1[PE].
4 RXINV	Receive Data Inversion
HAINV	Setting this bit, reverses the polarity of the received data input. In NRZ format, a one is represented by a mark and a zero is represented by a space for normal polarity, and the opposite for inverted polarity. In IrDA format, a zero is represented by short high pulse in the middle of a bit time remaining idle low for a one for normal polarity, and a zero is represented by short low pulse in the middle of a bit time remaining idle high for a one for inverted polarity. This bit is automatically set or cleared when C7816[INIT] and C7816[ISO7816E] are enabled and an initial character is detected.
	NOTE: Setting RXINV inverts the RxD input for: data bits, start and stop bits, break, and idle. When C7816[ISO7816E] is set/enabled then only the data bits and the parity bit are inverted.
	<ul><li>0 Receive data is not inverted.</li><li>1 Receive data is inverted.</li></ul>
3 RWUID	Receive Wakeup Idle Detect
HWUID	When RWU is set and WAKE is cleared, this bit controls whether the idle character that wakes the receiver sets the S1[IDLE] bit. This bit must be cleared when C7816[ISO7816E] is set/enabled.
	0 The S1[IDLE] bit is not set upon detection of an idle character.
	1 The S1[IDLE] bit is set upon detection of an idle character.
2 BRK13	Break Transmit Character Length
Briikio	This bit determines whether the transmit break character is 10, 11, or 12 bits long, or 13 or 14 bits long. Refer to Transmitting break characters for the length of the break character for the different configurations. The detection of a framing error is not affected by this bit.
	0 Break character is 10, 11, or 12 bits long.
	1 Break character is 13 or 14 bits long.
1 LBKDE	LIN Break Detection Enable
LBNDE	LBKDE selects a longer break character detection length. While LBKDE is set, the S1[RDRF], S1[NF], S1[FE], and S1[PF] flags are prevented from setting. When LBKDE is set, see Overrun operation. The LBKDE bit must be cleared when C7816[ISO7816E] is set.
	0 Break character is detected at length of 10 bit times (C1[M] = 0), 11 (C1[M] = 1 and C4[M10] = 0), or 12 (C1[M] = 1, C4[M10] = 1, and S1[PE] = 1).
	1 Break character is detected at length of 11 bits times (if C1[M] = 0 or 12 bits time (if C1[M] = 1).
0 RAF	Receiver Active Flag
	RAF is set when the UART receiver detects a logic 0 during the RT1 time period of the start bit search. RAF is cleared when the receiver detects an idle character when C7816[ISO7816E] is cleared/disabled. When C7816[ISO7816E] is enabled the RAF is cleared if the C7816[TTYPE] = 0 expires or the C7816[TTYPE] = 1 expires.
	<b>NOTE:</b> In the case when C7816[ISO7816E] is set and C7816[TTYPE] = 0, it is possible to configure the guard time to be 12. However, in the event that a NACK is required to be transmitted the data



### **UARTx\_S2** field descriptions (continued)

Field	Description					
	transfer actually takes 13 ETU with the 13th ETU slot being a inactive buffer. Hence in this situation the RAF may deassert one ETU prior to actually being inactive.					
	<ul><li>0 UART receiver idle/inactive waiting for a start bit.</li><li>1 UART receiver active (RxD input not idle).</li></ul>					

# 49.3.7 UART Control Register 3 (UARTx\_C3)

Writing to R8 bit does not have any effect. The TXDIR and TXINV bits can only be changed between transmit and receive packets.

Addresses: UART0\_C3 is 4006\_A000h base + 6h offset = 4006\_A006h


UART1\_C3 is 4006\_B000h base + 6h offset = 4006\_B006h

UART2\_C3 is 4006\_C000h base + 6h offset = 4006\_C006h

UART3\_C3 is 4006\_D000h base + 6h offset = 4006\_D006h

UART4\_C3 is 400E\_A000h base + 6h offset = 400E\_A006h

UART5\_C3 is 400E\_B000h base + 6h offset = 400E\_B006h



### **UARTx\_C3** field descriptions

Field	Description			
7 R8	Received Bit 8			
1.0	R8 is the ninth data bit received when the UART is configured for 9-bit data format $(C1[M] = 1)$ or $(C4[M10] = 1)$ .			
6 T8	Transmit Bit 8			
16	T8 is the ninth data bit transmitted when the UART is configured for 9-bit data format (C1[M] = 1) or $(C4[M10] = 1)$ .			
	<b>NOTE:</b> If the value of T8 is the same as in the previous transmission, T8 does not have to be rewritten. The same value is transmitted until T8 is rewritten.			
5 TXDIR	Transmitter Pin Data Direction in Single-Wire mode			
TADIN	This bit determines whether the TXD pin is used as an input or output in the single-wire mode of operation. This bit is relevant only to the single-wire mode. When C7816[ISO7816E] is set/enabled and C7816[TTYPE] = 1, this bit is automatically cleared after the requested block has been transmitted. This condition is detected when TL7816[TLEN] = 0 and 4 additional characters have been transmitted. Additionally, if C7816[ISO7816E] is set/enabled and C7816[TTYPE] = 0 and a NACK is being transmitted, the hardware will automatically override this bit as needed. In this situation TXDIR will not reflect the temporary state associated with the NACK.			

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



### **UARTx\_C3** field descriptions (continued)

Field	Description			
	0 TXD pin is an input in single-wire mode.			
	1 TXD pin is an output in single-wire mode.			
4 TXINV	Transmit Data Inversion.			
	Setting this bit reverses the polarity of the transmitted data output. In NRZ format, a one is represented by a mark and a zero is represented by a space for normal polarity, and the opposite for inverted polarity. In IrDA format, a zero is represented by short high pulse in the middle of a bit time remaining idle low for a one for normal polarity, and a zero is represented by short low pulse in the middle of a bit time remaining idle high for a one for inverted polarity. This bit is automatically set or cleared when C7816[INIT] and C7816[ISO7816E] are enabled and an initial character is detected.			
	NOTE: Setting TXINV inverts all transmitted values, including idle, break, start, and stop bits. In loop mode, if TXINV is set, the receiver gets the transmit inversion bit when RXINV is disabled. When C7816[ISO7816E] is set/enabled then only the transmitted data bits and parity bit are inverted.			
	<ul><li>0 Transmit data is not inverted.</li><li>1 Transmit data is inverted.</li></ul>			
3	Overrun Error Interrupt Enable			
ORIE	This bit enables the overrun error flag (S1[OR]) to generate interrupt requests.			
	0 OR interrupts are disabled.			
	1 OR interrupt requests are enabled.			
2	Noise Error Interrupt Enable			
NEIE	This bit enables the noise flag (S1[NF]) to generate interrupt requests.			
	0 NF interrupt requests are disabled.			
	1 NF interrupt requests are enabled.			
1 FEIE	Framing Error Interrupt Enable			
FEIE	This bit enables the framing error flag (S1[FE]) to generate interrupt requests.			
	0 FE interrupt requests are disabled.			
	1 FE interrupt requests are enabled.			
0 PEIE	Parity Error Interrupt Enable			
	This bit enables the parity error flag (S1[PF]) to generate interrupt requests.			
	0 PF interrupt requests are disabled.			
	1 PF interrupt requests are enabled.			

# 49.3.8 UART Data Register (UARTx\_D)

This register is actually two separate registers. Reads return the contents of the read-only receive data register and writes go to the write-only transmit data register.



### NOTE


In 8-bit or 9-bit data format, only UART data register (D) needs to be accessed in order to clear the S1[RDRF] bit (assuming receiver buffer level is less than RWFIFO[RXWATER]). The C3 register only needs to be read (prior to the D register) if the ninth bit of data needs to be captured. Likewise the ED register only needs to be read (prior to the D register) if the additional flag data for the dataword needs to be captured.

#### NOTE

In the normal 8-bit mode (M bit cleared) if the parity is enabled, you get seven data bits and one parity bit. That one parity bit will be loaded into the D register. So if you care about only the data bits, you have to mask off the parity bit from the value you read out of this register.

#### NOTE

When transmitting in 9-bit data format and using 8-bit write instructions, write first to transmit bit 8 in UART control register 3 (C3[T8]), then D. A write to C3[T8] stores the data in a temporary register. If D register is written first then the new data on data bus is stored in D register, while the temporary value (written by last write to C3[T8]) gets stored in C3[T8] register.



**UARTx\_D** field descriptions

# Description Reads return the contents of the read-only receive data register and writes go to the write-only transmit

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

Field

7-0


RT

data register.



# 49.3.9 UART Match Address Registers 1 (UARTx\_MA1)

The MA1 and MA2 registers are compared to input data addresses when the most significant bit is set and the associated C4[MAEN] bit is set. If a match occurs, the following data is transferred to the data register. If a match fails, the following data is discarded. These registers can be read and written at anytime.




### **UARTx\_MA1** field descriptions

Field	Description
7–0 MA	Match Address

# 49.3.10 UART Match Address Registers 2 (UARTx\_MA2)

These registers can be read and written at anytime. The MA1 and MA2 registers are compared to input data addresses when the most significant bit is set and the associated C4[MAEN] bit is set. If a match occurs, the following data is transferred to the data register. If a match fails, the following data is discarded.





### **UARTx\_MA2** field descriptions

Field	Description
7–0 MA	Match Address

# 49.3.11 UART Control Register 4 (UARTx\_C4)

Addresses: UART0\_C4 is 4006\_A000h base + Ah offset = 4006\_A00Ah

UART1\_C4 is 4006\_B000h base + Ah offset = 4006\_B00Ah

UART2\_C4 is 4006\_C000h base + Ah offset = 4006\_C00Ah

UART3\_C4 is 4006\_D000h base + Ah offset = 4006\_D00Ah

UART4\_C4 is 400E\_A000h base + Ah offset = 400E\_A00Ah

UART5\_C4 is 400E\_B000h base + Ah offset = 400E\_B00Ah

Bit	7	6	5	4	3	2	1	0
Read	MAEN1	MAEN2	M10			BRFA		
Write	IVIALIVI	IVIALINZ	IVITO			DITIA		
Reset	0	0	0	0	0	0	0	0

### **UARTx\_C4** field descriptions

Field	Description			
7 MAEN1	Match Address Mode Enable 1			
W. Z. V.	Refer to Match address operation for more information.			
	0 All data received is transferred to the data buffer if MAEN2 is cleared.			
	1 All data received with the most significant bit cleared, is discarded. All data received with the most significant bit set, is compared with contents of MA1 register. If no match occurs, the data is discarded. If match occurs, data is transferred to the data buffer. This bit must be cleared when C7816[ISO7816E] is set/enabled.			
6 MAEN2	Match Address Mode Enable 2			
1477 (2142	Refer to Match address operation for more information.			
	0 All data received is transferred to the data buffer if MAEN1 is cleared.			
	1 All data received with the most significant bit cleared, is discarded. All data received with the most significant bit set, is compared with contents of MA2 register. If no match occurs, the data is discarded. If match occurs, data is transferred to the data buffer. This bit must be cleared when C7816[ISO7816E] is set/enabled.			
5 M10	10-bit Mode select			
IVITO	The M10 bit causes a tenth, non-memory mapped bit to be part of the serial transmission. This tenth bit is generated and interpreted as a parity bit. The M10 bit does not affect the LIN send or detect break behavior. If M10 is set then both C1[M] and C1[PE] bits must also be set. This bit must be cleared when C7816[ISO7816E] is set/enabled. Refer to Data format (non ISO-7816) for more information.			



### **UARTx\_C4** field descriptions (continued)

Field	Description			
	0 The parity bit is the ninth bit in the serial transmission.			
	1 The parity bit is the tenth bit in the serial transmission.			
4–0 BRFA	Baud Rate Fine Adjust			
	This bit field is used to add more timing resolution to the average baud frequency, in increments of 1/32. Refer to Baud rate generation for more information.			

# 49.3.12 UART Control Register 5 (UARTx\_C5)

Addresses: UART0\_C5 is 4006\_A000h base + Bh offset = 4006\_A00Bh

UART1\_C5 is 4006\_B000h base + Bh offset = 4006\_B00Bh

UART2\_C5 is 4006\_C000h base + Bh offset = 4006\_C00Bh

UART3\_C5 is 4006\_D000h base + Bh offset = 4006\_D00Bh

UART4\_C5 is 400E\_A000h base + Bh offset = 400E\_A00Bh

UART5\_C5 is 400E\_B000h base + Bh offset = 400E\_B00Bh



# **UARTx\_C5** field descriptions

Field	Description		
7 TDMAS	Transmitter DMA Select		
	TDMAS configures the transmit data register empty flag, S1[TDRE], to generate interrupt or DMA requests if C2[TIE] is set.		
	NOTE: If C2[TIE] is cleared, TDRE DMA and TDRE interrupt request signals are not asserted when the TDRE flag is set, regardless of the state of TDMAS.		
	NOTE: If C2[TIE] and TDMAS are both set, then C2[TCIE] must be cleared, and D register must not be written outside of servicing of a DMA request.		
	0 If C2[TIE] is set and the S1[TDRE] flag is set, the TDRE interrupt request signal is asserted to request interrupt service.		
	1 If C2[TIE] is set and the S1[TDRE] flag is set, the TDRE DMA request signal is asserted to request a DMA transfer.		
6 Reserved	This read-only field is reserved and always has the value zero.		
5 RDMAS	Receiver Full DMA Select		
TIDWAS	RDMAS configures the receiver data register full flag, S1[RDRF], to generate interrupt or DMA requests if C2[RIE] is set.		

### **UARTx\_C5** field descriptions (continued)

Field	Description					
	NOTE: If C2[RIE] is cleared, the RDRF DMA and RDFR interrupt request signals are not asserted when the S1[RDRF] flag is set, regardless of the state of RDMAS.					
	0 If C2[RIE] is set and the S1[RDRF] flag is set, the RDFR interrupt request signal is asserted to request interrupt service.					
	1 If C2[RIE] is set and the S1[RDRF] flag is set, the RDRF DMA request signal is asserted to request a DMA transfer.					
4–0 Reserved	This read-only field is reserved and always has the value zero.					

### 49.3.13 UART Extended Data Register (UARTx ED)


This register contains additional information flags that are stored with a received dataword. This register may be read at any time but only contains valid data if there is a dataword in the receive FIFO.

#### NOTE

The data contained in this register represents additional information regarding the conditions on which a dataword was received. The importance of this data varies with application, and in some cases maybe completely optional. These fields automatically update to reflect the conditions of the next dataword whenever D is read.

#### NOTE

If the S1[NF] and S1[PF] flags have not been set since the last time the receive buffer was empty, the NOISY and PARITYE bits will be zero.





#### **UARTx\_ED** field descriptions

Field	Description
7 NOISY	The current received dataword contained in D and C3[R8] was received with noise.
	0 The dataword was received without noise.
	1 The data was received with noise.
6 PARITYE	The current received dataword contained in D and C3[R8] was received with a parity error.
	The dataword was received without a parity error.
	1 The dataword was received with a parity error.
5–0 Reserved	This read-only field is reserved and always has the value zero.


## 49.3.14 UART Modem Register (UARTx\_MODEM)

The MODEM register controls options for setting the modem configuration.

#### NOTE

RXRTSE, TXRTSPOL, TXRTSE and TXCTSE must all be cleared when C7816[ISO7816EN] is enabled. This will cause the RTS to deassert during ISO-7816 wait times. The ISO-7816 protocol does not make use of the RTS and CTS signals.

Addresses: UART0\_MODEM is 4006\_A000h base + Dh offset = 4006\_A00Dh
UART1\_MODEM is 4006\_B000h base + Dh offset = 4006\_B00Dh
UART2\_MODEM is 4006\_C000h base + Dh offset = 4006\_C00Dh
UART3\_MODEM is 4006\_D000h base + Dh offset = 4006\_D00Dh
UART4\_MODEM is 400E\_A000h base + Dh offset = 400E\_A00Dh
UART5\_MODEM is 400E\_B000h base + Dh offset = 400E\_B00Dh



## **UARTx\_MODEM** field descriptions

Field	Description
7–4 Reserved	This read-only field is reserved and always has the value zero.
3 RXRTSE	Receiver request-to-send enable  Allows the RTS output to control the CTS input of the transmitting device to prevent receiver overrun.
	NOTE: Do not set both RXRTSE and TXRTSE.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




#### wemory map and registers

## **UARTx\_MODEM** field descriptions (continued)

Field	Description
	0 The receiver has no effect on RTS.
	1 RTS is deasserted if the number of characters in the receiver data register (FIFO) is equal to or greater than RWFIFO[RXWATER]. RTS is asserted when the number of characters in the receiver data register (FIFO) is less than RWFIFO[RXWATER].
2 TXRTSPOL	Transmitter request-to-send polarity
17.11161 62	Controls the polarity of the transmitter RTS. TXRTSPOL does not affect the polarity of the receiver RTS. RTS will remain negated in the active low state unless TXRTSE is set.
	0 Transmitter RTS is active low.
	1 Transmitter RTS is active high.
1 TXRTSE	Transmitter request-to-send enable
	Controls RTS before and after a transmission.
	0 The transmitter has no effect on RTS.
	1 When a character is placed into an empty transmitter data buffer(FIFO), RTS asserts one bit time before the start bit is transmitted. RTS deasserts one bit time after all characters in the transmitter data buffer(FIFO) and shift register are completely sent, including the last stop bit.
0 TXCTSE	Transmitter clear-to-send enable
TACTOL	TXCTSE controls the operation of the transmitter. TXCTSE can be set independently from the state of TXRTSE and RXRTSE.
	0 CTS has no effect on the transmitter.
	1 Enables clear-to-send operation. The transmitter checks the state of CTS each time it is ready to send a character. If CTS is asserted, the character is sent. If CTS is deasserted, the signal TXD remains in the mark state and transmission is delayed until CTS is asserted. Changes in CTS as a character is being sent do not affect its transmission.

## 49.3.15 UART Infrared Register (UARTx\_IR)

The IR register controls options for setting the infrared configuration.






#### **UARTx\_IR** field descriptions

Field	Description
7–3 Reserved	This read-only field is reserved and always has the value zero.
2 IREN	Infrared enable  This bit enables/disables the infrared modulation/demodulation.  0 IR disabled.  1 IR enabled.
1–0 TNP	Transmitter narrow pulse  These bits enable whether the UART transmits a 1/16, 3/16, 1/32 or 1/4 narrow pulse.  00 3/16. 01 1/16. 10 1/32. 11 1/4.

## 49.3.16 UART FIFO Parameters (UARTx\_PFIFO)

This register provides the ability for the programmer to turn on and off FIFO functionality. It also provides the size of the FIFO that has been implemented. This register may be read at any time. This register should only be written when the C2[RE] and C2[TE] bits are cleared / not set and when the data buffer/FIFO is empty.



<sup>\*</sup> Notes:

- TXFIFOSIZE bitfield: The reset value depends on whether the specific UART instance supports the FIFO and on the size of
  that FIFO. See the Chip Configuration details for more information on the FIFO size supported for
  each UART instance.
- RXFIFOSIZE bitfield: The reset value depends on whether the specific UART instance supports the FIFO and on the size of
  that FIFO. See the Chip Configuration details for more information on the FIFO size supported for
  each UART instance.



#### wemory map and registers


# **UARTx\_PFIFO** field descriptions

Field	Description
7 TXFE	Transmit FIFO Enable  When this bit is set the built in FIFO structure for the transmit buffer is enabled. The size of the FIFO structure is indicated by the TXFIFOSIZE field. If this bit is not set then the transmit buffer operates as a FIFO of depth one dataword regardless of the value in TXFIFOSIZE. Both C2[TE] and C2[RE] must be cleared prior to changing this bit. Additionally TXFLUSH and RXFLUSH commands should be issued immediately after changing this bit.  O Transmit FIFO is not enabled. Buffer is depth 1. (Legacy support).  Transmit FIFO is enabled. Buffer is depth indicted by TXFIFOSIZE.
6–4 TXFIFOSIZE	Transmit FIFO. Buffer Depth  The maximum number of transmit datawords that can be stored in the transmit buffer. This field is read only.  O00 Transmit FIFO/Buffer Depth = 1 Dataword. O01 Transmit FIFO/Buffer Depth = 4 Datawords. O10 Transmit FIFO/Buffer Depth = 8 Datawords. O11 Transmit FIFO/Buffer Depth = 16 Datawords. O10 Transmit FIFO/Buffer Depth = 32 Datawords. O11 Transmit FIFO/Buffer Depth = 64 Datawords. O12 Transmit FIFO/Buffer Depth = 64 Datawords. O13 Transmit FIFO/Buffer Depth = 128 Datawords. O14 Transmit FIFO/Buffer Depth = 128 Datawords. O15 Transmit FIFO/Buffer Depth = 128 Datawords. O17 Transmit FIFO/Buffer Depth = 128 Datawords.
3 RXFE	When this bit is set the built in FIFO structure for the receive buffer is enabled. The size of the FIFO structure is indicated by the RXFIFOSIZE field. If this bit is not set then the receive buffer operates as a FIFO of depth one dataword regardless of the value in RXFIFOSIZE. Both C2[TE] and C2[RE] must be cleared prior to changing this bit. Additionally TXFLUSH and RXFLUSH commands should be issued immediately after changing this bit.  O Receive FIFO is not enabled. Buffer is depth 1. (Legacy support)  Receive FIFO is enabled. Buffer is depth indicted by RXFIFOSIZE.
2–0 RXFIFOSIZE	Receive FIFO. Buffer Depth  The maximum number of receive datawords that can be stored in the receive buffer before an overrun occurs. This field is read only.  000 Receive FIFO/Buffer Depth = 1 Dataword. 001 Receive FIFO/Buffer Depth = 4 Datawords. 010 Receive FIFO/Buffer Depth = 8 Datawords. 011 Receive FIFO/Buffer Depth = 16 Datawords. 100 Receive FIFO/Buffer Depth = 32 Datawords. 101 Receive FIFO/Buffer Depth = 64 Datawords. 110 Receive FIFO/Buffer Depth = 128 Datawords. 111 Reserved.



## 49.3.17 UART FIFO Control Register (UARTx\_CFIFO)

This register provides the ability to program various control bits for FIFO operation. This register may be read or written at any time. Note that writing the TXFLUSH and RXFLUSH bits may result in data loss and requires careful action to prevent unintended / unpredictable behavior, hence it is recommended that TE and RE be cleared prior to flushing the corresponding FIFO.



### **UARTx\_CFIFO** field descriptions

Field	Description
7 TXFLUSH	Transmit FIFO/Buffer Flush  Writing to this bit causes all data that is stored in the transmit FIFO/buffer to be flushed. This does not affect data that is in the transmit shift register.
	No flush operation occurs.     All data in the transmit FIFO/Buffer is cleared out.
6 RXFLUSH	Receive FIFO/Buffer Flush
	Writing to this bit causes all data that is stored in the receive FIFO/buffer to be flushed. This does not affect data that is in the receive shift register.
	<ul><li>No flush operation occurs.</li><li>All data in the receive FIFO/buffer is cleared out.</li></ul>
5–2 Reserved	This read-only field is reserved and always has the value zero.
1 TXOFE	Transmit FIFO Overflow Interrupt Enable
	When this bit is set the TXOF flag will generate an interrupt to the host.
	<ul><li>TXOF flag does not generate an interrupt to the host.</li><li>TXOF flag generates an interrupt to the host.</li></ul>
0	Receive FIFO Underflow Interrupt Enable
RXUFE	When this bit is set the RXUF flag will generate an interrupt to the host.

Table continues on the next page...




#### wemory map and registers

## **UARTx\_CFIFO** field descriptions (continued)

Field	Description
	0 RXUF flag does not generate an interrupt to the host.
	1 RXUF flag generates an interrupt to the host.

## 49.3.18 UART FIFO Status Register (UARTx\_SFIFO)

This register provides various status information regarding the transmit and receiver buffers/FIFOs, including interrupt information. This register may be written or read at anytime.



## **UARTx\_SFIFO** field descriptions

Field	Description
7 TXEMPT	Transmit Buffer/FIFO Empty  This status bit asserts when there is no data in the Transmit FIFO/buffer. This bit does not take into account data that is in the transmit shift register.  0 Transmit buffer is not empty.
	1 Transmit buffer is empty.
6 RXEMPT	Receive Buffer/FIFO Empty  This status bit asserts when there is no data in the receive FIFO/Buffer. This bit does not take into account data that is in the receive shift register.  0 Receive buffer is not empty. 1 Receive buffer is empty.
5–2 Reserved	This read-only field is reserved and always has the value zero.
1 TXOF	Transmitter Buffer Overflow Flag  This flag indicates that more data has been written to the transmit buffer than it can hold. This bit will assert regardless of the value of CFIFO[TXOFE]. However, an interrupt will only be issued to the host if the CFIFO[TXOFE] bit is set. This flag is cleared by writing a "1".

Table continues on the next page...




### **UARTx\_SFIFO** field descriptions (continued)

Field	Description
	0 No transmit buffer overflow has occurred since the last time the flag was cleared.
	1 At least one transmit buffer overflow has occurred since the last time the flag was cleared.
0 RXUF	Receiver Buffer Underflow Flag
, inter	This flag indicates that more data has been read from the receive buffer than was present. This bit will assert regardless of the value of CFIFO[RXUFE]. However, an interrupt will only be issued to the host if the CFIFO[RXUFE] bit is set. This flag is cleared by writing a "1".
	<ul> <li>No receive buffer underflow has occurred since the last time the flag was cleared.</li> <li>At least one receive buffer underflow has occurred since the last time the flag was cleared.</li> </ul>

## 49.3.19 UART FIFO Transmit Watermark (UARTx\_TWFIFO)

This register provides the ability to set a programmable threshold for notification of needing additional transmit data. This register may be read at any time but should only be written when C2[TE] is not set. Changing the value of the watermark will not clear the S1[TDRE] flag.




## **UARTx\_TWFIFO** field descriptions

Field	Description
7–0 TXWATER	Transmit Watermark  When the number of datawords in the transmit FIFO/buffer is equal to or less than the value in this register field then an interrupt via S1[TDRE] or a DMA request via C5[TDMAS] will be generated as determined by C5[TDMAS] and C2[TIE] fields. For proper operation the value in the TXWATER field must be set to be less than the size of the transmit buffer/FIFO size as indicated by PFIFO[TXFIFOSIZE] and PFIFO[TXFE].



## 49.3.20 UART FIFO Transmit Count (UARTx\_TCFIFO)

This is a read only register that indicates how many datawords are currently in the transmit buffer/FIFO. It may be read at anytime.




### **UARTx\_TCFIFO** field descriptions

Field	Description
7–0 TXCOUNT	Transmit Counter  The value in this register indicates the number of datawords that are in the transmit buffer/FIFO. If a dataword is in the process of being transmitted (i.e. in the transmit shift register) it is not included in the count. This value may be used in conjunction with the PFIFO[TXFIFOSIZE] field to calculate how much room is left in the transmit buffer/FIFO.

## 49.3.21 UART FIFO Receive Watermark (UARTx\_RWFIFO)

This register provides the ability to set a programmable threshold for notification of needing to remove data from the receiver buffer/FIFO. This register may be read at any time but should only be written when C2[RE] is not asserted. Changing the value in this register will not clear the S1[RDRF] flag.



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




#### **UARTx\_RWFIFO** field descriptions

Field	Description
7–0 RXWATER	Receive Watermark  When the number of datawords in the Receive FIFO/buffer is equal to or greater than the value in this register field the event is flagged. An interrupt via S1[RDRF] or a DMA request via C5[RDMAS] will be generated as determined by C5[RDMAS] and C2[RIE] fields. For proper operation the value in the RXWATER field must be set to be less than the size of the Receive buffer/FIFO size as indicated by PFIFO[RXFIFOSIZE] and PFIFO[RXFE] and greater than 0.

## 49.3.22 UART FIFO Receive Count (UARTx\_RCFIFO)

This is a read only register that indicates how many datawords are currently in the receive buffer/FIFO. It may be read at anytime.




## UARTx\_RCFIFO field descriptions

Field	Description
7–0 RXCOUNT	Receive Counter  The value in this register indicates the number of datawords that are in the receive buffer/FIFO. If a dataword is in the process of being received (i.e. in the receive shift register) it is not included in the count. This value may be used in conjunction with the PFIFO[RXFIFOSIZE] field to calculate how much room is left in the receive buffer/FIFO.



## 49.3.23 UART 7816 Control Register (UARTx\_C7816)

The C7816 register is the primary control register for ISO-7816 specific functionality. This register is specific to 7816 functionality and the values in this register have no effect on UART operation and should be ignored if ISO\_7816E is not set/enabled. This register may be read at anytime but values should only be changed when the ISO\_7816E bit is not set.



#### **UARTx\_C7816** field descriptions

Field	Description
7–5 Reserved	This read-only field is reserved and always has the value zero.
4 ONACK	Generate NACK on Overflow  When this bit is set, the receiver will automatically generate a NACK response if a receive buffer overrun occurs as indicated by the S1[OR] field. In many systems this will result in the transmitter resending the packet that overflowed until the retransmit threshold for that transmitter has been reached. A NACK is only generated if TTYPE=0. This bit operates independently of ANACK. See Overrun NACK considerations.  O The received data does not generate a NACK when the receipt of the data results in an overflow event.  If the receiver buffer overflows, a NACK is automatically sent on a received character.
3 ANACK	Generate NACK on Error  When this bit is set, the receiver will automatically generate a NACK response if a parity error occurs or if INIT is set and an invalid initial character is detected. A NACK is only generated if TTYPE = 0. If ANACK is set the UART will attempt to retransmit the data indefinitely. To stop retransmission attempts, clear C2[TE] or ISO_7816E and do not set until S1[TC] set C2[TE] again.  O No NACK is automatically generated.  A NACK is automatically generated if a parity error is detected or if an invalid initial character is detected.
2 INIT	Detect Initial Character

Table continues on the next page...




#### **UARTx\_C7816** field descriptions (continued)

Field	Description					
	When this bit is set, all received characters will be searched for a valid initial character. If an invalid initial character is identified then a NACK will be sent if ANACK is set. All received data is discarded and error flags blocked (S1[NF], S1[OR], S1[FE], S1[PF], IS7816[WT], IS7816[CWT], IS7816[BWT], IS7816[GTV]) until a valid initial character is detected. Upon detection of a valid initial character the configuration values S2[MSBF], C3[TXINV] and S2[RXINV] are automatically updated to reflect the initial character that was received. The actual INIT data value is not stored in the receive buffer. Additionally, upon detection of a valid initial character the IS7816[INITD] flag is set and an interrupt issued as programmed by the IE7816[INITDE] bit. When a valid initial character is detected the INIT bit is automatically cleared.  O Normal operating mode. Receiver does not seek to identify initial character.  Receiver searches for initial character.					
1 TTYPE	Transfer Type  This bit indicates the transfer protocol being used.  Refer to ISO-7816 / smartcard support for more details.  0  T = 0 Per the ISO-7816 specification.					
0 ISO_7816E	<ul> <li>T = 1 Per the ISO-7816 specification.</li> <li>ISO-7816 Functionality Enabled</li> <li>This bit indicates that the UART is operating according to the ISO-7816 protocol.</li> <li>NOTE: This bit should only be modified when no transmit or receive is occurring. If this bit is changed during a data transfer the data being transmitted or received may be transferred incorrectly.</li> <li>ISO-7816 functionality is turned off / not enabled.</li> <li>ISO-7816 functionality is turned on / enabled.</li> </ul>					

## 49.3.24 UART 7816 Interrupt Enable Register (UARTx\_IE7816)

The IE7816 register controls which flags result in an interrupt being issued. This register is specific to 7816 functionality, the corresponding flags that drive the interrupts will not assert when 7816E is not set/enabled. However, these flags may remain set if they asserted while 7816E was set and not subsequently cleared. This register maybe read or written at anytime.



K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory map and registers


# UARTx\_IE7816 field descriptions

Field	Description						
7 WTE	Wait Timer Interrupt Enable						
	0 The assertion of the IS7816[WT] bit will not result in the generation of an interrupt.						
	1 The assertion of the IS7816[WT] bit will result in the generation of an interrupt.						
6 CWTE	Character Wait Timer Interrupt Enable						
	0 The assertion of the IS7816[CWT] bit will not result in the generation of an interrupt.						
	1 The assertion of the IS7816[CWT] bit will result in the generation of an interrupt.						
5 BWTE	Block Wait Timer Interrupt Enable						
	0 The assertion of the IS7816[BWT] bit will not result in the generation of an interrupt.						
	1 The assertion of the IS7816[BWT] bit will result in the generation of an interrupt.						
4 INITDE	Initial Character Detected Interrupt Enable						
	0 The assertion of the IS7816[INITD] bit will not result in the generation of an interrupt.						
	1 The assertion of the IS7816[INITD] bit will result in the generation of an interrupt.						
3 Reserved	This read-only field is reserved and always has the value zero.						
2	Guard Timer Violated Interrupt Enable						
GTVE	0 The assertion of the IS7816[GTV] bit will not result in the generation of an interrupt.						
	1 The assertion of the IS7816[GTV] bit will result in the generation of an interrupt.						
1 TXTE	Transmit Threshold Exceeded Interrupt Enable						
	0 The assertion of the IS7816[TXT] bit will not result in the generation of an interrupt.						
	1 The assertion of the IS7816[TXT] bit will result in the generation of an interrupt.						
0 RXTE	Receive Threshold Exceeded Interrupt Enable						
	0 The assertion of the IS7816[RXT] bit will not result in the generation of an interrupt.						
	1 The assertion of the IS7816[RXT] bit will result in the generation of an interrupt.						



## 49.3.25 UART 7816 Interrupt Status Register (UARTx\_IS7816)

The IS7816 register provides a mechanism to read and clear the interrupt flags. All flags/interrupts are cleared by writing a "1" to the bit location. Writing a "0" has no effect. All bits are "sticky", meaning they only indicate that the flag condition occurred since the last time the bit was cleared not that the condition currently exists. The status flags are set regardless of if the corresponding bit in the IC7816 is set or cleared, the IC7816 only controls if a interrupt is issued to the host processor. This register is specific to 7816 functionality and the values in this register have no affect on UART operation and should be ignored if 7816E is not set/enabled. This register may be read or written at anytime.



### UARTx\_IS7816 field descriptions

Field	Description					
7 WT	Wait Timer Interrupt					
	This flag indicates that the wait time, the time between the leading edge of a character being transmitted and the leading edge of the next response character has exceeded the programed value. This flag only asserts when C7816[TTYPE] = 0. This interrupt is cleared by writing `1'.					
	0 Wait time (WT) has not been violated.					
	1 Wait time (WT) has been violated.					
6 CWT	Character Wait Timer Interrupt					
OWI	This flag indicates that the character wait time, the time between the leading edges of two consecutive characters in a block has exceed the programed value. This flag only asserts when C7816[TTYPE] = 1. This interrupt is cleared by writing `1'.					
	0 Character wait time (CWT) has not been violated.					
	1 Character wait time (CWT) has been violated.					
5 BWT	Block Wait Timer Interrupt					
	This flag indicates that the block wait time, the time between the leading edge of first received character of a block and the leading edge of the last character the previously transmitted block. This flag only asserts when C7816[TTYPE] = 1.This interrupt is cleared by writing '1'.					

Table continues on the next page...



#### wemory map and registers


# **UARTx\_IS7816** field descriptions (continued)

Field	Description						
	Block wait time (BWT) has not been violated.  Block wait tTime (BWT) has been violated.						
4 INITD	Initial Character Detected Interrupt  This flag indicates that a valid initial character was received. This interrupt is cleared by writing `1'.  O A valid initial character has not been received.  1 A valid initial character has been received.						
3 Reserved	This read-only field is reserved and always has the value zero.						
2 GTV	Guard Timer Violated Interrupt  This flag indicates that one or more of the character guard time, block guard time or guard time were violated. This interrupt is cleared by writing `1'.  A guard time (GT, CGT or BGT) has not been violated.  A guard time (GT, CGT or BGT) has been violated.						
1 TXT	Transmit Threshold Exceeded Interrupt  This flag indicates that the transmit NACK threshold has been exceeded as indicated by the ET7816[TXTHRESHOLD] field. Regardless if this flag is set, the UART will continue to retransmit indefinitely. This flag only asserts when C7816[TTYPE] = 0. If 7816E is cleared/disabled, ANACK is cleared/disabled, C2[TE] is cleared/disabled, C7816[TTYPE] = 1 or packet is transferred without receiving a NACK the internal NACK detection counter is cleared and the count restarts from zero on the next received NACK. This interrupt is cleared by writing `1'.  O The number of retries and corresponding NACKS does not exceed the value in the ET7816[TXTHRESHOLD] field.  The number of retries and corresponding NACKS exceeds the value in the ET7816[TXTHRESHOLD] field.						
0 RXT	Receive Threshold Exceeded Interrupt  This flag indicates that there were more than ET7816[RXTHRESHOLD] consecutive NACKS generated in response to parity errors on received data. This flag requires ANACK to be set. Additionally, this flag only asserts when C7816[TTYPE] = 0. Clearing this bit also resets the counter keeping track of consecutive NACKS. The UART will continue to attempt to receive data regardless of if this flag is set. If 7816E is cleared/disabled, RE is cleared/disabled, C7816[TTYPE] = 1 or packet is received without needing to issue a NACK, the internal NACK detection counter is cleared and the count restarts from zero on the next transmitted NACK. This interrupt is cleared by writing `1'.  O The number of consecutive NACKS generated as a result of parity errors and buffer overruns is less than or equal to the value in ET7816[RXTHRESHOLD].  The number of consecutive NACKS generated as a result of parity errors and buffer overruns is greater than the value in ET7816[RXTHRESHOLD].						



# 49.3.26 UART 7816 Wait Parameter Register (UARTx\_WP7816T0)

The WP7816 register contains constants used in the generation of various wait timer counters. To save register space this register is used differently when C7816[TTYPE] = 0 and C7816[TTYPE] = 1. This register may be read at anytime. This register must only be written when C7816[ISO\_7816E] is not set.




### **UARTx\_WP7816T0** field descriptions

Field	Description
7–0 WI	Wait Timer Interrupt (C7816[TTYPE] = 0)  This value is used to calculate the value used for the WT counter. It represents a value between 1 and 255. The value of zero is not valid. This value is only used when C7816[TTYPE] = 0. See Wait time and guard time parameters.



## 49.3.27 UART 7816 Wait Parameter Register (UARTx\_WP7816T1)

The WP7816 register contains constants used in the generation of various wait timer counters. To save register space this register is used differently when C7816[TTYPE] = 0 and C7816[TTYPE] = 1. This register maybe read at anytime. This register must only be written when C7816[ISO\_7816E] is not set.




## **UARTx\_WP7816T1** field descriptions

Field	Description
7–4 CWI	Character Wait Time Integer (C7816[TTYPE] = 1)
	This value is used to calculate the value used for the CWT counter. It represents a value between 0 and 15. This value is only used when C7816[TTYPE] = 1. See Wait time and guard time parameters.
3–0 BWI	Block Wait Time Integer(C7816[TTYPE] = 1)
	This value is used to calculate the value used for the BWT counter. It represent a value between 0 and 15. This value is only used when C7816[TTYPE] = 1. See Wait time and guard time parameters.



## 49.3.28 UART 7816 Wait N Register (UARTx\_WN7816)

The WN7816 register contains a parameter that is used in the calculation of the guard time counter. This register may be read at anytime. This register must only be written when C7816[ISO\_7816E] is not set.




### **UARTx\_WN7816** field descriptions

Field	Description
7–0 GTN	Guard Band N  This register field defines a parameter used in the calculation of GT, CGT and BGT counters. The value represents an integer number 0-255. See Wait time and guard time parameters.

## 49.3.29 UART 7816 Wait FD Register (UARTx\_WF7816)

The WF7816 contains parameters that are used in the generation of various counters including GT, CGT, BGT, WT and BWT. This register may be read from at anytime. This register must only be written to when C7816[ISO\_7816E] is not set.





#### wemory map and registers

## **UARTx\_WF7816** field descriptions

Field	Description
7–0 GTFD	FD Multiplier  This field is used as another multiplier in the calculation of WT and BWT. This values represents a number between 1 and 255. The value of 0 is invalid. This value is NOT used in baud rate generation. See Wait time and guard time parameters and Baud rate generation.

## 49.3.30 UART 7816 Error Threshold Register (UARTx\_ET7816)

The ET7816 register contains fields that determine the number of NACKs that must be received or transmitted before the host processor is notified. This register may be read at anytime. This register must only be written when C7816[ISO\_7816E] is not set.

Addresses: UART0_ET7816 is 4006_A000h base + 1Eh offset = 4006_A01Eh								
UA	UART1_ET7816 is 4006_B000h base + 1Eh offset = 4006_B01Eh							
UA	RT2_ET7816	is 4006_C00	Oh base + 1Eh	n offset = 4006	_C01Eh			
UA	RT3_ET7816	is 4006_D00	Oh base + 1Eh	n offset = 4006	_D01Eh			
UA	RT4_ET7816	is 400E_A00	0h base + 1Eh	n offset = 400E	_A01Eh			
UA	UART5_ET7816 is 400E_B000h base + 1Eh offset = 400E_B01Eh							
Bit	Bit 7 6 5 4 3 2 1 0							
Read								
Write	TXTHRESHOLD					KXTHRI	ESHOLD	
Reset	0	0	0	0	0	0	0	0


### **UARTx\_ET7816** field descriptions

Field	Description
7–4 TXTHRESHOLD	Transmit NACK Threshold  The value written to this field indicates the maximum number of failed attempts (NACKs) a transmitted character can have before the host processor is notified. Meaning a value of 0 will always result in TXT asserting on the first NACK that is received. A value of 1 will result in TXT being asserted on the second NACK that is received. This field is only meaningful when C7816[TTYPE] = 0 and C7816[ANACK] = 1. The value read from this field represents the number of consecutive NACKs that have been received since the last successful transmission. This counter saturates at 4'hF and does not wrap around. Regardless of how many NACKs that are received, the UART will continue to retransmit indefinitely. This flag only asserts when C7816[TTYPE] = 0. For additional information see the IS7816[TXT] bit description.
3–0 RXTHRESHOLD	Receive NACK Threshold  The value written to this field indicates the maximum number of consecutive NACKs generated as a result of a parity error or receiver buffer overruns before the host processor is notified. Once the counter exceeds that value in the field the IS7816[RXT] will be asserted. This field is only meaningful when C7816[TTYPE] = 0. The value read from this field represents the number of consecutive NACKs that have been transmitted since the last successful reception. This counter saturates at 4'hF and does not wrap around. Regardless of the number of NACKs sent, the UART will continue to receive valid packets indefinitely. For additional information see IS7816[RXT] bit description.



## 49.3.31 UART 7816 Transmit Length Register (UARTx\_TL7816)

The TL7816 register is used to indicate how many characters are contained in the block being transmitted. This register is only used when C7816[TTYPE] = 1. This register may be read at anytime. This register should only be written when C2[TE] is not enabled.



### **UARTx\_TL7816** field descriptions

Field	Description
7–0	Transmit Length
TLEN	
	This value plus 4 indicates the number of characters contained in the block being transmitted. This register is automatically decremented by 1 for each character in the information field portion of the block. Additionally, this register is automatically decremented by 1 for the first character of a CRC in the epilogue field. Hence, this register should be programmed with the number of bytes in the data packet if a LRC is being transmitted, and the number of bytes + 1 if a CRC is being transmitted. This register is not decremented for characters that are assumed to be part of the Prologue field (first three characters transmitted in a block) or the LRC or last CRC character in the Epilogue field (last character transmitted). This field should only be programed or adjusted when C2[TE] is cleared.

## 49.4 Functional description

This section provides a complete functional description of the UART block.

The UART allows full duplex, asynchronous, NRZ serial communication between the CPU and remote devices, including other CPUs. The UART transmitter and receiver operate independently, although they use the same baud rate generator. The CPU monitors the status of the UART, writes the data to be transmitted, and processes received data.



#### **Transmitter** 49.4.1




Figure 49-218. Transmitter Block Diagram

#### **Transmitter character length** 49.4.1.1

The UART transmitter can accommodate either 8, 9, or 10-bit data characters. The state of the C1[M] and C1[PE] bits and the C4[M10] bit determine the length of data characters. When transmitting 9-bit data, bit C3[T8] is the ninth bit (bit 8).



### 49.4.1.2 Transmission bit order

When the S2[MSBF] bit is set, the UART automatically transmits the MSB of the data word as the first bit after the start bit. Likewise the LSB of the data word is transmitted immediately preceding the parity bit (or the stop bit if parity is not enabled). All necessary bit ordering is handled automatically by the module hence the format of the data written to the D register for transmission is completely independent of the S2[MSBF] setting.

#### 49.4.1.3 Character transmission

To transmit data, the MCU writes the data bits to the UART transmit buffer using UART data registers (C3[T8]/D). Data in the transmit buffer is then in turn transferred to the transmitter shift register as needed. The transmit shift register then shifts a frame out through the transmit data output signal after it has prefaced it with any required start and stop bits. The UART data registers (C3[T8] and D) provide access to the transmit buffer structure.

The UART also sets a flag, the transmit data register empty flag (S1[TDRE]) and generates interrupt or DMA request (C5[TDMAS]), whenever the number of datawords in the transmit buffer is equal to or less than the value indicated by the TWFIFO[TXWATER]. The transmit driver routine may respond to this flag by writing additional datawords to the transmit buffer using (C3[T8]/D) as space permits.

See Application information for specific programing sequences.

Setting the C2[TE] bit automatically loads the transmit shift register with a preamble of 10 logic 1s (if C1[M] = 0), 11 logic 1s (if C1[M] = 1 and C4[M10] = 0), or 12 logic 1s (if C1[M] = 1, C4[M10] = 1, C1[PE] = 1). After the preamble shifts out, control logic transfers the data from the UART data register into the transmit shift register. The transmitter automatically transmits the correct start bit and stop bit before and after the dataword.

When C7816[ISO\_7816E] = 1 setting the C2[TE] bit does not result in a preamble being generated. The transmitter starts transmitting as soon as the corresponding guard time expires. When C7816[TTYPE] = 0 the value in GT is used, when C7816[TTYPE] = 1 the value BGT is used since it is assumed that the C2[TE] will remain asserted until the end of the block transfer. The C2[TE] bit is automatically cleared when in C7816[TTYPE] = 1 and the block being transmitted has been completed. When C7816[TTYPE] = 0, the transmitter listens for a NACK indication. If no NACK is received it is assumed that character was correctly received. If a NACK is received the transmitter will resend the data, assuming that the number of retries for that character (number of NACKs received) is less than or equal to the value in ET7816[TXTHRESHOLD].



#### runctional description

Hardware supports odd or even parity. When parity is enabled, the bit immediately preceding the stop bit is the parity bit.

When the transmit shift register is not transmitting a frame, the transmit data output signal goes to the idle condition, logic 1. If at any time software clears the C2[TE] bit, the transmitter enable signal goes low and the transmit signal goes idle.

If software clears C2[TE] while a transmission is in progress, the character in the transmit shift register continues to shift out, provided S1[TC] flag was cleared during the data write sequence. To clear the S1[TC] flag, the S1 register must be read followed by a write to UARTx\_D register.

If the S1[TC] flag is cleared during character transmission and the C2[TE] bit is cleared, the transmission enable signal is deasserted at the completion of current frame. Following this, the transmit data out signal enters the idle state even if there is data pending in the UART transmit data buffer. To ensure that all the data written in the FIFO is transmitted on the link before clearing C2[TE], wait for the S1[TC] flag to set. Alternatively, the same can be achieved by setting TWFIFO[TXWATER] to 0x0 and waiting for S1[TDRE] to set.

## 49.4.1.4 Transmitting break characters

Setting the C2[SBK] loads the transmit shift register with a break character. A break character contains all logic 0s and has no start, stop, or parity bit. Break character length depends on the C1[M] and C1[PE] bits, the S2[BRK13] bit, and the C4[M10] bit. Refer to the following table.

S2[BRK13]	C1[M]	C4[M10]	C1[PE]	Bits transmitted
0	0	_	_	10
0	1	0	_	11
0	1	1	0	11
0	1	1	1	12
1	0	_	_	13
1	1	_	_	14

Table 49-227. Transmit break character length

As long as C2[SBK] is set, transmitter logic continuously loads break characters into the transmit shift register. After software clears the C2[SBK] bit, the shift register finishes transmitting the last break character and then transmits at least one logic 1. The automatic logic 1 at the end of a break character guarantees the recognition of the start bit of the next character. Break bits are not supported when C7816[ISO\_7816E] is set/enabled.



#### NOTE

When queuing a break character, it will be transmitted following the completion of the data value currently being shifted out from the shift register. This means that if data is queued in the data buffer to be transmitted, the break character will preempt that queued data. The queued data will then be transmitted after the break character is complete.

#### 49.4.1.5 Idle characters

An idle character contains all logic 1s and has no start, stop, or parity bit. Idle character length depends on the C1[M] and C1[PE] bits and the C4[M10] bit. The preamble is a synchronizing idle character that begins the first transmission initiated after setting the C2[TE] bit. When C7816[ISO\_7816E] is set/enabled, idle characters are not sent or detected. When data is not being transmitted the data I/O line is in an inactive state.

If the C2[TE] bit is cleared during a transmission, the transmit data output signal becomes idle after completion of the transmission in progress. Clearing and then setting the C2[TE] bit during a transmission queues an idle character to be sent after the dataword currently being transmitted.

### Note

When queuing an idle character the idle character will be transmitted following the completion of the data value currently being shifted out from the shift register. This means that if data is queued in the data buffer to be transmitted, the idle character will preempt that queued data. The queued data will then be transmitted after the idle character is complete.

If the C2[TE] bit is cleared and the transmission is completed, the UART is not the master of the TXD pin.

## 49.4.1.6 Hardware flow control

The transmitter supports hardware flow control by gating the transmission with the value of  $\overline{CTS}$ . If the clear-to-send operation is enabled, the character is transmitted when  $\overline{CTS}$  is asserted. If  $\overline{CTS}$  is deasserted in the middle of a transmission with characters remaining in the receiver data buffer, the character in the shift register is sent and TXD remains in the mark state until  $\overline{CTS}$  is reasserted.



#### runctional description

If the clear-to-send operation is disabled, the transmitter ignores the state of  $\overline{CTS}$ . Also, if the transmitter is forced to send a continuous low condition because it is sending a break character, the transmitter ignores the state of  $\overline{CTS}$  regardless of whether the clear-to-send operation is enabled.

The transmitter's  $\overline{CTS}$  signal can also be enabled even if the same UART receiver's  $\overline{RTS}$  signal is disabled.


### 49.4.1.7 Transceiver driver enable

The transmitter can use  $\overline{RTS}$  as an enable signal for the driver of an external transceiver, see Transceiver driver enable using  $\overline{RTS}$  for details. If the request-to-send operation is enabled, when a character is placed into an empty transmitter data buffer,  $\overline{RTS}$  asserts one bit time before the start bit is transmitted.  $\overline{RTS}$  remains asserted for the whole time that the transmitter data buffer has any characters.  $\overline{RTS}$  deasserts one bit time after all characters in the transmitter data buffer and shift register are completely sent, including the last stop bit. Transmitting a break character also asserts  $\overline{RTS}$ , with the same assertion and deassertion timing as having a character in the transmitter data buffer.

The transmitter's  $\overline{RTS}$  signal only asserts when the transmitter is enabled. However, the transmitter's  $\overline{RTS}$  signal is unaffected by its  $\overline{CTS}$  signal.  $\overline{RTS}$  will remain asserted until the transfer is completed, even if the transmitter is disabled mid-way through a data transfer.

The following figure shows the functional timing information for the transmitter. Along with the actual character itself, TXD shows the start bit. The stop bit is also indicated, with a dashed line if necessary.

#### Chapter 49 Universal Asynchronous Receiver/Transmitter (UART)



1. Cn = transmit characters

Figure 49-219. Transmitter RTS and CTS timing diagram

runctional description

### 49.4.2 Receiver




Figure 49-220. UART receiver block diagram

## 49.4.2.1 Receiver character length

The UART receiver can accommodate 8-, 9-, or 10-bit data characters. The states of the C1[M] and C1[PE] bits and the C4[M10] bit determine the length of data characters. When receiving 9 or 10-bit data, bit C3[R8] is the ninth bit (bit 8).

# 49.4.2.2 Receiver bit ordering

When the S2[MSBF] bit is set, the receiver operates such that the first bit received after the start bit is the MSB of the data word. Likewise the bit received immediately preceding the parity bit (or the stop bit if parity is not enabled) is treated as the LSB for



the data word. All necessary bit ordering is handled automatically by the module hence the format of the data read from receive data buffer is completely independent of the S2[MSBF] setting.

## 49.4.2.3 Character reception

During UART reception, the receive shift register shifts a frame in from the unsynchronized receiver input signal. After a complete frame shifts into the receive shift register, the data portion of the frame transfers to the UART receive buffer. Additionally, the noise and parity error flags that are calculated during the receive process are also captured in the UART receive buffer. The receive data buffer is accessible via the D and C3[T8] registers. Additional received information flags regarding the receive dataword can be read in ED register. The S1[RDRF] flag is set if the number of resulting datawords in the receive buffer is equal to or greater than the number indicated by RWFIFO[RXWATER]. If the C2[RIE] is also set, the RDRF flag generates an RDRF interrupt request. Alternatively, by programming the C5[RDMAS] bit correctly a DMA request can be generated.

When 7816E is set/enabled and C7816[TTYPE] = 0, character reception operates slightly differently. Upon receipt of the parity bit, the validity of the parity bit is checked. If C7816[ANACK] is set and the parity check fails or if INIT and the received character is not a valid initial character, then a NACK is sent by the receiver. If the number of consecutive receive errors exceeds the threshold set by ET7816[RXTHRESHOLD] then the IS7816[RXT] flag is set and an interrupt generated if IE7816[RXTE] is set. If an error is detected (parity or invalid initial character) the data is NOT transferred from the receive shift register to the receive buffer. Instead, the data is overwritten by the next incoming data.

When the C7816[ISO\_7816E] is set/enabled and C7816[ONACK] is set/enabled and the received character would result in the receive buffer overflowing a NACK is issued by the receiver. Additionally, the S1[OR] flag is set and interrupt issued if appropriate and the data in the shift register is discarded.

## 49.4.2.4 Data sampling

The receiver samples the unsynchronized receiver input signal at the RT clock rate. The RT clock is an internal signal with a frequency 16 times the baud rate. To adjust for baud rate mismatch, the RT clock (see the following figure) is re-synchronized:



#### runctional description

- After every start bit.
- After the receiver detects a data bit change from logic 1 to logic 0 (after the majority of data bit samples at RT8, RT9, and RT10 returns a valid logic 1 and the majority of the next RT8, RT9, and RT10 samples returns a valid logic 0).

To locate the start bit, data recovery logic does an asynchronous search for a logic 0 preceded by three logic 1s. When the falling edge of a possible start bit occurs, the RT clock begins to count to 16.




Figure 49-221. Receiver data sampling

To verify the start bit and to detect noise, data recovery logic takes samples at RT3, RT5, and RT7 when C7816[ISO\_7816E] is cleared/disabled and RT8, RT9 and RT10 when C7816[ISO\_7816E] is set/enabled. The following table summarizes the results of the start bit verification samples.

RT3, RT5, and RT7 samples RT8, RT9, RT10 samples when 7816E	Start bit verification	Noise flag
000	Yes	0
001	Yes	1
010	Yes	1
011	No	0
100	Yes	1
101	No	0
110	No	0
111	No	0

Table 49-228. Start bit verification

If start bit verification is not successful, the RT clock is reset and a new search for a start bit begins.



To determine the value of a data bit and to detect noise, recovery logic takes samples at RT8, RT9, and RT10. The following table summarizes the results of the data bit samples.

Table 49-229. Data bit recovery

RT8, RT9, and RT10 samples	Data bit determination	Noise flag
000	0	0
001	0	1
010	0	1
011	1	1
100	0	1
101	1	1
110	1	1
111	1	0

#### **Note**

The RT8, RT9, and RT10 samples do not affect start bit verification. If any or all of the RT8, RT9, and RT10 start bit samples are logic 1s following a successful start bit verification, the noise flag (S1[NF]) is set and the receiver assumes that the bit is a start bit (logic 0). With the exception of when C7816[ISO\_7816E] is set/enabled, where the values of RT8, RT9 and RT10 exclusively determine if a start bit exists.

To verify a stop bit and to detect noise, recovery logic takes samples at RT8, RT9, and RT10. The following table summarizes the results of the stop bit samples. In the event that C7816[ISO\_7816E] is set/enabled and C7816[TTYPE] = 0, verification of a stop bit does not take place. Rather, starting with RT8 the receiver transmits a NACK as programmed until time RT9 of the following time period. Framing Error detection is not supported when C7816[ISO\_7816E] is set/enabled.

Table 49-230. Stop bit recovery

RT8, RT9, and RT10 samples	Framing error flag	Noise flag
000	1	0
001	1	1
010	1	1
011	0	1
100	1	1
101	0	1
110	0	1
111	0	0



#### runctional description

In the following figure, the verification samples RT3 and RT5 determine that the first low detected was noise and not the beginning of a start bit. In this example C7816[ISO\_7816E] = 0. The RT clock is reset and the start bit search begins again. The noise flag is not set because the noise occurred before the start bit was found.




Figure 49-222. Start bit search example 1 (C7816[ISO\_7816E] = 0)

In the following figure, verification sample at RT3 is high. In this example C7816[ISO\_7816E] = 0. The RT3 sample sets the noise flag. Although the perceived bit time is misaligned, the data samples RT8, RT9, and RT10 are within the bit time and data recovery is successful.




Figure 49-223. Start bit search example 2 (C7816[ISO\_7816E] = 0)

In the following figure, a large burst of noise is perceived as the beginning of a start bit, although the test sample at RT5 is high. In this example C7816[ISO\_7816E] = 0. The RT5 sample sets the noise flag. Although this is a worst-case misalignment of perceived bit time, the data samples RT8, RT9, and RT10 are within the bit time and data recovery is successful.

#### Chapter 49 Universal Asynchronous Receiver/Transmitter (UART)




Figure 49-224. Start bit search example 3 (C7816[ISO\_7816E] = 0)

The following figure shows the effect of noise early in the start bit time. In this example C7816[ISO\_7816E] = 0. Although this noise does not affect proper synchronization with the start bit time, it does set the noise flag.





Figure 49-225. Start bit search example 4 (C7816[ISO\_7816E] = 0)

The following figure shows a burst of noise near the beginning of the start bit that resets the RT clock. In this example C7816[ISO\_7816E] = 0. The sample after the reset is low but is not preceded by three high samples that would qualify as a falling edge. Depending on the timing of the start bit search and on the data, the frame may be missed entirely or it may set the framing error flag.








Figure 49-226. Start bit search example 5 (C7816[ISO\_7816E] = 0)

In the following figure, a noise burst makes the majority of data samples RT8, RT9, and RT10 high. In this example C7816[ISO\_7816E] = 0. This sets the noise flag but does not reset the RT clock. In start bits only, the RT8, RT9, and RT10 data samples are ignored. In this example, if C7816[ISO\_7816E] = 1 then a start bit would not have been detected at all since at least two of the three samples (RT8, RT9, RT10) were high.




Figure 49-227. Start bit search example 6

## 49.4.2.5 Framing errors

If the data recovery logic does not detect a logic 1 where the stop bit should be in an incoming frame, it sets the framing error flag, S1[FE] if S2[LBKDE] is disabled. A break character when S2[LBKDE] is disabled also sets the S1[FE] because a break character has no stop bit. The S1[FE] is set at the same time that received data is placed in the receive data buffer. Framing errors are not supported when C7816[ISO7816E] is set/enabled. However, if the S1[FE] is set data will not be received when C7816[ISO7816E] is set.



## 49.4.2.6 Receiving break characters

The UART recognizes a break character when a start bit is followed by eight, nine, or ten logic 0 data bits and a logic 0 where the stop bit should be. Receiving a break character has these effects on UART registers:

- Sets the framing error flag, S1[FE].
- Writes an all "0" dataword to the data buffer, which may cause S1[RDRF] to set depending on the watermark and number of values in the data buffer.
- May set the overrun flag, S1[OR], noise flag, S1[NF], parity error flag, S1[PE], or the receiver active flag, S2[RAF].

The detection threshold for a break character can be adjusted when using an internal oscillator in a LIN system by setting the S2[LBKDE] bit. The UART break character detection threshold depends on the C1[M] and C1[PE] bits, the C4[LBKDE] bit, and the C4[M10] bit. Refer to the following table.


LBKDE	M	M10	PE	Threshold (bits)
0	0	_	_	10
0	1	0	_	11
0	1	1	0	11
0	1	1	1	12
1	0	_	_	11
1	1	_	_	12

Table 49-231. Receive break character detection threshold

While C4[LBKDE] is set, it will have these effects on the UART registers:

- Prevents the S1[RDRF], S1[FE], S1[NF], and S1[PF] flags from being set. However, if they are already set they will remain set.
- Sets the LIN break detect interrupt flag, S2[LBKDIF] if a LIN break character is received.

Break characters are not detected or supported when C7816[ISO\_7816E] is set/enabled.



unctional description

#### 49.4.2.7 Hardware flow control

To support hardware flow control, the receiver can be programmed to automatically deassert and assert  $\overline{RTS}$ .

- RTS will remain asserted until the transfer is completed, even if the transmitter is disabled mid way through a data transfer, see Transceiver driver enable using RTS for more details.
- If the receiver request-to-send functionality is enabled, the receiver automatically deasserts RTS if the number of characters in the receiver data register is equal to or greater than receiver data buffer's watermark, RWFIFO[RXWATER].
- The receiver asserts  $\overline{RTS}$  when the number of characters in the receiver data register is less than the watermark. It is not affected by whether RDRF is asserted.
- Even if RTS is deasserted, the receiver continues to receive characters until the receiver data buffer is full or is overrun.
- If the receiver request-to-send functionality is disabled, the receiver  $\overline{RTS}$  remains deasserted.

The following figure shows receiver hardware flow control functional timing. Along with the actual character itself, RXD shows the start bit. The stop bit also indicated, with a dashed line if necessary. The watermark is set to 2.




Figure 49-228. Receiver hardware flow control timing diagram

#### Infrared decoder 49.4.2.8

The infrared decoder converts the received character from the IrDA format to the NRZ format used by the receiver. It also has a 16-RT clock counter that filters noise and indicates when a '1' is being received.



#### 49.4.2.8.1 Start bit detection

When S2[RXINV] is cleared, the first rising edge of the received character corresponds to the start bit. The infrared decoder resets its counter. At this time, the receiver also begins its start bit detection process. Once the start bit is detected, the receiver synchronizes its bit times to this start bit time. For the rest of the character reception, the infrared decoder's counter and the receiver's bit time counter count independently from each other.

## 49.4.2.8.2 Noise filtering

Any further rising edges detected during the first half of the infrared decoder counter are ignored by the decoder. Any pulses less than one RT clocks can be undetected by it regardless of whether it is seen in the first or second half of the count.

#### 49.4.2.8.3 Low-bit detection

During the second half of the decoder count, a rising edge is decoded as a '0', which is sent to the receiver. The decoder counter also is reset.

## 49.4.2.8.4 High-bit detection

At 16-RT clocks after the previous rising edge, if a rising edge is not seen, then the decoder sends a `1' to the receiver.

If the next bit is a `0' which arrives late, then a low-bit is detected according to Low-bit detection. The value sent to the receiver is changed from `1' to a `0'. Then if a noise pulse occurs outside of the receiver's bit time sampling period, then the delay of a `0' is not recorded as noise.

### 49.4.2.9 Baud rate tolerance

A transmitting device may be operating at a baud rate below or above the receiver baud rate. Accumulated bit time misalignment can cause one of the three stop bit data samples (RT8, RT9, and RT10) to fall outside the actual stop bit. A noise error will occur if the RT8, RT9, and RT10 samples are not all the same logical values. A framing error will occur if the receiver clock is misaligned in such a way that the majority of the RT8, RT9, and RT10 stop bit samples are a logic zero.



#### runctional description

As the receiver samples an incoming frame, it re-synchronizes the RT clock on any valid falling edge within the frame. Resynchronization within frames will correct a misalignment between transmitter bit times and receiver bit times.

#### 49.4.2.9.1 Slow data tolerance

The following figure shows how much a slow received frame can be misaligned without causing a noise error or a framing error. The slow stop bit begins at RT8 instead of RT1 but arrives in time for the stop bit data samples at RT8, RT9, and RT10.




Figure 49-229. Slow data

For an 8-bit data character, data sampling of the stop bit takes the receiver 154 RT cycles (9 bit times  $\times$  16 RT cycles + 10 RT cycles).

With the misaligned character shown in the above figure, the receiver counts 154 RT cycles at the point when the count of the transmitting device is 147 RT cycles (9 bit times × 16 RT cycles + 3 RT cycles).

The maximum percent difference between the receiver count and the transmitter count of a slow 8-bit data character with no errors is:

$$((154 - 147) \div 154) \times 100 = 4.54\%$$

For a 9-bit data character, data sampling of the stop bit takes the receiver 170 RT cycles (10 bit times × 16 RT cycles + 10 RT cycles).

With the misaligned character shown in the above figure, the receiver counts 170 RT cycles at the point when the count of the transmitting device is 163 RT cycles (10 bit times  $\times$  16 RT cycles + 3 RT cycles).

The maximum percent difference between the receiver count and the transmitter count of a slow 9-bit character with no errors is:

$$((170 - 163) \div 170) \times 100 = 4.12\%$$



#### 49.4.2.9.2 Fast data tolerance

The following figure shows how much a fast received frame can be misaligned. The fast stop bit ends at RT10 instead of RT16 but is still sampled at RT8, RT9, and RT10.




Figure 49-230. Fast data

For an 8-bit data character, data sampling of the stop bit takes the receiver 154 RT cycles (9 bit times  $\times$  16 RT cycles + 10 RT cycles).

With the misaligned character shown in the above figure, the receiver counts 154 RT cycles at the point when the count of the transmitting device is 160 RT cycles (10 bit times  $\times$  16 RT cycles).

The maximum percent difference between the receiver count and the transmitter count of a fast 8-bit character with no errors is:

$$((154 - 160) \div 154) \times 100 = 3.90\%$$

For a 9-bit data character, data sampling of the stop bit takes the receiver 170 RT cycles (10 bit times  $\times$  16 RT cycles + 10 RT cycles).

With the misaligned character shown in the above figure, the receiver counts 170 RT cycles at the point when the count of the transmitting device is 176 RT cycles (11 bit times  $\times$  16 RT cycles).

The maximum percent difference between the receiver count and the transmitter count of a fast 9-bit character with no errors is:

$$((170 - 176) \div 170) \times 100 = 3.53\%$$

# 49.4.2.10 Receiver wakeup

The C1[WAKE] bit determines how the UART is brought out of the standby state to process an incoming message. The C1[WAKE] bit enables either idle line wakeup or address mark wakeup.

Receiver wakeup is not supported when C7816[ISO\_7816E] is set/enabled since multi-receiver systems are not allowed.



#### 49.4.2.10.1 Idle input line wakeup (C1[WAKE] = 0)

In this wakeup method, an idle condition on the unsynchronized receiver input signal clears the C2[RWU] bit and wakes the UART. The initial frame or frames of every message contain addressing information. All receivers evaluate the addressing information, and receivers for which the message is addressed process the frames that follow. Any receiver for which a message is not addressed can set its C2[RWU] bit and return to the standby state. The C2[RWU] bit remains set and the receiver remains in standby until another idle character appears on the unsynchronized receiver input signal.

Idle line wakeup requires that messages be separated by at least one idle character and that no message contains idle characters.

When C2[RWU] is one and S2[RWUID] is zero, the idle character that wakes the receiver does not set the S1[IDLE] flag or the receive data register full flag, S1[RDRF]. The receiver wakes and waits for the first data character of the next message which will be stored in the receive data buffer. When S2[RWUID] and C2[RWU] bits are set and C1[WAKE] is cleared, any idle condition sets the S1[IDLE] flag and generates an interrupt if enabled.

Idle Input Line Wakeup is not supported when C7816[ISO\_7816E] is set/enabled.

## 49.4.2.10.2 Address mark wakeup (C1[WAKE] = 1)

In this wakeup method, a logic 1 in the bit position immediately preceding the stop bit of a frame clears the C2[RWU] bit and wakes the UART. A logic 1 in the bit position immediately preceding the stop bit marks a frame as an address frame that contains addressing information. All receivers evaluate the addressing information, and the receivers for which the message is addressed process the frames that follow. Any receiver for which a message is not addressed can set its C2[RWU] bit and return to the standby state. The C2[RWU] bit remains set and the receiver remains in standby until another address frame appears on the unsynchronized receiver input signal.

A logic 1 in the bit position immediately preceding the stop bit clears the receiver's C2[RWU] bit before the stop bit is received and places the received data into the receiver data buffer.

Address mark wakeup allows messages to contain idle characters but requires that the bit position immediately preceding the stop bit be reserved for use in address frames.

If module is in standby mode and nothing triggers to wake the UART, no error flag is set even if an invalid error condition is detected on the receiving data line.

Address mark wakeup is not supported when C7816[ISO\_7816E] is set/enabled.



#### 49.4.2.10.3 Match address operation

Match address operation is enabled when the C4[MAEN1] or C4[MAEN2] bit is set. In this function, a frame received by the RX pin with a logic 1 in the bit position immediately preceding the stop bit is considered an address and is compared with the associated MA1 or MA2 register. The frame is only transferred to the receive buffer, and S1[RDRF] is set, if the comparison matches. All subsequent frames received with a logic 0 in the bit position immediately preceding the stop bit are considered to be data associated with the address and are transferred to the receive data buffer. If no marked address match occurs then no transfer is made to the receive data buffer, and all following frames with logic zero in the bit position immediately preceding the stop bit are also discarded. If both the C4[MAEN1] and C4[MAEN2] bits are negated, the receiver operates normally and all data received is transferred to the receive data buffer.

Match Address operation functions in the same way for both MA1 and MA2 registers.

- If only one of C4[MAEN1] and C4[MAEN2] is asserted, a marked address is compared only with the associated match register and data is transferred to the receive data buffer only on a match.
- If C4[MAEN1] and C4[MAEN2] are asserted, a marked address is compared with both match registers and data is transferred only on a match with either register.

Address match operation is not supported when C7816[ISO\_7816E] is set/enabled.

## 49.4.3 Baud rate generation

A 13-bit modulus counter and a 5-bit fractional fine-adjust counter in the baud rate generator derive the baud rate for both the receiver and the transmitter. The value from 1 to 8191 written to the SBR[12:0] bits determines the module clock divisor. The SBR bits are in the UART baud rate registers (BDH and BDL). The baud rate clock is synchronized with the module clock and drives the receiver. The fractional fine-adjust counter adds fractional delays to the baud rate clock to allow fine trimming of the baud rate to match the system baud rate. The baud rate clock divided by 16 drives the transmitter. The receiver has an acquisition rate of 16 samples per bit time.

Baud rate generation is subject to two sources of error:

- Integer division of the module clock may not give the exact target frequency. This error can be reduced by means of the fine-adjust counter.
- Synchronization with the module clock can cause phase shift.



#### runctional description

The Table 49-232 lists the available baud divisor fine adjust values.

#### UART baud rate = UART module clock / $(16 \times (SBR[12:0] + BRFD))$

The following table lists some examples of achieving target baud rates with a module clock frequency of 10.2 MHz, with and without fractional fine adjustment.

Table 49-232. Baud rates (example: module clock = 10.2 MHz)

Bits SBR (decimal)	Bits BRFA	BRFD value	Receiver clock (Hz)	Transmitter clock (Hz)	Target Baud rate	Error (%)
17	00000	0	600,000.0	37,500.0	38,400	2.3
16	10011	19/32=0.59375	614,689.3	38,418.08	38,400	0.047
33	00000	0	309,090.9	19,318.2	19,200	0.62
33	00110	6/32=0.1875	307,344.6	19,209.04	19,200	0.047
66	00000	0	154,545.5	9659.1	9600	0.62
133	00000	0	76,691.7	4793.2	4800	0.14
266	00000	0	38,345.9	2396.6	2400	0.14
531	00000	0	19,209.0	1200.6	1200	0.11
1062	00000	0	9604.5	600.3	600	0.05
2125	00000	0	4800.0	300.0	300	0.00
4250	00000	0	2400.0	150.0	150	0.00
5795	00000	0	1760.1	110.0	110	0.00

Table 49-233. Baud rate fine adjust

BRFA	Baud Rate Fractional Divisor (BRFD)	
00000	0/32 = 0	
0 0 0 0 1	1/32 = 0.03125	
0 0 0 1 0	2/32 = 0.0625	
0 0 0 1 1	3/32 = 0.09375	
00100	4/32 = 0.125	
00101	5/32 = 0.15625	
0 0 1 1 0	6/32 = 0.1875	
00111	7/32 = 0.21875	
01000	8/32 = 0.25	
01001	9/32 = 0.28125	
01010	10/32 = 0.3125	
01011	11/32 = 0.34375	
01100	12/32 = 0.375	

Table continues on the next page...



#### Table 49-233. Baud rate fine adjust (continued)

BRFA	Baud Rate Fractional Divisor (BRFD)		
01101	13/32 = 0.40625		
01110	14/32 = 0.4375		
01111	15/32 = 0.46875		
10000	16/32 = 0.5		
1 0 0 0 1	17/32 = 0.53125		
10010	18/32 = 0.5625		
10011	19/32 = 0.59375		
10100	20/32 = 0.625		
10101	21/32 = 0.65625		
10110	22/32 = 0.6875		
10111	23/32 = 0.71875		
1 1 0 0 0	24/32 = 0.75		
1 1 0 0 1	25/32 = 0.78125		
11010	26/32 = 0.8125		
11011	27/32 = 0.84375		
1 1 1 0 0	28/32 = 0.875		
1 1 1 0 1	29/32 = 0.90625		
11110	30/32 = 0.9375		
11111	31/32 = 0.96875		

# 49.4.4 Data format (non ISO-7816)

Each data character is contained in a frame that includes a start bit and a stop bit. The rest of the data format depends upon UARTx\_C1[M], UARTx\_C1[PE], UARTx\_S2[MSBF], and UARTx\_C4[M10].

## 49.4.4.1 Eight-bit configuration

Clearing the UART\_C1[M] configures the UART for 8-bit data characters, that is, eight bits are memory mapped in UART\_D. A frame with eight data bits has a total of 10 bits. The most significant bit of the eight data bits can be used as an address mark to wake the receiver. If that bit is used in this way, then it serves as an address or data indication, leaving the remaining seven bits as actual data. When UART\_C1[PE] is set, the 8th databit is automatically calculated as the parity bit. Refer to the following table.

Table 49-234.	Configuration	of 8-bit data format
---------------	---------------	----------------------

UART_C1[PE]	Start	Data	Address	Parity	Stop
OART_CT[FL]	bit	bits	bits	bits	bit
0	1	8	0	0	1
0	1	7	1 <sup>1</sup>	0	1
1	1	7	0	1	1

<sup>1.</sup> The address bit identifies the frame as an address character. See Receiver wakeup.

## 49.4.4.2 Nine-bit configuration

When UARTx\_C1[M] is set and UARTx\_C4[M10] is cleared the UART is configured for 9-bit data characters. The 9th bit is either UARTx\_C3[T8/R8] or the internally generated parity bit if UARTx\_C1[PE] is enabled. This results in a frame consisting of a total of 11 bits. In the event that the 9th data bit is selected to be UARTx\_C3[T8] it will remain unchanged after transmission and can be used repeatedly without rewriting it unless the value needs to be changed. This feature may be useful when the 9th data bit is being used as an address mark.

When UARTx\_C1[M] is set and UARTx\_C4[M10] is set the UART is configured for 9-bit data characters, but the frame consists of a total of 12 bits. The 12 bits include the start and stop bits, the 9 data character bits and a 10th internal data bit. Note that if UARTx\_C4[M10] is set UARTx\_C1[PE] must also be set. In this case, the 10th bit is the internally generated parity bit. The 9th bit is can either be used as a address mark or a 9th data bit.

Refer to the following table.

Table 49-235. Configuration of 9-bit data formats

CHIDEL	IDE1 LIC1IMI	UC1[M] C1[M10]	Start	Data	Address	Parity	Stop
C1[PE]	UC I [IVI]		bit	bits	bits	bits	bit
0	0	0		See Eight-bit configuration			
0	0	1		In	valid configurati	on	
0	1	0	1	9	0	0	1
0	1	0	1	8	1 <sup>1</sup>	0	1
0	1	1	Invalid Configuration				
1	0	0	See Eight-bit configuration				
1	0	1	Invalid Configuration				
1	1	0	1	8	0	1	1
1	1	1	1	9	0	1	1
1	1	1	1	8	1 <sup>2</sup>	1	1



- 1. The address bit identifies the frame as an address character.
- 2. The address bit identifies the frame as an address character.

#### **Note**

Unless in 9-bit mode with M10 set, do not use address mark wakeup with parity enabled.

## 49.4.4.3 Timing examples

Timing examples of these configurations in the NRZ mark/space data format are illustrated in the following figures. The timing examples show all of the configurations in the following sub-sections along with the LSB and MSB first variations.

#### 49.4.4.3.1 Eight-bit format with parity disabled

The most significant bit can be used for address mark wakeup.

Figure 49-231. Eight bits of data with LSB first

Figure 49-232. Eight bits of data with MSB first

## 49.4.4.3.2 Eight-bit format with parity enabled

Figure 49-233. Seven bits of data with LSB first and parity

Figure 49-234. Seven bits of data with MSB first and parity

## 49.4.4.3.3 Nine-bit format with parity disabled

The most significant bit can be used for address mark wakeup.



Figure 49-235. Nine bits of data with LSB first

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011

runctional description

Figure 49-236. Nine bits of data with MSB first

#### 49.4.4.3.4 Nine-bit format with parity enabled

START BIT 0 BIT 1 BIT 2 BIT 3 BIT 4 BIT 5 BIT 6 BIT 7 PARITY STOP START BIT

Figure 49-237. Eight bits of data with LSB first and parity

Figure 49-238. Eight bits of data with MSB first and parity

#### 49.4.4.3.5 Non-memory mapped tenth bit for parity

The most significant memory-mapped bit can be used for address mark wakeup.

Figure 49-239. Nine bits of data with LSB first and parity

```
ADDRESS
MARK

START BIT 8 BIT 7 BIT 6 BIT 5 BIT 4 BIT 3 BIT 2 BIT 1 BIT 0 PARITY STOP START
BIT BIT
```

Figure 49-240. Nine bits of data with MSB first and parity

## 49.4.5 Single-wire operation

Normally, the UART uses two pins for transmitting and receiving. In single-wire operation, the RXD pin is disconnected from the UART and the UART implements a half-duplex serial connection. The UART uses the TXD pin for both receiving and transmitting.




Figure 49-241. Single-wire operation (C1[LOOPS] = 1, C1[RSRC] = 1)

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



Enable single-wire operation by setting the C1[LOOPS] bit and the receiver source bit, C1[RSRC]. Setting the C1[LOOPS] bit disables the path from the unsynchronized receiver input signal to the receiver. Setting the C1[RSRC] bit connects the receiver input to the output of the TXD pin driver. Both the transmitter and receiver must be enabled (C2[TE] = 1 and C2[RE] = 1). When C7816[ISO\_7816EN] is set, it is not a requirement that both C2[TE] and C2[RE] are set.

## 49.4.6 Loop operation

In loop operation the transmitter output goes to the receiver input. The unsynchronized receiver input signal is disconnected from the UART.




Figure 49-242. Loop operation (C1[LOOPS] = 1, C1[RSRC] = 0)

Enable loop operation by setting the C1[LOOPS] bit and clearing the C1[RSRC] bit. Setting the C1[LOOPS] bit disables the path from the unsynchronized receiver input signal to the receiver. Clearing the C1[RSRC] bit connects the transmitter output to the receiver input. Both the transmitter and receiver must be enabled (C2[TE] = 1 and C2[RE] = 1). When C7816[ISO\_7816EN] is set, it is not a requirement that both C2[TE] and C2[RE] are set.

## 49.4.7 ISO-7816 / smartcard support

The UART provides mechanisms to support the ISO-7816 protocol that is commonly used to interface with smartcards. The ISO-7816 protocol is an NRZ, single wire, half-duplex interface. The TxD pin is used in open-drain mode since the data signal is used for both transmitting and receiving. There are multiple subprotocols within the ISO-7816 standard. The UART supports both T=0 and T=1 protocols. The module also provides for automated initial character detection and configuration which allows for support of both direct convention and inverse convention data formats. A variety of interrupts specific to 7816 are provided in addition to the general interrupts to assist software.



#### **runctional** description

Additionally the module is able to provide automated NACK responses and has programing automated retransmission of failed packets. An assortment of programmable timeouts and guard band times are also supported.

The term elemental time unit (ETU) is frequently used in the context of ISO-7816. This concept is used to relate the frequency that the system (UART) is running at and the frequency that data is being transmitted and received. One ETU represents the time it takes to transmit or receive a single bit. For example, a standard 7816 packet, excluding any guard time or NACK elements is 10 ETUs (start bit, 8 data bits and a parity bit). Guard times and wait times are also measured in ETUs.

#### **NOTE**

The ISO-7816 specification may have certain configuration options that are reserved. In order to maintain maximum flexibility to support future 7816 enhancements or devices which may not strictly conform to the specification, the UART does not prevent those options being used. Further, the UART may provide configuration options that exceed the flexibility of options explicitly allowed by the 7816 specification. Failure to correctly configure the UART may result in unexpected behavior or incompatibility with the ISO-7816 specification.

#### 49.4.7.1 Initial characters

In ISO-7816 mode, the UART can be configured to use the C7816[INIT] bit to detect the next valid initial character, referred to by the ISO-7816 specifically as a TS character. When the initial character is detected, the UART provides the host processor with an interrupt if IE7816[INITDE] is set. Additionally, the UART will set the S2[MSBF], C3[TXINV] and S2[RXINV] register fields automatically based on the initial character. The corresponding initial character and resulting register settings are listed in the following table.

Table 49-236. Initial character automated settings

Initial character (bit 1-10)	Initial character (hex)	MSBF	TXINV	RXINV
LHHL LLL LLH	3F	1	1	1
inverse convention				
LHHL HHH LLH	3B	0	0	0
direct convention				



When the C7816[INIT] bit is set, the receiver will search all received data for the first valid initial character. All data received which is not a valid initial character will be ignored and all flags resulting from the invalid data will be blocked from asserting. If the C7816[ANACK] bit is set, a NACK will be returned for invalid received initial characters and a RXT interrupt will be generated as programmed.

#### 49.4.7.2 Protocol T = 0

When T = 0 protocol is selected, a relatively complex error detection scheme is used. Data characters are formatted as illustrated in the following figure. This scheme is also used for answer to reset and PPS formats.




Figure 49-243. ISO-7816 T = 0 data format

As with other protocols supported by the UART the data character includes a start bit. However, in this case there are two stop bits rather than the typical single stop bit. In addition to a standard even parity check, the receiver has the ability to generate and return a NACK during the second half of the first stop bit period. The NACK must be at least one time period (ETU) in length and no more than 2 time periods (ETU) in length. The transmitter must wait for at least two time units (ETU) after detection of the error signal before attempting to retransmit the character.

It is assumed that the UART and the device (smartcard) know in advance which device is receiving and which is transmitting. No special mechanism is supplied by the UART to control receive and transmit in the mode other than the C2[TE] and C2[RE] bits.

#### 49.4.7.3 Protocol T = 1

When T = 1 protocol is selected the NACK error detection scheme is not used. Rather, the parity bit is used on a character basis and a CRC or LRC is used on the block basis (i.e. each group of characters). As such, in this mode the data format allows for a single stop bit although additional inactive bit periods may be present between the stop bit and the next start bit. Data characters are formatted as illustrated in the following figure.



runctional description

ISO 7816 FORMAT (T=1)

#### Figure 49-244. ISO 7816 T=1 data format

The smallest data unit that is transferred is a block. A block is made up of several data characters and may vary in size depending on the block type. The UART does not provide a mechanism to decode the block type. As part of the block, an LRC or CRC is included. The UART does not calculate the CRC or LRC for transmitted blocks nor does it verify the validity of the CRC or LRC for received blocks. The 7816 protocol requires that the initiator and the smartcard (device) takes alternate turns in transmitting and receiving blocks. When the UART detects that the last character in a block has been transmitted it will automatically clear the C2[TE] bit and enter receive mode. Hence, software must program the transmit buffer with the next data to be transmitted and then enable the C2[TE] bit once software has determined that the last character of the received block has been received. The UART detects that the last character of the transmit block has been sent when TL7816[TLEN] = 0 and four additional characters have been sent. The four additional characters are made up of three prior to TL7816[TLEN] decrementing (prologue) and one after TL7816[TLEN] = 0, the final character of the epilogue.

## 49.4.7.4 Wait time and guard time parameters

The ISO-7816 specification defines several wait time and guard time parameters. The UART allows for flexible configuration and violation detection of these settings. On reset the wait time (IS7816[WT]) defaults to 9600 ETUs and guard time (GT) to 12 ETUs. These values are controlled by parameters in the WP7816, WN7816 and WF7816 registers. Additionally the value of C7816[TTYPE] also factors into the calculation. The formulas used to calculate the number ETU for each wait time and guard time value are shown in the following table.

Wait time (WT) is defined as the maximum allowable time between the leading edge of a character transmitted by the device (smartcard) and the leading edge of the previous character that was transmitted by the UART or the device. Likewise character wait time (CWT) is defined as the maximum allowable time between the leading edge of two characters within the same block, and block wait time (BWT) is defined as the maximum time between the leading edge character of the last block received by the device/smartcard.

Guard time (GT) is defined as the minimum allowable time between the leading edge of two consecutive characters. Character guard time (CGT) is the minimum allowable time between the leading edges of two consecutive characters in the same direction



(transmission or reception). Block guard time (BGT) is the minimum allowable time between the leading edges of two consecutive characters in opposite directions (transmission then reception or reception then transmission).

The GT and WT counters reset whenever C7816[TTYPE] = 1 or C7816[ISO\_7816E] = 0 or a new dataword start bit has been received or transmitted as specified by the counter descriptions. The CWT, CGT, BWT, BGT counters reset whenever C7816[TTYPE] = 0 or C7816[ISO\_7816E] = 0 or a new dataword start bit has been received or transmitted as specified by the counter descriptions. When C7816[TTYPE] = 1 some of the counter values require an assumption regarding the first data transferred when the UART first starts. This assumption is required when the 7816E has been disabled, when transition from C7816[TTYPE] = 0 to C7816[TTYPE] = 1 or when coming out of reset. In this case, it is assumed that the previous (non-existent) transfer was a received transfer.

The UART will automatically handle GT, CGT and BGT such that the UART will not send a packet prior to the corresponding guard time expiring.

Parameter	Reset value	C7816[TTYPE] = 0	C7816[TTYPE] = 1
Parameter	[ETU]	[ETU]	[ETU]
Wait time (WT)	9600	WI × 960 × GTFD	Not used
Character wait time (CWT)	Not used	Not used	11 + 2 <sup>CWI</sup>
Block wait time (BWT)	Not used	Not used	11 + 2 <sup>BWI</sup> × 960 × GTFD
Guard time (GT)	12	GTN not wqual to 255	Not used
		12 + GTN	
		GTN wqual to 255	
		12	
Character guard time (CGT)	Not used	Not used	GTN not equal to 255
			12 + GTN
			GTN equal to 255
			11
Block guard time (BGT)	Not used	Not used	22

Table 49-237. Wait and guard time calculations

## 49.4.7.5 Baud rate generation

The value in WF7816[GTFD] does not impact the clock frequency. The SBR and BRFD are used to generate the clock frequency. This clock frequency is used by the UART only and is not seen by the device (smartcard). The transmitter clocks operates at 1/16 the frequency of the receive clock so that the receiver is able to sample the received value 16 times during the ETU.



## 49.4.7.6 UART restrictions in ISO-7816 operation

Due to the flexibility of the UART module, there are several features and interrupts that are not supported while running in ISO-7816 mode. These restrictions are documented within the register bit definitions.

#### 49.4.8 Infrared interface

The UART provides the capability of transmitting narrow pulses to an IR LED and receiving narrow pulses and transforming them to serial bits, which are sent to the UART. The IrDA physical layer specification defines a half-duplex infrared communication link for exchanging data. The full standard includes data rates up to 16 Mbits/s. This design covers data rates only between 2.4 kbits/s and 115.2 kbits/s.

The UART has an infrared transmit encoder and receive decoder. The UART transmits serial bits of data which are encoded by the infrared submodule to transmit a narrow pulse for every zero bit. No pulse is transmitted for every one bit. When receiving data, the IR pulses are detected using an IR photo diode and transformed to CMOS levels by the IR receive decoder (external from the MCU). The narrow pulses are then stretched by the infrared receive decoder to get back to a serial bit stream to be received by the UART. The polarity of transmitted pulses and expected receive pulses can be inverted so that a direct connection can be made to external IrDA transceiver modules that use active low pulses.

The infrared submodule receives its clock sources from the UART. One of these two clocks are selected in the infrared submodule in order to generate either 3/16, 1/16, 1/32 or 1/4 narrow pulses during transmission.

## 49.4.8.1 Infrared transmit encoder

The infrared transmit encoder converts serial bits of data from transmit shift register to the TXD signal. A narrow pulse is transmitted for a zero bit and no pulse for a one bit. The narrow pulse is sent in the middle of the bit with a duration of 1/32, 1/16, 3/16 or 1/4 of a bit time. A narrow high pulse is transmitted for a zero bit when C3[TXINV] is cleared, while a narrow low pulse is transmitted for a zero bit when C3[TXINV] is set.



#### 49.4.8.2 Infrared receive decoder

The infrared receive block converts data from the RXD signal to the receive shift register. A narrow pulse is expected for each zero received and no pulse is expected for each one received. A narrow high pulse is expected for a zero bit when S2[RXINV] is cleared, while a narrow low pulse is expected for a zero bit when S2[RXINV] is set. This receive decoder meets the edge jitter requirement as defined by the IrDA serial infrared physical layer specification.

#### **49.5** Reset

All registers reset to a particular value are indicated in Memory map and registers.

# 49.6 System level interrupt sources

There are several interrupt signals that are sent from the UART. The following table lists the interrupt sources generated by the UART. The local enables for the UART interrupt sources are described in this table. Details regarding the individual operation of each interrupt are contained under various sub-sections of Memory map and registers. However, RXEDGIF description also outlines additional details regarding the RXEDGIF interrupt because of its complexity of operation. Any of the UART interrupt requests listed in the table can be used to bring the CPU out of wait mode.

Table 49-238. UART interrupt sources

Interrupt Source	Flag	Local enable	DMA select
Transmitter	TDRE	TIE	TDMAS = 0
Transmitter	TC	TCIE	-
Receiver	IDLE	ILIE	-
Receiver	RDRF	RIE	RDMAS = 0
Receiver	LBKDIF	LBKDIE	-
Receiver	RXEDGIF	RXEDGIE	-
Receiver	OR	ORIE	-
Receiver	NF	NEIE	-
Receiver	FE	FEIE	-
Receiver	PF	PEIE	-
Receiver	RXUF	RXUFE	-
Transmitter	TXOF	TXOFE	-

Table continues on the next page...



System level interrupt sources

Table 49-238. UART interrupt sources (continued)

Interrupt Source	Flag	Local enable	DMA select
Receiver	WT	WTWE	-
Receiver	CWT	CWTE	-
Receiver	BWT	BWTE	-
Receiver	INITD	INITDE	-
Receiver	TXT	TXTE	-
Receiver	RXT	RXTE	-
Receiver	GTV	GTVE	-

## 49.6.1 RXEDGIF description

The S2[RXEDGIF] is set when an active edge is detected on the RxD pin. Hence, the active edge can only be detected when in two wire mode. A RXEDGIF interrupt is only generated when S2[RXEDGIF] is set. If RXEDGIE is not enabled prior to S2[RXEDGIF] getting set, an interrupt is not generated until S2[RXEDGIF] bit gets set.

## 49.6.1.1 RxD edge detect sensitivity

Edge sensitivity can be software programmed to be either falling or rising. The polarity of the edge sensitivity is selected using the S2[RXINV] bit. To detect falling edge S2[RXINV] is programmed to zero and to detect rising edge S2[RXINV] is programmed to one.

Synchronizing logic is used prior to detect edges. Prior to detecting an edge, the receive data on RxD input must be at the de-asserted logic level. A falling edge is detected when the RxD input signal is seen as a logic 1 (the deasserted level) during one module clock cycle and then a logic 0 (the asserted level) during the next cycle. A rising edge is detected when the input is seen as a logic 0 during one module clock cycle and then a logic 1 during the next cycle.

# 49.6.1.2 Clearing RXEDGIF interrupt request

Writing a logic 1 to the S2[RXEDGIF] bit immediately clears the RXEDGIF interrupt request even if the RxD input remains asserted. S2[RXEDGIF] will remain set if another active edge is detected on RxD while attempting to clear the S2[RXEDGIF] flag by writing a 1 to it.



## 49.6.1.3 Exit from low-power modes

The receive input active edge detect circuit is still active on low power modes (wait and stop). An active edge on the receive input brings the CPU out of low power mode if the interrupt is not masked (S2[RXEDGIF]=1).

# 49.7 DMA operation

In the transmitter, flags S1[TDRE] can be configured to assert a DMA transfer request. In the receiver, flag S1[RDRF], can be configured to assert a DMA transfer request. The following table shows the configuration bit settings required to configure each flag for DMA operation.

 Flag
 Request enable bit
 DMA select bit

 TDRE
 TIE = 1
 TDMAS = 1

 RDRF
 RIE = 1
 RDMAS = 1

Table 49-239. DMA configuration

When a flag is configured for a DMA request, its associated DMA request is asserted when the flag is set. When the S1[RDRF] flag is configured as a DMA request, the clearing mechanism of reading S1 register followed by reading D register does not clear the associated flag. The DMA request remains asserted until an indication is received that the DMA transactions are done. When this indication is received, the flag bit and the associated DMA request are cleared. If the DMA operation failed to remove the situation that caused the DMA request another request will be issued.

# 49.8 Application information

This section describes the UART application information.

## 49.8.1 Transmit/receive data buffer operation

The UART has independent receive and transmit buffers. The size of these buffers may vary depending on the implementation of the module. The implemented size of the buffers is a fixed constant via the PFIFO[TXFIFOSIZE] and PFIFO[RXFIFOSIZE] fields. Additionally, legacy support is provided that allows for the FIFO structure to



#### Application information

operate as a depth of one. This is the default/reset behavior of the module and can be adjusted using the PFIFO[RXFE] and PFIFO[TXFE] bits. Individual watermark levels are also provided for transmit and receive.

There are multiple ways to ensure that a data block (set of characters) has completed transmission. These methods include:

- 1. Set TXFIFO[TXWATER] to 0. The TDRE flag will assert when there is no further data in the transmit buffer. Alternatively the S1[TC] flag can be used to indicate when the transmit shift register is also empty.
- 2. Poll the TCFIFO[TXCOUNT] field. Assuming that only data for a data block has been put into the data buffer, when TCFIFO[TXCOUNT] = 0 all data has been transmitted or is in the process of transmission.
- 3. The S1[TC] flag can be monitored. When S1[TC] asserts it indicates that all data has been transmitted and there is no data currently being transmitted in the shift register.

## 49.8.2 ISO-7816 initialization sequence

This section outlines how to program the UART for ISO-7816 operation. Elements such as procedures to power up or power down the smartcard, and when to take those actions, are beyond the scope of this description. To setup the UART for ISO-7816 operation:

- 1. Select a baud rate. Write this value to the UART baud registers (BDH/L) to begin the baud rate generator. Remember that the baud rate generator is disabled when the baud rate is zero. Writing to the BDH has no effect without also writing to BDL. According to the 7816 specification the initial (default) baud rating setting should be Fi = 372 and Di = 1 and a maximum frequency of 5 MHz. In other words the BDH, BDL and C4 registers should be programmed such that the transmission frequency should be 1/372th of the clock provided to the smartcard device and should not exceed 5 MHz.
- 2. Write to set BDH[LBKDIE] = 0.
- 3. Write to C1 to configure word length, parity, and other configuration bits (LOOPS, RSRC) and set C1[M] = 1, C1[PE] = 1, C1[PT] = 0.
- 4. Write to set S2[RWUID] = 0, S2[LBKDE] = 0.
- 5. Write to set MODEM[RXRTSE] = 0, MODEM[TXRTSPOL] = 0, MODEM[TXRTSE] = 0, and MODEM[TXCTSE] = 0.



- 6. Write to set up interrupt enable bits desired (C3[ORIE], C3[NEIE], C3[PEIE], and C3[FEIE])
- 7. Write to set C4[MAEN1] = 0 and C4[MAEN2] = 0.
- 8. Write to C5 register and configure DMA control register bits as desired for application.
- 9. Write to set C7816[INIT] = 1,C7816[ TTYPE] = 0, 7C7816[ISO\_7816E] = 1. Program C7816[ONACK] and C7816[ANACK] as desired.
- 10. Write to IE7816 register to set interrupt enable parameters as desired.
- 11. Write to ET7816 register and set as desired.
- 12. Write to set C2[ILIE] = 0, C2[RE] = 1, C2[TE] = 1, C2[RWU] = 0 and C2[SBK] = 0. Setup interrupt enables C2[TIE], C2[TCIE] and C2[RIE] as desired.

At this time the UART will start listening for an initial character. Once identified it will automatically adjust the S2[MSBF], C3[TXINV] and S2[RXINV] bits. The software should then receive and process an answer to reset. Upon processing the answer to reset software should write to set C2[RE] = 0 and C2[TE] = 0. Software should then adjust 7816 specific and UART generic parameters to match and configuration data that was received during the answer on reset period. Once the new settings have been programmed (including the new baud rate and C7816[TTYPE]) the C2[RE] and C2[TE] can be reenabled as required.

# 49.8.2.1 Transmission procedure for (C7816[TTYPE] = 0)

When the protocol selected is C7816[TTYPE] = 0, it is assumed that the software has a prior knowledge of who should be transmitting and receiving. Hence, no mechanism is provided for automated transmission/receipt control. Software should monitor the S1[TDRE] flag (or configure for an interrupt) and provide additional data for transmission as appropriate. Additionally, software should set C2[TE] = 1 and control TXDIR whenever it is the UART's turn to transmit information. For ease of monitoring it is suggested that only data to be transmitted until the next receiver/transmit switch over be loaded into the transmit buffer/FIFO.



**Application information** 

## 49.8.2.2 Transmission procedure for (C7816[TTYPE] = 1)

When the protocol selected is C7816[TTYPE] = 1, data is transferred in blocks. Prior to starting a transmission software should write the size (number of bytes) for the Information Field portion of the block in to the TLEN register. If a CRC is being transmitted for the block the value in TLEN should be one more than the size of the information field. Software should then set C2[TE] = 1, and C2[RE] = 1. Software should then monitor the S1[TDRE] flag / interrupt and write the prologue, Information and epilogue field to the transmit buffer. The TLEN register will automatically decrement (except for prologue bytes and the final epilogue byte). When the final epilogue byte has been transmitted the UART automatically clears the C2[TE] bit to 0, and the UART automatically starts capturing the response to the block that was transmitted. Once software has detected the receipt of the response, the transmission process should be repeated as needed with sufficient urgency to ensure that the block wait time and character wait times are not violated.

## 49.8.3 Initialization sequence (non ISO-7816)

To initiate an UART transmission:

- 1. Configure the UART:
  - a. Select a baud rate. Write this value to the UART baud registers (BDH/L) to begin the baud rate generator. Remember that the baud rate generator is disabled when the baud rate is zero. Writing to the BDH register has no effect without also writing to BDL register.
  - b. Write to C1 register to configure word length, parity, and other configuration bits (LOOPS, RSRC, M, WAKE, ILT, PE, PT). Write to C4, MA1 and MA2 register to configure.
  - c. Enable the transmitter, interrupts, receiver, and wakeup as required by writing to the C2 register bits (TIE, TCIE, RIE, ILIE, TE, RE, RWU, SBK), S2 register bits (MSBF, BRK13) and C3 register bits (ORIE, NEIE, PEIE, FEIE). A preamble or idle character is then shifted out of the transmitter shift register.
- 2. Transmit procedure for each byte:
  - a. Monitor the S1[TDRE] flag by reading the S1 or responding to the TDRE interrupt. Or monitor the amount of free space in the transmit buffer directly using TCFIFO[TXCOUNT].



- b. If the TDRE flag is set, or there is space in the transmit buffer, write the data to be transmitted to (C3[T8]/D). A new transmission will not result until data exists in the transmit buffer.
- 3. Repeat step 2 for each subsequent transmission.

#### **Note**

During normal operation, the S1[TDRE] flag is set when the shift register is loaded with the next data to be transmitted from the transmit buffer and the number of datawords contained in the transmit buffer is less than or equal to the value in TWFIFO[TXWATER], which occurs 9/16ths of a bit time after the start of the stop bit of the previous frame.

To separate messages with preambles with minimum idle line time, use this sequence between messages:

- 1. Write the last dataword of the first message to C3[T8]/D.
- 2. Wait for the S1[TDRE] flag to go high (with TWFIFO[TXWATER] = 0), indicating the transfer of the last frame to the transmit shift register.
- 3. Queue a preamble by clearing and then setting the C2[TE] bit.
- 4. Write the first (and subsequent) datawords of the second message to C3[T8]/D.

## 49.8.4 Overrun (OR) flag implications

To be flexible the overrun flag (OR) operates slight differently depending on the mode of operation. As such there may be implications that need to be carefully considered. This section clarifies that behavior and the resulting implications. Regardless of mode, if a dataword is received while the S1[OR] flag is set, the S1[RDRF] and S1[IDLE] flags are blocked from asserting. If the S1[RDRF] or S1[IDLE] flag were previously asserted they will remain asserted until cleared.

## 49.8.4.1 Overrun operation

The assertion of the S1[OR] flag indicates that a significant event has occurred. The assertion indicates that received data has been lost since there was a lack of room to store it in the data buffer. Hence, while the S1[OR] flag is set no further data will be stored in the data buffer until the S1[OR] flag is cleared. This ensures that the application will be able to handle the overrun condition.



#### **Application information**

In most applications since the total amount of lost data is known, the application will desire to return the system to a known state. Prior to the S1[OR] flag being cleared all received data will be dropped. To do this the software would:

- 1. Remove data from the receive data buffer. This could be done by reading data from the data buffer and processing it if the data in the FIFO was still valuable when though the overrun event occurred or using the CFIFO[RXFLUSH] bit to clear the buffer.
- 2. Clear the S1[OR] flag. Note that if data was cleared using the CFIFO[RXFLUSH] bit, then clearing the S1[OR] flag will result in the SFIFO[RXUF] flag asserting because the only way to clear the S1[OR] requires reading additional information from the FIFO. Care should be taken to disable the SFIFO[RXUF] interrupt prior to clearing the OR flag and then clearing the SFIFO[RXUF] flag after the OR flag has been cleared.

Note that in some applications if an overrun event is responded to fast enough, the lost data can be recovered. For example when C7816[ISO\_7816E] is asserted, C7816[TTYPE]=1 and C7816[ONACK] = 1 the application may reasonably be able to determine if the lost data will be resent by the device. In this scenario flushing the receiver data buffer might not be required. Rather, if the S1[OR] flag is cleared the lost data may be resent and hence recoverable.

When LIN break detect (LBKDE) is asserted the S1[OR] flag has significantly different behavior than in other modes. The S1[OR] bit will be set, regardless of how much space is actually available in the data buffer, if a LIN break character has been detected and the corresponding flag (S2[LBKDIF]) is not cleared before the first data character is received after the S2[LBKDIF] asserted. This behavior is intended to allow software sufficient time to read the LIN break character from the data buffer to ensure that a break character was actually detected. The checking of the break character was used on some older implementations and is hence supported for legacy reasons. Applications that do not require this checking can simply clear the S2[LBKDIF] without checking the stored value to ensure it is a break character.

## 49.8.5 Overrun NACK considerations

When C7816[ISO\_7816E] is enabled and C7816[TTYPE] = 0 the retransmission feature of the 7816 protocol can be used to help avoid lost data when the data buffer overflows. Using C7816[ONACK] the module can be programmed to issue a NACK on an overflow event. Assuming that the device (smartcard) has implemented retransmission, the lost data will be retransmitted. While useful, there is a programming implication which may require special consideration. The need to transmit a NACK must be determined and



committed to prior to the dataword being fully received. While the NACK is being received it is possible that the application code will read the data buffer such that sufficient room will be made to store the dataword that is being NACKed. Even if room has been made in the data buffer once the transmission of a NACK is completed, the received data will always be discarded as a result of an overflow and the ET7816[RXTHRESHOLD] value will be incremented by one. However, if sufficient space now exists to write the received data which was NACK'ed the S1[OR] flag will be blocked and kept from asserting.

## 49.8.6 Match address registers

The two match address registers allow a second match address function for a broadcast or general call address to the serial bus, as an example.

#### 49.8.7 Modem feature

This section describes the modem features.

# 49.8.7.1 Ready-to-receive using RTS

To help to stop overrun of the receiver data buffer, the  $\overline{RTS}$  signal can be used by the receiver to indicate to another UART that it is ready to receive data. The other UART can send the data when its  $\overline{CTS}$  signal is asserted. This handshaking conforms to the TIA-232-E standard. A transceiver is necessary if the required voltage levels of the communication link do not match the voltage levels of the UART's  $\overline{RTS}$  and  $\overline{CTS}$  signals.




Figure 49-245. Ready-to-receive

The transmitter's  $\overline{CTS}$  signal can be used for hardware flow control whether its  $\overline{RTS}$  signal is used for hardware flow control, transceiver driver enable, or not at all.



**Application information** 

## 49.8.7.2 Transceiver driver enable using RTS

RS-485 is a multiple drop communication protocol in which the UART transceiver's driver is 3-stated unless that UART is driving. The  $\overline{RTS}$  signal can be used by the transmitter to enable the driver of a transceiver. The polarity of  $\overline{RTS}$  can be matched to the polarity of the transceiver's driver enable signal. Refer to the following figure.




Figure 49-246. Transceiver driver enable using RTS

In the figure, the receiver enable signal is asserted. Another option for that connection is to connect RTS\_B to both DE and RE\_B. The transceiver's receiver is disabled while driving. A pullup can pull RXD to a non-floating value during this time. This option can be refined further by operating the UART in single-wire mode, freeing the RXD pin for other uses.

## 49.8.8 IrDA minimum pulse width

The IrDA specifies a minimum pulse width of 1.6  $\mu$ s. The UART hardware does not include a mechanism to restrict/force the pulse width to be greater than or equal to 1.6  $\mu$ s. However, configuring the baud rate to 115.2 kbit/s and the narrow pulse width to 3/16 of a bit time results in a pulse width of 1.6  $\mu$ s.

# 49.8.9 Clearing 7816 wait timer (WT, BWT, CWT) interrupts

The 7816 wait timer interrupts associated with IS7816[WT], IS7816[BWT] and IS7816[CWT] will automatically reassert if they are cleared and the wait time is still violated. This behavior is similar to most of the other interrupts on the UART as in most cases if the condition that caused the interrupt to trigger still exists when the interrupt is cleared, than the interrupt will reassert. For example, consider the following scenario:

- 1. IS7816[WT] is programmed to assert after 9600 cycles of unresponsiveness.
- 2. The 9600 cycles pass without a response resulting in the WT interrupt asserting.
- 3. The IS7816[WT] is cleared at cycle 9700 by the interrupt service routine.



4. After the WT interrupt has been cleared, the smartcard remains unresponsive. At cycle 9701 the WT interrupt will reasserted.

If the intent of clearing the interrupt is such that it does not reassert, the interrupt service routine must remove or clear the condition that originally caused the interrupt to assert prior to clearing the interrupt. There are multiple ways that this can be accomplished including ensuring that an event that results in the wait timer resetting occurs such as the transmission of another packet.

## 49.8.10 Legacy and reverse compatibility considerations

Recent versions of the UART have added several new features. Whenever reasonably possible reverse compatibility was maintained, however, in some cases this was either not feasible or the behavior was deemed as not intended. This section describes several differences to legacy operation that resulted from these recent enhancements. If application codes from previous versions is used, they should be reviewed and modified to take the following items into account. Depending on the application code, additional items that are not listed here may also need to be considered.

- 1. Various reserved registers and register bits were used (i.e. MSFB and M10).
- 2. This module now generates an error when invalid address spaces are used.
- 3. While documentation indicated otherwise, in some cases it was possible for S1[IDLE] to assert even if S1[OR] was set.
- 4. The S1[OR] flag will only be set if the data buffer (FIFO) does not have sufficient room. Previously, the data buffer was always a fixed size of one and the S1[OR] flag would set so long as the S1[RDRF] flag was set even if there was room in the data buffer. While the clearing mechanism is has remained the save for the S1[RDRF] flag, keeping the OR flag assertion tied to the RDRF event rather than the data buffer being full would have greatly reduced the usefulness of the buffer when its size is larger than one.
- 5. Previously when the C2[RWU] was set (and WAKE = 0), the IDLE flag could reassert up to every bit period causing an interrupt and requiring the host processor to reassert the C2[RWU] bit. This behavior has been modified. Now, when the C2[RWU] is set (and WAKE = 0) at least one non-idle bit must be detected before an idle can be detected.



Application information



# Chapter 50 Secured digital host controller (SDHC)

#### 50.1 Introduction

#### NOTE

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The chapter is intended for a module driver software developer. It describes module-level operation and programming.

## 50.2 Overview

## 50.2.1 Supported types of cards

Different types of cards supported by the SDHC are described briefly as follows:

The multi-media card (MMC) is a universal low cost data storage and communication media that is designed to cover a wide area of applications including mobile video and gaming. Old MMC cards are based on a 7-pin serial bus with a single data pin, while the new high speed MMC communication is based on an advanced 11-pin serial bus designed to operate in the low voltage range.

The secure digital card (SD) is an evolution of the old MMC technology. It is specifically designed to meet the security, capacity, performance, and environment requirements inherent in newly emerging audio and video consumer electronic devices. The physical form factor, pin assignment and data transfer protocol are forward compatible with the old MMC (with some additions).

Under the SD protocol, it can be categorized into memory card, I/O card and combo card, which has both memory and I/O functions. The memory card invokes a copyright protection mechanism that complies with the security of the SDMI standard. The I/O



#### Overview

card, which is also known as SDIO card, provides high-speed data I/O with low power consumption for mobile electronic devices. For the sake of simplicity, the figure does not show cards with reduced size or mini cards.




Figure 50-1. System connection of the SDHC

CE-ATA is a hard drive interface that is optimized for embedded applications storage. The device is layered on the top of the MMC protocol stack using the same physical interface. The interface electrical and signaling definition is defined like that in the MMC specification. Refer to the CE-ATA specification for more details.



## 50.2.2 SDHC block diagram




Figure 50-2. Enhanced secure digital host controller block diagram

## 50.2.3 Features

The features of the SDHC module include the following:

- Conforms to the SD Host Controller Standard Specification version 2.0 including test event register support
- Compatible with the MMC System Specification version 4.2/4.3
- Compatible with the SD Memory Card Specification version 2.0 and supports the high capacity SD memory card
- Compatible with the SDIO Card Specification version 2.0
- Compatible with the CE-ATA Card Specification version 1.0



#### Overview

- Designed to work with CE-ATA, SD memory, miniSD memory, SDIO, miniSDIO, SD Combo, MMC, MMC plus, and MMC RS cards
- Card bus clock frequency up to 52 MHz
- Supports 1-bit / 4-bit SD and SDIO modes, 1-bit / 4-bit / 8-bit MMC modes, 1-bit / 4-bit / 8-bit CE-ATA devices
  - Up to 200 Mbps of data transfer for SD/SDIO cards using 4 parallel data lines
  - Up to 416 Mbps of data transfer for MMC cards using 8 parallel data lines in SDR (single data rate) mode
- Supports single block, multi-block read and write
- Supports block sizes of 1 ~ 4096 bytes
- Supports the write protection switch for write operations
- Supports both synchronous and asynchronous abort (both hardware and software CMD12)
- Supports pause during the data transfer at block gap
- Supports SDIO read wait and suspend resume operations
- Supports auto CMD12 for multi-block transfer
- Host can initiate non-data transfer command while data transfer is in progress
- Allows cards to interrupt the host in 1-bit and 4-bit SDIO modes, also supports interrupt period
- Embodies a fully configurable 128x32-bit FIFO for read/write data
- Supports internal and external DMA capabilities
- Supports advanced DMA to perform linked memory access

## 50.2.4 Modes and operations

The SDHC can select the following modes for data transfer:

- SD 1-bit
- SD 4-bit
- MMC 1-bit



- MMC 4-bit
- MMC 8-bit
- CE-ATA 1-bit
- CE-ATA 4-bit
- CE-ATA 8-bit
- Identification mode (up to 400 kHz)
- MMC full speed mode (up to 20 MHz)
- MMC high speed mode (up to 52 MHz)
- SD/SDIO full speed mode (up to 25 MHz)
- SD/SDIO high speed mode (up to 50 MHz)

# 50.3 SDHC signal descriptions

## Table 50-1. SDHC signal descriptions

Signal	Description	I/O
SDHC_DCLK	Generated clock used to drive the MMC, SD, SDIO or CE-ATA cards.	0
SDHC_CMD	Send commands to and receive responses from the card.	I/O
SDHC_D0	DAT0 line or busy-state detect	I/O
SDHC_D1	8-bit mode: DAT1 line	I/O
	4-bit mode: DAT1 line or interrupt detect	
	1-bit mode: Interrupt detect	
SDHC_D2	4-/8-bit mode: DAT2 line or read wait	I/O
	1-bit mode: Read wait	
SDHC_D3	4-/8-bit mode: DAT3 line or configured as card detection pin	I/O
	1-bit mode: May be configured as card detection pin	
SDHC_D4	DAT4 line in 8-bit mode	I/O
	Not used in other modes	
SDHC_D5	DAT5 line in 8-bit mode	I/O
	Not used in other modes	

Table continues on the next page...



#### wemory map and register definition

Table 50-1. SDHC signal descriptions (continued)

Signal	Description	I/O
SDHC_D6	DAT6 line in 8-bit mode	I/O
	Not used in other modes	
SDHC_D7	DAT7 line in 8-bit mode	I/O
	Not used in other modes	

# 50.4 Memory map and register definition

This section includes the module memory map and detailed descriptions of all registers.

#### **SDHC** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400B_1000	DMA System Address Register (SDHC_DSADDR)	32	R/W	0000_0000h	50.4.1/ 1329
400B_1004	Block Attributes Register (SDHC_BLKATTR)	32	R/W	0000_0000h	50.4.2/ 1330
400B_1008	Command Argument Register (SDHC_CMDARG)	32	R/W	0000_0000h	50.4.3/ 1331
400B_100C	Transfer Type Register (SDHC_XFERTYP)	32	R/W	0000_0000h	50.4.4/ 1332
400B_1010	Command Response 0 (SDHC_CMDRSP0)	32	R	0000_0000h	50.4.5/ 1336
400B_1014	Command Response 1 (SDHC_CMDRSP1)	32	R	0000_0000h	50.4.6/ 1337
400B_1018	Command Response 2 (SDHC_CMDRSP2)	32	R	0000_0000h	50.4.7/ 1337
400B_101C	Command Response 3 (SDHC_CMDRSP3)	32	R	0000_0000h	50.4.8/ 1337
400B_1020	Buffer Data Port Register (SDHC_DATPORT)	32	R/W	0000_0000h	50.4.9/ 1339
400B_1024	Present State Register (SDHC_PRSSTAT)	32	R	0000_0000h	50.4.10/ 1339
400B_1028	Protocol Control Register (SDHC_PROCTL)	32	R/W	0000_0020h	50.4.11/ 1344
400B_102C	System Control Register (SDHC_SYSCTL)	32	R/W	0000_8008h	50.4.12/ 1348

Table continues on the next page...




#### **SDHC** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400B_1030	Interrupt Status Register (SDHC_IRQSTAT)	32	R/W	0000_0000h	50.4.13/ 1351
400B_1034	Interrupt Status Enable Register (SDHC_IRQSTATEN)	32	R/W	117F_013Fh	50.4.14/ 1357
400B_1038	Interrupt Signal Enable Register (SDHC_IRQSIGEN)	32	R/W	0000_0000h	50.4.15/ 1360
400B_103C	Auto CMD12 Error Status Register (SDHC_AC12ERR)	32	R	0000_0000h	50.4.16/ 1362
400B_1040	Host Controller Capabilities (SDHC_HTCAPBLT)	32	R	07F3_0000h	50.4.17/ 1365
400B_1044	Watermark Level Register (SDHC_WML)	32	R/W	0010_0010h	50.4.18/ 1367
400B_1050	Force Event Register (SDHC_FEVT)	32	W (always reads zero)	0000_0000h	50.4.19/ 1367
400B_1054	ADMA Error Status Register (SDHC_ADMAES)	32	R	0000_0000h	50.4.20/ 1370
400B_1058	ADMA System Address Register (SDHC_ADSADDR)	32	R/W	0000_0000h	50.4.21/ 1372
400B_10C0	Vendor Specific Register (SDHC_VENDOR)	32	R/W	0000_0001h	50.4.22/ 1372
400B_10C4	MMC Boot Register (SDHC_MMCBOOT)	32	R/W	0000_0000h	50.4.23/ 1374
400B_10FC	Host Controller Version (SDHC_HOSTVER)	32	R	0000_1201h	50.4.24/ 1375

# 50.4.1 DMA System Address Register (SDHC\_DSADDR)

This register contains the physical system memory address used for DMA transfers.

Address: SDHC\_DSADDR is 400B\_1000h base + 0h offset = 400B\_1000h



#### SDHC\_DSADDR field descriptions

Field	Description
31–2 DSADDR	DMA System Address

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### wemory map and register definition


## **SDHC\_DSADDR** field descriptions (continued)

Field	Description			
	This register contains the 32-bit system memory address for a DMA transfer. Since the address must be word (4 bytes) align, the least 2 bits are reserved, always 0. When the SDHC stops a DMA transfer, this register points to the system address of the next contiguous data position. It can be accessed only when no transaction is executing (i.e. after a transaction has stopped). Read operation during transfers may return an invalid value. The host driver shall initialize this register before starting a DMA transaction. After DMA has stopped, the system address of the next contiguous data position can be read from this register. This register is protected during a data transfer. When data lines are active, write to this register is ignored. The host driver shall wait, until the PRSSTAT[DLA] is cleared, before writing to this register.			
	The SDHC internal DMA does not support a virtual memory system. It only supports continuous physical memory access. And due to AHB burst limitations, if the burst must cross the 1 KB boundary, SDHC will automatically change SEQ burst type to NSEQ.			
	Since this register supports dynamic address reflecting, when IRQSTAT[TC] bit is set, it automatically alters the value of internal address counter, so SW cannot change this register when IRQSTAT[TC] bit is set.			
1–0 Reserved	This read-only field is reserved and always has the value zero.			

## 50.4.2 Block Attributes Register (SDHC\_BLKATTR)

This register is used to configure the number of data blocks and the number of bytes in each block.

Address: SDHC\_BLKATTR is 400B\_1000h base + 4h offset = 400B\_1004h



#### SDHC\_BLKATTR field descriptions

Field	Description
31–16 BLKCNT	Blocks Count For Current Transfer
BENOINT	This register is enabled when the XFERTYP[BCEN] is set to 1 and is valid only for multiple block transfers. For single block transfer, this register will always read as 1. The host driver shall set this register to a value between 1 and the maximum block count. The SDHC decrements the block count after each block transfer and stops when the count reaches zero. Setting the block count to 0 results in no data blocks being transferred.
	This register should be accessed only when no transaction is executing (that is after transactions are stopped). During data transfer, read operations on this register may return an invalid value and write operations are ignored.
	When saving transfer content as a result of a suspend command, the number of blocks yet to be transferred can be determined by reading this register. The reading of this register should be applied after transfer is paused by stop at block gap operation and before sending the command marked as suspend. This is because when suspend command is sent out, SDHC will regard the current transfer is aborted and change BLKCNT back to its original value instead of keeping the dynamical indicator of remained block count.

Table continues on the next page...

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




## SDHC\_BLKATTR field descriptions (continued)

Field	Description			
	When restoring transfer content prior to issuing a resume command, the host driver shall restore the previously saved block count.			
	NOTE: Although the BLKCNT field is 0 after reset, the read of reset value is 0x1. This is because when XFERTYP[MSBSEL] bit is 0, indicating a single block transfer, the read value of BLKCNT is always 1.			
	0000h Stop count			
	0001h 1 block			
	0002h 2 blocks			
	···			
	FFFFh 65535 blocks			
15–13 Reserved	This read-only field is reserved and always has the value zero.			
12-0 BLKSIZE	Transfer Block Size			
BEIGIZE	This register specifies the block size for block data transfers. Values ranging from 1 byte up to the maximum buffer size can be set. It can be accessed only when no transaction is executing (that is after a transaction has stopped). Read operations during transfers may return an invalid value, and write operations will be ignored.			
	000h No data transfer			
	001h 1 Byte			
	002h 2 Bytes			
	003h 3 Bytes			
	004h 4 Bytes			
	1FFh 511 Bytes			
	200h 512 Bytes			
	800h 2048 Bytes			
	1000h 4096 Bytes			

## 50.4.3 Command Argument Register (SDHC\_CMDARG)

This register contains the SD/MMC command argument.







#### SDHC\_CMDARG field descriptions

Field	Description
31-0 CMDARG	Command Argument  The CD/MMC command argument is an ariffied as hits 20.0 of the command format in the CD or MMC.
	The SD/MMC command argument is specified as bits 39-8 of the command format in the SD or MMC specification. This register is write protected when the PRSSTAT[CDIHB0] bit is set.

## 50.4.4 Transfer Type Register (SDHC\_XFERTYP)

This register is used to control the operation of data transfers. The host driver shall set this register before issuing a command followed by a data transfer, or before issuing a resume command. To prevent data loss, the SDHC prevents writing to the bits, that are involved in the data transfer of this register, when data transfer is active. These bits are DPSEL, MBSEL, DTDSEL, AC12EN, BCEN and DMAEN.

The host driver shall check the PRSSTAT[CDIHB] and the PRSSTAT[CIHB] before writing to this register. When the PRSSTAT[CDIHB] is set, any attempt to send a command with data by writing to this register is ignored; when the PRSSTAT[CIHB] bit is set, any write to this register is ignored.

On sending commands with data transfer invovled, it is mandatory that the block size is non-zero. Besides, block count must also be non-zero, or indicated as single block transfer (bit 5 of this register is '0' when written), or block count is disabled (bit 1 of this register is '0' when written), otherwise SDHC will ignore the sending of this command and do nothing. For write command, with all above restrictions, it is also mandatory that the write protect switch is not active (WPSPL bit of Present State Register is '1), otherwise SDHC will also ignore the command.

If the commands with data transfer does not receive the response in 64 clock cycles, i.e., response time-out, SDHC will regard the external device does not accept the command and abort the data transfer. In this scenario, the driver should issue the command again to re-try the transfer. It is also possible that for some reason the card responds the command but SDHC does not receive the response, and if it is internal DMA (either simple DMA or ADMA) read operation, the external system memory is over-written by the internal DMA with data sent back from the card.

The following table shows the summary of how register settings determine the type of data transfer.

Table 50-7. Transfer Type Register Setting for Various Transfer Types

Multi/Single block select	Block count enable	Block count	Function
0	Don't care	Don't care	Single transfer

Table continues on the next page...



Table 50-7. Transfer Type Register Setting for Various Transfer Types (continued)

Multi/Single block select	Block count enable	Block count	Function		
1	0	Don't care	Infinite transfer		
1	1	Positive number	Multiple transfer		
1	1	Zero	No data transfer		

The following table shows the relationship between the XFERTYP[CICEN] and XFERTYP[CCCEN], in regards to the XFERTYP[RSPTYP] as well as the name of the response type.

Table 50-8. Relationship Between Parameters and the Name of the Response Type


Response type (RSPTYP)	Index check enable (CICEN)	CRC check enable (CCCEN)	Name of response type			
00	0	0	No Response			
01	0	1	IR2			
10	0	0	R3,R4			
10	1	1	R1,R5,R6			
11	1	1	R1b,R5b			

#### NOTE

- In the SDIO specification, response type notation for R5b is not defined. R5 includes R5b in the SDIO specification. But R5b is defined in this specification to specify that the SDHC will check the busy status after receiving a response. For example, usually CMD52 is used with R5, but the I/O abort command shall be used with R5b.
- The CRC field for R3 and R4 is expected to be all 1 bits. The CRC check shall be disabled for these response types.



Address: SDHC\_XFERTYP is 400B\_1000h base + Ch offset = 400B\_100Ch



## SDHC\_XFERTYP field descriptions

Field	Description										
31–30 Reserved	This read-only field is reserved and always has the value zero.										
29–24 CMDINX	Command Index  These bits shall be set to the command number that is specified in bits 45-40 of the command-format in the SD Memory Card Physical Layer Specification and SDIO Card Specification.										
23–22 CMDTYP	Command Type  There are three types of special commands: suspend, resume and abort. These bits shall be set to 00b for all other commands.  • Suspend command: If the suspend command succeeds, the SDHC shall assume that the card bus has been released and that it is possible to issue the next command which uses the DAT line. Since the SDHC does not monitor the content of command response, it does not know if the suspend command succeeded or not. It is the host driver's responsibility to check the status of the suspend command and send another command marked as suspend to inform the SDHC that a suspend command was successfully issued. After the end bit of command is sent, the SDHC de-asserts read wait for read transactions and stops checking busy for write transactions. In 4-bit mode, the interrupt cycle starts. If the suspend command fails, the SDHC will maintain its current state, and the host driver shall restart the transfer by setting the PROCTL[CREQ].  • Resume command: The host driver re-starts the data transfer by restoring the registers saved before sending the suspend command and then sends the resume command. The SDHC will check for a pending busy state before starting write transfers.  • Abort command: If this command is set when executing a read transfer, the SDHC will stop reads to the buffer. If this command is set when executing a write transfer, the SDHC will stop driving the DAT line. After issuing the abort command, the host driver should issue a software reset (abort transaction).  Normal other commands  Olb Normal other commands  Suspend CMD52 for writing bus suspend in CCCR  10b Resume CMD52 for writing function select in CCCR										
21 DPSEL	Data Present Select										



# SDHC\_XFERTYP field descriptions (continued)

Field	Description									
	This bit is set to 1 to indicate that data is present and shall be transferred using the DAT line. It is set to 0 for the following:  • Commands using only the CMD line (for example: CMD52).  • Commands with no data transfer, but using the busy signal on DAT[0] line (R1b or R5b, for example: CMD38).									
	NOTE: In resume command, this bit shall be set, and other bits in this register shall be set the same as when the transfer was initially launched. When the Write Protect switch is on, (i.e. the WPSPL bit is active as '0'), any command with a write operation will be ignored. That is to say, when this bit is set, while the DTDSEL bit is 0, writes to the register Transfer Type are ignored.									
	0b No data present 1b Data present									
20 CICEN	Command Index Check Enable									
CICEN	If this bit is set to 1, the SDHC will check the index field in the response to see if it has the same value as the command index. If it is not, it is reported as a command index error. If this bit is set to 0, the index field is not checked.									
	0b Disable 1b Enable									
19 CCCEN	Command CRC Check Enable									
OCCLIV	If this bit is set to 1, the SDHC shall check the CRC field in the response. If an error is detected, it is reported as a Command CRC Error. If this bit is set to 0, the CRC field is not checked. The number of bits checked by the CRC field value changes according to the length of the response.									
	0b Disable 1b Enable									
18 Reserved	This read-only field is reserved and always has the value zero.									
17–16 RSPTYP	Response Type Select									
110. 111	00b No response									
	<ul><li>01b Response length 136</li><li>10b Response length 48</li></ul>									
	11b Response length 48, check busy after response									
15–6 Reserved	This read-only field is reserved and always has the value zero.									
5 MSBSEL	Multi/Single Block Select  This bit enables multiple block DAT line data transfers. For any other commands, this bit shall be set to 0. If this bit is 0, it is not necessary to set the block count register.									
	0b Single block 1b Multiple blocks									
4	Data Transfer Direction Select									
DTDSEL	This bit defines the direction of DAT line data transfers. The bit is set to 1 by the host driver to transfer data from the SD card to the SDHC and is set to 0 for all other commands.									




## SDHC\_XFERTYP field descriptions (continued)

Field	Description
	0b Write (host to card)
	1b Read (card to host)
3 Reserved	This read-only field is reserved and always has the value zero.
2 AC12EN	Auto CMD12 Enable  Multiple block transfers for memory require a CMD12 to stop the transaction. When this bit is set to 1, the SDHC will issue a CMD12 automatically when the last block transfer has completed. The host driver shall not set this bit to issue commands that do not require CMD12 to stop a multiple block data transfer. In particular, secure commands defined in File Security Specification (see reference list) do not require CMD12. In single block transfer, the SDHC will ignore this bit no matter if it is set or not.  Ob Disable  1b Enable
1 BCEN	Block Count Enable  This bit is used to enable the Block Count register, which is only relevant for multiple block transfers.  When this bit is 0, the internal counter for block is disabled, which is useful in executing an infinite transfer.  Ob Disable  1b Enable
0 DMAEN	DMA Enable  This bit enables DMA functionality. If this bit is set to 1, a DMA operation shall begin when the host driver sets the DPSEL bit of this register. Whether the simple DMA, or the advanced DMA, is active depends on the PROCTL[DMAS].  Ob Disable  1b Enable

# 50.4.5 Command Response 0 (SDHC\_CMDRSP0)

This register is used to store part 0 of the response bits from the card.

Address: SDHC\_CMDRSP0 is 400B\_1000h base + 10h offset = 400B\_1010h



## SDHC\_CMDRSP0 field descriptions


Field	Description
31-0 CMDRSP0	Command Response 0



# 50.4.6 Command Response 1 (SDHC\_CMDRSP1)

This register is used to store part 1 of the response bits from the card.

Address: SDHC\_CMDRSP1 is 400B\_1000h base + 14h offset = 400B\_1014h




### SDHC\_CMDRSP1 field descriptions

Field	Description
31-0 CMDRSP1	Command Response 1

# 50.4.7 Command Response 2 (SDHC\_CMDRSP2)

This register is used to store part 2 of the response bits from the card.

Address: SDHC\_CMDRSP2 is 400B\_1000h base + 18h offset = 400B\_1018h



## SDHC\_CMDRSP2 field descriptions

Field	Description	]
31-0 CMDRSP2	Command Response 2	Ī

# 50.4.8 Command Response 3 (SDHC\_CMDRSP3)

This register is used to store part 3 of the response bits from the card.

The following table describes the mapping of command responses from the SD bus to command response registers for each response type. In the table, R[] refers to a bit range within the response data as transmitted on the SD bus.



Table 50-13. Response bit definition for each response type


Response type	Meaning of response	Response field	Response register				
R1,R1b (normal response)	Card status	R[39:8]	CMDRSP0				
R1b (Auto CMD12 response)	Card status for auto CMD12	R[39:8]	CMDRSP3				
R2 (CID, CSD register)	CID/CSD register [127:8]	R[127:8]	{CMDRSP3[23:0], CMDRSP2, CMDRSP1, CMDRSP0}				
R3 (OCR register)	OCR register for memory	R[39:8]	CMDRSP0				
R4 (OCR register)	OCR register for I/O etc.	R[39:8]	CMDRSP0				
R5, R5b	SDIO response	R[39:8]	CMDRSP0				
R6 (Publish RCA)	New published RCA[31:16] and card status[15:0]	R[39:9]	CMDRSP0				

This table shows that most responses with a length of 48 (R[47:0]) have 32-bit of the response data (R[39:8]) stored in the CMDRSP0 register. Responses of type R1b (auto CMD12 responses) have response data bits (R[39:8]) stored in the CMDRSP3 register. Responses with length 136 (R[135:0]) have 120-bit of the response data (R[127:8]) stored in the CMDRSP0, 1, 2, and 3 registers.

To be able to read the response status efficiently, the SDHC only stores part of the response data in the command response registers. This enables the host driver to efficiently read 32-bit of response data in one read cycle on a 32-bit bus system. Parts of the response, the index field and the CRC, are checked by the SDHC (as specified by the XFERTYP[CICEN] and the XFERTYP[CCCEN] bits) and generate an error interrupt if any error is detected. The bit range for the CRC check depends on the response length. If the response length is 48, the SDHC will check R[47:1], and if the response length is 136 the SDHC will check R[119:1].

Since the SDHC may have a multiple block data transfer executing concurrently with a CMD\_wo\_DAT command, the SDHC stores the auto CMD12 response in the CMDRSP3 register. The CMD\_wo\_DAT response is stored in CMDRSP0. This allows the SDHC to avoid overwriting the Auto CMD12 response with the CMD\_wo\_DAT and vice versa. When the SDHC modifies part of the command response registers, as shown in the table above, it preserves the unmodified bits.








### SDHC\_CMDRSP3 field descriptions

Field	Description
31-0 CMDRSP3	Command Response 3

## 50.4.9 Buffer Data Port Register (SDHC\_DATPORT)

This is a 32-bit data port register used to access the internal buffer and it can not be updated in idle mode.

Address: SDHC\_DATPORT is 400B\_1000h base + 20h offset = 400B\_1020h



### SDHC\_DATPORT field descriptions

Description
Data Port register is for 32-bit data access by the CPU or the external DMA. When the internal bled, any write to this register is ignored, and any read from this register will always yield 0s.

# 50.4.10 Present State Register (SDHC\_PRSSTAT)

The host driver can get status of the SDHC from this 32-bit read only register.

#### NOTE

The host driver can issue CMD0, CMD12, CMD13 (for memory) and CMD52 (for SDIO) when the DAT lines are busy during a data transfer. These commands can be issued when Command Inhibit (CIHB) is set to zero. Other commands shall be issued when Command Inhibit (CDIHB) is set to zero. Possible changes to the SD Physical Specification may add other commands to this list in the future.



Address: SDHC\_PRSSTAT is 400B\_1000h base + 24h offset = 400B\_1024h

Bit	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
R	R DLSI								CLSL	0					CINS	
w																
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
R		C	)		BREN	BWEN	RTA	WTA	SDOFF	PEROFF	HCKOFF	IPGOFF	SDSTB	DLA	CDIHB	CIHB
w																
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

## **SDHC\_PRSSTAT** field descriptions

Field	Description
31–24 DLSL	DAT Line Signal Level  This status is used to check the DAT line level to recover from errors, and for debugging. This is especially
	useful in detecting the busy signal level from DAT[0]. The reset value is effected by the external pullup/ pulldown resistors. By default, the read value of this bit field after reset is 8'b11110111, when DAT[3] is pulled down and the other lines are pulled up.
	DAT[0] Data 0 line signal level
	DAT[1] Data 1 line signal level
	DAT[2] Data 2 line signal level
	DAT[3] Data 3 line signal level
	DAT[4] Data 4 line signal level DAT[5] Data 5 line signal level
	DAT[6] Data 6 line signal level
	DAT[7] Data 7 line signal level
23 CLSL	CMD Line Signal Level
CLSL	This status is used to check the CMD line level to recover from errors, and for debugging. The reset value is effected by the external pullup/pulldown resistor, by default, the read value of this bit after reset is 1b, when the command line is pulled up.
22–17 Reserved	This read-only field is reserved and always has the value zero.
16	Card Inserted
CINS	This bit indicates whether a card has been inserted. The SDHC debounces this signal so that the host driver will not need to wait for it to stabilize. Changing from a 0 to 1 generates a card insertion interrupt in the interrupt status register. Changing from a 1 to 0 generates a card removal interrupt in the interrupt status register. A write to the force event register does not effect this bit.



# SDHC\_PRSSTAT field descriptions (continued)

Field	Description
	The SYSCTL[RSTA] does not effect this bit.A software reset does not effect this bit.
	0b Power on reset or no card
	1b Card inserted
15–12	This read-only field is reserved and always has the value zero.
Reserved	
11	Buffer Read Enable
BREN	This status bit is used for non-DMA read transfers. The SDHC may implement multiple buffers to transfer data efficiently. This read only flag indicates that valid data exists in the host side buffer. If this bit is high, valid data greater than the watermark level exist in the buffer. This read only flag indicates that valid data exists in the host side buffer.
	0b Read disable, valid data less than the watermark level exist in the buffer.
	1b Read enable, valid data greater than the watermark level exist in the buffer.
10	Buffer Write Enable
BWEN	This status bit is used for non-DMA write transfers. The SDHC can implement multiple buffers to transfer data efficiently. This read only flag indicates if space is available for write data. If this bit is 1, valid data greater than the watermark level can be written to the buffer. This read only flag indicates if space is available for write data.
	0b Write disable, the buffer can hold valid data less than the write watermark level.
	1b Write enable, the buffer can hold valid data greater than the write watermark level.
9 RTA	Read Transfer Active This status bit is used for detecting completion of a read transfer. This bit is set for either of the following conditions:  • After the end bit of the read command.  • When writing a 1 to the PROCTL[CREQ] to restart a read transfer.
	<ul> <li>A transfer complete interrupt is generated when this bit changes to 0. This bit is cleared for either of the following conditions:</li> <li>When the last data block as specified by block length is transferred to the system, that is all data are read away from SDHC internal buffer.</li> <li>When all valid data blocks have been transferred from SDHC internal buffer to the system and no current block transfers are being sent as a result of the stop at block gap request being set to 1.</li> </ul>
	0b No valid data 1b Transferring data
8 WTA	Write Transfer Active This status bit indicates a write transfer is active. If this bit is 0, it means no valid write data exists in the SDHC. This bit is set in either of the following cases:  • After the end bit of the write command. • When writing 1 to the PROCTL[CREQ] to restart a write transfer.
	<ul> <li>This bit is cleared in either of the following cases:</li> <li>After getting the CRC status of the last data block as specified by the transfer count (single and multiple).</li> <li>After getting the CRC status of any block where data transmission is about to be stopped by a stop at block gap request.</li> </ul>



# SDHC\_PRSSTAT field descriptions (continued)

Field	Description
	During a write transaction, a block gap event interrupt is generated when this bit is changed to 0, as result of the stop at block gap request being set. This status is useful for the host driver in determining when to issue commands during write busy state.
	0b No valid data 1b Transferring data
7	SD Clock Gated Off Internally
SDOFF	This status bit indicates that the SD clock is internally gated off, because of buffer over/under-run or read pause without read wait assertion, or the driver has cleared SYSCTL[SDCLKEN] bit to stop the SD clock. This bit is for the host driver to debug data transaction on the SD bus.
	0b SD clock is active 1b SD clock is gated off
6	SDHC clock
PEROFF	Gated Off Internally
	This status bit indicates that the SDHC clock is internally gated off. This bit is for the host driver to debug transaction on the SD bus. When INITA bit is set, SDHC sending 80 clock cycles to the card, the SDCLKEN bit must be '1' to enable the output card clock, otherwise the
	SDHC clock
	will never be gate off, so
	SDHC clock
	and
	bus clock
	will be always active.
	0b SDHC clock
	is active
	1b SDHC clock
	is gated off
5	System Clock
HCKOFF	Gated Off Internally
	This status bit indicates that the system clock is internally gated off. This bit is for the host driver to debug during a data transfer.
	0b System clock
	is active
	1b System clock
	is gated off
4	Bus Clock
IPGOFF	Gated Off Internally



# SDHC\_PRSSTAT field descriptions (continued)

Field	Description
	0b Bus clock is active
	1b Bus clock is gated off
3 SDSTB	SD Clock Stable
020.2	This status bit indicates that the internal card clock is stable. This bit is for the host driver to poll clock status when changing the clock frequency. It is recommended to clear SYSCTL[SDCLKEN] bit to remove glitch on the card clock when the frequency is changing.
	<ul><li>0b Clock is changing frequency and not stable</li><li>1b Clock is stable</li></ul>
2 DLA	Data Line Active This status bit indicates whether one of the DAT lines on the SD bus is in use.
	In the case of read transactions:
	This status indicates if a read transfer is executing on the SD bus. Changes in this value from 1 to 0, between data blocks, generates a block gap event interrupt in the interrupt status register.
	This bit will be set in either of the following cases:  • After the end bit of the read command.  • When writing a 1 to the PROCTL[CREQ] to restart a read transfer.
	This bit will be cleared in either of the following cases:  1. When the end bit of the last data block is sent from the SD bus to the SDHC.  2. When the read wait state is stopped by a suspend command and the DAT2 line is released.
	The SDHC will wait at the next block gap by driving read wait at the start of the interrupt cycle. If the read wait signal is already driven (data buffer cannot receive data), the SDHC can wait for a current block gap by continuing to drive the read wait signal. It is necessary to support read wait in order to use the suspend / resume function. This bit will remain 1 during read wait.
	In the case of write transactions:
	This status indicates that a write transfer is executing on the SD bus. Changes in this value from 1 to 0 generate a transfer complete interrupt in the interrupt status register.
	This bit will be set in either of the following cases:
	<ul> <li>After the end bit of the write command.</li> <li>When writing to 1 to the PROCTL[CREQ] to continue a write transfer.</li> </ul>
	This bit will be cleared in either of the following cases:  • When the SD card releases write busy of the last data block, the SDHC will also detect if the output is not busy. If the SD card does not drive the busy signal after the CRC status is received, the SDHC shall assume the card drive "Not busy".
	<ul> <li>When the SD card releases write busy, prior to waiting for write transfer, and as a result of a stop at block gap request.</li> </ul>
	In the case of command with busy pending:
	This status indicates that a busy state follows the command and the data line is in use. This bit will be cleared when the DAT0 line is released.
	0b DAT line inactive
	1b DAT line active
1 CDIHB	Command Inhibit (DAT)



#### SDHC\_PRSSTAT field descriptions (continued)

Field	Description
	This status bit is generated if either the DLA or the RTA is set to 1. If this bit is 0, it indicates that the SDHC can issue the next SD/MMC Command. Commands with a busy signal belong to CDIHB (e.g. R1b, R5b type). Except in the case when the command busy is finished, changing from 1 to 0 generates a transfer complete interrupt in the interrupt status register.
	<b>NOTE:</b> The SD host driver can save registers for a suspend transaction after this bit has changed from 1 to 0.
	0b Can issue command which uses the DAT line
	1b Cannot issue command which uses the DAT line
0	Command Inhibit (CMD)
CIHB	If this status bit is 0, it indicates that the CMD line is not in use and the SDHC can issue a SD/MMC Command using the CMD line.
	This bit is set also immediately after the transfer type register is written. This bit is cleared when the command response is received. Even if the CDIHB bit is set to 1, Commands using only the CMD line can be issued if this bit is 0. Changing from 1 to 0 generates a command complete interrupt in the interrupt status register. If the SDHC cannot issue the command because of a command conflict error (Refer to command CRC error) or because of a command not issued by auto CMD12 error, this bit will remain 1 and the command complete is not set. The status of issuing an auto CMD12 does not show on this bit.
	0b Can issue command using only CMD line
	1b Cannot issue command

## 50.4.11 Protocol Control Register (SDHC\_PROCTL)


There are three cases to restart the transfer after stop at the block gap. Which case is appropriate depends on whether the SDHC issues a suspend command or the SD card accepts the suspend command.

- 1. If the host driver does not issue a suspend command, the continue request shall be used to restart the transfer.
- 2. If the host driver issues a suspend command and the SD card accepts it, a resume command shall be used to restart the transfer.
- 3. If the host driver issues a suspend command and the SD card does not accept it, the continue request shall be used to restart the transfer.

Any time stop at block gap request stops the data transfer, the host driver shall wait for a transfer complete (in the interrupt status register), before attempting to restart the transfer. When restarting the data transfer by continue request, the host driver shall clear the stop at block gap request before or simultaneously.



Address: SDHC\_PROCTL is 400B\_1000h base + 28h offset = 400B\_1028h



## SDHC\_PROCTL field descriptions

Field	Description
31–27 Reserved	This read-only field is reserved and always has the value zero.
26 WECRM	Wakeup Event Enable On SD Card Removal  This bit enables a wakeup event, via IRQSTAT[CRM]. FN_WUS (Wake Up Support) in CIS does not effect this bit. When this bit is set, the IRQSTAT[CRM] and the SDHC interrupt can be asserted without SD_CLK toggling. When the wakeup feature is not enabled, the SD_CLK must be active in order to assert the IRQSTAT[CRM] and the SDHC interrupt.  Ob Disabled  1b Enabled
25 WECINS	Wakeup Event Enable On SD Card Insertion  This bit enables a wakeup event, via IRQSTAT[CINS]. FN_WUS (Wake Up Support) in CIS does not effect this bit. When this bit is set, the IRQSTATEN[CINSEN] and the SDHC interrupt can be asserted without SD_CLK toggling. When the wakeup feature is not enabled, the SD_CLK must be active in order to assert the IRQSTATEN[CINSEN] and the SDHC interrupt.  Ob Disabled  1b Enabled
24 WECINT	Wakeup Event Enable On Card Interrupt  This bit enables a wakeup event, via IRQSTAT[CINT]. This bit can be set to 1 if FN_WUS (Wake Up Support) in CIS is set to 1. When this bit is set, the card interrupt status and the SDHC interrupt can be asserted without SD_CLK toggling. When the wakeup feature is not enabled, the SD_CLK must be active in order to assert the card interrupt status and the SDHC interrupt.  Ob Disabled  1b Enabled
23–20 Reserved	This read-only field is reserved and always has the value zero.
19 IABG	Interrupt At Block Gap



# SDHC\_PROCTL field descriptions (continued)

Field	Description
	This bit is valid only in 4-bit mode, of the SDIO card, and selects a sample point in the interrupt cycle. Setting to 1 enables interrupt detection at the block gap for a multiple block transfer. Setting to 0 disables interrupt detection during a multiple block transfer. If the SDIO card can't signal an interrupt during a multiple block transfer, this bit should be set to 0 to avoid an inadvertent interrupt. When the host driver detects an SDIO card insertion, it shall set this bit according to the CCCR of the card.
	0b Disabled 1b Enabled
18 RWCTL	The read wait function is optional for SDIO cards. If the card supports read wait, set this bit to enable use of the read wait protocol to stop read data using the DAT[2] line. Otherwise the SDHC has to stop the SD Clock to hold read data, which restricts commands generation. When the host driver detects an SDIO card insertion, it shall set this bit according to the CCCR of the card. If the card does not support read wait, this bit shall never be set to 1, otherwise DAT line conflicts may occur. If this bit is set to 0, stop at block gap during read operation is also supported, but the SDHC will stop the SD Clock to pause reading operation.
	<ul> <li>0b Disable read wait control, and stop SD clock at block gap when SABGREQ bit is set.</li> <li>1b Enable read wait control, and assert read wait without stopping SD clock at block gap when SABGREQ bit is set.</li> </ul>
17 CREQ	Continue Request  This bit is used to restart a transaction which was stopped using the PROCTL[SABGREQ]. When a suspend operation is not accepted by the card, it is also by setting this bit to restart the paused transfer. To cancel stop at the block gap, set PROCTL[SABGREQ] to 0 and set this bit to 1 to restart the transfer. The SDHC automatically clears this bit, therefore it is not necessary for the host driver to set this bit to 0. If both PROCTL[SABGREQ] and this bit are 1, the continue request is ignored.
	0b No effect 1b Restart
16 SABGREQ	Stop At Block Gap Request  This bit is used to stop executing a transaction at the next block gap for both DMA and non-DMA transfers. Until the IRQSTATEN[TCSEN] is set to 1, indicating a transfer completion, the host driver shall leave this bit set to 1. Clearing both the PROCTL[SABGREQ] and PROCTL[CREQ] does not cause the transaction to restart. Read Wait is used to stop the read transaction at the block gap. The SDHC will honor the PROCTL[SABGREQ] for write transfers, but for read transfers it requires that the SDIO card support read wait. Therefore, the host driver shall not set this bit during read transfers unless the SDIO card supports read wait and has set the PROCTL[RWCTL] to 1, otherwise the SDHC will stop the SD bus clock to pause the read operation during block gap. In the case of write transfers in which the host driver writes data to the data port register, the host driver shall set this bit after all block data is written. If this bit is set to 1, the host driver shall not write data to the data port register after a block is sent. Once this bit is set, the host driver shall not clear this bit before the IRQSTATEN[TCSEN] is set, otherwise the SDHC's behavior is undefined.  This bit effects PRSSTAT[RTA], PRSSTAT[WTA], PRSSTAT[CDIHB].
15–10 Reserved	This read-only field is reserved and always has the value zero.



# SDHC\_PROCTL field descriptions (continued)

Field	Description
9–8	DMA Select
DMAS	This field is valid while DMA (SDMA or ADMA) is enabled and selects the DMA operation.
	00 No DMA or simple DMA is selected
	01 ADMA1 is selected
	10 ADMA2 is selected
	11 Reserved
7 CDSS	Card Detect Signal Selection
	This bit selects the source for the card detection.
	0b Card detection level is selected (for normal purpose)
	1b Card detection test level is selected (for test purpose)
6 CDTL	Card Detect Test Level
0512	This is bit is enabled while the CDSS is set to 1 and it indicates card insertion.
	0b Card detect test level is 0, no card inserted
	1b Card detect test level is 1, card inserted
5–4 EMODE	Endian Mode
LINODE	The SDHC supports all four endian modes in data transfer.
	00b Big endian mode
	01b Half word big endian mode
	10b Little endian mode
	11b Reserved
3 D3CD	DAT3 as Card Detection Pin
D3CD	If this bit is set, DAT3 should be pulled down to act as a card detection pin. Be cautious when using this feature, because DAT3 is also a chip-select for the SPI mode. A pulldown on this pin and CMD0 may set the card into the SPI mode, which the SDHC does not support. Note: Keep this bit set if SDIO interrupt is used.
	0b DAT3 does not monitor card Insertion
	1b DAT3 as card detection pin
2–1	Data Transfer Width
DTW	This bit selects the data width of the SD bus for a data transfer. The host driver shall set it to match the data width of the card. Possible data transfer width is 1-bit, 4-bits or 8-bits.
	00b 1-bit mode
	01b 4-bit mode
	10b 8-bit mode
	11b Reserved
0	LED Control
LCTL	This bit, fully controlled by the host driver, is used to caution the user not to remove the card while the card is being accessed. If the software is going to issue multiple SD commands, this bit can be set during




## SDHC\_PROCTL field descriptions (continued)

Field	Description
	all these transactions. It is not necessary to change for each transaction. When the software issues multiple SD commands, setting the bit once before the first command is sufficient: it is not necessary to reset the bit between commands.
	0b LED off 1b LED on

# 50.4.12 System Control Register (SDHC\_SYSCTL)

Address: SDHC\_SYSCTL is 400B\_1000h base + 2Ch offset = 400B\_102Ch



## SDHC\_SYSCTL field descriptions

Field	Description
31–28 Reserved	This read-only field is reserved and always has the value zero.
27 INITA	Uhen this bit is set, 80 SD-clocks are sent to the card. After the 80 clocks are sent, this bit is self cleared. This bit is very useful during the card power-up period when 74 SD-clocks are needed and the clock auto gating feature is enabled. Writing 1 to this bit when this bit is already 1 has no effect. Writing 0 to this bit at any time has no effect. When either of the PRSSTAT[CIHB] and PRSSTAT[CDIHB] bits are set, writing 1 to this bit is ignored (i.e. when command line or data lines are active, write to this bit is not allowed). On the otherhand, when this bit is set, i.e., during intialization active period, it is allowed to issue command, and the command bit stream will appear on the CMD pad after all 80 clock cycles are done. So when this command ends, the driver can make sure the 80 clock cycles are sent out. This is very useful when the driver needs send 80 cycles to the card and does not want to wait till this bit is self cleared.
26 RSTD	Software Reset For DAT Line Only part of the data circuit is reset. DMA circuit is also reset. The following registers and bits are cleared by this bit:  • Data port register  • Buffer is cleared and initialized.Present State register  • Buffer Read Enable

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# SDHC\_SYSCTL field descriptions (continued)

Field	Description
	<ul> <li>Buffer Write Enable</li> <li>Read Transfer Active</li> <li>Write Transfer Active</li> <li>DAT Line Active</li> <li>Command Inhibit (DAT) Protocol Control register</li> <li>Continue Request</li> <li>Stop At Block Gap Request Interrupt Status register</li> <li>Buffer Read Ready</li> <li>Buffer Write Ready</li> <li>DMA Interrupt</li> <li>Block Gap Event</li> <li>Transfer Complete</li> </ul> Ob No reset 1b Reset
25 RSTC	Software Reset For CMD Line Only part of the command circuit is reset. The following registers and bits are cleared by this bit:  • PRSSTAT[CIHB]  • IRQSTAT[CC]  Ob No reset  1b Reset
24 RSTA	Software Reset For ALL  This reset effects the entire host controller except for the card detection circuit. Register bits of type ROC, RW, RW1C, RWAC are cleared. During its initialization, the host driver shall set this bit to 1 to reset the SDHC. The SDHC shall reset this bit to 0 when the capabilities registers are valid and the host driver can read them. Additional use of software reset for all does not affect the value of the capabilities registers. After this bit is set, it is recommended that the host driver reset the external card and re-initialize it.  Ob No reset  1b Reset
23–20 Reserved	This read-only field is reserved and always has the value zero.
19–16 DTOCV	Data Timeout Counter Value  This value determines the interval by which DAT line timeouts are detected. Refer to the IRQSTAT[DTOE] for information on factors that dictate time-out generation. Time-out clock frequency will be generated by dividing the base clock SDCLK value by this value.  The host driver can clear the IRQSTATEN[DTOESEN] to prevent inadvertent time-out events.  0000b SDCLK x 2 <sup>13</sup> 0001b SDCLK x 2 <sup>14</sup> 1110b SDCLK x 2 <sup>27</sup>
45.0	1111b Reserved
15–8 SDCLKFS	SDCLK Frequency Select  This register is used to select the frequency of the SDCLK pin. The frequency is not programmed directly, rather this register holds the prescaler (this register) and divisor (next register) of the base clock frequency register.



# SDHC\_SYSCTL field descriptions (continued)

Field	Description
	Setting 00h bypasses the frequency prescaler of the SD Clock. Multiple bits must not be set, or the behavior of this prescaler is undefined. The two default divider values can be calculated by the frequency of SDHC clock and the following divisor bits.
	The frequency of SDCLK is set by the following formula: Clock frequency = (Base clock) / (prescaler x divisor)
	For example, if the base clock frequency is 96 MHz, and the target frequency is 25 MHz, then choosing the prescaler value of 01h and divisor value of 1h will yield 24 MHz, which is the nearest frequency less than or equal to the target. Similarly, to approach a clock value of 400 kHz, the prescaler value of 08h and divisor value of eh yields the exact clock value of 400 kHz. The reset value of this bit field is 80h, so if the input base clock (SDHC clock) is about 96 MHz, the default SD clock after reset is 375 kHz.
	According to the SD Physical Specification Version 1.1 and the SDIO Card Specification Version 1.2, the maximum SD clock frequency is 50 MHz and shall never exceed this limit.
	Only the following settings are allowed:
	01h Base clock divided by 2
	02h Base clock divided by 4
	04h Base clock divided by 8
	08h Base clock divided by 16 10h Base clock divided by 32
	20h Base clock divided by 64
	40h Base clock divided by 128
	80h Base clock divided by 256
7–4	Divisor
DVS	This register is used to provide a more exact divisor to generate the desired SD clock frequency. Note the divider can even support odd divisor without deterioration of duty cycle.
	The setting are as following:
	0h Divisor by 1
	1h Divisor by 2
	Eh Divisor by 15
	Fh Divisor by 16
3 SDCLKEN	SD Clock Enable
SDOLKLIN	The host controller shall stop SDCLK when writing this bit to 0. SDCLK frequency can be changed when this bit is 0. Then, the host controller shall maintain the same clock frequency until SDCLK is stopped (stop at SDCLK = 0). If the IRQSTAT[CINS] is cleared, this bit should be cleared by the host driver to save power.
2 PEREN	Peripheral Clock Enable If this bit is set, SDHC clock will always be active and no automatic gating is applied. Thus the SDCLK is active except for when auto gating-off during buffer danger (buffer about to over-run or under-run). When this bit is cleared, the SDHC clock will be automatically off whenever there is no transaction on the SD bus. Since this bit is only a feature enabling bit, clearing this bit does not stop SDCLK immediately.  The SDHC clock will be internally gated off, if none of the following factors are met:  • The cmd part is reset, or  • Data part is reset, or  • A soft reset, or  • The cmd is about to send, or  • Clock divisor is just updated, or



## SDHC\_SYSCTL field descriptions (continued)

Field	Description
	<ul> <li>Continue request is just set, or</li> <li>This bit is set, or</li> <li>Card insertion is detected, or</li> <li>Card removal is detected, or</li> <li>Card external interrupt is detected, or</li> <li>80 clocks for initialization phase is ongoing</li> </ul>
	0b SDHC clock will be internally gated off 1b SDHC clock will not be automatically gated off
1 HCKEN	System Clock Enable  If this bit is set, system clock will always be active and no automatic gating is applied. When this bit is cleared, system clock
	will be automatically off when no data transfer is on the SD bus.  Ob System clock will be internally gated off  1b System clock will not be automatically gated off
0 IPGEN	IPG Clock Enable If this bit is set, bus clock will always be active and no automatic gating is applied. The bus clock will be internally gated off, if none of the following factors are met:  • The cmd part is reset, or  • Data part is reset, or  • Soft reset, or  • The cmd is about to send, or  • Clock divisor is just updated, or  • Continue request is just set, or  • This bit is set, or  • Card insertion is detected, or  • Card external interrupt is detected, or  • The SDHC clock is not gated off
	<b>NOTE:</b> The bus clock will not be auto gated off if the SDHC clock is not gated off. So clearing only this bit has no effect unless the PEREN bit is also cleared.
	0b Bus clock will be internally gated off 1b Bus clock will not be automatically gated off

# 50.4.13 Interrupt Status Register (SDHC\_IRQSTAT)

An interrupt is generated when the Normal Interrupt Signal Enable is enabled and at least one of the status bits is set to 1. For all bits, writing 1 to a bit clears it; writing to 0 keeps the bit unchanged. More than one status can be cleared with a single register write. For Card Interrupt, before writing 1 to clear, it is required that the card stops asserting the interrupt, meaning that when the Card Driver services the interrupt condition, otherwise the CINT bit will be asserted again.



The table below shows the relationship between the CTOE and the CC bits.

Table 50-19. SDHC status for CTOE/CC bit combinations

Command complete	Command timeout error	Meaning of the status
0	0	X
X	1	Response not received within 64 SDCLK cycles
1	0	Response received

The table below shows the relationship between the Transfer Complete and the Data Timeout Error.

Table 50-20. SDHC status for data timeout error/transfer complete bit combinations

Transfer complete	Data timeout error	Meaning of the status
0	0	X
0	1	Timeout occurred during transfer
1	Х	Data transfer complete

The table below shows the relationship between the command CRC error (CCE) and command timeout error (CTOE).

Table 50-21. SDHC status for CCE/CTOE Bit Combinations

Command complete	Command timeout error	Meaning of the status
0	0	No error
0	1	Response timeout error
1	0	Response CRC error
1	1	CMD line conflict



Address: SDHC\_IRQSTAT is 400B\_1000h base + 30h offset = 400B\_1030h

Bit	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
R		0		DMAE		0		AC12E	0	DEBE	DCE	DTOE	CIE	CEBE	CCE	СТОЕ
W				w1c				w1c		w1c	w1c	w1c	w1c	w1c	w1c	w1c
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
R				0				CINT	CRM	CINS	BRR	BWR	DINT	BGE	TC	СС
W								w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

## SDHC\_IRQSTAT field descriptions

Field	Description
31–29 Reserved	This read-only field is reserved and always has the value zero.
28 DMAE	DMA Error  Occurs when an Internal DMA transfer has failed. This bit is set to 1, when some error occurs in the data transfer. This error can be caused by either Simple DMA or ADMA, depending on which DMA is in use. The value in DMA System Address register is the next fetch address where the error occurs. Since any error corrupts the whole data block, the host driver shall re-start the transfer from the corrupted block boundary. The address of the block boundary can be calculated either from the current DSADDR value or from the remaining number of blocks and the block size.  Ob No Error  1b Error
27–25 Reserved	This read-only field is reserved and always has the value zero.
24 AC12E	Auto CMD12 Error  Occurs when detecting that one of the bits in the Auto CMD12 Error Status register has changed from 0 to 1. This bit is set to 1, not only when the errors in Auto CMD12 occur, but also when the Auto CMD12 is not executed due to the previous command error.  Ob No Error  1b Error
23 Reserved	This read-only field is reserved and always has the value zero.
22 DEBE	Data End Bit Error  Occurs either when detecting 0 at the end bit position of read data, which uses the DAT line, or at the end bit position of the CRC.



# SDHC\_IRQSTAT field descriptions (continued)

Field	Description
	0b No Error
	1b Error
21 DCE	Data CRC Error  Occurs when detecting a CRC error when transferring read data, which uses the DAT line, or when
	detecting the Write CRC status having a value other than 010.  0b No Error  1b Error
20 DTOE	Data Timeout Error
DIGE	Occurs when detecting one of following time-out conditions.  • Busy time-out for R1b,R5b type  • Busy time-out after Write CRC status  • Read Data time-out
	0b No Error 1b Time out
19 CIE	Command Index Error
	Occurs if a Command Index error occurs in the command response.
	0b No Error 1b Error
10	
18 CEBE	Command End Bit Error  Occurs when detecting that the end bit of a command response is 0.
	Ob No Error
	1b End Bit Error Generated
17 CCE	Command CRC Error
	<ul> <li>Command CRC Error is generated in two cases.</li> <li>If a response is returned and the Command Timeout Error is set to 0 (indicating no time-out), this bit is set when detecting a CRC error in the command response.</li> <li>The SDHC detects a CMD line conflict by monitoring the CMD line when a command is issued. If the SDHC drives the CMD line to 1, but detects 0 on the CMD line at the next SDCLK edge, then the SDHC shall abort the command (Stop driving CMD line) and set this bit to 1. The Command Timeout Error shall also be set to 1 to distinguish CMD line conflict.</li> </ul>
	0b No Error 1b CRC Error Generated
16 CTOE	Command Timeout Error
	Occurs only if no response is returned within 64 SDCLK cycles from the end bit of the command. If the SDHC detects a CMD line conflict, in which case a Command CRC Error shall also be set, this bit shall be set without waiting for 64 SDCLK cycles. This is because the command will be aborted by the SDHC.
	0b No Error 1b Time out



# SDHC\_IRQSTAT field descriptions (continued)

Field	Description
15–9 Reserved	This read-only field is reserved and always has the value zero.
8	Card Interrupt
CINT	This status bit is set when an interrupt signal is detected from the external card. In 1-bit mode, the SDHC will detect the Card Interrupt without the SD Clock to support wakeup. In 4-bit mode, the card interrupt signal is sampled during the interrupt cycle, so the interrupt from card can only be sampled during interrupt cycle, introducing some delay between the interrupt signal from the SDIO card and the interrupt to the host system. Writing this bit to 1 can clear this bit, but as the interrupt factor from the SDIO card does not clear, this bit is set again. In order to clear this bit, it is required to reset the interrupt factor from the external card followed by a writing 1 to this bit.
	When this status has been set, and the host driver needs to service this interrupt, the Card Interrupt Signal Enable in the Interrupt Signal Enable register should be 0 to stop driving the interrupt signal to the host system. After completion of the card interrupt service (It should reset the interrupt factors in the SDIO card and the interrupt signal may not be asserted), write 1 to clear this bit, set the Card Interrupt Signal Enable to 1, and start sampling the interrupt signal again.
	0b No Card Interrupt 1b Generate Card Interrupt
7	Card Removal
CRM	This status bit is set if the Card Inserted bit in the Present State register changes from 1 to 0. When the host driver writes this bit to 1 to clear this status, the status of the Card Inserted in the Present State register should be confirmed. Because the card state may possibly be changed when the host driver clears this bit and the interrupt event may not be generated. When this bit is cleared, it will be set again if no card is inserted. In order to leave it cleared, clear the Card Removal Status Enable bit in Interrupt Status Enable register.
	0b Card state unstable or inserted 1b Card removed
6	Card Insertion
CINS	This status bit is set if the Card Inserted bit in the Present State register changes from 0 to 1. When the host driver writes this bit to 1 to clear this status, the status of the Card Inserted in the Present State register should be confirmed. Because the card state may possibly be changed when the host driver clears this bit and the interrupt event may not be generated. When this bit is cleared, it will be set again if a card is inserted. In order to leave it cleared, clear the Card Inserted Status Enable bit in Interrupt Status Enable register.
	0b Card state unstable or removed 1b Card inserted
5	Buffer Read Ready
BRR	This status bit is set if the Buffer Read Enable bit, in the Present State register, changes from 0 to 1. Refer to the Buffer Read Enable bit in the Present State register for additional information.
	0b Not ready to read buffer 1b Ready to read buffer
4 BWR	Buffer Write Ready
	This status bit is set if the Buffer Write Enable bit, in the Present State register, changes from 0 to 1. Refer to the Buffer Write Enable bit in the Present State register for additional information.



# SDHC\_IRQSTAT field descriptions (continued)

Field	Description
	0b Not ready to write buffer
	1b Ready to write buffer
3	DMA Interrupt
DINT	Occurs only when the internal DMA finishes the data transfer successfully. Whenever errors occur during data transfer, this bit will not be set. Instead, the DMAE bit will be set. Either Simple DMA or ADMA finishes data transferring, this bit will be set.
	0b No DMA Interrupt
	1b DMA Interrupt is generated
2	Block Gap Event
BGE	If the PROCTL[SABGREQ] is set, this bit is set when a read or write transaction is stopped at a block gap If PROCTL[SABGREQ] is not set to 1, this bit is not set to 1.
	In the case of a read transaction: This bit is set at the falling edge of the DAT line active status (When the transaction is stopped at SD Bus timing). The read wait must be supported in order to use this function.
	In the case of write transaction: This bit is set at the falling edge of write transfer active status (After getting CRC status at SD bus timing).
	0b No block gap event
	1b Transaction stopped at block gap
11	Transfer Complete
TC	This bit is set when a read or write transfer is completed.
	In the case of a read transaction: This bit is set at the falling edge of the read transfer active status. There are two cases in which this interrupt is generated. The first is when a data transfer is completed as specified by the data length (after the last data has been read to the host system). The second is when data has stopped at the block gap and completed the data transfer by setting the PROCTL[SABGREQ] (after valid data has been read to the host system).
	In the case of a write transaction: This bit is set at the falling edge of the DAT line active status. There are two cases in which this interrupt is generated. The first is when the last data is written to the SD card as specified by the data length and the busy signal is released. The second is when data transfers are stopped at the block gap, by setting the PROCTL[SABGREQ], and the data transfers are completed. (after valid data is written to the SD card and the busy signal released).
	0b Transfer not complete
	1b Transfer complete
0	Command Complete
CC	This bit is set when you receive the end bit of the command response (except Auto CMD12). Refer to the PRSSTAT[CIHB].
	0b Command not complete
	1b Command complete





# 50.4.14 Interrupt Status Enable Register (SDHC\_IRQSTATEN)

Setting the bits in this register to 1 enables the corresponding interrupt status to be set by the specified event. If any bit is cleared, the corresponding interrupt status bit is also cleared (i.e. when the bit in this register is cleared, the corresponding bit in interrupt status register is always 0).

#### NOTE

- Depending on PROCTL[IABG] bit setting, SDHC may be programmed to sample the card interrupt signal during the interrupt period and hold its value in the flip-flop. There will be some delays on the card interrupt, asserted from the card, to the time the host system is informed.
- To detect a CMD line conflict, the host driver must set both IRQSTATEN[CTOESEN] and IRQSTATEN[CCESEN] to 1.





#### SDHC\_IRQSTATEN field descriptions

Field	Description
31–29 Reserved	This read-only field is reserved and always has the value zero.
28 DMAESEN	DMA Error Status Enable  0b Masked  1b Enabled
27–25 Reserved	This read-only field is reserved and always has the value zero.



# SDHC\_IRQSTATEN field descriptions (continued)

Field	Description
24 AC12ESEN	Auto CMD12 Error Status Enable
	0b Masked 1b Enabled
23 Reserved	This read-only field is reserved and always has the value zero.
22 DEBESEN	Data End Bit Error Status Enable
	0b Masked 1b Enabled
21 DCESEN	Data CRC Error Status Enable
	0b Masked 1b Enabled
20 DTOESEN	Data Timeout Error Status Enable
	0b Masked 1b Enabled
19 CIESEN	Command Index Error Status Enable
	0b Masked 1b Enabled
18 CEBESEN	Command End Bit Error Status Enable
	0b Masked 1b Enabled
17 CCESEN	Command CRC Error Status Enable
	0b Masked 1b Enabled
16 CTOESEN	Command Timeout Error Status Enable
	0b Masked 1b Enabled
15–9 Reserved	This read-only field is reserved and always has the value zero.
8 CINTSEN	Card Interrupt Status Enable
	If this bit is set to 0, the SDHC will clear the interrupt request to the system. The card interrupt detection is stopped when this bit is cleared and restarted when this bit is set to 1. The host driver should clear the this bit before servicing the card interrupt and should set this bit again after all interrupt requests from the card are cleared to prevent inadvertent interrupts.
	0b Masked 1b Enabled
7 CRMSEN	Card Removal Status Enable




# SDHC\_IRQSTATEN field descriptions (continued)


Field	Description
	0b Masked
	1b Enabled
6 CINSEN	Card Insertion Status Enable
	0b Masked
	1b Enabled
5 BRRSEN	Buffer Read Ready Status Enable
	0b Masked
	1b Enabled
4 BWRSEN	Buffer Write Ready Status Enable
	0b Masked
	1b Enabled
3 DINTSEN	DMA Interrupt Status Enable
	0b Masked
	1b Enabled
2 BGESEN	Block Gap Event Status Enable
	0b Masked
	1b Enabled
1 TCSEN	Transfer Complete Status Enable
	0b Masked
	1b Enabled
0 CCSEN	Command Complete Status Enable
	0b Masked
	1b Enabled



# 50.4.15 Interrupt Signal Enable Register (SDHC\_IRQSIGEN)

This register is used to select which interrupt status is indicated to the host system as the interrupt. These status bits all share the same interrupt line. Setting any of these bits to 1 enables interrupt generation. The corresponding status register bit will generate an interrupt when the corresponding interrupt signal enable bit is set.





### SDHC\_IRQSIGEN field descriptions

Field	Description
31–29 Reserved	This read-only field is reserved and always has the value zero.
28 DMAEIEN	DMA Error Interrupt Enable  0b Masked 1b Enabled
27–25 Reserved	This read-only field is reserved and always has the value zero.
24 AC12EIEN	Auto CMD12 Error Interrupt Enable  0b Masked 1b Enabled
23 Reserved	This read-only field is reserved and always has the value zero.
22 DEBEIEN	Data End Bit Error Interrupt Enable  0b Masked 1b Enabled
21 DCEIEN	Data CRC Error Interrupt Enable



# SDHC\_IRQSIGEN field descriptions (continued)

Field	Description
	0b Masked
	1b Enabled
20 DTOEIEN	Data Timeout Error Interrupt Enable
DIOLILIN	0b Masked
	1b Enabled
19 CIEIEN	Command Index Error Interrupt Enable
CILILIN	0b Masked
	1b Enabled
18 CEBEIEN	Command End Bit Error Interrupt Enable
	0b Masked
	1b Enabled
17 CCEIEN	Command CRC Error Interrupt Enable
	0b Masked
	1b Enabled
16 CTOEIEN	Command Timeout Error Interrupt Enable
	0b Masked
	1b Enabled
15–9 Reserved	This read-only field is reserved and always has the value zero.
8 CINTIEN	Card Interrupt Enable
	0b Masked
	1b Enabled
7 CRMIEN	Card Removal Interrupt Enable
	0b Masked 1b Enabled
6 CINSIEN	Card Insertion Interrupt Enable
	0b Masked
	1b Enabled
5 BRRIEN	Buffer Read Ready Interrupt Enable
	0b Masked
	1b Enabled
4 BWRIEN	Buffer Write Ready Interrupt Enable
	0b Masked
	1b Enabled
3 DINTIEN	DMA Interrupt Enable



## SDHC\_IRQSIGEN field descriptions (continued)

Field	Description
	0b Masked
	1b Enabled
2 BGEIEN	Block Gap Event Interrupt Enable
	0b Masked
	1b Enabled
1 TCIEN	Transfer Complete Interrupt Enable
	0b Masked
	1b Enabled
0 CCIEN	Command Complete Interrupt Enable
	0b Masked
	1b Enabled

## 50.4.16 Auto CMD12 Error Status Register (SDHC\_AC12ERR)

When the AC12ESEN bit in the Status register is set, the host driver shall check this register to identify what kind of error the Auto CMD12 indicated. This register is valid only when the Auto CMD12 Error status bit is set.

The following table shows the relationship between the Auto CMGD12 CRC error and the Auto CMD12 command timeout error.

Table 50-25. Relationship Between Command CRC Error and Command Timeout Error for Auto CMD12

Auto CMD12 CRC error	Auto CMD12 timeout error	Type of error
0	0	No error
0	1	Response timeout error
1	0	Response CRC error
1	1	CMD line conflict

Changes in Auto CMD12 Error Status register can be classified in three scenarios:


- 1. When the SDHC is going to issue an auto CMD12.
  - Set bit 0 to 1 if the auto CMD12 can't be issued due to an error in the previous command.
  - Set bit 0 to 0 if the auto CMD12 is issued.
- 2. At the end bit of an auto CMD12 response.



- Check errors correspond to bits 1-4.
- Set bits 1-4 corresponding to detected errors.
- Clear bits 1-4 corresponding to detected errors.
- 3. Before reading the auto CMD12 error status bit 7.
  - Set bit 7 to 1 if there is a command that can't be issued.
  - Clear bit 7 if there is no command to issue.

The timing for generating the auto CMD12 error and writing to the command register are asynchronous. After that, bit 7 shall be sampled when the driver is not writing to the command register. So it is suggested to read this register only when the IRQSTAT[AC12E] is set. An Auto CMD12 error interrupt is generated when one of the error bits (0-4) is set to 1. The command not issued by auto CMD12 error does not generate an interrupt.





#### SDHC\_AC12ERR field descriptions

Field	Description
31–8 Reserved	This read-only field is reserved and always has the value zero.



# SDHC\_AC12ERR field descriptions (continued)


Field	Description
7 CNIBAC12E	Command Not Issued By Auto CMD12 Error
ONIBACTZE	Setting this bit to 1 means CMD_wo_DAT is not executed due to an auto CMD12 error (D04-D01) in this register.
	0b No error 1b Not issued
6–5 Reserved	This read-only field is reserved and always has the value zero.
4 AC12IE	Auto CMD12 Index Error
NOTELL	Occurs if the command index error occurs in response to a command.
	0b No error 1b Error, the CMD index in response is not CMD12
3	Auto CMD12 CRC Error
AC12CE	Occurs when detecting a CRC error in the command response.
	0b No CRC error
2	1b CRC Error met in auto CMD12 Response  Auto CMD12 End Bit Error
AC12EBE	Occurs when detecting that the end bit of command response is 0 which should be 1.
	0b No error
	1b End bit error generated
1 AC12TOE	Auto CMD12 Timeout Error
	Occurs if no response is returned within 64 SDCLK cycles from the end bit of the command. If this bit is set to 1, the other error status bits (2-4) have no meaning.
	0b No error 1b Time out
0	Auto CMD12 Not Executed
AC12NE	If memory multiple block data transfer is not started, due to a command error, this bit is not set because it is not necessary to issue an auto CMD12. Setting this bit to 1 means the SDHC cannot issue the auto CMD12 to stop a memory multiple block data transfer due to some error. If this bit is set to 1, other error status bits (1-4) have no meaning.
	0b Executed
	1b Not executed



# 50.4.17 Host Controller Capabilities (SDHC\_HTCAPBLT)

This register provides the host driver with information specific to the SDHC implementation. The value in this register is the power-on-reset value, and does not change with a software reset. Any write to this register is ignored.





## SDHC\_HTCAPBLT field descriptions

Field	Description
31–27 Reserved	This read-only field is reserved and always has the value zero.
26 VS18	Voltage Support 1.8 V  This bit shall depend on the host system ability.  0b 1.8 V not supported
	1b 1.8 V supported
25 VS30	Voltage Support 3.0 V
	This bit shall depend on the host system ability.
	0b 3.0 V not supported
	1b 3.0 V supported
24 VS33	Voltage Support 3.3 V
1.000	This bit shall depend on the host system ability.
	0b 3.3 V not supported
	1b 3.3 V supported




# SDHC\_HTCAPBLT field descriptions (continued)


Field	Description
23 SRS	Suspend/Resume Support  This bit indicates whether the SDHC supports suspend / resume functionality. If this bit is 0, the suspend and resume mechanism, as well as the read Wwait, are not supported, and the host driver shall not issue either suspend or resume commands.  Ob Not supported  1b Supported
22 DMAS	DMA Support  This bit indicates whether the SDHC is capable of using the internal DMA to transfer data between system memory and the data buffer directly.  Ob DMA not supported  1b DMA supported
21 HSS	High Speed Support  This bit indicates whether the SDHC supports high speed mode and the host system can supply a SD Clock frequency from 25 MHz to 50 MHz.  Ob High speed not supported  1b High speed supported
20 ADMAS	ADMA Support  This bit indicates whether the SDHC supports the ADMA feature.  Ob Advanced DMA not supported  1b Advanced DMA supported
19 Reserved	This read-only field is reserved and always has the value zero.
18–16 MBL	Max Block Length  This value indicates the maximum block size that the host driver can read and write to the buffer in the SDHC. The buffer shall transfer block size without wait cycles.  000b 512 bytes 001b 1024 bytes 010b 2048 bytes 011b 4096 bytes
15–0 Reserved	This read-only field is reserved and always has the value zero.



## 50.4.18 Watermark Level Register (SDHC\_WML)

Both write and read watermark levels (FIFO threshold) are configurable. There value can range from 1 to 128 words. Both write and read burst lengths are also configurable. There value can range from 1 to 31 words.





#### SDHC\_WML field descriptions

Field	Description
31–29 Reserved	This read-only field is reserved and always has the value zero.
28–24 Reserved	This read-only field is reserved and always has the value zero.
23–16 WRWML	Write Watermark Level  The number of words used as the watermark level (FIFO threshold) in a DMA write operation. Also the number of words as a sequence of write bursts in back-to-back mode. The maximum legal value for the write watermark level is 128.
15–13 Reserved	This read-only field is reserved and always has the value zero.
12–8 Reserved	This read-only field is reserved and always has the value zero.
7–0 RDWML	Read Watermark Level  The number of words used as the watermark level (FIFO threshold) in a DMA read operation. Also the number of words as a sequence of read bursts in back-to-back mode. The maximum legal value for the read water mark level is 128.


## 50.4.19 Force Event Register (SDHC\_FEVT)

The force event register is not a physically implemented register. Rather, it is an address at which the interrupt status register can be written if the corresponding bit of the interrupt status enable register is set. This register is a write only register and writing 0 to it has no effect. Writing 1 to this register actually sets the corresponding bit of interrupt status register. A read from this register always results in 0's. In order to change the corresponding status bits in the interrupt status register, make sure to set SYSCTL[IPGEN] so that bus clock is always active.



Forcing a card interrupt will generate a short pulse on the DAT[1] line, and the driver may treat this interrupt as a normal interrupt. The interrupt service routine may skip polling the card interrupt factor as the interrupt is self cleared.

Address: SDHC\_FEVT is 400B\_1000h base + 50h offset = 400B\_1050h



## **SDHC\_FEVT** field descriptions

Field	Description
31 CINT	Force Event Card Interrupt
	Writing 1 to this bit generates a short low-level pulse on the internal DAT[1] line, as if a self clearing interrupt was received from the external card. If enabled, the CINT bit will be set and the interrupt service routine may treat this interrupt as a normal interrupt from the external card.
30–29 Reserved	This field is reserved.
28 DMAE	Force Event DMA Error
	Forces the DMAE bit of Interrupt Status Register to be set.
27–25 Reserved	This field is reserved.
24 AC12E	Force Event Auto Command 12 Error
	Forces the IRQSTAT[AC12E] to be set.
23 Reserved	This field is reserved.
22 DEBE	Force Event Data End Bit Error



# SDHC\_FEVT field descriptions (continued)

Field	Description					
	Forces the IRQSTAT[DEBE] bit to be set.					
21 DCE	Force Event Data CRC Error					
	Forces the IRQSTAT[DCE] bit to be set.					
20 DTOE	Force Event Data Time Out Error					
_	Force the IRQSTAT[DTOE] bit to be set.					
19 CIE	Force Event Command Index Error					
	Forces the IRQSTAT[CCE] bit to be set.					
18 CEBE	Force Event Command End Bit Error					
0252	Forces the IRQSTAT[CEBE] bit to be set.					
17 CCE	Force Event Command CRC Error					
332	Forces the IRQSTAT[CCE] bit to be set.					
16 CTOE	Force Event Command Time Out Error					
0102	Forces the IRQSTAT[CTOE] bit to be set.					
15–8 Reserved	This field is reserved.					
7 CNIBAC12E	Force Event Command Not Executed By Auto Command 12 Error					
CINIDACTZE	Forces the AC12ERR[CNIBAC12E] bit to be set.					
6–5 Reserved	This field is reserved.					
4 AC12IE	Force Event Auto Command 12 Index Error					
ACIZIE	Forces the AC12ERR[AC12IE] bit to be set.					
3 AC12EBE	Force Event Auto Command 12 End Bit Error					
ACIZEBE	Forces the AC12ERR[AC12EBE] bit to be set.					
2 AC12CE	Force Event Auto Command 12 CRC Error					
7.01202	Forces the AC12ERR[AC12CE] bit to be set.					
1 AC12TOE	Force Event Auto Command 12 Time Out Error					
7.0.2102	Forces the AC12ERR[AC12TOE] bit to be set.					
0 AC12NE	Force Event Auto Command 12 Not Executed					
ACIZINE	Forces the AC12ERR[AC12NE] bit to be set.					



## 50.4.20 ADMA Error Status Register (SDHC\_ADMAES)

When an ADMA error interrupt has occurred, the ADMA error states field in this register holds the ADMA state and the ADMA system address register holds the address around the error descriptor.

For recovering from this error, the host driver requires the ADMA state to identify the error descriptor address as follows:

- ST\_STOP: Previous location set in the ADMA System Address register is the error descriptor address.
- ST\_FDS: Current location set in the ADMA System Address register is the error descriptor address.
- ST\_CADR: This state is never set because it only increments the descriptor pointer and doesn't generate an ADMA error.
- ST\_TFR: Previous location set in the ADMA System Address register is the error descriptor address.


In case of a write operation, the host driver should use the ACMD22 to get the number of the written block, rather than using this information, since unwritten data may exist in the host controller.


The host controller generates the ADMA error interrupt when it detects invalid descriptor data (valid = 0) in the ST\_FDS state. The host driver can distinguish this error by reading the valid bit of the error descriptor.

Table 50-30. ADMA Error State Coding

D01-D00	ADMA error state (when error has occurred)	Contents of ADMA system address register		
00	ST_STOP (Stop DMA)	Holds the address of the next executable descriptor command		
01	ST_FDS (fetch descriptor)	Holds the valid descriptor address		
10	ST_CADR (change address)	No ADMA error is generated		
11	ST_TFR (Transfer Data)	Holds the address of the next executable descriptor command		







### SDHC\_ADMAES field descriptions


Field	Description
31–4 Reserved	This read-only field is reserved and always has the value zero.
3 ADMADCE	ADMA Descritor Error  This error occurs when invalid descriptor is fetched by ADMA.  Ob No error
	1b Error
2 ADMALME	ADMA Length Mismatch Error  This error occurs in the following 2 cases:  • While the block count enable is being set, the total data length specified by the descriptor table is
	different from that specified by the block count and block length.  Total data length can not be divided by the block length.
	0b No error
	1b Error
1–0 ADMAES	ADMA Error State (when ADMA Error is occurred.)
	This field indicates the state of the ADMA when an error has occurred during an ADMA data transfer.



# 50.4.21 ADMA System Address Register (SDHC\_ADSADDR)

This register contains the physical system memory address used for ADMA transfers.

Address: SDHC\_ADSADDR is 400B\_1000h base + 58h offset = 400B\_1058h




### SDHC\_ADSADDR field descriptions

Field	Description
31–2 ADSADDR	ADMA System Address  This register holds the word address of the executing command in the descriptor table. At the start of ADMA, the host driver shall set the start address of the Descriptor table. The ADMA engine increments this register address whenever fetching a descriptor command. When the ADMA is stopped at the block gap, this register indicates the address of the next executable descriptor command. When the ADMA error interrupt is generated, this register shall hold the valid descriptor address depending on the ADMA state. The lower 2 bits of this register is tied to '0' so the ADMA address is always word aligned. Since this register supports dynamic address reflecting, when TC bit is set, it automatically alters the value of internal address counter, so SW cannot change this register when TC bit is set.
1–0 Reserved	This read-only field is reserved and always has the value zero.

# 50.4.22 Vendor Specific Register (SDHC\_VENDOR)

This register contains the vendor specific control/status register.

Address: SDHC\_VENDOR is 400B\_1000h base + C0h offset = 400B\_10C0h





# SDHC\_VENDOR field descriptions


Field	Description
31–28 Reserved	This read-only field is reserved and always has the value zero.
27–24 Reserved	This read-only field is reserved and always has the value zero.
23–16 INTSTVAL	Internal State Value Internal state value, reflecting the corresponding state value selected by <b>Debug Select</b> field. This field is read-only and write to this field does not have effect.
15–2 Reserved	This read-only field is reserved and always has the value zero.
1 EXBLKNU	Exact block number block read enable for SDIO CMD53  This bit must be set before S/W issues CMD53 multi-block read with exact block number. This bit must not be set if the CMD53 multi-block read is not exact block number.  0 none exact block read. 1 Exact block read for SDIO CMD53.
0 EXTDMAEN	External DMA Request Enable  Enable the request to external DMA. When the internal DMA (either simple DMA or advanced DMA) is not in use, and this bit is set, SDHC will send out DMA request when the internal buffer is ready. This bit is particularly useful when transferring data by CPU polling mode, and it is not allowed to send out the external DMA request. By default, this bit is set.  O In any scenario, SDHC does not send out external DMA request.  When internal DMA is not active, the external DMA request will be sent out.



## 50.4.23 MMC Boot Register (SDHC\_MMCBOOT)

This register contains the MMC fast boot control register.

Address: SDHC\_MMCBOOT is 400B\_1000h base + C4h offset = 400B\_10C4h



### SDHC\_MMCBOOT field descriptions

Field	Description
31–16 BOOTBLKCNT	The value defines the stop at block gap value of automatic mode. When received card block cnt is equal to BOOTBLKCNT and AUTOSABGEN is 1, then stop at block gap.
15–8 Reserved	This read-only field is reserved and always has the value zero.
7 AUTOSABGEN	When boot, enable auto stop at block gap function. This function will be triggered, and host will stop at block gap when received card block cnt is equal to BOOTBLKCNT.
6 BOOTEN	Boot mode enable  0 Fast boot disable  1 Fast boot enable
5 BOOTMODE	Boot mode select  0 Normal boot  1 Alternative boot
4 BOOTACK	Boot ack mode select  0 No ack 1 Ack
3-0 DTOCVACK	Boot ACK time out counter value.  0000b SDCLK x 2^8  0001b SDCLK x 2^9  0010b SDCLK x 2^10

Table continues on the next page...




### **SDHC\_MMCBOOT** field descriptions (continued)

Field		Description							
	0011b	SDCLK x 2^11							
	0100b	SDCLK x 2^12							
	0101b	SDCLK x 2^13							
	0110b	SDCLK x 2^14							
	0111b	SDCLK x 2^15							
	1110b	SDCLK x 2^22							
	1111b	Reserved							

## 50.4.24 Host Controller Version (SDHC\_HOSTVER)

This register contains the vendor host controller version information. All bits are read only and will read the same as the power-reset value.

Address: SDHC\_HOSTVER is 400B\_1000h base + FCh offset = 400B\_10FCh



### SDHC\_HOSTVER field descriptions

Field	Description							
31–16 Reserved	This read-only field is reserved and always has the value zero.							
15–8 VVN	Vendor Version Number  These status bits are reserved for the vendor version number. The host driver shall not use this status.							
	00h Freescale SDHC version 1.0 10h Freescale SDHC version 2.0 11h Freescale SDHC version 2.1 12h Freescale SDHC version 2.2 All others Reserved							
7–0 SVN	Specification Version Number  These status bits indicate the host controller specification version.  01h SD host specification version 2.0, supports test event register and ADMA.  All others Reserved							

# 50.5 Functional description

The following sections provide a brief functional description of the major system blocks, including the data buffer, DMA crossbar switch interface, dual-port memory wrapper, data/command controller, clock & reset manager and clock generator.

### 50.5.1 Data buffer

The SDHC uses one configurable data buffer, so that data can be transferred between the system bus and the SD card, with an optimized manner to maximize throughput between the two clock domains (that is, the IP peripheral clock, and the master clock). The following diagram illustrates the buffer scheme. The buffer is used as temporary storage for data being transferred between the host system and the card. The watermark levels for read and write are both configurable, and can be any number from 1 to 128 words. The burst lengths for read and write are also configurable, and can be any number from 1 to 31 words.




Figure 50-27. SDHC buffer scheme

There are 3 transfer modes to access the data buffer:

- CPU polling mode:
  - For a host read operation, when the number of words received in the buffer meets or exceeds the RDWML watermark value, then by polling the IRQSTAT[BRR] bit the host driver can read the DATPORT register to fetch the amount of words set in the WML register from the buffer. The write operation is similar.



#### • External DMA mode:

• For a read operation, when there are more words received in the buffer than the amount set in the RDWML register, a DMA request is sent out to inform the external DMA to fetch the data. The request will be immediately de-asserted when there is an access on the DATPORT register. If the number of words in the buffer after the current burst meets or exceeds RDWML value, then the DMA request is asserted again. So for instance if there are twice as many words in the buffer than the RDWML value, there are two successive DMA requests with only one cycle of de-assertion between. The write operation is similar.

Note the accesses CPU polling mode and external DMA mode both use the IP bus, and if the external DMA is enable, in both modes an external DMA request is sent out whenever the buffer is ready.

- Internal DMA mode (includes simple and advanced DMA access's):
  - The internal DMA access, either by simple or advanced DMA, is over the crossbar switch bus. For internal DMA access mode, the external DMA request will never be sent out.

For a read operation, when there are more words in the buffer than the amount set in the WML register, the internal DMA starts fetching data over the crossbar switch bus. Except INCR4 and INCR8, the burst type is always INCR mode and the burst length depends on the shortest of following factors:

- 1. Burst length configured in the burst length field of the WML register
- 2. Watermark level boundary
- 3. Block size boundary
- 4. Data boundary configured in the current descriptor (if the ADMA is active)
- 5. 1 KB address boundary

## Write operation is similar.

Sequential and contiguous access is necessary to ensure the pointer address value is correct. Random or skipped access is not possible. The byte order, by reset, is little endian mode. The actually byte order is swapped inside the buffer, according to the endian mode configured by software, as illustrated in the following diagrams. For a host write operation, byte order is swapped after data is fetched from the buffer and ready to send to the SD bus. For a host read operation, byte order is swapped before the data is stored into the buffer.






Figure 50-28. Data swap between system bus and SDHC data buffer in byte little endian mode



Figure 50-29. Data swap between system bus and SDHC data buffer in half word big endian mode

### 50.5.1.1 Write operation sequence

There are three ways to write data into the buffer when the user transfers data to the card:

- 1. By using external DMA through the SDHC DMA request signal.
- 2. By processor core polling through the IRQSTAT[BWR] bit (interrupt or polling).
- 3. By using the internal DMA.

When the internal DMA is not used, (i.e. the XFERTYP[DMAEN] bit is not set when the command is sent), the SDHC asserts a DMA request when the amount of buffer space exceeds the value set in the WML register, and is ready for receiving new data. At the same time, the SDHC would set the IRQSTAT[BWR] bit. The buffer write ready interrupt will be generated if it is enabled by software.

When internal DMA is used, the SDHC will not inform the system before all the required number of bytes are transferred (if no error was encountered). When an error occurs during the data transfer, the SDHC will abort the data transfer and abandon the current block. The host driver should read the contents of the DSADDR to get the starting address of the abandoned data block. If the current data transfer is in multi block mode, the SDHC will not automatically send CMD12, even though the XFERTYP[AC12EN] bit is set. The host driver shall send CMD12 in this scenario and re-start the write operation from that address. It is recommended that a software reset for data be applied before the transfer is re-started after error recovery.



The SDHC will not start data transmission until the number of words set in the WML register can be held in the buffer. If the buffer is empty and the host system does not write data in time, the SDHC will stop the SD\_CLK to avoid the data buffer under-run situation.

### 50.5.1.2 Read operation sequence

There are three ways to read data from the buffer when the user transfers data to the card:

- 1. By using the external DMA through the SDHC DMA request signal
- 2. By processor core polling through the IRQSTAT[BRR] bit (interrupt or polling)
- 3. By using the internal DMA

When internal DMA is not used (i.e. XFERTYP[DMAEN] bit is not set when the command is sent), the SDHC asserts a DMA request when the amount of data exceeds the value set in the WML register, that is available and ready for system fetching data. At the same time, the SDHC would set the IRQSTAT[BRR] bit. The buffer read ready interrupt will be generated if it is enabled by software.

When internal DMA is used, the SDHC will not inform the system before all the required number of bytes are transferred (if no error was encountered). When an error occurs during the data transfer, the SDHC will abort the data transfer and abandon the current block. The host driver should read the content of the DMA system address register to get the starting address of the abandoned data block. If the current data transfer is in multi block mode, the SDHC will not automatically send CMD12, even though the XFERTYP[AC12EN] bit is set. The host driver shall send CMD12 in this scenario and re-start the read operation from that address. It is recommended that a software reset for data be applied before the transfer is re-started after error recovery.

For any write transfer mode, the SDHC will not start data transmission until the number of words set in the WML register are in the buffer. If the buffer is full and the Host System does not read data in time, the SDHC will stop the SDHC\_DCLK to avoid the data buffer over-run situation.

### 50.5.1.3 Data buffer and block size

The user needs to know the buffer size, for the buffer operation during a data transfer, to utilize it in the most optimized way. In the SDHC, the only data buffer can hold up to 128 words (32-bit), and the watermark levels for write and read can be configured respectively. For both read and write, the watermark level can be from 1 word to the



maximum of 128 words. For both read and write, the burst length, can be from 1 word to the maximum of 31 words. The host driver may configure the value according to the system situation and requirement.

During a multi-block data transfer, the block length may be set to any value between 1 and 4096 bytes inclusive which satisfies the requirements of the external card. The only restriction is from the external card. It might not support that large of a block or it doesn't support a partial block access (which is not the integer times of 512 bytes).

For block size not times of 4, i.e., not word aligned, SDHC requires stuff bytes at the end of each block, because SDHC treats each block individually. For example, the block size is 7 bytes, there are 12 blocks to write, the system side must write 2 times for each block, and for each block, the ending byte would be abandoned by SDHC since it only sends 7 bytes to the card and picks data from the following system write, so there would be 24 beats of write access in total.

### 50.5.1.4 Dividing large data transfer

This SDIO command CMD53 definition, limits the maximum data size of data transfers according to the following formula:

Max data size = Block size x Block count

The length of a multiple block transfer needs to be in block size units. If the total data length can't be divided evenly into a multiple of the block size, then there are two ways to transfer the data which depend on the function and the card design. Option 1 is for the host driver to split the transaction. The remainder of the block size data is then transferred by using a single block command at the end. Option 2 is to add dummy data in the last block to fill the block size. For option 2, the card must manage the removal of the dummy data.


The following diagram illustrates the dividing of large data transfers. Assuming a kind of WLAN SDIO card only supports block size up to 64 bytes. Although the SDHC supports a block size of up to 4096 bytes, the SDIO can only accept a block size less than 64 bytes, so the data must be divided (see example below).



#### 544 Bytes WLAN Frame

802. 11	IV	Frame Body	ICV	FCS
MAC header				

WLAN Frame is divided equally into 64 byte blocks plus the remainder 32 bytes



Eight 64 byte blocks are sent in Block transfer mode and the remainder 32 bytes are sent in Byte Transfer mode

CM D53	SDIO Data block #1	SDIO Data block #2		SDIO Data block #8	CIVIDOS	SDIO Data 32 bytes
--------	-----------------------	-----------------------	--	-----------------------	---------	-----------------------

Figure 50-30. Example for dividing large data transfers

### 50.5.1.5 External DMA request

When the internal DMA is not in use, and external DMA request is enabled, the data buffer will generate a DMA request to the system. During a write operation, when the number of WRWML words can be held in the buffer free space, a DMA request is sent, informing the host system of a DMA write. The IRQSTAT[BWR] bit is also set, as long as the IRQSTATEN[BWRSEN] bit is set. The DMA request is immediately de-asserted when an access to the DATPORT register is made. If the buffer's free space still meets the watermark condition, the DMA request is asserted again after a cycle.

On read operation, when the number of RDWML words are already in the buffer, a DMA request is sent, informing the host system for a DMA read. The IRQSTAT[BRR] bit is also set, as long as the IRQSTATEN[BRRSEN] bit is set. The DMA request is immediately de-asserted when an access to the DATPORT register is made. If the buffer's data still meets the watermark condition, the DMA request is asserted again after a cycle.



Because the DMA burst length can't change during a data transfer for an external DMA transfer, the watermark level (read or write) must be a divisor of the block size. If it is not, transferring of the block may cause buffer under-run (read operation) or over-run (write operation). For example, if the block size is 512 bytes, the watermark level of read (or write) must be a power of two between 1 and 128. For processor core polling access, as the last access in the block transfer can be controlled by software, there is no such issue. The watermark level can be any value, even larger than the block size (but no greater than 128 words). This is because the actual number of bytes transferred by the software can be controlled and does not exceed the block size in each transfer.

The SDHC also supports non-word aligned block size, as long as the card supports that block size. In this case, the watermark level should be set as the number of words. For example, if the block size is 31 bytes, the watermark level can be set to any number of word. For this case, the BLKATTR[BLKSIZE] bits shall be set as 1fh. For the CPU polling access, the burst length can be 1 to 128 words, without restriction. This is because the software will transfer 8 words, and the SDHC will also set the IRQSTAT[BWR] or IRQSTAT[BRR] bits when the remaining data does not violate data buffer. Refer to DMA burst length for more details about the dynamic watermark level of the data buffer. For the above example, even though 8 words are transferred via the DATPORT register, the SDHC will transfer only 31 bytes over the SD bus, as required by the BLKATTR[BLKSIZE] bits. In this data transfer, with non-word aligned block size, the endian mode should be set cautiously, or invalid data will be transferred to/from the card.

## 50.5.2 DMA crossbar switch interface

The internal DMA implements a DMA engine and the crossbar switch master. When the internal DMA is enabled (XFERTYP[DMAEN] is set), the interrupt status bits are set if they are enabled. To avoid setting them, clear IRQSTATEN[BWRSEN, BRRSEN]. The following diagram illustrates the DMA crossbar switch interface block.






Figure 50-31. DMA crossbar switch interface block

## 50.5.2.1 Internal DMA request

If the watermark level requirement is met in data transfer, and the internal DMA is enabled, the data buffer block sends a DMA request to the crossbar switch interface. Meanwhile, the external DMA request signal is disabled. The delay in response from the internal DMA engine depends on the system bus loading and the priority assigned to the SDHC. The DMA engine does not respond to the request during its burst transfer, but is ready to serve as soon as the burst is over. The data buffer de-asserts the request once an access to the buffer is made. Upon access to the buffer by internal DMA, the data buffer updates its internal buffer pointer, and when the watermark level is satisfied, another DMA request is sent.

The data transfer is in the block unit, and the subsequent watermark level is always set as the remaining number of words. For instance, for a multi block data read with each block size of 31 bytes, and the burst length set to 6 words. After the first burst transfer, if there are more than 2 words in the buffer (which might contain some data of the next block), another DMA request read is sent. This is because the remaining number of words to send for the current block is (31 - 6 \* 4) / 4 = 2. The SDHC will read 2 words out of the buffer, with 7 valid bytes and 1 stuff byte.

## 50.5.2.2 DMA burst length

Just like a CPU polling access, the DMA burst length for the internal DMA engine can be from 1 to 16 words. The actual burst length for the DMA depends on the lesser of the configured burst length or the remaining words of the current block. Take the example in Internal DMA request again. The following burst length after 6 words are read will be 2 words, and the next burst length will be 6 words again. This is because the next block



starts, which is 31 bytes, more than 6 words. The host driver writer may take this variable burst length into account. It is also acceptable to configure the burst length as the divisor of the block size, so that each time the burst length will be the same.

### 50.5.2.3 Crossbar switch master interface

It is possible that the internal DMA engine could fail during the data transfer. When this error occurs, the DMA engine stops the transfer and goes to the idle state as well as the internal data buffer stops accepting incoming data. The IRQSTAT[DMAE] is set to inform the driver.

Once the DMAE interrupt is received, the software shall send a CMD12 to abort the current transfer and read the DSADDR[DSADDR] to get the starting address of the corrupted block. After the DMA error is fixed, the software should apply a data reset and re-start the transfer from this address to recover the corrupted block.

### **50.5.2.4 ADMA** engine

In the SD host controller standard, the new DMA transfer algorithm called the ADMA (advanced DMA) is defined. For simple DMA, once the page boundary is reached, a DMA interrupt will be generated and the new system address shall be programmed by the host driver. The ADMA defines the programmable descriptor table in the system memory. The host driver can calculate the system address at the page boundary and program the descriptor table before executing ADMA. It reduces the frequency of interrupts to the host system. Therefore, higher speed DMA transfers could be realized since the host MCU intervention would not be needed during long DMA based data transfers.

There are two types of ADMA: ADMA1 and ADMA2 in host controller. ADMA1 can support data transfer of 4 KB aligned data in system memory. ADMA2 improves the restriction so that data of any location and any size can be transferred in system memory. Their formats of descriptor table are different.

ADMA can recognize all kinds of descriptors define in SD host controller standard, and if 'end' flag is detected in the descriptor, ADMA will stop after this descriptor is processed.

## 50.5.2.4.1 ADMA concept and descriptor format

For ADMA1, including the following descriptors:



- Valid/Invalid descriptor.
- Nop descriptor.
- Set data length descriptor.
- Set data address descriptor.
- Link descriptor.
- Interrupt flag and end flag in descriptor.

For ADMA2, including the following descriptors:

- Valid/Invalid descriptor.
- Nop descriptor.
- Rsv descriptor.
- Set data length & address descriptor.
- Link descriptor.
- Interrupt flag and end flag in descriptor.

ADMA2 deals with the lower 32-bit first, and then the higher 32-bit. If the 'Valid' flag of descriptor is 0, it will ignore the high 32-bit. Address field shall be set on word aligned(lower 2-bit is always set to 0). Data length is in byte unit.

ADMA will start read/write operation after it reaches the tran state, using the data length and data address analyzed from most recent descriptor(s).

For ADMA1, the valid data length descriptor is the last set type descriptor before tran type descriptor. Every tran type will trigger a transfer, and the transfer data length is extracted from the most recent set type descriptor. If there is no set type descriptor after the previous trans descriptor, the data length will be the value for previous transfer, or 0 if no set descriptor is ever met.

For ADMA2, tran type descriptor contains both data length and transfer data address, so only a tran type descriptor can start a data transfer

Table 50-35. Format of the ADMA1 descriptor table

Address/page field		Address/page field Attribute field							
31 12		11	6	5	4	3	2	1	0
Address or data length		000000		Act2	Act1	0	Int	End	Valid

Table continues on the next page...



Table 50-35. Format of the ADMA1 descriptor table (continued)

Act2	Act1		Symbol	Comment	31-28	27-12
0	0		nop	No operation	Don'	t care
0	1		set	Set data length	0000	Data length
1	0		tran	Transfer data	Data a	ddress
1	1		link	Link descriptor	Descriptor address	
Valid Valid			I indicates this	line of descriptor is effo	9	enerate ADMA error upt and stop ADMA.
End		End = 1 indicates current descriptor is the ending one.				
Int		Int = 1 generates DMA interrupt when this descriptor is processed.				




Figure 50-32. Concept and access method of ADMA1 descriptor table Table 50-36. Format of the ADMA2 descriptor table

Address field		Length		Reserved			Attribute field				
63	32	31	16	15	06	05	04	03	02	01	00
32-bit address		16-bit length		000000000		Act2	Act1	0	Int	End	Valid
Act2		Act1		Symbol		Com	ment	Operation			
0		0		nop		No operation		Don't care			
0		1		rsv		Reserved		Same as nop. Read this line and go to next one			
1		0		tran		Transfer data		Transfer data with address and length set in this descriptor line			
1		1		link		Link descriptor		Link to another descriptor			

Table continues on the next page...



### Table 50-36. Format of the ADMA2 descriptor table (continued)

Valid	Valid = 1 indicates this line of descriptor is effective. If valid = 0 generate ADMA error interrupt and stop ADMA.
End	End = 1 indicates current descriptor is the ending one.
Int	Int = 1 generates DMA interrupt when this descriptor is done.




Figure 50-33. Concept and access method of ADMA2 descriptor table

### **50.5.2.4.2 ADMA** interrupt

If the 'interrupt' flag of descriptor is set, ADMA will generate an interrupt according to different type descriptor:

### For ADMA1:

- Set type descriptor: interrupt is generated when data length is set.
- Tran type descriptor: interrupt is generated when this transfer is complete.
- Link type descriptor: interrupt is generated when new descriptor address is set.
- Nop type descriptor: interrupt is generated just after this descriptor is fetched.

### For ADMA2:

- Tran type descriptor: interrupt is generated when this transfer is complete.
- Link type descriptor: interrupt is generated when new descriptor address is set.
- Nop/Rsv type descriptor: interrupt is generated just after fetch this descriptor.



### 50.5.2.4.3 ADMA error

The ADMA stops whenever any error is encountered. These errors include:

- Fetching descriptor error
- Transfer error
- Data length mismatch error

ADMA descriptor error will be generated when it fails to detect 'valid' flag in the descriptor. If ADMA descriptor error occurs, the interrupt is not generated even if the 'interrupt' flag of this descriptor is set.

When XFERTYP[BCEN] bit is set, data length set in buffer must equal to the whole data length set in descriptor nodes, otherwise data length mismatch error will be generated.

If XFERTYP[BCEN] bit is not set, the whole data length set in descriptor should be times of block length, otherwise, when all data set in the descriptor nodes are done not at block boundary, the data mismatch error will occur.

# 50.5.3 SD protocol unit

The SD protocol unit deals with all SD protocol affairs.

The SD Protocol Unit performs the following functions:

- Acts as the bridge between the internal buffer and the SD bus
- Sends the command data as well as its argument serially
- Stores the serial response bit stream into corresponding registers
- Detects the bus state on the DAT[0] line
- Monitors the interrupt from the SDIO card
- Asserts the read wait signal
- Gates off the SD clock when buffer is announcing danger status
- Detects the write protect state

The SD protocol unit consists of four sub modules:

1. SD transceiver.



- 2. SD clock and monitor.
- 3. Command agent.
- 4. Data agent.

### 50.5.3.1 SD transceiver

In the SD protocol unit, the transceiver is the main control module. It consists of a FSM and control module, from which the control signals for all other three modules are generated.

### 50.5.3.2 SD clock & monitor

This module monitors the signal level on all 8 data lines, the command lines, and directly routes the level values into the register bank. The driver can use this for debug purposes.

The module also detects the CD (card detection) line as well as the DAT[3] line. The transceiver reports the card insertion state according to the CD state, or the signal level on the DAT[3] line, when the PROCTL[D3CD] bit is set.

The module detects the WP (write protect) line. With the information of the WP state, the register bank will ignore the command, accompanied by a write operation, when the WP switch is on.

If the internal data buffer is in danger, and the SD clock must be gated off to avoid buffer over/under-run, this module will assert the gate of the output SD clock to shut the clock off. After the buffer danger has recovered, and when the system access of the buffer catches up, the clock gate of this module will open and the SD clock will be active again.

This module also drive SDHC\_LCTL output signal when the PROCTL[LCTL] bit is set by the driver.

# 50.5.3.3 Command agent

The command agent deals with the transactions on the CMD line. The following diagram illustrates the structure for the command CRC Shift Register.






Figure 50-34. Command CRC Shift Register

The CRC polynomials for the CMD are as follows:

```
Generator polynomial: G(x) = x^7 + x^3 + 1

M(x) = (first bit) * x^n + (second bit) * x^{n-1} + ... + (last bit) * x^0

CRC[6:0] = Remainder [(M(x) * x^7) / G(x)]
```

## 50.5.3.4 Data agent

The data agent deals with the transactions on the eight data lines. Moreover, this module also detects the busy state on the DAT[0] line, and generate the read wait state by the request from the transceiver. The CRC polynomials for the DAT are as follows:

```
Generator polynomial: G(x) = x^{16} + x^{12} + x^5 + 1

M(x) = (first bit) * x^n + (second bit) * x^{n-1} + ... + (last bit) * x^0

CRC[15:0] = Remainder [(M(x) * x^{16}) / G(x)]
```

# 50.5.4 Clock & reset manager

This module controls all the reset signals within the SDHC.

There are four kinds of reset signals within SDHC:

- 1. Hardware reset.
- 2. Software reset for all.
- 3. Software reset for the data part.
- 4. Software reset for the command part.

All these signals are fed into this module and stable signals are generated inside the module to reset all other modules. The module also gates off all the inside signals.

There are three clocks inside the SDHC:



- 1. Bus clock.
- 2. SDHC clock.
- 3. System clock.

The module monitors the activities of all other modules, supplies the clocks for them, and when enabled, automatically gates off the corresponding clocks.

## 50.5.5 Clock generator

The clock generator generates the SDHC\_CLK by peripheral source clock in two stages. The following diagram illustrates the structure of the divider. The term "base" represents the frequency of peripheral source clock.




Figure 50-35. Two stages of the clock divider

The first stage outputs an intermediate clock (DIV), which can be base, base/2, base/3, ..., or base/16.

The second stage is a prescaler, and outputs the actual clock (SDHC\_CLK). This clock is the driving clock for all sub modules of the SD protocol unit, and the sync FIFOs to synchronize with the data rate from the internal data buffer. The frequency of the clock output from this stage, can be DIV, DIV/2, DIV/4,..., or DIV/256. Thus the highest frequency of the SDHC\_CLK is base, and the next highest is base/2, while the lowest frequency is base/4096. If the base clock is of equal duty ratio (usually true), the duty cycle of SDHC\_CLK is also 50%, even when the compound divisor is an odd value.

## 50.5.6 SDIO card interrupt

This section discusses SDIO interrupt handling.

### 50.5.6.1 Interrupts in 1-bit mode

In this case the DAT[1] pin is dedicated to providing the interrupt function. An interrupt is asserted by pulling the DAT[1] low from the SDIO card, until the interrupt service is finished to clear the interrupt.



### 50.5.6.2 Interrupt in 4-bit mode

Since the interrupt and data line 1 share Pin 8 in 4-bit mode, an interrupt will only be sent by the card and recognized by the host during a specific time. This is known as the interrupt period. The SDHC will only sample the level on pin 8 during the interrupt period. At all other times, the host will ignore the level on pin 8, and treat it as the data signal. The definition of the interrupt period is different for operations with single block and multiple block data transfers.

In the case of normal single data block transmissions, the interrupt period becomes active two clock cycles after the completion of a data packet. This interrupt period lasts until after the card receives the end bit of the next command that has a data block transfer associated with it.

For multiple block data transfers in 4-bit mode, there is only a limited period of time that the interrupt period can be active due to the limited period of data line availability between the multiple blocks of data. This requires a more strict definition of the interrupt period. For this case, the interrupt period is limited to two clock cycles. This begins two clocks after the end bit of the previous data block. During this 2-clock cycle interrupt period, if an interrupt is pending, the SDHC\_D1 line will be held low for one clock cycle with the last clock cycle pulling SDHC\_D1 high. On completion of the Interrupt Period, the card releases the SDHC\_D1 line into the high Z state. The SDHC samples the SDHC\_D1] during the interrupt period when the PROCTL[IABG] bit is set.

Refer to SDIO Card Specification v1.10f for further information about the SDIO card interrupt.

### 50.5.6.3 Card interrupt handling

When the IRQSIGEN[CINTIEN] bit is set to 0, the SDHC clears the interrupt request to the host system. The host driver should clear this bit before servicing the SDIO Interrupt and should set this bit again after all interrupt requests from the card are cleared to prevent inadvertent interrupts.

The SDIO status bit is cleared by resetting the SDIO interrupt. Writing to this bit would have no effects. In 1-bit mode, the SDHC will detect the SDIO interrupt with or without the SD clock (to support wakeup). In 4-bit mode, the interrupt signal is sampled during the interrupt period, so there are some sample delays between the interrupt signal from the SDIO card and the interrupt to the host system interrupt controller. When the SDIO status has been set, and the host driver needs to service this interrupt, so the SDIO bit in the interrupt control register of SDIO card will be cleared. This is required to clear the



SDIO interrupt status latched in the SDHC and to stop driving the interrupt signal to the system interrupt controller. The host driver must issue a CMD52 to clear the card interrupt. After completion of the card interrupt service, the SDIO Interrupt Enable bit is set to 1, and the SDHC starts sampling the interrupt signal again.

The following diagram illustrates the SDIO card interrupt scheme and for the sequences of software and hardware events that take place during a card interrupt handling procedure.




Figure 50-36. Card interrupt scheme and card interrupt detection and handling procedure

## 50.5.7 Card insertion and removal detection

The SDHC uses either the DAT[3] pin or the CD pin to detect card insertion or removal. When there is no card on the MMC/SD bus, the DAT[3] will be pulled to a low voltage level by default. When any card is inserted to or removed from the socket, the SDHC detects the logic value changes on the DAT[3] pin and generates an interrupt. When the DAT[3] pin is not used for card detection (for example, it is implemented in GPIO), the CD pin must be connected for card detection. Whether DAT[3] is configured for card



detection or not, the CD pin is always a reference for card detection. Whether the DAT[3] pin or the CD pin is used to detect card insertion, the SDHC will send an interrupt (if enabled) to inform the Host system that a card is inserted.

## 50.5.8 Power management and wakeup events

When there is no operation between the SDHC and the card through the SD bus, the user can completely disable the bus clock and SDHC clock in the chip level clock control module to save power. When the user needs to use the SDHC to communicate with the card, it can enable the clock and start the operation.

In some circumstances, when the clocks to the SDHC are disabled, for instance, when the system is in low power mode, there are some events for which the user needs to enable the clock and handle the event. These events are called wakeup interrupts. The SDHC can generate these interrupt even when there are no clocks enabled. The three interrupts which can be used as wake up events are:

- 1. Card removal interrupt
- 2. Card insertion interrupt
- 3. Interrupt from SDIO card

The SDHC offers a power management feature. By clearing the clock enabled bits in the system control register, the clocks are gated in the low position to the SDHC. For maximum power saving, the user can disable all the clocks to the SDHC when there is no operation in progress.

These three wake up events (or wakeup interrupts) can also be used to wake up the system from low-power modes.

### **Note**

To make the interrupt a wakeup event, when all the clocks to the SDHC are disabled or when the whole system is in low power mode, the corresponding wakeup enabled bit needs to be set. Refer to protocol control register for more information.

### 50.5.8.1 Setting wakeup events

For the SDHC to respond to a wakeup event, the software must set the respective wakeup enable bit before the CPU enters sleep mode. Before the software disables the host clock, it should ensure that all of the following conditions have been met:



- No read or write transfer is active
- Data and command lines are not active
- No interrupts are pending
- Internal data buffer is empty

### 50.5.9 MMC fast boot

In Embedded MultiMediaCard(eMMC4.3) spec, add fast boot feature need hardware support.

In boot operation mode, the master (multimediacard host) can read boot data from the slave (MMC device) by keeping CMD line low after power-on, or sending CMD0 with argument + 0xFFFFFFA (optional for slave), before issuing CMD1.

There are two types of fast boot mode, 'boot operation 'and 'Alternative boot operation 'in eMMC4.3 spec. Each type also has with acknowledge and without acknowledge modes.

### **Note**

for the eMMC4.3 card setting, please refer to eMMC4.3 spec

### 50.5.9.1 Boot operation

#### **Note**

in this block guide, this fast boot is called normal fast boot mode

If the CMD line is held low for 74 clock cycles and more after power-up before the first command is issued, the slave recognizes that boot mode is being initiated and starts preparing boot data internally.

Within 1 second after the CMD line goes low, the slave starts to send the first boot data to the master on the DAT line(s). The master must keep the CMD line low to read all of the boot data.

If boot acknowledge is enabled, the slave has to send acknowledge pattern '010' to the master within 50 ms after the CMD line goes low. If boot acknowledge is disabled, the slave will not send out acknowledge pattern '010'.

The master can terminate boot mode with the CMD line high.



Boot operation will be terminated when all contents of the enabled boot data are sent to the master. After boot operation is executed, the slave shall be ready for CMD1 operation and the master needs to start a normal MMC initialization sequence by sending CMD1.






Figure 50-37. Multimediacard state diagram (normal boot mode)

## 50.5.9.2 Alternative boot operation

This boot function is optional for the device. If bit 0 in the extended CSD byte[228] is set to '1', the device supports the alternative boot operation.

After power-up, if the host issues CMD0 with the argument of 0xFFFFFFA after 74 clock cycles, before CMD1 is issued or the CMD line goes low, the slave recognizes that boot mode is being initiated and starts preparing boot data internally.

Within 1 second after CMD0 with the argument of 0xFFFFFFA is issued, the slave starts to send the first boot data to the master on the DAT line(s).

If boot acknowledge is enabled, the slave has to send the acknowledge pattern '010' to the master within 50ms after the CMD0 with the argument of 0xFFFFFFA is received. If boot acknowledge is disabled, the slave will not send out acknowledge pattern '010'.

The master can terminate boot mode by issuing CMD0 (Reset).

Boot operation will be terminated when all contents of the enabled boot data are sent to the master. After boot operation is executed, the slave shall be ready for CMD1 operation and the master needs to start a normal MMC initialization sequence by sending CMD1.






Figure 50-38. MultiMediaCard state diagram (alternative boot mode)

# 50.6 Initialization/application of SDHC

All communication between system and cards are controlled by the host. The host sends commands of two types: broadcast and addressed (point-to-point).

Broadcast commands are intended for all cards, such as "GO\_IDLE\_STATE", "SEND\_OP\_COND", "ALL\_SEND\_CID" and etc. In broadcast mode, all cards are in the open-drain mode to avoid bus contention. Refer to Commands for MMC/SD/SDIO/CE-ATA for the commands of bc and bcr categories.

After the broadcast command CMD3 is issued, the cards enter standby mode. Addressed type commands are used from this point. In this mode, the CMD/DAT I/O pads will turn to push-pull mode, to have the driving capability for maximum frequency operation. Refer to Commands for MMC/SD/SDIO/CE-ATA for the commands of ac and adte categories.

# 50.6.1 Command send and response receive basic operation

Assuming the data type WORD is an unsigned 32-bit integer, the below flow is a guideline for sending a command to the card(s):

```
send_command(cmd_index, cmd_arg, other requirements)
{
WORD wCmd; // 32-bit integer to make up the data to write into Transfer Type register, it is
recommended to implement in a bit-field manner
wCmd = (<cmd_index> & 0x3f) >> 24; // set the first 8 bits as '00'+<cmd_index>
set CMDTYP, DPSEL, CICEN, CCCEN, RSTTYP, DTDSEL according to the command index;
if (internal DMA is used) wCmd |= 0x1;
if (multi-block transfer) {
   set MSBSEL bit;
   if (finite block number) {
```

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### unualization/application of SDHC

```
set BCEN bit;
if (auto12 command is to use) set AC12EN bit;
}

write_reg(CMDARG, <cmd_arg>); // configure the command argument
write_reg(XFERTYP, wCmd); // set Transfer Type register as wCmd value to issue the command
wait_for_response(cmd_index)
{
while (CC bit in IRQ Status register is not set); // wait until Command Complete bit is set read IRQ Status register and check if any error bits about Command are set
if (any error bits are set) report error;
write 1 to clear CC bit and all Command Error bits;
}
```

For the sake of simplicity, the function wait\_for\_response is implemented here by means of polling. For an effective and formal way, the response is usually checked after the command complete interrupt is received. By doing this, make sure the corresponding interrupt status bits are enabled.

For some scenarios, the response time-out is expected. For instance, after all cards respond to CMD3 and go to the standby state, no response to the host when CMD2 is sent. The host driver shall deal with 'fake' errors like this with caution.

### 50.6.2 Card identification mode

When a card is inserted to the socket or the card was reset by the host, the host needs to validate the operation voltage range, identify the cards, request the cards to publish the relative card address (RCA) or to set the RCA for the MMC cards. For CE-ATA, the device is connected in a point-to-point manner, and no RCA is needed. All data communications in the Card Identification Mode use the command line (CMD) only. Refer to CE-ATA Digital Protocol, Revision 1.1 for more details.

### 50.6.2.1 Card detect

The following diagram illustrates the detection of MMC, SD and SDIO cards using the SDHC.






Figure 50-39. Flow diagram for card detection

Here is the card detection sequence:

- Set the CINSIEN bit to enable card detection interrupt
- When an interrupt from the SDHC is received, check the IRQSTAT[CINS] bit in the Interrupt Status register to see if it was caused by card insertion
- Clear the CINSIEN bit to disable the card detection interrupt and ignore all card insertion interrupts afterwards

To detect a CE-ATA device, after completing the normal MMC reset and initialization procedures, the host driver shall issue CMD 60 to check for a CE-ATA signature. If the device responds to the command with the CE-ATA signature, a CE-ATA device has been found. Then the driver should query EXT\_CSD register byte 504 (S\_CMD\_SET) in the MMC register space. If the ATA bit (bit 4) is set, then the MMC device is an ATA device. If the device indicates that it is an ATA device, the Driver should set the ATA bit (bit 4) of the EXT\_CSD register byte 191 (CMD\_SET) to activate the ATA command set for use. To choose the command set, the driver shall issue CMD6. It is possible that the CE-ATA device does not support the ATA mode, so the driver shall not issue ATA command to the device.

### 50.6.2.2 Reset

The host consists of three types of resets:

• Hardware reset (card and host) which is driven by POR (power on reset)



#### mualization/application of SDHC

- Software reset (host only) is proceed by the write operation on the SYSCTL[RSTD], SYSCTL[RSTC], or SYSCTL[RSTA] bits to reset the data part, command part, or all parts of the host controller, respectively
- Card reset (card only). The command, "Go\_Idle\_State" (CMD0), is the software reset command for all types of MMC cards, SD Memory cards, and CE-ATA cards. This command sets each card into the idle state regardless of the current card state. For an SD I/O Card, CMD52 is used to write an I/O reset in the CCCR. The cards are initialized with a default relative card address (RCA = 0x0000) and with a default driver stage register setting (lowest speed, highest driving current capability).

After the card is reset, the host needs to validate the voltage range of the card. The following diagram illustrates the software flow to reset both the SDHC and the card.

For CE-ATA device that supports ATA mode, before issuing CMD0 to reset the MMC layer, two CMD39 should be issued back-to-back to the ATA control register. The first CMD39 shall have the SRST bit set to one. The second CMD39 command shall have the SRST bit cleared to zero.




Figure 50-40. Flow chart for reset of the SDHC and SD I/O card

```
software_reset()
{
set_bit(SYSCTRL, RSTA); // software reset the Host
set DTOCV and SDCLKFS bit fields to get the SD_CLK of frequency around 400kHz
configure IO pad to set the power voltage of external card to around 3.0V
poll bits CIHB and CDIHB bits of PRSSTAT to wait both bits are cleared
set_bit(SYSCTRL, INTIA); // send 80 clock ticks for card to power up
send_command(CMD_GO_IDLE_STATE, <other parameters>); // reset the card with CMDO
or send_command(CMD_IO_RW_DIRECT, <other parameters>);
}
```



### 50.6.2.3 Voltage validation

All cards should be able to establish communication with the host using any operation voltage in the maximum allowed voltage range specified in the card specification. However, the supported minimum and maximum values for  $V_{DD}$  are defined in the Operation Conditions Register (OCR) and may not cover the whole range. Cards that store the CID and CSD data in the preload memory are only able to communicate this information under data transfer  $V_{DD}$  conditions. This means if the host and card have non-common  $V_{DD}$  ranges, the card will not be able to complete the identification cycle, nor will it be able to send CSD data.

Therefore, a special command Send\_Op\_Cont (CMD1 for MMC), SD\_Send\_Op\_Cont (ACMD41 for SD Memory) and IO\_Send\_Op\_Cont (CMD5 for SD I/O) is used. For a CE-ATA card, the process is the same as that of an MMC card. The voltage validation procedure is designed to provide a mechanism to identify and reject cards which do not match the  $V_{DD}$  range(s) desired by the host. This is accomplished by the host sending the desired  $V_{DD}$  voltage window as the operand of this command. Cards that can't perform the data transfer in the specified range must discard themselves from further bus operations and go into the Inactive State. By omitting the voltage range in the command, the host can query each card and determine the common voltage range before sending out-of-range cards into the inactive state. This query should be used if the host is able to select a common voltage range or if a notification shall be sent to the system when a non-usable card in the stack is detected.

The following steps show how to perform voltage validation when a card is inserted:

```
voltage validation(voltage range arguement)
label the card as UNKNOWN;
send command(IO SEND OP COND, 0x0, <other parameters are omitted>); // CMD5, check SDIO
operation voltage, command argument is zero
if (RESP_TIMEOUT != wait_for_response(IO_SEND_OP_COND)) { // SDIO command is accepted
 if (0 < number of IO functions) {
  label the card as SDIO;
 while (!(IORDY in IO OCR response)) { // set voltage range for each IO function
  send command(IO SEND OP COND, <voltage range>, <other parameter>);
  wait_for_response(IO_SEND_OP_COND);
  } // end of while ...
  // end of if (0 < ...
 if (memory part is present inside SDIO card) Label the card as SDCombo; // this is an
SD-Combo card
} // end of if (RESP TIMEOUT ...
if (the card is labeled as SDIO card) return; // card type is identified and voltage range
set, so exit the function;
send command(APP CMD, 0x0, <other parameters are omitted>); // CMD55, Application specific
if (no error calling wait_for_response(APP_CMD, <...>) { // CMD55 is accepted
send command(SD APP OP COND, <voltage range>, <...>); // ACMD41, to set voltage range
for memory part or SD card
 wait_for_response(SD_APP_OP_COND); // voltage range is set
 if (card type is UNKNOWN) label the card as SD;
```



#### mualization/application of SDHC

```
return; //
} // end of if (no error ...
else if (errors other than time-out occur) { // command/response pair is corrupted
 deal with it by program specific manner;
} // of else if (response time-out
else { // CMD55 is refuse, it must be MMC card or CE-ATA card
 if (card is already labelled as SDCombo) \{\ //\ {\it change\ label}
 re-label the card as SDIO;
  ignore the error or report it;
 return; // card is identified as SDIO card
 } // of if (card is ...
 send command(SEND OP COND, <voltage range>, <...>);
 if (RESP_TIMEOUT == wait_for_response(SEND_OP_COND)) { // CMD1 is not accepted, either
 label the card as UNKNOWN;
 return;
 } // of if (RESP TIMEOUT ...
 if (check for CE-ATA signature succeeded) { // the card is CE-ATA
  store CE-ATA specific info from the signature;
 label the card as CE-ATA;
 } // of if (check for CE-ATA ...
 else label the card as MMC;
 // of else
```

### 50.6.2.4 Card registry

Card registry for the MMC and SD/SDIO/SD combo cards are different. For CE-ATA, it enters the tran state after reset is completed.

For the SD card, the identification process starts at a clock rate lower than 400 kHz and the power voltage higher than 2.7 V (as defined by the card specification). At this time, the CMD line output drives are push-pull drivers instead of open-drain. After the bus is activated, the host will request the card to send their valid operation conditions. The response to ACMD41 is the operation condition register of the card. The same command shall be send to all of the new cards in the system. Incompatible cards are put into the inactive state. The host then issues the command, All\_Send\_CID (CMD2), to each card to get its unique card identification (CID) number. Cards that are currently unidentified (in the ready state), send their CID number as the response. After the CID is sent by the card, the card goes into the identification state.

The host then issues Send\_Relative\_Addr (CMD3), requesting the card to publish a new relative card address (RCA) that is shorter than the CID. This RCA will be used to address the card for future data transfer operations. Once the RCA is received, the card changes its state to the standby state. At this point, if the host wants the card to have an alternative RCA number, it may ask the card to publish a new number by sending another Send\_Relative\_Addr command to the card. The last published RCA is the actual RCA of the card.

The host repeats the identification process with CMD2 and CMD3 for each card in the system until the last CMD2 gets no response from any of the cards in system.



For MMC operation, the host starts the card identification process in open-drain mode with the identification clock rate lower than 400 kHz and the power voltage higher than 2.7 V. The open drain driver stages on the CMD line allow parallel card operation during card identification. After the bus is activated the host will request the cards to send their valid operation conditions (CMD1). The response to CMD1 is the "wired OR" operation on the condition restrictions of all cards in the system. Incompatible cards are sent into the inactive state. The host then issues the broadcast command All Send CID (CMD2), asking all cards for their unique card identification (CID) number. All unidentified cards (the cards in ready state) simultaneously start sending their CID numbers serially, while bit-wise monitoring their outgoing bit stream. Those cards, whose outgoing CID bits do not match the corresponding bits on the command line in any one of the bit periods, stop sending their CID immediately and must wait for the next identification cycle. Since the CID is unique for each card, only one card can be successfully send its full CID to the host. This card then goes into the identification state. Thereafter, the host issues Set\_Relative\_Addr (CMD3) to assign to the card a relative card address (RCA). Once the RCA is received the card state changes to the standby state, and the card does not react in further identification cycles, and its output driver switches from open-drain to push-pull. The host repeats the process, mainly CMD2 and CMD3, until the host receives a time-out condition to recognize the completion of the identification process.

For CE-ATA operation (same interface as MMC cards):

```
card registry()
do { // decide RCA for each card until response time-out
 if card is labelled as SDCombo or SDIO) { // for SDIO card like device
  send command(SET RELATIVE ADDR, 0x00, <...>); // ask SDIO card to publish its
 retrieve RCA from response;
 } // end if (card is labelled as SDCombo ...
 else if (card is labelled as SD) { // for SD card
  send_command(ALL_SEND_CID, <...>);
if (RESP_TIMEOUT == wait_for_response(ALL_SEND_CID)) break;
  send command(SET RELATIVE ADDR, <...>);
 retrieve RCA from response;
 } // else if (card is labelled as SD ...
 else if (card is labelled as MMC or CE-ATA) { // treat CE-ATA as MMC
  send_command(ALL_SEND_CID, <...>);
  rca = 0x1; // arbitrarily set RCA, 1 here for example, this RCA is also the
relative address to access the CE-ATA card
  send command(SET_RELATIVE_ADDR, 0x1 << 16, <...>); // send RCA at upper 16
 } // end of else if (card is labelled as MMC ...
 while (response is not time-out);
```

## 50.6.3 Card access

This section discusses the various card access methods.



### 50.6.3.1 Block write

This section discusses the block write access methods.

#### 50.6.3.1.1 Normal write

During a block write (CMD24 - 27, CMD60, CMD61), one or more blocks of data are transferred from the host to the card with a CRC appended to the end of each block by the host. If the CRC fails, the card shall indicate the failure on the dat line. The transferred data will be discarded and not written, and all further transmitted blocks (in multiple block write mode) will be ignored.

If the host uses partial blocks whose accumulated length is not block aligned and block misalignment is not allowed (CSD parameter WRITE\_BLK\_MISALIGN is not set, and the CE-ATA card does not support partial block write, either), the card detects the block misalignment error and aborts the programming before the beginning of the first misaligned block. The card sets the ADDRESS\_ERROR error bit in the status register, and while ignoring all further data transfer, waits in the Receive-data-State for a stop command. For a CE-ATA card, check the CE-ATA card specification for its behavior in block misalignment. The write operation is also aborted if the host tries to write over a write protected area.

For MMC and SD cards, programming of the CID and CSD registers does not require a previous block length setting. The transferred data is also CRC protected. If a part of the CSD or CID register is stored in ROM, then this unchangeable part must match the corresponding part of the receive buffer. If this match fails, then the card will report an error and not change any register contents.

For all types of cards, some may require long and unpredictable periods of time to write a block of data. After receiving a block of data and completing the CRC check, the card will begin writing and hold the DAT line low if its write buffer is full and unable to accept new data from a new WRITE\_BLOCK command. The host may poll the status of the card with a SEND\_STATUS command (CMD13) or other means for SDIO and CE-ATA cards at any time, and the card will respond with its status. The responded status indicates whether the card can accept new data or whether the write process is still in progress. The host may deselect the card by issuing a CMD7 (to select a different card) to place the card into the Standby State and release the DAT line without interrupting the write operation. When re-selecting the card, it will reactivate the busy indication by pulling DAT to low if the programming is still in progress and the write buffer is unavailable.



The software flow to write to a card incorporates the internal DMA and the write operation is a multi-block write with the Auto CMD12 enabled. For the other two methods (by means of external DMA or CPU polling status) with different transfer methods, the internal DMA parts should be removed and the alternative steps should be straightforward.

The software flow to write to a card is described below:

- 1. Check the card status, wait until the card is ready for data.
- 2. Set the card block length/size:
  - a. For SD/MMC cards, use SET\_BLOCKLEN (CMD16)
  - b. For SDIO cards or the I/O portion of SDCombo cards, use IO\_RW\_DIRECT (CMD52) to set the I/O Block Size bit field in the CCCR register (for function 0) or FBR register (for functions 1~7)
  - c. For CE-ATA cards, configure bits 1~0 in the scrControl register
- 3. Set the eSDHC block length register to be the same as the block length set for the card in Step 2.
- 4. Set the eSDHC number block register (NOB), nob is 5 (for instance).
- 5. Disable the buffer write ready interrupt, configure the DMA settings and enable the eSDHC DMA when sending the command with data transfer. The AC12EN bit should also be set.
- 6. Wait for the Transfer Complete interrupt.
- 7. Check the status bit to see if a write CRC error occurred, or some another error, that occurred during the auto12 command sending and response receiving.

## 50.6.3.1.2 Write with pause

The write operation can be paused during the transfer. Instead of stopping the SD\_CLK at any time to pause all the operations, which is also inaccessible to the host driver, the driver can set the PROCTL[SABGREQ] to pause the transfer between the data blocks. As there is no time-out condition in a write operation during the data blocks, a write to all types of cards can be paused in this way, and if the DAT0 line is not required to de-assert to release the busy state, no suspend command is needed.

Like in the flow described in Normal write, the write with pause is shown with the same kind of write operation:



#### mualization/application of SDHC

- 1. Check the card status, wait until card is ready for data.
- 2. Set the card block length/size:
  - a. For SD/MMC, use SET\_BLOCKLEN (CMD16)
  - b. For SDIO cards or the I/O portion of SDCombo cards, use IO\_RW\_DIRECT(CMD52) to set the I/O Block Size bit field in the CCCR register (for function 0) or FBR register (for functions 1~7)
  - c. For CE-ATA cards, configure bits 1~0 in the scrControl register
- 3. Set the SDHC block length register to be the same as the block length set for the card in Step 2.
- 4. Set the SDHC number block register (NOB), nob is 5 (for instance).
- 5. Disable the buffer write ready interrupt, configure the DMA settings and enable the SDHC DMA when sending the command with data transfer. The XFERTYP[AC12EN] bit should also be set.
- 6. Set the PROCTL[SABGREQ] bit.
- 7. Wait for the transfer complete interrupt.
- 8. Clear the PROCTL[SABGREQ] bit.
- 9. Check the status bit to see if a write CRC error occurred.
- 10. Set the PROCTL[CREQ] bit to continue the write operation.
- 11. Wait for the transfer complete interrupt.
- 12. Check the status bit to see if a write CRC error occurred, or some another error, that occurred during the auto12 command sending and response receiving.

The number of blocks left during the data transfer is accessible by reading the contents of the BLKATTR[BLKCNT]. As the data transfer and the setting of the PROCTL[SABGREQ] bit are concurrent, and the delay of register read and the register setting, the actual number of blocks left may not be exactly the value read earlier. The driver shall read the value of BLKATTR[BLKCNT] after the transfer is paused and the transfer complete interrupt is received.

It is also possible the last block has begun when the stop at block gap request is sent to the buffer. In this case, the next block gap is actually the end of the transfer. These types of requests are ignored and the Driver should treat this as a non-pause transfer and deal with it as a common write operation.



When the write operation is paused, the data transfer inside the host system is not stopped, and the transfer is active until the data buffer is full. Because of this (if not needed), it is recommended to avoid using the suspend command for the SDIO card. This is because when such a command is sent, the SDHC thinks the system will switch to another function on the SDIO card, and flush the data buffer. The SDHC takes the resume command as a normal command with data transfer, and it is left for the driver to set all the relevant registers before the transfer is resumed. If there is only one block to send when the transfer is resumed, the XFERTYP[MSBSEL] and XFERTYP[BCEN] bits are set as well as the XFERTYP[AC12EN] bit. However, the SDHC will automatically send a CMD12 to mark the end of the multi-block transfer.

## 50.6.3.2 Block read

This section discusses the block read access methods.

## 50.6.3.2.1 Normal read

For block reads, the basic unit of data transfer is a block whose maximum size is stored in areas defined by the corresponding card specification. A CRC is appended to the end of each block, ensuring data transfer integrity. The CMD17, CMD18, CMD53, CMD60, CMD61, and so on, can initiate a block read. After completing the transfer, the card returns to the transfer state. For multi blocks read, data blocks will be continuously transferred until a stop command is issued.

The software flow to read from a card incorporates the internal DMA and the read operation is a multi-block read with the Auto CMD12 enabled. For the other two methods (by means of external DMA or CPU polling status) with different transfer methods, the internal DMA parts should be removed and the alternative steps should be straightforward.

The software flow to read from a card is described below:

- 1. Check the card status, wait until card is ready for data.
- 2. Set the card block length/size:
  - a. For SD/MMC, use SET\_BLOCKLEN (CMD16)
  - b. For SDIO cards or the I/O portion of SDCombo cards, use IO\_RW\_DIRECT(CMD52) to set the I/O block size bit field in the CCCR register (for function 0) or FBR register (for functions 1~7)
  - c. For CE-ATA cards, configure bits 1~0 in the scrControl register



#### mualization/application of SDHC

- 3. Set the SDHC block length register to be the same as the block length set for the card in Step 2.
- 4. Set the SDHC number block register (NOB), nob is 5 (for instance).
- 5. Disable the buffer read ready interrupt, configure the DMA settings and enable the SDHC DMA when sending the command with data transfer. The XFERTYP[AC12EN] bit should also be set:
- 6. Wait for the transfer complete interrupt.
- 7. Check the status bit to see if a read CRC error occurred, or some another error, occurred during the auto12 command sending and response receiving.

## 50.6.3.2.2 Read with pause

The read operation is not generally able to pause. Only the SDIO card (and SDCombo card working under I/O mode) supporting the read and wait feature can pause during the read operation. If the SDIO card support read wait (SRW bit in CCCR register is 1), the Driver can set the SABGREQ bit in the Protocol Control register to pause the transfer between the data blocks. Before setting the SABGREQ bit, make sure the RWCTL bit in the Protocol Control register is set, otherwise the eSDHC will not assert the Read Wait signal during the block gap and data corruption occurs. It is recommended to set the RWCTL bit once the Read Wait capability of the SDIO card is recognized.

Like in the flow described in Normal read, the read with pause is shown with the same kind of read operation:

- 1. Check the SRW bit in the CCR register on the SDIO card to confirm the card supports Read Wait.
- 2. Set the RWCTL bit.
- 3. Check the card status and wait until the card is ready for data.
- 4. Set the card block length/size:
  - a. For SD/MMC, use SET\_BLOCKLEN (CMD16)
  - b. For SDIO cards or the I/O portion of SDCombo cards, use IO\_RW\_DIRECT(CMD52) to set the I/O Block Size bit field in the CCCR register (for function 0) or FBR register (for functions 1~7)
  - c. For CE-ATA cards, configure bits 1~0 in the scrControl register



- 5. Set the SDHC block length register to be the same as the block length set for the card in Step 2.
- 6. Set the SDHC number block register (NOB), nob is 5 (for instance).
- 7. Disable the buffer read ready interrupt, configure the DMA setting and enable the eSDHC DMA when sending the command with data transfer. The AC12EN bit should also be set
- 8. Set the SABGREQ bit.
- 9. Wait for the Transfer Complete interrupt.
- 10. Clear the SABGREQ bit.
- 11. Check the status bit to see if read CRC error occurred.
- 12. Set the CREQ bit to continue the read operation.
- 13. Wait for the Transfer Complete interrupt.
- 14. Check the status bit to see if a read CRC error occurred, or some another error, occurred during the auto12 command sending and response receiving.

Like the write operation, it is possible to meet the ending block of the transfer when paused. In this case, the SDHC will ignore the Stop At Block Gap Request and treat it as a command read operation.

Unlike the write operation, there is no remaining data inside the buffer when the transfer is paused. All data received before the pause will be transferred to the Host System. No matter if the Suspend Command is sent or not, the internal data buffer is not flushed.

If the Suspend Command is sent and the transfer is later resumed by means of a Resume Command, the SDHC takes the command as a normal one accompanied with data transfer. It is left for the Driver to set all the relevant registers before the transfer is resumed. If there is only one block to send when the transfer is resumed, the MSBSEL and BCEN bits of the Transfer Type register are set, as well as the AC12EN bit. However, the SDHC will automatically send the CMD12 to mark the end of multi-block transfer.

# 50.6.3.3 Suspend resume

The SDHC supports the suspend resume operations of SDIO cards, although slightly different than the suggested implementation of Suspend in the SDIO card specification...



#### **ınınalization/application of SDHC**

## 50.6.3.3.1 Suspend

After setting the PROCTL[SABGREQ] bit, the host driver may send a suspend command to switch to another function of the SDIO card. The SDHC does not monitor the content of the response, so it doesn't know if the suspend command succeeded or not. Accordingly, it doesn't de-assert read wait for read pause. To solve this problem, the driver shall not mark the suspend command as a "suspend", (i.e. setting the XFERTYP[CMDTYP] bits to 01). Instead, the driver shall send this command as if it were a normal command, and only when the command succeeds, and the BS bit is set in the response, can the driver send another command marked as "suspend" to inform the SDHC that the current transfer is suspended. As shown in the following sequence for suspend operation:

- 1. Set the PROCTL[SABGREQ] bit to pause the current data transfer at block gap.
- 2. After the IRQSTAT[BGE] bit is set, send the suspend command to suspend the active function. The XFERTYP[CMDTYP] bit field must be 2'b00.
- 3. Check the BS bit of the CCCR in the response. If it is 1, repeat this step until the BS bit is cleared or abandon the suspend operation according to the Driver strategy.
- 4. Send another normal I/O command to the suspended function. The XFERTYP[CMDTYP] of this command must be 2'b01, so the SDHC can detect this special setting and be informed that the paused operation has successfully suspended. If the paused transfer is a read operation, the SDHC stops driving DAT2 and goes to the idle state.
- 5. Save the context registers in the system memory for later use, including the DMA system address register (for internal DMA operation), and the block attribute register.
- 6. Begin operation for another function on the SDIO card.

### 50.6.3.3.2 Resume

To resume the data transfer, a resume command shall be issued:

- 1. To resume the suspended function, restore the context register with the saved value in step #5 of the suspend operation above.
- 2. Send the resume command. In the transfer type register, all bit fields are set to the value as if this were another ordinary data transfer, instead of a transfer resume (except the CMDTYP is set to 2'b10).
- 3. If the resume command has responded, the data transfer will be resumed.



# 50.6.3.4 ADMA usage

To use the ADMA in a data transfer, the host driver must prepare the correct descriptor chain prior to sending the read/write command. The steps to accomplish this are:

- 1. Create a descriptor to set the data length that the current descriptor group is about to transfer. The data length should be even numbers of the block size.
- 2. Create another descriptor to transfer the data from the address setting in this descriptor. The data address must be at a page boundary (4 KB address aligned).
- 3. If necessary, create a link descriptor containing the address of the next descriptor. The descriptor group is created in steps  $1 \sim 3$ .
- 4. Repeat steps  $1 \sim 3$  until all descriptors are created.
- 5. In the last descriptor, set the end flag to 1 and make sure the total length of all descriptors match the product of the block size and block number configured in the BLKATTR register.
- 6. Set the DSADDR register to the address of the first descriptor and set the PROCTL[DMAS] field to 01 to select the ADMA.
- 7. Issue a write or read command with the XFERTYP[DMAEN] bit set to 1.

Steps  $1 \sim 5$  are independent of step 6, so step 6 can finish before steps  $1 \sim 5$ . Regarding the descriptor configuration, it is recommended not to use the link descriptor as it requires extra system memory access.

## 50.6.3.5 Transfer error

This section discusses the handling of transfer errors.

## 50.6.3.5.1 CRC error

It is possible at the end of a block transfer, that a write CRC status error or read CRC error occurs. For this type of error the latest block received shall be discarded. This is because the integrity of the data block is not guaranteed. It is recommended to discard the following data blocks and re-transfer the block from the corrupted one. For a multi-block transfer, the host driver shall issue a CMD12 to abort the current process and start the transfer by a new data command. In this scenario, even when the XFERTYP[AC12EN] and BCEND bits are set, the SDHC does not automatically send a CMD12 because the



#### mualization/application of SDHC

last block is not transferred. On the other hand, if it is within the last block that the CRC error occurs, an auto CMD12 will be sent by the SDHC. In this case, the driver shall resend or re-obtain the last block with a single block transfer.

#### 50.6.3.5.2 Internal DMA error

During the data transfer with internal simple DMA, if the DMA engine encounters some error on the system bus, the DMA operation is aborted and DMA error interrupt is sent to the host system. When acknowledged by such an interrupt, the driver shall calculate the start address of data block in which the error occurs. The start address can be calculated by either:

- 1. Read the DMA system address register. The error occurs during the previous burst. Taking the block size, the previous burst length and the start address of the next burst transfer into account, it is straight forward to obtain the start address of the corrupted block.
- 2. Read the BLKCNT field of the block attribute register. By the number of blocks left, the total number to transfer, the start address of transfer, and the size of each block, the start address of corrupted block can be determined. When the BCEN bit is not set, the contents of the block attribute register does not change, so this method does not work.

When a DMA error occurs, it is recommended to abort the current transfer by means of a CMD12 (for multi block transfer), apply a reset for data, and re-start the transfer from the corrupted block to recover from the error.

## 50.6.3.5.3 ADMA error

There are three kinds of possible ADMA errors. The transfer, invalid descriptor, and data-length mismatch errors. Whenever these errors occur, the DMA transfer stops and the corresponding error status bit is set. For acknowledging the status, the host driver should recover the error as shown below and re-transfer from the place of interruption.

1. Transfer error: Such errors may occur during data transfer or descriptor fetch. For either scenario, it is recommended to retrieve the transfer context, reset for the data part and re-transfer the block that was corrupted, or the next block if no block is corrupted.



- 2. Invalid descriptor error: For such errors, it is recommended to retrieve the transfer context, reset for the data part and re-create the descriptor chain from the invalid descriptor and issue a new transfer. As the data to transfer now may be less than the previous setting, the data length configured in the new descriptor chain should match the new value.
- 3. Data-length mismatch error: It is similar to recover from this error. The host driver polls relating registers to retrieve the transfer context, apply a reset for the data part, configure a new descriptor chain, and make another transfer if there is data left. Like the previous scenario of the invalid descriptor error, the data length must match the new transfer.

#### 50.6.3.5.4 Auto CMD12 error

After the last block of the multi block transfer is sent or received, and the XFERTYP[AC12EN] bit is set when the data transfer is initiated by the data command, the SDHC automatically sends a CMD12 to the card to stop the transfer. When errors with this command occur, it is recommended to the driver to deal with the situations in the following manner:

- 1. Auto CMD12 response time-out. It is not certain whether the command is accepted by the card or not. The driver should clear the IRQSTAT[AC12E] bits and re-send the CMD12 until it is accepted by the card.
- 2. Auto CMD12 response CRC error. Since card responds to the CMD12, the card will abort the transfer. The driver may ignore the error and clear the IRQSTAT[AC12E] bit.
- 3. Auto CMD12 conflict error or not sent. The command is not sent, so the driver shall send a CMD12 manually.

## 50.6.3.6 Card interrupt

The external cards can inform the host controller by means of some special signals. For the SDIO card, it can be the low level on the DAT[1] line during some special period. For the CE-ATA card, it can be a pulse on the CMD line to inform the host controller that the command and its response is finished, and it is possible that some additional external interrupt behaviors are defined. The SDHC only monitors the DAT[1] line and supports the SDIO interrupt.



#### mualization/application of SDHC

When the SDIO interrupt is captured by the SDHC, and the host system is informed by the SDHC asserting the SDHC interrupt line, the interrupt service from the host driver is called.

As the interrupt factor is controlled by the external card, the interrupt from the SDIO card must be served before the IRQSTAT[CINT] bit is cleared by written 1. Refer to Card interrupt handling for the card interrupt handling flow.

## 50.6.4 Switch function

MMC cards transferring data at bus widths other than 1-bit is a new feature added to the MMC specifications. The high speed timing mode for all card devices, was also recently defined in various card specifications. To enable these new features, a "switch" command shall be issued by the host driver.

For SDIO cards, the high speed mode is enabled by writing the EHS bit in the CCCR register after the SHS bit is confirmed. For SD cards, the high speed mode is queried and enabled by a CMD6 (with the mnemonic symbol as SWITCH\_FUNC). For MMC cards (and CE-ATA over MMC interface), the high speed mode is queried by a CMD8 and enabled by a CMD6 (with the mnemonic symbol as SWITCH).

The 4-bit and 8-bit bus width of the MMC is also enabled by the SWITCH command, but with a different argument.

These new functions can also be disabled by a software reset. For SDIO cards it can be done by setting the RES bit in the CCCR register. For other cards, it can be accomplished by issuing a CMD0. This method of restoring to the normal mode is not recommended because a complete identification process is needed before the card is ready for data transfer.

For the sake of simplicity, the following flowcharts do not show current capability check, which is recommended in the function switch process.

## 50.6.4.1 Query, enable and disable SDIO high speed mode

```
enable_sdio_high_speed_mode(void)
{
send CMD52 to query bit SHS at address 0x13;
if (SHS bit is '0') report the SDIO card does not support high speed mode and return;
send CMD52 to set bit EHS at address 0x13 and read after write to confirm EHS bit is set;
change clock divisor value or configure the system clock feeding into eSDHC to generate the
card_clk of around 50MHz;
(data transactions like normal peers)
}
disable_sdio_high_speed_mode(void)
{
```



```
send CMD52 to clear bit EHS at address 0x13 and read after write to confirm EHS bit is
cleared;
change clock divisor value or configure the system clock feeding into eSDHC to generate the
card_clk of the desired value below 25MHz;
(data transactions like normal peers)
}
```

## 50.6.4.2 Query, enable and disable SD high speed mode

```
enable sd high speed mode (void)
set BLKCNT field to 1 (block), set BLKSIZE field to 64 (bytes);
send CMD6, with argument 0xFFFFF1 and read 64 bytes of data accompanying the R1 response;
wait data transfer done bit is set;
check if the bit 401 of received 512 bit is set;
if (bit 401 is '0') report the SD card does not support high speed mode and return;
send CMD6, with argument 0x80FFFFF1 and read 64 bytes of data accompanying the R1 response;
check if the bit field 379~376 is 0xF;
if (the bit field is 0xF) report the function switch failed and return;
change clock divisor value or configure the system clock feeding into eSDHC to generate the
card clk of around 50MHz;
(data transactions like normal peers)
disable sd high speed mode (void)
set BLKCNT field to 1 (block), set BLKSIZE field to 64 (bytes);
send CMD6, with argument 0x80FFFFF0 and read 64 bytes of data accompanying the R1 response;
check if the bit field 379~376 is 0xF;
if (the bit field is 0xF) report the function switch failed and return;
change clock divisor value or configure the system clock feeding into eSDHC to generate the
card clk of the desired value below 25MHz;
(data transactions like normal peers)
```

# 50.6.4.3 Query, enable and disable MMC high speed mode

```
enable mmc high speed mode (void)
send CMD9 to get CSD value of MMC;
check if the value of SPEC VER field is 4 or above;
if (SPEC VER value is less than 4) report the MMC does not support high speed mode and
set BLKCNT field to 1 (block), set BLKSIZE field to 512 (bytes);
send CMD8 to get EXT CSD value of MMC;
extract the value of CARD TYPE field to check the 'high speed mode' in this MMC is 26MHz or
send CMD6 with argument 0x1B90100;
send CMD13 to wait card ready (busy line released);
send CMD8 to get EXT_CSD value of MMC;
check if HS_TIMING byte (byte number 185) is 1;
if (HS TIMING is not 1) report MMC switching to high speed mode failed and return;
change clock divisor value or configure the system clock feeding into eSDHC to generate the
card clk of around 26MHz or 52MHz according to the CARD TYPE;
(data transactions like normal peers)
disable_mmc_high_speed_mode(void)
send CMD6 with argument 0x2B90100;
set BLKCNT field to 1 (block), set BLKSIZE field to 512 (bytes);
send CMD8 to get EXT CSD value of MMC;
check if HS TIMING byte (byte number 185) is 0;
```

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### mualization/application of SDHC

```
if (HS_TIMING is not 0) report the function switch failed and return;
change clock divisor value or configure the system clock feeding into eSDHC to generate the
card_clk of the desired value below 20MHz;
(data transactions like normal peers)
}
```

## 50.6.4.4 Set MMC bus width

```
change_mmc_bus_width(void)
{
  send CMD9 to get CSD value of MMC;
  check if the value of SPEC_VER field is 4 or above;
  if (SPEC_VER value is less than 4) report the MMC does not support multiple bit width and return;
  send CMD6 with argument 0x3B70x00; (8-bit, x=2; 4-bit, x=1; 1-bit, x=0)
  send CMD13 to wait card ready (busy line released);
  (data transactions like normal peers)
}
```

# 50.6.5 ADMA operation

This section presents code examples for ADMA operation.

## 50.6.5.1 ADMA1 operation

```
Set_adma1_descriptor
      if (to start data transfer) {
          // Make sure the address is 4KB align.
          Set 'Set' type descriptor;
              Set Act bits to 01;
              Set [31:12] bits data length (byte unit);
          Set 'Tran' type descriptor;
              Set Act bits to 10;
              Set [31:12] bits address (4KB align);
      else if (to fetch descriptor at non-continuous address) {
          Set Act bits to 11;
          Set [31:12] bits the next descriptor address (4KB align);
      else { // other types of descriptor
          Set Act bits accordingly
      if (this descriptor is the last one) {
          Set End bit to 1;
      if (to generate interrupt for this descriptor) {
          Set Int bit to 1;
      Set Valid bit to 1;
```



# 50.6.5.2 ADMA2 operation

```
Set_adma2_descriptor
      if (to start data transfer) {
          // Make sure the address is 32-bit boundary (lower 2-bit are always '00').
          Set higher 32-bit of descriptor for this data transfer initial address;
          Set [31:16] bits data length (byte unit);
          Set Act bits to '10';
      else if (to fetch descriptor at non-continuous address) {
          Set Act bits to '11';
          // Make sure the address is 32-bit boundary (lower 2-bit are always set to '00').
          Set higher 32-bit of descriptor for the next descriptor address;
      else { // other types of descriptor
          Set Act bits accordingly
      if (this descriptor is the last one) {
          Set 'End' bit '1';
      if (to generate interrupt for this descriptor) {
          Set 'Int' bit '1';
      Set the 'Valid' bit to '1';
```

# 50.6.6 Fast boot operation

This section discusses fast boot operations.

## 50.6.6.1 Normal fast boot flow

- 1. Software need to configure SYSCTL[INITA] to make sure 74 card clocks are finished.
- 2. Software need to configure MMCBOOT[BOOTEN] to 1, and MMCBOOT[BOOTMODE] to 0, and MMCBOOT[BOOTACK] to select the ack mode or not. If need to send through DMA mode, need to configure MMCBOOT[AUTOSABGEN] to enable automatically stop at block gap feature. And need to configure MMCBOOT[DTOCVACK] to select the ack timeout value according to the sd clk frequence.
- 3. Software then need to configure BLKATTR register to set block size/no.
- 4. Software need to configure PROCTL[DTW].
- 5. Software need to configure CMDARG to set argument if needed(no need in normal fast boot).



#### mualization/application of SDHC

- 6. Software need to configure XFERTYP register to start the boot process . In normal boot mode, XFERTYP[CMDINX], XFERTYP[CMDTYP], XFERTYP[RSPTYP], XFERTYP[CICEN], XFERTYP[CCCEN], XFERTYP[AC12EN], XFERTYP[BCEN] and XFERTYP[DMAEN] are kept default value. XFERTYP[DPSEL] bit is set to 1, XFERTYP[DTDSEL] is set to 1, XFERTYP[MSBSEL] is set to 1. Note XFERTYP[DMAEN] should be configured as 0 in polling mode. And if XFERTYP[BCEN] is configured as 1, better to configure BLKATTR[BLKSIZE] to the max value.
- 7. When the step 6 is configured, boot process will begin. Software need to poll the data buffer ready status to read the data from buffer in time. If boot time-out happened(ack time out or the first data read time out), Interrupt will be triggered, and software need to configure MMCBOOT[]BOOTEN] to 0 to disable boot. Thus will make CMD high, and then after at least 56 clocks, it is ready to begin normal initialization process.
- 8. If no time out, software need to decide the data read is finished and then configure MMCBOOT[]BOOTEN] to 0 to disable boot. This will make CMD line high and command completed asserted. After at least 56 clocks, it is ready to begin normal initialization process.
- 9. Reset the host and then can begin the normal process.

## 50.6.6.2 Alternative fast boot flow

- 1. Software need to configure init\_active bit (system control register bit 27) to make sure 74 card clocks are finished.
- 2. Software need to configure MMCBOOT [BOOTEN] to 1, and MMCBOOT [BOOTMODE] to 1, and MMCBOOT [BOOTACK] to select the ack mode or not. If need to send through DMA mode, need to configure MMCBOOT [AUTOSABGEN] to enable automatically stop at block gap feature. And need to configure MMCBOOT [DTOCVACK] to select the ack timeout value according to the sd clk frequence.
- 3. Software then need to configure BLKATTR register to set block size/no.
- 4. Software need to configure PROCTL[DTW].
- 5. Software need to configure CMDARG register to set argument to 0xFFFFFFA.
- 6. Software need to configure XFERTYP register to start the boot process by CMD0 with 0xFFFFFFA argument . In alternative boot, CMDINX, CMDTYP, RSPTYP, CICEN, CCCEN, AC12EN, BCEN and DMAEN are kept default value. DPSEL bit



is set to 1, DTDSEL is set to 1, MSBSEL is set to 1. Note DMAEN should be configured as 0 in polling mode. And if BCEN is configured as 1 in polling mode, better to configure blk no in Bock Attributes Register to the max value.

- 7. When the step 6 is configured, boot process will begin. Software need to poll the data buffer ready status to read the data from buffer in time. If boot time out (ack data time out in 50ms or data time out in 1s), host will send out the interrupt and software need to send CMD0 with reset and then configure boot enable bit to 0 to stop this process. After command completed, configure MMCBOOT[BOOTEN] to 0 to disable boot. After at least 8 clocks from command completed, card is ready for identification step.
- 8. If no time out, software need to decide when to stop the boot process, and send out the CMD0 with reset and then after command completed, configure MMCBOOT[BOOTEN] to stop the process. After 8 clocks from command completed, slave(card) is ready for identification step.
- 9. Reset the host and then can begin the normal process.

# 50.6.6.3 Fast boot application case (in DMA mode)

In the boot application case, because the image destination and the image size are contained in the

beginning of the image, need to switch DMA parameters on the fly during MMC fast boot.

In fast boot, host can use ADMA2(advanced DMA2) with two destinations.

### The detail flow:

- 1. Software need to configure init\_active bit (system control register bit 27) to make sure 74 card clocks are finished.
- 2. Software need to configure MMCBOOT[BOOTEN] to 1; and MMCBOOT[BOOTMODE] to 0 (normal fast boot), to 1(alternative boot); and MMCBOOT[BOOTACK] to select the ack mode or not. In DMA mode, configure MMCBOOT[AUTOSABGEN] to 1 for enable automatically stop at block gap feature. Also configure MMCBOOT[BOOTBLKCNT] to set the VAULE1(value of block count that need to trans first time), that host will stop at block gap when card block counter is equal to this value. And need to configure MMCBOOT[DTOCVACK] to select the ack timeout value according to the sd clk frequence.



#### mualization/application of SDHC

- 3. Software then need to configure BLKATTR register to set block size/no. In DMA mode, it is better to set block number to the max value(16'hffff).
- 4. Software need to configure PROCTL[DTW].
- 5. Software enable ADMA2 by configuring PROCTL[DMAS].
- 6. Software need to set at least three pairs ADMA2 descriptor in boot memory (ie, in IRAM, at least 6 words). The first pair descriptor define the start address (ie, IRAM) and data length(ie,512byte\*VALUE1) of first part boot code. Software also need to set the second pair descriptor, the second start address (any value that is writable), data length is suggest to set 1~2word (record as VAULE2). Note: the second couple desc also transfer useful data even at lease 1 word. Because our ADMA2 can't support 0 data\_length data transfer descriptor.
- 7. Software need to configure CMDARG register to set argument to 0xFFFFFFA in alternative fast boot, and don't need set in normal fast boot.
- 8. Software need to configure XFERTYP register to start the boot process . XFERTYP[CMDINX], XFERTYP[CMDTYP], XFERTYP[RSPTYP], XFERTYP[CICEN], XFERTYP[CCCEN], XFERTYP[AC12EN], XFERTYP[BCEN] and XFERTYP[DMAEN] are kept default value. XFERTYP[DPSEL] bit is set to 1, XFERTYP[DTDSEL] is set to 1, XFERTYP[MSBSEL] is set to 1. XFERTYP[DMAEN] is configured as 1 in DMA mode. And if XFERTYP[BCEN] is configured as 1, better to configure blk no in BLKATTR register to the max value.
- 9. When the step 8 is configured, boot process will begin, the first VAULE1 block number data has transfer. Software need to polling IRQSTAT[TC] bit to determine first transfer is end. Also software need to polling IRQSTAT[BGE] bit to determine if first transfer stop at block gap.
- 10. When IRQSTAT[TC] and IRQSTAT[BGE] bits are 1, . SW can analyzes the first code of VAULE1 block, initializes the new memory device, if required, and sets the third pair of descriptors to define the start address and length of the remaining part of boot code (VAULE3 the remain boot code block). Remember set the last descriptor with END.
- 11. Software need to configure MMCBOOT register (offset 0xc4) again. Set MMCBOOT[BOOTEN] bit to 1; and MMCBOOT[BOOTMODE] bit to 0 (normal fast boot), to 1(alternative boot); and MMCBOOT[BOOTACK] bit to select the ack mode or not. In DMA mode, configure MMCBOOT[AUTOSABGEN] bit to 1 for enable automatically stop at block gap feature. Also configure MMCBOOT[BOOTBLKCNT] bit to set the (VAULE1+1+VAULE3), that host will



- stop at block gap when card block counter is equal to this value. And need to configure MMCBOOT[DTOCVACK] bit to select the ack timeout value according to the sd clk frequence.
- 12. Software need to clear IRQSTAT[TC] and IRQSTAT[BGE] bit. And software need to clear PROCTL[SABGREQ], and set PROCTL[CREQ] to 1 to resume the data transfer. Host will transfer the VALUE2 and VAULE3 data to the destination that is set by descriptor.
- 13. Software need to polling IRQSTAT[BGE] bit to determine if the fast boot is over.

#### **Note**

- 1. When ADMA boot flow is started, for SDHC, it is like a normal ADMA read operation. So setting ADMA2 descriptor as the normal ADMA2 transfer.
- 2. Need a few words length memory to keep descriptor.
- 3. For the 1~2 words data in second descriptor setting, it is the useful data, so software need to deal the data due to the application case.

## 50.6.7 Commands for MMC/SD/SDIO/CE-ATA

The following table lists the commands for the MMC/SD/SDIO/CE-ATA cards.

Refer to the corresponding specifications for more details about the command information.

There are four kinds of commands defined to control the Multimediacard:

- 1. broadcast commands (bc), no response.
- 2. broadcast commands with response (bcr), response from all cards simultaneously.
- 3. addressed (point-to-point) commands (ac), no data transfer on the DAT.
- 4. addressed (point-to-point) data transfer commands (adtc).

Table 50-37. Commands for MMC/SD/SDIO/CE-ATA cards

CMD INDEX	Туре	Argument	Resp	Abbreviation	Description	
CMD0	bc	[31:0] stuff bits	-		Resets all MMC and SD memory cards to idle state.	



## **ınıualization/application of SDHC**

# Table 50-37. Commands for MMC/SD/SDIO/CE-ATA cards (continued)

CMD INDEX	Туре	Argument	Resp	Abbreviation	Description	
CMD1	bcr [31:0] OCR without busy		R3	SEND_OP_COND	Asks all MMC and SD memory cards in idle state to send their operation conditions register contents in the response on the CMD line.	
CMD2	bcr	[31:0] stuff bits	R2	ALL_SEND_CID	Asks all cards to send their CID numbers on the CMD line.	
CMD3 <sup>1</sup>	ac	[31:6] RCA [15:0] stuff bits	R1 R6 (SDIO)	SET/ SEND_RELATIVE_AD DR	Assigns relative address to the card.	
CMD4	bc	[31:0] DSR [15:0] stuff bits	-	SET_DSR	Programs the DSR of all cards.	
CMD5	bc	[31:0] OCR without busy	R4	IO_SEND_OP_COND	Asks all SDIO cards in idle state to send their operation conditions register contents in the response on the CMD line.	
CMD6 <sup>2</sup>	adtc	[31] Mode  0: Check function  1: Switch function [30:8] Reserved for function groups 6 ~ 3 (All 0 or 0xFFFF)  [7:4] Function group1 for command system [3:0] Function group2 for access mode	R1	SWITCH_FUNC	Checks switch ability (mode 0) and switch card function (mode 1). Refer to "SD Physical Specification V1.1" for more details.	
CMD6 <sup>3</sup>	ac	[31:26] Set to 0 [25:24] Access [23:16] Index [15:8] Value [7:3] Set to 0 [2:0] Cmd Set	R1b	SWITCH	Switches the mode of operation of the selected card or modifies the EXT_CSD registers. Refer to "The MultiMediaCard System Specification Version 4.0 Final draft 2" for more details.	
CMD7	ac	[31:6] RCA [15:0] stuff bits	R1b	SELECT/ DESELECT_CARD	Toggles a card between the stand-by and transfer states or between the programming and disconnect states. In both cases, the card is selected by its own relative address and gets deselected by any other address. Address 0 deselects all.	



# Table 50-37. Commands for MMC/SD/SDIO/CE-ATA cards (continued)

CMD INDEX Type		Argument	Resp	Abbreviation	Description
CMD8	CMD8 adtc [3		R1	SEND_EXT_CSD	The card sends its EXT_CSD register as a block of data, with a block size of 512 bytes.
CMD9	ac	[31:6] RCA [15:0] stuff bits	R2	SEND_CSD	Addressed card sends its card-specific data (CSD) on the CMD line.
CMD10	ac	[31:6] RCA [15:0] stuff bits	R2	SEND_CID	Addressed card sends its card-identification (CID) on the CMD line.
CMD11	adtc	[31:0] data address	R1	READ_DAT_UNTIL_S TOP	Reads data stream from the card, starting at the given address, until a STOP_TRANSMISSION follows.
CMD12	ac	[31:0] stuff bits	R1b	STOP_TRANSMISSIO	Forces the card to stop transmission.
CMD13	ac	[31:6] RCA [15:0] stuff bits	R1	SEND_STATUS	Addressed card sends its status register.
CMD14	Reserved	d			
CMD15	ac	[31:6] RCA [15:0] stuff bits	-	GO_INACTIVE_STAT	Sets the card to inactive state in order to protect the card stack against communication breakdowns.
CMD16	ac	[31:0] block length	R1	SET_BLOCKLEN	Sets the block length (in bytes) for all following block commands (read and write). Default block length is specified in the CSD.
CMD17	adtc	[31:0] data address	R1	READ_SINGLE_BLOC	Reads a block of the size selected by the SET_BLOCKLEN command.
CMD18	adtc	[31:0] data address	R1	READ_MULTIPLE_BL OCK	Continuously transfers data blocks from card to host until interrupted by a stop command.
CMD19	Reserved	t	1	'	1
CMD20	adtc	[31:0] data address	R1	WRITE_DAT_UNTIL_S TOP	Writes data stream from the host, starting at the given address, until a STOP_TRANSMISION follows.
CMD21-23	Reserved	t		·	1
CMD24	adtc	[31:0] data address	R1	WRITE_BLOCK	Writes a block of the size selected by the SET_BLOCKLEN command.



## **ınıualization/application of SDHC**

# Table 50-37. Commands for MMC/SD/SDIO/CE-ATA cards (continued)

CMD INDEX	Туре	Argument	Resp	Abbreviation	Description		
CMD25	adtc	[31:0] data address	R1	WRITE_MULTIPLE_BL OCK	Continuously writes blocks of data until a STOP_TRANSMISSION follows.		
CMD26	adtc [31:0] s		R1	PROGRAM_CID	Programming of the card identification register. This command shall be issued only once per card. The card contains hardware to prevent this operation after the first programming. Normally this command is reserved for the manufacturer.		
CMD27	adtc	[31:0] stuff bits	R1	PROGRAM_CSD	Programming of the programmable bits of the CSD.		
CMD28	ac	[31:0] data address	R1b	SET_WRITE_PROT	If the card has write protection features, this command sets the write protection bit of the addressed group. The properties of write protection are coded in the card specific data (WP_GRP_SIZE).		
CMD29	ac	[31:0] data address	R1b	CLR_WRITE_PROT	If the card provides write protection features, this command clears the write protection bit of the addressed group.		
CMD30	adtc	[31:0] write protect data address	R1	SEND_WRITE_PROT	If the card provides write protection features, this command asks the card to send the status of the write protection bits.		
CMD31	Reserved	1		,			
CMD32	ac	[31:0] data address	R1	TAG_SECTOR_STAR T	Sets the address of the first sector of the erase group.		
CMD33	ac	[31:0] data address	R1	TAG_SECTOR_END	Sets the address of the last sector in a continuous range within the selection of a single sector to be selected for erase.		
CMD34	ac	[31:0] data address	R1	UNTAG_SECTOR	Removes one previously selected sector from the erase selection.		
CMD35	ac	[31:0] data address	R1	TAG_ERASE_GROUP _START	Sets the address of the first erase group within a range to be selected for erase.		



# Table 50-37. Commands for MMC/SD/SDIO/CE-ATA cards (continued)

CMD INDEX Type		Argument	Resp	Abbreviation	Description		
CMD36	ac [31:0] data address		R1	TAG_ERASE_GROUP _END	Sets the address of the last erase group within a continuous range to be selected for erase.		
CMD37	ac	[31:0] data address	R1	UNTAG_ERASE_GRO UP	Removes one previously selected erase group from the erase selection.		
CMD38	ac	[31:0] stuff bits	R1b	ERASE	Erase all previously selected sectors.		
CMD39	ac	[31:0] RCA [15] register write flag [14:8] register address [7:0] register data	R4	FAST_IO	Used to write and read 8-bit (register) data fields. The command addresses a card, and a register, and provides the data for writing if the write flag is set. The R4 response contains data read from the address register. This command accesses application dependent registers which are not defined in the MMC standard.		
CMD40	bcr	[31:0] stuff bits	R5	GO_IRQ_STATE	Sets the system into interrupt mode.		
CMD41	Reserved	t					
CDM42	adtc	[31:0] stuff bits	R1b	LOCK_UNLOCK	Used to set/reset the password or lock/unlock the card. The size of the data block is set by the SET_BLOCK_LEN command.		
CMD43~51	Reserved	t		-			
CMD52	ac	[31:0] stuff bits	R5	IO_RW_DIRECT	Access a single register within the total 128k of register space in any I/O function.		
CMD53	ac	[31:0] stuff bits	R5	IO_RW_EXTENDED	Accesses a multiple I/O register with a single command. Allows the reading or writing of a large number of I/O registers.		
CMD54	Reserved	t	1				
CMD55			R1	APP_CMD	Indicates to the card that the next command is an application specific command rather that a standard command.		



## **ınıualization/application of SDHC**

# Table 50-37. Commands for MMC/SD/SDIO/CE-ATA cards (continued)

CMD INDEX	Туре	Argument	Resp	Abbreviation	Description
CMD56	adtc	[31:1] stuff bits [0]: RD/WR	R1b	GEN_CMD	Used either to transfer a data block to the card or to get a data block from the card for general purpose / application specific commands. The size of the data block is set by the SET_BLOCK_LEN command.
CMD57~59	Reserved	d			
CMD60	adtc	[31] WR [30:24] stuff bits [23:16] address [15:8] stuff bits [7:0] byte count	R1b	RW_MULTIPLE_REGI STER	CE-ATA devices contain a set of Status and Control registers that begin at register offset 80h. These registers are used to control the behavior of the device and to retrieve status information regarding the operation of the device. All Status and Control registers are WORD (32-bit) in size and are WORD aligned. CMD60 shall be used to read and write these registers.
CMD61	adtc	[31] WR [30:16] stuff bits [15:0] data unit count	R1b	RW_MULTIPLE_BLOC K	The host issues a RW_MULTIPLE_BLOCK (CMD61) to begin the data transfer for the ATA command.
CMD62~63	Reserved	d	•	·	
ACMD6 <sup>4</sup>	ac	[31:2] stuff bits [1:0] bus width	R1	SET_BUS_WIDTH	Defines the data bus width ('00'=1bit or '10'=4bit bus) to be used for data transfer. The allowed data bus widths are given in SCR register.
ACMD13 <sup>5</sup>	adtc	[31:0] stuff bits	R1	SD_STATUS	Send the SD memory card status.
ACMD22 <sup>6</sup>	adtc	[31:0] stuff bits	R1	SEND_NUM_WR_SEC TORS	Send the number of the written sectors (without errors). Responds with 32-bit plus the CRC data block.
ACMD23 <sup>7</sup>	ac		R1	SET_WR_BLK_ERAS E_COUNT	-
ACMD41 <sup>8</sup>	ber	[31:0] OCR	R3	SD_APP_OP_COND	Asks the accessed card to send its operating condition register (OCR) contents in the response on the CMD line.
ACMD42 <sup>9</sup>	ac		R1	SET_CLR_CARD_DET ECT	-



## Table 50-37. Commands for MMC/SD/SDIO/CE-ATA cards (continued)

CMD INDEX	Туре	Argument	Resp	Abbreviation	Description	
ACMD51 <sup>10</sup>	adtc	[31:0] stuff bits	R1	SEND_SCR	Reads the SD Configuration Register (SCR).	

- 1. CMD3 differs for MMC and SD cards. For MMC cards, it is referred to as SET\_RELATIVE\_ADDR, with a response type of R1. For SD cards, it is referred to as SEND\_RELATIVE\_ADDR, with a response type of R6 (with RCA inside).
- 2. CMD6 differs completely between high speed MMC cards and high speed SD cards. Command SWITCH\_FUNC is for high speed SD cards.
- 3. Command SWITCH is for high speed MMC cards as well as for CE-ATA cards over the MMC interface. The Index field can contain any value from 0-255, but only values 0-191 are valid. If the Index value is in the 192-255 range the card does not perform any modification and the SWITCH\_ERROR status bit in the EXT\_CSD register is set. The Access Bits are shown in Table 50-38.
- ACMDs shall be preceded with the APP\_CMD command. (Commands listed are used for SD only, other SD commands not listed are not supported on this module).
- 5. ACMDs shall be preceded with the APP\_CMD command. (Commands listed are used for SD only, other SD commands not listed are not supported on this module).
- 6. ACMDs shall be preceded with the APP\_CMD command. (Commands listed are used for SD only, other SD commands not listed are not supported on this module).
- 7. ACMDs shall be preceded with the APP\_CMD command. (Commands listed are used for SD only, other SD commands not listed are not supported on this module).
- 8. ACMDs shall be preceded with the APP\_CMD command. (Commands listed are used for SD only, other SD commands not listed are not supported on this module).
- 9. ACMDs shall be preceded with the APP\_CMD command. (Commands listed are used for SD only, other SD commands not listed are not supported on this module).
- 10. ACMDs shall be preceded with the APP\_CMD command. (Commands listed are used for SD only, other SD commands not listed are not supported on this module).

The Access Bits for the EXT\_CSD Access Modes are shown in the following table.

### Table 50-38. EXT\_CSD Access Modes

Bits	Access Name	Operation
00	Command Set	The command set is changed according to the Cmd Set field of the argument
01	Set Bits	The bits in the pointed byte are set, according to the 1 bits in the Value field.
10	Clear Bits	The bits in the pointed byte are cleared, according to the 1 bits in the Value field.
11	Write Byte	The Value field is written into the pointed byte.

# 50.7 Software restrictions

Software for the SDHC must observe the following restrictions.



**SOLWARE restrictions** 

## 50.7.1 Initialization active

The driver cannot set SYSCTL[INITA] bit when any of the command line or data lines is active, so the driver must ensure both PRSSTAT[CDIHB] and PRSSTAT[CIHB] bits are cleared. And in order to auto clear the SYSCTL[INITA] bit, the SYSCTL[SDCLKEN] bit must be '1', otherwise no clocks can go out to the card and SYSCTL[INITA] will never clear.

# 50.7.2 Software polling procedure

For polling read or write, once the software begins a buffer read or write, it must access exactly the number of times as the values set in the watermark level register; moreover, if the block size is not the times of the value in watermark level register (read and write respectively), the software must access exactly the remained number of words at the end of each block. For example, for read operation, if the WML[RDWML] is 4, indicating the watermark level is 16 bytes, block size is 40 bytes, and the block number is 2, then the access times for the burst sequence in the whole transfer process must be 4, 4, 2, 4, 4, 2.

# 50.7.3 Suspend operation

In order to suspend the data transfer, the software must inform SDHC that the suspend command is successfully accepted. To achieve this, after the Suspend command is accepted by the SDIO card, software must send another normal command marked as suspend command (XFERTYP[CMDTYP] bits set as '01') to inform SDHC that the transfer is suspended.

If software needs resume the suspended transfer, it should read the value in BLKATTR[BLKCNT] to save the remained number of blocks before sending the normal command marked as suspend, otherwise on sending such 'suspend' command, SDHC will regard the current transfer is aborted and change BLKATTR[BLKCNT] to its original value, instead of keeping the remained number of blocks.

# 50.7.4 Data length setting

For either ADMA (ADMA1 or ADMA2) transfer, the data in the data buffer must be word aligned, so the data length set in the descriptor must be times of 4.



# 50.7.5 (A)DMA address setting

To configure ADMA1/ADMA2/DMA address register, when TC[IRQSTAT] bit is set, the register will always update itself with the internal address value to support dynamic address synchronization, so software must make sure TC[IRQSTAT] bit is cleared prior to configuring ADMA1/ADMA2/DMA address register.

# 50.7.6 Data port access

Data port does not support parallel access. For example, during an external DMA access, it is not allowed to write any data to the data port by CPU; or during a CPU read operation, it is also prohibited to write any data to the data port, by either CPU or external DMA. Otherwise the data would be corrupted inside the SDHC buffer.

# 50.7.7 Change clock frequency

SDHC does not automatically gates off the card clock when the host driver changes the clock frequency. To remove possible glitch on the card clock, clear SYSCTL[SDCLKEN] bit when changing clock divisor value and set SYSCTL[SDCLKEN] bit to '1' after PRSSTAT[SDSTB] bit is '1' again.

## 50.7.8 Multi-block read

For pre-defined multi-block read operation, i.e., the number of blocks to read has been defined by previous CMD23 for MMC, or pre-defined number of blocks in CMD53 for SDIO/SDCombo, or whatever multi-block read without abort command at card side, an abort command, either automatic or manual CMD12/CMD52, is still required by SDHC after the pre-defined number of blocks are done, to drive the internal start response timeout. It is recommended to manually send an abort command with XFERTYP[RSPTYP] both bits cleared.



**SOLWARE restrictions** 



# **Chapter 51 Integrated interchip sound (I2S)**

## 51.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

This section discusses the architecture, the programming model, the operating modes, and initialization of integrated interchip sound (I<sup>2</sup>S) module.

The I<sup>2</sup>S is a full-duplex, serial port that allows the chip to communicate with a variety of serial devices. Such serial devices are:

- Standard codecs
- Digital signal processors (DSPs)
- Microprocessors
- Peripherals
- Audio codecs that implement the inter-IC sound bus (I<sup>2</sup>S) and the Intel<sup>®</sup> AC97 standards

The I<sup>2</sup>S module typically transfers samples in a periodic manner. The I<sup>2</sup>S consists of independent transmitter and receiver sections with independent clock generation and frame synchronization.



muroduction

# 51.1.1 Block diagram

The following figure illustrates the organization of the I<sup>2</sup>S. It consists of control registers to set up the port, status register, separate transmit and receive circuits with FIFO registers, and separate serial clock and frame sync generation for the transmit and receive sections. The second set of Tx and Rx FIFOs replicates the logic used for the first set of FIFOs.




Figure 51-1. Customer-facing I<sup>2</sup>S block diagram

# 51.1.2 Features

The I<sup>2</sup>S includes the following features:

- Independent (asynchronous) or shared (synchronous) transmit and receive sections with separate or shared internal/external clocks and frame syncs, operating in master or slave mode.
- Normal mode operation using frame sync



- Network mode operation allowing multiple devices to share the port with as many as thirty-two time slots
- Gated clock mode operation requiring no frame sync
- 2 sets of transmit and receive FIFOs. Each of the four FIFOs is 15x32 bits. The two sets of Tx/Rx FIFOs can be used in network mode to provide 2 independent channels for transmission and reception
- Programmable data interface modes such as I<sup>2</sup>S, lsb- and msb-aligned
- Programmable word length (8, 10, 12, 16, 18, 20, 22 or 24 bits)
- Program options for frame sync and clock generation
- Programmable I<sup>2</sup>S modes (master, slave or normal). Oversampling clock available as output from SRCK in I<sup>2</sup>S master mode
- AC97 support
- Completely separate clock and frame sync selections for the receive and transmit sections. In the AC97 standard, the clock is taken from an external source and frame sync is generated internally.
- External network clock input for I<sup>2</sup>S master mode. Programmable oversampling clock of the sampling frequency available as output in master mode at SRCK, when operated in synchronous mode.
- Programmable internal clock divider
- Transmit and receive time slot mask registers for reduced CPU overhead
- I<sup>2</sup>S power-down feature

# 51.1.3 Modes of operation

I<sup>2</sup>S has the following basic operating modes.

- Normal mode
  - Asynchronous protocol
  - Synchronous protocol
- Network mode



#### ınıroduction

- Asynchronous protocol
- Synchronous protocol
- Gated clock mode
  - Synchronous protocol only
- I<sup>2</sup>S mode
- AC97 mode
  - AC97 fixed mode (ACNT[FV] = 0)
  - AC97 variable mode (ACNT[FV] = 1)

These modes can be programmed by several bits in the I<sup>2</sup>S control registers. The following table lists these operating modes and some of the typical applications in which they can be used:

Serial clock TX, RX Sections Mode Typical application Asynchronous Continuous Normal Multiple synchronous CODECs Asynchronous Network TDM codec or DSP networks Continuous Synchronous Normal Multiple synchronous codecs Continuous Synchronous Continuous Network TDM codec or DSP network Synchronous Gated Normal SPI-type devices: DSP to MCU

Table 51-1. I<sup>2</sup>S Operating Modes

The transmit and receive sections of the I<sup>2</sup>S can be synchronous or asynchronous. In synchronous mode, the transmitter and the receiver use a common clock and frame synchronization signal. Masking of slots for transmit and receive section can differ in synchronous mode. Also the RCR[RXBIT0, RSHFD] bits can continue affecting shifting-in of received data in synchronous mode. In asynchronous mode, the transmitter and receiver each has its own clock and frame synchronization signals. Continuous or gated clock mode can be selected. In continuous mode, the clock runs continuously. In gated clock mode, the clock is only functioning during transmission.

Normal or network mode can also be selected. In normal mode, the I<sup>2</sup>S functions with one data word of I/O per frame. In network mode, any number from two to thirty-two data words of I/O per frame can be used. Network mode is typically used in star time-division-multiplex networks with other processors or codecs, allowing interface to time division multiplexed networks without additional logic. Use of gated clock mode is not allowed in network mode. These distinctions result in the basic operating modes that allow the I<sup>2</sup>S to communicate with a wide variety of devices.



The I<sup>2</sup>S supports both normal and network modes, and these can be selected independently of whether the transmitter and receiver are synchronous or asynchronous. Typically, these protocols are used in a periodic manner, where data transfers at regular intervals, such as at the sampling rate of an external codec. Both modes use the concept of a frame. The beginning of the frame is marked with a frame sync when programmed with continuous clock. The RCCR[DC] or TCCR[DC] bits determine the length of the frame, depending on whether data is being transmitted or received.

The number of words transferred per frame depends on the mode of the  $I^2S$ . In normal mode, one data word is transferred per frame. In network mode, the frame divides into two to 32 time slots. In each time slot, one data word is optionally transferred.

Apart from the above basic modes of operation, I<sup>2</sup>S supports the following modes which require some specific programming.

- I<sup>2</sup>S mode
- AC97 mode
  - AC97 fixed mode
  - AC97 variable mode

In non-I<sup>2</sup>S slave modes (external frame sync), the I<sup>2</sup>S's programmed word length setting should be equal to the word length setting of the master. In I<sup>2</sup>S slave mode, the I<sup>2</sup>S's programmed word length setting can be lesser than or equal to the word length setting of the I<sup>2</sup>S master (external codec).

In slave modes, the I<sup>2</sup>S's programmed frame length setting (TCCR[DC] or RCCR[DC] bits) can be lesser than or equal to the frame length setting of the master (external codec).

See Detailed operating mode descriptions for more details on the above modes.

# 51.2 I<sup>2</sup>S signal descriptions

Table 51-2. I<sup>2</sup>S signal descriptions

Signal	Description	I/O
SRCK	Serial receive clock. SRCK can be used as an input or output.	I/O
	<ul> <li>In asynchronous mode the receiver uses this clock signal and it is always continuous.</li> </ul>	
	<ul> <li>In synchronous mode, the STCK port is used instead for clocking in data.</li> </ul>	



#### ເ∠ວ signal descriptions

Table 51-2. I<sup>2</sup>S signal descriptions (continued)


Signal	Description	I/O
SRFS	Serial receive frame Sync. The SRFS port can be used as an input or output. The frame sync is used by the receiver to synchronize the transfer of data. The frame sync signal can be one bit or one word in length and can occur one bit before the transfer of data or right at the transfer of data. If SRFS is configured as an input, the external device should drive SRFS during the rising edge of STCK or SRCK.	I/O
SRXD	Serial receive data. The SRXD port is an input and is used to bring serial data into the receive data shift register.	I
STCK	Serial transmit clock. The STCK port can be used as an input or output. This clock signal is used by the transmitter and can be continuous or gated. During gated clock mode, data on STCK is valid only during the transmission of data. Otherwise, it is pulled to the inactive state. In synchronous mode, this port is used by the transmit and receive sections.	I/O
STFS	Serial transmit frame sync. The STFS port can be used as an input or output. The frame sync is used by the transmitter to synchronize the transfer of data. The frame sync signal can be one bit or one word in length and can occur one bit before the transfer of data or right at the transfer of data. In synchronous mode, this port is used by both the transmit and receive sections. In gated clock mode, frame sync signals are not used. If STFS is configured as an input, the external device should drive STFS during the rising edge of STCK if TSCKP is positive-edge triggered. The external device should drive STFS during the falling edge of STCK if TSCKP is negative-edge triggered.	I/O
STXD	Serial transmit data. The STXD port is an output and transmits data from the serial transmit shift register. The STXD port is an output port when data is being transmitted and is disabled between data word transmissions and on the trailing edge of the bit clock after the last bit of a word is transmitted.	0

The following figure shows the main I<sup>2</sup>S configurations. These ports support all transmit and receive functions with continuous or gated clock as shown.


## **Note**

Gated clock implementations do not require the use of the frame sync ports (STFS and SRFS).






I2S internal continuous clock for TX/RX (RCR[RXDIR] = 1,TCR[TXDIR] = 1, RCR[RFDIR] = 1,TCR[TFDIR] = 1, CR[SYN] = 0)




I2S external continuous clock for TX/RX (RCR[RXDIR] = 0,TCR[TXDIR] = 0, RCR[RFDIR] = 0,TCR[TFDIR] = 0, CR[SYN] = 0)



I2S internal continuous clock for RX (RCR[RXDIR] = 1, TCR[TXDIR] = 0, RCR[RFDIR] = 1, TCR[TFDIR] = 0, CR[SYN] = 0)

I2S external continuous clock for TX



I2S internal continuous clock for TX (RCR[RXDIR] = 0, TCR[TXDIR] = 1, RCR[RFDIR] = 0, TCR[TFDIR] = 1, CR[SYN] = 0)

I2S external continuous clock for RX

Figure 51-2. Asynchronous (SYN = 0)  $I^2S$  configurations—continuous clock

The following figure shows an example of the port signals for an 8-bit data transfer. Continuous and gated clock signals are shown, as well as the bit-length frame sync signal and the word-length frame sync signal.



#### ı∠ə signal descriptions




Figure 51-3. Serial clock and frame sync timing

The following table shows a list of clock pin configurations.

Table 51-3. Clock pin configurations

CR	RO	CR	TO	CR		CDCK	CTOV	CDEC	CTEC			
[SYN]	RXDIR	RFDIR	TXDIR	TFDIR		SRCK	STCK	SRFS	STFS			
	Asynchronous Mode											
0	0	0	0	0		RCK in	TCK in	RFS in	TFS in			
0	0	0	0	1		RCK in	TCK in	RFS in	TFS out			
0	0	1	0	0		RCK in	TCK in	RFS out	TFS in			
0	0	1	0	1		RCK in	TCK in	RFS out	TFS out			
0	0	0	1	0		RCK in	TCK out	RFS in	TFS in			
0	0	0	1	1		RCK in	TCK out	RFS in	TFS out			
0	0	1	1	0		RCK in	TCK out	RFS out	TFS in			
0	0	1	1	1		RCK in	TCK out	RFS out	TFS out			
0	1	0	0	0		RCK out	TCK in	RFS in	TFS in			
0	1	0	0	1		RCK out	TCK in	RFS in	TFS out			
0	1	1	0	0		RCK out	TCK in	RFS out	TFS in			
0	1	1	0	1		RCK out	TCK in	RFS out	TFS out			



Table 51-3. Clock pin configurations (continued)

CR	R	CR	TO	CR	SRCK	STCK	SRFS	STFS
[SYN]	RXDIR	RFDIR	TXDIR	TFDIR	Shok	SICK	Shra	3173
0	1	0	1	0	RCK out	TCK out	RFS in	TFS in
0	1	0	1	1	RCK out	TCK out	RFS in	TFS out
0	1	1	1	0	RCK out	TCK out	RFS out	TFS in
0	1	1	1	1	RCK out	TCK out	RFS out	TFS out
					Synchronous me	ode		
1	0	х	0	0	_	CK in	_	FS in
1	0	х	0	1	_	CK in	_	FS out
1	0	х	1	0	_	CK out	_	FS in
1	0	х	1	1	_	CK out	_	FS out
1	1	х	0	х	_	Gated in	_	_
1	1	х	1	х	_	Gated out	_	_

# 51.3 Memory map/register definition

This section consists of register descriptions in address order. Each description includes a standard register diagram with an associated figure number. Details of register bit and field function follow the register diagrams in bit order.

## I2S memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4002_F000	I2S Transmit Data Registers 0 (I2S0_TX0)	32	R/W	0000_0000h	51.3.1/ 1441
4002_F004	I2S Transmit Data Registers 1 (I2S0_TX1)	32	R/W	0000_0000h	51.3.2/ 1441
4002_F008	I2S Receive Data Registers 0 (I2S0_RX0)	32	R	0000_0000h	51.3.3/ 1442
4002_F00C	I2S Receive Data Registers 1 (I2S0_RX1)	32	R	0000_0000h	51.3.4/ 1442
4002_F010	I2S Control Register (I2S0_CR)	32	R/W	0000_0000h	51.3.5/ 1443
4002_F014	I2S Interrupt Status Register (I2S0_ISR)	32	R/W	0000_3003h	51.3.6/ 1446



## wemory map/register definition

# I2S memory map (continued)


Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4002_F018	I2S Interrupt Enable Register (I2S0_IER)	32	R/W	0000_3003h	51.3.7/ 1451
4002_F01C	I2S Transmit Configuration Register (I2S0_TCR)	32	R/W	0000_0200h	51.3.8/ 1455
4002_F020	I2S Receive Configuration Register (I2S0_RCR)	32	R/W	0000_0200h	51.3.9/ 1457
4002_F024	I2S Transmit Clock Control Registers (I2S0_TCCR)	32	R/W	0004_0000h	51.3.10/ 1459
4002_F028	I2S Receive Clock Control Registers (I2S0_RCCR)	32	R/W	0004_0000h	51.3.11/ 1461
4002_F02C	I2S FIFO Control/Status Register (I2S0_FCSR)	32	R/W	0081_0081h	51.3.12/ 1462
4002_F038	I2S AC97 Control Register (I2S0_ACNT)	32	R/W	0000_0000h	51.3.13/ 1468
4002_F03C	I2S AC97 Command Address Register (I2S0_ACADD)	32	R/W	0000_0000h	51.3.14/ 1469
4002_F040	I2S AC97 Command Data Register (I2S0_ACDAT)	32	R/W	0000_0000h	51.3.15/ 1470
4002_F044	I2S AC97 Tag Register (I2S0_ATAG)	32	R/W	0000_0000h	51.3.16/ 1470
4002_F048	I2S Transmit Time Slot Mask Register (I2S0_TMSK)	32	R/W	0000_0000h	51.3.17/ 1471
4002_F04C	I2S Receive Time Slot Mask Register (I2S0_RMSK)	32	R/W	0000_0000h	51.3.18/ 1471
4002_F050	I2S AC97 Channel Status Register (I2S0_ACCST)	32	R	0000_0000h	51.3.19/ 1472
4002_F054	I2S AC97 Channel Enable Register (I2S0_ACCEN)	32	W (always reads zero)	0000_0000h	51.3.20/ 1472
4002_F058	I2S AC97 Channel Disable Register (I2S0_ACCDIS)	32	W (always reads zero)	0000_0000h	51.3.21/ 1473



## 51.3.1 I<sup>2</sup>S Transmit Data Registers 0 (I2Sx\_TX0)

The TX0 registers store the data to be transmitted by the I2S.

Addresses: I2S0\_TX0 is 4002\_F000h base + 0h offset = 4002\_F000h




#### I2Sx\_TX0 field descriptions

Field	Description
31–0 TX0	I2S transmit data. These bits store the data to be transmitted by the I2S. These are implemented as the first word of their respective Tx FIFOs. Data written to these registers transfers to the transmit shift register (TXSR), when shifting of the previous data is complete. If both FIFOs are in use, data alternately transfers from TX0 and TX1 to TXSR. TX1 can only be used in two-channel mode. Multiple writes to the TX registers do not result in the previous data being over-written by the subsequent data. Instead they are ignored. Protection from over-writing is present irrespective of whether the transmitter is enabled or not. Example: If Tx FIFO0 is in use and you write Data1 - 16 to TX0, Data16 does not overwrite Data1. Data1 - 15 are stored in the FIFO while Data16 is discarded. Example: If Tx FIFO0 is not in use and you write Data1, Data2 to TX0, then Data2 does not overwrite Data1 and is discarded.  NOTE: Enable I2S (CR[I2SEN]=1) before writing to the I2S transmit data registers.

## 51.3.2 I<sup>2</sup>S Transmit Data Registers 1 (I2Sx\_TX1)

The TX1 registers store the data to be transmitted by the I2S.

Addresses: I2S0\_TX1 is 4002\_F000h base + 4h offset = 4002\_F004h



### I2Sx\_TX1 field descriptions

Field	Description
31–0 TX1	I2S transmit data. These bits store the data to be transmitted by the I2S. These are implemented as the first word of their respective Tx FIFOs. Data written to these registers transfers to the transmit shift register (TXSR), when shifting of the previous data is complete. If both FIFOs are in use, data alternately transfers from TX0 and TX1 to TXSR. TX1 can only be used in two-channel mode. Multiple writes to the TX registers do not result in the previous data being over-written by the subsequent data. Instead they are
	ignored. Protection from over-writing is present irrespective of whether the transmitter is enabled or not.




### I2Sx\_TX1 field descriptions (continued)

Field	Description
	Example: If Tx FIFO0 is in use and you write Data1 - 16 to TX0, Data16 does not overwrite Data1. Data1 -
	15 are stored in the FIFO while Data16 is discarded. Example: If Tx FIFO0 is not in use and you write Data1, Data2 to TX0, then Data2 does not overwrite Data1 and is discarded.
	<b>NOTE:</b> Enable I <sup>2</sup> S (CR[I2SEN]=1) before writing to the I <sup>2</sup> S transmit data registers.

## 51.3.3 I<sup>2</sup>S Receive Data Registers 0 (I2Sx\_RX0)

The RX0 registers store the data received by the I2S.

Addresses: I2S0\_RX0 is 4002\_F000h base + 8h offset = 4002\_F008h




### I2Sx\_RX0 field descriptions

Field	Description
31–0 RX0	I2S Receive Data  These bits store the data received by the I <sup>2</sup> S. These are implemented as the first word of their respective Rx FIFOs. These bits receive data from the RXSR depending on the mode of operation. In case both FIFOs are in use, data is transferred to each data register alternately. RX1 can only be used in two-channel mode of operation.

# 51.3.4 I<sup>2</sup>S Receive Data Registers 1 (I2Sx\_RX1)

The RX1 registers store the data received by the I2S.

Addresses: I2S0\_RX1 is 4002\_F000h base + Ch offset = 4002\_F00Ch



### I2Sx\_RX1 field descriptions

Field	Description
31–0 RX1	I2S Receive Data
	These bits store the data received by the I <sup>2</sup> S. These are implemented as the first word of their respective Rx FIFOs. These bits receive data from the RXSR depending on the mode of operation. In case both

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011





### I2Sx\_RX1 field descriptions (continued)

Field	Description
	FIFOs are in use, data is transferred to each data register alternately. RX1 can only be used in two-channel mode of operation.

# 51.3.5 I<sup>2</sup>S Control Register (I2Sx\_CR)

The I2S Control Register (CR) sets up the I2S. I2S reset is controlled by bit 0 in the CR. I2S operating modes are also selected in this register (except AC97 mode which is selected in the ACNT register).





### I2Sx\_CR field descriptions

Field	Description
31–13 Reserved	This read-only field is reserved and always has the value zero.
12 SYNCTXFS	SYNCTXFS bit provides a safe window for CR[TE] to be visible to the internal circuit which is just after FS occurrence. When SYNCTXFS is set, CR[TE] gets latched on FS occurrence and latched CR[TE] is used to enable/disable I <sup>2</sup> S transmitter. CR[TE] needs setup of 2 bit-clock cycles before occurrence of FS. If CR[TE] is changed within 2 bit-clock cycles of FS occurrence, there is high probability that CR[TE] will be latched on next FS.  NOTE: With TFRCLKDIS feature on, CR[TE] is used directly to enable transmitter in following cases (i)
	Sync mode and Rx disabled (ii) Async Mode. Latched-TE is used to disable the transmitter.  This bit has no relevance in gated mode and AC97 mode.  CR[TE] not latched with FS occurrence and used directly for transmitter enable/disable.  CR[TE] latched with FS occurrence and latched-TE used for transmitter enable/disable.
11 RFRCLKDIS	Receive Frame Clock Disable.



## I2Sx\_CR field descriptions (continued)

Field	Description
	This bit provides the option to keep the frame-sync and clock enabled or to disable them after the receive frame in which the receiver is disabled. Writing to this bit has effect only when CR[RE] is disabled. The receiver is disabled by clearing the CR[RE] bit.
	<ul> <li>Continue frame-sync/clock generation after current frame during which CR[RE] is cleared. This may be required when Frame-sync and Clocks are required from I<sup>2</sup>S, even when no data is to be received</li> <li>Stop frame-sync/clock generation at next frame boundary. This will be effective also in case where receiver is already disabled in current or previous frames.</li> </ul>
10	Transmit Frame Clock Disable.
TFRCLKDIS	This bit provide option to keep the frame-sync and clock enabled or disabled after current transmit frame, in which transmitter is disabled by clearing CR[TE] bit. Writing to this bit has effect only when I <sup>2</sup> S is enabled CR[TE] is disabled.
	<ul> <li>Continue frame-sync/clock generation after current frame during which CR[TE] is cleared. This may be required when frame-sync and clocks are required from I<sup>2</sup>S, even when no data is to be received.</li> <li>Stop frame-sync/clock generation at next frame boundary. This will be effective also in case where transmitter is already disabled in current or previous frames.</li> </ul>
9	Clock Idle State.
CLKIST	This bit controls the idle state of the transmit clock port during I <sup>2</sup> S internal gated mode. Note: When Clock idle state is `1' the clock polarity should always be negedge triggered and when clock idle = `0' the clock polarity should always be positive edge triggered.
	<ul><li>0 Clock idle state is `0'.</li><li>1 Clock idle state is `1'.</li></ul>
8 TCHEN	Two-Channel Operation Enable.
IGHEN	This bit allows I <sup>2</sup> S to operate in the two-channel mode.In this mode while receiving, the RXSR transfers data to RX0 and RX1 alternately and while transmitting, data is alternately transferred from TX0 and TX1 to TXSR. For an even number of slots, two-channel operation can be enabled to optimize usage of both FIFOs or disabled as in the case of odd number of active slots. This feature is especially useful in I2S mode, where data for left speaker can be placed in Tx-FIFO0 and for right speaker in Tx-FIFO1.
	<ul><li>0 Two-channel mode disabled.</li><li>1 Two-channel mode enabled.</li></ul>
7	System Clock (Oversampling Clock) Enable.
SYSCLKEN	When set, this bit allows the I <sup>2</sup> S to output the (network clock) at the SRCK port, provided that synchronous mode, and transmit internal clock mode are set. The relationship between bit clock and network clock is determined by DIV2, PSR, and PM bits. This feature is especially useful in I2S master mode to output oversampling clock on SRCK port.
	<ul><li>Network clock not output on SRCK port.</li><li>Network clock output on SRCK port.</li></ul>
6–5 I2SMODE	I2S Mode Select
IZGIVIODE	These bits allow the I <sup>2</sup> S to operate in normal, I <sup>2</sup> S master or I <sup>2</sup> S slave mode.
	00 Normal mode 01 I <sup>2</sup> S master mode



## I2Sx\_CR field descriptions (continued)

Field	Description
	10 I <sup>2</sup> S slave mode
	11 Normal mode
4 SYN	Synchronous Mode.
	This bit controls whether I <sup>2</sup> S is in synchronous mode or not. In synchronous mode, the transmit and receive sections of I <sup>2</sup> S share a common clock port (STCK) and frame sync port (STFS).
	0 Asynchronous mode selected.
	1 Synchronous mode selected.
3 NET	Network Mode.
INE I	This bit controls whether I <sup>2</sup> S is in network mode or not.
	0 Network mode not selected.
	1 Network mode selected.
2	Receive Enable.
RE	Enables the receive section of the I <sup>2</sup> S. When this bit is enabled, data reception starts with the arrival of the next frame sync. If data is being received when this bit is cleared, data reception continues until the end of the current frame and then stops. If this bit is set again before the second to last bit of the last tin slot in the current frame, then reception continues without interruption. CR[RE] should not be toggled in the same frame.
	Receive section disabled.
	1 Receive section enabled.
1	Transmit Enable.
TE	This control bit enables the transmit section of the I <sup>2</sup> S. It enables the transfer of the contents of the TX registers to the TXSR and also enables the internal transmit clock. The transmit section is enabled whe this bit is set and a frame boundary is detected. When this bit is cleared, the transmitter continues to se data until the end of the current frame and then stops. Data can be written to the TX registers with the CR[TE] bit cleared (the corresponding TDE bit will be cleared). If the CR[TE] bit is cleared and then set again before the second to last bit of the last time slot in the current frame, data transmission continues without interruption. The normal transmit enable sequence is to write data to the TX register(s) and ther set the CR[TE] bit. The normal disable sequence is to clear the CR[TE] and IER[TIE] bits after the TDE is set.
	In gated clock mode, clearing the CR[TE] bit results in the clock stopping after the data currently in TXS has shifted out. When the CR[TE] bit is set, the clock starts immediately (for internal gated clock mode) CR[TE] should not be toggled in the same frame.
	After enabling/disabling transmission, I <sup>2</sup> S expects 4 setup clock cycles before arrival of frame-sync for frame-sync to be accepted by I <sup>2</sup> S. In case of fewer clock cycles, there is high probability of the frame-sy to get missed.
	<b>NOTE:</b> If continuos clock is not provided, I <sup>2</sup> S expects 6 clock cycles before arrival of frame-sync for frame-sync to be accepted by I <sup>2</sup> S.
	0 Transmit section disabled.
	1 Transmit section enabled.
0	I2S Enable.
I2SEN	

#### I2Sx\_CR field descriptions (continued)

Field	Description
	This bit is used to enable/disable the I <sup>2</sup> S. When disabled, all I <sup>2</sup> S status bits are preset to the same state produced by the power-on reset, all control bits are unaffected, the contents of Tx and Rx FIFOs are cleared. When I <sup>2</sup> S is disabled, all internal clocks are disabled (except register access clock).
	<ul> <li>0 I<sup>2</sup>S is disabled.</li> <li>1 I<sup>2</sup>S is enabled.</li> </ul>


## 51.3.6 I<sup>2</sup>S Interrupt Status Register (I2Sx\_ISR)

The I2S interrupt status register (ISR) is used to monitor the I2S. This register is used by the core to interrogate the status of the I2S. In gated mode of operation the TFS, RFS, TLS, RLS, TFRC and RFRC bits of AISR register are not generated. The status bits are described in the following table.

#### NOTE

- I<sup>2</sup>S status flags are valid when I<sup>2</sup>S is enabled.
- All the flags in the ISR are updated after the first bit of the next I<sup>2</sup>S word has completed transmission or reception. Certain status bits (ROE0/1 and TUE0/1) are cleared by writing 1 to the corresponding interrupt status bit in ISR.

Addresses: I2S0\_ISR is 4002\_F000h base + 14h offset = 4002\_F014h





## I2Sx\_ISR field descriptions

Field	Description
31–25 Reserved	This read-only field is reserved and always has the value zero.
24 RFRC	Receive Frame Complete.  This flag is set at the end of the frame during which receiver is disabled. If receive frame and clock are not disabled in the same frame, this flag is also set at the end of the frame in which receive frame and clock are disabled. See description of CR[RFRCLKDIS] bit for more details on how to disable receiver frame and clock or keep them enabled after receiver is disabled.  0 End of frame not reached.  1 End of frame reached after disabling CR[RE] or disabling CR[RFRCLKDIS], when receiver is already disabled.
23 TRFC	Transmit Frame Complete.  This flag is set at the end of the frame during which transmitter is disabled. If transmit frame and clock are not disabled in the same frame, this flag is also set at the end of the frame in which transmit frame and clock are disabled. See description of CR[TFRCLKDIS] bit for more details on how to disable transmit frame and clock or keep them enabled after transmitter is disabled.  0 End of frame not reached.  1 End of frame reached after disabling CR[TE] or disabling CR[TFRCLKDIS], when transmitter is already disabled.
22–19 Reserved	This read-only field is reserved and always has the value zero.
18 CMDAU	Command Address Register Updated.  This bit causes the command address Updated interrupt (when IER[CMDAUEN] bit is set). This status bit is set each time there is a difference in the previous and current value of the received command address. This bit is cleared on reading the ACADD register.  O No change in ACADD register.  ACADD register updated with different value.
17 CMDDU	Command Data Register Updated.  This bit causes the command data updated interrupt (when IER[CMDDUEN] bit is set). This status bit is set each time there is a difference in the previous and current value of the received command data. This bit is cleared on reading the ACDAT register.  No change in ACDAT register.  ACDAT register updated with different value.
16 RXT	Receive Tag Updated.  This status bit is set each time there is a difference in the previous and current value of the received tag. It causes the receive tag interrupt (if IER[RXTEN] bit is set). This bit is cleared on reading the ATAG register.  O No change in ATAG register.  ATAG register updated with different value.
15 RDR1	Receive Data Ready 1.



## I2Sx\_ISR field descriptions (continued)

Field	Description
	This flag bit is set when RX1 or Rx FIFO 1 is loaded with a new value and two-channel mode is selected. RDR1 is cleared when the core reads the RX1 register. If Rx FIFO 1 is enabled, RDR1 is cleared when the FIFO is empty. If IER[RIE] and IER[RDR1EN] are set, a receive data 1 interrupt request is issued on setting of RDR1 bit in case Rx FIFO1 is disabled, if the FIFO is enabled, the interrupt is issued on RFF1 assertion. The RDR1 bit is cleared by POR and I <sup>2</sup> S reset.
	<ul><li>0 No new data for core to read.</li><li>1 New data for core to read.</li></ul>
14	Receive Data Ready 0.
RDR0	This flag bit is set when RX0 or Rx FIFO 0 is loaded with a new value. RDR0 is cleared when the core reads the RX0 register. If Rx FIFO 0 is enabled, RDR0 is cleared when the FIFO is empty. If IER[RIE] and IER[RDR0EN] are set, a receive data 0 interrupt request is issued on setting of RDR0 bit in case Rx FIFO0 is disabled, if the FIFO is enabled, the interrupt is issued on RFF0 assertion. The RDR0 bit is cleared by POR and I <sup>2</sup> S reset.
	0 No new data for core to read.
	1 New data for core to read.
13 TDE1	Transmit Data Register Empty 1.
IDEI	This flag is set whenever data is transferred to TXSR from TX1 register and two-channel mode is selected. If Tx FIFO1 is enabled, this occurs when there is at least one empty slot in TX1 or Tx FIFO1. If Tx FIFO1 is not enabled, this occurs when the contents of TX1 are transferred to TXSR.
	The TDE1 bit is cleared when the core writes to TX1. If IER[TIE] and IER[TDE1EN] are set, an I <sup>2</sup> S transmit data 1 interrupt request is issued on setting of TDE1 bit. The TDE1 bit is cleared by POR and I <sup>2</sup> S reset.
	<ul> <li>Data available for transmission.</li> <li>Data needs to be written by the core for transmission.</li> </ul>
12	Transmit Data Register Empty 0.
TDE0	This flag is set whenever data is transferred to TXSR from TX0 register. If Tx FIFO 0 is enabled, this occurs when there is at least one empty slot in TX0 or Tx FIFO 0. If Tx FIFO 0 is not enabled, this occurs when the contents of TX0 are transferred to TXSR. The TDE0 bit is cleared when the core writes to TX0. If IER[TIE] and TIE[TDE0EN] are set, an I <sup>2</sup> S transmit data 0 interrupt request is issued on setting of TDE0 bit. The TDE0 bit is cleared by POR and I <sup>2</sup> S reset.
	0 Data available for transmission.
	1 Data needs to be written by the core for transmission.
11 ROE1	Receiver Overrun Error 1.
HUE1	This flag is set when the RXSR is filled and ready to transfer to RX1 register or to Rx FIFO 1 (when enabled) and these are already full and Two-Channel mode is selected. If Rx FIFO 1 is enabled, this is indicated by RFF1 flag, else this is indicated by the RDR1 flag. The RXSR is not transferred in this case. The ROE1 flag causes an interrupt if IER[RIE] and IER[ROE1EN] are set.
	The ROE1 bit is cleared by POR and I <sup>2</sup> S reset. It is also cleared by writing `1' to this bit. Clearing the CR[RE] bit does not affect the ROE1 bit.
	0 No overrun detected
	1 Receiver overrun error occurred
10 ROE0	Receiver Overrun Error 0.



## I2Sx\_ISR field descriptions (continued)

Field	Description
	This flag is set when the RXSR is filled and ready to transfer to RX0 register or to Rx FIFO 0 (when enabled) and these are already full. If Rx FIFO 0 is enabled, this is indicated by RFF0 flag, else this is indicated by the RDR0 flag. The RXSR is not transferred in this case. The ROE0 flag causes an interrupt if IER[RIE] and IER[ROE0EN] are set.
	The ROE0 bit is cleared by POR and $I^2S$ reset. It is also cleared by writing `1' to this bit. Clearing the CR[RE] bit does not affect the ROE0 bit.
	<ul><li>No overrun detected</li><li>Receiver overrun error occurred</li></ul>
9	Transmitter Underrun Error 1.
TUE1	This flag is set when the TXSR is empty (no data to be transmitted), the TDE1 flag is set, a transmit time slot occurs and the I <sup>2</sup> S is in two-channel mode. When a transmit underrun error occurs, the previous data is retransmitted. In Network mode, each time slot requires data transmission (unless masked through TMSK register), when the transmitter is enabled (CR[TE] is set).
	The TUE1 flag causes an interrupt if IER[TIE] and IER[TUE1EN] are set.
	The TUE1 bit is cleared by POR and I <sup>2</sup> S reset. It is also cleared by writing `1' to this bit.
	No underrun detected     Transmitter underrun error occurred
8	Transmitter Underrun Error 1.
TUE0	This flag is set when the TXSR is empty (no data to be transmitted), the TDE0 flag is set and a transmit time slot occurs. When a transmit underrun error occurs, the previous data is retransmitted. In Network mode, each time slot requires data transmission (unless masked through TMSK register), when the transmitter is enabled (CR[TE] is set). The TUE0 flag causes an interrupt if IER[TIE] and IER[TUE0EN] are set.
	The TUE0 bit is cleared by POR and I <sup>2</sup> S reset. It is also cleared by writing `1' to this bit.
	0 No underrun detected
	1 Transmitter underrun error occurred
7	Transmit Frame Sync.
TFS	This flag indicates the occurrence of transmit frame sync. Data written to the TX registers during the time slot when the TFS flag is set, is sent during the second time slot (in network mode) or in the next first time slot (in normal mode). In network mode, the TFS bit is set during transmission of the first time slot of the frame and is then cleared when starting transmission of the next time slot. In normal mode, this bit is high for the first time slot. This flag causes an interrupt if IER[TIE] and IER[TFSEN] are set. The TFS bit is cleared by POR and I <sup>2</sup> S reset.
	0 No occurrence of transmit frame sync.
	1 Transmit frame sync occurred during transmission of last word written to TX registers.
6 RFS	Receive Frame Sync.
111 3	This flag indicates the occurrence of receive frame sync. In network mode, the RFS bit is set when the first slot of the frame is being received. It is cleared when the next slot begins to be received. In normal mode, this bit is always high. This flag causes an interrupt if IER[RIE] and IER[RFSEN] are set. The RFS bit is cleared by POR and I <sup>2</sup> S reset.
	0 No occurrence of receive frame sync.
	1 Receive frame sync occurred during reception of next word in RX registers.



## I2Sx\_ISR field descriptions (continued)

Field	Description
5	Transmit Last Time Slot.
TLS	This flag indicates the last time slot in a frame. When set, it indicates that the current time slot is the last time slot of the frame. TLS is set at the start of the last transmit time slot and causes the I <sup>2</sup> S to issue an interrupt (if IER[TIE] and TLSEN are set). TLS is not generated when frame rate is 1 in normal mode of operation. TLS is cleared when the ISR is read with this bit set. The TLS bit is cleared by POR and I <sup>2</sup> S reset.  O Current time slot is not last time slot of frame.
	1 Current time slot is the last transmit time slot of frame.
4 RLS	Receive Last Time Slot.
	This flag indicates the last time slot in a frame. When set, it indicates that the current time slot is the last receive time slot of the frame. RLS is set at the end of the last time slot and causes the I <sup>2</sup> S to issue an interrupt (if IER[RIE] and IER[RLSEN] are set). RLS is cleared when the ISR is read with this bit set. The RLS bit is cleared by POR and I <sup>2</sup> S reset.
	0 Current time slot is not last time slot of frame.
	1 Current time slot is the last receive time slot of frame.
3 RFF1	Receive FIFO Full 1.
TUTT	This flag is set when Rx FIFO1 is enabled, the data level in Rx FIFO1 reaches the selected Rx FIFO WaterMark 1 (RFWM1) threshold and the I <sup>2</sup> S is in two-channel mode. The setting of RFF1 only causes an interrupt when IER[RIE] and IER[RFF1EN] are set, Rx FIFO1 is enabled and the two-channel mode is selected. RFF1 is automatically cleared when the amount of data in Rx FIFO1 falls below the threshold. The RFF1 bit is cleared by POR and I <sup>2</sup> S reset.
	When Rx FIFO1 contains 15 words, the maximum it can hold, all further data received (for storage in this FIFO) is ignored until the FIFO contents are read.
	Space available in receive FIFO1.     Receive FIFO1 is full.
2	Receive FIFO Full 0.
RFF0	This flag is set when Rx FIFO0 is enabled and the data level in Rx FIFO0 reaches the selected Rx FIFO WaterMark 0 (RFWM0) threshold. The setting of RFF0 only causes an interrupt when IER[RIE] and IER[RFF0EN] are set and Rx FIFO0 is enabled. RFF0 is automatically cleared when the amount of data in Rx FIFO0 falls below the threshold. The RFF0 bit is cleared by POR and I <sup>2</sup> S reset.
	When Rx FIFO0 contains 15 words, the maximum it can hold, all further data received (for storage in this FIFO) is ignored until the FIFO contents are read.
	Space available in receive FIFO0.     Receive FIFO0 is full.
1	Transmit FIFO Empty 1.
TFE1	This flag is set when the empty slots in Tx FIFO exceed or are equal to the selected Tx FIFO WaterMark 1 (TFWM1) threshold and the two-channel mode is selected. The setting of TFE1 only causes an interrupt when IER[TIE] and IER[TFE1EN] are set, Tx FIFO1 is enabled and two-channel mode is selected. The TFE1 bit is automatically cleared when the data level in Tx FIFO1 becomes more than the amount specified by the watermark bits. The TFE1 bit is set by POR and I <sup>2</sup> S reset.
	0 Transmit FIFO1 has data for transmission.
	1 Transmit FIFO1 is empty.




### I2Sx\_ISR field descriptions (continued)

Field	Description
0 TFE0	Transmit FIFO Empty 0.
	This flag is set when the empty slots in Tx FIFO exceed or are equal to the selected Tx FIFO WaterMark 0 (TFWM0) threshold. The setting of TFE0 only causes an interrupt when IER[TIE] and IER[TFE0EN] are set and Tx FIFO0 is enabled. The TFE0 bit is automatically cleared when the data level in Tx FIFO0 becomes more than the amount specified by the watermark bits. The TFE0 bit is set by POR and I <sup>2</sup> S reset.
	<ul><li>Transmit FIFO0 has data for transmission.</li><li>Transmit FIFO0 is empty.</li></ul>

# 51.3.7 I<sup>2</sup>S Interrupt Enable Register (I2Sx\_IER)

The I2S interrupt enable register (IER) is a 25-bit register used to set up the I2S interrupts and DMA requests.





### I2Sx\_IER field descriptions

Field	Description
31–25 Reserved	This read-only field is reserved and always has the value zero.
24 RFRC_EN	Enable Bit.  Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.  O Corresponding status bit cannot issue interrupt.  1 Corresponding status bit can issue interrupt.
23 TFRC_EN	Enable Bit.  Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## I2Sx\_IER field descriptions (continued)

Field	Description
	Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
22 RDMAE	Receive DMA Enable.
HOWAL	This bit allows I <sup>2</sup> S to request for DMA transfers. When enabled, DMA requests are generated when any of the RFF0/1 bits in the ISR are set and if the corresponding RFEN bit is also set. If the corresponding FIFO is disabled, a DMA request is generated when the corresponding RDR bit is set.
	<ul> <li>0 I<sup>2</sup>S receiver DMA requests disabled.</li> <li>1 I<sup>2</sup>S receiver DMA requests enabled.</li> </ul>
21	Receive Interrupt Enable.
RIE	This control bit allows the I <sup>2</sup> S to issue receiver related interrupts to the core.
	0 I <sup>2</sup> S receiver interrupt requests disabled.
	1 I <sup>2</sup> S receiver interrupt requests enabled.
20 TDMAE	Transmit DMA Enable.
IDIVIAE	This bit allows I <sup>2</sup> S to request for DMA transfers. When enabled, DMA requests are generated when any of the ISR[TFE0/1] bits are set and if the corresponding TCR[TFEN] bit is also set. If the corresponding FIFO is disabled, a DMA request is generated when the corresponding TDE bit is set.
	<ul> <li>0 I<sup>2</sup>S transmitter DMA requests disabled.</li> <li>1 I<sup>2</sup>S transmitter DMA requests enabled.</li> </ul>
19	Transmit Interrupt Enable.
TIE	This control bit allows the I <sup>2</sup> S to issue transmitter data related interrupts to the core.
	0 I <sup>2</sup> S transmitter interrupt requests disabled.
	1 I <sup>2</sup> S transmitter interrupt requests enabled.
18 CMDAUEN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
17 CMDDUEN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	<ul><li>Corresponding status bit cannot issue interrupt.</li><li>Corresponding status bit can issue interrupt.</li></ul>
16 RXTEN	Enable Bit.
TOOLET .	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
15 RDR1EN	Enable Bit.



## I2Sx\_IER field descriptions (continued)

Field	Description
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
14	Enable Bit.
RDR0EN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
13 TDE1EN	Enable Bit.
IDETEN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
12 TDE0EN	Enable Bit.
TDE0EN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
11 ROE1EN	Enable Bit.
HOLILIN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	O Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
10 ROE0EN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
9	Enable Bit.
TUE1EN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
8 TUE0EN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
7 TFSEN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.



## I2Sx\_IER field descriptions (continued)


Field	Description
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
6	Enable Bit.
RFSEN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
5	Enable Bit.
TLSEN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
4 RLSEN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
3 RFF1EN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
2 RFF0EN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
1 TFE1EN	Enable Bit.
	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.
0	Enable Bit.
TFE0EN	Each bit controls whether the corresponding status bit in ISR can issue an interrupt to the core or not.
	0 Corresponding status bit cannot issue interrupt.
	1 Corresponding status bit can issue interrupt.



### 51.3.8 I<sup>2</sup>S Transmit Configuration Register (I2Sx\_TCR)

The TCR directs the transmit operation of the I2S. A power-on reset clears all TCR bits. However, I2S reset does not affect the TCR bits.

Addresses: I2S0\_TCR is 4002\_F000h base + 1Ch offset = 4002\_F01Ch



### I2Sx\_TCR field descriptions

Field	Description
31–10 Reserved	This read-only field is reserved and always has the value zero.
9 TXBIT0	Transmit Bit 0.
	This control bit allows I <sup>2</sup> S to transmit the data word from bit position 0 or 15/31 in the transmit shift register. The shifting data direction can be MSB or LSB first, controlled by the TCR[TSHFD] bit.
	<ul> <li>Shifting with respect to bit 31 (if word length = 16, 18, 20, 22 or 24) or bit 15 (if word length = 8, 10 or 12) of transmit shift register (MSB aligned).</li> <li>Shifting with respect to bit 0 of transmit shift register (LSB aligned).</li> </ul>
8	Transmit FIFO Enable 1.
TFEN1	This bit enables transmit FIFO 1. When enabled, the FIFO allows 15 samples to be transmitted by the I <sup>2</sup> S (per channel) (a 9th sample can be shifting out) before TDE1 bit is set. When the FIFO is disabled, an interrupt is generated when a single sample is transferred to the transmit shift register (provided the interrupt is enabled).
	0 Transmit FIFO 1 disabled.
	1 Transmit FIFO 1 enabled.
7 TFEN0	Transmit FIFO Enable 0.
	This bit enables transmit FIFO 0. When enabled, the FIFO allows 15 samples to be transmitted by the I <sup>2</sup> S per channel (a 9th sample can be shifting out) before TDE0 bit is set. When the FIFO is disabled, an interrupt is generated when a single sample is transferred to the transmit shift register (provided the interrupt is enabled).
	<ul><li>0 Transmit FIFO 0 disabled.</li><li>1 Transmit FIFO 0 enabled.</li></ul>
6 TFDIR	Transmit Frame Direction.
	This bit controls the direction and source of the transmit frame sync signal. Internally generated frame sync signal is sent out through the STFS port and external frame sync is taken from the same port.
	0 Frame sync is external.
	1 Frame sync generated internally.



## I2Sx\_TCR field descriptions (continued)


Field	Description
5 TXDIR	Transmit clock direction
	This bit controls the direction and source of the clock signal used to clock the TXSR. Internally generated clock is output through the STCK port. External clock is taken from this port.
	0 Transmit clock is external.
	1 Transmit clock generated internally
4 TSHFD	Transmit Shift Direction.
	This bit controls whether the MSB or LSB will be transmitted first in a sample.
	<b>NOTE:</b> The CODEC device labels the MSB as bit 0, whereas the core labels the LSB as bit 0. Therefor when using a standard CODEC, core MSB (CODEC LSB) is shifted in first (TCR[TSHFD] cleared).
	0 Data transmitted MSB first.
	1 Data transmitted LSB first.
3 TSCKP	Transmit Clock Polarity.
	This bit controls which bit clock edge is used to clock out data for the transmit section.
	<b>NOTE:</b> TSCKP is 0 CLKIST = 0; TSCKP is 1CLKIST = 1
	0 Data clocked out on rising edge of bit clock.
	Data clocked out on falling edge of bit clock.
2 TFSI	Transmit Frame Sync Invert.
11 31	This bit controls the active state of the frame sync I/O signal for the transmit section of I <sup>2</sup> S.
	0 Transmit frame sync is active high.
	1 Transmit frame sync is active low.
1 TEQI	Transmit Frame Sync Length.
TFSL	This bit controls the length of the frame sync signal to be generated or recognized for the transmit section. The length of a word-long frame sync is same as the length of the data word selected by WL[3:0].
	Transmit frame sync is one-word long.
	1 Transmit frame sync is one-clock-bit long.
0 TEFS	Transmit Early Frame Sync.
	This bit controls when the frame sync is initiated for the transmit section. The frame sync signal is deasserted after one bit-for-bit length frame sync and after one word-for-word length frame sync. In case of synchronous operation, the frame sync can also be initiated on receiving the first bit of data.
	O Transmit frame sync initiated as the first bit of data is transmitted.
	1 Transmit frame sync is initiated one bit before the data is transmitted.



### 51.3.9 I<sup>2</sup>S Receive Configuration Register (I2Sx\_RCR)

RCR directs the receive operation of the I2S. A power-on reset clears all RCR bits. However, I2S reset does not affect the RCR bits.

Addresses: I2S0\_RCR is 4002\_F000h base + 20h offset = 4002\_F020h



### I2Sx\_RCR field descriptions

Field	Description
31–11 Reserved	This read-only field is reserved and always has the value zero.
10 RXEXT	Receive Data Extension.  This control bit allows I <sup>2</sup> S to store the received data word in sign extended form. This bit affects data storage only in case received data is LSB aligned (RCR[9]=1)  0 Sign extension turned off.
	1 Sign extension turned on.
9 RXBIT0	Receive Bit 0.  This control bit allows I <sup>2</sup> S to receive the data word at bit position 0 or 15/31 in the receive shift register. The shifting data direction can be MSB or LSB first, controlled by the RSHFD bit.  O Shifting with respect to bit 31 (if word length = 16, 18, 20, 22 or 24) or bit 15 (if word length = 8, 10 or 12) of receive shift register (MSB aligned).  Shifting with respect to bit 0 of receive shift register (LSB aligned).
8	Receive FIFO Enable 1.
RFEN1	This bit enables receive FIFO 1. When enabled, the FIFO allows 15 samples to be received by the I <sup>2</sup> S per channel (a 16th sample can be shifting in) before RDR1 bit is set. When the FIFO is disabled, an interrupt is generated when a single sample is received by the I <sup>2</sup> S (provided the interrupt is enabled).  O Receive FIFO 1 disabled.  Receive FIFO 1 enabled.
7 RFEN0	Receive FIFO Enable 0.  This bit enables receive FIFO 0. When enabled, the FIFO allows 15 samples to be received by the I <sup>2</sup> S (per channel) (a 16th sample can be shifting in) before RDR0 bit is set. When the FIFO is disabled, an interrupt is generated when a single sample is received by the I <sup>2</sup> S (provided the interrupt is enabled).  0 Receive FIFO 0 disabled.  1 Receive FIFO 0 enabled.
6 RFDIR	Receive Frame Direction.




## I2Sx\_RCR field descriptions (continued)


Field	Description
	This bit controls the direction and source of the receive frame sync signal. Internally generated frame sync signal is sent out through the SRFS port and external frame sync is taken from the same port.
	0 Frame Sync is external.
	1 Frame Sync generated internally.
5 RXDIR	Receive Clock Direction.
	This bit controls the direction and source of the clock signal used to clock the RXSR. Internally generated clock is output through the SRCK port. External clock is taken from this port.
	0 Receive Clock is external.
	Receive Clock generated internally.
4 RSHFD	Receive Shift Direction.
	This bit controls whether the MSB or LSB will be received first in a sample.
	NOTE: The CODEC device labels the MSB as bit 0, whereas the Core labels the LSB as bit 0. Therefore, when using a standard CODEC, Core MSB (CODEC LSB) is shifted in first (RSHFD cleared).
	0 Data received MSB first.
	1 Data received LSB first.
3 RSCKP	Receive Clock Polarity.
	This bit controls which bit clock edge is used to latch in data for the receive section.
	Data latched on falling edge of bit clock.
	1 Data latched on rising edge of bit clock.
2 RFSI	Receive Frame Sync Invert.
1.1.01	This bit controls the active state of the frame sync I/O signal for the receive section of I <sup>2</sup> S.
	0 Receive frame sync is active high.
	1 Receive frame sync is active low.
1 RFSL	Receive Frame Sync Length.
	This bit controls the length of the frame sync signal to be generated or recognized for the receive section. The length of a word-long frame sync is same as the length of the data word selected by WL[3:0].
	Receive frame sync is one-word long.
	1 Receive frame sync is one-clock-bit long.
0 REFS	Receive Early Frame Sync.
	This bit controls when the frame sync is initiated for the receive section. The frame sync is disabled after one bit-for-bit length frame sync and after one word-for-word length frame sync.
	Receive frame sync initiated as the first bit of data is received.
	1 Receive frame sync is initiated one bit before the data is received.



### 51.3.10 I<sup>2</sup>S Transmit Clock Control Registers (I2Sx\_TCCR)

The I2S Transmit and Receive Control (TCCR and RCCR) registers are 19-bit, read/write control registers used to direct the operation of the I2S. The Clock and Reset Module (CRM) can source the I2S clock (network clock) from multiple sources and perform fractional division to support commonly used audio bit rates. The CRM can maintain the network clock frequency at a constant rate even in cases where the peripheral clock frequency changes. These registers control the I2S clock generator, bit and frame sync rates, word length, and number of words per frame for the serial data. The TCCR register is dedicated to the transmit section, and the RCCR register is dedicated to the receive section except in Synchronous mode, in which the TCCR register controls both the receive and transmit sections. Power-on reset clears all TCCR and RCCR bits. I2S reset does not affect the TCCR and RCCR bits. The control bits are described in the following paragraphs. Although the bit patterns of the TCCR and RCCR registers are the same, the contents of these two registers can be programmed differently.





#### I2Sx\_TCCR field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18 DIV2	Divide By 2.  This bit controls a divide-by-two divider in series with the rest of the prescalers.  0 Divider bypassed. 1 Divider used to divide clock by 2.
17 PSR	Prescaler Range.  This bit controls a fixed divide-by-eight prescaler in series with the variable prescaler. It extends the range of the prescaler for those cases where a slower bit clock is required.  O Prescaler bypassed.  1 Prescaler used to divide clock by 8.
16–13 WL	Word Length Control.  Specifies the number of bits per data word being transferred by the I <sup>2</sup> S. These bits control the Word Length Divider in the Clock Generator. They also control the frame sync pulse length when the FSL bit is cleared. In I2S Master mode, the I <sup>2</sup> S works with a fixed word length of 32, and the WL bits are used to




## I2Sx\_TCCR field descriptions (continued)


Field	Description
	control the amount of valid data in those 32 bits. In AC97 Mode of operation, if word length is set to any value other than 16 bits, it will result in a word length of 20 bits.
	0000 Reserved. Do not program this value.
	0001 Reserved. Do not program this value.
	0010 Reserved. Do not program this value.
	0011 8
	0100 10
	0101 12
	0110 Reserved. Do not program this value.
	0111 16
	1000 18
	1001 20
	1010 22
	1011 24
	1100 Reserved. Do not program this value.
	1101 Reserved. Do not program this value.
	1110 Reserved. Do not program this value.
	1111 Reserved. Do not program this value.
12–8 DC	Frame Rate Divider Control.
БС	These bits are used to control the divide ratio for the programmable frame rate dividers. The divide ratio works on the word clock. In Normal mode, this ratio determines the word transfer rate. In Network mode this ratio sets the number of words per frame. The divide ratio ranges from 1 to 32 in Normal mode and from 2 to 32 in Network mode. In Normal mode, a divide ratio of 1 (DC=00000) provides continuous periodic data word transfer. A bit-length frame sync must be used in this case.
	These bits can be programmed with values ranging from "00000" to "111111" to control the number of words in a frame.
7–0	Prescaler Modulus Select.
PM	These bits control the prescale divider in the clock generator. This prescaler is used only in Internal Clomode to divide the internal clock. The bit clock output is available at the clock port. A divide ratio from 1 to 256 (PM[7:0] = 0x00 to 0xFF) can be selected.



### 51.3.11 I<sup>2</sup>S Receive Clock Control Registers (I2Sx\_RCCR)

The I2S Transmit and Receive Control (TCCR and RCCR) registers are 19-bit, read/write control registers used to direct the operation of the I2S. The Clock and Reset Module (CRM) can source the I2S clock (network clock) from multiple sources and perform fractional division to support commonly used audio bit rates. The CRM can maintain the network clock frequency at a constant rate even in cases where the peripheral clock frequency changes. These registers control the I2S clock generator, bit and frame sync rates, word length, and number of words per frame for the serial data. The TCCR register is dedicated to the transmit section, and the RCCR register is dedicated to the receive section except in Synchronous mode, in which the TCCR register controls both the receive and transmit sections. Power-on reset clears all TCCR and RCCR bits. I2S reset does not affect the TCCR and RCCR bits. The control bits are described in the following paragraphs. Although the bit patterns of the TCCR and RCCR registers are the same, the contents of these two registers can be programmed differently.





#### I2Sx\_RCCR field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18 DIV2	Divide By 2.  This bit controls a divide-by-two divider in series with the rest of the prescalers.  0 Divider bypassed. 1 Divider used to divide clock by 2.
17 PSR	Prescaler Range.  This bit controls a fixed divide-by-eight prescaler in series with the variable prescaler. It extends the range of the prescaler for those cases where a slower bit clock is required.  O Prescaler bypassed.  1 Prescaler used to divide clock by 8.
16–13 WL	Word Length Control.  These bits are used to control the length of the data words being transferred by the I <sup>2</sup> S. These bits control the Word Length Divider in the Clock Generator. They also control the frame sync pulse length when the FSL bit is cleared. In I2S Master mode, the I <sup>2</sup> S works with a fixed word length of 32, and the WL bits are

### I2Sx\_RCCR field descriptions (continued)

Field	Description
	used to control the amount of valid data in those 32 bits. In AC97 Mode of operation, if word length is set to any value other than 16 bits, it will result in a word length of 20 bits.
	0000 Number of Bits/Word: 2; Supported in Implementation: No.
	0001 Number of Bits/Word: 4; Supported in Implementation: No.
	0010 Number of Bits/Word: 6; Supported in Implementation: No.
	0011 Number of Bits/Word: 8; Supported in Implementation: Yes.
	0100 Number of Bits/Word: 10; Supported in Implementation: Yes.
	0101 Number of Bits/Word: 12; Supported in Implementation: Yes.
	0110 Number of Bits/Word: 14; Supported in Implementation: No.
	0111 Number of Bits/Word: 16; Supported in Implementation: Yes.
	1000 Number of Bits/Word: 18; Supported in Implementation: Yes.
	1001 Number of Bits/Word: 20; Supported in Implementation: Yes.
	1010 Number of Bits/Word: 22; Supported in Implementation: Yes.
	1011 Number of Bits/Word: 24; Supported in Implementation: Yes.
	1100 Number of Bits/Word: 26; Supported in Implementation: No.
	1101 Number of Bits/Word: 28; Supported in Implementation: No.
	1110 Number of Bits/Word: 30; Supported in Implementation: No.
	1111 Number of Bits/Word: 32; Supported in Implementation: No.
12–8	Frame Rate Divider Control.
DC	These bits are used to control the divide ratio for the programmable frame rate dividers. The divide ratio works on the word clock. In Normal mode, this ratio determines the word transfer rate. In Network mode, this ratio sets the number of words per frame. The divide ratio ranges from 1 to 32 in Normal mode and from 2 to 32 in Network mode. In Normal mode, a divide ratio of 1 (DC=00000) provides continuous periodic data word transfer. A bit-length frame sync must be used in this case.
	These bits can be programmed with values ranging from "00000" to "11111" to control the number of words in a frame.
7–0	Prescaler Modulus Select.
PM	These bits control the prescale divider in the clock generator. This prescaler is used only in Internal Clock mode to divide the internal clock . The bit clock output is available at the clock port. A divide ratio from 1 to 256 (PM[7:0] = 0x00 to 0xFF) can be selected.

# 51.3.12 I<sup>2</sup>S FIFO Control/Status Register (I2Sx\_FCSR)

The following table indicates the status of the Transmit FIFO Empty flag, with different settings of the Transmit FIFO WaterMark bits and varying amounts of data in the Tx FIFO.

Table 51-40. Status of Transmit FIFO Empty Flag


Transmit FIFO Watermark (TFWM)	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0



### Table 51-40. Status of Transmit FIFO Empty Flag (continued)

Transmit FIFO Watermark (TFWM)	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
2	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0
3	1	1	1	1	1	1	1	1	1	1	1	1	0	0	0
4	1	1	1	1	1	1	1	1	1	1	1	0	0	0	0
5	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0
6	1	1	1	1	1	1	1	1	1	0	0	0	0	0	0
7	1	1	1	1	1	1	1	1	0	0	0	0	0	0	0
8	1	1	1	1	1	1	1	0	0	0	0	0	0	0	0
9	1	1	1	1	1	1	0	0	0	0	0	0	0	0	0
10	1	1	1	1	1	0	0	0	0	0	0	0	0	0	0
11	1	1	1	1	0	0	0	0	0	0	0	0	0	0	0
12	1	1	1	0	0	0	0	0	0	0	0	0	0	0	0
13	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0
14	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0
15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Addresses: I2S0\_FCSR is 4002\_F000h base + 2Ch offset = 4002\_F02Ch



### I2Sx\_FCSR field descriptions

Field	Description
31–28 RFCNT1	Receive FIFO Counter1.
	These bits indicate the number of data words in Receive FIFO 1.
	0000 0 data word in receive FIFO.
	0001 1 data word in receive FIFO.
	0010 2 data word in receive FIFO.
	0011 3 data word in receive FIFO.
	0100 4 data word in receive FIFO.
	0101 5 data word in receive FIFO.
	0110 6 data word in receive FIFO.
	0111 7 data word in receive FIFO.
	1000 8 data word in receive FIFO.
	1000 8 data word in receive FIFO.
	1001 9 data word in receive FIFO.
	1010 10 data word in receive FIFO.
	1011 11 data word in receive FIFO.

Table continues on the next page...

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## I2Sx\_FCSR field descriptions (continued)

Field	Description
	1100 12 data word in receive FIFO.
	1101 13 data word in receive FIFO.
	1110 14 data word in receive FIFO.
	1111 15 data word in receive FIFO.
27–24 TFCNT1	Transmit FIFO Counter1.
	These bits indicate the number of data words in Transmit FIFO.
	0000 0 data word in transmit FIFO.
	0001 1 data word in transmit FIFO.
	0010 2 data word in transmit FIFO.
	0011 3 data word in transmit FIFO.
	0100 4 data word in transmit FIFO.
	0101 5 data word in transmit FIFO.
	0110 6 data word in transmit FIFO.
	0111 7 data word in transmit FIFO.
	1000 8 data word in transmit FIFO.
	1001 9 data word in transmit FIFO.
	1010 10 data word in transmit FIFO.
	1011 11 data word in transmit FIFO.
	1100 12 data word in transmit FIFO. 1101 13 data word in transmit FIFO.
	1110 14 data word in transmit FIFO.
	1111 15 data word in transmit FIFO.
00.00	
23–20 RFWM1	Receive FIFO Full WaterMark 1.
	These bits control the threshold at which the RFF1 flag will be set. The RFF1 flag is set whenever the data level in Rx FIFO 1 reaches the selected threshold.
	0000 Reserved
	0001 RFF set when at least one data word have been written to the Receive FIFO Set when RxFIFO =
	1,215 data words
	0010 RFF set when more than or equal to 2 data word have been written to the Receive FIFO. Set when RxFIFO = 2,315 data words
	0011 RFF set when more than or equal to 3 data word have been written to the Receive FIFO. Set when RxFIFO = 3,415 data words
	0100 RFF set when more than or equal to 4 data word have been written to the Receive FIFO. Set when RxFIFO = 4,515 data words
	0101 RFF set when more than or equal to 5 data word have been written to the Receive FIFO. Set when RxFIFO = 5,615 data words
	0110 RFF set when more than or equal to 6 data word have been written to the Receive. Set when RxFIFO = 6,715 data words
	0111 RFF set when more than or equal to 7 data word have been written to the Receive FIFO. Set when RxFIFO = 7,815 data words
	1000 RFF set when more than or equal to 8 data word have been written to the Receive FIFO. Set when RxFIFO = 8,915 data words
	1001 RFF set when more than or equal to 9 data word have been written to the Receive FIFO. Set when RxFIFO = 9,1015 data words



## I2Sx\_FCSR field descriptions (continued)

Field		Description
i iciu	40:0	· · · · · · · · · · · · · · · · · · ·
	1010	RFF set when more than or equal to 10 data word have been written to the Receive FIFO. Set when RxFIFO = 10,1115 data words
	1011	RFF set when more than or equal to 11 data word have been written to the Receive FIFO. Set when RxFIFO = 11,1215 data words
	1100	RFF set when more than or equal to 12 data word have been written to the Receive FIFO. Set when RxFIFO = 12,1315 data words
	1101	RFF set when more than or equal to 13 data word have been written to the Receive FIFO. Set when RxFIFO = 13,14,15data words
	1110	RFF set when more than or equal to 14 data word have been written to the Receive FIFO. Set when RxFIFO = 14,15 data words
	1111	RFF set when 15 data word have been written to the Receive FIFO (default). Set when RxFIFO = 15 data words
19–16 TFWM1	Transr	mit FIFO Empty WaterMark 1.
TT WIVIT		bits control the threshold at which the TFE1 flag will be set. The TFE1 flag is set whenever the slots in Tx FIFO exceed or are equal to the selected threshold.
	0000	Reserved
	0001	TFE set when there are more than or equal to 1 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO ≤ 14 data.
	0010	TFE set when there are more than or equal to 2 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO ≤ 13 data.
	0011	TFE set when there are more than or equal to 3 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO ≤ 12 data.
	0100	TFE set when there are more than or equal to 4 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 11$ data.
	0101	TFE set when there are more than or equal to 5 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 10$ data.
	0110	TFE set when there are more than or equal to 6 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 9$ data.
	0111	TFE set when there are more than or equal to 7 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 8$ data.
	1000	TFE set when there are more than or equal to 8 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 7$ data.
	1001	TFE set when there are more than or equal to 9 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 6 data.
	1010	TFE set when there are more than or equal to 10 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 5 data.
	1011	TFE set when there are more than or equal to 11 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 4 data.
	1100	TFE set when there are more than or equal to 12 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 3 data.
	1101	TFE set when there are more than or equal to 13 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 2 data.
	1110	TFE set when there are more than or equal to 14 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 1 data.
	1000	TFE set when there are more than or equal to 15 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 0 data.
15–12 RFCNT0	Receiv	ve FIFO Counter 0.



## I2Sx\_FCSR field descriptions (continued)

Field	Description
	These bits indicate the number of data words in Receive FIFO 0.
	0000 0 data word in receive FIFO.
	0001 1 data word in receive FIFO.
	0010 2 data word in receive FIFO.
	0011 3 data word in receive FIFO.
	0100 4 data word in receive FIFO.
	0101 5 data word in receive FIFO.
	0110 6 data word in receive FIFO.
	0111 7 data word in receive FIFO.
	1000 8 data word in receive FIFO.
	1000 8 data word in receive FIFO.
	1001 9 data word in receive FIFO.
	1010 10 data word in receive FIFO.
	1011 11 data word in receive FIFO.
	1100 12 data word in receive FIFO.
	1101 13 data word in receive FIFO.
	1110 14 data word in receive FIFO.
	1111 15 data word in receive FIFO.
11–8	Transmit FIFO Counter 0.
TFCNT0	These bits indicate the number of data words in Transmit FIFO 0.
	0000 0 data word in transmit FIFO.
	0001 1 data word in transmit FIFO.
	0010 2 data word in transmit FIFO.
	0011 3 data word in transmit FIFO.
	0100 4 data word in transmit FIFO.
	0101 5 data word in transmit FIFO.
	0110 6 data word in transmit FIFO.
	0111 7 data word in transmit FIFO.
	1000 8 data word in transmit FIFO.
	1001 9 data word in transmit FIFO.
	1010 10 data word in transmit FIFO.
	1011 11 data word in transmit FIFO.
	1100 12 data word in transmit FIFO.
	1101 13 data word in transmit FIFO.
	1110 14 data word in transmit FIFO.
	1111 15 data word in transmit FIFO.
7–4 RFWM0	Receive FIFO Full WaterMark 0.
	These bits control the threshold at which the RFF0 flag will be set. The RFF0 flag is set whenever the data level in Rx FIFO 0 reaches the selected threshold.
	0000 Reserved
	0001 RFF set when at least one data word have been written to the Receive FIFO Set when RxFIFO = 1,215 data words




## I2Sx\_FCSR field descriptions (continued)


Field		Description
	0010	RFF set when more than or equal to 2 data word have been written to the Receive FIFO. Set when RxFIFO = 2,315 data words
	0011	RFF set when more than or equal to 3 data word have been written to the Receive FIFO. Set when RxFIFO = 3,415 data words
	0100	RFF set when more than or equal to 4 data word have been written to the Receive FIFO. Set when RxFIFO = 4,515 data words
	0101	RFF set when more than or equal to 5 data word have been written to the Receive FIFO. Set when RxFIFO = 5,615 data words
	0110	RFF set when more than or equal to 6 data word have been written to the Receive. Set when RxFIFO = 6,715 data words
	0111	RFF set when more than or equal to 7 data word have been written to the Receive FIFO. Set when RxFIFO = 7,815 data words
	1000	RFF set when more than or equal to 8 data word have been written to the Receive FIFO. Set when RxFIFO = 8,915 data words
	1001	RFF set when more than or equal to 9 data word have been written to the Receive FIFO. Set when RxFIFO = 9,1015 data words
	1010	RFF set when more than or equal to 10 data word have been written to the Receive FIFO. Set when RxFIFO = 10,1115 data words
	1011	RFF set when more than or equal to 11 data word have been written to the Receive FIFO. Set when RxFIFO = 11,1215 data words
	1100	RFF set when more than or equal to 12 data word have been written to the Receive FIFO. Set when RxFIFO = 12,1315 data words
	1101	RFF set when more than or equal to 13 data word have been written to the Receive FIFO. Set when RxFIFO = 13,14,15data words
	1110	RFF set when more than or equal to 14 data word have been written to the Receive FIFO. Set when RxFIFO = 14,15 data words
	1111	RFF set when 15 data word have been written to the Receive FIFO (default). Set when RxFIFO = 15 data words
3–0 TFWM0	Transr	nit FIFO Empty WaterMark 0.
TT WIVIO		bits control the threshold at which the TFE0 flag will be set. The TFE0 flag is set whenever the slots in Tx FIFO exceed or are equal to the selected threshold.
	0000	Reserved
	0001	TFE set when there are more than or equal to 1 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 14$ data.
	0010	TFE set when there are more than or equal to 2 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 13$ data.
	0011	TFE set when there are more than or equal to 3 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 12$ data.
	0100	TFE set when there are more than or equal to 4 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 11$ data.
	0101	TFE set when there are more than or equal to 5 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 10$ data.
	0110	TFE set when there are more than or equal to 6 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 9$ data.
	0111	TFE set when there are more than or equal to 7 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 8$ data.
	1000	TFE set when there are more than or equal to 8 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 7$ data.

## I2Sx\_FCSR field descriptions (continued)

Field		Description
	1001	TFE set when there are more than or equal to 9 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 6$ data.
	1010	TFE set when there are more than or equal to 10 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 5$ data.
	1011	TFE set when there are more than or equal to 11 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 4$ data.
	1100	TFE set when there are more than or equal to 12 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 3$ data.
	1101	TFE set when there are more than or equal to 13 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 2$ data.
	1110	TFE set when there are more than or equal to 14 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when $TxFIFO \le 1$ data.
	1000	TFE set when there are more than or equal to 15 empty slots in Transmit FIFO. (default) Transmit FIFO empty is set when TxFIFO $\leq$ 0 data.

## 51.3.13 I<sup>2</sup>S AC97 Control Register (I2Sx\_ACNT)





### I2Sx\_ACNT field descriptions

Field	Description							
31–11 Reserved								
10–5 FRDIV	Frame Rate Divider.  These bits control the frequency of AC97 data transmission/reception. They are programmed with the number of frames for which the I <sup>2</sup> S should be idle, after operating in one frame. Through these bits, AC97 frequency of operation, from 48 KHz (000000) to 1 KHz (101111) can be achieved.  Sample Value: 001010 (10 Decimal) = I <sup>2</sup> S will operate once every 11 frames							
4 WR	Write Command.							

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011




### I2Sx\_ACNT field descriptions (continued)

Field	Description
	This bit specifies whether the next frame will carry an AC97 Write Command or not. The programmer should take care that only one of the bits (WR or RD) is set at a time. When this bit is set, the corresponding tag bits (corresponding to Command Address and Command Data slots of the next Tx frame) are automatically set. This bit is automatically cleared by the I <sup>2</sup> S after completing transmission of frame.
	0 Next frame will not have a Write Command.
	1 Next frame will have a Write Command.
3 RD	Read Command.
<b>-</b>	This bit specifies whether the next frame will carry an AC97 Read Command or not. The programmer should take care that only one of the bits (WR or RD) is set at a time. When this bit is set, the corresponding tag bit (corresponding to Command Address slot of the next Tx frame) is automatically set. This bit is automatically cleared by the I <sup>2</sup> S after completing transmission of a frame.
	Next frame will not have a Read Command.
	1 Next frame will have a Read Command.
2 TIF	Tag in FIFO.
111	This bit controls the destination of the information received in AC97 tag slot (Slot #0).
	0 Tag info stored in ATAG register.
	1 Tag info stored in ATAG register and Rx FIFO 0.
1 FV	Fixed/Variable Operation.
FV	This bit selects whether the I <sup>2</sup> S is in AC97 Fixed mode or AC97 Variable mode.
	0 AC97 Fixed Mode
	1 AC97 Variable Mode.
0 AC97EN	AC97 Mode Enable.
	This bit is used to enable I <sup>2</sup> S AC97 operation.
	0 AC97 mode disabled.
	1 I <sup>2</sup> S in AC97 mode.

## 51.3.14 I<sup>2</sup>S AC97 Command Address Register (I2Sx\_ACADD)

Addresses: I2S0\_ACADD is 4002\_F000h base + 3Ch offset = 4002\_F03Ch






### I2Sx\_ACADD field descriptions

Field	Description
31–19 Reserved	This read-only field is reserved and always has the value zero.
18–0 ACADD	AC97 Command Address.  These bits store the Command Address Slot information (bit 19 of the slot is sent in accordance with the Read and Write Command bits in ACNT register). These bits can be updated by a direct write from the Core. They are also updated with the information received in the incoming Command Address Slot. If the contents of these bits change due to an update, the CMDAU bit in ISR is set.

# 51.3.15 I<sup>2</sup>S AC97 Command Data Register (I2Sx\_ACDAT)

Addresses: I2S0\_ACDAT is 4002\_F000h base + 40h offset = 4002\_F040h




### I2Sx\_ACDAT field descriptions

Field	Description
31–20 Reserved	This read-only field is reserved and always has the value zero.
19–0 ACDAT	AC97 Command Data.  The outgoing Command Data Slot carries the information contained in these bits. These bits can be updated by a direct write from the Core. They are also updated with the information received in the incoming Command Data Slot. If the contents of these bits change due to an update, the CMDDU bit in ISR is set. These bits are transmitted only during AC97 Write Command. During AC97 Read Command, 0x00000 is transmitted in time slot #2.

## 51.3.16 I<sup>2</sup>S AC97 Tag Register (I2Sx\_ATAG)

Addresses: I2S0\_ATAG is 4002\_F000h base + 44h offset = 4002\_F044h







### I2Sx\_ATAG field descriptions

Field	Description
31–16 Reserved	This read-only field is reserved and always has the value zero.
15–0 ATAG	AC97 Tag Value.  Writing to this register (by the Core) sets the value of the Tx-Tag in AC97 fixed mode of operation. On a read, the Core gets the Rx-Tag Value received (in the last frame) from the Codec. If TIF bit in ACNT register is set, the TAG value is also stored in Rx-FIFO in addition to ATAG register. When the received Tag value changes, the RXT bit in ISR register is set. Bits ATAG[1:0] convey the Codec -ID. In current implementation only Primary Codecs are supported. Thus writing value 2'b00 to this field is mandatory.

## 51.3.17 I<sup>2</sup>S Transmit Time Slot Mask Register (I2Sx\_TMSK)






### I2Sx\_TMSK field descriptions

Field	Description
31–0 TMSK	Transmit Mask.
	These bits indicate which slot has been masked in the current frame. The Core can write to this register to control the time slots in which the I <sup>2</sup> S transmits data. Each bit has info corresponding to the respective time slot in the frame. Transmit mask bits should not be used in I2S Slave mode of operation. TMSK register value must be set before enabling Transmission.
	<ul><li>Valid Time Slot.</li><li>Time Slot masked (no data transmitted in this time slot).</li></ul>

### 51.3.18 I<sup>2</sup>S Receive Time Slot Mask Register (I2Sx\_RMSK)

Addresses: I2S0\_RMSK is 4002\_F000h base + 4Ch offset = 4002\_F04Ch




### I2Sx\_RMSK field descriptions

Field	Description
31-0 RMSK	Receive Mask.
	These bits indicate which slot has been masked in the current frame. The Core can write to this register to control the time slots in which the I <sup>2</sup> S receives data. Each bit has info corresponding to the respective time slot in the frame. RMSK register value must be set before enabling Receiver.Receive mask bits should not be used in I2S Slave mode of operation.
	<ul><li>0 Valid Time Slot.</li><li>1 Time Slot masked (no data received in this time slot).</li></ul>

## 51.3.19 I<sup>2</sup>S AC97 Channel Status Register (I2Sx\_ACCST)

Addresses: I2S0\_ACCST is 4002\_F000h base + 50h offset = 4002\_F050h




### I2Sx\_ACCST field descriptions

Field	Description
31–10 Reserved	This read-only field is reserved and always has the value zero.
9-0 ACCST	AC97 Channel Status.  These bits indicate which data slot has been enabled in AC97 variable mode operation. This register is updated in case the core enables/disables a channel through a write to ACCEN/ACCDIS register or the external codec enables a channel by sending a `1' in the corresponding SLOTREQ bit. Bit [0] corresponds to the first data slot in an AC97 frame (Slot #3) and Bit [9] corresponds to the tenth data slot (slot #12). The contents of this register only have relevance while the I²S is operating in AC97 variable mode. Writes to this register result in an error response on the IP interface.  Data channel disabled.  Data channel enabled.

# 51.3.20 I<sup>2</sup>S AC97 Channel Enable Register (I2Sx\_ACCEN)

Addresses: I2S0\_ACCEN is 4002\_F000h base + 54h offset = 4002\_F054h






### I2Sx\_ACCEN field descriptions

Field	Description
31–10 Reserved	This read-only field is reserved and always has the value zero.
9–0 ACCEN	AC97 Channel Enable.  The Core writes a `1' to these bits to enable an AC97 data channel. Writing a `0' has no effect. Bit [0] corresponds to the first data slot in an AC97 frame (Slot #3) and Bit [9] corresponds to the tenth data slot (slot #12). Writes to these bits only have effect in the AC97 Variable mode of operation. These bits are always read as `0' by the Core.  0 Write has no effect.  1 Write enables the corresponding data channel.

## 51.3.21 I<sup>2</sup>S AC97 Channel Disable Register (I2Sx\_ACCDIS)

Addresses: I2S0\_ACCDIS is 4002\_F000h base + 58h offset = 4002\_F058h



### I2Sx\_ACCDIS field descriptions

Field	Description
31–10 Reserved	This read-only field is reserved and always has the value zero.
9–0 ACCDIS	AC97 Channel Disable.  The Core writes a `1' to these bits to disable an AC97 data channel. Writing a `0' has no effect. Bit [0] corresponds to the first data slot in an AC97 frame (Slot #3) and Bit [9] corresponds to the tenth data slot (slot #12). Writes to these bits only have effect in the AC97 Variable mode of operation. These bits are always read as `0' by the Core.
	<ul><li>0 Write has no effect.</li><li>1 Write disables the corresponding data channel.</li></ul>

# 51.4 Functional description

This section provides the functional details of the I<sup>2</sup>S module.



**runctional description** 

### 51.4.1 Detailed operating mode descriptions

The following sections provide detailed descriptions of the above modes.

#### 51.4.1.1 Normal mode

Normal mode is the simplest mode of the I<sup>2</sup>S. It transfers data in one time slot per frame. A time slot is a unit of data and the RCCR[WL] bits define the number of bits in a time slot. In continuous clock mode, a frame sync occurs at the beginning of each frame. The following factors determine the length of the frame:

- Period of the serial bit clock (TCCR[DIV2], TCCR[PSR], TCCR[PM] bits for internal clock or the frequency of the external clock on the STCK port)
- Number of bits per time slot (RCCR[WL] bits)
- Number of time slots per frame (TCCR[DC] bits)

If normal mode is configured with more than one time slot per frame, data transfers only in the first time slot of the frame. No data transfers in subsequent time slots. In normal mode, TCCR[DC] values corresponding to more than a single time slot in a frame only result in lengthening the frame.

#### 51.4.1.1.1 Normal mode transmit

Conditions for data transmission from the I<sup>2</sup>S in normal mode are:

- 1.  $I^2S$  enabled (CR[I2SEN] = 1)
- 2. Enable FIFO and configure transmit and receive watermark if the FIFO is used
- 3. Write data to transmit data register (TX)
- 4. Transmitter enabled (CR[TE] = 1)
- 5. Frame sync active (for continuous clock case)
- 6. Bit clock begins (for gated clock case)

When the above conditions occur in normal mode, the next data word transfers into the transmit shift register (TXSR) from the transmit data register 0 (TX0), or from the transmit FIFO 0 register, if enabled.

• In continuous clock mode, the data word is transmitted on arrival of frame-sync preceded by clocks.



- In gated-external mode, the data word in transmitted on the external clock.
- In gated-internal mode, the data word is transmitted whenever data is available in the transmit FIFO.

If transmit FIFO 0 is not enabled and the transmit data register empty enable (IER[TDE0EN]) and transmit interrupt enable (IER[TIE]) bits are set, transmit interrupt 0 occurs when the word in I<sup>2</sup>S\_TX0 is shifted to transmit shift (TXSR) register.

If transmit FIFO 0 is enabled and the transmit FIFO full enable (IER[TFF0EN]) and transmit interrupt enable (IER[TIE]) bits are set, transmit interrupt 0 occurs when the number of empty slots in transmit FIFO 0 are equal to or exceed the selected threshold value (transmit FIFO 0 watermark (FCSR[TFWM0]). If transmit FIFO 0 is enabled and filled with data, 15 data words can be transferred before the core must write new data to the TX0 register.

The STXD port is disabled except during the data transmission period. For a continuous clock, the optional frame sync output and clock outputs are not disabled, even if the receiver and transmitter are disabled.

#### 51.4.1.1.2 Normal mode receive

The conditions for data reception from the  $I^2S$  are:

- 1.  $I^2S$  enabled (CR[I2SEN] = 1)
- 2. Enable receive FIFO (optional)
- 3. Receiver enabled (CR[RE] = 1)
- 4. Frame sync active (for continuous clock case)
- 5. Bit clock begins (for gated clock case)

With the above conditions in normal mode with a continuous clock, each time the frame sync signal is generated (or detected) a data word is clocked in. With the above conditions and a gated clock, each time the clock begins, a data word is clocked in.

If receive FIFO 0 is not enabled and receive interrupt enable (IER[RIE]) and received data 0 ready enable (IER[RDR0EN]) bits are set, receive interrupt 0 occurs when received data word is transferred from the receive shift register (RXSR) to the receive data register 0 (RX0), thus setting the receive data ready 0 (RDR0) flag.



#### runctional description

If receive FIFO 0 is enabled and receive interrupt enable (IER[RIE]) and received FIFO 0 full enable (IER[RDR0EN]) bits are set, receive interrupt 0 occurs when the received data word is transferred to the receive FIFO 0 and receive FIFO 0 reaches the selected threshold. This results in receive FIFO full 0 (RFF0) flag to set.

The core has to read the data from the receive data register 0 (RX0) (if receive FIFO 0 is disabled) before a new data word is transferred from the receive shift register (RXSR). Otherwise, the receive overrun error 0 (IER[ROE0EN]) bit is set. If receive FIFO 0 is enabled, the receive overrun error 0 (ROE0) bit sets when the receive FIFO 0 data level reaches the selected threshold and a new data word is ready to transfer to the receive FIFO 0.

The following figure shows transmitter and receiver timing for an 8-bit word in the first time slot in normal mode and continuous clock with a late word length frame sync. The transmit data register is loaded with the data to be transmitted. On arrival of the clock, this data is transferred to the transmit shift register which is transmitted on arrival of the frame-sync on the STXD output. Simultaneously, the receive shift register shifts in the received data available on the SRXD input. At the end of the time slot, this data is transferred to the receive data register.




Figure 51-46. Normal mode timing - continuous clock

The following figure shows a similar case for internal (I<sup>2</sup>S generates clock) gated clock mode.



#### **Note**

A pull-down resistor is required in the gated clock mode, because the clock port is disabled between transmissions.

The Tx data register is loaded with the data to be transmitted. On arrival of the clock, this data is transferred to the transmit shift register which gets transmitted on the STXD output. Simultaneously, the receive shift register shifts in the received data available on the SRXD input and at the end of the time slot, this data is transferred to the Rx data register. In internal gated clock mode, the Tx data line and clock output port are put in the high-impedance state at the end of transmission of the last bit (at the completion of the complete clock cycle). Whereas, in external gated clock mode, the Tx data line is tristated at the last inactive edge of the incoming bit clock (during the last bit in a data word).




Figure 51-47. Normal mode timing - internal gated clock

The following figure shows a case for external (I<sup>2</sup>S receives clock) gated clock mode






Figure 51-48. Normal mode timing - external gated clock

#### **51.4.1.2** Network mode

Network mode creates a time division multiplexed (TDM) network, such as a TDM CODEC network or a network of DSPs. In continuous clock mode, a frame sync occurs at the beginning of each frame. In this mode, the frame is divided into more than one time slot. During each time slot, one data word can be transferred. Each time slot is then assigned to an appropriate codec or DSP on the network. The processor can be a master device that controls its own private network, or a slave device that is connected to an existing TDM network and occupies a few time slots.

The frame sync signal indicates the beginning of a new data frame. Each data frame is divided into time slots and transmission and/or reception of one data word can occur in each time slot (rather than in just the frame sync time slot as in normal mode).

The frame rate dividers, controlled by the DC bits, select two to thirty-two time slots per frame. The length of the frame is determined by:

- Period of the serial bit clock (PSR, PM bits for internal clock, or the frequency of the external clock on the STCK port)
- Number of bits per sample (WL bits)
- Number of time slots per frame (DC bits)

In network mode, data can be transmitted in any time slot. The distinction of the network mode is that each time slot is identified with respect to the frame sync (data word time). This time slot identification allows the option of transmitting data during the time slot by



writing to the TX registers or ignoring the time slot as determined by TMSK register bits. The receiver is treated in the same manner and received data is only transferred to the receive data register/FIFO if the corresponding time slot is enabled through RMSK.

By using the TMSK and RMSK registers, software only has to service the I<sup>2</sup>S during valid time slots. This eliminates any overhead associated with unused time slots.

In the two-channel mode, the second set of transmit and receive FIFOs and data registers create two separate channels. These channels are completely independent with their own set of interrupts and DMA requests, which are identical to the ones available for the default channel. In this mode, data is transmitted/received in enabled time slots alternately from/to FIFO 0 and FIFO 1, starting from FIFO 0. The first data word is taken from FIFO 0 and transmitted in the first enabled time slot and subsequently, data is loaded from FIFO 1 and FIFO 0 alternately and transmitted. Similarly, the first received data is sent to FIFO 0 and subsequent data is sent to FIFO 1 and FIFO 0 alternately. Time slots are selected through the transmit and receive time slot mask registers (TMSK and RMSK). For using this mode of operation, the CR[TCHEN] bit must be set.

#### 51.4.1.2.1 Network mode transmit

The transmit portion of I<sup>2</sup>S is enabled when the CR[I2SEN and TE] bits are set. However, for continuous clock, when the CR[TE] bit is set, the transmitter is enabled only after detection of a new frame sync (transmission starts from the next frame boundary).

Normal start-up sequence for transmission:

- 1. Enable network mode
- 2. Enable I<sup>2</sup>S
- 3. Write the data to be transmitted to the TX register. This clears the ISR[TDE] flag
- 4. Set the CR[TE] bit to enable the transmitter on the next frame boundary (for continuous clock)
- 5. Enable transmit interrupts

Alternatively, the user may decide not to transmit in a time slot by configuring the TMSK[STMSK]. The ISR[TDE] flag is cleared as data is shifted from TX register to TXSR, but the STXD port remains disabled during the time slots. When the next frame sync is detected or generated (continuous clock), the data word in TXSR and is shifted out (transmitted). When the TX register is empty, the ISR[TDE] bit is set, which causes a transmitter interrupt (in case the FIFO is disabled) to be sent if the TIE bit is set. Software can poll the ISR[TDE] bit or use interrupts to reload the TX register with new data for the



next time slot. Failing to reload the TX register before the TXSR is finished shifting (empty) causes a transmitter underrun and the TUE error bit is set. In case the FIFO is enabled, the ISR[TFE] flag is set in accordance with the watermark setting and this flag causes the transmitter interrupt to occur.

Clearing the TE bit disables the transmitter after completion of transmission of the current frame. Setting the TE bit enables transmission from the next frame. During that time the STXD port is disabled. The TE bit should be cleared after the ISR[TDE] bit is set to ensure that all pending data is transmitted.

To summarize, the network mode transmitter generates interrupts every enabled time slot (when FIFO is disabled) and requires the processor to respond to each enabled time slot. These responses may be:

- Write data in data register to enable transmission in the next time slot.
- Configure the time slot register to disable transmission in the next time slot (unless time slot is already masked by TMSK[STMSK] register bit).
- Do nothing—transmit underrun occurs at the beginning of the next time slot and the previous data is re-transmitted.

In two-channel mode, both channels (data registers, FIFOs, interrupts, and DMA requests) operate in the same manner, as described above. The only difference is interrupts related to the second channel are generated only if this mode of operation is selected (ISR[TDE1] is low by default).

#### 51.4.1.2.2 Network mode receive

The receiver portion of the I<sup>2</sup>S is enabled when the CR[I2SEN and RE] bits are set. However, the receive enable only takes place during that time slot if RE is enabled before the second to last bit of the word. If the RE bit is cleared, the receiver is disabled at the end of the current frame. The I<sup>2</sup>S module is capable of finding the start of the next frame automatically. When the word is completely received, it is transferred to the RX register, which sets the ISR[RDR] bit. This causes a receive interrupt to occur if the receiver interrupt is enabled (IER[RIE] is set) and receive data ready is enabled (IER[RDR0EN] and IER[RDR1EN] is set). The second data word (second time slot in the frame) begins shifting in immediately after the transfer of the first data word to the RX register. The processor has to read the data from the receive data register (which clears ISR[RDR]) before the second data word is completely received (ready to transfer to RX data register) or a receive overrun error occurs (the ISR[ROE] bit is set).

An interrupt can occur after the reception of each enabled data word or the user can poll the ISR[RDR] flag. The response can be:



- Read RX and use the data.
- Read RX and ignore the data.
- Do nothing—the receiver overrun exception occurs at the end of the current time slot.

#### **Note**

For a continuous clock, the optional frame sync output and clock output signals are not affected, even if the transmitter or receiver is disabled. TE and RE do not disable the bit clock or the frame sync generation. To disable the bit clock and the frame sync generation, the CR[I2SEN] bit can be cleared, or CR[TFRCLKDIS]/CR[RFRCLKDIS] bits can be set, or the port control logic external to the I<sup>2</sup>S can be reconfigured.

In two-channel mode, both channels (data registers, FIFOs, interrupts and DMA requests) operate in the same manner, as described above. The only difference is second channel interrupts are generated only in this mode of operation.

The following figure shows the transmitter and receiver timing for an 8-bit word with continuous clock, FIFO disabled, three words per frame sync in network mode.


#### Note

The transmitter repeats the value 0x5E because of an underrun condition

For the receive section, data received on the SRXD pin is transferred to the Rx Data register at the end of each time slot. If the FIFO is disabled, the ISR[RDR] flag sets and causes a receiver interrupt if the CR[RE], IER[RIE], and IER[RDREN] bits are set. If the FIFO is enabled, then the ISR[RFF] flag generates interrupts (this flag is set in accordance with the watermark settings). In this example all time slots are enabled. The receive data ready flag is set after reception of the first data (0x55). Because the flag is not cleared (Rx data register is not read), the receive overrun error (ROE) flag is set on reception of the next data (0x5E). The ISR[ROE] flag is cleared by writing one to the corresponding interrupt status bit in I<sup>2</sup>S status register.







Note: Processor must write '1' to the corresponding TUE/ROE Interrupt status bit in ISR to clear TUE/ROE Interrupt

Figure 51-49. Network mode timing - continuous clock

## 51.4.1.3 Gated clock mode

Gated clock mode often connects to SPI-type interfaces on microcontroller units (MCUs) or external peripheral devices. In gated clock mode, the presence of the clock indicates that valid data is on the STXD or SRXD signals. For this reason, no frame sync is needed in this mode. After transmission of data completes, the clock is pulled to the inactive state. Gated clocks are allowed for the transmit and receive sections with either internal or external clock in normal mode. Gated clocks are not allowed in network mode. See Table 51-3 for I<sup>2</sup>S configuration for gated-mode operation.


The clock operates when the CR[TE] bit and/or the CR[RE] bit are appropriately enabled. For the case of internally generated clock, all internal bit clocks, word clocks, and frame clocks continue to operate. When a valid time slot occurs (such as the first time slot in

ROE



normal mode), the internal bit clock is enabled onto the appropriate clock port. This allows data to be transferred out in periodic intervals in gated clock mode. With an external clock, the I<sup>2</sup>S module waits for a clock signal to be received. After the clock begins, valid data is shifted in. Ensure all RCCR[DC] bits are cleared when the module is used in gated mode. In gated mode the ISR[TFS], ISR[RFS], ISR[TLS], ISR[RLS], ISR[TRFC] and ISR[RFRC] bits are not generated.

For gated clock operated in external clock mode, proper clock signalling must apply to the  $I^2S$  STCK for it to function properly. When TCR[TSCKP] is cleared, CR[CLKIST] must be set. When TCR[TSCKP] is set, CR[CLKIST] value must be cleared. If the  $I^2S$  uses rising edge transition to clock data (TCR[TSCKP] = 0) and the falling edge transition to latch data (RCR[RSCKP] = 0), the clock must be in an active low state when idle. If the  $I^2S$  uses falling edge transition to clock data (TCR[TSCKP] = 1) and the rising edge transition to latch data (RCR[RSCKP] = 1), the clock must be in a active high state when idle. The following diagrams illustrate the different edge clocking/latching.



TCR[TSCKP] = 0, RCR[RSCKP] = 0

Figure 51-50. Internal gated mode timing - rising edge clocking/falling edge latching




Figure 51-51. Internal gated mode timing - falling edge clocking/rising edge latching





Figure 51-52. External gated mode timing - rising edge clocking/falling edge latching



TCR[TSCKP] = 1, RCR[RSCKP] = 1

Figure 51-53. External gated mode timing - falling edge clocking/rising edge latching

#### **Note**

- The bit clock signals must not have timing glitches. If a single glitch occurs, all ensuing transfers are out of synchronization.
- In external gated mode, even though the transmit data line is tri-stated at the last non-active edge of the bit clock, the round trip delay should sufficiently take care of hold time requirements at the external receiver.

## 51.4.1.4 I<sup>2</sup>S mode

The I<sup>2</sup>S is compliant to the Inter-IC Sound (I<sup>2</sup>S) bus specification from Philips Semiconductors (February 1986, Revised June 5, 1996). The following figure depicts basic I<sup>2</sup>S protocol timing.




Figure 51-54. I<sup>2</sup>S mode timing - serial clock, frame sync and serial data

Select I<sup>2</sup>S mode using the options listed in the following table.

Table 51-50. I<sup>2</sup>S mode selection

CR[I2SMODE]	Mode type
00	Normal mode
01	I <sup>2</sup> S master mode

Table continues on the next page...



## Table 51-50. I<sup>2</sup>S mode selection (continued)

CR[I2SMODE]	Mode type					
10	I <sup>2</sup> S slave mode					
11	Normal mode					

In normal (non-I<sup>2</sup>S) mode operation, no register bits are forced to any particular state internally, and the user can program the I<sup>2</sup>S to work in any operating condition.

When  $I^2S$  modes are entered (CR[I2SMODE] = 01 or 10), these settings are recommended:

- Synchronous mode (CR[SYN] =1)
- Tx shift direction: msb transmitted first (TCR[TSHFD] = 0)
- Rx shift direction: msb received first (RCR[RSHFD] = 0)
- Tx data clocked at falling edge of the clock (TCR[TSCKP] = 1)
- Rx data latched at rising edge of the clock (RCR[RSCKP] = 1)
- Tx frame sync active low (TCR[TFSI] = 1)
- Rx frame sync active low (RCR[RFSI] = 1)
- Tx frame sync initiated one bit before data is transmitted (TCR[TEFS] = 1)
- Rx frame sync initiated one bit before data is received (RCR[REFS] = 1)
- Tx frame rate should be 2 (TCCR[DC] = 1)
- Rx frame rate should be 2 (RCCR[DC] = 1)

# 51.4.1.4.1 I<sup>2</sup>S master mode

In  $I^2S$  master mode (CR[I2SMODE] = 01b), the following additional settings are recommended:

- Internal generated bit clock (TCR[TXDIR] = 1)
- Internal generated frame sync (TCR[TFDIR] = 1)

The processor automatically performs these settings in  $I^2S$  master mode:

- Network mode is selected (CR[NET] = 1)
- Tx frame sync length set to one-word-long-frame (TCR[TFSL]=0)



- Rx frame sync length set to one-word-long-frame (RCR[RFSL]=0)
- Tx shifting w.r.t. bit 0 of TXSR (TCR[TXBIT0] = 1)
- Rx shifting w.r.t. bit 0 of RXSR (RCR[RXBIT0] = 1)

Set the TCCR[PM, PSR, DIV2, WL, DC] to configure the bit clock and frame sync.

The word length is fixed to 32 in I<sup>2</sup>S master mode and the RCCR[WL] bits determine the number of bits that contain valid data (out of the 32 transmitted/received bits in each channel).

## 51.4.1.4.2 I<sup>2</sup>S slave mode

In  $I^2S$  slave mode (CR[I2SMODE] = 10b), the following additional settings are recommended:

- External generated bit clock (TCR[TXDIR] = 0)
- External generated frame sync (TCR[TFDIR] = 0)

The processor automatically performs these settings in  $I^2S$  slave mode:

- Normal mode is selected (CR[NET] = 0)
- Tx frame sync length set to one-bit-long-frame (TCR[TFSL] = 1)
- Rx frame sync length set to one-bit-long-frame (RCR[RFSL] = 1)
- Tx shifting w.r.t. bit 0 of TXSR (TCR[TXBIT0] = 1)
- Rx shifting w.r.t. bit 0 of RXSR (RCR[RXBIT0] = 1)

Set the TCCR[WL, DC] bits to configure the data transmission.

The word length is variable in I<sup>2</sup>S slave mode and the RCCR[WL] bits determine the number of bits that contain valid data. The actual word length is determined by the external codec. The external I<sup>2</sup>S master sends a frame sync according to the I<sup>2</sup>S protocol (early, word wide, and active low). The I<sup>2</sup>S internally operates so each frame sync transition is the start of a new frame (the RCCR[WL] bits determine the number of bits to be transmitted/received). After one data word has been transferred, the I<sup>2</sup>S waits for the next frame sync transition to start operation in the next time slot. Transmit and receive mask bits should not be used in I<sup>2</sup>S slave mode.



#### 51.4.1.5 AC97 mode

In AC97 mode, the I<sup>2</sup>S transmits a 16-bit tag slot at the start of a frame and the rest of the slots (in that frame) are all 20-bits wide. The same sequence is followed while receiving data. Refer to the AC97 specification for details regarding transmit and receive sequences and data formats.

#### **Note**

The Audio Codec specification released in 1997 [AC '97] defines the architecture and digital Interface, specifically designed for implementing audio and modem I/O functionality in personal computers. Companion specifications include the Modem Codec [MC '97], and the combined Audio/Modem Codec standard [AMC '97]. The current version of AC '97 was produced in 2002. The AC-97 specification defines a recommended 48-pin QFP IC package.

Since the I<sup>2</sup>S has only one RxDATA pin only one codec is supported. Secondary codecs are not supported.

When AC97 mode is enabled, the hardware internal overrides the following settings. The programmed register values are not changed by entering AC97 mode but they no longer apply to the module's operation. Writing to the programmed register fields updates their values. These updates can be seen by reading back the register fields. However, these settings do not take effect until AC97 mode is turned off.

The register bits within the bracket are equivalent settings:

- Synchronous mode is entered (CR[SYN] = 1)
- Network mode is selected (CR[NET] = 1)
- Tx shift direction is msb transmitted first (TCR[TSHFD] = 0)
- Rx shift direction is msb received first (RCR[RSHFD] = 0)
- Tx data is clocked at rising edge of the clock (TCR[TSCKP] = 0)
- Rx data is latched at falling edge of the clock (RCR[RSCKP] = 0)
- Tx frame sync is active high (TCR[TFSI] = 0)
- Rx frame sync is active high (RCR[RFSI] = 0)
- Tx frame sync length is one-word-long-frame (TCR[TFSL] = 0)
- Rx frame sync length is one-word-long-frame (RCR[RFSL] = 0)



- Tx frame sync initiated one bit before data is transmitted (TCR[TEFS] = 1)
- Rx frame sync initiated one bit before data is received (RCR[REFS] = 1)
- Tx shifting w.r.t. bit 0 of TXSR (TCR[TXBIT0] = 1)
- Rx shifting w.r.t. bit 0 of RXSR (RCR[RXBIT0] = 1)
- Tx FIFO is enabled (TCR[TFEN0] = 1)
- Rx FIFO is enabled (RCR[RFEN0] = 1)
- Internally-generated frame sync (TCR[TFDIR] = 1)
- Externally-generated bit clock (TCR[TXDIR] = 0)

Any alteration of these bits does not affect the operational conditions of the I<sup>2</sup>S unless AC97 mode is deselected. Hence, the only control bits that need to be set to configure the data transmission/reception are the TCCR[WL, DC] bits. In AC97 mode, the WL bits can only legally take the values corresponding to 16-bit (truncated data) or 20-bit time slots. If the WL bits are set to select 16-bit time slots while receiving, the I<sup>2</sup>S pads the transmit data (four least significant bits) with zeros and while receiving, the I<sup>2</sup>S stores only the 16 most significant bits in the Rx FIFO.

Follow the sequence for programming the  $I^2S$  to work in AC97 mode:

- 1. Program the TCCR[WL] bits to a value corresponding to 16 or 20 bits. The WL bit setting is only for the data portion of the AC97 frame (slots #3 through #12). The tag slot (slot #0) is always 16 bits wide and the command address and command data slots (slots #1 and #2) are always 20 bits wide.
- 2. Select the number of time slots through the TCCR[DC] bits. For AC97 operation, the DC bits should be set to a value of 0xC, resulting in 13 time slots per frame.
- 3. Write data to be transmitted in Tx FIFO 0 (through Tx data register 0) and Tx FIFO 1 while using two-channel mode (CR[TCHEN] = 1).
- 4. Program the ACNT[FV, TIF, RD, WR, and FRDIV] bits
- 5. Update the contents of ACADD, ACDAT, and ATAG (for fixed mode only) registers
- 6. Enable AC97 mode (ACNT[AC97EN])

After the I<sup>2</sup>S starts transmitting and receiving data (after being configured in AC97 mode), the processor needs to service the interrupts when they are raised (updates to command address/data or tag registers, reading of received data, and writing more data for transmission). Further details regarding fixed and variable mode implementation appear in the following sections.



While using AC97 in two-channel mode (CR[TCHEN] = 1), it is recommended that the received tag is not stored in the Rx FIFO (ACNT[TIF] = 0). If you need to update the ATAG register and also issue a RD/WR command (in a single frame), it is recommended that the ATAG register is updated prior to issuing a RD/WR command.

## 51.4.1.5.1 AC97 fixed mode (ACNT[FV] = 0)

In fixed mode, I<sup>2</sup>S transmits in accordance with the AC97 frame rate divider bits (ACNT[FRDIV) that decide the number of frames for which the I<sup>2</sup>S should be idle, after operating for one frame. The following shows the slot assignments in a valid transmit frame:.

- Slot 0: The tag value (written by the user program)
- Slot 1: If RD/WR command, command address
- Slot 2: If WR command, command data
- Slot 3–12: Transmit FIFO data, depending on the valid slots indicated by the TAG value

While receiving, bit 15 of the tag slot is checked to see if the codec is ready. If this bit is set, the frame is received. The received tag provides the information about slots containing valid data. If the corresponding tag bit is valid, the command address (slot #1) and command data (slot #2) values are stored in the corresponding registers. The received data (slot #3–12) is then stored in the receive FIFO (for valid slots).

# 51.4.1.5.2 AC97 variable mode (ACNT[FV] = 1)

In variable mode, the transmit slots that should contain data in the current frame are determined by the SLOTREQ bits received in the previous frame. While receiving, if the codec is ready, the frame is received and the SLOTREQ bits are stored for scheduling transmission in the next frame.

The ACCST, ACCEN and ACCDIS registers helps determine which transmit slots are active. This information is used to ensure that I<sup>2</sup>S does not transmit data for powered-down/inactive channels.

# 51.4.2 I<sup>2</sup>S clocking

The I<sup>2</sup>S uses the following clocks:



- Bit clock Serially clocks the data bits in and out of the I<sup>2</sup>S port. This clock is either generated internally or taken from external clock source (through the Tx/Rx clock ports).
- Word clock Counts the number of data bits per word (8, 10, 12, 16, 18, 20, 22 or 24 bits). This clock is generated internally from the bit clock.
- Frame clock (frame sync) Counts the number of words in a frame. This signal can be generated internally from the bit clock, or taken from external source (from the Tx/Rx frame sync ports).
- Master clock —In master mode, this is an integer multiple of frame clock. It is used in cases when I<sup>2</sup>S has to provide the clock.

Ensure that the bit clock frequency (internally generated by dividing the network clock or sourced from external device through Tx/Rx clock ports) is never greater than 1/5 of the peripheral clock frequency.

In normal mode, the bit clock, used to serially clock the data, is visible on the serial transmit clock (STCK) and serial receive clock (SRCK) ports. The word clock is an internal clock used to determine when transmission of an 8, 10, 12, 16, 18, 20, 22 or 24 bit word has completed. The word clock then clocks the frame clock, which counts the number of words in the frame. The frame clock can be viewed on the STFS and SRFS frame sync ports, because a frame sync generates after the correct number of words in the frame have passed. In master and synchronous mode, the SRCK port is used as serial oversampling clock (network clock) enabled by the CR[SYSCLKEN] bit. This serial system clock is an oversampling clock of the frame sync clock (STFS). In this mode, the word length (WL), prescaler range (PSR), prescaler modulus (PM), and frame rate (DC) selects the ratio of network clock to sampling clock, STFS. In I<sup>2</sup>S mode, the oversampling clock network clock is available on this port if the CR[SYSCLKEN] bit is set.

The following figure shows the relationship between the clocks and the dividers. The bit clock can be received from an I<sup>2</sup>S clock port or can be generated from the network clock through a divider, as shown in Figure 51-56.




Figure 51-55. I<sup>2</sup>S clocking



# 51.4.2.1 I<sup>2</sup>S clock and frame sync generation

Data clock and frame sync signals can be generated internally, or can be obtained from external sources. If internally generated, the I<sup>2</sup>S clock generator is used to derive bit clock and frame sync signals from the network clock . The I<sup>2</sup>S clock generator consists of a selectable, fixed prescaler and a programmable prescaler for bit rate clock generation. In gated clock mode, the data clock is valid only when data is being transmitted. Otherwise the clock port is pulled to the inactive state. A programmable frame rate divider and a word length divider are used for frame rate sync signal generation.

The following figure shows a block diagram of the clock generator for the transmit section. The serial bit clock can be internal or external, depending on the TCR[TXDIR] bit. The receive section contains an equivalent clock generator circuit.




Figure 51-56. I<sup>2</sup>S transmit clock generator block diagram

The following figure shows the frame sync generator block for the transmit section. When internally generated, both receive and transmit frame sync are generated from the word clock and are defined by the frame rate divider (DC) bits and the word length (WL) bits of the TCCR. The receive section contains an equivalent circuit for the frame sync generator.






Figure 51-57. I<sup>2</sup>S transmit frame sync generator block diagram

## 51.4.2.2 DIV2, PSR and PM bits description

The bit clock frequency can be calculated from the I<sup>2</sup>S serial system clock using id-73884.

#### **Note**

You must ensure that the bit-clock frequency must be 5 times the peripheral clock frequency. The oversampling clock frequency can go up to peripheral clock frequency. Bits DIV2, PSR and PM must not be cleared at the same time.

$$f_{INT\_BIT\_CLK} = \frac{I^2 S serial system clock}{(DIV2+1) \times (7 \times PSR+1) \times (PM+1) \times 2}$$

From this, the frame clock frequency can be calculated:

$$f_{FS\_CLK} = \frac{f_{INT\_BIT\_CLK}}{(DC+1) \times (2 \times (WL+1))}$$

Figure 51-58. I<sup>2</sup>S bit clock equation

For example, if the  $I^2S$  oversampling clock (network clock) is 12.288 MHz, in 8-bit word normal mode with DC = 1, PM = 47, PSR = 0, DIV2 = 1, a bit clock rate of 64 kHz is generated. Since the 8-bit word rate is equal to one (i.e. normal mode), the sampling rate (or frame sync rate) would then be  $64/(1\times8) = 8$  kHz.



In the next example, the oversampling clock (network clock) clock is 11.2896 MHz. A 16-bit word network mode with TCCR[DC] = 1, TCCR[PM] = 3, TCCR[PSR] = 0, TCCR[DIV2] = 0, a bit clock rate of 1.4112 MHz is generated. Since the 16-bit word rate is equal to two, the sampling rate (or frame sync rate) would be  $1.4112/(2\times16) = 44.1$  kHz.

The following table shows examples of programming the TCCR[PSR] and TCCR[PM] bits to generate various bit clock (STCK) frequencies.

Table 51-51. I<sup>2</sup>S bit clock and frame rate as a function of PSR, PM, and DIV2

		MCLK/network clock		тс	CR			Bit clock	Frame
Bits/ word	Words/ frame	freq (MHz)	DIV2	PSR	PM	WL	DC	(kHz) STCK	rate (kHz)
16	1	12.288	0	0	47	7	0	128	8
16	2	12.288	0	0	23	7	1	256	8
16	4	12.288	0	0	11	7	3	512	8
16	1	12.288	0	0	31	7	0	192	12
16	2	12.288	0	0	15	7	1	384	12
16	4	12.288	0	0	7	7	3	768	12
16	1	12.288	0	0	23	7	0	256	16
16	2	12.288	0	0	11	7	1	512	16
16	4	12.288	0	0	5	7	3	1024	16
16	1	12.288	0	0	15	7	0	384	24
16	2	12.288	0	0	7	7	1	768	24
16	4	12.288	0	0	3	7	3	1536	24
16	1	12.288	0	0	11	7	0	512	32
16	2	12.288	0	0	5	7	1	1024	32
16	4	12.288	0	0	2	7	3	2048	32
16	1	12.288	0	0	15	7	0	768	48
16	2	12.288	0	0	3	7	1	1536	48
16	4	12.288	0	0	1	7	3	3072	48
16	1	11.2896	0	0	31	7	0	176.4	11.025
16	2	11.2896	0	0	15	7	1	352.8	11.025
16	4	11.2896	0	0	7	7	3	705.6	11.025
16	1	11.2896	0	0	15	7	0	352.8	22.05
16	2	11.2896	0	0	7	7	1	705.6	22.05
16	4	11.2896	0	0	3	7	3	1411.2	22.05

Table continues on the next page...



Table 51-51. I<sup>2</sup>S bit clock and frame rate as a function of PSR, PM, and DIV2 (continued)

<b>-</b> /	,	MCLK/network clock		TC	CR	Bit clock	Frame			
Bits/ word	Words/ frame	freq (MHz)	DIV2	PSR	PM	WL	DC	(kHz)	rate	
		,						STCK	(kHz)	
16	1	11.2896	0	0	7	7	0	705.6	44.1	
16	2	11.2896	0	0	3	7	1	1411.2	44.1	
16	4	11.2896	0	0	1	7	3	2822.4	44.1	

The table below shows an example of programming clock controller divider ratios to generate the appropriate oversampling clock and peripheral clock frequencies for various sampling rates. In these examples, the master mode is selected either by setting  $I^2S$  master bit (CR[I2SMODE] = 01b) or individually programming the  $I^2S$  in network, synchronous, transmit internal mode. (The table specifically illustrates the  $I^2S$  mode frequencies/sample rates). The oversampling clock is network clock.

 $I^2S$  master mode requires a 32-bit word length, regardless of the actual data type. Consequently, the fixed  $I^2S$  frame rate of 64 bits per frame (word length (TCCR[WL]) can be any value) and TCCR[DC] = 1 are assumed.

Table 51-52. I<sup>2</sup>S system clock, bit clock, frame clock in master mode

Sampling/frame		MCLK/network		CR		Bit clk (kHz)	
rate (kHz)	Over- sampling rate	clock freq (MHz)	DIV2	PS R	РМ	STCK	
44.10	384	16.934	0	0	2	2822.33	
22.05	384	16.934	0	0	5	1411.17	
11.025	384	16.934	0	0	11	705.58	
48.00	256	12.288	0	0	1	3072	

# 51.4.3 External frame and clock operation

When applying external frame sync and clock signals to I<sup>2</sup>S, there should be at least four bit-clock cycles between the enabling of the transmit or receive section and the rising edge of the corresponding frame sync signal. The transition of TFS or RFS should be synchronized with the rising edge of external clock signal, STCK or SRCK.



# 51.4.3.1 Supported data alignment formats

The I<sup>2</sup>S supports three data formats to provide flexibility with handling data. These formats dictate how data is written to (and read from) the data registers. Therefore, data can appear in different places in TX0/1 and RX0/1 based on the data format and the number of bits per word. Independent data formats are supported for both the transmitter and receiver (that is, the transmitter and receiver can use different data formats).

The supported data formats are:

- msb alignment
- 1sb alignment
  - Zero-extended (receive data only)
  - Sign-extended (receive data only)

With msb alignment, the most significant byte is bits 31 through 24 of the data register if the word length is larger than or equal to 16 bits. If the word length is less than 16 bits and msb alignment is chosen, the most significant byte is bits 15–8. With lsb alignment, the least significant byte is bits 7–0. Data alignment is controlled by the TCR[TXBIT0] bit and the RCR[RXBIT0] bit. See the following table for the bit assignment for all the data formats supported by the I<sup>2</sup>S.

Bit number **Format** 13 4 15 7 2 <u>၂</u> ၈ 💩 17 ည 4 |ω |α 7:0 8-bit Isb aligned 7:0 8-bit msb aligned 10-bit lsb aligned 9:0 10-bit msb aligned 9:0 12-bit lsb aligned 11:0 12-bit msb aligned 11:0 15:0 16-bit lsb aligned 15:0 16-bit msb aligned 18-bit lsb aligned 17:0 18-bit msb aligned 17:0 19:0 20-bit lsb aligned 20-bit msb aligned 19:0 22-bit lsb aligned 21:0 22-bit msb aligned 21:0

Table 51-53. Data alignment

Table continues on the next page...



## Table 51-53. Data alignment (continued)

24-bit lsb aligned					23:0				
24-bit msb aligned		_			23:0				

In addition, if lsb alignment is selected, the receive data can be zero-extended or sign-extended.

- In zero-extension, all bits above the most significant bit are 0s. This format is useful when data is stored in a pure integer format.
- In sign-extension, all bits above the most significant bit are equal to the most significant bit. This format is useful when data is stored in a fixed-point integer format (which implies fractional values).

The RCR[RXEXT] bit controls receive data extension. Transmit data used with 1sb alignment has no concept of sign/zero-extension. Unused bits above the most significant bit are simply ignored.

When configured in I<sup>2</sup>S or AC97 mode, the I<sup>2</sup>S forces the selection of lsb alignment. However, RXEXT chooses zero-extension and sign-extension.

# 51.4.4 Receive interrupt enable bit description

If the receive FIFO is not enabled and the IER[RIE] and CR[RE] bits are set:

- an interrupt occurs when the corresponding I<sup>2</sup>S receive data ready (ISR[RDR0/1]) bit is set
- one value can be read from the RX register (one each in two-channel mode)

If the receive FIFO is enabled and the IER[RIE] and CR[RE] bits are set:

- an interrupt occurs when either of the I<sup>2</sup>S receive FIFO full (ISR[RFF0/1) bits is set
- a maximum of 15 values are available to be read (15 values per channel in two-channel mode)

If the IER[RIE] bit is cleared, these interrupts are disabled. However, the RFF0/1 and RDR0/1 bits indicate the receive data register full condition. Reading the RX registers clears the ISR[RDR] bits, thus clearing the pending interrupt. Two receive data interrupts (two per channel in two-channel mode) are available: receive data with exception status and receive data without exception. The following table shows the conditions under which these interrupts are generated.



## Table 51-54. I<sup>2</sup>S receive data interrupts

Interrupt	RIE	ROEn	RFFn/RDRn
Receive data 0 interru	ipts (n = 0)		
Receive data 0 (with exception status)	1	1	1
Receive data 0 (without exception)	1	0	1
Receive data 1 interru	ipts (n = 1)		
Receive data 1 (with exception status)	1	1	1
Receive data 1 (without exception)	1	0	1

# 51.4.5 Transmit interrupt enable bit description

If the transmit FIFO is not enabled and the IER[TIE] and CR[TE] bits are set:

- an interrupt occurs when the corresponding I<sup>2</sup>S transmit data register empty (ISR[TDE0/1]) flag is set
- one value can be written to the I<sup>2</sup>S\_TX0 register (one per channel, in two-channel mode using I<sup>2</sup>S\_TX1)

If the transmit FIFO is enabled and the IER[TIE] and CR[TE] bits are set:

- an interrupt occurs when either of the I<sup>2</sup>S transmit FIFO empty (ISR[TFE0/1]) flags is set
- a maximum of 15 values can be written to the I<sup>2</sup>S (15 per channel in two-channel mode, using Tx FIFO 1)

When the IER[TIE] bit is cleared, all transmit interrupts are disabled. However, the ISR[TDE0/1] bits always indicate the corresponding TX register empty condition, even when the transmitter is disabled by the transmit enable (CR[TE]) bit. Writing data to the TX clears the corresponding ISR[TDE] bit, thus clearing the interrupt.

Two transmit data interrupts are available (four in two-channel mode, two per channel): transmit data with exception status and transmit data without exceptions. The following table shows the conditions under which these interrupts are generated.

Table 51-55. I<sup>2</sup>S transmit data interrupts

Interrupt	TIE	TUEn	TFEn/TDEn
Transmit data 0 interru	upts (n = 0)		
Transmit data 1 (with exception status)	1	1	1

Table continues on the next page...



## Table 51-55. I<sup>2</sup>S transmit data interrupts (continued)

Interrupt	TIE	TUEn	TFEn/TDEn				
Transmit data 1 (without exception)	1	0	1				
Transmit data 1 interrupts (n = 1)							
Transmit data 0 (with exception status)	1	1	1				
Transmit data 0 (without exception)	1	0	1				

## 51.4.6 Internal frame and clock shutdown

During transmit/receive operation, clearing TE/RE stops data transmission/reception when the current frame ends. If the CR[TFRCLKDIS, RFRCLKDIS] bit is set in the current or previous frames, the I<sup>2</sup>S stops driving the frame sync and clock signals when the current frame ends. After this, the TCRTFRC]] and TCR[RFRC] status bits are set to indicate the frame completion state. If TE is cleared four clock cycles before the next frame, an extra invalid frame is generated.

The following figure is an illustration of transmission case where:

- TCR[TXDIR] and TCR[TFDIR] are set
- CR[TE] is cleared
- CR[TFRCLKDIS] is set during the current or previous frame




Figure 51-59. CR[TFRCLKDIS] assertion in current or previous frame as CR[TE] is Disabled

If CR[TFRCLKDIS or RFRCLKDIS] bit is not set while CR[TE or RE] is cleared, the I<sup>2</sup>S continues generating frame sync and clock signals (if direction is from the I<sup>2</sup>S), Upun setting CR[TFRCLKDIS or RFRCLKDIS], the I<sup>2</sup>S stops driving these signals at the end of the current frame. Following this, the TFRC/RFRC status bits are set to indicate the frame completion state.



The following figure is illustrates a transmission case where:

- TCR[TXDIR] and TCR[TFDIR] are set
- CR[TFRCLKDIS] is set a few frames after clearing CR[TE]
- ISR[TRFC] is set at the frame boundary after CR[TE] is cleared. Once software services this interrupt and later sets CR[TFRCLKDIS] bit, the ISR[TRFC] bit is set again at next frame boundary.




Figure 51-60. CR[TFRCLKDIS] assertion in subsequent frame after disabling CR[TE]

## 51.4.7 Reset

The  $I^2S$  is affected by the following types of reset:

- Power-on reset—This reset clears the CR[I2SEN] bit, which disables the I<sup>2</sup>S. All other status and control bits in the I<sup>2</sup>S are affected as described in Memory map/register definition.
- I<sup>2</sup>S reset—The I<sup>2</sup>S reset is generated when the CR[I2SEN] bit is cleared. The I<sup>2</sup>S status bits are reset to the same state produced by the power-on reset. The I<sup>2</sup>S control bits, including those in CR register, are unaffected. The I<sup>2</sup>S reset is useful for selective reset of the I<sup>2</sup>S, without changing the present I<sup>2</sup>S control bits and without affecting other peripherals.

# 51.5 Initialization/application information

The correct sequence to initialize the  $I^2S$  is as follows:

1. Issue a power-on or  $I^2S$  reset (CR[I2SEN] = 0).



#### unualization/application information

- 2. Set all control bits for configuring the  $I^2S$  (see the following table ).
- 3. Enable appropriate interrupts/DMA requests through IER.
- 4. Set the CR[I2SEN] bit to enable the  $I^2S$ .
- 5. In AC97 mode, set the ACNT[AC97EN] bit after programming the ATAG register (if needed, for AC97 Fixed mode).
- 6. In AC97 fixed mode, do not program the slot request bits without programming the frame valid bits in ATAG register.
- 7. In gated clock mode, refer to Table 51-3.
- 8. Set CR[TE/RE] bits.

To ensure proper operation of the  $I^2S$ , use the power-on or  $I^2S$  reset before changing any of the  $I^2S$  control bits listed in the following table.

#### **Note**

These control bits should not be changed when the I<sup>2</sup>S module is enabled

Table 51-56. I<sup>2</sup>S control bits requiring I<sup>2</sup>S to be disabled before change

Control Register	Bit
CR	[9]=CLKIST
	[8]=TCHEN
	[7]=SYSCLKEN
	[6:5]=I2SMODE
	[4]=SYN
	[3]=NET
IER	[22]=RDMAE
	[20]=TDMAE

Table continues on the next page...



# Table 51-56. I<sup>2</sup>S control bits requiring I<sup>2</sup>S to be disabled before change (continued)

Control Register	Bit
RCR	[9]=RXBIT0
TCR	[9]=TXBIT0
	[8]=RFEN1
	[8]=TFEN1
	[7]=RFEN0
	[7]=TFEN0
	[6]=RFDIR
	[6]=TFDIR
	[5]=RXDIR
	[5]=TXDIR
	[4]=RSHFD
	[4]=TSHFD
	[3]=RSCKP
	[3]=TSCKP
	[2]=RFSI
	[2]=TFSI
	[1]=RFSL
	[1]=TFSL
	[0]=REFS
	[0]=TEFS
RCCR	[16]=WL3
TCCR	[15]=WL2
	[14]=WL1
	[13]=WL0
ACNT	[1]=FV
	[10:5]=FRDIV
PHCONFIG	[10:7]=CLKSRCSEL
	[0:2]=GAINSEL



unualization/application information



# Chapter 52 General purpose input/output (GPIO)

## 52.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The general purpose input and output (GPIO) module interfaces to the processor core via a zero wait state interface for maximum pin performance. Accesses of any data size are supported to the GPIO registers.

The GPIO data direction and output data registers control the direction and output data of each pin when the pin is configured for the GPIO function. The GPIO input data register displays the logic value on each pin when the pin is configured for any digital function, provided the corresponding port control and interrupt module for that pin is enabled.

Efficient bit banging of the general purpose outputs is supported through the addition of set, clear and toggle write-only registers for each port output data register.

## 52.1.1 Features

- Rapid general purpose input and output
  - Pin input data register visible in all digital pin-muxing modes
  - Pin output data register with corresponding set/clear/toggle registers
  - Pin data direction register
  - Zero wait state access to GPIO registers

# 52.1.2 Modes of operation



muroduction

## 52.1.2.1 Run mode

In run mode, the GPIO operates normally.

## 52.1.2.2 Wait mode

In wait mode, the GPIO operates normally.

# 52.1.2.3 Stop mode

The GPIO is disabled in stop mode, although the pins retain their state.

# **52.1.2.4** Debug mode

In debug mode, the GPIO operates normally.

# 52.1.3 GPIO signal descriptions

Table 52-1. GPIO signal descriptions

Signal	Description	1/0
PORTA[31:0]	General purpose input/output	I/O
PORTB[31:0]	General purpose input/output	I/O
PORTC[31:0]	General purpose input/output	I/O
PORTD[31:0]	General purpose input/output	I/O
PORTE[31:0]	General purpose input/output	I/O

#### NOTE

Not all pins within each port are implemented on each device. Refer to the Signal Multiplexing chapter for the number of GPIO ports available in the device.



# 52.1.3.1 Detailed signal description

# Table 52-2. GPIO interface-detailed signal descriptions

Signal	I/O	Description		
PORTA[31:0]	I/O	General purpose input/output.		
PORTB[31:0]		State meaning	Asserted - pin is logic one.	
PORTC[31:0]			Negated - pin is logic zero.	
PORTD[31:0] PORTE[31:0]		Timing	Assertion - when output, occurs on rising edge of the system clock. For input, may occur at any time and input may be asserted asynchronously to the system clock.	
			Negation - when output, occurs on rising edge of the system clock. For input, may occur at any time and input may be asserted asynchronously to the system clock.	

# 52.2 Memory map and register definition

Any read or write access to the GPIO memory space that is outside the valid memory map results in a bus error. All register accesses complete with zero wait states, except error accesses which complete with one wait state.

## **GPIO** memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400F_F000	Port Data Output Register (GPIOA_PDOR)	32	R/W	0000_0000h	52.2.1/ 1508
400F_F004	Port Set Output Register (GPIOA_PSOR)	32	W (always reads zero)	0000_0000h	52.2.2/ 1508
400F_F008	Port Clear Output Register (GPIOA_PCOR)	32	W (always reads zero)	0000_0000h	52.2.3/ 1509
400F_F00C	Port Toggle Output Register (GPIOA_PTOR)	32	W (always	0000_0000h	52.2.4/ 1509

Table continues on the next page...



#### wemory map and register definition

# **GPIO** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
			reads zero)		
400F_F010	Port Data Input Register (GPIOA_PDIR)	32	R	0000_0000h	52.2.5/ 1510
400F_F014	Port Data Direction Register (GPIOA_PDDR)	32	R/W	0000_0000h	52.2.6/ 1510
400F_F040	Port Data Output Register (GPIOB_PDOR)	32	R/W	0000_0000h	52.2.1/ 1508
400F_F044	Port Set Output Register (GPIOB_PSOR)	32	W (always reads zero)	0000_0000h	52.2.2/ 1508
400F_F048	Port Clear Output Register (GPIOB_PCOR)	32	W (always reads zero)	0000_0000h	52.2.3/ 1509
400F_F04C	Port Toggle Output Register (GPIOB_PTOR)	32	W (always reads zero)	0000_0000h	52.2.4/ 1509
400F_F050	Port Data Input Register (GPIOB_PDIR)	32	R	0000_0000h	52.2.5/ 1510
400F_F054	Port Data Direction Register (GPIOB_PDDR)	32	R/W	0000_0000h	52.2.6/ 1510
400F_F080	Port Data Output Register (GPIOC_PDOR)	32	R/W	0000_0000h	52.2.1/ 1508
400F_F084	Port Set Output Register (GPIOC_PSOR)	32	W (always reads zero)	0000_0000h	52.2.2/ 1508
400F_F088	Port Clear Output Register (GPIOC_PCOR)	32	W (always reads zero)	0000_0000h	52.2.3/ 1509
400F_F08C	Port Toggle Output Register (GPIOC_PTOR)	32	W (always reads zero)	0000_0000h	52.2.4/ 1509
400F_F090	Port Data Input Register (GPIOC_PDIR)	32	R	0000_0000h	52.2.5/ 1510
400F_F094	Port Data Direction Register (GPIOC_PDDR)	32	R/W	0000_0000h	52.2.6/ 1510
400F_F0C0	Port Data Output Register (GPIOD_PDOR)	32	R/W	0000_0000h	52.2.1/ 1508

Table continues on the next page...




# **GPIO** memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
400F_F0C4	Port Set Output Register (GPIOD_PSOR)	32	W (always reads zero)	0000_0000h	52.2.2/ 1508
400F_F0C8	Port Clear Output Register (GPIOD_PCOR)	32	W (always reads zero)	0000_0000h	52.2.3/ 1509
400F_F0CC	Port Toggle Output Register (GPIOD_PTOR)	32	W (always reads zero)	0000_0000h	52.2.4/ 1509
400F_F0D0	Port Data Input Register (GPIOD_PDIR)	32	R	0000_0000h	52.2.5/ 1510
400F_F0D4	Port Data Direction Register (GPIOD_PDDR)	32	R/W	0000_0000h	52.2.6/ 1510
400F_F100	Port Data Output Register (GPIOE_PDOR)	32	R/W	0000_0000h	52.2.1/ 1508
400F_F104	Port Set Output Register (GPIOE_PSOR)	32	W (always reads zero)	0000_0000h	52.2.2/ 1508
400F_F108	Port Clear Output Register (GPIOE_PCOR)	32	W (always reads zero)	0000_0000h	52.2.3/ 1509
400F_F10C	Port Toggle Output Register (GPIOE_PTOR)	32	W (always reads zero)	0000_0000h	52.2.4/ 1509
400F_F110	Port Data Input Register (GPIOE_PDIR)	32	R	0000_0000h	52.2.5/ 1510
400F_F114	Port Data Direction Register (GPIOE_PDDR)	32	R/W	0000_0000h	52.2.6/ 1510



# 52.2.1 Port Data Output Register (GPIOx\_PDOR)



## GPIOx\_PDOR field descriptions

Field	Description
31–0 PDO	Port Data Output Unimplemented pins for a particular device read as zero.
	<ul> <li>Logic level 0 is driven on pin provided pin is configured for General Purpose Output.</li> <li>Logic level 1 is driven on pin provided pin is configured for General Purpose Output.</li> </ul>

# 52.2.2 Port Set Output Register (GPIOx\_PSOR)


```
Addresses: GPIOA_PSOR is 400F_F000h base + 4h offset = 400F_F004h

GPIOB_PSOR is 400F_F040h base + 4h offset = 400F_F044h

GPIOC_PSOR is 400F_F080h base + 4h offset = 400F_F084h

GPIOD_PSOR is 400F_F0C0h base + 4h offset = 400F_F0C4h

GPIOE_PSOR is 400F_F100h base + 4h offset = 400F_F104h
```



## **GPIOx\_PSOR** field descriptions


Field	Description
31–0 PTSO	Port Set Output
	Writing to this register will update the contents of the corresponding bit in the Port Data Output Register (PDOR) as follows:
	0 Corresponding bit in PDORn does not change.
	1 Corresponding bit in PDORn is set to logic one.

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# 52.2.3 Port Clear Output Register (GPIOx\_PCOR)

Addresses: GPIOA\_PCOR is 400F\_F000h base + 8h offset = 400F\_F008h GPIOB\_PCOR is 400F\_F040h base + 8h offset = 400F\_F048h GPIOC\_PCOR is 400F\_F080h base + 8h offset = 400F\_F088h GPIOD\_PCOR is 400F\_F0C0h base + 8h offset = 400F\_F0C8h GPIOE\_PCOR is 400F\_F100h base + 8h offset = 400F\_F108h




## GPIOx\_PCOR field descriptions

Field	Description
31–0 PTCO	Port Clear Output  Writing to this register will update the contents of the corresponding bit in the Port Data Output Register (PDOR) as follows:
	<ul><li>0 Corresponding bit in PDORn does not change.</li><li>1 Corresponding bit in PDORn is set to logic zero.</li></ul>

# 52.2.4 Port Toggle Output Register (GPIOx\_PTOR)

Addresses: GPIOA\_PTOR is 400F\_F000h base + Ch offset = 400F\_F00Ch
GPIOB\_PTOR is 400F\_F040h base + Ch offset = 400F\_F04Ch
GPIOC\_PTOR is 400F\_F080h base + Ch offset = 400F\_F08Ch
GPIOD\_PTOR is 400F\_F0C0h base + Ch offset = 400F\_F0CCh
GPIOE\_PTOR is 400F\_F100h base + Ch offset = 400F\_F10Ch



## GPIOx\_PTOR field descriptions

Field	Description
31–0 PTTO	Port Toggle Output  Writing to this register will update the contents of the corresponding bit in the Port Data Output Register (PDOR) as follows:




#### memory map and register definition

# **GPIOx\_PTOR** field descriptions (continued)

Field	Description
	0 Corresponding bit in PDORn does not change.
	1 Corresponding bit in PDORn is set to the inverse of its existing logic state.

# 52.2.5 Port Data Input Register (GPIOx\_PDIR)



## **GPIOx\_PDIR** field descriptions

Field	Description
31–0 PDI	Port Data Input
	Unimplemented pins for a particular device read as zero. Pins that are not configured for a digital function read as zero. If the corresponding Port Control and Interrupt module is disabled, then that Port Data Input Register does not update.
	<ul> <li>0 Pin logic level is logic zero or is configured for use by digital function.</li> <li>1 Pin logic level is logic one.</li> </ul>

# 52.2.6 Port Data Direction Register (GPIOx\_PDDR)

The PDDR configures the individual port pins for input or output.

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## **GPIOx\_PDDR** field descriptions

Field	Description
31–0 PDD	Port data direction
	0 Pin is configured as general purpose input, if configured for the GPIO function
	1 Pin is configured for general purpose output, if configured for the GPIO function

# 52.3 Functional description

# 52.3.1 General purpose input

The logic state of each pin is available via the pin data input registers, provided the pin is configured for a digital function and the corresponding port control and interrupt module is enabled.

The pin data input registers return the synchronized pin state after any enabled digital filter in the port control and interrupt module. The input pin synchronizers are shared with the port control and interrupt module, so that if the corresponding port control and interrupt module is disabled then synchronizers are also disabled. This reduces power consumption when a port is not required for general purpose input functionality.

# 52.3.2 General purpose output

The logic state of each pin can be controlled via the pin data output registers and pin output enable registers, provided the pin is configured for the GPIO function.

If a pin is configured for the GPIO function and the corresponding data output enable register bit is clear then the pin is configured as an input.

If a pin is configured for the GPIO function and the corresponding pin data output enable register bit is set then the pin is configured as an output and the logic state of the pin is equal to the corresponding pin data output register.

To facilitate efficient bit banging on the general purpose outputs, pin data set, pin data clear and pin data toggle registers exist to allow one or more outputs within the one port to be set, cleared or toggled from a single register write.

The corresponding port control and interrupt module does not need to be enabled to update the state of the pin output enable registers and pin data output registers (including the set/clear/toggle registers).





## **Chapter 53 Touch sense input (TSI)**

#### 53.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The touch sensing input (TSI) module provides capacitive touch sensing detection with high sensitivity and enhanced robustness. Each TSI pin implements the capacitive measurement of an electrode having individual programmable detection thresholds and result registers. The TSI module can be functional in several low power modes with ultra low current adder and waking up the CPU in a touch event. It provides a solid capacitive measurement module for the implementation of touch keypad, rotaries and sliders.

## 53.2 Features

- Support as many as 16 input capacitive touch sensing pins with individual result registers
- Automatic detection of electrode capacitance change with programmable upper and lower threshold
- Automatic periodic scan unit with different duty cycles for run and low power modes
- Full support with FSL touch sensing SW library (TSS) for the implementation of keypads, rotaries and sliders
- Operation across all low power modes: Wait,Stop, VLPR, VLPW, VLPS, LLS,VLLS{3,2,1}
- Capability to wake up MCU from low power modes
- Configurable interrupts:
  - End-of-scan or out-of-range interrupt
  - TSI error interrupts: pad short to  $V_{DD}/V_{SS}$  or conversion overrun
- Compensate temperature and supply voltage variations
- Stand alone operation not requiring any external crystal even in low power modes



#### Overview

- Configurable integration of each electrode capacitance measurement from 1 to 4096 times
- Programmable electrode oscillator and TSI Reference Oscillator for high sensitivity, small scan time and low power functionality
- Only uses one pin per electrode implementation with no external hardware required

#### 53.3 Overview

This section presents an overview of the TSI module. The following figure presents the simplified TSI module block diagram.




Figure 53-1. Touch sensing input block diagram

## 53.3.1 Electrode capacitance measurement unit

The electrode capacitance measurement unit senses the capacitance of a TSI pin and outputs a 16-bit result. This module is based in dual oscillator architecture. One oscillator is connected to the external electrode array and oscillates according to the electrode



capacitance, while the other according to an internal reference capacitor. The pin capacitance measurement is given by the counted number of periods of the reference oscillator during a configurable number of oscillations of the external electrode oscillator.

The electrode oscillator charges and discharges the pin capacitance with a programmable 5-bit binary current source in order to accommodate different sizes of electrode capacitance. The electrode oscillator frequency, before being compared to that of the reference oscillator, goes through a prescaler and modulo counter to decrease its frequency and consecutively increase the measurement resolution and noise robustness.

The following figure presents the simplified block diagram of how the electrode capacitance is measured.




Figure 53-2. TSI capacitance measurement unit block diagram

#### 53.3.2 Electrode scan unit

This section describes the functionality of the electrode scan unit. It is responsible for triggering the start of the active electrode scan.

The touch sense input module needs to periodically scan all active electrodes to determine if a touch event has occurred. The electrode scan unit has two independent scan periods, one for TSI active mode and the other for TSI low power mode. This independent control allows the application to configure longer scan period during low power mode, so contributing to smaller average power consumption. The TSI, in low power mode, has the capability to wake the CPU upon an electrode capacitance change. When the CPU wakes, the TSI enters active mode, and produces a shorter scan period for a faster response and more robust touch detection. Apart from the periodical mode, the



#### woues of operation

electrode scan unit also allows software triggering of the electrode scans. This feature is very useful for initialization of the touch application to detect the initial electrode capacitances. This module generates configurable end-of-scan interrupt to indicate the application that all electrodes were scanned. If a new electrode scan is started while the previous one is still in progress, an overrun error flag is generated, TSI continues the previous scan sequence and the latest trigger is ignored.

#### 53.3.3 Touch detection unit

The touch detection unit indicates the change in the pin capacitance. This module compares the pin capacitance value in the result register with a pre-configured low and high threshold. If the capacitance result register value is outside the ranges defined by the upper and lower threshold, the touch detection unit generates an out-of-range flag to indicate a pin capacitance change.

The upper and lower threshold values are configurable allowing the application to select the magnitude of the capacitance change to trigger the out-of-range flag. With the threshold values programmed properly the application noise level does not cause frequent CPU interrupts, so minimizes the CPU touch application usage. This feature also allows the TSI to wake up the CPU from low power modes only in a capacitance change event.

## 53.4 Modes of operation

The TSI module has three operation modes: disabled, active mode and low power mode.

#### 53.4.1 TSI disabled mode

When GENCS[TSIEN] is cleared, the TSI module is disabled.

## 53.4.2 TSI active mode

In active mode, the TSI module has its full functionality, being able to scan up to 16 electrodes. The TSI can be in active mode with the MCU in Run, Wait, VLPR, and VLPW modes, and the TSI can run in low power mode (only one electrode scanning in Stop, VLPS, LLS, and VLLSx modes).

Three clock sources can be selected for the TSI module in active mode: BUS\_CLK, MCGIRCLK and OSCERCLK.



## 53.4.3 TSI low power mode

The TSI module enters low power mode if the GENCS[STPE] is set to one and the MCU is programmed into one of the following operational modes: LLS, VLLS1, VLLS2 or VLLS3. In low power mode, only one selectable pin is active, being able to perform capacitance measurements. The scan period is defined by GENCS[LPSCNITV]. Two low power clock sources are available in the TSI low power mode, LPOCLK and VLPOSCCLK, being selected by the GENCS[LPCLKS].

In low power mode the TSI interrupt can also be configured as end-of-scan or out-of-range and the GENCS[TSIIEN] must be set in order to generate these interrupts. The TSI interrupt causes the exit of the low power mode, entrance into the active mode, and the MCU wake up.

In low power mode the electrode scan unit is always configured to periodical low power scan.

## 53.4.4 Block diagram

The following figure shows the block diagram of TSI module.




Figure 53-3. TSI block diagram



## 53.5 TSI signal descriptions

The TSI module has up to 16 external pins for touch sensing. The table below itemizes all the TSI external pins.

Table 53-1. TSI signal descriptions

Signal	Description	I/O
TSI_IN[15:0]	TSI pins. Switchable driver that connects directly to the electrode pins TSI[15:0] can operate as GPIO pins	I/O

## 53.5.1 TSI\_IN[15:0]

When TSI functionality is enabled by the PEN[PEN], the TSI analog portion uses corresponding TSICHn to connect external on-board touch capacitors. The connection between the pin and the touch pad must be kept as short as possible to reduce distribution capacity on board that will add to the system base capacitance.

## 53.6 Memory map and register definition

This section presents the touch sensing input module memory map and registers definition.

TSI memory map

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_5000	General Control and Status Register (TSI0_GENCS)	32	R/W	0000_0000h	53.6.1/ 1520
4004_5004	SCAN control register (TSI0_SCANC)	32	R/W	0000_0000h	53.6.2/ 1523
4004_5008	Pin enable register (TSI0_PEN)	32	R/W	0000_0000h	53.6.3/ 1526
4004_500C	Status Register (TSI0_STATUS)	32	w1c	0000_0000h	53.6.4/ 1529
4004_5100	Counter Register (TSI0_CNTR1)	32	R	0000_0000h	53.6.5/ 1532



## TSI memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_5104	Counter Register (TSI0_CNTR3)	32	R	0000_0000h	53.6.5/ 1532
4004_5108	Counter Register (TSI0_CNTR5)	32	R	0000_0000h	53.6.5/ 1532
4004_510C	Counter Register (TSI0_CNTR7)	32	R	0000_0000h	53.6.5/ 1532
4004_5110	Counter Register (TSI0_CNTR9)	32	R	0000_0000h	53.6.5/ 1532
4004_5114	Counter Register (TSI0_CNTR11)	32	R	0000_0000h	53.6.5/ 1532
4004_5118	Counter Register (TSI0_CNTR13)	32	R	0000_0000h	53.6.5/ 1532
4004_511C	Counter Register (TSI0_CNTR15)	32	R	0000_0000h	53.6.5/ 1532
4004_5120	Channel n threshold register (TSI0_THRESHLD0)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5124	Channel n threshold register (TSI0_THRESHLD1)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5128	Channel n threshold register (TSI0_THRESHLD2)	32	R/W	0000_0000h	53.6.6/ 1533
4004_512C	Channel n threshold register (TSI0_THRESHLD3)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5130	Channel n threshold register (TSI0_THRESHLD4)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5134	Channel n threshold register (TSI0_THRESHLD5)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5138	Channel n threshold register (TSI0_THRESHLD6)	32	R/W	0000_0000h	53.6.6/ 1533
4004_513C	Channel n threshold register (TSI0_THRESHLD7)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5140	Channel n threshold register (TSI0_THRESHLD8)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5144	Channel n threshold register (TSI0_THRESHLD9)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5148	Channel n threshold register (TSI0_THRESHLD10)	32	R/W	0000_0000h	53.6.6/ 1533
4004_514C	Channel n threshold register (TSI0_THRESHLD11)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5150	Channel n threshold register (TSI0_THRESHLD12)	32	R/W	0000_0000h	53.6.6/ 1533




#### TSI memory map (continued)

Absolute address (hex)	Register name	Width (in bits)	Access	Reset value	Section/ page
4004_5154	Channel n threshold register (TSI0_THRESHLD13)	32	R/W	0000_0000h	53.6.6/ 1533
4004_5158	Channel n threshold register (TSI0_THRESHLD14)	32	R/W	0000_0000h	53.6.6/ 1533
4004_515C	Channel n threshold register (TSI0_THRESHLD15)	32	R/W	0000_0000h	53.6.6/ 1533

## 53.6.1 General Control and Status Register (TSIx\_GENCS)

All GENCS bits can be read at any time, but must not be written while GENCS[SCNIP] is set.

Addresses: TSI0\_GENCS is 4004\_5000h base + 0h offset = 4004\_5000h



#### TSIx\_GENCS field descriptions

Field	Description
31 Reserved	Reserved This field is reserved.
30–29 Reserved	This read-only field is reserved and always has the value zero.
28 LPCLKS	Low Power Mode Clock Source Selection



## TSIx\_GENCS field descriptions (continued)

Field	Description
	0 LPOCLK
	1 VLPOSCCLK
27-24 LPSCNITV	TSI Low Power Mode Scan Interval
2. 33.11.1	0000 1 ms scan interval
	0001 5 ms scan interval
	0010 10 ms scan interval
	0011 15 ms scan interval
	0100 20 ms scan interval
	0101 30 ms scan interval
	0110 40 ms scan interval
	0111 50 ms scan interval
	1000 75 ms scan interval
	1001 100 ms scan interval
	1010 125 ms scan interval
	1011 150 ms scan interval
	1100 200 ms scan interval
	1101 300 ms scan interval
	1110 400 ms scan interval
	1111 500 ms scan interval
23–19 NSCN	Number of Consecutive Scans per Electrode
	00000 1 time per electrode
	00001 2 times per electrode
	00010 3 times per electrode
	00011 4 times per electrode
	00100 5 times per electrode
	00101 6 times per electrode
	00110 7 times per electrode
	00111 8 times per electrode
	01000 9 times per electrode 01001 10 times per electrode
	·
	01010 11 times per electrode 01011 12 times per electrode
	01100 13 times per electrode
	01101 14 times per electrode
	01110 15 times per electrode
	01111 16 times per electrode
	10000 17 times per electrode
	10001 18 times per electrode
	10010 19 times per electrode
	10011 20 times per electrode
	10100 21 times per electrode
	10101 22 times per electrode
	10110 23 times per electrode
	10111 24 times per electrode
	11000 25 times per electrode



#### memory map and register definition

## TSIx\_GENCS field descriptions (continued)

Field	Description
	11001 26 times per electrode 11010 27 times per electrode 11011 28 times per electrode
	11100 29 times per electrode 11101 30 times per electrode 11110 31 times per electrode 11111 32 times per electrode
18–16 PS	Electrode oscillator prescaler  000 Electrode oscillator frequency divided by 1  001 Electrode oscillator frequency divided by 2  010 Electrode oscillator frequency divided by 4  011 Electrode oscillator frequency divided by 8  100 Electrode oscillator frequency divided by 16  101 Electrode oscillator frequency divided by 32  110 Electrode oscillator frequency divided by 64
15 EOSF	111 Electrode oscillator frequency divided by 128  End of scan flag  Write 1 to clear the flag.
14 OUTRGF	Out of Range Flag Write 1 to clear the flag.
13 EXTERF	External electrode error occurred  0 No short  1 Short to VDD or VSS occured on the electrodes
12 OVRF	Overrun error flag  0 No overrun  1 Overrun occurred
11–10 Reserved	This read-only field is reserved and always has the value zero.
9 SCNIP	Scan-in-progress status  Indicates if a scanning process is in progress. This bit is read-only and is changed automatically by the TSI module.
8 SWTS	Software trigger start  Setting this bit starts a scan sequence. Writing zero to this bit has no effect.
7 TSIEN	TSI module enable  0 TSI disabled  1 TSI enabled
6 TSIIE	TSI interrupt enable




#### TSIx\_GENCS field descriptions (continued)

Field	Description
	0 Disable
	1 Enable
5 ERIE	TSI error interrupt Enable
	Caused by a short or overrun error.
	0 Error interrupt disabled
	1 Error interrupt enabled
4 ESOR	End-of-scan or out-of-range interrupt select
	0 Out-of-range interrupt selected
	1 End-of-scan interrupt selected
3 Reserved	Reserved
	This field is reserved.
2	Reserved
Reserved	This field is reserved.
1 STM	Scan trigger mode
	0 Software trigger scan
	1 Periodical scan
0 STPE	TSI stop enable while in low-power modes (STOP, VLPS, LLS, and VLLS{3,2,1})
	0 Disable TSI when MCU enters low-power modes
	1 Allow TSI to continue running in all low power modes

## 53.6.2 SCAN control register (TSIx\_SCANC)

All SCANC bits can be read at any time, but must not be written while GENCS[SCNIP] is set.





K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



#### memory map and register definition

## TSIx\_SCANC field descriptions

Field	Description
31–27	Reference oscillator charge current select
REFCHRG	00000 1 µA charge current
	00001 2 μA charge current 00010 3 μA charge current
	00011 4 μA charge current 00100 5 μA charge current
	00100 5 μA charge current
	00110 7 μA charge current
	00110 7 μA charge current
	01000 9 μA charge current
	01001 10 μA charge current
	01010 11 μA charge current
	01011 12 μA charge current
	01100 13 μA charge current
	01101 14 μA charge current
	01110 15 μA charge current
	01111 16 μA charge current
	10000 17 μA charge current
	10001 18 μA charge current
	10010 19 μA charge current
	10011 20 μA charge current
	10100 21 μA charge current
	10101 22 μA charge current
	10110 23 μA charge current
	10111 24 μA charge current
	11000 25 μA charge current
	11001 26 μA charge current
	11010 27 μA charge current
	11011 28 µA charge current
	11100 29 µA charge current
	11101 30 µA charge current
	11110 31 µA charge current
	11111 32 µA charge current
26–24 CAPTRM	Internal capacitance trim value
CAPTRIVI	000 0.5 pF internal reference capacitance
	001 0.6 pF internal reference capacitance
	010 0.7 pF internal reference capacitance
	011 0.8 pF internal reference capacitance
	100 0.9 pF internal reference capacitance
	101 1.0 pF internal reference capacitance
	110 1.1 pF internal reference capacitance
	111 1.2 pF internal reference capacitance
23–19	External oscillator charge current select
EXTCHRG	00000 1 μA charge current



## TSIx\_SCANC field descriptions (continued)

Field	Description
	00001 2 μA charge current
	00010 3 µA charge current
	00011 4 µA charge current
	00100 5 μA charge current
	00101 6 μA charge current
	00110 7 μA charge current
	00111 8 μA charge current
	01000 9 μA charge current
	01001 10 μA charge current
	01010 11 μA charge current
	01011 12 μA charge current
	01100 13 μA charge current
	01101 14 μA charge current
	01110 15 μA charge current
	01111 16 μA charge current
	10000 17 μA charge current
	10001 18 μA charge current
	10010 19 μA charge current
	10011 20 μA charge current
	10100 21 µA charge current
	10101 22 μA charge current
	10110 23 μA charge current
	10111 24 μA charge current
	11000 25 µA charge current
	11001 26 µA charge current
	11010 27 µA charge current
	11011 28 µA charge current
	11100 29 µA charge current
	11101 30 μA charge current
	11110 31 µA charge current
	11111 32 μA charge current
18–16 DELVOL	Delta voltage select applied to analog oscillators
	000 100 mV delta voltage is applied
	001 150 mV delta voltage is applied
	010 200 mV delta voltage is applied
	011 250 mV delta voltage is applied
	100 300 mV delta voltage is applied
	101 400 mV delta voltage is applied
	110 500 mV delta voltage is applied
	111 600 mV delta voltage is applied
15–8 SMOD	Scan modulo
	00000000 Continuous scan
	Others Scan period modulo
7–6 Reserved	This read-only field is reserved and always has the value zero.



#### wemory map and register definition

#### TSIx\_SCANC field descriptions (continued)

Field	Description
5 AMCLKDIV	Active mode clock divider
	0 Divider set to 1
	1 Divider set to 2048
4–3 AMCLKS	Active mode clock source
	00 Bus Clock
	01 MCGIRCLK
	10 OSCERCLK
	11 Not valid
2-0 AMPSC	Active mode prescaler
	000 Input clock source divided by 1
	001 Input clock source divided by 2
	010 Input clock source divided by 4
	011 Input clock source divided by 8
	100 Input clock source divided by 16
	101 Input clock source divided by 32
	110 Input clock source divided by 64
	111 Input clock source divided by 128

#### 53.6.3 Pin enable register (TSIx\_PEN)


#### **NOTE**

Do not change PEN when GENCS[TSIEN] is set.

#### NOTE

All PEN bits can be read at any time, but must not be written while GENCS[SCNIP] is set.

Addresses: TSI0\_PEN is 4004\_5000h base + 8h offset = 4004\_5008h



#### TSIx\_PEN field descriptions

Field	Description
31–20 Reserved	This read-only field is reserved and always has the value zero.
19–16 LPSP	Low-power scan pin

Table continues on the next page...

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



## TSIx\_PEN field descriptions (continued)

Field	Description							
	Selects which input is active in low-power mode.							
	0000 TSI_IN[0] is active in low power mode							
	0001 TSI_IN[1] is active in low power mode							
	0010 TSI_IN[2] is active in low power mode							
	0011 TSI_IN[3] is active in low power mode							
	0100 TSI_IN[4] is active in low power mode							
	0101 TSI_IN[5] is active in low power mode							
	0110 TSI_IN[6] is active in low power mode							
	0111 TSI_IN[7] is active in low power mode							
	1000 TSI_IN[8] is active in low power mode 1001 TSI_IN[9] is active in low power mode							
	1010 TSI_IN[10] is active in low power mode							
	1011 TSI_IN[11] is active in low power mode							
	1100 TSI_IN[12] is active in low power mode							
	1101 TSI_IN[13] is active in low power mode							
	1110 TSI_IN[14] is active in low power mode							
	1111 TSI_IN[15] is active in low power mode							
15 DEN16	TSI pin 15 enable							
PEN15	0 The corresponding pin is not used by TSI							
	1 The corresponding pin is used by TSI							
14	TSI pin 14 enable							
PEN14								
	<ul><li>The corresponding pin is not used by TSI</li><li>The corresponding pin is used by TSI</li></ul>							
	1 21 1							
13 PEN13	TSI pin 13 enable							
1 21110	0 The corresponding pin is not used by TSI							
	1 The corresponding pin is used by TSI							
12	TSI pin 12 enable							
PEN12	0 The corresponding pin is not used by TSI							
	<ul><li>The corresponding pin is not used by TSI</li><li>The corresponding pin is used by TSI</li></ul>							
11	TSI pin 11 enable							
PEN11	13  piil 11 eliable							
	0 The corresponding pin is not used by TSI							
	1 The corresponding pin is used by TSI							
10	TSI pin 10 enable							
PEN10	0 The corresponding pin is not used by TSI							
	1 The corresponding pin is used by TSI							
9	TSI pin 9 enable							
PEN9								
	O The corresponding pin is not used by TSI							
	1 The corresponding pin is used by TSI							



#### wemory map and register definition

## TSIx\_PEN field descriptions (continued)

Field	Description
8	TSI pin 8 enable
PEN8	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI
7	TSI pin 7 enable
PEN7	
	<ul><li>The corresponding pin is not used by TSI</li><li>The corresponding pin is used by TSI</li></ul>
6 PEN6	TSI pin 6 enable
. 2.10	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI
5	TSI pin 5 enable
PEN5	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI
4	TSI pin 4 enable
PEN4	
	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI
3 PEN3	TSI pin 3 enable
1 2140	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI
2 PEN2	TSI pin 2 enable
	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI
1 PEN1	TSI pin 1 enable
	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI
0 PEN0	TSI pin 0 enable
	0 The corresponding pin is not used by TSI
	1 The corresponding pin is used by TSI



## 53.6.4 Status Register (TSIx\_STATUS)

Addresses: TSI0\_STATUS is 4004\_5000h base + Ch offset = 4004\_500Ch

Bit	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
R	ERROF15	ERROF14	ERROF13	ERROF12	ERROF11	ERROF10	ERROF9	ERROF8	ERROF7	ERROF6	ERROF5	ERROF4	ERROF3	ERROF2	ERROF1	ERROF0
w	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bit	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
R	ORNGF15	ORNGF14	ORNGF13	ORNGF12	ORNGF11	ORNGF10	ORNGF9	ORNGF8	ORNGF7	ORNGF6	ORNGF5	ORNGF4	ORNGF3	ORNGF2	ORNGF1	ORNGF0
w	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c	w1c
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

#### TSIx\_STATUS field descriptions

Field	Description
31 ERROF15	TouchSensing Error Flag 15
	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
30 ERROF14	TouchSensing Error Flag 14
	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
29 ERROF13	TouchSensing Error Flag 13
Entrol 10	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
28 ERROF12	TouchSensing Error Flag 12
LITTOI 12	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
27 ERROF11	TouchSensing Error Flag 11
LIMOTTI	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
26 ERROF10	TouchSensing Error Flag 10



#### memory map and register definition

## TSIx\_STATUS field descriptions (continued)

Field	Description
	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
25 ERROF9	TouchSensing Error Flag 9
Linor	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
24 ERROF8	TouchSensing Error Flag 8
Lintoro	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
23 ERROF7	TouchSensing Error Flag 7
Linor	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
22 ERROF6	TouchSensing Error Flag 6
211110110	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
21 ERROF5	TouchSensing Error Flag 5
Linior	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
20 ERROF4	TouchSensing Error Flag 4
Linor	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
19 ERROF3	TouchSensing Error Flag 3
Linors	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
18 ERROF2	TouchSensing Error Flag 2
LIMOIZ	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
17 ERROF1	TouchSensing Error Flag 1
Linter	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
16 ERROF0	TouchSensing Error Flag 0
2.111010	This bit indicates when the corresponding electrode is shorted to VDD or VSS. If the GENCS[ERIE] bit is set, an error interrupt is generated. Write a one to clear this bit.
15 ORNGF15	Touch Sensing Electrode Out-of-Range Flag 15
CHINGETS	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
14 ORNGF14	Touch Sensing Electrode Out-of-Range Flag 14



## TSIx\_STATUS field descriptions (continued)

Field	Description
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
13 ORNGF13	Touch Sensing Electrode Out-of-Range Flag 13
21.1.3.1.3	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
12 ORNGF12	Touch Sensing Electrode Out-of-Range Flag 12
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
11 ORNGF11	Touch Sensing Electrode Out-of-Range Flag 11
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
10 ORNGF10	Touch Sensing Electrode Out-of-Range Flag 10
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
9 ORNGF9	Touch Sensing Electrode Out-of-Range Flag 9
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
8 ORNGF8	Touch Sensing Electrode Out-of-Range Flag 8
J (G)	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
7 ORNGF7	Touch Sensing Electrode Out-of-Range Flag 7
OHIVOI 1	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
6 ORNGF6	Touch Sensing Electrode Out-of-Range Flag 6
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
5 ORNGF5	Touch Sensing Electrode Out-of-Range Flag 5
2	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
4 ORNGF4	Touch Sensing Electrode Out-of-Range Flag 4
OTHIOL T	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
3 ORNGF3	Touch Sensing Electrode Out-of-Range Flag 3
OTHING! O	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
2 ORNGF2	Touch Sensing Electrode Out-of-Range Flag 2




#### wemory map and register definition

#### TSIx\_STATUS field descriptions (continued)

Field	Description
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.
1 ORNGF1	Touch Sensing Electrode Out-of-Range Flag 1
0 ORNGF0	Touch Sensing Electrode Out-of-Range Flag 0
	This bit indicates when the corresponding electrode is out of range. If the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared, an out-of-range interrupt is generated. Write a one to clear this bit.

## 53.6.5 Counter Register (TSIx\_CNTR)

Addresses: TSI0\_CNTR1 is 4004\_5000h base + 100h offset = 4004\_5100h TSI0\_CNTR3 is 4004\_5000h base + 104h offset = 4004\_5104h TSI0\_CNTR5 is 4004\_5000h base + 108h offset = 4004\_5108h TSI0\_CNTR7 is 4004\_5000h base + 10Ch offset = 4004\_510Ch TSI0\_CNTR9 is 4004\_5000h base + 110h offset = 4004\_5110h TSI0\_CNTR11 is 4004\_5000h base + 114h offset = 4004\_5114h TSI0\_CNTR13 is 4004\_5000h base + 118h offset = 4004\_5118h TSI0\_CNTR15 is 4004\_5000h base + 11Ch offset = 4004\_511Ch



#### TSIx CNTRn field descriptions


Field	Description
31–16 CTN	TouchSensing channel <i>n</i> counter value
15–0 CTN1	TouchSensing channel n-1 counter value



#### 53.6.6 Channel n threshold register (TSIx\_THRESHLD)

All THRESHLD bits can be read at any time, but must not be written while GENCS[SCNIP] is set.

Addresses:  $4004\_5000h$  base + 120h offset +  $(4d \times n)$ , where n = 0d to 15d



#### TSIx\_THRESHLDn field descriptions

Field	Description
31–16 LTHH	Low threshold value
15–0 HTHH	High threshold value

## 53.7 Functional descriptions

This section provides functional description of the TSI module.

## 53.7.1 Capacitance measurement

The electrode pin capacitance measurement uses a dual oscillator approach. The TSI electrode oscillator has its frequency dependable on the external electrode capacitance and the TSI module configuration. After going to a configurable prescaler, the TSI electrode oscillator signal goes to the input of the modulo counter. The time for the external electrode oscillations is measured using the TSI reference oscillator. The measured electrode capacitance is directly proportional to this time.

#### 53.7.1.1 TSI electrode oscillator

The TSI electrode oscillator circuit is illustrated in the following figure. A configurable constant current source is used to charge and discharge the external electrode capacitance. A buffer hysteresis defines the oscillator delta voltage. The delta voltage defines the margin of high and low voltage which are the reference input of the comparator in different time.






Figure 53-64. TSI electrode oscillator circuit

The current source applied to the pad capacitance is 5-bit binary controlled by the SCANC[EXTCHRG]. The hysteresis delta voltage is also configurable and is 3-bit binary controlled by the SCANC[DELVOL]. The figure below shows the voltage amplitude waveform of the electrode capacitance charging and discharging with a programmable current.




Figure 53-65. TSI electrode oscillator chart

The oscillator frequency is given by the following equation:

$$F_{elec} = \frac{I}{2 * C_{elec} * \Delta V}$$

Figure 53-66. Equation 1: TSI electrode oscillator frequency

Where:

I: constant current

C<sub>elec</sub>: electrode capacitance

 $\Delta V$ : Hysteresis delta voltage



So by this equation, for example, an electrode with  $C_{elec}$ = 20 pF, with a current source of I = 16  $\mu$ A and  $\Delta$ V = 600 mV will have the following oscillation frequency:

$$F_{elec} = \frac{16 \ \mu A}{2 * 20pF * 600mV} = 0.67MHz$$

Figure 53-67. Equation 2: TSI electrode oscillator frequency

The current source and hysteresis delta voltage are used to accommodate the TSI electrode oscillator frequency with different electrode capacitance sizes.

#### 53.7.1.2 Electrode oscillator and counter control

The TSI oscillator frequency signal goes through a prescaler defined by the GENCS[PS] and then enters a counter. The bit field GENCS[NSCN] defines the number of scans for each external electrode.

The pin capacitance sampling time is given by the time the module counter takes to go from zero to its maximum value, defined by NSCN. The electrode sample time is expressed by the following equation:

$$T_{cap\_samp} = \frac{PS * NSCN}{F_{elec}}$$

Using Equation 1.

$$T_{cap\_samp} = \frac{2 * PS * NSCN * C_{elec} * \Delta V}{I}$$

Figure 53-68. Equation 3: Electrode sampling time

Where:

PS: prescaler value

NSCN: number of scan

I: constant current

C<sub>elec</sub>: electrode capacitance

ΔV: Hysteresis delta voltage

By this equation, an electrode with C = 20 pF, with a current source of  $I = 16 \mu A$  and  $\Delta V = 600$  mV, PS = 2 and NSCN = 16 will have the following sampling time:



runctional descriptions

$$T_{cap\_samp} = \frac{2*2*16*20pF*600mV}{16\mu A} = 48\mu s$$

#### 53.7.1.3 TSI reference oscillator

The TSI reference oscillator has the same topology of the TSI electrode oscillator. The TSI reference oscillator instead of using an external capacitor for the electrode oscillator has an internal reference capacitor which can be programmable. The SCANC[CAPTRM] defines the internal reference capacitor trimming value \*.

The TSI reference oscillator share the same voltage hysteresis levels defined with the SCANC[DELVOL] and has an independent programmable current source controlled by the SCANC[REFCHRG].

\* The reference oscillator frequency is given by the following equation:

$$F_{ref\_osc} = \frac{I_{ref}}{2 \cdot C_{ref} \cdot \Delta V}$$

Figure 53-69. Equation 4: TSI reference oscillator frequency

Where:

C<sub>ref</sub>: Internal reference capacitor

I<sub>ref</sub>: Reference oscillator current source

 $\Delta V$ : Hysteresis delta voltage

Considering  $C_{ref} = 1.0 \text{ pF}$ ,  $I_{ref} = 12 \mu A$  and  $\Delta V = 600 \text{ mV}$ , follows

$$F_{ref\_osc} = \frac{12\mu A}{2 * 1.0 pF * 600 mV} = 10.0 MHz$$

#### 53.7.2 TSI measurement result

The capacitance measurement result is defined by the number of TSI reference oscillator periods during the sample time and is stored in the TSICHnCNT register.

$$TSICHnCNT = T_{cap\_samp} * F_{ref\_osc}$$

Using Equation 2 and Equation 1 follows:



TSICHNCNT = 
$$\frac{I_{ref} * PS * NSCN}{C_{ref} * I_{ref}} * C_{elec}$$

Figure 53-70. Equation 5: Capacitance result value

In the example where  $F_{ref osc} = 10.0 MHz$  and  $T_{cap samp} = 48 \mu s$ , TSICHnCNT = 480

#### 53.7.3 Electrode scan unit

This section describes the functionality of the electrode scan unit. It is responsible for triggering the start of the active electrode scan.

The touch sense input module needs to periodically scan all active electrodes to determine if a touch event has occurred. The electrode scan unit has two independent scan periods, one for TSI active mode and the other for TSI low power mode. This independent control allows the application to configure longer scan period during low power mode, so contributing to smaller average power consumption. The TSI, in low power mode, has the capability to wake the CPU upon an electrode capacitance change. When the CPU wakes, the TSI enters active mode, and produces a shorter scan period for a faster response and more robust touch detection. Apart from the periodical mode, the electrode scan unit also allows software triggering of the electrode scans. This feature is very useful for initialization of the touch application to detect the initial electrode capacitances. This module generates configurable end-of-scan interrupt to indicate the application that all electrodes were scanned. If a new electrode scan is started while the previous one is still in progress, an overrun error flag is generated, TSI continues the previous scan sequence and the latest trigger is ignored.

#### 53.7.3.1 Active electrodes

The electrode scan unit starts the capacitance measurement of all active electrodes. Each electrode pin should be activated by writing a 1 to the respective PEN[PEN] 16-bit field.

Once an electrode scan is triggered, the electrode scan unit controls the scanning of all the active electrodes sequentially. It starts the scanning of the electrode pin TSI\_IN[0] and goes sequentially scanning until it reaches the electrode pin TSI\_IN[15]. The electrode pin that does not have its bit (PEN[PEN]) enabled is not scanned and is skipped.

Only one electrode pin is functional in the low power mode scan and it's defined by the PEN[LPSP]. In low power scan mode, the configuration of PEN[PEN] bits is ignored.



runctional descriptions

#### 53.7.3.2 Scan trigger

The scan trigger can be set to periodical scan or software trigger. The bit GENCS[STM] determines the TSI scan trigger mode. If STM = 1 the trigger mode is selected as continuous. If STM = 0, the software trigger mode is selected. In periodic mode the scan trigger is generated automatically by the electrode scan unit.

#### **NOTE**

It takes some time (less than 40  $\mu$ s) for TSI oscillators to be stable in software trigger mode and periodical scan mode. In the first scan process, TSI\_GENCS[SCNIP] lags some time before a valid after trigger happens.

#### 53.7.3.3 Software trigger mode

The software trigger scan is started by writing 1 to the bit GENCS[SWTS]. A single scan of all active electrodes is performed. The software trigger scan only can be initiated by the GENCS[SWTS] bit if the STM = 0. If STM = 1, any write in the GENCS[SWTS] bit is ignored.

#### 53.7.3.4 Periodic scan control

The electrode scan unit operates both in TSI active mode and TSI low power mode. It has a separate scan period control for each one of these modes. It allows the application to controls the trade-off of the scan frequency and the average TSI module power consumption.

#### 53.7.3.4.1 Active mode periodic scan

In active mode periodic scan the scan following clocks can be selected: BUS\_CLK, MCGIRCLK and OSCERCLK. The bit field SCANC[AMCLKS] selects the TSI clock source for the active mode scan. The scan period is determined by the SCANC[SMOD] value. SMOD is the modulo of the counter that determines the scan period.

The following figure presents the scan sequence performed by the TSI module. Every active electrode is scanned sequentially, stating with the TSI\_IN[0] and ending with the TSI\_IN[15] pin, if they are active.

When the electrode scan unit starts a scan sequence, all the active electrodes will be scanned sequentially where each electrode has the scanned time defined by GENCS[NSCN]. The counter value is the sum of the total scan times of that electrode.






Figure 53-71. Scan sequence

#### 53.7.3.4.2 Low power mode scan

In low power periodic scan, the scan period is define by the 4-bit binary GENCS[LPSCNITV]. The TSI module is enabled in low power modes only if the bit GENCS[STPE] is 1.

Only one electrode pin is functional in the low power mode scan and its defined by the bit-field PEN[LPSP].

## 53.7.3.4.3 End-of-scan interrupt

Once all the active electrodes are scanned, TSI scan unit will assert the end-of-scan flag. Upon the end-of-scan event, each electrode conversion result will be loaded to the corresponding counter register, compared with each threshold to determine if its value is out of range specified by the threshold registers, and if the counter value is stuck at extreme values(0x0000 or 0xFFFF), the corresponding error flag will also assert.

The electrode scan unit sets the EOSF flag in the GENCS registers once all the active electrode scan finishes. The EOSF flag generates an end-of-scan interrupt request if it is enabled. The interrupt is asserted if enabled by GENCS[TSIIE] and GENCS[ESOR] bits.

The GENCS[EOSF] indicates that all active electrode scans are finished and the respective capacitance results are in the TSICHnCNT registers. The GENCS[EOSF] is cleared by writing one to it.



#### runctional descriptions

It is worthy to note that, since all the possible flags are asserted upon the end of scan event, in TSI interrupt service routine, the end-of-scan flag will be always set until the software clears it.

#### 53.7.3.4.4 Over-run interrupt

If an electrode scan is in progress and there is a scan trigger, the electrode scan unit generates an over-run error by asserting the GENCS[OVRF]. If the TSI error interrupt is active by setting the GENCS[ERIE] bit a interrupt request is asserted. The OVRF flag is cleared by writing 1 to it.

#### 53.7.4 Touch detection unit

The touch detection unit is responsible to detect electrode capacitance changes. It also detects the occurrence of error with the electrode in case the capacitance result is 0x0000 or 0xFFFF. The errors can be caused by the electrode pin shorted to  $V_{DD}$  or  $V_{SS}$  or by electrode capacitances out of the configuration range of the TSI module.

#### 53.7.4.1 Capacitance change threshold

Each TSI pin has its result register TSICHnCNT. At the end of each electrode conversion the touch detection unit compares if the TSICHnCNT result value is inside a configurable range. The comparison range is defined individually for each TSI pin by the following registers, TSICHnHTH, the upper threshold value and TSICHnLTH, the lower threshold value. If the TSICHnCNT happens to be out of the range defined by TSICHnLTH and TSICHnHTH the GENCS[OUTRGF] flag is set. Also the corresponding bit STATUS[ORNGFx] is set indicating which electrode pins happened to have their result register out-of- range.

To clear the GENCS[OUTRGF] write 1 to it.

#### 53.7.4.1.1 Out-of-range interrupt

The GENCS[OUTRGF] flag generates a TSI interrupt request if the GENCS[TSIIE] bit is set and the GENCS[ESOR] bit is cleared. With this configuration, after the end-of-electrode scan, the TSI interrupt is only requested if there is a capacitance change. The capacitance change is detected when the result register gets outside the window defined by the TSI\_THRESHLD register. If the electrodes capacitance does not vary, the TSI does not interrupt the CPU.



When GENCS[OUTRGF] flag is asserted, it is requested the software to poll which specific electrode is out of range by reading the status from STATUS register, clearing the corresponding electrodes flags will also clear the out-of-range flag in GENCS[OUTRGF].

#### 53.7.4.2 Error interrupt

The GENCS[EXTERF] is set in the case the capacitance result registers, TSICHnCNT, of a TSI pin is either 0 or 0xFFFF, the two possible extreme values. The EXTERF flag generates a TSI Error Interrupt request if the GENCS[ERIE] bit is set.

When the GENCS[EXTERF] is set, the registers STATUS register indicates which TSI pins have the error condition by setting the correspondent STATUS[ERRORx] bit.

Before clearing the error flags, users need to check which channel is problematic and then clear the corresponding flags in STATUS register.

## 53.8 Application information

After enabling the TSI module for the first time, it is highly recommended to calibrate all the enabled channels by setting proper high and low threshold value for each active channel. All the channel dedicated counter values can be read from each counter value registers. The software suite can then adjust the threshold based on these values.

Follow proper PCB layout guidelines for board design on electrode shapes, sizes, routes, etc. Visit <a href="http://www.freescale.com/touch">http://www.freescale.com/touch</a> for application notes and reference designs.

## 53.8.1 TSI module sensitivity

The TSI module sensitivity is defined by the increment in the two 16-bit TSICHnCNT result registers caused by a reference capacitor value delta in the electrode pin capacitance.

It is given by the following equation:

$$TSI_{sensitivity} = \frac{I_{ref} * PS * NSCN}{C_{ref} * I}$$

For the example provided,  $I_{ref}$  = 2  $\mu$ A, PS = 2; NSCN = 16,  $C_{ref}$  = 1.0 pF and I =1  $\mu$ A, the TSI<sub>sensitivity</sub> = 64 count/pF



Application information



# **Chapter 54 JTAG Controller (JTAGC)**

#### 54.1 Introduction

#### **NOTE**

For the chip-specific implementation details of this module's instances see the chip configuration chapter.

The JTAGC block provides the means to test chip functionality and connectivity while remaining transparent to system logic when not in test mode. Testing is performed via a boundary scan technique, as defined in the IEEE 1149.1-2001 standard. All data input to and output from the JTAGC block is communicated in serial format.

## 54.1.1 Block diagram

The following is a block diagram of the JTAG Controller (JTAGC) block.



#### muroduction




Figure 54-1. JTAG (IEEE 1149.1) block diagram

#### **54.1.2** Features

The JTAGC block is compliant with the IEEE 1149.1-2001 standard and supports the following features:

- IEEE 1149.1-2001 Test Access Port (TAP) interface
  - 4 pins (TDI, TMS, TCK, and TDO)
- Instruction register that supports several IEEE 1149.1-2001 defined instructions as well as several public and private device-specific instructions. Refer to Table 54-3 for a list of supported instructions.
- Data registers, bypass register, boundary scan register, and device identification register.
- TAP controller state machine that controls the operation of the data registers, instruction register and associated circuitry.

## 54.1.3 Modes of operation

The JTAGC block uses a power-on reset indication as its primary reset signals. Several IEEE 1149.1-2001 defined test modes are supported, as well as a bypass mode.



#### 54.1.3.1 Reset

The JTAGC block is placed in reset when either power-on reset is asserted, or the TMS input is held high for enough consecutive rising edges of TCK to sequence the TAP controller state machine into the Test-Logic-Reset state. Holding TMS high for five consecutive rising edges of TCK guarantees entry into the Test-Logic-Reset state regardless of the current TAP controller state. Asserting power-on reset results in asynchronous entry into the reset state. While in reset, the following actions occur:

- The TAP controller is forced into the Test-Logic-Reset state, thereby disabling the test logic and allowing normal operation of the on-chip system logic to continue unhindered
- The instruction register is loaded with the IDCODE instruction

#### 54.1.3.2 IEEE 1149.1-2001 defined test modes

The JTAGC block supports several IEEE 1149.1-2001 defined test modes. A test mode is selected by loading the appropriate instruction into the instruction register while the JTAGC is enabled. Supported test instructions include EXTEST, HIGHZ, CLAMP, SAMPLE and SAMPLE/PRELOAD. Each instruction defines the set of data register(s) that may operate and interact with the on-chip system logic while the instruction is current. Only one test data register path is enabled to shift data between TDI and TDO for each instruction.

The boundary scan register is enabled for serial access between TDI and TDO when the EXTEST, SAMPLE or SAMPLE/PRELOAD instructions are active. The single-bit bypass register shift stage is enabled for serial access between TDI and TDO when the BYPASS, HIGHZ, CLAMP or reserved instructions are active. The functionality of each test mode is explained in more detail in JTAGC block instructions.

## **54.1.3.3** Bypass mode

When no test operation is required, the BYPASS instruction can be loaded to place the JTAGC block into bypass mode. While in bypass mode, the single-bit bypass shift register is used to provide a minimum-length serial path to shift data between TDI and TDO.

## NP

## 54.2 External signal description

The JTAGC consists of a set of signals that connect to off chip development tools and allow access to test support functions. The JTAGC signals are outlined in the following table and described in the following sections.

Name	I/O	Function	Reset State	Pull
TCK	Input	Test Clock	_	Down
TDI	Input	Test Data In	_	Up
TDO	Output	Test Data Out	High Z <sup>1</sup>	_
TMS	Input	Test Mode Select	_	Up

Table 54-1. JTAG signal properties

## 54.2.1 TCK—Test clock input

Test Clock Input (TCK) is an input pin used to synchronize the test logic and control register access through the TAP.

## 54.2.2 TDI—Test data input

Test Data Input (TDI) is an input pin that receives serial test instructions and data. TDI is sampled on the rising edge of TCK.

#### 54.2.3 TDO—Test data output

Test Data Output (TDO) is an output pin that transmits serial output for test instructions and data. TDO is three-stateable and is actively driven only in the Shift-IR and Shift-DR states of the TAP controller state machine, which is described in TAP controller state machine.

#### 54.2.4 TMS—Test mode select

Test Mode Select (TMS) is an input pin used to sequence the IEEE 1149.1-2001 test control state machine. TMS is sampled on the rising edge of TCK.

TDO output buffer enable is negated when the JTAGC is not in the Shift-IR or Shift-DR states. A weak pull may be implemented at the TDO pad for use when JTAGC is inactive.



## 54.3 Register description

This section provides a detailed description of the JTAGC block registers accessible through the TAP interface, including data registers and the instruction register. Individual bit-level descriptions and reset states of each register are included. These registers are not memory-mapped and can only be accessed through the TAP.

## 54.3.1 Instruction register

The JTAGC block uses a 4-bit instruction register as shown in the following figure. The instruction register allows instructions to be loaded into the block to select the test to be performed or the test data register to be accessed or both. Instructions are shifted in through TDI while the TAP controller is in the Shift-IR state, and latched on the falling edge of TCK in the Update-IR state. The latched instruction value can only be changed in the Update-IR and Test-Logic-Reset TAP controller states. Synchronous entry into the Test-Logic-Reset state results in the IDCODE instruction being loaded on the falling edge of TCK. Asynchronous entry into the Test-Logic-Reset state results in asynchronous loading of the IDCODE instruction. During the Capture-IR TAP controller state, the instruction shift register is loaded with the value 0001b, making this value the register's read value when the TAP controller is sequenced into the Shift-IR state.




Figure 54-2. Instruction register

## 54.3.2 Bypass register


The bypass register is a single-bit shift register path selected for serial data transfer between TDI and TDO when the BYPASS, CLAMP, HIGHZ or reserve instructions are active. After entry into the Capture-DR state, the single-bit shift register is set to a logic 0. Therefore, the first bit shifted out after selecting the bypass register is always a logic 0.



negister description

## 54.3.3 Device identification register

The device identification (JTAG ID) register, shown in the following figure, allows the revision number, part number, manufacturer, and design center responsible for the design of the part to be determined through the TAP. The device identification register is selected for serial data transfer between TDI and TDO when the IDCODE instruction is active. Entry into the Capture-DR state while the device identification register is selected loads the IDCODE into the shift register to be shifted out on TDO in the Shift-DR state. No action occurs in the Update-DR state.



The following table describes the device identification register functions.

Table 54-2. Device identification register field descriptions

Field	Description
PRN	Part Revision Number. Contains the revision number of the part. Value is 0x0.
DC	Design Center. Indicates the design center. Value is 0x2C.
PIN	Part Identification Number. Contains the part number of the device. Value is TBD.
MIC	Manufacturer Identity Code. Contains the reduced Joint Electron Device Engineering Council (JEDEC) ID. Value is 0x00E.
IDCODE ID	IDCODE Register ID. Identifies this register as the device identification register and not the bypass register. Always set to 1.

## 54.3.4 Boundary scan register

The boundary scan register is connected between TDI and TDO when the EXTEST, SAMPLE or SAMPLE/PRELOAD instructions are active. It is used to capture input pin data, force fixed values on output pins, and select a logic value and direction for bidirectional pins. Each bit of the boundary scan register represents a separate boundary



scan register cell, as described in the IEEE 1149.1-2001 standard and discussed in Boundary scan. The size of the boundary scan register and bit ordering is device-dependent and can be found in the device BSDL file.

# 54.4 Functional description

This section explains the JTAGC functional description.

# 54.4.1 JTAGC reset configuration

While in reset, the TAP controller is forced into the Test-Logic-Reset state, thus disabling the test logic and allowing normal operation of the on-chip system logic. In addition, the instruction register is loaded with the IDCODE instruction.

# 54.4.2 IEEE 1149.1-2001 (JTAG) Test Access Port

The JTAGC block uses the IEEE 1149.1-2001 TAP for accessing registers. This port can be shared with other TAP controllers on the MCU. Ownership of the port is determined by the value of the currently loaded instruction.

Data is shifted between TDI and TDO though the selected register starting with the least significant bit, as illustrated in the following figure. This applies for the instruction register, test data registers, and the bypass register.




Figure 54-3. Shifting data through a register

### 54.4.3 TAP controller state machine

The TAP controller is a synchronous state machine that interprets the sequence of logical values on the TMS pin. The following figure shows the machine's states. The value shown next to each state is the value of the TMS signal sampled on the rising edge of the TCK signal. As the following figure shows, holding TMS at logic 1 while clocking TCK through a sufficient number of rising edges also causes the state machine to enter the Test-Logic-Reset state.



#### runctional description



The value shown adjacent to each state transition in this figure represents the value of TMS at the time of a rising edge of TCK.

Figure 54-4. IEEE 1149.1-2001 TAP controller finite state machine

# 54.4.3.1 Enabling the TAP controller

The JTAGC TAP controller is enabled by setting the JTAGC enable to a logic 1 value.



### 54.4.3.2 Selecting an IEEE 1149.1-2001 register

Access to the JTAGC data registers is achieved by loading the instruction register with any of the JTAGC block instructions while the JTAGC is enabled. Instructions are shifted in via the Select-IR-Scan path and loaded in the Update-IR state. At this point, all data register access is performed via the Select-DR-Scan path.

The Select-DR-Scan path is used to read or write the register data by shifting in the data (LSB first) during the Shift-DR state. When reading a register, the register value is loaded into the IEEE 1149.1-2001 shifter during the Capture-DR state. When writing a register, the value is loaded from the IEEE 1149.1-2001 shifter to the register during the Update-DR state. When reading a register, there is no requirement to shift out the entire register contents. Shifting may be terminated once the required number of bits have been acquired.

#### 54.4.4 JTAGC block instructions

The JTAGC block implements the IEEE 1149.1-2001 defined instructions listed in the following table. This section gives an overview of each instruction; refer to the IEEE 1149.1-2001 standard for more details. All undefined opcodes are reserved.

Instruction Code[3:0] **Instruction Summary IDCODE** 0000 Selects device identification register for shift **EZPORT** Enables the EZPORT function for the SoC 0001 SAMPLE/PRELOAD 0010 Selects boundary scan register for shifting, sampling, and preloading without disturbing functional operation SAMPLE 0011 Selects boundary scan register for shifting and sampling without disturbing functional operation 0100 **EXTEST** Selects boundary scan register while applying preloaded values to output pins and asserting functional reset 0101 Intended for factory debug only Factory debug reserved 0110 Factory debug reserved Intended for factory debug only Factory debug reserved 0111 Intended for factory debug only ARM JTAG-DP Reserved 1000 This instruction goes the ARM JTAG-DP controller. See the ARM JTAG-DP documentation for more information. **HIGHZ** 1001 Selects bypass register while three-stating all output pins and asserting functional reset ARM JTAG-DP Reserved 1010 This instruction goes the ARM JTAG-DP controller. See the ARM JTAG-DP documentation for more information.

Table 54-3. 4-bit JTAG instructions

Table continues on the next page...



#### **runctional** description

### Table 54-3. 4-bit JTAG instructions (continued)

Instruction	Code[3:0]	Instruction Summary
ARM JTAG-DP Reserved	1011	This instruction goes the ARM JTAG-DP controller. See the ARM JTAG-DP documentation for more information.
CLAMP	1100	Selects bypass register while applying preloaded values to output pins and asserting functional reset
ARM JTAG-DP Reserved	1110	This instruction goes the ARM JTAG-DP controller. See the ARM JTAG-DP documentation for more information.
BYPASS	1111	Selects bypass register for data operations

#### 54.4.4.1 IDCODE instruction

IDCODE selects the 32-bit device identification register as the shift path between TDI and TDO. This instruction allows interrogation of the MCU to determine its version number and other part identification data. IDCODE is the instruction placed into the instruction register when the JTAGC block is reset.

#### 54.4.4.2 EZPORT instruction

The EZPORT instruction allows for the EZPORT module to program the on-chip flash from a simple 4-pin interface. The JTAGC forces the core into a reset state and forces the EZPORT mode select/chip select low. In this mode, the flash can be programmed through the JTAG test port pins, which are connected to the EZPORT module.

### 54.4.4.3 SAMPLE/PRELOAD instruction

The SAMPLE/PRELOAD instruction has two functions:

- The SAMPLE portion of the instruction obtains a sample of the system data and control signals present at the MCU input pins and just before the boundary scan register cells at the output pins. This sampling occurs on the rising edge of TCK in the Capture-DR state when the SAMPLE/PRELOAD instruction is active. The sampled data is viewed by shifting it through the boundary scan register to the TDO output during the Shift-DR state. Both the data capture and the shift operation are transparent to system operation.
- The PRELOAD portion of the instruction initializes the boundary scan register cells before selecting the EXTEST or CLAMP instructions to perform boundary scan tests. This is achieved by shifting in initialization data to the boundary scan register during the Shift-DR state. The initialization data is transferred to the parallel outputs



of the boundary scan register cells on the falling edge of TCK in the Update-DR state. The data is applied to the external output pins by the EXTEST or CLAMP instruction. System operation is not affected.

#### 54.4.4.4 SAMPLE instruction

The SAMPLE instruction obtains a sample of the system data and control signals present at the MCU input pins and just before the boundary scan register cells at the output pins. This sampling occurs on the rising edge of TCK in the Capture-DR state when the SAMPLE instruction is active. The sampled data is viewed by shifting it through the boundary scan register to the TDO output during the Shift-DR state. There is no defined action in the Update-DR state. Both the data capture and the shift operation are transparent to system operation.

### 54.4.4.5 EXTEST External test instruction

EXTEST selects the boundary scan register as the shift path between TDI and TDO. It allows testing of off-chip circuitry and board-level interconnections by driving preloaded data contained in the boundary scan register onto the system output pins. Typically, the preloaded data is loaded into the boundary scan register using the SAMPLE/PRELOAD instruction before the selection of EXTEST. EXTEST asserts the internal system reset for the MCU to force a predictable internal state while performing external boundary scan operations.

### 54.4.4.6 HIGHZ instruction

HIGHZ selects the bypass register as the shift path between TDI and TDO. While HIGHZ is active all output drivers are placed in an inactive drive state (e.g., high impedance). HIGHZ also asserts the internal system reset for the MCU to force a predictable internal state.

#### 54.4.4.7 CLAMP instruction

CLAMP allows the state of signals driven from MCU pins to be determined from the boundary scan register while the bypass register is selected as the serial path between TDI and TDO. CLAMP enhances test efficiency by reducing the overall shift path to a



#### mualization/Application information

single bit (the bypass register) while conducting an EXTEST type of instruction through the boundary scan register. CLAMP also asserts the internal system reset for the MCU to force a predictable internal state.

#### 54.4.4.8 BYPASS instruction

BYPASS selects the bypass register, creating a single-bit shift register path between TDI and TDO. BYPASS enhances test efficiency by reducing the overall shift path when no test operation of the MCU is required. This allows more rapid movement of test data to and from other components on a board that are required to perform test functions. While the BYPASS instruction is active the system logic operates normally.

### 54.4.5 Boundary scan

The boundary scan technique allows signals at component boundaries to be controlled and observed through the shift-register stage associated with each pad. Each stage is part of a larger boundary scan register cell, and cells for each pad are interconnected serially to form a shift-register chain around the border of the design. The boundary scan register consists of this shift-register chain, and is connected between TDI and TDO when the EXTEST, SAMPLE, or SAMPLE/PRELOAD instructions are loaded. The shift-register chain contains a serial input and serial output, as well as clock and control signals.

# 54.5 Initialization/Application information

The test logic is a static logic design, and TCK can be stopped in either a high or low state without loss of data. However, the system clock is not synchronized to TCK internally. Any mixed operation using both the test logic and the system functional logic requires external synchronization.

To initialize the JTAGC block and enable access to registers, the following sequence is required:

- 1. Place the JTAGC in reset through TAP controller state machine transitions controlled by TMS
- 2. Load the appropriate instruction for the test or action to be performed



# **Appendix A Release Notes for Revision 6**

# A.1 General changes throughout document

· No substantial content changes

# A.2 About This Document chapter changes

No substantial content changes

### A.3 Introduction chapter changes

• Updated 'Kinetis MCU portfolio' diagram for K6x family.

# A.4 Chip Configuration chapter changes

- · Clarified 'PDB Module Interconnections' section.
- In 'UART interrupts' section, updated LON and ISO7816 interrupt sources.
- · Clarified 'I2S/SAI clock generation' section.
- · Added note to 'VREF Overview' section.
- Added notes to USB controller and USB voltage regulator configurations.
- Clarified the "Wake-up Sources" section within the "Low-Leakage Wake-up Unit (LLWU) Configuration" section.
   Renamed the "LLWU inputs" table to "Wakeup sources for LLWU inputs", removed the multiplexed signals and provided the pin name only. Added a reference to the signal multiplexing table for the individual signal options.
- In ADCx Channel Assignment, updated AD27 and AD29 input signal description.
- Clarified ADC and PGA Reference Options section.
- In LPTMR pulse counter input options section, clarified LPTMR\_CSR[TPS]=11 chip input.
- Added notes to VREF Overview and DAC External Trigger Input Connections sections.
- · Updated ADC and PGA Reference Options section.

# A.5 Memory Map chapter changes

· Added Alternate non-volatile IRC user trim description topic.

# A.6 Clock Distribution chapter changes

- Added 'SAI clock generation' diagram.
- Updated Clock Diagram for standard XTAL, EXTAL, and MCG clock names.
- In Device Clock Summary table, updated bus clock, external reference clock, USB FS clock, and TRACE clock.
- Updated Clocking diagram for IRC clock and updated MCGFFCLK definition.
- · Added note to Debug trace clock section.
- In Clock Summary table, added RTC\_CLKOUT clock.
- Updated Debug trace clock diagram.
- Updated the "Internal clocking requirements" section.
- For the "USB FS OTG Controller clocking" section, added this note: "The MCGFLLCLK does not meet the USB jitter specifications for certification."

# A.7 Reset and Boot chapter changes

• In System resets section, updated associated input pins for JTAG.

# A.8 Power Management chapter changes

- In 'Module Operation in Low Power Modes' section, changed LPT to LPTMR.
- In 'Entering and exiting power modes' section, updated wake-up flow from VLLSx.

# A.9 Security chapter changes

· No substantial content changes

# A.10 Debug chapter changes

Updated the section "Debug Resets".



# A.11 Signal Multiplexing and Signal Descriptions chapter changes

- Updated pinout diagrams and tables
- In 'Port control and interrupt module features' section, updated digital filter clock cycles from 1 to 32.
- Updated CMPx\_IN signals to 5:0.
- In 'System Signal Descriptions' table, modified RESET\_b pin to I/O.
- For the "Signal Multiplexing and Pin Assignments" table, added the LLWU inputs to the appropriate pin names.

# A.12 PORT changes

· No substantial content changes

# A.13 SIM changes

• Updated ADCxTRGSEL, PFSIZE, and EESIZE field descriptions.

# A.14 Mode Controller changes

- In Modes of Operation section, updated VLPR mode description in Power modes table.
- · Clarified Very Low Power Run (VLPR) Mode section.

### A.15 PMC changes

No substantial content changes

# A.16 LLWU changes

No substantial content changes

# A.17 MCM changes

No substantial content changes



# A.18 Crossbar switch chapter changes

· No substantial content changes

# A.19 MPU changes

No substantial content changes

# A.20 AIPS-Lite changes

No substantial content changes

# A.21 DMAMUX changes

No substantial content changes

# A.22 DMA changes

· No substantial content changes

# A.23 EWM changes

No substantial content changes

# A.24 WDOG changes

Clarification added for no reset due to unlock sequence when ALLOW\_UPDATE is cleared in Section "Unlocking and Updating the Watchdog".

# A.25 MCG changes

• Updated CME, VDIV, PRDIV, PLLCLKEN bit field descriptions

Support of PLL loss of lock resets

#### K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# A.26 OSC changes

· No substantial content changes

# A.27 RTC Oscillator changes

· No substantial content changes

# A.28 FMC changes

Terminology update: changed "Directory" to "Tag" in the names of tag cache registers.

# A.29 FTFL changes

- Erase All pin executes even if swap system has been initialized
- Clarify that certain erase commands allowed in UPDATE or UPDATE-ERASED swap states
- Swap system initializes to UPDATE-ERASED state
- Read Resource command accesses program flash 1 IFR using flash address [17]
- Swap indicator address not implicitly protected during Erase All Blocks command
- Erase All Blocks command erases program flash 1 IFR to uninitialize the swap system
- Modify swap command error handling
- · Add sector size to feature list
- Correct address range for reserved field in program flash IFR
- Add protection check to list of command processing steps
- · Remove references to NVM Normal and Special modes related to command protection checks

# A.30 FlexBus changes

No substantial content changes

### A.31 EzPort changes

· No substantial content changes



# A.32 CRC changes

No substantial content changes

# A.33 ADC changes

- Removed CLPD from generating gain calibration values procedure.
- Updated Pseudo-code example section for CFG1 and SC2 register bits.
- · Removed band gap voltages, BGH and BGL.

# A.34 CMP changes

• Updated CMPx\_CR1[PMODE] field description.

# A.35 DAC changes

• Updated DACx\_C0[LPEN] field description.

# A.36 VREF changes

No substantial content changes

# A.37 OPAMP changes

Updated OPAMPx\_C0[LPEN] field description.

# A.38 TRIAMP changes

• Updated TRIAMPx\_C0[LPEN] field description.



# A.39 PDB changes

Added Debug mode and updated PDBEN encodings.

# A.40 FTM changes

No substantial content changes

# A.41 PIT changes

· No substantial content changes

# A.42 LPTMR changes

Added note in LPTMR clocking section.				
	7 Nov 2011	S Gallimore	Added LPTPM_Doze_Yes condition for the latest version that disables counting during debug mode.	

# A.43 CMT changes

• No substantial content changes

# A.44 RTC changes

Updated RTC\_CR[14] bit field access.

Updated Time Alarm section with IER[TAIE].

# A.45 USB changes

No substantial content changes

K50 Sub-Family Reference Manual, Rev. 6, Nov 2011



# A.46 USBDCD changes

No substantial content changes

# A.47 USB VREG changes

· No substantial content changes

# A.48 DSPI chapter changes

- In 'Transmit FIFO Fill Interrupt or DMA Request' section, added note on using TFFF flag.
- Added links to corresponding functional description in the Delay fields in CTAR register.
- Renamed DSICR to DSICR0.
- Updated EOQ interrupt request description.
- · Added SPITCF and DSITCF interrupt request descriptions and updated corresponding bit fields in SR register.
- Updated DIS\_TXF and DIS\_RXF bit field descriptions in MCR register.
- Updated 'Sample MSC downstream transmission using ITSB mode' diagram.

# A.49 I2C changes

In the "Address Matching Wakeup" section, expanded the note to clarify the feature's purpose.

### A.50 UART changes

• Changed TWFIFO[TXWATER] in RDRF register to RWFIFO[RXWATER].

# A.51 SDHC changes

Removed the feature of "Support voltage selection by configuring vendor specific register bit"

### A.52 I2S changes

• Updated 1111 encoding for TFWM0 and TFWM1 bit fields.



# A.53 GPIO changes

· No substantial content changes

# A.54 TSI changes

No substantial content changes

# A.55 JTAG Controller changes

No substantial content changes





#### How to Reach Us:

#### **Home Page:**

www.freescale.com

#### Web Support:

http://www.freescale.com/support

#### **USA/Europe or Locations Not Listed:**

Freescale Semiconductor
Technical Information Center, EL516
2100 East Elliot Road
Tempe, Arizona 85284
+1-800-521-6274 or +1-480-768-2130
www.freescale.com/support

#### Europe, Middle East, and Africa:

Freescale Halbleiter Deutschland GmbH Technical Information Center Schatzbogen 7 81829 Muenchen, Germany +44 1296 380 456 (English) +46 8 52200080 (English) +49 89 92103 559 (German) +33 1 69 35 48 48 (French) www.freescale.com/support

#### Japan:

Freescale Semiconductor Japan Ltd. Headquarters ARCO Tower 15F 1-8-1, Shimo-Meguro, Meguro-ku, Tokyo 153-0064 Japan 0120 191014 or +81 3 5437 9125 support.japan@freescale.com

#### Asia/Pacific:

Freescale Semiconductor China Ltd.
Exchange Building 23F
No. 118 Jianguo Road
Chaoyang District
Beijing 100022
China
+86 10 5879 8000
support.asia@freescale.com

#### For Literature Requests Only:

Freescale Semiconductor Literature Distribution Center 1-800-441-2447 or +1-303-675-2140 Fax: +1-303-675-2150

 $LDCF or Free scale Semiconductor @\,hibbert group.com$ 

Information in this document is provided solely to enable system and software implementers to use Freescale Semiconductors products. There are no express or implied copyright licenses granted hereunder to design or fabricate any integrated circuits or integrated circuits based on the information in this document.

Freescale Semiconductor reserves the right to make changes without further notice to any products herein. Freescale Semiconductor makes no warranty, representation, or guarantee regarding the suitability of its products for any particular purpose, nor does Freescale Semiconductor assume any liability arising out of the application or use of any product or circuit, and specifically disclaims any liability, including without limitation consequential or incidental damages. "Typical" parameters that may be provided in Freescale Semiconductor data sheets and/or specifications can and do vary in different applications and actual performance may vary over time. All operating parameters, including "Typicals", must be validated for each customer application by customer's technical experts. Freescale Semiconductor does not convey any license under its patent rights nor the rights of others. Freescale Semiconductor products are not designed, intended, or authorized for use as components in systems intended for surgical implant into the body, or other applications intended to support or sustain life, or for any other application in which failure of the Freescale Semiconductor product could create a situation where personal injury or death may occur. Should Buyer purchase or use Freescale Semiconductor products for any such unintended or unauthorized application, Buyer shall indemnify Freescale Semiconductor and its officers, employees, subsidiaries, affiliates, and distributors harmless against all claims, costs, damages, and expenses, and reasonable attorney fees arising out of, directly or indirectly, any claim of personal injury or death associated with such unintended or unauthorized use, even if such claims alleges that Freescale Semiconductor was negligent regarding the design or manufacture of

RoHS-compliant and/or Pb-free versions of Freescale products have the functionality and electrical characteristics as their non-RoHS-complaint and/or non-Pb-free counterparts. For further information, see http://www.freescale.com or contact your Freescale sales representative.

For information on Freescale's Environmental Products program, go to http://www.freescale.com/epp.

Freescale<sup>TM</sup> and the Freescale logo are trademarks of Freescale Semiconductor, Inc. All other product or service names are the property of their respective owners.

© 2011-2012 Freescale Semiconductor, Inc.



Document Number: K50P144M100SF2RM

Rev. 6, Nov 2011

